

वीर सेवा मन्दिर
दिल्ली

★

4616

क्रम संख्या

काल नं०

29 S. 2 FLE

संख्या

CORPUS INSCRIPTIONUM INDICARUM

Vol. III

**INSCRIPTIONS OF THE EARLY GUPTA KINGS
AND THEIR SUCCESSORS**

BY

JOHN FITHFULL FLEET, C.I.E.,

OF H. M. S. BOMBAY CONVENANTED CIVIL SERVICE
MEMBER OF THE ROYAL ASIATIC SOCIETY OF GREAT BRITAIN AND IRELAND,
MEMBER OF THE BOMBAY BRANCH OF THE ROYAL ASIATIC SOCIETY,
MEMBER OF THE ASIATIC SOCIETY OF BENGAL,
CORRESPONDING MEMBER OF THE ROYAL SOCIETY OF SCIENCE, GOTTINGEN
FELLOW OF THE UNIVERSITY OF BOMBAY.

WITH

Notes and Bibliography of Gupta Inscriptions

BY

Dr. A. K. NARAIN

Head of the Dept. of Ancient Indian History Culture & Archaeology

B. H. U.

"In the scarcity of authentic materials for the ancient, and even for the modern, history of the Hindu race, importance is justly attached to all genuine monuments, and especially inscriptions on stone and metal"—*Colebrooke's Essays*,

Vol. II. p. 213

INDOLOGICAL BOOK HOUSE

ANTIQUARIAN BOOKSELLERS & PUBLISHERS

VARANASI (INDIA), 1970

**PUBLISHED BY
RAMESHWAR SINGH
INDOLOGICAL BOOK HOUSE
VARANASI**

RS. 175

ALL RIGHTS RESERVED BY GOVT. OF INDIA

**PRINTED AT TODAY & TOMORROW'S
PRINTERS & PUBLISHERS
FARIDABAD (Haryana)**

CORPUS INSCRIPTIONUM INDICARUM

Vol. III

INSCRIPTIONS OF THE EARLY GUPTA KINGS AND THEIR SUCCESSORS

BY

JOHN FAITHFULL FLEET, C.I.E.,

OF H. M.'S BOMBAY COVENANTED CIVIL SERVICE,
MEMBER OF THE ROYAL ASIATIC SOCIETY OF GREAT BRITAIN AND IRELAND;
MEMBER OF THE BOMBAY BRANCH OF THE ROYAL ASIATIC SOCIETY;
MEMBER OF THE ASIATIC SOCIETY OF BENGAL,
CORRESPONDING MEMBER OF THE ROYAL SOCIETY OF SCIENCE, GÖTTINGEN,
FELLOW OF THE UNIVERSITY OF BOMBAY.

"In the scarcity of authentic materials for the ancient, and even for the modern, history of the Hindu race, importance is justly attached to all genuine monuments, and especially inscriptions on stone and metal"—*Colebrooke's Essays*,

Vol. II p. 213

INDOLOGICAL BOOK HOUSE

ANTIQUARIAN BOOKSELLERS & PUBLISHERS

VARANASI (INDIA), 1970

● GUNSHI RAM MANOHAR LAL

Oriental & Foreign Book Sellers

P B 1165, Nai Sarak, DELHI-4

© ALL RIGHTS RESERVED BY GOVERNMENT OF INDIA

Third Revised Edition

Rs. 175/-

PUBLISHED BY RAMESHWAR SINGH FOR INDIOLOGICAL BOOK HOUSE,
VARANASI (INDIA), PRINTED AT TODAY & TOMORROW'S
PRINTERS & PUBLISHERS, FARIDABAD (HARYANA)

PUBLISHER'S NOTE

As book-sellers specializing in oriental books we have been facing great difficulties in procuring rare and out of print books to meet growing demands of our customers. If a copy or two of a rare book could be obtained with much strenuous efforts it was always on prohibitive price. We, therefore, decided to re-publish some of the very rare and useful books on the various subjects in the field of Indology. We are conscious of our difficulties and limitations in facing this stupendous task but we hope this will be minimized through the co-operation of those for whom we have undertaken this enterprise. After we had already gone ahead with the work of re-printing some of the books, we were able to get the advice and help of Professor A. K. Narain, Head of the Department of Ancient Indian History, Culture and Archaeology of Banaras Hindu University, who has kindly agreed to supervise such publications and to be the General Editor of such works which belong to his general field of studies.

INSTRUCTIONS TO BINDER.

INSTRUCTIONS TO BINDER.

Plate i	a folding Plate between	pages	8, 9
.. ii.	to face	page	20
... iii.	28
... iv	36
... v.	44
... vi.	46
... vii.	54
... viii.	a folding Plate between	pages	60, 61
... ix.	to face	page	68
... x.	76
... xi	a folding Plate between	pages	82, 83
... xii.	to face	page	90
.. xiii	104
.. xiv	108
... xv	112
... xvi	120
... xvii.	124
... xviii.	128
... xix	132
... xx.	138
... xxi A & B.	a folding Plate between	pages	142, 143
... xxi C	to face	page	150
... xxii.	154
... xxiii	160
... xxiv	168
... xxv.	180
... xxvi.	194
... xxvii.	198
.. xxviii	a folding Plate between	pages	204, 205
... xxix.	to face	page	210
.. xxx.	220
... xxxi.	226
... xxxii	230
... xxxiii.	234
... xxxiv.	240
... xxxv.	248
... xxxvi	250
... xxxvii	256
... xxxviii.	260
... xxxix	264
... xl	270
... xli	276
... xlii	280
... xliii.	284
.. xliv	290

CONTENTS.

Preface	Page 1
Introduction	7
The Gupta Era	16
Table I.—Genealogy of the Early Gupta Kings	17
The Nomenclature of the Era	19
Albérún's Statements, as rendered by M. Reinaud	23
Albérún's Statements, as rendered by Prof. Sachse	24
The Results of the above Renderings	25
Albérún's Statements, as rendered by Prof. Wright	27
The Theories based on M. Reinaud's rendering of Albérún's Statements	31
Examination of the previous Theories	33
Table II.—Genealogy of the Kings of Valabhi	41
The Mandasôr Inscription of Málava-Samvat 529	65
The Determination of the Exact Epoch of the Era	69
The Scheme of the Gupta-Valabhi Year	69
Table III.—Comparative Table of the Vikrama, Saka, and Gupta-Valabhi Years	71
The Calculation of Recorded Dates	86
The Éran Inscription of the year 165	86
The Veráwal Inscription of Valabhi-Samvat 945	84
The Veráwal Inscription of Valabhi-Samvat 927	90
The Kaira Grant of the year 330	93
The Népal Inscription of the year 386	95
The Môrbi Grant of the year 586	97
The Use of the Twelve-Year Cycle of Jupiter in Records of the Early Gupta Period	101
A.—The Khôh Grant of the year 156	104
Table IV.—The Samvatsaras of the Twelve-Year Cycle of Jupiter	105
B.—The Khôh Grant of the year 163	110
C.—The Majhgawâm Grant of the year 191	114
D.—The Khôh Grant of the year 209	117
E.—The Bhumarâ Pillar Inscription	119
Summary of Results	124
The Origin of the Era	130
Appendix I.—A Note on the Epoch and Reckoning of the Śaka Era	137
Appendix II.—A Method of Calculating the Week-Days of Hindu Tithis and the corresponding English Dates. By Shankar Balkrishna Dikshit; Bombay Educational Department	145
Explanation of Technical Terms	145
To find the Week-Day of a given Tithi	149
Table V.—Calculation of the Week-Day of a given Tithi	151
Table VI.—The Times, after Sunrise, of the ending of a given Tithi	157
Table VII.—Calculation of the English Date of a given Tithi	157
To find the English Date for a given Tithi	158

Appendix III.—The Twelve-Year Cycle of Jupiter	By Shankar Balkrishna Dikshit, Bombay Educational Department	Page 161
Table VIII.—Regulation of the Names of the <i>Saṃvatsaras</i> from the <i>Nakshatras</i>		163
Table IX.—Longitudes of the Ending-points of the <i>Nakshatras</i>		163
Table X.—Details of two Twelve-Year Cycles of Jupiter		167
Appendix IV.—The Chronology of the Early Rulers of <i>Nēpāl</i>		177
Table XI.—List of the Early Rulers of <i>Nēpāl</i>		189
Appendix V.—System of Transliteration		193

TEXTS AND TRANSLATIONS.

THE EARLY GUPTA KINGS.

No	1	Plate	i	Allahābād posthumous pillar inscription of Samudragupta	1
2	ii	A	Ēran inscription of Samudragupta	18	
3	ii	B	Udayagiri cave inscription of Chandragupta II.—The year 82	21	
4	iii	A	Mathurā inscription of Chandragupta II	25	
5	iii	B	Sānchi inscription of Chandragupta II.—The year 93	29	
6	iv	A	Udayagiri cave inscription of Chandragupta II.	34	
7	iv	B	Gadhwa inscription of Chandragupta II —The year 88	36	
8	iv	C	Gadhwa inscription of Kumāragupta	39	
9	iv	D	Gadhwa inscription of Kumāragupta —The year 98	40	
10	v		Bilsad pillar inscription of Kumāragupta.—The year 96	42	
11	vi	A	Mankuwar image inscription of Kumāragupta.—The year 129	45	
12	vi	B	Bihār pillar inscription of Skandagupta	47	
13	vii		Bhitār pillar inscription of Skandagupta	52	
14	viii		Junāgaḍh rock inscription of Skandagupta.—The years 136, 137, and 138	56	
15	ix	A	Kahāum pillar inscription of Skandagupta.—The year 141	65	
16	ix	B	Indōr plate of Skandagupta —The year 146	68	

THE RULERS OF MALAVA.

17	x	Gangdhār inscription of Viśvavarman —The year 480	72
18	xi	Mandasor inscription of Kumāragupta and Bandhuvarman —The Mālava years 493 and 529	79

BUDHAGUPTA AND BHANŪGUPTA.

19	xii	A	Ēraṇ pillar inscription of Budhagupta.—The year 165	88
20	xii	B	Ēran posthumous pillar inscription of Gōparāja.—The year 191	91

THE PARIVRAJAKA MAHARAJAS.

21	Nil	Khōh plates of the Mahārāja Hastin.—The year 156	93	
22	xiii	Khōh plates of the Mahārāja Hastin.—The year 163	100	
23	xiv	Mājhgawām plates of the Mahārāja Hastin.—The year 191	106	
24	xv	A	Bhumarā pillar inscription of the Mahārājas Hastin and Sarvanātha	110
25	xv	B	Khōh plates of the Mahārāja Sambhōbha —The year 209	112

CONTENTS.

THE MAHARAJAS OF UCHCHAKALPA.

No. 26	Plate xvi	... Kārtalāl plates of the Mahārāja Jayanātha —The year 174	... Page 117
.. 27	... xvii	... Khōh plates of the Mahārāja Jayanātha —The year 177	... 121
... 28	... xviii	... Khōh plates of the Mahārāja Śarvanātha —The year 193	... 125
... 29	... xix A	... Khōh plate of the Mahārāja Śarvanātha	... 129
... 30	... xix B	... Khōh plate of the Mahārāja Śarvanātha.—The year 197	... 132
... 31	... xx	.. Khōh plates of the Mahārāja Śarvanātha.—The year 214	... 135

CHANDRA.

... 32	... xxi A	... Mēharaulī posthumous pillar inscription of Chandra	... 136
--------	-----------	--	---------

YASODHARMA AND VISHNUVARDHANA.

... 33	... xxi B	... Mandasōr pillar inscription of Yasōdharma	... 142
... 34	... xxi C	... Mandasōr duplicate pillar inscription of Yasōdharma	... 149
... 35	... xxii	.. Mandasōr inscription of Yasōdharma and Vishnuvardhana.—The Mālava year 589	... 150

TORAMANA AND MIHIRAKULA.

... 36	... xxiii A	... Éraṅ boar inscription of Tōramāna	... 158
... 37	... xxiii B	.. Gwālīor inscription of Mihirakula	... 161

THE KINGS OF VALABHI.

... 38	... xxiv	.. Mālyā plates of the Mahārāja Dharasēna II.—The year 252	... 164
... 39	... xxv	... Aīnā plates of Śīlāditya VII.—The year 447	... 171

THE RAJAS OF SARABHAPURA.

... 40	... xxvi	... Āraṅ plates of the Rāja Mahā-Jayarāja	... 191
... 41	... xxvii	.. Rāypur plates of the Rāja Mahā-Sudēvatāja	... 196

THE GUPTAS OF MAGADHA.

... 42	... xxviii	... Apsad inscription of Ādityasēna	... 200
... 43	... xxix A	... Shāhpur image inscription of Ādityasēna	... 208
... 44	} ... Nil	.. Mandār Hill inscriptions of Ādityasēna	... 211
... 45			
... 46	... xxix B	.. Dēō-Baranārī inscription of Jīvtagupta II.	... 213

THE MAUKHARIS.

... 47	... xxx A	... Aīrḡaḡh seal of Sarvavarman	... 219
... 48	... xxx B	.. Barābar Hill cave inscription of Anantavarman	... 221
... 49	... xxxi A	.. Nāḡārjuni Hill cave inscription of Anantavarman	... 223
... 50	... xxxi B	.. Nāḡārjuni Hill cave inscription of Anantavarman	... 226
... 51	... xxxii A	.. Jaunpur inscription of Iśvaravarman	... 228

THE KINGS OF KANAUJ

... 52	... xxxii B	... Sōnpat seal of Harshavardhana	... 231
--------	-------------	-----------------------------------	---------

THE VAKATAKA MAHARAJAS.

... 53	... xxxiii A	} .. Nachē-kt-talāl inscriptions of the Mahārāja Prīthivishēna	... 233
... 54	... xxxiii B		
... 55	... xxxiv	... Chammak plates of the Mahārāja Pravarasēna II.—(For the seal, see Plate xxxiii C.)	... 235
.. 56	... xxxv	.. Siwanī plates of the Mahārāja Pravarasēna II.—(For the seal, see Plate xxxiii D.)	... 243

MISCELLANEOUS INSCRIPTIONS.

No. 57	Plate xxxvi A	... Pahlādpur pillar inscription	Page 249
... 58	... xxxvi B	... Bijayagadh inscription of the Yaudhēyas	251
... 59	... xxxvi C	... Bijayagadh pillar inscription of Vishnūvardhana—The year 428	252
... 60	... xxxvii	... Spurious Gayā plate of Samudragupta	254
... 61	... xxxviii A	... Udayagiri cave inscription.—The year 106	258
... 62	... xxxviii B	... Sāñchi inscription.—The year 131	260
... 63	... xxxix A	... Mathurā image inscription.—The year 135	262
... 64	... xxxix B	... Gadhwā inscription	264
... 65	... xxxix C	... Kōsam image inscription of the Mahārāja Bhīmavarman.—The year 139	266
... 66	... xxxix D	... Gadhwā inscription—The year 148	267
... 67	... xl A	... Tuṣām rock inscription	269
... 68	... xl B	... Dēdrīyā image inscription	271
... 69	... xl C	... Kasiā image inscription	272
... 70	... xl D	... Mathurā image inscription—The year 230	273
... 71	... xli A	... Bōdh-Gayā inscription of Mahānāman—The year 269	274
... 72	... xli B	... Bōdh-Gayā image inscription of Mahānāman	278
... 73	... xli A	... Sāñchi pillar inscription	279
... 74	... xlii B	... Calcutta Museum image inscription	280
... 75	... xlii C	... Sārnāth inscription	281
... 76	... xlii D	... Bōdh Gayā image inscription	281
... 77	... xliii A	... Lāhōr seal of the Mahārāja Mahēśvaranāga	282
... 78	... xliii B	... Rōhtāsgadh seal-matrix of the Mahāsāmānta Śaśāñkadēva	283
... 79	... xliii C	... Sārnāth inscription of Prakāśāditya	284
... 80	... xliv	... Nirmāṇḍ plate of the Mahāsāmānta and Mahārāja Samudrasēna	286
... 81	... xlv	... Rājim plates of the Rāja Tivaradēva	291

Index	301
-------	--------	-----

Errata	349
--------	--------	-----

PREFACE.

JUST half a century ago, in 1837, in the *Four. Beng. As. Soc.* Vol. VI. p. 663, Mr. James Prinsep, by whom the study of Indian archæology was first placed on a sound and critical basis, indicated the necessity of systematically arranging the epigraphical materials for the study of the ancient history of India, which were then being gradually found to exist in considerable numbers; and also suggested the name which the collective publication of them should bear, viz. *Corpus Inscriptionum Indicarum*.

For nearly forty years, however, owing to the manner in which the collection and publication of these epigraphical materials was left almost entirely to private enterprise, the scheme lay dormant; until it was revived, about ten years ago, by General Sir Alexander Cunningham, C.S.I., K.C.I.E., who in 1870 was selected by the Government of India for the newly-created post of Director-General of the Archæological Survey of India, and who, in 1877, brought out the first volume of 'his series, under the title of *Corpus Inscriptionum Indicarum*, Volume I., containing the Inscriptions of Aśoka.

At the same time, he announced that, in the continuation of the series, Volume II. would contain the Inscriptions of the Indo-Scythians and of the Satraps of Saurashtra, and Vol. III. the Inscriptions of the Guptas and of other contemporary dynasties of Northern India. And, with the special sanction of the Secretary of State for India, in 1881 I was selected for the newly-created post of Epigraphist to the Government of India, with the primary duty of preparing the volume that was to contain the Inscriptions of the Early Gupta Kings. I joined that appointment on the 17th January, 1883; and held it up to the 4th June, 1886, when it was abolished.

At first sight, the principal task that lay before me seemed neither lengthy nor laborious; it being understood that the necessary materials had already been fully collected, and merely required to be critically examined and published. And the only practical difficulty that then appeared to lie in my way, was, that, as the intended volume of Indo-Scythian inscriptions, which had been entrusted to other hands and ought, for the proper consideration in due chronological order of all the questions concerned, to have appeared first, had not been previously published,—and, in fact, it has not even yet been issued,—and their dates had not been determined beyond dispute, the all-important question of the exact historical period to which the Early Gupta dynasty must be referred, would probably still be left undecided, save by historical and other inferences and arguments which might at any future time be proved, by further discoveries, to be unsound and erroneous.

My task, however, quickly assumed more ample proportions ; for I found at once that hardly any of the materials previously collected, in the shape of ink-impressions of the original records on stone and copper, could be relied on for purposes of critical editing ; and much less for the reproduction in facsimile Plates, which must always be an inseparable part of such researches, in order that scholars who cannot examine the original records themselves, may nevertheless be in a position to check the published results that are submitted to them. I found, in fact, that, with only eleven or twelve exceptions, it was unavoidable that I should have fresh impressions prepared of all the materials throughout ; and also that, as far as might be practicable, I should examine the original stone-records *in situ*, and the original copper-records by collecting them together again from the various owners of them. The arrangements entailed much correspondence, and a great deal of travelling, than which nothing is more obstructive of continuous and successful literary work. And it was not until April, 1885, that I found myself in possession of the last of the materials required by me, *viz.* an ink-impression and estampage of the Gangdhâr inscription of Viśvavarman, No. 17, page 72.

Meanwhile, of course, a certain amount of progress had been made in the preparation of the Texts and Translations, and in the arrangement of the Plates and other subsidiary work ; subject always to the fact that no division of the work could be actually finished off, until it should be known that there were no more materials to come in. And the delay that was entailed by the necessity of collecting all the previously known materials afresh, has proved to be no matter for regret ; if only for the reason that it enabled me to obtain, amongst other perfectly new materials, the invaluable Mandasôr inscription, No. 18, page 79, which furnished the information that was required, to set at rest the long-disputed question of the epoch of the Gupta era. This inscription was only discovered, under my direction, in March, 1884 ; and even then the full value of it was not apparent, in consequence of some serious imperfections in the ink-impressions that were first brought to me. I myself visited Mandasôr at the end of February, 1885, and was then able to examine this record *in situ*, and to have proper ink-impressions of it made, and thus to ascertain its full and conclusive bearing. And it was on this journey that, for the first time, by visiting Ujjain, I became aware of the almost equally important inscription of Yaśôdharman and Vishṇuwardhana, No. 35, page 150, which gave the key to the whole history of the period, by supplying a definite date for Yaśôdharman, who was known, from the Mandasôr inscription, No. 33, page 142, discovered under my direction in March, 1884, to have overthrown the well-known foreign invader and conqueror, Mihirakula, who, again, I had previously determined, must have effected the final downfall of the Early Gupta dynasty. Without these discoveries, the period of the Early Gupta supremacy would have still remained the subject of argument and doubt. Whereas, with them, I have been able now to set this question at rest, and thus to establish a starting-point from which we can work back in developing the Indo-Scythian history ; and, also, through fixing, for the first time,

the date of Mihirakula,—who, as we learn from the writings of the Chinese pilgrim Hiuen Tsiang, played a most leading and important part in early Indian history,—to furnish the means of adjusting the chronology, before and after him, of the early history of Kaśmīr, as recorded in the *Rājatarāṅginī*, and also of testing the accuracy of the Chinese accounts of the same early period.

The collection of the required materials having been at length completed, the next step was the preparation of the photo-lithographic facsimile Plates. And this was one of the most special divisions of the work. My object throughout has been, to place before my readers, in these Plates, as good substitutes, as can possibly be provided, for the original records; in order that they may be in a position to satisfy themselves as to the correctness or otherwise of my readings, and, on any doubtful points, to adopt any improvements which future researches may indicate. Any lithographs prepared from hand-tracings, eye-copies, or any similar materials, or even from mechanical impressions subsequently worked up by hand, are, of course, of absolutely no value whatever for critical purposes; for the reason that, no matter what amount of personal learning, skill, and care, may be brought to the work, the results are, not facsimiles of the original records as they really stand, but only facsimiles of those records as they have presented themselves to the eye of the individual reader of them; and, as long as such pseudo-facsimiles are the only substitutes available, so long there cannot cease to be varieties of opinion, and doubts and speculation, as to what the readings might be found to be, if the originals could be examined again *in situ*. To avoid anything of this kind, such of the ink-impressions as have been prepared under my own direction, *i.e.* all save eleven or twelve in the whole series, have been made with the most particular care, by purely mechanical means, by a man whom I have for a long time employed on such work, and who has attained considerable proficiency in it. And, by special sanction, the reproduction of them was made over to the well-known Photo-lithographic Establishment of Mr. W. Griggs, at Peckham, in which a good deal of work of the same kind had been previously turned out; and I was allowed to proceed to England, in order to superintend this part of the work in person. My own share here has simply been to see that the photo-lithographic reproduction was a faithful and mechanical process throughout; but this, of course, entailed the minute examination of two or three Proofs of each Plate, up to the final printing, in order to guard against the occasional distortion and blocking-up of letters, which is always liable to occur in reproducing such materials; and anyone, who has had practical experience, will know that careful supervision of such work takes up no little time. The results, however, have fully compensated for all the time and trouble that were spent in attaining them. And, with the valuable co-operation given by Mr. Griggs himself, through the personal interest which he takes in the reproduction of inscriptions, I am now able to submit to my readers a series of as absolutely faithful reduced facsimiles, as could possibly be prepared, of the original inscriptions and all their surroundings.

This part of the work was finished in December, 1885. I then returned to India, to complete the volume; and the Texts and Translations were ready for the Press at the end of May, 1886; though not quite in the same form throughout, in which they now appear. It was, however, then found that a number of accented types had to be prepared specially for this volume; and, owing to this and other causes, the first proofs were not fairly in hand till the following November. That they were so far started then, and that the work has progressed so quickly since then, is due to the friendly and earnest personal co-operation of Messrs. E. J. Dean and A. Sanderson, the Superintendent and Deputy-Superintendent of Government Printing, India, in whose office the volume has been printed; and I think I may fairly say that the volume gives a most excellent specimen of the style in which, under intelligent direction, the printing of large and important books can be done in India. I would also acknowledge here much assistance given by my friend, Mr. W. Rees Philipps, in reading the final proofs; as, since the commencement of the printing, I have never been less than five days distant from the Press by post, and have been part of the time in England, the assistance given by him on the spot, in Calcutta, has been most valuable in saving time. The printing of the Texts and Translations was completed in July, 1887. And the delay since then is due to the large amount of important matter, which, while they were being taken through the Press, I found myself in a position to include in the Introduction.

It will doubtless be remarked that, in the notes to my Texts, I have but seldom referred to the readings given in previously published versions of the same inscriptions. It soon became apparent to me that, to make any such references throughout, would increase the bulk of the book to at least twice what it now is, and encumber the pages of it with hundreds of footnotes of not the slightest practical value. I therefore abandoned, almost at starting, any idea of such a course; considering that the point was one which could interest only a very limited class of readers, and that, by giving in the introduction to each Text every reference that I could find to previous versions of it by other hands, I should afford those few special readers every facility for making any comparisons that might be necessary; and I have confined myself to noting previous mislections, only when they have had a bearing upon some historical name or other point of special importance. I offer my present versions of the Texts, not as absolutely final ones throughout, but as the most reliable ones that have as yet been produced; and as rendering possible now, for the first time, a thoroughly critical start in all the lines of research connected with the epigraphical materials of the period with which I have dealt. To take one special line as an instance,—it is only now that we are beginning to know properly the correct processes by which Hindu dates may be converted into their English equivalents. Much, in connection with this, still remains to be made known. And, as our knowledge advances, many improvements will undoubtedly be made in the interpretation, for instance, of numerical symbols, and of the other particular details of recorded dates. As an apposite instance, I would refer to note 2 on page 274. In this line, as in any other, I shall be only

too thankful for any suggestions that may be made to me, with a view to improvements in any future edition.

A serious obstacle, hitherto, in the prosecution of epigraphical researches, has been the want of full and systematic indexes. To the Index of the present volume, special attention has been given; in order that it shall include an easy reference to anything in this series of inscriptions that can bear on any of the lines of research connected with epigraphy. And, to this point, I trust that full attention will be paid, in future volumes of this series by other hands.

The original sanction for this volume, limited by the heavy cost of the Plates, was for two hundred and fifty copies. Towards the end of my work, however, many gratifying intimations came from England, the Continent, and India, that the book was likely to be far more popular, and a far more general subject of study, than even I myself had ever anticipated. Under these circumstances, there has now been printed an additional issue of two hundred and fifty copies, without Plates, and thus procurable at a moderate price. The copies of this issue, of course, contain everything that is essential for general readers. And the complete copy, with Plates, in the nearest Public Library, Society's Rooms, or College, will always furnish special students with the means of prosecuting inquiries on particular points of interpretation of the original texts.

As I have indicated above, the volume does not appear in quite the form in which it was originally prepared for the Press. It will not be thoroughly complete, without the Historical Chapters that should form the second part of it. These however could not be even drafted to any considerable extent, until the Texts and Translations were all in print, in order to facilitate constant reference and quotation. And the writing of the Historical Chapters will entail so enormous an amount of miscellaneous reading and annotation, for the purpose of tracing to their origin, in order to explain and completely refute, all the erroneous theories, in every connected line of inquiry, which have been started during the last fifty years in order to support any epoch rather than the correct one, that, having now again to give all my principal attention and energy to the ordinary duties of official life in the Revenue Department, I doubt much whether those chapters will ever be written by me. It has, in fact, been difficult enough for me to finish, to my satisfaction, even the present part of the volume. I have, therefore, taken advantage of the delay in printing, to incorporate in this part of the volume a variety of notes and remarks which I should have preferred keeping back for the Historical Chapters. They will, however, I think, be found to be not altogether misplaced; even if I may subsequently have to modify the views expressed in some of them.

Another point in which the delay in publication has been turned to even greater advantage, is in respect of the valuable matter which I have been able to include in the Introduction through the kind co-operation of Mr. Shankar Balkrishna Dikshit, of

the Bombay Educational Department. It was only at the end of December, 1886, that I made his acquaintance. But, since then, he has been most assiduous in making all the astronomical calculations, which were suggested by me to him as each new point developed itself in the special inquiries that, through his assistance, became possible. Two of his papers will be given in full in Appendices II. and III.; and the first of them will be found to explain thoroughly the process by which, with the late Professor Kero Lakshman Chhatre's Tables, anyone may now be able to calculate correctly the week-day, and the corresponding English date, for any given Hindu *tithi* or lunar day. The second point to which he has given his attention, is the elucidation of the system of the Twelve-Year Cycle of Jupiter, the years of which form so important a part in some of the records of the Early Gupta period. I find it impossible to over-estimate the work which he has done for me during the short period of our acquaintance. His assistance has been simply invaluable. Without it, I must have left all these subsidiary points for future determination; and must, of course, have left the all-important subject of the epoch of the Gupta era still open, within the limits of one year before and after the true date, to doubt and argument. With it, I am now able to prove everything that I have sought to establish, from the time when I first became aware of the full purport of the Mandasor inscription that gives the date of Kumāragupta and Bandhuvarman; and to present my case, as will be seen, in a thoroughly complete and satisfactory form.

J. F. FLEET.

INTRODUCTION.

BEFORE entering on the leading subject of this Introduction,—the determination of the epoch of the so-called Gupta era,—I would give a brief account of the scope of the book, and the arrangement of its contents.

The leading records are, of course, those of the **Early Guptas** themselves; ¹ from No. 1, the Allahâbâd posthumous stone pillar inscription of Samudragupta, down to No. 16, page 68, the Indôr copper-plate grant of Skandagupta, who, as far as we know at present, was the last of the direct line of the Early Gupta dynasty. The actual dates of these records extend from A.D. 401 to A.D. 466.

To the same period belong the two inscriptions of the **Rulers of Mâlava**; No. 17, page 72, the Gaṅgdhâr inscription of Viśvavarman, dated ² in A.D. 424; and No. 18, page 79, the Mandasôr inscription, dated in A.D. 474, which gives us the date of A.D. 437 for Kumâragupta and his feudatory, Bandhuvvarman; and, in doing so, has supplied what was always felt to be the most urgent desideratum, *viz.* a date, for any one of the Early Gupta kings, recorded in a standard era, capable of identification, other than the era which was habitually used by the Early Guptas themselves. With the exception of a few among the Miscellaneous Inscriptions, to be noticed hereafter, No. 17 is the last record that belongs specifically to the Early Gupta dynasty.

But, shortly after the time of Skandagupta, we meet with the two names of **Budhagupta** and **Bhânugupta**, with the dates of respectively A.D. 484, in No. 19, page 88, and A.D. 510, in No. 20, page 91. And, coupled with the fact that, in the inscriptions of the Parivrâjaka *Mahârâjas*, the Gupta sovereignty is distinctly stated to have continued down to A.D. 528, the termination of these names raises at least a presumption that these two kings were of the Early Gupta lineage, though possibly not connected by direct descent with Skandagupta. Budhagupta comes, chronologically, immediately after Skandagupta. Bhânugupta comes somewhat later; after Tôrâmaṇa, whose power meanwhile succeeded that of Budhagupta in Eastern Mâlwa. But, under all the circumstances,

¹ I call the members of this family the "Early Guptas," by way of easily distinguishing them from the later Guptas of Magadha, whose genealogy is given in the Apsad inscription, No. 42, page 200, and in the Dêô-Baraṇârî inscription, No. 46, page 213.

² In respect of these three dates, I follow here the equivalents that I have given in my introductory remarks to the two inscriptions. But, when the proper value of expired years of the Mâlava or Vikrama era can be determined, perhaps it may be found that these three dates, and any others of the same series, are each one year earlier than as at present given by me.

the most convenient arrangement has been, to place the record which mentions him, next after that of Budhagupta.

In No. 21, page 93, down to No. 25, page 112, we have some inscriptions, ranging from A.D. 475 to A.D. 528, which overlap, on one side, the time of Budhagupta, and on the other, the periods of Tōramāna, Bhānugupta, and Mihirakula. They are the records of a feudatory family, to the members of which it is convenient to give the name of the **Parivrājaka Mahārājas**.¹ And the extreme importance of them lies in the fact that they expressly shew that, though the direct line of the Early Gupta dynasty itself may have become extinct, the Gupta dominion still continued, and the name of the Gupta kings was still recognised as a power, down to A.D. 528. Another very special feature in them, as will be seen, is the use of the Twelve-Year Cycle of Jupiter, in the records of the dates. As will now be shewn for the first time, this point really furnishes most valuable corroboration, if not actually independent and conclusive proof, of my general results as to the exact year from which the dates of the Early Guptas and their successors run.

Closely connected with the preceding, both chronologically and territorially, was another family, that of the **Mahārājas of Uchchakalpa**, whose records we have in No. 26, page 117, to No. 31, page 135; with also a mention of one member of this family, the *Mahārāja Śarvanātha*, in No. 24, page 110, which proves that, at the date therein referred to, he was the contemporary of the Parivrājaka *Mahārāja* Hasun. And the recorded dates of this family, if referred to the Gupta era, range from A. D. 497 to 533-34. That this is the proper interpretation of the dates, was assumed by General Cunningham who first brought all the Uchchakalpa grants, save one, to notice.² And my own view has been the same. But a later consideration of the question shewed that there are a few points in the inscriptions, which, if the existence of the Kalachuri or Chèdl era, as a separate era, could be satisfactorily established, render it possible that these dates are recorded, not in the Gupta era, but in the Kalachuri era; which, even with General Cunningham's proposed epoch³ of A.D. 249-50, would suit all the requirements almost as well as the Gupta era, and, with an epoch about twenty-five or thirty years later, would suit them much better. Thus, in particular, the understanding that, while the Parivrājaka *Mahārājas* were feudatories of later members of the Early Gupta dynasty, the *Mahārājas* of Uchchakalpa, whose territories evidently lay more to the east and south-east, were feudatories of Kalachuri kings, would explain at once why no era is quoted in the Bhumarā pillar inscription, No. 24, page 110; the reason being that the feudatories of the two rival dynasties could not agree as to which of the two rival eras should be used. Again, this same record shews that the *Mahārājas* Hastin and Śarvanātha were contemporaneous in the Mahā-Māgha *samvatsara* that is mentioned in it. Now, for Hastin we have the extreme dates

¹ See page 95, note 1.

² *Archæol. Surv. Ind.* Vol. IX. p. 9 ff.

³ See *Indian Eras*, p. 60 ff.

of Gupta-Sarvat 156 and 191; and for Śarvanātha, the extreme dates of the years 193 and 214, with the year 177 as the latest known date for his father Jayanātha. And, as it is unlikely that Hastin continued alive and in power for any length of time after Gupta-Sarvat 191, it seemed, on the supposition that both the series of dates were to be referred to the Gupta era, that the Mahā-Māgha *samvatsara* in question was the one commencing in Gupta-Sarvat 189, rather than that commencing in Gupta-Sarvat 201; since, the former was easily obtained by adding only four years at the commencement of the period for Śarvanātha; whereas, to obtain the latter, we should have to add on ten years at the end of Hastin's already long enough period of thirty-six years. On the other hand, the Mahā-Māgha *samvatsara* occurred previously, in Hastin's period, in Gupta-Sarvat 165 and 177. If the Uchchakalpa dates were referred to the Kalachuri era, with General Cunningham's epoch of A.D. 249-50, Śarvanātha's latest date the year 214, would be equivalent to A.D. 463-64, or Gupta-Sarvat 144; and we should have to add on twenty-one years at the end of his known period, in order to make him the contemporary of Hastin in Gupta-Sarvat 165. Whereas, if an epoch could be found for the Kalachuri era about twenty-five years later than that proposed by General Cunningham, the two *Mahārājas* would be naturally contemporaneous in Gupta-Sarvat 165 or A.D. 484-85. By calculation, however, Mr. Sh. B. Dikshit found that, though General Cunningham's proposed epoch might be very close to the real truth, yet it was certainly not the absolutely correct one. Also, though he found that nearly all of the ten Kalachuri or Chēdī dates, given by General Cunningham,¹ would work out correctly with an epoch of A.D. 248-49, or just one year earlier than that proposed by General Cunningham, yet both he and I felt that the available data, in the shape of the published readings and lithographs of the dates, were not sufficiently reliable for any definite theory to be built up on the results obtained by him. Again, if the Kalachuri era really existed in that early time,²—in which case, of course, there were then actually kings of the Kalachuri dynasty,—it seemed strange that no distinct reference should be made to the dynasty in the Allahābād pillar inscription, which, with much minuteness of detail, claims for Samudragupta the conquest of the whole earth;³ especially since the Mahākūṭ pillar inscription of the Early Chalukya king

¹ *Indian Eras*, p. 61.

² I do not overlook the 'Pardi' grant of the Traikūṭjaka *Mahārāja* Dahrasēna (*Jour. Bo. Br. R. As. Soc.* Vol. XVI. p. 346 ff.), which is dated in the year 207 of an unspecified era; or the Kanheri plate (see No. 10 of the separate publications of the Archaeological Survey of Western India, p. 57 ff.), which is dated "in two centuries of years, increased by forty-five, of the augmenting sovereignty of the Traikūṭjakas." But it still has to be proved, either, on general grounds, that the era of these two records, is the Kalachuri era; or that the Trikūṭja whence these Traikūṭjakas derived their name, is identical with Tripura or Tripurī, the capital of the Kalachuris of Central India.

³ Prinsep, indeed (see, for instance, *Prinsep's Essays*, Vol. I. p. 237), found the possible mention of a Tripura in the Karttipura which is spoken of in line 22 of this inscription. But he would have identified it with the modern 'Tipperah.' And the immediate connection of Karttipura, in the inscription, with Samatāja or Lower Bengal, Davāka (? 'Dacca' if the correct spelling really is *Dākā*), Kāmarūpa or Assam, and Nēpāl, shews that the place was indeed very far away from Central India.

Maṅgallā¹ shews that the dynastic name was very well established in at least the sixth century A.D., and mentions it under the Sanskritised form of Kalatsūri. As, however, the Kalachuris, in their later records, represent themselves as descendants of Sahasra-Arjuna or Sahasrabāhu-Arjuna,² the required reference to them in the Allahābād inscription might be found in the Ārjunāyanas, who are mentioned in line 22; and no special objection need be taken on that ground. The real difficulty was to prove that the Kalachuri era, and, with it, sovereigns of the Kalachuri dynasty, really existed in early times; and that the era was not merely one of somewhat later invention, fitted to an early epoch. But, since the time when I first drafted the preceding remarks, Prof. Kielhorn has determined, quite recently,³ that, if we only take three of the ten dates in question as denoting expired years, all the dates will work out correctly with the epoch of A.D. 248-49. It is, therefore, really a question for consideration whether the *Mahārājas* of Uchchakalpa were not indeed feudatories of early kings of the Kalachuri dynasty; and whether the dates of their records do not furnish the earliest instances of the use of the Kalachuri era. Unfortunately, these Uchchakalpa dates do not contain details for computation; and the question, accordingly, cannot at present be decided in that way.

The inscriptions contain various hints as to the causes which led to the downfall of the Early Gupta sovereignty. But, looking round on all these intimations, with the help of extraneous information, the person who accomplished their final extinction seems undoubtedly to have been the great king Mihirakula, of Śākala in the Pañjāb, and subsequently of Kaśmir, whose career in India is so graphically described by the Chinese pilgrim Hiuen Tsiang. Among epigraphical records, his name had long been extant, though it had not been recognised, in an inscription at Gwālīor, No. 37, page 161, where it occurs as the name of a son of Tōramāṇa. I myself, when I first recognised the word as a proper name, took it to be the appellation of a second Mihirakula, given in memory of his father Tōramāṇa's former lord and master. The first discovery that militated against this view, was, my finding that the great Mihirakula himself is mentioned in the Mandasōr duplicate pillar inscriptions, No. 33, page 142, and No. 34, page 149, as having been overthrown by a powerful king of Northern India named Yaśōdharman; shortly after which I obtained for Yaśōdharman the date of A.D. 533-34, in the Mandasōr inscription, No. 35, page 150. From certain details in their Ēraṇ inscriptions, it was evident that Tōramāṇa came, in Eastern Mālwa, very shortly after Budhagupta; the proof of this is that Budhagupta's inscription mentions a certain *Mahārāja* named Mātrivishṇu, and his younger brother Dhanyavishṇu, as being both then alive; whereas Tōramāṇa's inscription mentions Dhanyavishṇu as still alive, but Mātrivishṇu as deceased; and these statements shew that Tōramāṇa followed Budhagupta, in Eastern Mālwa, within the remnant of the generation

¹ See my *Dynasties of the Kanarese Districts*, pp. 22, 58

² *Ind. Ant.* Vol. XII p. 250, line 16.

³ *Archæol. Surv. Ind.* Vol. IX. p. 92, verse 7.

⁴ See the *Academy* of the 10th December, 1867, p. 394 f.

to which the brothers Mātṛivishṇu and Dhanyavishṇu belonged. Putting everything together, in writing my paper on "The History and Date of Mihirakula,"¹ it soon became perfectly clear that the king who is mentioned in the Gwālior inscription, is the great Mihirakula himself; that he was the son of Tōramāna; and that his downfall was accomplished by Yaśōdharman within a very few years on either side of A.D. 533-34. In proper chronological order, therefore, Tōramāna and Mihirakula come next after Budhagupta; and Tōramāna certainly, and probably Mihirakula also, so far as Eastern Mālwa is concerned before Bhānugupta. Plate xxiii A. and B. should, therefore, properly have been placed next after Plate xx. To my present brief notice of these two kings,—who belonged to a foreign race, which, whether best and most properly known as Indo-Scythians, Sakas, Hūṇas, Turushkas, Shāhis, Shāhanushāhis, or Daivaputras, had established itself in the Pañjāb at an early date, and continued in power down to at least the time of Samudragupta,—I will only add that, the first year of Tōramāna, which is recorded in his inscription, and which fell for certain after A.D. 484, which is Budhagupta's inscriptional date, and before A.D. 510, which is Bhānugupta's inscriptional date, is evidently only the first year of his possession of Eastern Mālwa. Coming down, as he did, from the extreme north-west corner of India, it is impossible that we should suddenly find him, fully established as the first of a new dynasty, in the very heart of the Gupta country, in absolutely the first year of his reign. His own dynastic date, which must correspond to just about the same year, is given in his silver coins, which follow the Early Gupta silver coins in general style, but differ from them in certain marked peculiarities that were evidently introduced for the express purpose of shewing that his power was hostile to theirs, and had superseded it. There are two excellent specimens of his coins, which I have examined, in the British Museum; and the date on them is the year 52 or 82, in numerical symbols. General Cunningham² has read the dates as 52 and 53; but the second symbol in each case is certainly 2; as regards the first symbol, I will not at present give a final opinion as to whether it is 50 or 80; since, though probably a 50, it is possibly an 80, turned half round on the die, so as to lie vertically, instead of horizontally, in order that it might not fall chiefly beyond the edge of the coin. Without doubt, it would make the case very simple indeed, if we could read the date as 182, as Mr. Thomas did,³— or even read it as 82, and, on the theory of "omitted hundreds," interpret it as 182,— and refer it to the Gupta era, with the result, now, of A.D. 501-502. But the date is either 52 or 82, and nothing else; without the slightest grounds for supposing that the symbol for 100 was stamped, but has now become obliterated, or was engraved on the die, but, in the stamping, fell beyond the edge of the coin; and, if it has to be interpreted as 152, on the theory of "omitted hundreds," then at any rate it cannot possibly be referred

¹ *Ind. Ant.* Vol. XV. p. 245 ff.

² *Archæol. Surv. Ind.* Vol. IX. p. 26 f.; and see *id.* Plate v. Nos. 18, 19.

³ *Prinsep's Essays*, Vol. I. p. 340, and *Archæol. Surv. West. Ind.* Vol. II. p. 66; see also *id.* p. 36, Plate vii. Nos. 27, 28.

to the Gupta era. I have shewn elsewhere¹ that Mihirakula's fifteenth year, which is recorded in his Gwālior inscription, must fall somewhere very close to A.D. 533-34, which is the recorded date of Yaśōdharman; and in all probability a year or two before it; so that we shall be very near the mark, if we select A.D. 515 for the commencement of his career. If, then, the date on Tōramāṇa's coins is 52, and if we apply it as his regnal date, about which there need be felt no special difficulty. Tōramāṇa's reign must have commenced, roughly, about A.D. 460. This falls very near the latest date, A.D. 466, that we have for Śkandagupta, who, up to A.D. 457-58, held the whole of Northern India, below the Pañjāb, from Kāthiāwād to the frontier of Nēpāl. And it was doubtless the death of Skandagupta, that enabled the Hūnas, who had been repulsed by him, to assume the aggressive again, under the leadership of Tōramāṇa; and, on this occasion, with such success as to hold even Central India for a short time. This view is also in perfect accordance with the statement of the Valabhl inscriptions,² that it was the founder of their family, the *Sēndapati* Bhaṭārka; with the date of about A.D. 500, who successfully fought, in Kāthiāwād, against the Maitrakas, i.e. the Mihiras, i.e. the particular family or clan, among the Hūnas, to which Tōramāṇa and Mihirakula belonged. If, or the other hand, the date on Tōramāṇa's coins is 82, then it cannot be applied as a regnal date; and, though it must then run for the period at which his own branch of the Hūnas rose to power, it cannot be used to fix the commencement of his own accession. The general outline of the history of the period, which I have briefly indicated above, would, however, remain much the same.

To some time or other in this early period belongs the mysterious emperor **Chandra**, of whom we have a posthumous record in the iron pillar inscription at Mēharaul. No. 32, page 139. I call him mysterious, because, though the inscription speaks of him as a powerful supreme monarch, who conquered the whole of Northern India, from beyond the river Indus down to the plains of Bengal, yet it makes no mention of his lineage, and gives no clue by which we can determine exactly his period and surroundings. All that we know for certain, is, that his inscription belongs, on palæographical grounds, to a fairly early date. In the palæography of it, there is, in fact, no real obstacle to our allotting it to Chandragupta I., the first paramount sovereign in the Early Gupta family; and the only objection that I can see, is, that it contains no reference to the Indo-Scythian kings, unless they are here called Vāhlikas, by overthrowing whom Chandragupta I. must have established the power of his own family. But there is an interesting point in the fact that the name of the village at which this inscription stands, *vis.* Mēharaul or Mēhharaul, is an evident corruption of Mihirapurī, 'the city of the Sun, or of the Mihiras.' Mihira, as a proper name, is a Sanskritised form of the name of the family, clan, or tribe among the Hūnas, to which belonged Mihirakula and his father Tōramāṇa. And it is not

¹ *Ind. Ant.* Vol. XV. p. 252.

² See page 167, and note 11.

impossible that this inscription may be shewn hereafter to be a record of the younger brother of Mihirakula, who, when Mihirakula was defeated by Bāladitya of Magadha, usurped his throne in the Pañjāb, and whose own name is not mentioned by Hiuen Tsiang.

As has been indicated above, the Mandasōr duplicate pillar inscriptions, No. 33, page 149, and No. 34, page 149, which are brand-new discoveries, introduce us to a powerful king of Northern India, named Yaśōdharman, who is of extreme interest from being mentioned in them as the conqueror of Mihirakula. And the remaining Mandasōr inscription, No. 35, page 150,—again a brand-new discovery,—is another record of this same Yaśōdharman, coupled in this case with a king named Vishṇuvardhana; and it is of extreme value from the fact that, by supplying for Yaśōdharman a specific date, A.D. 533-34, it has completed the clue to the whole history of the period. Who Vishṇuvardhana was, cannot at present be determined; but he is at any rate not the feudatory Vishṇuvardhana, the Varika, who is mentioned in No. 53, page 252.

Next in chronological sequence, but slightly overlapping some of the preceding records, come the inscriptions of the Kings of Valabhi, ranging, so far as absolutely definite dates are concerned, from A.D. 426 to A.D. 766. Of the numerous copper-plate inscriptions of this family that have been discovered, I have given two, as specimens; No. 38, page 164, and No. 39, page 171. Apart from the full genealogical tree which they give, including twelve generations, they are of interest chiefly because they make known the historical fact that the *Sēndapati* Bhaṭārka, the founder of the family, successfully waged war against, and overthrew, a dynasty, tribe, or clan, called Maitrakas, which has already been the subject of comment; and because they shew that the Gupta era continued in use, in Kāthiāwāḍ and some neighbouring parts of Gujarāt, at least as late as A.D. 766, and thus explain, through its special connection with their own family, how it came to have, in later times, the name, in the same part of the country, of the Valabhi era. Otherwise, the inscriptions of this family contain but little of historical importance; though a full examination of them would throw much light on the ancient geography of the localities from which they come. It is a curious fact that no stone-inscriptions of this family,—at least, none that can be definitely attributed to them,—have as yet been discovered. Last year, it is true, Colonel J. W. Watson obtained at Walā, which is the modern representative of the ancient Valabhi, part of a stone-inscription, now in the Library of the Bombay Branch of the Royal Asiatic Society, the characters of which shewed me that it belonged to the earlier part of the Valabhi period. But it is the merest fragment; with no historical clue in it. It is, however, of interest, in shewing that the excavations at Walā are now reaching the level of stone-remains. When that level can be properly explored, discoveries of importance ought to follow; since, for some reason or other, inscriptions on stone nearly always contain much more historical information than copper-plate grants do.

In the Ēraṇ posthumous pillar inscription of Gôparāja, No. 20, page 91, mention is made of the family of the Śarabha kings. Two inscriptions of the Rājas of Śarabhapura are given in No. 40, page 191, and No. 41, page 196. There is nothing to shew the exact period to which they belong; much less to identify either of the Rājas mentioned in them with Gôparāja's maternal grandfather. But the characters indicate that they may perhaps be attributed to a period not far distant from that of Gôparāja; and the present place has been found a convenient one for introducing them. At the same time, they may possibly be found hereafter to belong to a period later by a couple of centuries than the time of Gôparāja. Another inscription of the Rāja Mahā-Sudēvarāja has been published by Dr Rajendralala Mitra, in the *Four. Beng. As. Soc.* Vol. XXXV. page 195 ff.; but the original plates have disappeared, with several other valuable copper-plate grants that were presented to the Bengal Asiatic Society; and the published version is not sufficiently reliable to be reproduced. I have, therefore not been able to include that inscription in this collection.

In No. 42, page 200, to No. 46, page 113, we have some inscriptions of the Guptas of Magadha, a family of which one memoir at least, the great Ādityasēna, played an important part in the history of the seventh century A.D., when the Kanauj kingdom was broken up on the death of Harshavardhana. From the way in which, through the eleven generations of this family that are recorded, every name, except that of Ādityasēna, has the termination *gupta*, there can be little doubt that the family is an offshoot of the original Gupta stock. And, reckoning back from the time of Ādityasēna, for whom the date of A.D. 672-73 is supplied by the Shāhpur inscription, No. 43, page 208 Krishna Gupta, from whom the descent is traced, has to be placed between A.D. 475 and 500. He was, therefore, a contemporary of Budhagupta or Bhānugupta, or of both of them, and came very shortly after Skandagupta. His exact connection, however, with any of these three kings, still remains to be determined.

The Aphaṣḍ inscription of Ādityasēna, No. 42, page 200, introduces us to two important contemporaneous families. The first of these is that of the Maukharis, or Mukharas, of whom we have inscriptions in No. 47, page 219, to No. 51, page 228. The great antiquity of this family is shewn by a clay seal in General Cunningham's possession, obtained at Gaya, which has on it, in Aśōka characters, the Pāli legend *Mōkhalinam*, "of the Mōkhalis, Maukhalis, or Maukharis." No. 47, page 219, gives us the names of three feudatory *Mahārājas*, followed by two paramount sovereigns, of one branch of this family; and it is probably the *Mahārāja* Īśvaravarman, of this branch, of whom we have a record in No. 51, page 228. A connecting link between these aukharis and the Guptas of Magadha seems to be established in Ādityavarman's wife, Harshaguptā, who was probably the sister of Harshagupta of Magadha. Subsequently, the relations between the two families were less friendly. Thus, it can hardly be doubted that the king Īśānavarman of this family is the one who, as recorded in line 6 f. of the Aphaṣḍ inscription, was conquered in battle by

Harshagupta's grandson, Kumāragupta. Dāmōdaragupta, again, in the same inscription, is mentioned as breaking-up the forces of the Maukhari king, which had previously overcome the army of the Hūpas. And the Susthitavarman who was conquered in battle by Mahāsēnagupta, doubtless belonged to the same lineage. Other references to the Maukharis are to be found in the *Harshacharita* of Bāṇa, and in the Nēpāl inscriptions.¹ Nos. 48, 49, and 50, give us another minor branch of the Maukhari lineage, of evidently much less importance, belonging to the neighbourhood of Gayā.

The second of the contemporaneous families introduced by the Aphaṣṣ inscription, is that of the **Kings of Kanauj**, to which belonged the great Harshadēva or Harshavardhana. Of this king I am able to give a brand-new inscription, in the Sōnpat seal, No. 52, page 231. This is the first epigraphical record of this family that has ever been obtained; and it is of extreme interest in carrying back the genealogy to two generations before Harshavardhana's well-known father, Prabhākaravardhana, and in showing that the latter was the first paramount sovereign in the family. The verse in the Aphaṣṣ inscription which mentions Harshavardhana, under the name of Harshadēva, is partly obliterated; but it refers to Mādhavagupta either as a feudatory of the Kanauj king, or as seeking an alliance with him. A connection between the two families appears to be established in Mahāsēnaguptā,² the wife of the *Mahārāja* Ādityavardhana, who was the grandfather of Harshavardhana; it can hardly be doubted that she was a sister of Mahāsēnagupta of Magadha, the father of Mādhavagupta. Another point of importance in this Sōnpat seal, is, that it shews that the father of Prabhākaravardhana was neither Pushpabhūti or Pushyabhūti, who is mentioned by Bāṇa, in his *Harshacharita*, in connection with this family; nor king Śīlāditya of Mālava, who is spoken of by Hiuen Tsiang, but the feudatory *Mahārāja* Ādityavardhana. That Śīlāditya of Mālava was the father of Prabhākaravardhana, was assumed by Mr. Fergusson.³ And Prof. Max Müller has asserted the same relationship in respect of Pushpabhūti;⁴ but Dr. F. E. Hall⁵ only speaks of Pushpabhūti as an ancestor, more or less remote, of Harshavardhana; and Dr. Bhagwanlal Indrajī,⁶ who writes the name Pushyabhūti, only speaks of Harshavardhana as belonging to the Pushyabhūti dynasty.

No. 53, page 233, to No. 56, page 243, are inscriptions of the **Vākātaka Mahārājas**. Their date is determined by the marriage of Rudrasēna II. with Prabhāvatiguptā, the daughter of the paramount sovereign Dēvagupta, who, it can hardly be doubted, was Dēvagupta of Magadha,⁷ the son of Ādityasēna, mentioned in the Dēś-Baraṇṅk inscription, No. 46, page 213, and belonging to the period of about A.D. 680 to 700. This brings

¹ *Ind. Ant.* Vol. IX, p. 103 ff.

² See page 232, note 3.

³ *India; What can it teach us?*, p. 288.

⁴ *Vāsavadattā*, Preface, p. 51; in his analysis of the *Harshacharita*.

⁵ *Ind. Ant.* Vol. XIII, p. 74.

⁶ *Jour. R. As. Soc. N. S.* Vol. IV, p. 87

⁷ See page 215, note 7.

the Vākātaka *Mahārājas* to a period later by fully two centuries than has hitherto been allotted to them; but there is nothing in the palæography of their grants to oppose this result, even if it does not actually prove it. A clear instance of the comparatively long preservation of antique characters for official purposes, is furnished by the Rājim grant of the *Rāja* Tivarādēva, No. 81, page 291, which is undoubtedly almost, if not quite, the latest record in this volume, though at first sight its characters would seem to refer it to a much earlier period.


In No. 57, page 249, to No. 81, page 291, I have given a variety of **Miscellaneous Inscriptions**, which, either from their not mentioning the name of any particular king, or for other reasons, it was not convenient to introduce in other places in accordance with the chronological order that has been the chief basis of the arrangement of the volume. Of these, the most interesting are No. 60, page 254, which is a spurious grant purporting to have been issued by the Early Gupta king Samudragupta; No. 61, page 258, which, apart from its recorded date, expressly refers itself to the Early Gupta period, and which also, like No. 15, page 65, furnishes interesting proof of the existence of the Jain sect in the fourth century, A.D.; and No. 71, page 274, the Bôdh-Gayâ inscription of Mahânâman, dated in A.D. 588. This is another brand-new discovery, made by General Cunningham. And its extreme interest lies in the fact that, as the Mahânâman, whose record it is, can hardly be any other than the well-known person of that name who wrote the more ancient part of the Pâli *Mahāvamsa* or History of Ceylon, its date shews either that the details of the Ceylonese chronology, as hitherto accepted, are not as reliable as they have been supposed to be, or else that a wrong starting-point has been selected in working out those details; and it furnishes a definite point from which the chronology may now be adjusted backwards.

THE GUPTA ERA.

We come now to the question which, for the last forty years, has been at issue among all scholars who have been interested in the ancient history of India, and which, from the impossibility, until the discovery of the Mandasôr inscription of Kumâragupta and Bandhuvarman, of arriving at any sound and final settlement of it, has created the almost inextricable confusion that now prevails in every line of research connected with the Early Gupta period: *vis.* the determination of the exact chronological point to which we must refer the commencement of the era that was used, for the purpose of dating their records and coins, by the Early Gupta kings and some of their successors.

For reference in the following discussion, I give, in Table I. page 17 below, a **genealogy of the dynasty**, with the official titles and recorded dates of the members of it. And, below the unbroken succession, I insert the names of Budhagupta and Bhânugupta;

TABLE I.
Genealogy of the Early Gupta Kings.



because there is at least a strong possibility that they were descended from the same stock, though their connection with each other, and with Skandagupta, has not as yet been made clear; and because the date of Budhagupta, at least, has always been accepted as bearing on the chronological question. The dates are taken partly from the inscriptions, and partly from the silver coins, on which I have published a note in the *Ind. Ant.* Vol. XIV. p. 65 ff. Thus, the coins supply the dates of Gupta-Samvat 94 or 95, for Chandragupta II.; 130 odd, for Kumâragupta; ¹ 144, 145, 148, and 147 or 149, for Skandagupta: and 175, and possibly also 180 odd, for Budhagupta. The secondary names of the kings are taken partly from the silver coins, and partly from the gold coins, on which a very exhaustive and valuable treatise has been published by Mr. V. A. Smith, in the *Four. Beng. As. Soc.* Vol. LIII. Part I. p. 119 ff., noticed by me in the *Ind. Ant.* Vol. XIV. p. 92 ff. The names of Vikramāditya, Mahêndrāditya, and Kramāditya, for respectively Chandragupta II., Kumâragupta, and Skandagupta, are supplied by the silver coins; and the first two, in the abbreviated forms of Vikrama and Mahêndra, occur also on some of the gold coins; as also, perhaps does the full name Kramāditya, for Skandagupta. And Vikramânka, which is of constant occurrence as a synonym for Vikrama and Vikramāditya, occurs on a silver coin which seems undoubtedly to belong to Chandragupta II. As regards Chandragupta I., it is still a moot point whether certain gold coins, which bear the name of Vikrama and Vikramāditya, are to be allotted to him, or to his grandson; but I myself do not see any difficulty about allotting them to him, and in understanding, therefore, that he also had these same secondary names; I have, however, inserted them in brackets, as being open to the possibility of doubt. Kâcha, as a possible second name of Samudragupta, is taken from some gold coins on which I have commented at page 27, note 4; this however, is also bracketed, as being not yet quite certain. The coins, both gold and silver, present many other points of considerable interest, some of which I have briefly alluded to in my notes to the Texts and Translations, but the full consideration of them belongs to the Historical Chapters.

The genealogy, as given by Mr. Thomas in his edition of *Prinsep's Essays*, Vol. I. p. 245, includes the name of Dêvi, a daughter of Mahâdaitya, as one of the queens of Samudragupta; and, as a son of Skandagupta, a young prince, whose name is suggested to be Mahêndragupta. The entry of Dêvi and Mahâdaitya, appears also in the same list as republished by Mr. Thomas in the *Archæol. Surv. West. Ind.* Vol. II. p. 19, and again in the *Four. R. As. Soc.* N. S. Vol. XIII. p. 533; in each of which places we also find, as another wife of Samudragupta, a queen, name unknown, the daughter of an independent princess 'Sanhârikâ.' The second list repeats the name of Mahêndragupta; but, in the third, there are substituted the words "royal issue expected at the date of this inscription," i. e. of the Bhitari pillar inscription of Skandagupta. The existence of the supposed

¹ *Archæol. Surv. Ind.* Vol. IX. p. 24, and Plate v. No. 7.

Mahēndragupta, however, as pointed out by me on page 56, note 2, is due to nothing but Dr. Mill's original mislection of the Bhitari inscription, coupled with the real name of Mahēndrāditya on Kumāragupta's coins. And the existence of the independent princess 'Sanhārikā,' with her unnamed daughter, and of Mahādaitya, and his daughter Dēvi, is equally imaginary; being due, as indicated on page 1, only to early mislections of the Allahābād pillar inscription. In his first list, Mr. Thomas entered the *Mahārāja* Gupta, and his descendants, as belonging to the Solar lineage; and this mistake, though not repeated in his second and third lists, has not even yet been completely eradicated; but, as shewn on page 1, the statement rests on nothing but Dr. Mill's mislection of a passage in the Allahābād inscription.

The Nomenclature of the Era.

Before proceeding further, however, it is desirable now to draw attention pointedly to the fact that, though it is convenient to speak of the era in question as the Gupta era, yet we have no ancient authority whatever for connecting the name of the Guptas with it, as the establishers of it, and much less for accepting the early existence of any such technical appellation for it, as *Gupta-kāli*.

It is true that this term is used by Albērūni, who speaks of the *Gūbt-kāl* or *Gūbita-kāl*, i.e. *Gupta-kāli*. But, in just the same manner, he uses also the expression *Śaka-kāli* for the Śaka era. In each instance, his use of the word *kāli* is in perfect consonance with its meaning, 'time, or a space of time,' and with the application of it in the sense of 'an era.' And the Hindus who furnished him with the information that he recorded, but who can have known nothing certain about the origin of the era, save only that it had come down to them through the Gupta kings, would naturally speak of it as the *Gupta-kāli*. But Albērūni's statements belong to the eleventh century A.D.; and furnish no real authority, on such a point as this, for early times.

It is true, also, that the words *Guptasya kālād*, "from the era of Gupta," were supposed by Dr. Bhau Daji¹ to exist in line 15 of the *Junāgaḍh rock inscription of Skandagupta*. But the real reading there, as is quite clear even in the lithograph from which Dr. Bhau Daji worked, is not *Guptasya kālād*[*d*]-*ganandm vidhāya*, "counting from the era of Gupta," but *Gupta-prakālā ganandm vidhāya*, "making the calculation in the reckoning of the Guptas." And there can be little doubt that Dr. Bhau Daji's reading, and his translation, which was more or less unavoidable after the adoption of the reading, were suggested by M. Reinaud's previously published translation of the extract from Albērūni, in which, though translating *Śaka-kāli* by "the era of Śaka," he transliterated the original Arabic by *Gupta-kāli*, with the words "era of the Guptas" added in brackets.² Dr. Bhau Daji's

¹ *Jour. Bo. Br. R. As. Soc.* Vol. VI. p. 207; Vol. VII. pp. 114, 123.

² *Fragments Arabes et Persans*, p. 143.

reading was unfortunately accepted without further investigation; and has stood up to the present time. And, in particular, it was most emphatically endorsed by Mr. Thomas, who, in 1876, and again in 1881, stated that he had previously had doubts as to the correctness of the reading and translation, but had then become quite satisfied concerning it, from a personal comparison of Dr. Bhau Daji's materials with others.¹ It is undoubtedly only to this erroneous opinion, that we must attribute Mr. Thomas' later belief² that on certain coins of 'Syalapati,' he could read the syllables *Gu* and *Gupta*, with possible indications of even *Guptasya*, shewing, it was supposed, that the dates on these coins referred to an era of Gupta, or the era of the Guptas. These, however, are purely imaginary readings. And the fact remains that, in the Junâgadh inscription, the expression *Guptasya kâla* does not occur. And,—apart from the obvious meaning of the words; and from the fact, which will be insisted on more strongly further on, that the *Mahârâja* Gupta, the founder of the family, being only a feudatory *Mahârâja*, had not the power of establishing an era at all,—that, in the real reading *Gupta-prakâsh*, we are to interpret the first member of the compound as representing the genitive plural, not singular, is expressly indicated by the use of the full genitive plural, *Guptânâm*, governed by *kâla*, in another date in line 27 of the same inscription. Of course, both these passages connect the era with the Guptas, as belonging to them, and as being used by them; which had then been the case, so far as their epigraphical records go, for at least three generations. But not either of them suffices to shew that it had been established by them; or even that it had, at that time, acquired the technical name of the "Gupta era." And what the first expression really shews, is, simply that the date was being recorded in an era which was new to Kâthiâwâd, and was not the customary era of that part of the country.

In dated records, the genitive plural, *Guptânâm*, occurs again in line 2 of the **Kahâuh pillar inscription of Skandagupta**, No. 15, page 65. But there it is governed by *vamsa*, in *vamsha-jasya*. "of Skandagupta, who is born in the lineage of the Guptas." So, also, we have *Gupta-ânvayânâm* in line 1 of the **Udayagiri cave inscription** of the year 106, No. 61, page 258. But it is governed by *kulasya*; "in the augmenting sovereignty of the family of those who belong to the lineage of the Guptas." These two passages, therefore, do not bear on the question at all.

Again, in the **grants of the Parivrâjaka Mahârâjas Hastin and Sankshôbha**, No. 21, page 93, to No. 23, page 106, and No. 25, page 112, we have the expression *Gupta-nripa-râjya-bhuktâu*, "in the enjoyment of sovereignty by the Gupta kings." And this

¹ *Archæol. Surv. West. Ind.* Vol. II. p. 22; and *Jour. R. As. Soc. N. S.* Vol. XIII. p. 538.

² See Sir E. Clive Bayley's "Remarks on certain Dates occurring on the Coins of the Hind Kings of Kâbul," in the *Numismatic Chronicle*, Third Series, Vol. II. p. 128 ff.

expression is of importance, in shewing clearly that the Gupta dynasty and sway were still continuing, and that the dates of these records are to be referred to the same era with the dates of the Early Guptas themselves. But there is nothing at all in the expression, tending to give the era the name of the "Gupta era."

In the **Môrbī grant of Jâinika**, again, as read by Dr. R. G. Bhandarkar,¹ we are supposed to have a very clear intimation indeed, that the era was then known as the Gupta era; his reading and translation being,—*pañc-âśtīyâ yutê-titê samânâm śata-pañchakê | Gaupťê dadāv=adô nripah s-ôparâge=rka-niamđalê*,—of which a more literal translation than that given by him, would be "the Gupta fifth century of years, together with eighty-five (*years*), having elapsed, the king gave this, when the disc of the sun was eclipsed" There is a difficulty in disposing finally of the whole bearing of this inscription; for the reason that the first plate had been lost sight of, before the grant was obtained for examination at all; as the result of which, the genealogy of Jâinika is not known; and the second plate contains no name of a place, unless we are to find it in the verse that I have quoted. And now, even the second plate also, the published one, has been mislaid, and is not forthcoming. That the date refers in all probability to the Gupta era, I do not dispute. But the above reading of it, takes no notice of the fact that the real word, in line 17, is not *gaupťê* at all, but *gôptê*; the *au* being arrived at only by applying again, as a component of the vowel, a perfectly distinct and separate sign, which is in reality nothing but the single mark of punctuation after *pañchakê*, at the end of the half-verse, and which had already been properly interpreted as such. It is only by the deliberate correction of *ô* into *au*,² that the name of the Guptas can be introduced into this passage; but even then the adjective occupies a very inconveniently detached position as regards the noun, *pañchaka*, which it qualifies. We might, with just as much reason, correct *gôptê* into *gôptrê*, 'to the protector, i.e. the local governor;' and this would be even more sustainable; for the word stands immediately before *dadau*, 'he gave,' in connection with which we have every reason to look for a dative, or some other case. Or, again, without any correction at all, we might translate "the king gave this (*charter*) at (*the village of*) Gôpta." And this, I expect, will be found to be the real meaning, if ever the first plate, which is said to be now at Gaᅅgâsâgar in Bengal, can be obtained for examination. As matters stand, there is at least nothing in this passage that compels us to connect the name of the Guptas with the date. And, at the best, even if a future discovery of the first plate should force us to adopt the reading of *Gaupťê* in the date, the grant belongs to rather a late period, when, in Kâthiâwâđ and Gujarât, any knowledge of the real origin of the era must have been lost, and all that remained was that it was the Gupta kings who had introduced the era into those parts.

¹ *Ind. Ant.* Vol. II. p. 258, line 16 f.

² The mistake of *ô* for *au* does occur in the word *svavbhânô*, for *svavbhânau*, in line 3 of the grant. But in line 9, in the word *paurnva*, the *au* is formed quite correctly and completely.

And, finally, in a curious passage from the *Achâratikâ*, which I give in full at page 32 below, note 3, we have the date "when there have gone by seven centuries of years of the Guptas, increased by seventy-two;" in which there is used again the genitive plural, *Guptânâm*. But the passage contains, as will be seen, a remarkable confusion, which cannot at present be cleared up, between the Gupta and the Śaka eras. And, like the Mörbl grant, this record belongs to a late period, and furnishes no authority for early times.

In the records of the Early Guptas themselves, the date is always expressed simply by the word *samvatsara*, 'a year,' as in the Udayagiri cave inscription of Chandragupta II., of the year 82, No. 3, page 25, line 2; or by the abbreviation *sam* as in the Sâfchi inscription of the same king, of the year 93, No. 5, page 32, line 11; or by the fuller abbreviation *samvat*, as in the Mankuwâr image inscription of Kumâragupta, No. 11, page 47, line 2. And such of their coins as are dated at all, give simply the numerical symbols, without the accompaniment of any word meaning 'year,' and much less of any dynastic qualification of it. For a reason which I indicate in Appendix I. below, these methods of expression, which are exactly analogous to the usages of other dynasties also, do not necessarily prove that the era was not established by the Guptas. At the same time, they contain no proof that it was established by them; and nothing to connect their name with it.

The fact remains, therefore, that in no early record can we find any indication that the era was founded by the Guptas; and much less that there ever existed any technical expressions analogous to *Śaka-nripa-kâla*, "the time or era of the Śaka king or kings," *Śaka-nripa-samvatsara*, "the years of the Śaka king;" *Śaka-kâla*, "the Śaka era;" *Vikrama-kâla*, "the Vikrama era," *Vikramâditya-âpâdita-samvatsara*, "the years established by Vikramâditya," &c.;¹ or even analogous to the terms *Valabhî-sam* and *Valabhî-samvat*, which are of actual occurrence in later times. This fact will become of more importance, when we come to deal with the question of the probable origin of the era. Meanwhile, I have drawn attention to it, because it is a point that must be borne in mind throughout the whole discussion. It is necessary, however, in order to avoid periphrasis, to have some convenient name for the era; and therefore, as a simple matter

¹ See my notes "On the Nomenclature of the principal Hindu Eras, and the use of the word *Samvatsara* and its Abbreviations," in the *Ind. Ant.* Vol. XII. pp. 207 ff., 291 ff.; where, of course, owing to our advance in knowledge, my remarks on the Kaira grants (p. 208), and on the Kâvi grant, (p. 291 ff.) now require to be entirely recast.—I have shewn there that, as is now generally recognised, the use of the abbreviation *samvat* is in no way restricted, as was formerly held to be the case, to the Vikrama era; see also a pointed instance supplied by Dr. Bühler in the *Ind. Ant.* Vol. XIV. p. 63. It is simply an abbreviation of the base *samvatsara*, 'a year,' or of any declensional case of it that can be used in expressing a date (see No. 5, page 30, note 3). And, bearing this in mind, such expressions as *Gupta-Samvat*, *Śaka-Samvat*, *Vikrama-Samvat*, &c., of which the two latter actually occur in original records (see *Ind. Ant.* Vol. XII. pp. 213, 293), give a uniform, convenient, and unobjectionable method of quoting the years of the different eras.

of convenience, I follow the custom of the last forty years, and speak of it as "the Gupta era." Also, as the era did certainly in later times, in Kāthiawād, acquire the name of "the Valabhī era," I shall, according to the convenience of the moment, speak of it indifferently as "the Gupta era," "the Valabhī era," and "the Gupta-Valabhī era." Subject to the remarks that I have made above, this nomenclature needs no further apology, if I point out that, even by those who maintain that the Early Guptas were themselves anterior to A.D. 319, it is admitted that the Gupta era which has come down to us in the writings of Albêrûnî, had the same epoch with the Valabhī era; they only maintain that the Early Guptas used a Gupta era which was not this Gupta era.

Albêrûnî's Statements, as rendered by M. Reinaud.

Until the discovery of the Mandasôr inscription, No. 18, page 79, the only direct information available as to the epoch of the Gupta era, was the statement of Albêrûnî, who, writing in the period¹ between the 30th April and the 30th September, A.D. 1030, left on record the following notes, as taken from M. Reinaud's French translation in his *Fragments Arabes et Persans*, page 158 ff:—

"People employ ordinarily the eras of Śrî-Harsha,² of Vikramāditya, of Śāka, of **Ballaba**,³ and of the **Guptas**, **Ballaba**, who also has given his name⁴ to an era, was the prince of the town of **Ballabha**, to the south of Aṅghilwāra, at a "distance of about thirty *yōjanas*.⁴ The era of **Ballaba** is subsequent to that of Śāka "by 241 years. In order to make use of it, we set down the era of Śāka, and deduct at

¹ See Sachau's *Albêrûnî's India*, Preface, p. x.

² As is shewn by Albêrûnî's statement further on, this is not the era of Harshavardhana of Kanauj, commencing A.D. 606 or 607, of which we have an instance in this volume, in No. 43, page 208; but an earlier era, commencing B.C. 457, of which we have no epigraphical record, and, in fact, no information of its existence beyond Albêrûnî's statement, which is accompanied by the remark that, in a *Kāsmīrī* almanac, he had read that Śrî-Harsha was 664 years later than Vikramāditya, and that he could obtain no explanation of the discrepancy (*Sachau's Albêrûnî's India*, Translation Vol. II. p. 5).

³ Reinaud's Arabic text contains no authority for his use of the double *l* throughout, and of the aspirated *bh* in the name of the town. So, also, Sachau's text contains no authority for his use, once of the form *Ballabha*, and once of *Balabha*. These forms can only be attributed to some fancied connection between the name of the city of Valabhī and the Sanskrit word *vallabha*, 'lover, husband, friend, favourite,' which was very often used as a proper name, but not in the case of any of the rulers of Valabhī. The word *valabhī* itself means 'the wooden frame of a thatch, a roof; a turret or temporary building on the roof of a house.' It occurs in No. 18, line 6, page 81; and, in the form *vaḍabhī*, in No. 66, line 2, page 268.—Albêrûnî himself, in treating the name as that of a person, as well as of a town, possibly wrote under some similar misconception. But, setting aside any such mistake as this, which is rather like that of his treating Śāka as the name of an individual, instead of a tribe, he is of course speaking of the era that was used by the well-known Kings of Valabhī.

⁴ The *yōjana*, a measure of distance, seems to have varied from 2½ to 9, or even 18, English miles; but with an average length of between 4 and 5 miles.—Wālā, the modern representative of the ancient Valabhī, is about one hundred and thirty-five miles almost due south of Aṅghilwād.

"the same time the cube of 6 (216) and the square of 5 (25). The remainder is the era of **Ballaba**. This era will be discussed in its place. As to the **Gupta-kâla** (the era of the Guptas), we understand by the word *gupta* certain people who, it is said, were "wicked and powerful; and the era which bears their name, is the epoch of their extermination. Apparently **Ballaba** followed the **Guptas** immediately; for, the era of the **Guptas** also commences the year 241 of the era of Śaka. The era of the astronomers commences the year 587 of the era of Śaka. It is to this era that the *Kandakhâtaka* Tables of Brahmagupta are referred. This work has among us the title of *Arkand*. Accordingly, placing ourselves in the year 400 of the era of Yazdajird,¹ we find ourselves "in the year 1488 of the era of Śrī-Harsha; the year 1088 of the era of Vikramāditya; the year 953 of the era of Śaka; the year 712 of the era of **Ballaba** and of that of the **Guptas**."

Albêrûni's Statements, as rendered by Prof. Sachau.

And to this we have now to add Prof. Sachau's English rendering of the same passages, in his *Albêrûni's India*, Translation,² Vol. II. page 5 ff. —

"For this reason, people have given up using them,³ and have adopted instead the "eras of — (1) Śrī Harsha; (2) Vikramāditya; (3) Śaka; (4) **Ballabha**;⁴ and (5) **Gupta**. The era of **Balaba** is called so from **Balaba**, "the ruler of the town **Balabha**,⁵ nearly 30 *yôjanas* south of Anhilvâra. The epoch "of this era falls 241 years later than the epoch of the Śaka era. People use it in "this way. They first put down the year of the Śakakâla, and then subtract from it "the cube of 6 and the square of 5 (216 + 25 = 241). The remainder is the year of the "**Balaba** era. The history of **Balaba** is given in its proper place.⁶ As regards the "**Guptakâla**, people say that the **Guptas** were wicked powerful people, and that, when "they ceased to exist, this date was used as the epoch of an era. It seems that **Balaba** "was the last of them, because the epoch of the era of the **Guptas** falls, like that of the "**Balaba** era, 241 years later than the Śakakâla. The era of the astronomers begins 587

¹ This era dates from the accession of Yazdajird III., a Sassanian king of Persia, in A. D. 632 (see *Prinsep's Essays*, Vol. II. Useful Tables, p. 302 and note). The "gauge-year," 400, selected by Albêrûni for the comparison of dates, is one year ahead of that in which he was writing.

² It is not certain whether Prof. Sachau's Translation will have been actually published before the issue of this volume. But, as it will be the standard translation, he has kindly allowed me to make the necessary references to it, from advanced proofs.

³ i.e. the eras of the Bhârata war and of the Kaliyuga, and certain other methods of reckoning time, just previously detailed by Albêrûni, who states that they had been abandoned because of the very large numbers involved in the use of them.

⁴ and ⁵ See page 23 above, note 3.

⁶ The reference appears to be to the story of the fruit-seller Raṅka and the king Vallabha; Translation, Vol. I. p. 192 f., in Chapter XVII., "on Hindu Sciences which prey on the Ignorance of People."

"years later than the Śakakāla. On this era is based the canon *Khundakhdadyaka* by Brahmagupta, which among Muhammadans is known as *Al-arkand*. Now, the year 400 of Yazdjird, which we have chosen as a gauge, corresponds to the following years of the Indian eras:—(1) to the year 1488 of the era of Śri Harsha; (2) to the year 1088 of the era of Vikramāditya; (3) to the year 953 of the Śakakāla; (4) to the year 712 of the **Balaba** era, which is identical with the **Guptakāla**."

The Results of the above Renderings.

The passages given above mention an era, connected with the names both of the Guptas and of the Valabhi family, in respect of which we have to notice the following leading points.

In the first place, Alberūni calls this era, both "the Gupta era," and "the Valabhi era." As regards its connection with the Guptas, he tells us, according to the above renderings, that it commenced at the time of the cessation of the Gupta sway, and seems to imply that, as a matter of fact, it was that event which led to the establishment of it; and, of course, the result of this would be, that the dates recorded in the inscriptions of the Guptas themselves, could not be referred to this Gupta era, but must belong to some era with a considerably earlier starting-point. And, as regards its connection with the Valabhi family, from the fact that their era had the same starting-point with this Gupta era, he infers that the members of this family came after the Guptas in chronological sequence; but he does not indicate any connection between them and the establishment of the era.

And secondly, in respect of the initial point, he seems first to state, very clearly, that the epoch of the era, under either name, was when Śaka-Samvat 216 + 25 = 241 had expired; which, taking the expired Śaka year in the way in which it has to be used for the purposes of the present Tables,¹ gives us A.D. 319-20 current* for the epoch or year 0 of the era, and A.D. 320-21 current for its commencement or first current year. This is shewn, first by the rule for subtracting 241 complete Śaka years; and secondly by Gupta-Valabhi-Samvat 712 being quoted as equivalent to Śaka-Samvat 953, which is known to be intended as an expired year, since Alberūni gives it as the equivalent of the year 400 of Yazdjird, which is A.D. 1031-32 current. In his next mention, however, as rendered by M. Reinaud, he apparently speaks of the era as commencing with, *i.e.* as having for its first current year, Śaka-Samvat 241, which must be understood as an expired year: according

¹ *e.g.* those in Gen. Cunningham's *Book of Indian Eras*, and Prof. K. L. Chhatra's *Graha-siddhantāchārā Kōshikā*, or "Tables for calculating the Places of the Planets."

*Or, more accurately, the period from the 9th March, A.D. 319, to the 25th February, A.D. 320.—It is, perhaps, desirable to point out, for general readers, that the quotation of two years of the Christian era in this way, "A.D. 319-20," does not denote the whole period of the two years, but only the period from the commencement of the Śaka year in the first of them, to the end of it in the second

to which its epoch would be when 240 years had expired. While, in a third passage, a little further on in the book,¹ in mentioning the "roundabout way" in which the Hindus computed the date (in January, A.D. 1026) of the destruction of Sômnâthpâtan by Mahmûd of Ghazni, which event took place "in the year of the Hijra 416, or 947 Śakakâla," he tells us that they first wrote down 242, then 606 under it, and then, again, 99; with the result, by addition of the figures, of Śaka-Samvat 947, which, as an expired year, brings us to the period A.D. 1025-26 current, inclusive of the month of January, A.D. 1026. And here the first figures would seem, at first sight, to indicate that, in this calculation, the epoch of the era was treated as being when Śaka-Samvat 242 had expired.²

¹ *Albérûnî's India*, Translation, Vol. II. p. 9.

² This last passage is introduced by Albérûnî in connection with his remarks on the Lôkakâla or popular reckoning by cycles of a hundred years. And he expresses himself as being inclined to think that the number 242 indicates the years which preceded the time when the Hindus commenced to use the cycle of a hundred years, and that they adopted this cycle together with the Gupta era; also that the number 606 represents the completed cycles, *viz.* six, "each of which they must reckon as 101 years;" and that the number 99 gives the expired years of the current cycle. He goes on to say that the rule, as found by him in the writings of Durlabha of Multân, was, to write down 848, and add the Lôkakâla, the sum of which would give the Śaka year. But, in proceeding to apply this rule to Śaka-Samvat 953 (expired), as corresponding to the year of Yazdjird which he had already used as a "gauge-year," he points out that, subtracting 848, there remained 105 for the Lôkakâla, while the destruction of Sômnâthpâtan would fall in the 98th year of the cycle.—There are subsidiary difficulties here, which cannot at present be fully cleared up. One of them is, the reference of the destruction of Sômnâthpâtan to both the ninety-eighth and the ninety-ninth years of a Lôkakâla cycle; with the addition, moreover, that the ninety-eighth year is indicated as current, and the ninety-ninth is inferred to be expired.—Another is, that, according to the only Lôkakâla reckoning the nature of which has been fully explained (*Indian Eras*, p. 6 ff.), *viz.* that used in Kâsmîr,—which, Albérûnî tells us, had been adopted by the people of Multân a few years before his own time,—the event in question would fall in the first current year of a cycle. Thus, Kalhana, in the *Rājataranginî*, i. 52 (Calcutta edition, p. 3), makes a very explicit statement regarding the equation between the Śaka era and the Lôkakâla of Kâsmîr. His words are — *laukikê=bdê chatur-vimśê Śaka-kâlasya sampratañ saptaty=atyadhikam yâtam sahasram parivatsarâh*,—"at this present moment, in the twenty-fourth *laukika* (or popular) year, there have gone by one thousand years, increased by seventy, of the Śaka era." In this passage, he quotes the Śaka year as expired, in accordance with the practice of astronomers; but the Lôkakâla year as current, as would naturally be the case in using a popular reckoning of that kind. He was writing, therefore, in Lôkakâla 24 current, and when Śaka-Samvat 1070 had expired; which is equivalent to A.D. 1148-49 current. And this gives Lôkakâla 1 current of the same cycle, as corresponding to Śaka-Samvat 1047 expired; which is equivalent to A.D. 1025-26 current. Now, that the scheme of each year of the Kâsmîrî Lôkakâla cycle was identical with the scheme of the Śaka years of Northern India, commencing with the first day of the month Chaitra (March-April), is shown by Albérûnî's statements, and by the notes put together by Gen. Cunningham in his exposition of this reckoning. And it follows that the first year, current, of each Kâsmîrî Lôkakâla cycle coincides exactly with the forty-seventh year expired, and the forty-eighth current, of each century of the Śaka era, and with part of the twenty-fifth and part of the twenty-sixth years, current, of each century of the Christian era. The month of January, A.D. 1026, therefore, fell in Lôkakâla 1 current, of Kâsmîr, which coincided with Śaka-Samvat 947 expired, and extended (see *Indian Eras*, p. 171) from the 3rd March, A.D. 1025, to the 21st March, A.D. 1026. And it is difficult to see how, in the

Albérún's Statements, as rendered by Prof. Wright.

The leading historical item of Albérún's information, as rendered by M. Reinaud,—*vis.* that the Gupta era commemorated the epoch of the extermination of the Gupta dynasty,—naturally at once attracted special attention; because of the *prima-facie* improbability of such a fact. And, as will be seen further on, various attempts were made, to find an explanation for it; and with very conflicting results.

application of a Lōkakāla reckoning introduced from Kāśmīr, an event occurring in that month can be correctly referred even to Lōkakāla 99 expired; and, much more so, to Lōkakāla 99 current. To suit the former case, we require a cycle commencing one year later than the Kāśmīr cycle; and to suit the latter case, a cycle commencing three years later than the same. And, that there were varying starting-points of this kind, as well as a want of uniformity in respect of the scheme of the years, is indicated by Albérún's remark that the totally different accounts of the Lōkakāla reckonings, given to him, rendered him unable to make out the truth about it.—One point, however, seems clear. As to the number 606, given by Albérún in his first illustration, it is impossible that a centenary cycle can consist of a hundred and one years. And Albérún himself had previously said distinctly (*Albérún's India*, Translation, Vol. II, p 8) "if a *centennium* is finished, they drop it, and simply begin to date by a new one." It is plain, in fact, that the odd six years do not belong to the cycles of the Lōkakāla. To that reckoning, only the six even centuries belong. I shall shew hereafter that the epoch of the Gupta-Valabhī era really was A.D. 319-20 current; which might be quoted either as Śāka-Samvat 241 expired or 242 current. If we add the odd six years to Śāka-Samvat 241 expired, we obtain Śāka-Samvat 247 expired, or 248 current, equivalent to A.D. 325-26 current; and this, as we have just seen, would coincide with the first current year of a Lōkakāla cycle, as reckoned in Kāśmīr. But it is one year too early for the first current year of any cycle of a reckoning, in a subsequent cycle of which the event in question belonged to the ninety-ninth year expired and the hundredth year current. Now, I suppose that we must assume that Albérún has quoted Durlabha correctly. And, if so, then the first current year of each cycle in the Multān reckoning really was one year later than in the Kāśmīr reckoning; and coincided with the forty-eighth year expired, and the forty-ninth current, of each century of the Śāka era, and with part of the twenty-sixth and part of the twenty-seventh years, current, of each century of the Christian era. And, if the introduction of the reckoning, at Multān, could be carried back so far, it commenced with Śāka-Samvat 248 expired, and 249 current. This year might have been obtained by adding even to Śāka-Samvat 241 expired. But, as will be seen hereafter, the real use of Śāka-Samvat 241 expired is only for obtaining the basis with which Gupta-Valabhī dates have to be calculated, and it only brings us to the beginning of the Gupta epoch. The difference between Gupta-Valabhī and Śāka years, both treated as current for purposes of comparison, is 242. And Śāka-Samvat 242 expired brings us to the beginning of the first current Gupta year. This is the starting-point that was really wanted for a process of the kind shewn to Albérún. And this is why that year was selected as the apparent basis of the computation; the true basis being Śāka-Samvat 848 expired.—It is evident, therefore, that the process illustrated by the figures given to Albérún does involve a method of adapting the Lōkakāla reckoning to the Gupta era; or, more properly, of converting Lōkakāla dates into Śāka dates through the Gupta reckoning. So far, however, from the figures tending to support any inference that the Lōkakāla reckoning was introduced by, or in the time of, the Early Guptas, the fact that Durlabha of Multān would deduct 848, with a remainder, in the particular instance, of 105, or one complete Lōkakāla cycle and five years over, seems to indicate very clearly that the use of this reckoning in that part of the country commenced with Śāka-Samvat 848 expired, equivalent to A.D. 926-27 current; and had it been otherwise, Durlabha's rule would surely have been worded in such a way

That the true solution was to be found, not in wrong information given to Alberŭnĭ or in a mistake made by him in reporting correct information, but in an erroneous interpretation of his meaning, was first indicated to me by Mr. Rehatsek, who, in December, 1886, gave me, from M. Reinaud's published text, the following literal rendering of the crucial passage,—“and (*as regards*) the Gupta era, it was, as is said, a nation wicked (*and*) strong; and when they perished, dating was made according to them.”¹ Such a rendering as this would enable us to give to Alberŭnĭ's words a meaning perfectly clear and consistent with the usual order of things; *vis.* that the Guptas, though wicked and inferentially unpopular, yet had exercised so powerful a sway that, even when their dynasty came to an end, the era, that had been used by them, still continued to be used.

So also, somewhat later, Mr. H. C. Kay, translating the words by “dating was made by (or, according to) them,” added the following remarks on the interpretation of them.—“The author's meaning is not clear. But, taking the words as they stand, I think they “can most consistently be understood as signifying an adoption or continuation of the “method of dating that had been used by the Guptas. The preceding words ‘when they “came to an end’ suggest the possible meaning that the dating ran from that event. But “it seems to me that this construction can be properly preferred, only if there be something “else in the context, or in the known facts of the case, that would make it obligatory; or, “at least, that clearly points to it.”

I had the hope that, before it came to my own turn to write finally on the subject, Prof. Sachau's translation of the Arabic text would have removed all doubt as to Alberŭnĭ's real meaning on this point. This, however, has not been the case; because of the introduction in his translation as in M. Reinaud's, of the word ‘epoch,’ which does not exist in the original text, and the use of which gives the translation a fixed obligatory meaning that, at any rate, a literal rendering of the original does not compel us to adopt.

that, in the particular instance, 948 must be deducted, with a remainder of only 3 years over.—Gen. Cunningham, in giving a somewhat similar explanation of the figures 606 (*Indian Eras*, p. 16), has assumed that in this process Śaka-Samvat 242 is a mistake for 241. But this, as I have now shewn, is not the case. And I do not agree with the manner in which he deals with the figures as a whole. Śaka-Samvat 241 expired or completed brings us to the end of A. D. 318-19 and the beginning of A. D. 319-20. If to this we add 6 and 600 and 99 complete years, it only brings us to Śaka-Samvat 946 expired, or to the end of A. D. 1023-24 and the beginning of A. D. 1024-25; and leaves us still one year short of that in which the event in question occurred.

¹ Similarly, some thirteen years ago, Mr. Blochmann (see the *Jour. Beng. As. Soc.* Vol. XLIII. Part I. p. 368) proposed to translate—“as regards the Guptakā, they were, as is related, a people wicked and powerful; and when they were cut off, it was dated in them (the era commenced?).”—This translator, however, is spoilt by the bracketed words “(the era commenced?).”; the use of which shews why Mr. Blochmann, though giving a translation capable of a totally different meaning, expressed himself as not able to see any fault in Reinaud's translation.

I am, therefore, glad to be able now to publish the following transliteration, with interlinear word-for-word rendering, and translation, which Prof. William Wright, of Cambridge, has recently been kind enough to give me, from Prof. Sachau's published text, of the original of the whole passages of which M. Reinaud's and Prof. Sachau's renderings have been printed above:—

Text and Literal Rendering.

{	Wa-li-dhālika		'a'raḍū		'an-hā		wa-jā'ū		'ila
{	And for this		they have turned awa		from them		and have come		to
{	tawārkh	Shrī-Hrīsh	wa-Bigarmādita		wa-Shaka		wa-Bilaba		
{	(the eras of	[Śrī-Harsha]	and [Vikramāditya]		and [Śaka]		and [Valabhi]		
{	wa-Kūbita.	Wa-'ammā		ta'rkh		Balba		
{	and [Gupta].	And as regards		the era of		[Valabhi]		
{	wa-huwa	ṣāhib	madnat		Balbah		wa-hiya		janūblyah
{	and he	lord of	the city of		[Valabhi]		and it		south
{	madnat	'Anhwārah	bi-kartb		min		thalāthn		jozhan
{	(the city of	[Aṅhīlvāḍa]	by near		to		thirty		[yōjāna]
{	'auwala-hu	muta'akhhir	'an		ta'rkh		Shk		bi-mi'atain
{	(the first of it	posterior	to		the era of		[Śaka]		by two hundred
{	wa-iḥdā	wa-'arba'in	sanah.		Wa-musta'milū-hu		yāḍa'ūn		Shg-kāl
{	and one	and forty	years.		And the users of it		put down		[Śaka]-era
{	wa-yankuṣūn	min-hu	majmū'		muka'ab		'as-sittah		wa-murabba'
{	and lessen	from it	the sum of		the cube of		six		and the square of
{	'al-khamsah	fa-yabkā	ta'rkh		Balba.		Wa khabaru-hu		'ātin
{	five	and remains	the era of		[Valabhi].		And his history		is coming
{	ft	mauḍi'i-hi.	Wa-'ammā		Gūbt-kāl		fa-kānū		kamā
{	in	its place.	And as regards		[Gupta]-era		they were		as
{	kauman	'ashrāran	'aḳwiyā'a		fa-lammā		'inḳaraḍū		'urrikha
{	a people	wicked	strong		and so after		they perished		it was dated
{	bi-him.	Wa-ka-'anna	Bib		kān		'akhra-hum.		Fa'inna
{	by them.	And as if that	[Valabhi]		was		the last of them.		And behold
{	'auwala	ta'rkhhi-him	'aiḍan		muta'akhhir		'an		Shg-kāl
{	(the first	of their era	also		posterior		to		[Śaka]-era

{ 241.	Wa-ta'rīkh	al-munajjimīn	yata'akhhkar	'an	Shg-kāl
{ 241.	And the era of	the astronomers	is posterior	to	[Śaka]-era
{ 587	wa-'alai-hi	buniya	zlj	Kndkātḱ	li-Brhmġūpt
{ 587	and on it	is built	the canon	[Khaṇḍakāṭaka]	by [Brahmagupta]
{ wa-huwa	'al-ma'rūf	'inda-nā		bi'l'-Arknd.	
{ and it	the known	with us (<i>ches nous</i>)		by (the name of) Al-Arkand.	
{ Fa-'idhan	sinū	ta'rīkh	Shrī-Harish	li-sanati-nā	
{ And so then	the years of	the era of	[Śrī-Harsha]	to our year	
{ 'al-mumaththal	bi-hā	1488	wa-ta'-rīkh	Bkrmādt	1088
{ that is used as an example		1488	and the era of	[Vikramāditya]	1088
{ wa-Shg-kāl	953	wa-ta'rīkh	Balba	'alladhī	huwa
{ and [Śaka]-era	953	and the era of	[Valabhī]	which	it also
{ Gōbīta-kāl	712.				
{ [Gupta]-era	712.				

Translation.

"And for this reason they have given them up, and have adopted the eras of Śrī-Harsha, Vikramāditya, Śaka, Valabhī, and the Guptas. And as regards the era of Valabhī,—who was the ruler of the city of Valabhī, which was south of the city of Aṇhīlvāḍa by nearly thirty *yōjanas*,—its beginning was later than the Śaka era by two hundred and forty-one years. Those who use it put down (*the year of*) the Śaka era, and subtract from it the sum of the cube of six and the square of five; and there remains (*the year of*) the era of Valabhī. His history is coming in its proper place.¹ And as regards the Gupta era,—(*the members of this dynasty*) were, it is said, a race wicked (*and*) strong; and so, after they became extinct, people dated by them. And it seems as if Valabhī was the last of them. And so the beginning of their era also is later than the Śaka era (*by*) 241 (*years*). And the era of the astronomers is later than the Śaka era (*by*) 587 (*years*); and on it is based the astronomical canon (*named*) *Khaṇḍakāṭaka*, by Brahmagupta, which among us is known by (*the name of*) *Al-Arkand*. So, then, 1488 years of the era of Śrī-Harsha are in correspondence with the year (*of Yasudajird*) that we have taken as a gauge; and 1088 of the era of Vikramāditya; and 953 of the Śaka era; and 712 of the era of Valabhī, which is also the Gupta era."

The essence of the whole matter, of course, lies in the precise meaning that is to be given to the words which follow the statement that the Guptas were wicked and powerful.

¹ See, however, page 24 above, note 6.

Prof. Wright states that, in the original, we have a vague impersonal passive, meaning "it was dated by them," "there was a dating by them," or "people dated by them;" but that this certainly does not expressly imply that this dating took place from the year of the extinction of the Gupta power, and in consequence of that event. That such an interpretation might, if found on other grounds to be justifiable, be given to this expression may be admitted. But it is at the least equally open to us to interpret the expression as meaning that the Guptas had been so powerful that, even when they were dead and gone, people still used their era to date by. And we shall have to determine hereafter, from an examination of the details of the recorded Gupta and Valabhī dates, which of these two possible interpretations is the one that must be adopted.

There is also one other point in the revised translations, to which special attention should be paid. Prof. Wright's rendering, "*(the year)* 712 of the era of Valabhī, which is also the Gupta era,"—and Prof. Sachau's, "the year 712 of the Balaba era, which is identical with the Guptakāla,"—are essentially different, in their ultimate bearing, from M. Reinaud's, "the year 712 of the era of Ballaba and of that of the Guptas." They shew very clearly that Albérūnī was speaking of absolutely one and the same era, under two names; not of two different eras, with the same, or almost the same, epoch.

The Theories based on M. Reinaud's rendering of Albérūnī's Statements.

Up to the present time, however, the only rendering of Albérūnī's statements that has been available, is that given by M. Reinaud. His translation has been taken as the basis of argument by all writers on the subject. And, for a full comprehension of the whole question, it will be necessary now to consider the matter from the light that was given by him.

According to his rendering, we had three years to choose between, for the epoch of the era,—Śaka-Samvat 240, 241, or 242, expired; involving a question, especially in respect of the exact determination of the corresponding date in the Christian era, that could only be settled by accurate calculations of the data available from the inscriptions, explained in detail, so that general readers might see that the processes were satisfactory.

But, whatever might be the final settlement of this point, the fact remained that Albérūnī had information given to him of the existence of an era, coupled with the name of the Guptas and of the city of Valabhī, which began at some point in A.D. 319, or within a year on either side of that date, and which it is convenient to speak of as the Gupta, the Valabhī, or the Gupta-Valabhī era. And, that this era was actually used in connection with the name of Valabhī, at any rate, was proved by the Verāwal inscription of the Chalukya king Arjunadēva of Aphilwād,¹ in which the leading record of the year is

¹ Originally brought to notice, many years ago, by Tod, in his *Annals of Rājasthān*; but critically edited, for the first time, by Hultzsch, in 1882, in the *Ind. Ant.* Vol. XL. p. 241 ff.

Valabhi-Samvat 945, together with Vikrama-Samvat 1320, which is equivalent to A.D. 1263-64, and with the Hijra year 662, which ran¹ from the 4th November, A.D. 1263, to the 23rd October, A.D. 1264.

So much was certain. But it was felt to be highly improbable that the Gupta era should date from the extermination of the Guptas. And students of the subject divided themselves, almost at once, into two schools.

The first, represented most publicly and with undeviating tenacity up to the last by the late **Mr. J. Fergusson**, accepted Alberûnî's statement as to the period of the commencement of the era, but,—on the analogy of the statement which, on the authority of Hindu tradition, he also makes, that the Śaka era, too, dated from the overthrow of the Śakas; a statement which is certainly wrong,²—rejected the addition that it dated from the downfall of the Guptas; and took A.D. 318 for the date of the rise of the dynasty, as well as the establishment of the era; selecting this particular year on the theory that the era did not date from the accession of a king, or from any particular historical event, but, for convenience of comparison, was simply regulated by the completion of four of the Sixty-Year Cycles of Jupiter from the commencement of the Śaka era.

The other school accepted A.D. 318, or thereabouts, for the downfall of the Guptas, and took the Valabhi era of Arjunadēva's inscription, which indisputably began at that period, as being separate altogether from the real Gupta era, and as having been established in commemoration of the overthrow of the Gupta power; and began then to look about for an earlier date for the rise of the Gupta dynasty, and for the starting-point of the era used by the Gupta kings, and also,—as was maintained, with some inconsistency, by the majority,—by the Kings of Valabhi, in preference to their own Valabhi era. The chief exponents of this school have been—the late **Mr. E. Thomas**, who held that the era was identical with that of the Śakas,³ with the epoch of A.D. 77-78;—**General Sir Alexander**

¹ See *Indian Eras*, p. 126.

² See Appendix I. below.

³ A curious instance of confusion between the Gupta and the Śaka eras, on the part of a Hindu writer, is furnished by the following two passages from the commentary named *Āchāraṭkā*, by Śīlāchārya, on the Jain work called *Āchāraṅgasaḍra*; I have taken them from a manuscript, supposed to be about three hundred years old, shewn to me in the early part of 1883 by Dr. Bhagwanlal Indraji.—This first passage, on pp. 207b and 208a, is in metre, and runs—*dvasaptaty-adhikēshu hi śatēshu saptasu gatēshu Guptānām | samvatsarēshu māsi cha Bh[A*]drapadē śuklā(kla)-panchamyām || Śīlāchāryēṇa kritā Gambhūtāyām sthitēna (fk-aishā | samyag-upayujya śodhyā mātsarya-vinākrītail-āryē (ryai)h ||*. This passage gives Gupta-Samvat 772, expired, the fifth day of the bright fortnight of the month Bhādrapada, as the date on which this portion of the Commentary was completed by Śīlāchārya, at Gambhūtā (? Cambay)—The second passage, on p. 256b, at the end of the whole book, is in prose, and runs—*Śaka-nripa-kāl-tiṭṭa-samvatsara-śatēsashu (read śatēshu) saptasu | ashtānavaty-adhikēshu Vaiśākha-śuddha-panchamyām Āchāraṭkākā krit-ēti || Ba || Samvat (page 256b ends here; and the next page, containing the repetition of the date in figures, and the last final words of the author, is lost) This passage gives Śaka-Samvat 798, expired, the fifth day of the bright fortnight of the month Vaiśākha, as the date of the completion of the whole Commentary.—The two passages, indicating, as*

Cunningham, who finally fixed on A.D. 166-67 as the epoch;—and the late Sir E. Clive Bayley, who selected A.D. 190-91.

Examination of the previous Theories.

Mr. Fergusson's theory of A.D. 318-19 for the epoch of the era, and A.D. 319-20 for its commencement, is easily disposed of. It was wrong; but by one year only. The reason is, that, as has been said, his assumption,—based apparently on a suggestion thrown out by Dr. Bhau Daji in 1864,—was, that the commencement of it was regulated only by the completion of four of Jupiter's Sixty-Year Cycles from the commencement of the Śaka era, in order that there might be always an even and convenient difference of two hundred and forty years between the Śaka and Gupta dates. This however, could be arranged only by applying the Sixty-Year Cycle as used now in Southern India, where it is not in reality an astronomical cycle at all; since there the cyclic years run on in regular succession, without any adjustment of them to the motion of the planet, with reference to his sign-passing or his heliacal rising, by the omission of a year on certain occasions, and are taken as commencing and ending with the luni-solar years. According to the present southern system, Śaka-Samvat 1 current (A.D. 78-79) was the Bahudhānya samvatsara; and Śaka-Samvat 241 current (A.D. 318-19) was again the same cyclic year, Bahudhānya; and, by this means, some justification might be found for Mr. Fergusson's view. But I shall shew hereafter that the real epoch of the Gupta era was A.D. 319-20, which does not correspond to Śaka-Samvat 241 current; so that there was, in reality, a completion of four cycles and one year, even by the southern system; and this, alone, is fatal to

they stand, that Śīlāchārya treated the Gupta and Śaka eras as identical, contain a mistake of some kind or another, which must be attributed to a pedantic desire on his part to introduce a mention of an era,—whether the Gupta or the Śaka, as the case may be,—with which he was only imperfectly acquainted. And the mistake cannot be cleared away, unless we can obtain some independent record of the real date of Śīlāchārya, sufficient to shew whether the *Āchṛaṣṭakā* was written during Gupta-Samvat 772 to 798 expired (A.D. 1092 to 1118), or during Śaka-Samvat 772 to 798 expired (A.D. 850 to 876). As to this, I can only say that the Śaka era was used so rarely, if at all, in Gujarāt and Kāthiāwād, except by the Gujarāt branch of the Rāshtrakūṭa family, that probably the Gupta era gives the real date for Śīlāchārya. And I would throw out a suggestion that possibly some mistake of the same kind may account for the dates, Śaka-Samvat 400 and 417, of the apparently spurious Umētā and Ilāḍ grants of Dadda II. (*Ind. Ant.* Vol. VII. p. 61 ff.; and Vol. XIII. p. 115 ff).—The passages, however, are of some interest, in shewing that, in Śīlāchārya's time, there was still a recollection of the fact that the era,—which must have been known best from its use by the rulers of Valabhī, and which came eventually, in Kāthiāwād, to be called the Valabhī era,—was connected originally and specially with the Gupta kings, by whom it was introduced into Kāthiāwād and the neighbouring parts.—After writing this note, which appeared originally in the *Ind. Ant.* Vol. XV. p. 188, I found an allusion by Dr. Bhau Daji, in 1864, to what is evidently the same manuscript, though he quoted only the Gupta date. He wrote (*Jour. Bo. Br. R. As. Soc.* Vol. VIII. p. 246) "I have a Jaena manuscript which is dated in the 772nd year of the Guptakāla; but unfortunately the corresponding Vikrama or Śāli-vāhana's year is not given; nor is it possible at present to ascertain the exact date of the author from other sources."

the proposed epoch of A.D. 318-19. And, in addition to this, amongst other inscriptions, the Waṅḡ grant of the Rāshṭrakūṭa king Gōvinda III., which records¹ that in Śāka-Saṁvat 730 the Vyaya *saṁvatsara* was current on the full-moon day of the month Vaiśākha (April-May), and the Rādhanpur grant of the same king, which records² that the Sarvajit *saṁvatsara*, the next in the cycle, was current on the new-moon day of the month Śrāvāṇa (July-August) in the same year, shew very plainly that the present arrangement was not the original one, even in Southern India.

If the Sixty-Year Cycle was in use at all at the time of the commencement of the Gupta era, then, in Northern India, and in connection with a northern era,—which the Gupta era emphatically was,—the only system that can have been followed, is the regular northern system, according to which the cycle is truly an astronomical cycle, and the *saṁvatsaras* are regulated entirely and only by the passing of Jupiter from one sign of the zodiac into another. By Mr. Sh. B. Dikshit's calculations, from the *Sūrya-Siddhānta*, at the commencement of Śāka-Saṁvat 1 current (A.D. 78-79), the *saṁvatsara* was Śukla, the third in the cycle; and it was followed by Pramōda, the fourth, on the full-moon day of the month Pausha, in December, A.D. 78. And, at the commencement of Śāka-Saṁvat 241 current (A.D. 318-19), the *saṁvatsara* was Angiras, the sixth in the cycle; which was followed by Śrīmukha, the seventh, on the ninth lunar day of the bright fortnight of the month Phālguna, in February, A.D. 319. Thus, four complete cycles and three *saṁvatsaras* over passed between Śāka-Saṁvat 1 and 241; and the epoch of the Gupta era, unless it were placed three years earlier, in A.D. 315-16, could not be determined by any consideration of this kind.

Nor can it have been determined by the Twelve-Year Cycle of Jupiter, the years of which may be regulated either by the passing of Jupiter from one sign of the zodiac to another; or, as was the more ancient custom, by his heliacal rising in a particular lunar mansion.³ Taking first the sign-passing system, Mr. Sh. B. Dikshit finds that, at the commencement of Śāka-Saṁvat 1 current (A.D. 78-79), the *saṁvatsara* was Mahā-Āśvayuja, the twelfth in the cycle: which was followed by Mahā-Kārttika, the first of the next cycle, on, as before, the full-moon day of the month Pausha, in December, A.D. 78. While, at the commencement of Śāka-Saṁvat 241 current (A.D. 318-19), the *saṁvatsara* was Mahā-Pausha, the third in the cycle; which was followed by Mahā-Māgha, the fourth, on, as before, the ninth lunar day of the bright fortnight of the month Phālguna, in February, A.D. 319. And, by the heliacal-rising system, at the commencement of Śāka-Saṁvat 1 current (A.D. 78-79), the *saṁvatsara* was Mahā-Bhādrapada, the eleventh in the cycle; which was followed by Mahā-Āśvayuja, the twelfth, on the twelfth lunar day of

¹ *Ind. Ant.* Vol. XI. p. 159, line 46 f.

² *id.* Vol. VI. p. 68, line 53 f.

³ For an explanation of the systems of the Twelve-Year Cycle of Jupiter, see Appendix III. below.

the bright fortnight of the month Vaiśākha, in April, A.D. 78, soon after the commencement of the year. While, at the commencement of Śaka-Saṃvat 241 current (A.D. 318-19), the *samvatsara* was Mahā-Pausha, the third in the cycle; which was followed by Mahā-Māgha, the fourth, on the sixth lunar day of the bright fortnight of the month Śrāvaṇa, in July, A.D. 318. Thus, between Śaka-Saṃvat 1 and Śaka-Saṃvat 241, there had expired twenty complete cycles and three *samvatsaras* over, by the sign-passing system, and twenty cycles and four *samvatsaras* over, by the heliacal-rising system; and the epoch of the Gupta era could not be determined by any consideration connected with this cycle, unless it should be placed in A.D. 315-16 or A.D. 314-15.

The other three theories, however, are more complicated; and, in order to understand them properly, and estimate them at their right value, it will be necessary to run briefly through the facts and supposed discoveries on which they are based, and the arguments by which they have been built up, so far as those facts, discoveries, and arguments relate to the recorded dates themselves, and the interpretation of them. Our object is not now to enter into a lengthy discussion of extraneous questions of palæography, numismatics, architecture, contemporary history, &c., which, if a rational process is to be followed, have to be settled by the dates, instead of the dates by them; and which must be left for treatment at some future time, after the proper settlement of the Early Gupta chronology.

The first reference to the Gupta era that I can trace,—or, at any rate, the first suggestion of the existence of an era connected with the Guptas, apart from any general reference to the chronological period to which they might be referred,—is in Mr. James Prinsep's treatment of the Kahāum pillar inscription of Skandagupta, No. 15, page 65, in 1838, in the *Jour. Beng. As. Soc.* Vol. VII. p. 36 ff. By his rendering of this record, it was dated (*id.* p. 37) "in the year one hundred and thirty-three after the decease of Skandagupta;" on which he remarked (*id.* p. 38) "the death of this prince is here employed as an epoch in a somewhat enigmatical way." The supposed enigma refers to the actual manner in which the total of 133,—or, more properly, 141,—is arrived at. As regards the other point, the reference of the years to the death of Skandagupta is due only to a mislection of the last word in line 2 of the text. The real reading there is *śāntī*, the locative singular of *śānta*, in apposition with *rājyē* in the same line; "in the tranquil reign (of Skandagupta)." Mr. Prinsep, however, read *śāntī*, the ablative or genitive singular of *śānti*, 'quiet, tranquillity, calmness, rest, repose;' and, with this reading, it was, of course, hardly possible to do otherwise than translate it by "after the decease," "of the repose, *i.e.* death," and "after the death," of Skandagupta, and to make the years that were recorded run from that event. No discussion of the question was then entered into. But Skandagupta then was, and still is, the last known king of the direct succession of the Early Gupta dynasty. And it is evidently the above rendering which first suggested the idea of an era dating from the extermination of the Gupta power at the

death of Skandagupta. All else, serviceable for our present inquiry, that I can find in Mr. Prinsep's writings, is his statement in the same volume (p. 354), that the dates recorded in the Valabhi charters must be referred to the Vikrama era.

In 1845, M. Reinaud republished collectively, under the title of *Fragments Arabes et Persans*, certain extracts, with French translations, from works relating to India, which he had previously published separately in the *Journal Asiatique*, in September and October, 1844, and February-March, 1845. In this book, as we have already seen, he renders Alberûni (*id.* p. 143) as stating that the Gupta era dated from the extermination of the Guptas. I do not find that he makes any reference to Prinsep on this specific point. But he shews, throughout, so good an acquaintance with Prinsep's writings, as also with those of other English scholars, that he must certainly have read Prinsep's translation of, and comments on, the Kahâm inscription. And, though he may not have intentionally allowed himself to be guided by Prinsep's views, it can hardly be doubted that he had a reminiscence of the purport of them, when he was translating Alberûni's remarks. In fact, in the face of Mr. Blochmann's, Mr. Rehatsek's, and Prof. Wright's versions, it is difficult to see how M. Reinaud can have arrived at the exact words used in his translation, except under some such predisposing influence.

After this, in a paper read on the 15th April, 1848, and published in 1850 in the *jour. R. As. Soc. F. S.* Vol. XII. p. 1 ff., Mr. Thomas entered into an extensive disquisition on the history connected with the dynasty of the so-called 'Sâh' kings¹ of Saurâshtra or Kâthiawâd; in the course of which, it became incumbent on him to consider the Early Gupta dates. Accepting it as proved by M. Reinaud's rendering

¹ As I have had occasion to remark elsewhere (*Ind. Ant.* Vol. XIV. pp. 65, 325), this name of 'Sâh,'—and, with it, also an idea that these princes were Śakas or Indo-Scythians,—owes its origin to nothing but the fact that, on the silver coins of this series, as also on the silver coins, and even some of the gold coins, of the Early Guptas, it was the custom, as a rule, not to cut on the dies such vowels as, if engraved, would fall on or above the top line of the writing of the marginal legend. The reason, of course, was, want of sufficient space. This custom was observed uniformly in the Gupta silver coins; and hence such legends as (*id.* p. 65 f.) *paramahagavata-maharajadharaja-tya-Chandragupta-Vakramaditya*, which represents *paramahāgavata-mahārājādhirāja-śrī-Chandragupta-Vikramāditya*; "the most devout worshipper of the Divine One, the *Mahārājādhirāja*, the glorious Chandragupta-Vikramāditya." On the Saurâshtra coins, the custom was observed almost uniformly, but not quite so; and hence, to select an instance of its partial observance, such legends as (*id.* p. 325) *rajâh mahakshatrapasa Rudradamna putrasa rajâh mahakshatrapasa Rudrasihasa*, in which the superscript vowel *h* is exceptionally introduced in the last word, and which represents *rājâh mahākshatrapasya Rudraddamnah putrasya rājâh mahākshatrapasya Rudrasihasya*; "of the *Rāja*, the *Mahākshatrapa* Rudrasihâ, the son of the *Rāja*, the *Mahākshatrapa* Rudradâman." The word *sihâ*, i.e. *simha*, 'a lion,' is the termination of the names of several of the *Kshatrapas* or *Mahākshatrapas*. And, because the long vowel *h*, or the short vowel *i* with a following *anusvâra*, is usually omitted in the coins, thus giving the readings of *saha* and *sahasya*, these princes came to be invested with the imaginary family or dynastic name of 'Sâh' or 'Sâh.' Owing to the same fact, also, the termination of some of the names in the list has occasionally been read as *sâna*.

of Albérúni's statements, and by the Veráwal inscription of Valabhi-Samvat 945, that the Valabhi era commenced A.D. 319 (*id.* p. 4) or A.D. 318-19 (*id.* p. 4, note 1), and, by Albérúni's statements, that a family of Guptas reigned as paramount sovereigns in Gujarát shortly before that date, and were then exterminated, he arrived at the conclusions—(1) that this Valabhi era, commencing A.D. 319, may have been established by the *Mahárája* Guhaséna of Valabhi, and may have dated from his accession, or from some striking event of his reign; (2) that there could scarcely be a doubt that these Guptas, who had reigned shortly before A.D. 319, were identical with the Guptas of the Allahábad, Junághadh, and Bhitari inscriptions; (3) that the Guptas were the immediate successors of the Indo-Scythians in Sauráshtra, though traces of the latter might be found, west of the Indus, down to the end of the fourth century A.D.; and (4) that the so-called Sáh kings preceded the Indo-Scythians. His chronological results are tabulated on p. 48 of the same volume. Anterior to B.C. 157 he placed "one or more Sáh kings," who are represented on p. 49 by "Íśvaradatta, son of Varsha."¹ He is followed by thirteen Sáh kings, whose coin-dates are interpreted as being all dated in the fourth century of an era which was assumed to be Albérúni's era of Harsha commencing B.C. 457; and the result for the thirteen kings was from B.C. 157 to B.C. 57. Then comes the Indo-Scythic conquest; to which is allotted the date of B.C. 26. Then the Guptas. And then the Valabhi era, commencing A.D. 319. In this Table, curiously enough, no date is entered opposite the Guptas. But this was probably a printer's omission. For, referring to the note commencing on p. 4, we find it distinctly stated (*id.* p. 5) that the dates in the Gupta inscriptions, and in the Valabhi charters, are to be referred to the Śaka era. These results contained the first intimation that the rulers of Valabhi acted with such inconsistency as to invent an era of their own, dating from the extermination of the Guptas, and yet to continue to use the Gupta era in preference to their own; and also the first intimation of the exact epoch, anterior to A.D. 319, to which the Gupta dates were to be referred. One point on which Mr. Thomas was evidently inclined to lay some stress (*id.* p. 13 ff.), is Albérúni's statement,—based on, but in its application different from, Hindu tradition,—that the Śaka era commemorated the defeat and slaughter of a Śaka or Scythian king by a king named Vikramáditya, who, as Albérúni points out, is evidently not identical with the supposed founder of the Vikrama era; coupled with the occurrence of this last name, Vikramáditya, as a secondary title, on some of the Early Gupta coins.²

¹ *i.e.*, literally, "Íśvaradatta, son of a year"!! The legend on his coin is given, on *id.* p. 50, as ending with *Varsha putha*, in which *putha* is taken (*id.* p. 51) as a Zend substitute for the Sanskrit *putra*, 'a son'!! The two *aksharas* are in reality the first two syllables of the Sanskrit word *prathamé*,—*varshé prathamé*, "in the first year;" see Newton, in *Jour. Bo. Br. R. As. Soc.* Vol. VII. p. 8, and Plate, No. 8; see also Plate i. No. 1, accompanying Thomas' paper, where the legend is almost equally clear.

² I myself think it not at all improbable that, hereafter, it may be shewn that the name of Vikrama, or Vikramáditya, came to be connected with the Málava era of B.C. 57, in consequence of some confused reminiscence of a conquest of the Indo-Scythians by Chandragupta I. or II. But the establishment of the Śaka era is not concerned in this question at all.


Hindu eras, had mentioned the Valabhī era (*id.* Vol. II. Useful Tables, p. 158), to which, on the authority of the Sōmnāthpāṭan or Verāwal inscription of Valabhī-Samvat 945, he allotted the epoch of A.D. 318. But he had made no mention of a Gupta era. Mr. Thomas, however (*id.* Vol. I. p. 270 ff.), introduced his own previously expressed opinion that the Gupta dates had to be referred to the Śāka era; and supplied some further facts which seemed to give additional corroboration to this view. And, on this occasion, he wound up with the general conclusions (*id.* Vol. I. p. 276) that the dates in the Valabhī grants, if applied to the Valabhī era of A.D. 318-19, would give far too modern a period; that these dates did not appear to belong to the same consecutive series with the numbers employed by the Guptas themselves; and that, while still applying the Śāka era to the Gupta dates, the Vikrama era was probably the one which, "in spite of any apparent inconsistency involved," should apply preferentially to the Valabhī grants. Curiously enough he quoted (*id.* Vol. I. p. 271, note 1) a modification of meaning which one portion of Alberūnī's original words would bear; *viz.* "again, the Kūbat-Kāl (Gupta era), "that was, as is said, a wicked and powerful family; when it ceased, it was dated from; "and, as it were (it would seem that), *Balab was the last of them*, for the first of their era "also is 241 years after the Śāka-Kāl." But, he still had not arrived at the absolutely literal translation of the words which he rendered by "when it ceased, it was dated from;" and, partly through this, partly through having his attention directed principally to the connection between the Kings of Valabhī and the Guptas, as described in the words italicised by him, he still failed to see the real bearing of this passage on the epoch of both the Gupta and the Valabhī eras. In this treatment of the question, he quoted Prof. Lassen's views (*Indische Alterthumskunde*, Vol. II.), to the effect that the rise of the Guptas took place between A.D. 150 to 160; but I have not had the opportunity of examining that theory.

Meanwhile, in 1853, 1857, and 1858, there had been published **M. Stanislas Julien's** French translation of the Life and Travels of the Chinese pilgrim Hiuen Tsiang, in which there is contained the important statement that, when the pilgrim visited Valabhī,—which was in or about A.D. 640,—the reigning king there, a nephew of Śīlāditya of Mālava, a son-in-law of Śīlāditya of Kanauj, and a member of the Kshatriya caste, was named *Tou-lou-p'o-po-ŕ'o* (*id.* Vol. I. p. 206), *Tou-lou-po-ŕa-tch'a* (*id.* Vol. I. p. 254), or *T'ou-lou-p'o-po-tou* (*id.* Vol. III. p. 163). Such were M. Julien's renderings of the Chinese transliteration of the original Sanskrit name; which latter he restored as 'Dhrouvapatu,' *i.e.* Dhruvapātu. And it had already been suggested that this name represented that of one of the Dhruvasēnas of the Valabhī family. Mr. Thomas himself (*Prinsep's Essays*, Vol. I. p. 267, note 4) had attached no value to this supposed identification. But Hiuen Tsiang's statement had begun to be looked on, and very properly, as an important factor in the

general inquiry. And I, therefore, now give, for ready reference, in Table II. on page 41 below, a complete genealogy of the Valabhī family, with the official titles of the members of it, and their dates as far as I have been able to verify them. Here, however, in connection with Hiuen Tsiang's statements, I have to draw attention to one or two points which still remain to be cleared up. In his general account of the Life and Travels of the Chinese pilgrim, M. Julien (*id.* Vol. I. p. 206) represents him as telling us, in respect of the kingdom of Valabhī, that "the present king is of the race of the Kshatriyas (*Tsa-ti-ti*); he is the son-in-law of Śīlāditya (*Chi-lo-o-t'ie-to*), king of Kanyākubja (*Kie-jo-kio-che*); his name is Dhruvapaṭu (*Tou-lou-p'o-po-t'o*)." Whereas, in the more detailed account of the Travels, M. Julien renders the pilgrim as speaking, in the same connection, of not one king only, but more than one, and as saying (*id.* Vol. III. p. 163) "the kings of the present period are of the race of the Kshatriyas (*T'sa-ti-ti*); they all are nephews of king Śīlāditya (*Chi-lo-o-t'ie-to*), of the kingdom of Mālava (*Mo-la-p'o*). Now the son of king Śīlāditya (*Chi-lo-o-t'ie-to*), of the kingdom of Kanyākubja (*Kie-jo-ko-che*), has a son-in-law named Dhruvapaṭu (*T'ou-lou-p'o-po-tou*)." While, in Mr. Beal's *Buddhist Records of the Western World*, published in 1884, Vol. II. p. 267, this latter passage appears in the singular again,—“the present king is of the Kshatriya caste, as they all are. He is the nephew of Śīlādityarāja of Mālava, and son-in-law of the son of Śīlāditya, the present king of Kanyākubja. His name is Dhruvapaṭa (*T'u-lu-h'o-po-tu*),”—without any comment explaining the important difference between his rendering and that given by M. Julien. And again, according to M. Julien (*id.* Vol. I. pp. 254 f., 260), the pilgrim speaks of a Dhruvapaṭu (*Tou-lou-po-pa-tch'a*, and also simply *Pa-tch'a*), king of Southern India; but the kingdom of Valabhī can hardly be included in, and much less can it include, Southern India; and the statement is inconsistent with the fact that, at that time, the king of the greater part, if not of the whole, of Southern India, was Pulikēsin II., of the Western Chalukya dynasty, for whom we have on record no title that at all resembles the Chinese transliteration, unless it can be found in the second component of the name of Satyāśraya-Dhruvarāja-Indravarma, the supreme lord or governor of four *vishayas* and *maṅḍalas*, stationed or resident at Rēvatdvīpa, who is mentioned in line 4 f. of the Goa grant of Maṅgallīsa,¹ the uncle of Pulikēsin II., and the wielder of sovereignty during the minority of the latter. These passages present points which must be carefully considered, before any final opinion is arrived at in respect of the identity of the person, or persons, intended by Hiuen Tsiang; the more especially because the dates render it impossible that he should be Śīlāditya VII. of Valabhī, the only one in the family for whom as yet we have obtained the second name of Dhruvabhāṭa; and because M. Julien tells us (*id.* Vol. III. p. 163, note) that the Chinese translation of the name of Dhruvapaṭu of Valabhī was Tch'ang-jouī, 'constantly intelligent,' which of course supports the supposition that

¹ *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 365.—This person, however, may be a son of Maṅgallīsa; see my *Dynasties of the Kanarese Districts*, p. 22.

TABLE II.
Genealogy of the Kings of Valabhi.



the termination of the Sanskrit name, the first part of which, *dhruva*, means 'constant,' really was *patu*, 'smart, dexterous, intellectual,' rather than *bhata*, 'a warrior.' It is to be hoped that some light will be thrown on these points by Mr. Beal's forthcoming translation of the Life of Hiuen Tsiang, corresponding to the first of M. Julien's three volumes.

In 1861 the question was taken up by the late **Dr. Bhau Daji**, in connection with his paper "On the Sanskrit poet Kālidāsa," published in the *Four. Bo. Br. R. As. Soc.* Vol. VIII. pp. 19 ff., 207 ff. As regards the Gupta era, he here only expressed his opinion that it commenced, with the Valabhi era, in A.D. 319. But he brought to notice an important point (*id.* p. 207, note), in the fact that the Kāhām pillar inscription, of which he seems to have then had the opportunity of examining a more reliable version prepared for him by Dr. Bhagwanlal Indrajī, was dated in the 141st year of the Gupta dynasty, and in the reign of Skandagupta; not after his death, as rendered by Prinsep. And he also announced his opinion (*id.* p. 208, note) that the *Tou-lou-p' o-po-to* or *Tu-lu-h'o-po-tu* of Hiuen Tsiang was to be identified with the *Mahārdja* Dharapaṭṭa, the fourth and youngest son of the *Sēndapati* Bhatārka who founded the Valabhi family.

Also in 1861, in the *Four. Beng. As. Soc.* Vol. XXX. p. 1 ff., **Dr. FitzEdward Hall** edited the two grants of the Parivrājaka *Mahārdja* Hastin, dated in the years 156 and 163, No. 21, page 93, and No. 22, page 100, which, now that the *samvatsaras* of the Twelve-Year Cycle of Jupiter that are quoted in them can be calculated with certainty, are of such extreme importance, because the records also state that they are dated "in the enjoyment of sovereignty by the Gupta kings." They had been previously brought to notice, in 1858, in Mr. Thomas' edition of Prinsep's *Essays*, Vol. I. p. 251 f., by Prof. H. H. Wilson's combined translation of the two inscriptions from Mr. Thomas' reading of the texts; but they were first published in full by Dr. Hall. The crucial expression in them is *Gupta-nripa-rājya-bhuktāu*, "in the enjoyment of sovereignty by the Gupta kings," which had been read correctly by Mr. Thomas, and had been suitably rendered by Prof. Wilson in the words "(in the 163rd year) of the occupation of the kingdom by the Gupta kings." The same reading was adopted by Dr. Hall. But, without quoting any authority in support, he laid down the dictum (*Four. Beng. As. Soc.* Vol. XXX. p. 3 ff., note) that *bhukti*, which means literally 'the act of enjoying or eating; enjoyment, eating; fruition, possession, usufruct,' "if unqualified by a temporal particle, denotes 'possession' or 'fruition' only as a thing of the past;" and he translated the phrase (*id.* p. 7) by "(in the 'year one hundred and fifty-six) of the extinction of the sovereignty of the Gupta kings;" and, again (*id.* p. 12), "(one hundred and sixty-three years) after the domination of the 'Guptas had been laid to rest;" thus producing apparently conclusive evidence of an era that dated from the extermination of the Gupta kings; in support of which he quoted (*id.* p. 5, note) the Hindu tradition referred to by Alberūnī, now completely refuted, that the Śaka era dates from the discomfiture of the Śakas. In the course of his remarks, he introduced his reading and revised translation of the first verse of the Kāhām pillar

inscription, in which, though he adopted the correct reading, *śāntī*, at the end of line 2, he followed the general tenor of Prinsep's translation, and rendered the date (*id.* p. 3, note) by "the empire of Skandagupta being extinct for the hundred and forty-first year." To this he appended the remark, "in supersession of a proposal formerly put forth, and from which my present state of information would have withheld me, I now accede to the view that the Kahārum inscription is dated from the overthrow of the Guptas, of whom Skanda must have been virtually the last." These words referred to his previous treatment of the verse in 1859, in the *Jour. Amer. Or. Soc.* Vol. VI. p. 530, when he had rendered the date by "in the one hundred and forty-first year; the empire of Skandagupta being quiescent;" with the remark "there is, then, nothing here recorded concerning the death of Skandagupta, as Mr. Prinsep supposes. Being neither the first ruler of the Gupta dynasty, nor the last, nor of special note, it would be extraordinary indeed, if time had been computed from his decease." As regards the expression in the grants of the *Mahārāja* Hastin, it seems almost needless to comment further on its meaning; because any unbiassed Sanskrit scholar will see at once what the real purport of it is. But it is curious what vitality some mistakes possess. The suggestion has been made to me, quite recently, that possibly even Albérni's own apparent statement, as to the Gupta era dating from the extermination of the Gupta kings, may have originated in a misunderstanding, by the Hindus who supplied him with information, of this same expression *Gupta-nripa-rājya-bhuktāu*. I can only say that it is absolutely and utterly impossible that any Hindu, acquainted with Sanskrit, could interpret this expression as meaning anything except that, at the date connected with it, the sovereignty of the Guptas was still continuing. And it is equally impossible for any European Sanskritist to give it any other meaning; unless, as I have said elsewhere, under the influence of a preconceived bias, so strong as to preclude entirely the critical consideration which would at once shew the error.—In the same volume, page 14 ff., Dr. Hall published his own versions of the Êran inscriptions of Budhagupta and Tôramāna, No. 19, page 88, and No. 20, page 91; and, in the course of his remarks, announced (*id.* p. 15, note) that the details of the date of Budhagupta's record were correct if referred to the Vikrama era, the English equivalent being Thursday, the 7th June, A.D. 108, New Style.—And the general question was taken up by him again in his "Note on Budhagupta," published in the same volume (p. 139 ff.); with the conclusion (*id.* p. 148 ff.) that Budhagupta was probably the first sovereign of a more ancient branch of the Gupta family which ended with himself; and that the dates in the records of Skandagupta and his ancestors possibly ran from an epoch in A.D. 278, which Pandit Bapu Deva Shastri of Benares had found, by actual calculation, to suit the details of the Bhêra Ghaut inscription of the Kalachuri king Narasiṃhadêva, dated in the year 907 (of the era used by his dynasty), and the Têwar inscription of the same king, dated in the year 928.

In 1862, in the *Jour. Bo. Br. R. As. Soc.* Vol. VII. p. 1 ff., Mr. Newton published a lengthy disquisition "On the Sâh, Gupta, and other Ancient Dynasties of Kâthiâwâd

and Gujarât," based on their coins, which, in respect at any rate of the so-called Sâh coins, were then properly examined for the first time. And his conclusions were (*id.* p. 30) that the dates on the Sâh coins were to be referred to the Vikrama era, with the result that the kings of this dynasty extended from A.D. 30 or 40 to A.D. 240 or 250; (*id.* p. 36) that they were immediately succeeded, in Gujarât, by Kumâragupta and Skandagupta, without any intervention of the Indo-Scythians there; and that these two were followed by the Valabhl dynasty, in A.D. 319. His conclusions, however, were chiefly founded on the basis (*id.* p. 31) that "Mr. Prinsep, Mr. Thomas, and Prof. Wilson, agree that the Sâhs preceded the Guptas; and it seems clear that the Guptas preceded the Valabhl dynasty;" coupled with his acceptance of the fact that the Valabhl era,—and with it I conclude, the rise of the family after the last of the Guptas,—had been satisfactorily fixed at A.D. 319; though he also held the opinion (*id.* p. 30) that the dates in the Valabhl grants were probably to be referred to the Vikrama era.

In the same volume, p. 113 ff., Dr. Bhau Daji published his readings and translations of the Junâgaḍh rock inscription of Skandagupta, No. 14, page 56, and of the so-called Sâh inscription of the *Mahâkshatrâpa* Rudradâman on the same boulder. For our present purpose, this paper is chiefly of importance because, in line 15 of Skandagupta's inscription, instead of *Gupta-prakâlê ganandm vidhâya*, "making the calculation in the reckoning of the Guptas," Dr. Bhau Daji read (*id.* pp. 123, 129) *Guptasya kâlê[a*]-ganandm vidhâya*, "counting from the era of Gupta." It is upon this mislection that we are entirely dependent in any supposition that the era dates from the time of the *Mahârâja* Gupta, who is given in the inscriptions as the founder of the family; and it is to this mislection alone that we have to attribute the supposition that the era had the technical name of *Guptasya kâlê*, "the era of Gupta." Attached to Dr. Bhau Daji's rendering of these two inscriptions, there are a few general observations, promising a more ample inquiry afterwards; from which we learn that his views then were (*id.* p. 115) that the Gupta dates were evidently dated in the Gupta era and should be referred to the Valabhl epoch, which was known, from the Verâwal inscription of Valabhl-Sarhvat 945, to be A.D. 318; that accordingly, with his revised translation of the Kahlûm inscription, Skandagupta must be placed in the period A.D. 448 to 459, with a margin of five or ten years on either side; that the dates in the Valabhl grants themselves were to be referred to the Śâka era, with the result that such of them as were then known, belonged to the period A.D. 388 to 443; and that, accordingly, the Valabhl family, founded by the *Sêndrapati* Bhaṭârka, had its rise shortly before Skandagupta.

In 1864, in the *Four. Bo. Br. R. As. Soc.* Vol. VIII. p. 236 ff., Dr. Bhau Daji took the matter up again, in his "Brief Survey of Indian Chronology, from the first century of the Christian era to the fifth;" giving, on this occasion, the more ample inquiry that he had previously promised. In this paper he brought to notice the spurious grant of the *Mahârâja* Dharasêna II. of Valabhl, dated Śâka-Sarhvat 400, which has now been edited by Dr. Bühler in the *Ind. Ant.* Vol. X. p. 277 ff. Dr. Bhau Daji fully recognised the spuri-

ous nature of the grant. But, treating the date as being in the fourth century of the Śaka era,—not in specifically the Śaka year 400,—and expressing his belief that the grant though a forgery, was an ancient one, and was forged within fifty years of the latest of the Valabhi grants discovered up to that time, he recorded his opinion (*id.* p. 244) that “whether the grant be genuine or not, the evidence in regard to the name of the era does “not materially lose its value; as the forger has been careful not to give the exact year, “but simply to state the century of the era, which we must accept as correct, as this “forger may naturally be expected to avoid an error in date, which would vitiate the “document more than any other single error.” His general conclusions were much the same as those arrived at on the previous occasion; *vis.* (*id.* p. 247) that the dates in the Valabhi grants refer to the Śaka era, which, he held (*id.* p. 238), was the era “of Nahapāna, in all likelihood a Parthian monarch, and a descendant of Phrahates;” (*id.* p. 246) that the Gupta era commenced A.D. 318, and Kumāragupta and Skandagupta succeeded the last of the kings of Valabhi; and consequently (*id.* p. 247 f.) that the Valabhi era of Albérunt, if identical with the Gupta era, was certainly not the era used by the Kings of Valabhi themselves, but was the Gupta era, introduced into Kāthiawād by Kumāragupta and Skandagupta. His results led him also to the conclusion (*id.* p. 249 ff.) that Hiuen Tsiang’s visit to India, must really be placed about sixty years earlier than the accepted and well-established period, about A.D. 630 to 643; a proposition which in itself almost ought to have shewn him that there was some radical error in his deductions. And on this occasion (*id.* p. 246) he put forward the suggestion, afterwards accepted and endorsed by Mr. Fergusson,—or at least he drew pointed attention to the apparent fact,—that the Gupta era commenced on the completion of four of the Sixty-Year Cycles of Jupiter after the commencement of the Śaka era; to suit this suggestion, however, he had to distinctly put aside Albérunt’s statement that the difference between the two eras is two-hundred and forty-one years, which, of course, by any arrangement, is one year over and above four cycles of sixty years each. These conclusions are, of course, about as good a sample as could well be sought, of the general state of confusion into which the question had then fallen.

Meanwhile, in 1863, in the *Jour. Beng. As. Soc.* Vol. XXXII. pp. ii. to cxix., General Cunningham had published his Archæological Report for 1861-62, which was subsequently reprinted in 1871 in the *Archæol. Surv. Ind.* Vol. I. pp. 1 to 130, and which I shall notice again further on. In this, he laid aside his original opinion of A.D. 319 for the commencement of the Gupta era; and adopted, instead of it, the view that this year was really the date of the extermination of the dynasty, and that their recorded dates should be referred, as proposed by Mr. Thomas, to the Śaka era. Again, in 1865, in his paper on the “Coins of the nine Nāgas,” in the *Jour. Beng. As. Soc.* Vol. XXXIV. p. 115 ff., he stated that, from a comparison of the Gupta gold coins with their Indo-Scythian prototypes, and of the Gupta silver coins with the Sāh coins of Saurāshtra, he had seen (*id.* p. 118) “that the first Guptas must certainly have been contemporary with the earlier princes of the

"Kushān Scythians, and consequently t' at their date could not possibly be later than the "first century of the Christian era." And, on the grounds that the only scheme, as far as he could see, that would suit all the known dates and other conditions of the dynasty, was to make Chandragupta I. the founder of the era; that Albérūn's information was that the Śāka era was established by a king named Vikramāditya, after a victory over the Śakas; that the name of Vikramāditya was found on coins which were properly assigned to Chandragupta I.; and that the Allahābād pillar inscription mentions Samudragupta, the son of Chandragupta I., as receiving tribute from the Śakas,—he expressed himself (*id.* p. 119) as "inclined to adopt the Śāka era, which began in A.D. 79, "as the actual era of the Gupta dynasty and to attribute its establishment to Chandragupta I."

In 1870, in the *Four R. As. Soc. N. S. Vol. IV. p. 81 ff.*, Mr. Fergusson published his paper "On Indian Chronology," which had been read before the Society two years earlier, in February, 1869. In this paper, the facts were dealt with in considerable detail, and with a good deal of soundness, except for one serious and radical error, *vis.* that the Early and Western Chalukyas and the Kings of Valabhī belonged to one and the same family, of which the Chalukyas were the southern branch (*id.* pp. 89, 91); the grounds for this assumption seem to be nothing except the supposition that (*id.* p. 94) it was Dharasēna IV., the first paramount sovereign in the Valabhī family,¹ who overthrew the Western Chalukya king Vikramāditya II., the son of Pulikéśin II.; but this, again, is a purely mistaken supposition, in support of which there is not the slightest evidence whatever, and against which there is plenty, of the most conclusive kind. Setting aside this, and other important mistakes,—such as his endorsement of Dr. Bhau Daji's reading of *Guptasya kālāt* in the Junāgaḍh inscription of Skandagupta, but his variation of the translation, so as to make it mean, not "from the era of Gupta," but (*id.* p. 112) "from the era of the Guptas;" such as his assumption (*id.* pp. 108, 126) that the Udayagiri cave inscription of the year 82, and the Sāñchi inscription of the year 93, belong to the time of Chandragupta I., with the result that his son Samudragupta could not have ascended the throne before A.D. 411; and such as (*id.* p. 118) his identification of the Buddhagupta of the Êran pillar inscription with the Buddhagupta of Magadha, mentioned by Hiuen Tsiang,²—there is a good deal that is sound in the arguments employed and the results

¹ Mr. Fergusson says Dharasēna III.; but this is an evident mistake.

² On this point, Mr. Fergusson wrote—"I do not think the difference of spelling here indicated, of any importance. Hiuen Tsiang's name was translated first from Sanskrit into Chinese, and from Chinese into French; and might easily have been more changed in the process."—The same mistake has been made in more recent times. And I will, therefore, now point out that the two names are utterly distinct, and belong to totally different persons. In respect of the king mentioned by Hiuen Tsiang (Beal's *Buddh Rec. West. World*, Vol. II. p. 168 ff.; Julien's *Hiouen Tsiang*, Vol. I. p. 149 f., Vol. III. p. 41 ff.), we are not dependent on the correctness of the restoration in the French or English translation. Hiuen Tsiang gives, as the first component of this name, the well-known *Fo-fo*, which he uses so habitually for Buddha, the teacher, the holy Śākya-Tathāgata, and in respect of which he could not possibly be

arrived at; but, of course, they were established only as matters of argument, and not by means of any definite proof. On the grounds that (*id.* p. 90) it was inconceivable that the Valabhi era should not have been used by the Kings of Valabhi themselves; that (*id.* p. 89 f.), by applying the Valabhi dates to A.D. 318, we obtained a Dhruvasēna, who would answer to the Dhruvapaṭu who was on the throne at the time of Hiuen Tsiang's visit to India; that (*id.* p. 104), in addition to the inherent improbability in Albérūnī's statement about the Gupta era dating from the extermination of the dynasty, there was no battle, massacre, or other important event that could be placed in A.D. 318, that (*id.* p. 104), the latest date of the Guptas themselves being that of Budhagupta in the year 165, this, if referred to the Śaka era, with the result of A.D. 243, still left a gap of seventy-five years, with no names to fill it, before we arrived at the last of the Guptas in A.D. 318, and (*id.* p. 107) a still longer interval if referred to the Vikrama era; on the general admission that (*id.* p. 121) the order of succession was, first the so-called Sāhs, then the Guptas, and then the Kings of Valabhi; and on architectural grounds, and general historical and numismatic arguments which are not within the scope of my present remarks, Mr. Fergusson arrived at the conclusions that (*id.* p. 128 ff.) the Vikrama era of B.C. 57 was founded by the so-called Sāh dynasty; that this dynasty continued down to A.D. 235 that there then rose the Andhra dynasty, in which Gōtamiputra was the king of Western India in A.D. 318-19; that the Valabhi era was established then, probably on the building of the city of Valabhi; that the *Mahārāja* Gupta, the founder of the Gupta family, must have been the viceroy of one of the Andhra kings, but not necessarily at the time of the building of Valabhi; and that the Early Guptas and the Kings of Valabhi thus derived the era which afterwards came to be known by the names of both of them. And, in the course of this paper, Mr. Fergusson first broached the theory (*id.* p. 131 ff.) that no such person as Vikramāditya, the traditional enemy of the Śakas and founder of the Vikrama era, existed anterior to the Christian era, or within some centuries of that time; but that, "some time after Vikramāditya of Mālwa," whom he placed (*id.* p. 90) about A.D. 490 to 530, "had rendered the name so celebrated, the Hindus, on the revival of Brāhmanism, wished to possess an era which should, at least, be older than the Buddhist era of Śālivāhana," i.e. he Śaka era. "At that time, the Sāh era, established by Nahapāna, was vacant, having fallen into disuse on the destruction of that dynasty and its supersession by the era of Valabhi; and that the Hindus then appropriated it, by attaching to it the name that it now bears, and inventing the history requisite to render its adoption feasible." This adaptation of the era was then allotted by him either to the time of Bhōja of Dhārā, about A.D. 993, or to the restoration of the Western Chālukya dynasty, in A.D. 973.

mistaken. Whereas, in respect of the king mentioned in the Eraṅ inscription, the metre, as well as the perfect clearness of the reading, shew^s as conclusively that the first component of that name is Budha, the planet Mercury. Sanskrit scholars will recognise at once the thorough difference between the two names.—For my own remarks on the date of Budhagupta of Magadha, see the *Ind. Ant.* Vol. XV. p. 251 f.

In 1871, in the *Four. R. As. Soc. N. S. Vol. V. p. 193 ff.*, **General Cunningham** attached a note to Professor Dowson's paper on "Ancient Inscriptions from Mathurā;" in which (*id. p. 196*), on the grounds that both Kanishka and Huvishka must have preceded the establishment of the Śaka era, he referred the dates of their inscriptions to the Vikrama era; and he quoted the reference, in the Allahābād pillar inscription, to the Daiva-putras and Shāhānushāhis, "who must have been the Turushka kings of the Pañjāb," as shewing that Samudragupta was "a contemporary of the Turushka kings, whose dominion, according to the Chinese authorities, had already passed away in the beginning of "the third century after Christ." As to this last point, I will only say that what we have in reality, in the Allahābād inscription, is, not the means of fixing the date of Samudragupta through the Chinese accounts, but the means of correcting the Chinese accounts by the date of Samudragupta.

In the same year, 1871, **General Cunningham** published his *Archæol. Surv. Ind. Vol. I.*, containing, in the first part of it, his Archæological Report for the season 1861-62, which, as already noted, had appeared originally in the *Four. Beng. As. Soc. Vol. XXXII. pp. iii to cix.* In this (*id. p. 94*), he expressed the opinion that the Śaka era, for the Early Gupta dates, would accord best with the then general acceptance of the fact that the Gupta dynasty was overthrown in A.D. 319; and he consequently now interpreted the date of the year 141, in the Kaḥāuṃ pillar inscription of Skandagupta, as equivalent to A.D. 219. And, incidentally, (*id. p. 139 f.*) in connection with the question of the Vikrama and Śaka eras, he identified the Vikramāditya, mentioned by Albēruṅ,—in commemoration of whose victory over the Śakas at Karūr, between Multān and Lōnl, one hundred and thirty-five years after the establishment of the Vikrama era of B.C. 57, the Śaka era was supposed to have been founded,¹—with the Śālivāhana, whose name came subsequently to be connected by the Hindus with the Śaka era, as the founder of it. The same opinion, as to the dominion of the Guptas having probably commenced about A.D. 78, was also expressed by him in 1873, in the *Archæol. Surv. Ind. Vol. III. p. 4*; in which volume he also (*id. p. 41 ff.*) referred the dates of Kanishka and Huvishka to the Vikrama era; proposed to take the three kings Hushka, Jushka, and Kanishka, of the *Rājatarānginī*, i. 168-73, as being represented by the Vikramāditya who, according to Mērutuṅga, reigned for sixty years; and fixed the Indo-Scythian rule, in India, as commencing B.C. 57 and ending A.D. 79, "at which latter date, according to Hindu belief, the dynasty of "Vikramāditya was finally overthrown by Śālivāhana."

In 1872, in the *Four. Bo. Br. R. As. Soc. Vol. X. p. 72 ff.*, **Dr. R. G. Bhandarkar** threw in his adherence to the opinion held by Mr. Thomas and Dr. Bhau Daji, that the era to which the dates in the Valabhi grants refer, is the Śaka era, as affording "an intelligible starting-point for the Valabhi era, ascertained by Colonel Tod to have commenced in A.D. 319;" his own opinion as to the establishment of this Valabhi era

¹ *Albēruṅ in Indi Translation Vol. II. p. 6.*

being that it commemorated the coronation, as *Mahārāja*, of *Dr̥ṇasimha*, the second son of the *Sēndapati* Bhaṭārka, by a sovereign who, in the Valabhi grants, e.g. No. 38, line 5, page 168, is described as "the paramount master, the sole lord of the circumference of the territory of the whole earth;" from the date of this event, he held, the members of the Valabhi family were independent kings. In 1874, however, in the *Ind. Ant.* Vol. III. p. 303 f., on the grounds that the alphabet used in the Valabhi grants resembles very much that used in the Western Chalukya grants belonging to the early part of the eighth century, and for other reasons not fully specified, he modified this opinion, so far as "to think that the Valabhi dates must be referred to an era other than the Śāka;" and he proceeded to join Mr. Fergusson in referring them to an era commencing A D. 318. But he still maintained a verbal difference with Mr. Fergusson, to the effect that, since in the Valabhi family there was no individual named 'Ballaba,' or Valabhi, "it is doubtful whether the era was really of Bhaṭārka's family. If the era was not the era of the dynasty, but was in use in Saurāshtra before the foundation of the dynasty, the Valabhi dates may be referred to it. Or, more likely, since the Guptas, who preceded that dynasty, introduced their era into the country, the grants must have been dated in that era. But there is no difference in effect; since the initial dates of both are the same."

In 1873, in the *Ind. Ant.* Vol. II. p. 313, Col. J. W. Watson published the following tradition, attributed to the bards of Kāṭhiāwāḍ:—"The bards relate that VALĀ RĀMA RĀJĀ, son of VALĀ Warsingij, reigned at Junāgaḍh and Vanthall. He was famed for his munificence; and it is told of him that, when his beard was shaved for the first time, he gave in charity twenty-one villages, and distributed fifty lakhs of rupees¹ as alms to the poor. RĀMA RĀJĀ was of the VALĀ race. It is said in Saurāshtra that, previous to the rise of the kingdom of Junāgaḍh-Vanthall, Valabhīnagara was the capital of Gujarāt. The rise of Valabhi is thus told by the bards. The Gupta kings reigned between the Ganges and Jamnā rivers. One of these kings sent his son, Kumārapālagupta, to conquer Saurāshtra; and placed his viceroy Chakrapāni, son of Prāpadatta, one of his Amirs, to reign as a provincial Governor in the city of Wāmanasthall (the modern Vanthall). Kumārapāla now returned to his father's kingdom. His father reigned twenty-three years after the conquest of Saurāshtra, and then died; and Kumārapāla ascended the throne. Kumārapālagupta reigned twenty years, and then died, and was succeeded by Skandagupta; but this king was of weak intellect. His *Sēndapati* Bhaṭāraka, who was of the Gehlot race, taking a strong army, came into Saurāshtra, and made his rule firm there. Two years after this, Skandagupta died. The *Sēndapati* now assumed the title of King of Saurāshtra; and, having placed a Governor at Wāmanasthall, founded the city of Valabhīnagara. At this time, the Gupta race were dethroned by foreign invaders. The *Sēndapati* was a Gehlot, and his forefathers reigned at Ayōdhyanagarī, until displaced by the Gupta dynasty. After founding Valabhi, he established his rule

¹ Nominally, half a million pounds sterling.

“in Saurāshtra, Kachchh, Lāṭadēsa, and Mālava. The Vājās were a branch of the Gehlots. After the fall of Valabhī, the Vājā governor of Wāmanasthall became independent. Rāma Rājā had no son; but his sister was married to the Rājā of Nagar Ṭhāṭha,” &c. This story was criticised by Dr. R. G. Bhandarkar in the *Ind. Ant.* Vol. III. p. 303; his opinion being that “the tradition itself, though interesting, as giving the truth generally, cannot be considered to be true in the particulars; it simply gives us what was known before, that the Valabhis succeeded the Guptas.” In reply to this, and in defence of the supposed tradition, Mr. Thomas¹ said that it “may be imperfect, as such old-world tales are liable to become; but there is an instructive confirmation of one obscure portion of the earlier history given by the Muhammadan inquirer,² and a clear explanation of the causes of the local transfer of power, combined with an important reference to the conventional imperial delegation of authority to a son, as well as an indication of the length of the reigns of two kings, to be found nowhere else; and, to complete the tale, we trace in its details, a fully reasonable accord with the more precise data furnished by inscriptions and coins.” Of course, this supposed tradition is of that half-perfect kind which carries its own confirmation with it; if we could but accept it. Nothing is more natural, for instance, than the introduction of the termination *pāla* into the middle of the name of Kumāragupta; and than the substitution of Prāṇadatta and Chakrapāṇi for the Paṇadatta, and his son Chakrapālita, of the Junāgadh rock inscription of Skandagupta, and of Bhattāraka for Bhatārka, as the name of the upstart *Sēnāpati*. But no further attention need be paid to the matter; since I have it on the best possible authority,—that of Dr. Bhagwanlal Indrajī himself,—that the supposed tradition has only sprung into existence within the last fifteen or twenty years, and owes its origin only to certain speculations of his, which found their way to the bards through an educational treatise! It simply furnishes an instance of the extreme suspicion with which we must view every Hindu historical legend.

In 1874, in the *Four. Beng. As. Soc.* Vol. XLIII. Part I. p. 363 ff., the question was considered by Dr. Rajendralala Mitra, in then bringing to notice the Indōr grant of Skandagupta, No. 16, page 68. He introduced (*id.* p. 369 ff.) a new, and perfectly gratuitous, point in the Kahām pillar inscription, by connecting the word *śāntā*, in line 3, with *varshā*, in line 4; and, hankering after the meanings given by Mr. Prinsep and Dr. Hall, to the word *śānta* in particular, though he aimed also at giving to the whole verse a purport which should be more correct than that made out by them, and should be an improvement even on Dr. Bhau Dajī's translation, he translated (*id.* p. 371) “in the empire “of Skandagupta; the year one hundred and forty-one having passed away.” The paper adds nothing of any value to the general discussion; beyond (*id.* p. 371) following, in contradiction to Dr. F. E. Hall, Prof. H. H. Wilson's rendering of the expression in the *Mahā-*

¹ *Archzol. Surv. West. Ind.* Vol. II. p. 30.

² *i.e.* Alberūnī.

rdja Hastin's grants as shewing that the supremacy of the Gupta kings was still continuing in his time; and beyond introducing (*id.* p. 368) Mr. Blochmann's proposed emendation of the translation of Albérûnî's statement, which I have quoted at page 28 above, note 1. But Dr. R. Mitra failed to see the interpretation that might be put upon the emended rendering; and he expressed his own conviction (*id.* p. 372) that the Early Gupta dates, and those of Budhagupta and of the *Mahārāja* Hastin, are recorded in the Śaka era; and that Albérûnî's Gupta era commemorates the expulsion of the Guptas from Gujarât by the Kings of Valabhi.

In 1876, in the *Archæol. Surv. West. Ind.* Vol. II. p. 18 ff.; Mr. Thomas published a chapter on the "Sâh and Gupta Coins, &c.," in which, as already noted, he included some strong remarks in support of the authenticity of the supposed bardic tradition from Kâthiawâd, that had been brought to notice by Col. Watson. In his tabular statement of the Early Gupta dynasty (*id.* p. 70), he referred the Gupta dates, as before, to the Saka era, and, with them, the date on Tōramāna's coin, which he interpreted (*id.* p. 66) as 182; on the authority of the supposed tradition, he placed the *Sēndpati* Bhaṭārka, the founder of the Valabhi family, specifically two years before the death of Skandagupta; and he added a remark indicating apparently that his opinion was, that the Valabhi era, commencing A.D. 319, was established by the *Mahārāja* Dharasēna II., "who seems "to have been the earliest monarch of any real pretensions."

In 1878, in the *Ind. Ant.* Vol. VII. p. 79 ff., Dr. Bühler brought to notice the newly discovered Alinā grant of Śīlāditya VII. of Valabhi, No. 39, page 171, which gives for him the date of Gupta-Samvat 447 (A.D. 766-67), and the *biruda*, or title or second name, of Dhrūbhāṭa or Dhruvabhāṭa. Drawing attention (*id.* p. 80) to the pointed similarity of this name with the *T'u-lu-p'o-po-tu* of Hiuen Tsiang's account, and suggesting that Hiuen Tsiang's translation of the name by 'constantly intelligent' might be due to incorrect information, or to some confusion between *bhata*, 'a warrior,' and *bhatta*, 'a learned man,' Dr. Bühler expressed himself as inclined to believe that Śīlāditya VII. was Hiuen Tsiang's contemporary; the result of which would be that the era used in the Valabhi grants must have commenced either shortly before or shortly after A.D. 200. He pointed out, however, (*id.* p. 81) that the occurrence of the title of Dhrūbhāṭa or Dhruvabhata in this grant, was in reality only one point among many, requiring careful consideration, in connection with a question that was by no means a simple one.

In 1879, in the *Archæol. Surv. Ind.* Vol. IX. p. 9 ff., General Cunningham brought to notice the grant of the *Mahārāja* Hastin, of the year 191, No. 23, page 106; the Bhumarā pillar inscription, No. 24, page 110; the *Mahārāja* Samkshōbhā's grant, of the year 209, No. 25, page 112; and, with the exception of No. 28, page 125, the grants of the *Mahārājas* of Uchchakalpa, No. 26, page 117, to No. 31, page 135, ranging from the year 174 to the year 214. And, in the grants of Hastin and Samkshōbhā, he followed Prof. Wilson in giving to the expression *Gupta-nripa-rāja-bhuktāu* interpretations which, though

not grammatically, were substantially correct, in shewing that it indicated that the Gupta sovereignty was still continuing when the grants in question were issued. To his notice of these inscriptions he annexed some remarks (*id.* p. 16 ff.) on the "Date of the Guptas," in which he arrived at the conclusion that the probable epoch of the Gupta era was A.D. 194-95, and its commencement A.D. 195-96. Starting with accepting it to be almost certain that Śīlāditya VII. was the king of Valabhl who was reigning at the time of Hiuen Tsiang's visit in A.D. 640, he pointed out (*id.* p. 17) that, as the year 447 of the grant might fall twenty-five or thirty years either earlier or later than the pilgrim's visit, the initial point of the Gupta era might lie anywhere between A.D. 163 and 223. Within this period, he found, the only year which would suit the conditions of the record in the Êraṇ pillar inscription of Budhagupta and the Mōrbl grant of Jāīnkadēva, was A.D. 194-95 as the epoch of the era. Applying this epoch to the Êraṇ date, the result (*id.* p. 18) was A.D. 359; in which year the twelfth lunar day of the bright fortnight of Āṣāḍha, according to his calculation, was, as required, a Thursday; *vis.* the 24th June. And applying it to the solar eclipse mentioned in the Mōrbl grant, which he assumed to have occurred on the new-moon day of the month Māgha, five days before the writing of the grant, the result was the 10th February, A.D. 780, "on which very day there was an eclipse of the sun, "visible in Eastern Asia."¹ The fourth test, which, he indicated, should be applied, was the mention of some of the *samvatsaras* of Jupiter's Twelve-Year Cycle in the grants of the *Mahārājās* Hastin and Saṁkshōbha. Exact information about this cycle, however, was not then forthcoming; and, in making the Mahā-Vaiśākha *samvatsara* correspond (*id.* p. 19) with A.D. 350, which, with the epoch of A.D. 194-95, would be the equivalent of Gupta-Samvat 156, recorded in the *Mahārāja* Hastin's grant, No. 21, page 93, he seems to have acted on pure assumption; while, in order to make the Mahā-Āsvayuja *samvatsara*, recorded in the same *Mahārāja's* grant of Gupta-Samvat 163, No. 22, page 100, fit in with his view of the cycle, he had to alter² the original date from 163 to 173, with the result of A.D. 367. On this occasion, General Cunningham (*id.* p. 21) again referred the establishment of the Gupta era to Chandragupta I.; and he placed the foundation of the Valabhl era of A.D. 319 in the twentieth year of the reign of Kumāragupta. And, in connection with this Valabhl era, he expressed the opinion (*id.* p. 20) that it could have no connection whatever with the downfall of the Gupta dynasty; for the reason that, applied to the epoch of A.D. 194-95, the dates of 138 and 139 in the Junāgaḍh rock inscription of Skandagupta, No. 14, page 56, shewed that the Gupta dominion was still intact, in Saurāsh-ṭra or Kāṭhiāwāḍ, up to³ A.D. 333. And he expressed the opinion that the apparent incon-

¹ For the full details of this eclipse, see *Ind. Ant.* Vol. IX. p. 308.

² See page 102, note 2, below my introductory remarks to this inscription, where I have shewn that a very material obstacle exists in the way of this alteration of the text. Also, as will be seen further on, from the correct point of view as regards the Gupta era, any alteration is quite unnecessary.

³ This is with the supposed date of 139. But the real dates in the record are 136, 137, and 138; they do not include 139.

sistencies in Albérúni's statements arose from his finding that the Guptas and the Kings of Valabhi had actually used one and the same era, and from his taking it for granted that that era must have been the era which he found to be called the Valabhi era, and to have commenced in A.D. 319. He placed the *Sénapati* Bhaṭarka of Valabhi in A.D. 339 (*id.* p. 21), twenty years after the establishment of the Valabhi era of 319. And, interpreting the coin-dates of Tōramāpa as 52 and 53 (*id.* p. 27), he referred them (*id.* p. 21) to the Valabhi era of A.D. 319.

The subject was taken up again by **General Cunningham** in 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 111 ff., in his Appendix on "The Gupta Era;" and on this occasion he arrived at the final conclusion, that (*id.* p. 126) the commencement of the era was probably in A.D. 167 and, therefore, its epoch was A.D. 166-67. Of the leading general facts on which he relied (*id.* p. 116), the first was that Samudragupta's date seemed to be fixed approximately, within rather narrow limits, by two facts; *vis.*—(1) "his own mention" (in the Allahābād pillar inscription) "of the tribute received from "the Daivaputra, Shāhi, Shāhānushāhi, which we now know to be the titles of the Yue-chi "Indo-Scythians, Kanishka, Huvishka, and Vāsudeva, and their successors, shews him to "have been a contemporary of some prince of this race;" and (2) "according to "Chinese authority, the Yue-chi, during the period between A.D. 220-80, put their kings "to death, and established military chiefs." From a comparison of these two statements, General Cunningham inferred that Samudragupta must have reigned before the time when the Yue-chi put their kings to death, or not later than some time between A.D. 200 and 250; and that his father, Chandragupta I., must be placed towards the end of the second century A.D. But, with regard to this, I have only to repeat a remark which I have already had occasion to make; *vis.* that what we really have, is, not the means of fixing the period of Samudragupta through the Chinese accounts, but the means of correcting the Chinese accounts through the Early Gupta chronology. The second leading point was that, as already indicated by him, the Alinā grant of Śīlāditya VII. shewed that the initial point of the Gupta era must fall between A.D. 164 and 224. Putting these two approximate results together, he inferred that the beginning of the Gupta era must have been not very far from A.D. 180 to 200. Meanwhile, he had obtained certain information regarding the Twelve-Year Cycle of Jupiter, from Bapu Deva Shastri, Professor of Mathematics in the Benares College, which enabled him now to take this test also into consideration; with the result that, subject to the approximate limits which he had already arrived at on general grounds, and having regard also to the week-day recorded in the Êraṇ pillar inscription of Budhagupta, the only years that would meet all the requirements of the case were A.D. 166-67 as the epoch, and A.D. 167-68 as the commencement, of the Gupta era. In order, however, to make all the *samvatsaras* of the Twelve-Year Cycle of Jupiter, mentioned in the grants of the *Mahārājas* Hastin and Samkshōbha, tally with this epoch, he had still to maintain the alteration of the date of

Gupta-Samvat 163 into 173. Accepting this alteration, his theory and arrangement of the *samvatsaras* of the Twelve-Year Cycle, and his general results, have seemed sound, consistent, and reliable. But it is now known that his process for determining the *samvatsaras* is wrong, and cannot give satisfactory results. This part of the subject will be explained fully further on. Meanwhile I will only state here that General Cunningham's theory of the Twelve-Year Cycle is based on the assumption, the incorrectness of which can now be proved, that the *samvatsaras* of it begin and end with the luni-solar years; and that his process for determining the *samvatsaras* (*id.* pp. vi. 114 f., and *Indian Eras*, p. 27 f.) only gives the *samvatsara* that is current, according to the sign-passing system, at the commencement of any given luni-solar year; it does not provide for the really essential point, even of this system, which is the determination of the *samvatsara* that is current on any given date in a given year after the commencement of it. On this occasion (*id.* p. 112) General Cunningham fully accepted Albêrûnî's apparent statement regarding the extinction of the Gupta sovereignty, in the Valabhi country, in A.D. 319, in which year he now placed the *Sênâpati* Bhaṭârka of Valabhi. And he recorded the opinion (*id.* p. 126) that the foundation of the Valabhi era of A.D. 319 might very probably have been brought about by the opportunity afforded by the death of Skandagupta, for whom the latest recorded date, supplied by a coin of the year 149, would be, according to his new theory, A.D. 315. In general support of his results, he also quoted certain numismatic facts, such as (*id.* p. 112) that a comparison of the gold coins of the Guptas with those of the Indo-Scythian king Vâsudêva, shewed that they must have followed him very closely; while a comparison of their silver coins with those of the Satraps of Saurâshṭra,—formerly called the Sâh kings,—and those of the Valabhi family, proved distinctly that the Guptas must have followed the Satraps of Saurâshṭra and preceded the Valabhi family; but this is a line of study with which we are not concerned in the present inquiry.

In the same year, in the *Four. R. As. Soc. N. S.* Vol. XII. p. 259 ff., Mr. Fergusson issued his paper "On the Śaka, Samvat, and Gupta Eras," as a supplement to his original paper "On Indian Chronology," which has been noticed at page 46 f. above. In his previous paper, he had adopted General Cunningham's view that Kanishka died A.D. 24. Now, however, on arguments based (*id.* p. 264) on the comparative state of decay exhibited by coins of Kanishka and by some belonging to the Roman Consular period, found in Kanishka's *Stûpa* at 'Manikyala,' on the understanding (*id.* p. 265) that the legend of St. Thomas having visited the East in the reign of a certain king Gondophares,—which visit, if it really occurred, must have been after A.D. 33 and probably before A.D. 50,—is at any rate admissible so far as to shew that the inventors of the legend must have known that the king of 'Taxila' at that time was Gondophares, whose name occurs, on coins, among a series of kings "who reigned in the north-west of India, certainly subsequent to the fall of the Greek dynasties, and as certainly anterior to Kanishka;" and

on similar grounds, he arrived at the conclusion (*id.* p. 261) that the Śaka era was established by Kanishka, and took the name of the Śālivāhana era from having been introduced into India in the reign of Śātakarpi II. of the Andhra dynasty, the "chief of the Śātavāhana or Śālivāhana race." As regards the Gupta era, Mr. Fergusson took this opportunity of recording his impression (*id.* p. 285) that his view of it "would never have been considered doubtful, had it not been that the chronology of that period had hitherto been based almost exclusively on numismatic researches." And, in repeating his conviction (*id.* p. 281) that the commencement of the era was in A.D. 319, and (*id.* p. 270) that it was established in the reign of the Andhra king Gôtamiputra, he also now maintained (*id.* p. 271) that the era did not necessarily date from the accession of the king, or from his death, or from any specific event in his reign, but that, in order that dates in the new era might be easily convertible into the old era, the commencement of the new era was simply fixed by the expiration of four of Jupiter's Sixty-Year Cycles from the commencement of the Śaka era. In respect of his theory that the Śaka era was established by Kanishka, and of some others of his general results, I see no reason, at present, to dispute them, apart from the arguments on which they were based. But a few words seem necessary in connection with the key-note to his whole paper, which is plainly to be recognised in his desire to find for the Vikrama era some origin other than its actual establishment in B.C. 57, and, according to tradition, by a king Vikrama or Vikramāditya, actually reigning at that time. He had already thrown out this suggestion in his previous paper. And now he claimed that, granting the correctness of his other conclusions, there could be found (*id.* p. 271) no direct evidence for the existence of a Vikrama era in the first century B.C., nor for a very long time afterwards, for so long, in fact, that it was impossible to establish any connection between a king Vikrama and the original establishment of the era. Referring to two passages in the *Rājatarāṅginī*, one of which¹ speaks of Pratāpāditya, who was brought from another country to be crowned king of Kaśmīr, as a kinsman of a king Vikramāditya who, the book states, was wrongly thought by some to be the Śākāri or 'enemy of the Śakas,' and the other of which² states that, at the time of the death of Hiranya of Kaśmīr, there reigned at Ujjain a powerful king Vikramāditya, who had the second name of Harsha, and who also had destroyed the Śakas; and quoting also Alberūnī's explanation that the Vikramāditya who, according to the tradition given to him, conquered the Śakas a hundred and thirty-five years after the establishment of the Vikrama era, could not be identical with the founder of that era,—the conclusions at which he arrived were (*id.* p. 274) that the Vikramāditya who conquered the Śakas at the battle of Karūr, was Harsha-Vikramāditya of Ujjain; that his death took place about A.D. 550, and the battle of Karūr, in A.D. 544; that, about or before A.D. 1000, when "the struggle with the Buddhists was over, and a new era was opening for the "Hindu religion," the Hindus sought to establish some new method of marking time, to

¹ Calcutta edition, ii. line 6; page 15.

² Calcutta edition, iii. lines 125, 128; page 26.

supersede the Buddhist Saka era of Kanishka ; that, the Guptas and the Kings of Valabhi having then passed away, and having also been insignificant and of doubtful orthodoxy, in looking back for some name and event of sufficient importance to mark the commencement of a new era, they hit on the name of Vikramāditya, as the most illustrious known to them, and his victory at Karūr as the most important event of his reign ; and that then, since the date of that victory, A.D. 544, was too recent to be adopted, they antedated the epoch by ten cycles of sixty years, thus arriving at B.C. 56 for their Vikrama era, and also, not content with this, devised another era, which they called the Harsha era, from the other part of his name, and the epoch of which was fixed in B.C. 456, by placing it ten even centuries before the date of the battle of Karūr. It is an actual fact, that the name of Vikrama does not occur in connection with the era of B.C. 57 until a comparatively late date.¹ But Mr. Fergusson's arguments are vitiated throughout by the undue reliance which he placed on the quasi-historical records of the *Rājatarangini*. The early chronology of Kaśmīr has still to be fixed ; and the means of adjusting it are to be found in A.D. 533 as the date of Mihirakula, who, according to the book itself, reigned in the eighth century B.C. And, if the date of Harsha-Vikramāditya of Ujjain is really dependent on the date of Hiraṇya of Kaśmīr, it certainly cannot be placed as early as the sixth century A.D.

In 1881, in the *Ind. Ant.* Vol. X. p. 213 ff., Dr. Oldenberg published his paper "On the Dates of ancient Indian Inscriptions and Coins," the whole of which well deserves careful study. Holding (*id.* p. 214) as the result of Herr von Sallet's numismatic researches, that Kanishka, Huvishka, and Vāsudēva, cannot be placed earlier than the first century A.D., and must be placed before A.D. 200 ; quoting the Bādāmi cave inscription of the Western Chalukya king Maṅgallsa,² dated Śaka-Samvat 500 expired, as proving conclusively that the Śaka era ran from the coronation, not the defeat or death, of a Śaka king (or kings) ; finding (*id.* p. 214 f.), from the coins, that Kanishka belonged undoubtedly to the Śaka tribe ; and finding also (*id.* p. 215) that, at the time to which Kanishka must be referred, there was no Indian king who at all equalled him in power and fame, he arrived at the primary conclusion that the era used in the inscriptions of Kanishka, Huvishka, and Vāsudēva, is the Śaka era, and that the event from which it dates, is the accession of Kanishka. Working from this starting-point, after indicating very correctly (*id.* p. 217) that the fundamental mistake which vitiates the researches of Mr. Thomas and others "consists in their touching only incidentally upon the direct "and very clear ancient tradition," preserved by Albérūti, "which we possess regarding "the Gupta era, instead of placing distinctly this tradition in the foreground, and of "systematically discussing the question whether any serious objections can be opposed

¹ I am not prepared at present to specify the exact date. But the 'Gyāraspur' or 'Gyāriapur' inscription (*Archæol. Surv. Ind.*, Vol. X. p. 33, and Plate xi.) shows that the era was still known as the Mālava era, in Central India, down to about A.D. 880.

² *Ind. Ant.* Vol. VI. p. 363 f. and Vol. X. p. 57 ff.

"to it," he arrived, by a series of historical, numismatic, and palæographical arguments, at the conclusion that the rise of the Early Guptas must be placed in A.D. 319, and their downfall about A.D. 480. In the course of the paper, he suggested (*id.* p. 219) that the *T'u-lu-p'o-po-tu* of Hiuen Tsiang may be Dêrabhaṭa of Valabhi, or may indicate one of the Dharasênas or one of the earlier Śîlâdityas of that family; and that, at any rate, the occurrence of the title Dhrûbhaṭa in the Allnâ grant, as only a secondary title, furnishes no conclusive evidence against the commencement of the era in A.D. 319. He announces (*id.* p. 220) that, with the epoch of A.D. 319, the record of the Êraṇ pillar inscription of Budhagupta, that the twelfth lunar day of the bright fortnight of the month Âshâdha of Gupta-Samvat¹ 165 was a Thursday, was quite correct by the Tables and formulæ in Warren's *Kala-Sankalita*. And (*id.* p. 222), referring to the supposed tradition of the bards of Kâthiawâd, he gave perfectly good reasons for holding, even without further proof, that it was nothing but "a very poor compilation, pieced up of what those "bards" knew by hearsay of the results of modern epigraphical and numismatical investigation."

In the same year, the general question was taken up again by **Mr. Thomas**, in his paper on "The Epoch of the Guptas," published in the *Four. R. As. Soc. N. S.* Vol. XIII. p. 524 ff. On this occasion (*id.* p. 524) he abandoned the opinion that the dates on the Sâh coins were to be referred to the supposed Harsha era commencing B.C. 456; and expressed himself as inclined to accept Mr. Newton's theory that they are recorded in the Vikrama era of B.C. 57. But, as regards the Gupta era, he still (*id.* p. 549) adhered to the view that it was identical with the Śaka era, or, at any rate, that the Gupta dates were to be referred to the Śaka epoch. In this paper (*id.* p. 529 f.) he introduced some other passages from Albêrûni, shewing that eras had been established from the death of 'Alexander the Founder' and of 'Yazdajird ben Shahryâr,' which were used by him as indicating that Albêrûni must have exercised due deliberation before making the (supposed) statement that the Gupta era dated from the extermination of the Guptas; and he brought forward a discovery (*id.* p. 545) that certain signs in front of the horse's head on the reverse of some coins of 'Syalapati,' Sâmantadêva, 'Khadavayaka,' and Bhimadêva, of Kâbul, represented, in various degrees of legibility, the syllables *Ga*, *Gup*, and *Gupta*, which were consequently held to refer to the Gupta era the conventional date, 617, which these signs introduced. He had previously suggested A.D. 935 for the accession of Sâmantadêva.² And, pointing out that the conventional

¹ Or, rather, of Gupta-Samvat 166; since he treated the record as meaning the year 165 expired and 166 current. But the epoch would then be A.D. 318, not 319. It was probably through an oversight that Dr. Oldenberg spoke in this connection of A.D. 319 as the epoch. Elsewhere (*id.* pp. 215, 227) he distinctly specifies A.D. 319 as the beginning of the Gupta era; according to which, A.D. 318 would be the epoch selected by him.

² *Four. R. As. Soc. F. S.* Vol. IX. p. 179.

date of 617, if added to A.D. 319, gave A.D. 936,—within one year of his date for Śāmantadēva,—he quoted these coins (*id.* p. 544) as proof of “the practical survival of “the method of dating from the extinction of the Gupta rule.”

Closely connected with the preceding, is Sir E. Clive Bayley's paper “On certain Dates occurring on the Coins of the Hindu kings of Kābul, expressed in the Gupta Era and in Arabic (or quasi-Arabic) numerals,” published in 1882, in the *Numismatic Chronicle*, Third Series, Vol. II. p. 128 ff. This paper was issued in support of his theory of A.D. 189-(90) or 190-(91) for the epoch of the Gupta era, which was based to a great extent on the apparent deduction from the Alinā grant of Śilāditya VII., noted at page 51 above, that the era cannot have commenced later than A.D. 200; coupled with his reading of “698 Gupta” on the earliest of the coins of ‘Syalapati,’ which, as he placed ‘Syalapati’ between A.D. 887 and 916, would shew that the Gupta era commenced after A.D. 180. As regards the era of A.D. 319, his suggestion, based on the weakness attributed to Skandagupta in the supposed tradition of the Kāthiāvād bards, was (*id.* p. 155 f.) that it might date from the death of Kumāragupta, and might memorialise a rebellion against Skandagupta by the members of the Valabhī family. The latter dynasty, he held, still continued, in spite of any such circumstances, to use the Gupta era. The key-note to the whole theory is to be found in Sir E. Clive Bayley's agreement with Mr. Thomas, that the specified abbreviations of a full legend, which must be taken as ‘Guptasya Kāl,’ were really to be found in the dates on the Kābul coins. But in details he differed widely from Mr. Thomas. Thus (*id.* p. 145) he read the signs in the opposite way to that in which Mr. Thomas would read them; and, instead of accepting the conventional date of 617, he found in the figures various values, to suit the period, A.D. 887 to 916, which he assigned to ‘Syalapati.’ The question of the true interpretation of the dates on the coins in question, depends chiefly on the real period, still to be proved, that is to be assigned to ‘Syalapati’¹ and the other kings in ques-

¹ In connection with this, I would draw special attention to the coin of ‘Syalapati’ figured in *Prinsep's Essays*, Vol. I. p. 304, Pl. xxv. No. 2, which, as now explained by Sir E. Clive Bayley's Table, gives the unmistakable date of 814, traces of which are also discernible in No. 1 on the same Plate. This No. 2 has behind the horseman the same monogram, *u u*, (not *f t*), as Sir E. Clive Bayley's Nos. 25, 26, and 27 have; also, as explained by No. 1, it has in the upper corner, in front of the horseman, the same symbol (interpreted by Sir E. Clive Bayley on his No. 20 as a rude imitation of *adal*, ‘just [weight or value]’) that appears in the same position on others of these coins, and resembles a crescent moon on the top of a short staff with a cross-handle. These points of similarity suggest that possibly Sir E. Clive Bayley's Nos. 25, 26, and 27 (and others) belong really to ‘Syalapati,’ though his name is not on the obverse. And the unmistakable date of 814 on at any rate *Prinsep's Essays*, Pl. xxv. No. 2, further suggests that the figures on Sir E. Clive Bayley's Nos. 7, 8, 9, and 10, should not be read as 707 and 727.—Sir E. Clive Bayley placed ‘Syalapati’ in A.D. 887 to 916; which would agree very satisfactorily with the date of 814 on Prinsep's coin, if we might refer it to the Saka era, with the result of A.D. 891-92. Mr. Thomas (*Jour. R. As. Soc. F. S* Vol. IX. p. 179) placed him about the same time; *vis.* “early in the tenth century.” On the other hand, General Cunningham (*Archaeol. Surv. Ind.* Vol. XIV. p. 45) has placed him rather earlier, about A.D. 800; but he quoted no authority for this. I have not been able to find any other information as to the probable date of ‘Syalapati.’

tion. And, without attempting any full discussion of the matter here, where it would be out of place, I will only bring forward a few points to shew that, at any rate, Sir E. Clive Bayley's interpretation of the dates is quite untenable. Of the coins in question, those that have the clearest dates on them (*id.* Plate vii, Nos. 24 to 27), belong to some unnamed king. They are not attributed to 'Syalapati;' but are considered to be rather more recent. It is admitted, however, that they belong to the same series; and I take them first, because they are so very clear. If we examine them with the help of Sir E. Clive Bayley's Table of Numerals (*id.* Plate vii.), it is evident at once that No. 24 reads, not "802 Gu," but simply "804," with nothing after it; and that Nos. 25, 26, and 27 read, not "812 Gu," but simply "814," again with nothing after it; the figures being, in fact, absolutely identical with those which Sir E. Clive Bayley himself read as simply "814" or Nos. 19 to 23, 29 to 31, and 34. In these instances, the supposed *Gu* is nothing but the sign that makes the difference in these numerals between a 2 and a 4. And Sir E. Clive Bayley's reading further involves the peculiar anomaly that the figures have to be read in one direction, from the rim of the coin, and the supposed *Gu* in the opposite direction, from the inside of the coin; which results in the curious arrangement of "802 ၈၅" and "812 ၈၅." We have here to note that Sir E. Clive Bayley reported (*id.* p. 145 f.) that Mr. Thomas, reading the signs that were supposed to mean *Gu*, *Gup*, and *Gupta*, in the opposite way to that in which he himself read them, read the whole date in one direction, from the inside of the coins, and interpreted all the figures as giving only one uniform and conventional date, *viz.* "Gu 617," denoting the initial date of Sāmanta's dynasty according to the Gupta era. Allowing for the possibility of the first sign being capable of meaning *Gu*, this way of interpreting the figures seems to be equally well borne out by Sir E. Clive Bayley's Table. But the first sign cannot mean *Gu*, and does not mean *Gu*. And a reference to the Table will shew immediately that the figures have to be read, as Sir E. Clive Bayley read them, from the rims of the coins; and that the dates are in reality nothing but 804 and 814, as I have pointed out above. Of the coins of 'Syalapati' himself (Plate i, Nos. 3 to 5, and 7 to 10), No. 7 is read as "707," and Nos. 8, 9, and 10 as "727," without any supposed reference at all to the Gupta era; and these readings are in accordance with the Table of Numerals, if the dates are read from the rim of the coins, like the dates of Nos. 19 to 27, 29 to 31, and 34, referred to above. On the other hand, if we might read the figures on these seven coins from the inside, there appears no particular objection to interpreting them as respectively "808" and "868." There remain Nos. 3, 4, and 5, which are read respectively as "Gupta" with two doubtful figures, "98 Gu," and "99 Gu," meaning (6)98 and (6)99 on the principle of "omitted hundreds." And these, unfortunately, are not so easy to deal with; since,—though the signs that are supposed to mean *Gupta* must be in reality numerals of some kind or another,—there is nothing in Sir E. Clive Bayley's Table, and I can obtain nothing elsewhere, to explain their value as numerals. But, in attempting to find a proper reading of them, we must in the first place notice that the sign which,

on Nos. 4 and 5, Sir E. Clive Bayley interpreted as the figure 9, and entered as such in his Table, occupies exactly the position which is filled in Prinsep's coin No. 1, referred to on page 58 above, note 1, by a symbol resembling a crescent moon on the top of a short staff with a cross-handle; and this suggests that the sign in question is not a figure at all. I give here a reproduction of Sir E. Clive Bayley's representation (*id.* Plate vi. No. 6) of the signs in question, which were supposed by him, and by Mr. Thomas, to represent the word *Gupta*, and were claimed by him (*id.* p. 127) to be "a fair rendering of the usual form of the word." What they really mean, I will not attempt to decide; beyond pointing out that, as I have said above, they may be numerals of some kind or another. But it will be admitted at once, by any qualified palæographer, that they answer in no way whatever to the usual form of the word *Gupta*, and cannot be so interpreted in accordance with any known alphabet; even though we should follow Mr. Thomas (*id.* p. 128) in looking upon them as "a degraded and contracted form of the word," or Sir E. Clive Bayley (*id.* p. 145) in holding them to be "a gross corruption of it." And to these remarks I will only add that, as I have shewn at page 19 ff. above, the very expression *Guptasya kála* or *Gupta-kála* is a purely imaginary one, without any real epigraphical existence; and, therefore, abbreviations of it cannot possibly exist on the Kábul coins, or on any others. As a Postscript to his paper, Sir E. Clive Bayley shortly afterwards issued some remarks on the Twelve-Year Cycle of Jupiter, as used in the grants of the *Mahārājas* Hastin and Samkshóbha. His views on this point, however, were radically vitiated, in the first place, by his following General Cunningham's mistaken assumption that the *samvatsaras* of this cycle always begin and end with the lunisolar years; and, further, by a series of mistakes which it is really difficult to know how to criticise properly. He took the *samvatsara* that is mentioned in the Bhumará pillar inscription, No. 24, page 110, to be Mahā-Mārgasira, instead of Mahā-Māgha, a mistake which threw this record out by two *samvatsaras*. He proved General Cunningham's results to be right only in one instance out of the five, *viz.* in the case of this supposed Mahā-Mārgasira *samvatsara* of the Bhumará record, by himself making them gratuitously wrong, in assuming that General Cunningham's epoch for the era was A.D. 107-68, instead of A.D. 166-67. And he entirely overlooked the fact that, as there are ordinarily twelve years in each cycle, and as his own proposed epoch was exactly twenty-four years later than that proposed by General Cunningham, his own results could be neither any more nor any less correct than General Cunningham's under ordinary circumstances; but would, in the particular case, be less correct than General Cunningham's, because, by General Cunningham's Table, which he accepted as correct, there was an expunction of a *samvatsara* between A.D. 394 and 395, which, while it did not affect General Cunningham's results, did affect his own, in making Gupta-Samvat 209 coincide with the Mahā-Kārttika *samvatsara*, instead of Mahā-Āshvayuja (for which, by the way, Sir E. Clive Bayley again wrote Mahā-Mārgasira) as recorded in the grant itself, No. 25, page 112. In fact, a full examination of the original



Gu-pta.

paper and its Postscript, will shew that, for the proposed epoch of A.D. 190, there are absolutely no grounds whatever; and that the theory has no importance at all, except in introducing one of the side-issues which, endorsed by a name that carries authority, have to be disposed of, before any settlement of the main question will be accepted as final by general readers.

In 1883, **General Cunningham** published his *Book of Indian Eras*, in which he recast, with some additions, his treatise on the Gupta era and the Twelve-year Cycle of Jupiter, that had appeared in the *Archæol. Surv. Ind.* Vol. X. p. 111 ff.; and with the same results as on the former occasion. He admitted (*id.* p. x.) that the question of the Gupta era had still not been quite finally settled. But, of the two dates, A.D. 167-68 and 262-63, to which his investigations seemed to limit him for the commencement of the era, he still (*id.* p. 57) much preferred the earlier date, both as contrasted specially with A.D. 262, and also as having (*id.* p. 58) "a better claim for acceptance than any other that has yet been proposed." And, accordingly, in the column for the Gupta era in his Table XVII., we find (*id.* p. 142) the epoch entered as A.D. 166-67, and the commencement as A.D. 167-68. The *samvatsaras* of the Twelve-year Cycle of Jupiter are shewn in another column of the same Table; and, from his detailed remarks on this cycle (*id.* p. 26 ff.), we find that his method of determining the *samvatsaras* was the same as that applied on the previous occasion. In respect of the Valabhi era, he still held (*id.* pp. 53, 63) that the Verāwal inscription of Valabhi-Samvat 945 proves that A.D. 319 was its commencement; not its epoch. And he also (*id.* p. 50) seems to indicate very clearly that, in his opinion, the scheme of the years of this era was identical with that of the years of the southern Vikrama era, commencing with the first day of the bright fortnight of the month Kārttika (October-November). He also held (*id.* p. 57) "that the era used by the Valabhi kings "was that of the Guptas, seems to be almost certain; as the *Śendapati* Bhaṭārka, the founder "of the Valabhi dynasty, is said," in the supposed tradition of the bards of Kāthiāwād, "to have been the governor of Surāshṭra during the last two years of Skandagupta's reign." And he suggested (*id.* p. 53) that it is to this use by the Valabhi family, of the Gupta era of A.D. 166-67, instead of the Valabhi era itself, that we must attribute all the existing confusion. Of the new points brought forward on this occasion, the most important is (*id.* pp. x f., 47 ff., 58) the reference to the Dhiniki copper-plate grant of king Jāikadēva of Saurāshṭra, published by Dr. Bühler in the *Ind. Ant.* Vol. XII. p. 151. This grant is dated in Vikrama-Samvat 794, equivalent to A.D. 736-37; and, on the assumption that it is genuine, and that this Jāikadēva is identical with the Jāinka of the Mōrbi grant, the date of which, (Gupta)-Samvat 585 expired, by General Cunningham's view would represent A.D. 751-52, the synchronism established by the two grants would, of course, lend strong support to his theory. Upon a full examination, however, of the details of the date, which from the first evidently contained elements of doubt, I think that this Dhiniki

grant must certainly be rejected as spurious.¹ If not so, then it can only be held that Jāiṅka and Jāikadēva were distinct and separate persons. Under any circumstances, this grant is of no use in connection with the question of the Gupta era.

¹ In this grant, the date (from the published lithograph; *Ind. Ant.* Vol. XII. p. 155, and Plate, line 1 ff.) runs—*Vikrama-samvatsara-satshu saplasu chatur-navaty-adhikēshu-ankatah 974 Kārttikamś-āpara-pakshē amāc:śyāyām Ādityavārhē Jyēshthā-nakshatrē ravigrāhana-parvāni asyām samvatsara-māsa-paksha-divasa-pūrvayām tithēv-ady-ēha Bhūmilikāyām &c.*—“in seven centuries, increased by ninety-four, of the years of Vikrama, (or) in figures, 974 [the interpretation of the figures, however, with the exception of the 4, depends purely on the preceding expression in words, the first two of them present anything but the appearance of 7 and 9]; in the latter fortnight of the month Kārttika; on the new-moon *tithi*; on Sunday; under the Jyēshthā *nakshatra*; on the occasion of an eclipse of the sun; on this lunar day, (specified) as above by the year, and month, and fortnight, and (solar) day; to-day; here, at Bhūmilikā,” &c.—This gives us for calculation, Vikrama-Samvat 794, current according to the literal meaning of the text; the month Kārttika (October-November); the second, and as shewn by the following mention of the new-moon day and a solar eclipse, the dark fortnight; the new-moon *tithi*; Sunday; an eclipse of the sun, and the Jyēshthā *nakshatra* or lunar mansion. And, as the details of the inscription connect it specifically with Saurāshtra or Kāthiāwād, we have to understand that the Vikrama year quoted is the southern Vikrama year, commencing with Kārttika śukla 1, and having the *Amānta* southern arrangement of the months (see Table III., page 71 below), in which the second fortnight of each month is the dark fortnight. This is, in fact, proved by the record itself, in allotting to the second fortnight of the month the new-moon *tithi*, which of course belongs to the dark fortnight. And, Mr. Sh. B. Dikshit tells me, it is also shewn by the mention of the Jyēshthā *nakshatra*, which can never occur on the new-moon *tithi* of the *Pūrnimānta* northern Kārttika.—As belonging to southern Vikrama-Samvat 794, the given *tithi* belonged, according to the Tables, to Śāka-Samvat 659, expired; and, if it belonged to southern Vikrama-Samvat 795, it would belong to Śāka-Samvat 660, expired. With the basis of these two Śāka years, taken as expired, Mr. Sh. B. Dikshit gives me the following English equivalents of the recorded date;—for Vikrama-Samvat 794, Monday, the 28th October, A.D. 737, when there was the Anurādhā *nakshatra*, and most probably no eclipse of the sun (none, at least, is recorded in *Indian Eras*, p. 211);—and for Vikrama-Samvat 795, Sunday, the 16th November, A.D. 738, when there was the Jyēshthā *nakshatra*; but there cannot have been an eclipse of the sun, since there was one on the preceding new-moon *tithi*, on Friday, the 17th October, A.D. 738, or, by the English Tables (*Indian Eras*, p. 211) Saturday, the 18th October (the difference in the day is because the conjunction of the sun and the moon occurred late towards sunrise, and, for the same reason, the eclipse was not visible in India). This, of course, was the new-moon *tithi* of the *Pūrnimānta* northern Kārttika that fell in A.D. 738; but the supposition that this is the day intended, is barred by the facts that I have mentioned above, which prevent our understanding that the month recorded is the *Pūrnimānta* northern month at all, and also by the fact, ascertained by Mr. Sh. B. Dikshit, that on the 17th October, A.D. 738, the *nakshatras* were Svāti and Visākhā. To complete the details, I would add that he finds that the English equivalent of the new-moon *tithi* of the *Pūrnimānta* northern Kārttika, which fell in A.D. 737, was Saturday, the 28th September, A.D. 737, when the *nakshatras* were Chitrā and Svāti, and there was no solar eclipse.—The only English date, therefore, which at all answers to the record, is Sunday, the 16th November, A.D. 738; and this is the date that was accepted by Dr. Bühler, in publishing the inscription, on calculations made by Prof. Jacobi. In order to arrive at it, however, he translated the record as meaning Vikrama-Samvat 794 expired and 795 current. And in dealing with the eclipse, which, according to the same *Amānta* reckoning, occurred one lunation earlier, on the new-moon *tithi* of the preceding month Āśvina, he arrived at the conclusions, that the

In 1884, Dr. R. G. Bhandarkar issued a note on the question in his *Early History of the Dekkan*, Appendix A. p. 97 ff.; and announced his acceptance of the theory of A.D.

grant was actually made on the new-moon *tithi* of Āśvina, because, though the eclipse was not visible, yet the occurrence of it was known, and therefore the occasion was one of special merit; but that the actual drafting of the charter was done a month later, on the new-moon *tithi* of Kārttika, and the person who drafted it was careless, and omitted to draw a distinction between the two occasions.—This date has also been discussed by Gen. Cunningham, in his *Indian Eras*, p. 48 f. His conclusions were, that the date belongs to Vikrama-Saṃvat 794, not 795; but that the eclipse intended really is that of the (17th or) 18th October, A.D. 738. In order, however, to arrive at these conflicting results, he assumed that the year commenced, not with the month Kārttika, but with the month Mārgaśr̥ṣha (November-December), in accordance with a custom which Alberŭnfi tells us, was current among the people of Sindh and Kanauj and other localities, and had been followed at Multān up to a few years before his own time. By this arrangement, of course, the month Kārttika of Vikrama-Saṃvat 794 would belong to the end of the year, and would therefore fall in A.D. 738, not 737. But, by the southern reckoning, the new-moon day of Kārttika in A.D. 738 would be the 16th November, which was not the day of the eclipse. Accordingly, there remained something still to be explained; and Gen. Cunningham proposed to complete the arrangement by reading Āśvina, instead of Kārttika; which would agree with the real eclipse-day, viz. the (17th or) 18th October, A.D. 738. "But, as that day was a Saturday, a very inauspicious day, the writing of the grant was probably made on the following day, or Sunday, which was the first day of Kārttika; and this might have led to the substitution of the name of Kārttika, for that of Āśvina, as the actual day of the eclipse." There was, really, no reason at all for proposing this alteration of the text; for, from the localities mentioned by Alberŭnfi, a year commencing with Mārgaśr̥ṣha could only be coupled with the *Pārnimānīa* northern arrangement of the months; and, by that arrangement, the 17th October, A.D. 738, on which day, as we have seen, the eclipse occurred for India, actually was the new-moon day of Kārttika. The *Pārnimānīa* northern arrangement, however, is barred in the present case by the points to which I have drawn attention above.—Gen. Cunningham's proposals, therefore, will not do, Nor will Dr. Bühler's interpretation of the date. For, though it remains to be finally decided whether the given date in the southern Vikrama-Saṃvat 794, current, or expired, belongs to Śaka-Saṃvat 659 expired, or to 660 expired, yet the eclipse selected by him, as by General Cunningham, was not visible in India, and the assumption that it is the one referred to, also entails a greater variation between the facts and the recorded statements than could possibly occur in a genuine charter.—I confess that from the first, I have thought that the Dhiniki grant is not genuine; partly from the type of the Dēvanāgarī characters used in it, which, though they present some apparently antique characteristic, are much inferior to those used in certain early palm-leaf MSS., and are also rude, even as compared with the characters of the Sāmānāḍ grant of the Rāshtrakūṭa king Dantidurga, of Śaka-Saṃvat 675 expired (*Ind. Ant.* Vol. XI. p. 108 ff. and Plate), which belongs to just about the alleged period; and partly from its giving so much earlier an instance than can be found anywhere else, of the use of the name of Vikrama in connection with the era. My impression has been that the grant was made spurious by substituting the word Vikrama for Valabhī. This view, I find, cannot be upheld; as the recorded details are not correct for Valabhī-Saṃvat 794 (A.D. 1113-14), or a year before or after. But, that the grant really is spurious, is, I think, now certain, from all the results that I have recited above. And judging by the characters, I should be inclined to refer the fabrication of it to about the eleventh or twelfth century A.D. As the Jyēṣṭhā *nakṣatra* appears to occur always on, or within two days after, the new-moon *tithi* of Kārttika, this detail was probably selected as a fairly safe one; the others being purely fictitious.

318-19 for the epoch of the Gupta era.¹ He held (*id.* p. 97) that Albérûnt's statement regarding the era dating from the extermination of the Guptas, was to be attributed to nothing but the fact that, as in the case also of the Śaka era, the Hindus had repeated to him a mistaken tradition; and that the only reasonable course was, while accepting his initial date for the era, to reject his explanation of the circumstances under which it was established; and he held (*id.* p. 98) that the fact that this era came to be known in later times by the name of the Valabhī era, was due only to its having been introduced into Saurāshtra by the Valabhī family, who were originally dependents of the Guptas, and the dates in whose grants could, at any rate, plainly not be referred to the rise of the family under the *Sēndapati* Bhaṭārka. The principal tests applied by him were, the record of the week-day in the Êraṅ pillar inscription of Budhagupta; and the names of the *samvatsaras* of the Twelve-year Cycle of Jupiter, as recorded in the grants of the *Mahārājas* Hastin and Samkshōbha. In respect of the Êraṅ record, he announced (*id.* p. 99) that Prof. K. L. Chhatre had found that it was correct for Śaka-Samvat 406, as an expired year,² and equivalent to A.D. 484-85, *i.e.* for the Śaka year for which it should be correct according to the initial date given by Albérûnt; and his grounds so far were correct. In respect, however, of the Twelve-year Cycle of Jupiter (*id.* p. 99) he went quite astray; partly through accepting the view that the *samvatsaras* of the cycle begin and end with the luni-solar years; partly through assuming, evidently in order to apply General Cunningham's Tables of the *samvatsaras*, that the Gupta dates denoted expired years, with current *samvatsaras*, which led to the result that Gupta-Samvat 156 should be the Mahā-Chaitra *samvatsara*, instead of Mahā-Vaiśākha as recorded; and partly through his acceptance of General Cunningham's alteration of the date of No. 22, page 100, from Gupta-Samvat 163 to 173. In the course of the arguments which occupy the rest of his paper, he suggested that the *T'u-lu-p'o-po-tu* of Hiuen Tsiang was Dhruvasēna II, of Valabhī. But on this point it is hardly possible to endorse any part of his statement (*id.* p. 100) that "nothing important is involved in the suffix *bhaṭa*. It was a mere title or honorific termination, "as *pant* and *rdv* are among us, the Marāṭhās. *Sēna*, *simha*, and *bhaṭa* were the Valabhī honorific endings; and they could be used promiscuously. The king spoken of in "the plates as Dhruvasimha, may have been called Dhruvabhaṭa by ordinary people, from "whom Hiuen Tsiang must have got the name." But the name of Dhruvasimha does not

¹ He seems to quote A.D. 319-20 as the epoch (*eg.* p. 99, line 15). But, since he treated the Gupta years as expired years, the epoch that he apparently proved is A.D. 318-19.

² It was from this that he inferred that the Gupta-Samvat 165 of the record, was itself an expired year. But this does not follow at all. The equation between the Gupta date and the corresponding English date, is not intrinsically dependent on the Śaka date at all; only, in using Hindu Tables, we have to arrive at it through a Śaka year, and to use as the basis of the calculation, the last Śaka year expired before the current Śaka year corresponding to Gupta-Samvat 165 current.—A most curious confusion between current and expired years of the Śaka era runs through his remarks. Thus though quite rightly taking Śaka Samvat 406 expired to be equivalent to A.D. 484-85, with a difference of 78-79, he also, with the same difference, took, *eg.*, A.D. 511-12 as the equivalent of Śaka Samvat 433 current.

occur at all in any of the numerous Valabhi grants that have come to light; nor does any one of them furnish the slightest grounds for the assertion that there was ever any confusion between the terminations *sēna*, *simha*, and *bhaṣa*. And, though Dr. R. G. Bhandarkar pointed out that Hiuen Tsiang seems to be referring to more than one king of Valabhi, whom he held to be the two brothers Dharasēna III. and Dhruvasēna II., yet I cannot find any authority, either in M. Stanislas Julien's translation, or in Mr. Beal's, for his assertion that Hiuen Tsiang was speaking of only two kings, and that it was the younger of them whom he denoted by the name of *T'u-lu-p'o-po-lu*. This, however, as I have indicated at page 40f. above, is a point which cannot be finally cleared up, until we have some more explicit and reliable exposition of the words actually used by Hiuen Tsiang.

And finally, in 1885, in the *Centenary Review* of the Asiatic Society of Bengal from 1784 to 1883, Dr. A. F. R. Hoernle, after a brief résumé of the results of the work of preceding investigators, arrived at the opinion (*id.* Part II. p. 111) that "the terminal "date," A.D. 319, "of the Gupta empire, as determined by Mr. Thomas, may now be considered as one of those great historical landmarks, the truth of which is admittedly no "more open to question;" and (*id.* 113) that General Cunningham's theory of A.D. 166-67 for the epoch¹ of the Gupta era, "has every prospect of ultimately meeting with universal assent, and being the final verdict of the historic researches regarding the Gupta "dynasty."

The Mandasôr Inscription of Málava-Sarivât 529.

The summary that I have given above will shew sufficiently well the curious ingenuity that was displayed from time to time, in aiming at any settlement of the question rather than the correct one, and also the insufficiency of the arguments used in support of the true solution, even by those who perceived it.

But of course it may be claimed that, as long as M. Reinaud's translation of the statement regarding the circumstances under which the era of A.D. 319-20 or thereabouts was established, remained without correction, there was something to be said from the point of view that we had to deal with a mistake made by Albêrûnî, lying in a confusion between a true Gupta era, anterior to A.D. 319, used by the Early Gupta kings themselves, and another Gupta era, or more properly a Valabhi era, with an epoch of A.D. 319-20 or thereabouts, established, whether used or not, by some member of the Valabhi family: and that he was right in respect of the historical event, from which, as he appeared to assert, this latter era took its origin. And, in default of definite evidence, settling the question one way or the other, perhaps the strongest argument against the views held by Mr. Thomas, General Cunningham, and Sir E. Clive Bayley, was to be found in the fol-

¹ Dr. Hoernle called A.D. 166 the initial year of the era; but this is not an exact representation of Gen. Cunningham's results.

lowing anomalous position, which had occasionally been noticed more or less directly, but had never been disposed of. It was held by all that the Valabhi family came immediately after the Guptas. It was also held that in A.D. 318 or 319, some member of this family founded the city of Valabhi, and, in commemoration partly of that event, and partly of the Gupta rule having then ceased and the power having passed into his own hands, established the Valabhi era dating from then. And yet, — as is proved by, amongst other things, the fact that Bhatârka, the founder of the family, came only one generation before the year 207, the earliest date that we have in the era used in their own charters, — the founder of this era, and his successors, did not allow this era of their own, established under such memorable circumstances, to supersede the Gupta era, but continued the use of the Gupta era for, in accordance with the three earlier starting-points given on page 32 f. above, respectively 205, 294, and 318 years at least, (as is shown by the Aññā grant of Śīlāditya VII., dated in the year 447), after the establishment of their own era! This surely involves an improbability far greater than any other, of whatever kind, that can be imagined in connection with the whole subject.

In order to arrive at any prospect of a final settlement of the question, what was wanted was a date for one of the Early Gupta kings, recorded in some era, capable of identification, other than that which was specially used by them in their own inscriptions. This has now, at length, been found in my new **Mandasôr inscription** which composed and engraved when the year 529 had expired from the tribal constitution of the Málava. It gives us, through his feudatory Bandhuvatman, the date of the year 493, expired, of the same era, for Kumâragupta.

This was not the first instance that had been obtained of the use of this era which may for convenience be called the Málava era. For, it is obviously identical with the era which is alluded to in the Kanawā inscription¹ dated when the 525th year of the Málava lords had expired; and is also mentioned, under the Gupta name of the Málava-kāla, i.e. 'the Málava era,' or 'the time of the Málavas,' in a fragmentary inscription at 'Gyâraspur' or 'Gyârispur' in Central India dated when the 930th year had expired.² But

¹ Edited by Dr. Kielhorn, in *Ind. Ant.* Vol. XIII p. 162 ff. The date from the published text p. 164 f., line 14 f) runs—*samvatsara-tatara = sūtan 50-pāhāḥ navasv 77, itāh = aptabhya = Mālavā-śānām mandīram Dhurjateh kṛtam,*—'in the year that is denoted by seven hundred and ninety-five of the Málava lords, (this) temple of (the god) Dhurjati has been made.'

² *Archæol. Surv. Ind.* Vol. X p. 33 f., and Plate xi. The date, part of which is broken away, (from the Plate runs — *Mālava-kālāch = chharadām śat-trimsat-samyutīshv = atītīshu navasv 525,*—'when nine centuries of autumns, paired with thirty-six, have gone by, from (the commencement of) the Málava era (or, from the time of the Málavas)'.—The counting of the era by autumns is followed also in line 21 of the Mandasôr inscription of Yasôdharman and Vishnouvardhana, of Málava-Samvat 589 expired, No. 35, page 150. And it is worth noting, as being one of the points which identify the Málava era with the Vikrama era. It can hardly be doubted, that the

though, in commenting on this latter inscription, General Cunningham expressed the opinion¹ that this Málava era must be the same as the era of Vikramádiya of Ujjain, commencing in B. C. 57, this point has not hitherto been capable of proof, for the reason that neither of these two dates gave sufficient details for actual computation, or any other available grounds for historical identification. Nor does the Mandasôr inscription, now brought to notice, furnish any details for calculation. But, in its mention of Kumáragupta, it answers the purpose equally well.

Turning to the Gupta inscriptions and coins, the earliest and latest dates that we have for Kumáragupta, are, respectively, Gupta-Samvat 96 and 130 odd. The first is established by his well-known Bilsad pillar inscription, No. 10, page 42, and the latter, by one of General Cunningham's coins.² Last, however, the coin-date should be looked upon as at all doubtful, we must note also his Mankuwâr inscription, No. 11, page 45, dated Gupta-Samvat 129. And, of these extreme dates, we may take Gupta-Samvat 113 as the mean.

Applying this mean year to the various theories regarding the epoch of the Gupta era, it represents—(1) according to Mr. Thomas, A. D. 190-91; (2) according to General Cunningham, A. D. 270-80, (3) according to Sir E. Clive Bayley, A. D. 303-304; and (4) according to my own view, A. D. 432-33.

Next, applying to these figures the date of Málava-Samvat 493 expired, recorded for Kumáragupta in the inscription under notice, we find that the initial point of the Málava era must be within a few years on either side of—(1) B. C. 301; (2) B. C. 214; (3) B. C. 100; and (4) B. C. 61-60.

The first three results, however, each entail the supposition of a brand-new era, hitherto unheard-of, and entirely unexpected. At the same time, as regards the second possible result of about B. C. 214, we must not overlook the existence of certain coins, found in large numbers at Nâgar in the north of Málwa, about forty-five miles north of Kôta, and originally brought to notice by Mr. Carlleyle,³ which have on them the legend *Málavânâma jayah*, "the victory of the Málavas," in characters ranging, in General Cunningham's opinion, "from perhaps B. C. 250 to A. D. 250." These coins shew that the Málavas existed, as a recognised and important clan, long before the time when, as I consider, their "tribal

original scheme of the Vikrama years is the one commencing with the first day of the bright fortnight of Kârttika (October-November). And Kârttika is still the second month in the Hindu autumn, according to the usual division of the six seasons. It seems, however, to be more properly the first autumn month, according to the true southern division of the seasons. And it appears also to have been the first month of a season, when the year was divided, in ancient times, into only three seasons.

¹ *Archæol. Surv. Ind.* Vol. X. p. 34.

² *id.* Vol. IX. p. 24, and Plate v. No. 7.

id. Vol. VI. pp. 165 f., and 174 ff. see also *id.* Vol. XIV. p. 149 ff., and Pl. xxxi. Nos. 19 to 25

constitution," which led to the establishment of their era, took place; and so also, in the other direction, does the mention of them in the Allahâbâd pillar inscription, among the tribes subjugated by Samudragupta, shew that, down to his time at least, they maintained their tribal constitution and importance. And, if we were compelled to have recourse to a new era, these coins might justifiably induce us to select, as its epoch, B.C. 223, the date fixed by General Cunningham for the death of Aśoka;¹ which would make the date of Mâlava-Samvat 493 correspond with A.D. 270, or well on into the first decade of Kumâragupta's reign according to General Cunningham's theory. But this entails, as I have said, the supposition of the existence of an era, of which not the slightest indication has ever yet been afforded by the very numerous inscriptions that have now been examined from all parts of the country; and this is an expedient that must by all possible means be avoided. And, further, it forces the Kaṇaswa inscription of Mâlava-Samvat 795, and the 'Gyâraspur' inscription of Mâlava-Samvat 936, back to respectively A.D. 572 and 713, periods to which, from their alphabets, they cannot possibly belong. And thus,—since, within certain limits, palæographical evidence must be followed,—it creates a palæographical difficulty that is insuperable. So also does the third result, to practically the same extent; and the first, to a still more marked degree.

The fourth result, on the contrary, satisfies all the palæographical requirements of the case. And it brings us so very close to B.C. 57, the commencement of the well-known Vikrama era,—which, by the tradition of later times, is closely connected with the country of the Mâlavas, through the name of its supposed founder, king Vikramāditya, whose capital, Ujjain, was the principal city in Mâlwa,—that we are compelled to find in it the solution of the question, and to adjust the equation of the dates thus,—Gupta-Samvat 113 (the mean date for Kumâragupta) + A.D. 319-20 = A.D. 432-33, and Mâlava-Samvat 493 — B.C. 57-56 = A.D. 436-37; which, of course, falls well within the seventeen years of Kumâragupta's reign, remaining after his mean date.

My new **Mandasôr inscription, therefore, proves** — (1) that any statement by Albêrûni that the Early Gupta power came to an end in or about A.D. 319, must certainly be wrong;—(2) that, on the contrary, Kumâragupta's dynastic dates,—and, with them, those of his father Chandragupta II., and his son Skandagupta, which belong undeniably to the same series; and also any others which can be shewn to run uniformly with them,—must be referred to the epoch of A.D. 319-20, or thereabouts, brought to notice by Albêrûni and substantiated by the Verâwal inscription of Valabhi-Samvat 945:—and (3) incidentally, that, under another name, connecting it with the Mâlava tribe, the Vikrama era did undoubtedly exist anterior to A.D. 544, which, as we have seen, at page 55 above, was held by Mr. Fergusson to be the year in which it was invented. These results are, of course, independent of the question whether the Early Guptas established an era of their own, with the above-mentioned epoch, or whether they only adopted the era of some other dynasty.

The Determination of the Exact Epoch of the Era.

I have shewn, so far, that the Early Gupta dates, and, with them, any others that can be proved to belong to the same uniform series, are to be referred to the epoch of A.D. 319-20, or thereabouts, brought to notice by Albérûnî and substantiated by the Verāwal inscription of Valabhi-Saṃvat 945.

It now remains to be shewn why, out of the three possible epochs of A.D. 318-19, 319-20, and 320-21, current, which appear, at first sight, to be deducible from Albérûnî's statements, **we have to select, as the true and exact epoch, that of A.D. 319-20,** equivalent to Śāka-Saṃvat 241 expired.

This point is one that can be settled only by accurate calculations of the recorded dates, explained in detail, so that it may be seen that the process applied is satisfactory, and that the inferences drawn are correct. And, as a preliminary matter, we must determine what was the nature of the years of the Gupta-Valabhi era.

The Scheme of the Gupta-Valabhi Year.

Bearing in mind that, in all cases in which the notation and computation of *tithis* or lunar days are concerned, as also of solar days connected with lunar months, the years of the Kaliyuga era¹ and of the northern Vikrama era have to be treated as commencing, like the years of the Śāka era, with the first day of the bright fortnight of the month Chaitra (March-April); and also that the decision as to the order of the dark and bright lunar fortnights of the months must of necessity go with the decision as to the general northern or southern nature of the era and its years, since we cannot have a northern year coupled with the southern arrangement of the fortnights, or a southern year coupled with the northern arrangement,—the question now before us is, whether the years of the Gupta-Valabhi era had a distinct scheme and initial day of their own, or whether they followed the scheme and initial day of the years of the Śāka era, according to either the northern or the southern arrangement, or the scheme and initial day of the years of the southern Vikrama era.

¹ This era is also of extremely exceptional use in epigraphical records. The only instances that I can quote are (1) the Aihole inscription of the Western Chalukya king Pulikēsin II. (*Ind. Ant.* Vol. VIII. p. 237 ff.), which is dated when three thousand seven hundred and thirty-five years had elapsed from the Bhārata war, supplemented by the statement that, at the same time, five hundred and fifty-six years of the Śāka kings also had gone by, in (their own era as a sub-division of) the Kali age, the figures of which are marked by those of the Bhārata war; and (2) some of the inscriptions of the Kādambas of Goa, ranging from A.D. 1167 to 1247 (*Four. Bo. Br. As. Soc.* Vol. IX. pp. 241 f., 262 ff., and *Ind. Ant.* Vol. XIV. p. 288 ff.), which, for some capricious reason, are dated in the Kaliyuga, without any reference to the Śāka era at all, though other records of the same family (see my *Dynasties of the Kanarese Districts*, p. 90 ff.) are dated in the Śāka era, and in that alone.

A reference to Table III. on page 71 below, will explain at once the difference in the schemes of these years, and the necessity for determining the question that we have under consideration.¹

The Śāka years of both Northern and Southern India commence with the first day of the bright fortnight of Chaitra, immediately after the new-moon conjunction. But, in the scheme of the year, there is the important difference that, in the northern arrangement, the dark fortnight of each month precedes the bright;² whereas in the southern year, it is the bright fortnight that stands first. Popularly, and in *Pañchāngs* or Hindu almanacs, the northern arrangement is called *Pūrṇimānta*, or 'ending with the full-moon,' and the southern arrangement is called *Amānta*, or 'ending with the conjunction (of the sun and the moon), i.e. with the new-moon,' and these terms will be found very convenient for practical use. The result of this difference of arrangement, is, that, in the northern year, the dark fortnight of Chaitra stands at the end of the year, instead of in the place of the second fortnight, which it occupies in the southern year, and that the dark half of the southern Chaitra is the same lunar period as the dark half of the northern Vasākha, and so on all through the year. For dates in the bright fortnights of Śāka years, it obviously is immaterial whether we follow the northern or the southern scheme. But for dates in the dark fortnights, it is as obviously essential, in order to compute them correctly, that we should know exactly which scheme they conform to, since, for instance, the thirteenth lunar or solar day of the dark fortnight of the lunar month Āshādha represents, if treated as a southern date, an English day later by one complete lunation, or practically a month, than the English equivalent of it as a northern date.

In the southern Vikrama year, the arrangement of the fortnight is the regular *Amānta* southern arrangement. But the year commences seven lunations later than the equivalent Śāka year, and corresponding northern Vikrama year,³ viz. with the first day of the bright fortnight of the month Kārttika (October-November). Here, again, for purposes of computation, any date in a southern Vikrama year has to be treated as the same date in the equivalent Śāka year. And a reference to the right-hand column in Table III. on page 71, will shew at once the way in which the years overlap, and will explain fully the

¹ Contrary to the hitherto prevalent custom, I enter the current Hindu years in the Table. It is, under any circumstances, quite illogical to speak of, for instance, "Chaitra sukla 1 of, in, or belonging to, Śāka-Samvat 500," when the Śāka year is intended as an expired year. And it is particularly necessary to use the current Hindu years, when the object is to compare them with years of the Christian era, of which the current years are always quoted, leaving it to any one who has to calculate a date by Hindu Tables, to take the preceding expired year as the basis of the calculation.

² See Beal's *Buddh. Rec. West. World*, Vol. I, p. 71, where Hsien Tsiang's account shews that the arrangement was just the same twelve centuries ago.

³ This is the customary way of putting it. But the more correct statement would be, that the Vikrama year of Northern India now commences, with the equivalent Śāka year, seven lunations earlier than the corresponding southern Vikrama year (see page 66 above, note 2.)

TABLE III.

Comparative Table of the Vikrama, Śaka, and Gupta-Valabhi Years.

Northern India. <i>Purnamānta.</i>	Months and Fortnights.	Southern India. <i>Amānta</i>	
Śaka-Samvat 1186, Vikrama-Samvat 1321, Gupta-Valabhi-Samvat 944, A.D. 1263-64.	Chaitra { bright } Chaitra	Vikrama-Samvat 1320 A.D. 1262-63.	
	Vaisākha { dark } Vaisākha		
	Jyēshtha { bright } Jyēshtha		
	Ashādha { dark } Ashādha		
	Śrāvana { bright } Śrāvana		
	Bhādrapada { dark } Bhādrapada		
	Āsвина { bright } Āsвина		Śaka-Samvat 1186, A.D. 1263-64.
	Kārttika { dark } Kārttika		
	Mārgaśrīṣa { bright } Mārgaśrīṣa		
	Pausha { dark } Pausha		
	Māgha { bright } Māgha		
	Phālguna { dark } Phālguna		
	Chaitra { bright } Chaitra		Vikrama-Samvat 1321, A.D. 1263-64.
	Vaisākha { dark } Vaisākha		
Jyēshtha { bright } Jyēshtha			
Ashādha { dark } Ashādha	<i>Verulam Inscription, Ashādha; the dark fortnight, the 13th solar day, Sunday.</i>		
Śrāvana { bright } Śrāvana	Śaka-Samvat 1187, Vikrama-Samvat 1322, Gupta-Valabhi-Samvat 945, A.D. 1264-65.		
Bhādrapada { dark } Bhādrapada	Śaka-Samvat 1187, A.D. 1264-65.		
Āsвина { bright } Āsвина	Vikrama-Samvat 1322, A.D. 1264-65.		
Kārttika { dark } Kārttika			
Mārgaśrīṣa { bright } Mārgaśrīṣa			
Pausha { dark } Pausha			
Māgha { bright } Māgha			
Phālguna { dark } Phālguna			
Chaitra { bright } Phālguna			
Chaitra { dark } Phālguna			

necessity of determining the question with which we are concerned. By the epochs of the two eras, the nearest equivalent of, for instance, southern Vikrama-Samvat 1321 current is Śaka-Samvat 1186 current; and this is also its actual equivalent for any date from Kārttika śukla 1 up to Phālguna kṛishṇa 15, both included; but, for any date from the following Chaitra śukla 1 up to Āśvina kṛishṇa 15, both included, the actual equivalent of Vikrama-Samvat 1321 current is the following Śaka-Samvat 1187 current. Consequently, if the Gupta-Valabhi year is to be treated as a southern Vikrama year, any such date as Gupta-Valabhi-Samvat 944, Chaitra śukla 1, up to Āśvina kṛishṇa 15, will give an English equivalent later by twelve complete lunations, or practically a year,¹ or else any such date as Gupta-Valabhi-Samvat 944, Kārttika śukla 1, up to Phālguna kṛishṇa 15, will give an English equivalent earlier by twelve complete lunations, than the English equivalents if the year is to be treated as a Śaka year.

The question, whether by any chance we can be concerned, in the Gupta-Valabhi era, at any period, with the scheme of the southern Vikrama year, is, if possible, still more an essential point, because the dates that we have in the era, under its later name of the Valabhi era, come from Kāthiawād, where, as in the neighbouring provinces of Gujarāt and the Northern Konkan, the national era is the Vikrama era, in the southern arrangement. In those parts there would of course be a tendency, sooner or later, to adapt the original scheme of the Gupta-Valabhi year to the scheme of the years of the local national era. And a distinct instance of this adaptation having been actually made in Gujarāt, is furnished by the Kaira (Khēḍā) grant of Dharasēna IV. of Valabhi, published by Dr. Bühler in the *Ind. Ant.* Vol. XV. p. 335 ff. Its date is the year 330; the "second" month Mārgaśīra (November-December); the bright fortnight; and the second *tithi* or lunar day. And the interest and importance of it result from its shewing that, in that year, there was an intercalation of a month, which, according to this record, was Mārgaśīra or Mārgaśīrsha. Now, allowing for the moment, what I shall shortly prove, as closely as absolute certainty can be obtained, *vis.* that the true original scheme of the Gupta-Valabhi year is the scheme of the northern Śaka year, the month Mārgaśīrsha of this record should belong to Śaka-Samvat 572 current, and should fall in A.D. 649. The detailed consideration of this date, however, at page 93 ff. below, shews that the intercalation in question can only have occurred in A.D. 648, and belonged to Śaka-Samvat 571 current, or, according to the popular usage of Gujarāt, to the southern Vikrama-Samvat 706 current. And, since the localities mentioned in the charter connect it absolutely with a district in Gujarāt, the year 330 of this record must have commenced, like the southern Vikrama-Samvat 706, with the month Kārttika that preceded the true commencement of Gupta-Samvat 330, with Chaitra śukla 1 of Śaka-Samvat 572 current, according to the original scheme of the years of the era. Bearing in mind, however, that this record belongs to Gujarāt, we have

¹ Or, in the case of certain intercalations, later here, and in the other case earlier, by thirteen lunations, or practically a year and a month.

not to seek far for the explanation of this discrepancy. When once the Gupta-Valabhi era had been fairly introduced in Gujarât, the natural tendency, as I have said, would soon be to disregard the original scheme of its years, and to substitute for it the scheme of the southern Vikrama years. Let us assume that this substitution took place in Gupta-Valabhi-Samvat¹ 303, which commenced, approximately, on the 19th March, A.D. 622, about half-way through southern Vikrama-Samvat 679 current. Then, if the change of scheme was effected in the first seven lunations of the Gupta-Valabhi year, the Gujarâtis would make the new year, Gupta-Valabhi-Samvat 304, commence with their own new year, southern Vikrama-Samvat 680, on the next Kârttika śukla 1, or approximately the 12th October, A.D. 622; and Gupta-Valabhi-Samvat 303, as thus adapted and shortened by them, would contain only seven lunations, from Chaitra śukla 1 up to Āśvina kṛishna 15. If, on the other hand, the change was effected in the last five lunations of the Gupta-Valabhi year, when southern Vikrama-Samvat 680 current had already commenced, then the Gujarâtis would defer the commencement of the new year, Gupta-Valabhi-Samvat 304, until the commencement of their own new year, southern Vikrama-Samvat 681, on again the next Kârttika śukla 1, or approximately the 1st October, A.D. 623; and Gupta-Valabhi-Samvat 303, as thus adapted and prolonged, would contain nineteen lunations. The years of the era would, for the future, always commence, in Gujarât, with the years of the southern Vikrama era, on the first day of the bright fortnight of Kârttika. Under the second condition, every subsequent year in Gujarât would commence seven lunations later than it would in Kâthiawâd, as long as the true original reckoning was preserved in the latter country; which was the case up to at least Gupta-Valabhi-Samvat 945. Under the first condition, every subsequent year in Gujarât would commence five lunations earlier than in Kâthiawâd. And the grant of Dharasēna IV., now under notice, shews that this latter was the manner in which the change of scheme, which had already been accomplished, was effected; since this is the only method by which the intercalary Mârgaśirsha of this record can be made to belong to Gupta-Samvat 330, instead of to 329.

The Verâwal inscription, however, of the Chalukya king Arjunadēva, dated Valabhi-Samvat 945, which I have mentioned at page 31 f. above, and the surroundings and full bearings of which will be explained in detail further on, contains such particulars, in the record of its date, as shew that, in it at all events, there is no reference to the scheme of the southern Vikrama year, or even of the southern Śaka year.

But, apart from any particular instances which supply proof by means of the circumstances under which the recorded week-days are found to be correct, there is, as I have said, the general fact that we cannot have either a southern year coupled with

¹ I do not mean to assert that the change took place in this particular year, or even within a few years on either side of it. All that is certain, is, that it took place before Gupta-Valabhi-Samvat 330. And I have used the year 303, instead of 300 in round numbers, for purposes of illustration, only in order to avoid a year with an intercalary month.

the *Pārnimānta* northern arrangement of the fortnights of the months, or a northern year coupled with the *Amānta* southern arrangement. And, in proof of this position, I will here adduce some very instructive information gathered from the Nēpāl inscriptions, which were published by Dr. Bhagwanlal Indraji in the *Ind. Ant.* Vol. IX. p. 163 ff.

The earliest eras used in these inscriptions, are the Gupta era, and the era of Harshavardhana of Kanauj. And the recorded dates in them range, respectively, from A.D. 35 to 854, and from A.D. 639 to 758. Soon after that time, these eras were supplanted, in Nēpāl, by the Nēwār¹ era, the epoch of which, according to Mr. Prinsep's statement² that the year 951 ended in A.D. 1831, is A.D. 879-80; and the commencement, A.D. 880-81. Mr. Prinsep also recorded that each year of the era began in October; which is in accordance, broadly, with the information obtained by Dr. Bhagwanlal Indraji, when travelling in Nēpāl, that the initial day of each year is the first day of the bright fortnight of the month Kārttika (October-November).

As regards the origin of the era, the Nēpāl *Vamsāvali*, or List of Kings, states³ that it was established by Jayadēvamalla, of the second Thākuri dynasty of Amśuvarman. But a more important indication of the truth is given by its immediately following statement, that, on the seventh day of the bright fortnight of the month Śrāvāṇa, in the ninth year of the era, coupled with Śaka-Samvat 811 which as an expired year is equivalent to A.D. 889-90, during the joint reign of Jayadēvamalla and his younger brother Ānandamalla, there came from the south a certain Nānyadēva, who conquered the whole of Nēpāl, and established the Karṇāṭaka Dynasty. The truth probably is that Nānyadēva was a minister of Jayadēvamalla, and eventually usurped the sovereignty, which, according to the *Vamsāvali*, remained with his descendants for five generations after him. Whether Nānyadēva really came from the south, it is of course difficult to say. That statement, and the name of his dynasty, may perhaps be only inventions, to account for the nature of the year that was coupled with the new era, which was evidently introduced by him, and not by Jayadēvamalla. But it is plain that, in addition to the establishment of a new era, there was made an important change in the calendar, consisting of the substitution of a foreign Karṇāṭaka year for the year that had hitherto been used in Nēpāl. The available dates do not furnish absolute proof that the initial day of the new year was Kārttika śukla 1. But the *Vamsāvali* gives the following two equations,—under Nānyadēva, as already noted, Nēpāla-Samvat 9 = Śaka-Samvat 811 (expired), with the date of Śrāvāṇa śukla 7; and under Harisinhadēva, No. 1 in the Sūryavamsi Dynasty of Bhātgam, Nēpāla-Samvat 444

¹ Dr. Bhagwanlal Indraji tells me that this word, Nēwār, is a local corruption of 'Nēpāl.'—In the inscriptions, this era, when it is not simply referred to in the usual way by the word *samvat*, is spoken of by the terms *Nēpāla-varsha* (e.g. *Ind. Ant.* Vol. IX. p. 185, line 13 from the bottom), *Nēpāla-samvata* (*id.* p. 191, line 4 from the top), and *Nēpāla-abda* (*id.* p. 192, line 2 from the top).

² *Prinsep's Essays*, Vol. II. Useful Tables, p. 10; ³ *1850 Indian Eras*, p. 74.

³ *Ind. Ant.* Vol. XIII. p. 414.

=Śaka-Saṃvat 1245 (expired),—which, as the difference in the first case is 802 years, and in the second, 801, shew that the scheme of the year differed from that of the Śaka years. And, taking this in connection with the information obtained by Mr. Prinsep and Dr. Bhagwanlal Indraji, and with the fact that all such dates as have been examined tend to support the result, it seems certain that the initial day of each year was Kārttika śukla 1; and it is evident that the year was borrowed from the southern Vikrama year. The question remains as regards the arrangement of the fortnights of the months; and here, though we might most reasonably expect that, so far north as Nēpāl, even a year borrowed from the southern Vikrama year, would be coupled with the *Pūrṇimānta* northern arrangement of the lunar fortnights, yet we find that this distinctly was not the case, but the *Amānta* southern arrangement was preserved. This is proved, in the first instance, by the mention in the inscription of Siddhinishimha, dated Nēpāla-Saṃvat 757, of Śrāvaṇa kṛishna 8 after Śrāvaṇa śukla 12; and still more explicitly by the provision, in the same passage,¹ for performing the *janmāshṭamī-pūjā*, or 'worship on the eighth lunar day which is (the anniversary of) the birth (of Kṛishṇa),' on the eighth *tithi* of the dark fortnight of Śrāvaṇa; for, a comparison of any *Pañchāṅgs* will shew that the festival in question occurs in the dark fortnight of Śrāvaṇa only according to the *Amānta* southern reckoning, but, according to the *Pūrṇimānta* northern reckoning, on the same *tithi* in the dark fortnight of Bhādra-pada. Further, the inscription of Riddhilakshmi gives a date in a dark fortnight, available for calculation. The details² are Nēpāla-Saṃvat 810 current; the month Kārttika; the dark fortnight; the second lunar day; and Sunday. With the epoch of A.D. 879-80, the given *tithi* should fall in A.D. 1689; and, by Prof. K. L. Chhatre's Tables, Mr. Sh. B. Dikshit finds that, by the *Amānta* southern arrangement, it did end on a Sunday, *vis.* the 20th October, A.D. 1689; while, by the *Pūrṇimānta* northern arrangement, it ended on a Friday, *vis.* the 20th September. Also, in connection with the question of the epoch itself being A.D. 879-80, he finds that the given *tithi* did not end on a Sunday in either A.D. 1688 or 1690, by either the *Amānta* or the *Pūrṇimānta* arrangement.³ It is absolutely certain, therefore, that the year which was used in connection with the Nēwār era of Nēpāl, and which had Kārttika śukla 1 for its initial day, was a southern

¹ See *Ind. Ant.* Vol. IX. p. 186, last two lines.

² *Ind. Ant.* Vol. IX. p. 192,—*Nēpāl-dēśē gagana-dharinī-nāga-yuktē kil-Ūrjē māśē-pakṣē vidhu-virahitē su-dvīṣṭyā-tithau śā kṛitvā dēvdayam=api Ravau Riddhilakshmi prasannē chakrē dēśē su-vidhī-viditām Śankarasya pratishṭhām*,—"in the Nēpāl year possessed of the sky (=0), the earth (=1), and the (8) Nāgas; in (the month) Ūrja (*i.e.* Kārttika); in the fortnight which is deprived of the moon; on the excellent second lunar day; on Sunday; having made (this) temple, she, the gracious (and) majestic Riddhilakshmi, made an installation, according to all the proper rites, of (the god) Śankara."—The name of the week-day is overlooked in the published version.

³ The English equivalents for those years, are, by the *Amānta* arrangement, Tuesday, the 30th October, A.D. 1688, and Saturday, the 8th November, A.D. 1690; and, by the *Pūrṇimānta* arrangement, Monday, the 1st October, A.D. 1688, and Thursday, the 9th October, A.D. 1690.

year. On the other hand, when the Népālese abandoned this offshoot of the southern Vikrama era, and introduced the Vikrama era itself from the neighbouring parts of Northern India, they adopted it in its northern variety, with Chaitra śukla 1 as its initial day, and with the *Pārṇimānta* northern arrangement of the fortnights; as is proved by Mr. Sh. B. Dikshit's calculations of the dates in dark fortnights, recorded in the inscription of queen Lalitātrīpurāsundarī.¹ The dates are, Vikrama-Saṁvat 1874, Bhādrapada kṛṣṇa 9, Śukravāra² or Friday; Vikrama-Saṁvat 1875, Mārgaśīrṣa kṛṣṇa 5, Budhavāra or Wednesday; and Vikrama-Saṁvat 1877, Jyēshṭha kṛṣṇa 10, Ravivāra or Sunday. By the *Amānta* southern arrangement, the week-days do not come out right at all. While by the *Pārṇimānta* northern arrangement, the English equivalents are, as required, Friday, the 5th September, A.D. 1817; Wednesday, the 18th November, A.D. 1818; and Sunday, the 7th May, A.D. 1820.

These facts amply establish my position that we cannot have either the *Pārṇimānta* northern arrangement of the fortnights coupled with a southern year and era, or the *Amānta* southern arrangement of the fortnights coupled with a northern year and era. And now I shall bring forward some perfectly conclusive evidence, to prove that the scheme of the months of the Gupta-Valabhī year proper was the regular *Pārṇimānta* northern scheme; and that, therefore, in this era, in its original constitution, we cannot be concerned with any southern reckoning at all.

The Khōh copper-plate grant of the Parivrājaka *Mahārāja* Saṁkshōbha, of the year 209 (A.D. 528-29), No. 25, page 112, is dated "in the enjoyment of sovereignty by the Gupta kings; in the Mahā-Āśvayuja *samvatsara*;" and, as regards other details, in fortunately a double manner. In line 2 f. we have—Chaitra-māsa-śukla-pakṣa-trayō-daśyām (where, in apposition with *trayōdaśyām*, we have to supply *tithau*),—"on the thirteenth *tithi*, or lunar day, of the bright fortnight of the month Chaitra." And at the end, in line 24, in numerical symbols, this date is repeated as—Chaitra di³ 20 7 (where the abbreviation *di* stands for *dina*, *dīnē*, *dīvasa*, or *dīvasē*),—" (the month) Chaitra; the (solar) day 20 (*and*) 7." This double record is explicable only on the understanding that, in the scheme of the months of the Gupta year, the dark fortnights stood first, according

¹ *Ind. Ant.* Vol. IX. p. 193 f.

² The published text has *suklē*, which is obviously a mistake for *sukrē*.

³ In my printed version of this inscription, the second numerical symbol is given as 9, with a reference (page 112, note 4) to a note that it might possibly be 7, 8, or 9. Mr. Sh. B. Dikshit having found by calculation that this *tithi* was the twenty-seventh solar day in the month, I now substitute 7 for 9 (see page 274, note 2).—The point that is proved by this double record had been missed, until I brought it to notice in the *Ind. Ant.* Vol. XVI. p. 145; because Gen. Cunningham, who first brought the inscription to notice, read the first symbol in line 24 as 10, instead of 20, and overlooked the second symbol altogether. He thus obtained "Chaitra, day 10:" and added the remark "this figure should be 13, to agree with the written date given above" [in line 2 f.] (*Archæol. Surv. Ind.* Vol. p. 15). There are, however, distinctly two symbols, meaning 20 and 7; or, together, 27.

to the regular *Pūrṇimānta* northern scheme. By this means only can the thirteenth *tithi*, or lunar day, of the bright fortnight answer to the twenty-seventh solar day of the whole month. A double record of precisely the same kind is given in the Majhgawān grant of the Parivrājaka *Mahārāja* Hastin, of the year 191, No. 23, page 106, in which we have, in line 2,—*Māgha-māsa-bahula-paksha-trīṭhyāyām*.—"on the third *tithi*, or lunar day, of the dark fortnight of the month *Māgha*;" and, in line 21,—*Māgha di 3*,—"Māgha, the (solar) day 3." But, the number of the solar day in this instance being under sixteen, this record is not in itself sufficient to prove the case, one way or the other.¹ What we require is a double date, in which the *tithi* of the fortnight, the number of which cannot exceed fifteen is connected with a solar day, the number of which, exceeding sixteen, shews itself to be referred to the whole month, and not to the fortnight. This we have in the grant of the *Mahārāja* Samkshōbha. And the record proves absolutely that, in the arrangement of the fortnights of the months of the Gupta year, it is the *Pūrṇimānta* northern system that is concerned; and, consequently, the general scheme of the years of the era was not that of any southern year at all.

At present, the Verāwal inscription of Arjunadēva, dated Valabhī-Samvat 945, is the only instance in which the equation of the Gupta-Valabhī era and another era is accompanied by the full details of a month, fortnight, and day.² And the thirteenth solar day in the dark fortnight of *Āshāḍha*, which is mentioned in it, might be the last or the first day of the Gupta-Valabhī year. As a single instance, therefore, it does not help us in any way to fix the initial day of the year.

Consequently, the remaining point,—whether the years of the Gupta-Valabhī era followed in all respects the scheme of the northern Śāka year, or whether they had some distinct initial day of their own,—is one which cannot be absolutely settled, until we obtain, either some more double records like that of the Verāwal inscription, which will

¹ There seemed to be also a double record of the same kind in the Êraṇ pillar inscription of Gopārāja, of the year 191, No. 20, page 91, in which we have, in line 2, *Śrāvāna da di 7*, "(the month) *Śrāvāna*; the dark fortnight; the (solar) day 7;" and, in line 1, apparently *Śrāvāna-bahula-paksha-sap[ṭ]amy[ḍm]* (or *sap[ṭ]am[yḍm]*), "on the seventh *tithi*, or lunar day, of the dark fortnight of (the month) *Śrāvāna*." Mr. Sh. B. Dikshit, however, finds that, in Gupta-Samvat 191, the seventh *tithi* or lunar day of the dark fortnight of *Śrāvāna*, ended on Monday, the 14th June, A.D. 510; and that this was the sixth solar day in the fortnight or month; since, the preceding new-moon *tithi* ended on Tuesday, the 8th June. Accordingly, at the end of line 1, we should perhaps read *sap[ṭ]am[ḍ]*, *sap[ṭ]am[ḍhni]*, or *sap[ṭ]am[ḍ dind]*.

² The only other instance in which the Gupta-Valabhī era is mentioned in direct connection with another era, is Alberūnī's statement (page 30 above), in which Gupta-Valabhī-Samvat 712 is given as equivalent to Vikrama-Samvat 1088, and Śāka-Samvat 953. It cannot be turned to any practical use, in determining the scheme of the year, because he does not give any details of a month, &c.; and because we do not know for certain whether he is referring to the northern or to the southern Vikrama year.

enable us to gradually decrease the limits within which the commencement of the Gupta-Valabhi year is to be placed on the sliding scale of the twelve months; or the entry of an early date, approximating closely to Chaitra śukla 1, followed, in the same record, by a late date, approximating closely to the new-moon of Chaitra, both of them referred to one and the same Gupta-Valabhi year, and the latter of them distinctly connected with an event or ceremony which is specifically said to follow after the event or ceremony with which the former is connected; or the entry of a late date, approximating closely to the new-moon of Chaitra, followed, in the same record, by an early date approximating closely to Chaitra śukla 1, the two of them referred to two consecutive Gupta-Valabhi years, and, in the same way, the latter of them distinctly connected with an event or ceremony which is specifically said to follow the event or ceremony with which the former is connected. And these conditions, of course, are rather difficult of fulfilment.

Meanwhile, I have now made it clear that the original Gupta year was a northern year with the *Pūrṇimānta* northern arrangement of the lunar fortnights; as was, in fact, to be expected in the case of a year used by so essentially a Northern India dynasty as the Early Guptas were. And, further on, I shall shew that the *samvatsaras* of the Twelve-year Cycle of Jupiter, which are quoted in the grants of the *Mahārājas* Hastin and Saṁkshōbha, not only confirm the above results by proving that the details of them cannot be referred to a year commencing with the month Kārttika, but also prove that we cannot be concerned even with a year commencing with the new-moon of the month Mārgaśirsha (November-December), which is mentioned by Alḅérūnī¹ as having been in use, at any rate in connection with the Lōkakāla reckoning, by the people of Sindh, Multān, Kanauj, and other parts, and as having been abandoned at Multān only shortly before his own time. As a matter of fact, a year commencing with Mārgaśirsha, and having the *Pūrṇimānta* northern arrangement of the fortnights, would suit the details of every Gupta-Valabhi date,—including even the Kaira grant of Dharasēna IV. of the year 330 mentioned above, and a Verāwal inscription of Valabhi-Samvat 927 which will be fully exhibited further on,—except one, *vis.* the Majhgawān grant of the *Mahārāja* Hastin of the year 191, which has been referred to above. This being the sole exception, the calculations which determine the commencement and end of the *samvatsara* that is quoted in it, were gone through again and tested with very great care. But the result is that they distinctly bar the use of a year commencing with Mārgaśirsha. And thus,—having no other

¹ *Alḅérūnī's India*, Translation, Vol. II. p. 8 f.—He also, in the same place, mentions a year commencing with the month Bhādrapada (August-September). But, from his statement, it seems to have been confined to the vicinity of Kaśmīr. And, under any circumstances, as Bhādrapada is earlier than Kārttika in the Śāka year, the circumstances which bar a year commencing with Kārttika, still more emphatically bar one commencing with Bhādrapada.

known year of general use to fall back on, except the Śaka year;¹ and giving due consideration to the explicit manner in which Albêrûnî connects the years of the Gupta-Valabhi era with those of the Śaka era by an even number, without any fractions; and having regard also to the fact that any Hindu date has to be converted, for purposes of calculation, into its equivalent Śaka date,—we may accept it as almost certain that, whatever may have been the real historical initial point of the Gupta-Valabhi era, after no great lapse of time the scheme of its years became in all respects identical with the scheme of the Śaka year, with the first day of the bright fortnight of Chaitra as the initial day of each year, and with the *Pūrṇimānta* northern arrangement of the lunar fortnights, in accordance, in both respects, with what seems to have been always the custom of Northern India.²

¹ I have heard from Mr. Vajeshankar Gaurishankar that, in the west of Kāthiāwād, there is current a year commencing with the Āshādha śukla 1 that precedes the Kārttika śukla 1 with which the Vikrama year of the rest of the Province commences. This year is called the HĀlārī year, as belonging to the HĀlār Prānt or Sub-Division of Kāthiāwād. I do not know whether it is coupled with the *Amānta* or with the *Pūrṇimānta* arrangement of the lunar fortnights. But it appears to be of purely local usage; it does not help to reconcile the discrepancy in the results for the dates of the Kaira grant of Dharasēna IV. of the year 330 and the Verāwal inscription of Valabhi-Samvat 927, as compared with the results for all the other dates, and, in order to suit the dates in the Ēran pillar inscription of Budhagupta and other records, it ought to commence with the Āshādha śukla 1 following, not preceding, the Kārttika śukla 1 with which the Vikrama year of the rest of the Province commences. There appear, therefore, no grounds for supposing that this HĀlārī year is any remnant of the Gupta reckoning.

² Evidence is, in fact accumulating that, even in Southern India, or at least in some parts of it, the *Amānta* southern arrangement of the lunar fortnights was not coupled with the Śaka years until a comparatively late period.—One point in favour of this is the Haidarābād (Dekkan) grant of the Western Chalukya king Pulikēśin II., in which the details for computation (*Ind. Ant.* Vol. VI. p. 73, line 11 ff.) are Śaka-Samvat 534 expired, the month Bhādrapada (August-September), the new-moon *tithi* and an eclipse of the sun. I have noticed this date in the *Ind. Ant.* Vol. XVI. p. 109 ff., and I arrived then at the conclusion that the solar eclipse in question is that of the 23rd July, A.D. 613. This, however, was in consequence of a mistake as to the English equivalent of the indicated current Śaka year, due to the manner in which the Tables are arranged for expired years without any distinct intimation to that effect, and (see Appendix I. below) by no means confined to myself. Śaka-Samvat 534 expired, and 535 current, is really equivalent to A.D. 612-13. In this period there was an eclipse of the sun (see *Indian Eras*, p. 210) on the 2nd August, A.D. 612; which was the new-moon *tithi* of Bhādrapada according to the *Pūrṇimānta* northern arrangement. Mr. Sh. B. Dikshit finds, however, by the *Sūrya-Siddhānta*, that the *tithi* ended at 35 *ghaṭṭas*, 46 *palas*; and consequently that the eclipse, occurring in the night, was not visible in India. Accordingly, there being no eclipse of the sun on the given *tithi* in the preceding year, it is doubtful whether the record really refers to the eclipse of the 2nd August, A.D. 612; or whether we have here a genuine instance of a mistake in the year that is quoted, and the eclipse that is really intended is that which occurred, fully visible under very impressive circumstances at the locality, Bādāmi, to which the record refers itself, on the 23rd July, A.D. 613, which date again answers to the new-moon *tithi* of Bhādrapada according to the *Pūrṇimānta* northern arrangement. But the point to which I have to draw attention here, is, that, whichever of these two eclipses we select, the *Pūrṇimānta* northern arrangement of the lunar fort-

The Calculation of Recorded Dates.

Our next step, therefore, will be, to see how far the available Gupta-Valabhī dates, converted into Śaka dates by the addition of two hundred and forty-one years in accordance with Alberdri's most specific statement regarding the equation of the two eras, and treated as northern dates, with the *Pūrnimānta* arrangement of the lunar fortnights, and with Chaitra śukla 1 as the initial day of the year, give satisfactory results; and what uniform equations can be established between, on the one hand, the years of the Gupta-Valabhī era, and, on the other, those of the Śaka and the Christian eras.

The Êraṅ Inscription of the year 165.

The earliest record that furnishes the easy test which is provided by the mention of the name of a week-day, combined with the other necessary details, and the first that was tested for me by Mr. Sh. B. Dikshit, is that given in the Êraṅ pillar inscription

nights has to be applied.—Again, in a grant of the Rāshtrakūta king Gōvinda III., from the Kanarese country, we have for calculation (*Ind. Ant.* Vol. XI. p. 126, line 1 ff.) Śaka-Samvat 726, the Subhānu *samvatsara* of the Sixty-Year Cycle of Jupiter, the month Vaisākha (April-May), the dark fortnight, the fifth *tithi*, and Bṛihaspativāra or Thursday. Whether a literal translation of the text indicates the given Śaka year as current, or as expired, is not quite certain. But correct results can be obtained only by taking it as an expired year. With the basis of Śaka-Samvat 726 expired, the given *tithi*, belonging to Śaka-Samvat 727 current, ended, by the *Amānta* arrangement, on Friday, the 3rd May, A.D. 804; but, by the *Pūrnimānta* arrangement, on Thursday, the 4th April, as required. And this is in accordance with the Northern System of the Sixty-Year Cycle, by which the Subhānu *samvatsara* commenced in Śaka-Samvat 726 current, on the 17th June, A.D. 803, and was followed by the Tārāga *samvatsara* in Śaka-Samvat 727 current, on the 12th June, A.D. 804, so that it was current, as recorded, on the given date. By the Southern System of the cycle, the Subhānu *samvatsara* coincided with Śaka-Samvat 726 current (A.D. 803-804). And for this year, with the basis of Śaka-Samvat 725 expired, the equivalents of the given *tithi* are, by the *Amānta* arrangement, Saturday, the 15th April, A.D. 803, and, by the *Pūrnimānta* arrangement, Friday, the 17th March.—On the other hand, the Sīrūr (Dhārwād District) inscription of the Rāshtrakūta king Amoghavarsha I. gives us for calculation (*Ind. Ant.* Vol. XII. p. 219, line 15 ff.) Śaka-Samvat 788, the Vyaya *samvatsara*, the month Jyēsthā (Maj-June), the new-moon *tithi* Ādityavāra or Sunday, and an eclipse of the sun. Here, again, it is not quite certain whether a literal translation of the text indicates the given Śaka year as current, or as expired. But correct results can be obtained only by taking it as an expired year. In Śaka-Samvat 788 current (A.D. 865-66), there was no eclipse of the sun on the given *tithi*. Also, by the Southern System of the Sixty-Year Cycle the Vyaya *samvatsara* coincided with Śaka-Samvat 789 current (A.D. 866-67), and by the Northern System it commenced in Śaka-Samvat 788 current, on the 23rd September, A.D. 865, and was followed by the Sarvajit *samvatsara* in Śaka-Samvat 789 current, on the 20th September, A.D. 866. With the basis of Śaka-Samvat 788 expired, the given *tithi* ended, by the *Pūrnimānta* arrangement, on Saturday, the 18th May, A.D. 866, when there was no solar eclipse, but, by the *Amānta* arrangement, on Sunday, the 16th June, as required, when there was an eclipse of the sun (see *Indian Eras*, p. 212), which, as the *tithi* ended about 2 o P.M. (for Bombay), would, *cæteris paribus*, be visible in India.—It would appear, therefore, that the *Amānta* southern arrangement of the lunar fortnights was applied to the Śaka years, in Southern India, at some point between A.D. 804 and 866.

of **Budhagupta**, from the Sâgar District in the Central Provinces, No. 19, page 88; in which the date (line 2 l.) runs — satê pañcha-shashṭy-adhikê varshânâm bhôpatau cha Budhaguptê I Âshâdha-mâsa-śukla-dvâdaśyâm Suragurôr-divasê II Sam 100 60 5,—“ in a century of years, increased by sixty-five; and while Budhagupta (*is*) king; on the twelfth *tithi*, or lunar day, of the bright fortnight of the month Âshâdha; on the day of Suraguru; (*or in figures*) the year 100 (*and*) 60 (*and*) 5.”

As the palæography of this record shews that the year quoted in it belongs to the same uniform series with the years quoted in the Early Gupta records,—a point, in fact, that has never been disputed,—this gives us, for calculation, Gupta-Samvat 165, current; the month Ashâdha (June-July); the bright fortnight; the twelfth *tithi*; and the day of Suraguru, which, — Suraguru, ‘the preceptor of the gods,’ being another name of Bṛihaspati, the *regent* of the planet Jupiter, — is Bṛihaspativâra or Guruvâra. *i.e.* **Thursday**.

This date has been constantly the subject of calculation and controversy. Thus, in 1861, in the *Four. Beng. As. Soc.* Vol. XXX. p. 15, note, Dr. F. E. Hall announced, on the authority of Bapu Deva Shastri of Benares, that, as applied to the epoch of the Vikrama era, it represented Thursday, the 7th June, A.D. 108, New Style.

Again, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. p. 17 l., General Cunningham,—whose theory then was that the epoch should be A.D. 194-(95),—announced as the result, Thursday, the 24th June, A.D. 359, Old Style.¹ The basis of this calculation was Tuesday, the 16th March, corresponding to Chaitra śukla 1, as the initial day of Gupta-Samvat 165 + A.D. 194-95 = A.D. 359-60 = Śaka-Samvat 281 expired; and the result was derived from the assumption that the given *tithi* fell on its theoretical normal place on the 101st solar day of the year.² And, in the same place, he intimated that, with the epoch of A.D. 318-(19), the result would be Friday, the 3rd June, A.D. 483. The basis

¹ It will be understood that the English equivalents of all Hindu dates anterior to the adoption of the Gregorian Calendar or New Style, given by me and I believe by Gen. Cunningham, are given according to the Julian Calendar or Old Style. It is not necessary to complicate matters by using the New Style for a period anterior to its introduction in England.

² This is on the assumption that the lunar months of the Hindu luni-solar years contain thirty and twenty-nine solar days alternately, in regular succession; see, for instance, Cowasjee Patell’s *Chronology*, p. 66 ff., Tables III. to XIII., and Cunningham’s *Indian Eras*, p. 66, Table X. The arrangement given in those Tables, is convenient enough for obtaining approximate results. But, apart from the principles involved, an examination of any *Pañchāṅgs*, for any series of years, will shew that the assumption is not in accordance with facts; and that no definite rule of this kind can be laid down, to determine, more closely than within one and occasionally two days, the exact running solar day, from the commencement of the year, on which a given *tithi* will fall. As a matter of fact, in the ten years Śaka-Samvat 1809 to 1808 inclusive, the position of the end of the twelfth *tithi* of the bright fortnight of Âshâdha, varied from the 100th to the 102nd solar day of the year, and there is a chance of the *tithi* in question ending on a Thursday, in any year of which the initial day is a Monday, a Tuesday, or a Wednesday.—The theoretical arrangement in question also involves a peculiar anomaly. The first month of the year is supposed to consist of thirty days; and the result is that, in a Śaka year.

of this latter calculation was Wednesday, the 23rd February, corresponding to Chaitra śukla 1, as the initial day of Gupta-Samvat 165 + A.D. 318-19 = A.D. 483-84 = Śaka-Samvat 405 expired; and the result was derived from the same assumption as regards the position of the *tithi*.

In 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 115 ff., General Cunningham,—who had then modified his theory, so as to select A.D. 166-(67) as the epoch,—announced that the result obtained by Bapu Deva Shastri from the reckoning of the *Sūrya-Siddhanta*, was a Friday in A.D. 331; but that his own result, obtained from the *Ārya-Siddhanta*, was a Thursday in the same year. He did not then give any further details. But, from the fuller particulars given in his recapitulation of these statements in 1883, in his *Book of Indian Eras*, p. 55 f., we learn that the dates intended were respectively Friday, the 4th June, and Thursday, the 3rd June, A.D. 331; and that his own result was arrived at, in the same way, with the basis of Tuesday, the 23rd February, corresponding to Chaitra śukla 1, as the initial day of Gupta-Samvat 165 + A.D. 166-67 = A.D. 331-32 = Śaka-Samvat 253 expired, and with the same assumption as regards the position of the *tithi*. In the former reference, he repeated the same result of Friday (the 3rd June), A.D. 483, for the epoch of A.D. 318-(19).

In 1882, in the Postscript to his paper on the "Dates on Coins of the Hindu Kings of Kābul" which was published in the *Numismatic Chronicle*, Third Series, Vol. II. p. 128 ff., Sir E. Clive Bayley,—whose theory was that the epoch should be A.D. 190-(91),—announced that the result was a Thursday in A.D. 355, and that it seemed to be Thursday, the 17th May, in that year. But he gave no indication of the way in which this result was obtained; beyond a general reference to Prinsep's Tables in Thomas' Edition of his *Essays*, Vol. II. Useful Tables, pp. 180, 181. And, as a matter of fact, this result was altogether wrong. The 17th May, A.D. 355, was a Wednesday, not a Thursday; and, as closely as can be ascertained by General Cunningham's Tables, it represents Āshāḍha kṛishṇa 5 of the northern year. Sir E. Clive Bayley seems to have very soon become aware of the mistake; since, at the end of the copy of the Postscript which, with a copy of the principal article, reached me from him in May, 1883, there is added, in manuscript, the remark—"this date is erroneous; but the real date, as calculated by Professor Jacobi, comes out a Thursday." The real date of Āshāḍha śukla 12 of Gupta-Samvat 165 + A.D. 190-91 = A.D. 355-56 = Śaka-Samvat 277 expired, is Thursday, the 8th June, A.D. 355; as obtained by Mr. Sh. B. Dikshit, from Prof. Kero Lakshman Chhatre's Tables.

when there is no intervening intercalation of a month, the month Kārttika, as the eighth month, is to contain twenty-nine solar days (see *Chronology*, Tables IV. and XIII., and *Indian Eras*, Table X.) But, as standing first in the southern Vikrama year, the same month Kārttika is to contain thirty solar days (see *Chronology*, Table III.) This is an obvious impossibility.

And in 1881, in the *Ind. Ant.* Vol. X. p. 220, Dr. Oldenberg announced, from the Tables in Warren's *Kala-Sankalita*, the correct result; *viz.* Thursday, the 21st June, A.D. 484.

Now, the results given by Dr. Hall, General Cunningham, and Sir E. Clive Bayley, whether right or wrong, and any similar coincidences, may be accepted without hesitation. And I would only point out, as regards General Cunningham's results for the epoch of A.D. 166-67, that Mr. Sh. B. Dikshit, by actual calculation from all the authorities, including the *Ārya-Siddhānta* on which General Cunningham specially relied, finds that, in A.D. 331, the given *tithi*, belonging to Śāka-Samvat 254 current, and calculated with the basis of Śāka-Samvat 253 expired, ended on Friday, the 4th June, and at such an hour that there is no possibility whatever of Thursday, the 3rd June;¹ and, incidentally, that the initial day of the same Śāka year was Wednesday, the 24th February, A.D. 331, not Tuesday, the 23rd February.

The essential point with which we are concerned, is, whether the week-day of Āshāḍha sukla 12 was a Thursday, if, following Al-Bīrūnī's most specific statement regarding an even difference of two hundred and forty-one years between the Gupta-Valabhi and the Śāka eras we make the calculation for Gupta-Samvat 165 + 241 = Śāka-Samvat 406; or, if the result fails for that year, for the immediately preceding or following Śāka year.

Mr. Sh. B. Dikshit has made the necessary calculations, by Prof. K. L. Chhatre's Tables, with these three Śāka years as expired years. And his results are — with Śāka-Samvat 405 expired, Friday, the 3rd June, A.D. 483; with Śāka-Samvat 406 expired, **Thursday, the 21st June, A.D. 484;**² and with Śāka-Samvat 407 expired, Tuesday, the 11th June, A.D. 485. The process by which these results are obtained, is exhibited in detail, for the second result, in Appendix II. below.

¹ It will be sufficient to quote the four principal authorities. The times for the ending of the given *tithi* on Friday, the 4th June, A.D. 331, reckoned (1) from mean sunrise at Bombay, (2) from mean sunrise at Ujjain, (3) from mean sunrise at Ēraṇ, and (4) from apparent sunrise at Ēraṇ, are — by Prof. K. L. Chhatre's Tables, (1) 5 *ghatis*, 46 *palas*; (2) 6 *gh.* 15 *p.*; (3) 6 *gh.* 40 *p.*; (4) 8 *gh.* 40 *p.*; — by the *Sūrya-Siddhānta*, (1) 7 *gh.* 0 *p.*; (2) 7 *gh.* 29 *p.*; (3) 7 *gh.* 54 *p.*; (4) 9 *gh.* 54 *p.*; — by the *Ārya-Siddhānta*, (1) 8 *gh.* 14 *p.*; (2) 8 *gh.* 43 *p.*; (3) 9 *gh.* 8 *p.*; (4) 11 *gh.* 8 *p.*; — and by the *Brahma-Siddhānta*, (1) 9 *gh.* 16 *p.*; (2) 9 *gh.* 45 *p.*; (3) 10 *gh.* 10 *p.*; (4) 12 *gh.* 10 *p.*. The times are not absolutely accurate; but the results obtained by absolute accuracy would differ by only a few *palas*.

² The results are put in this way for the sake of brevity. The more absolutely accurate method of expressing them, would be to say, in this instance, that the given *tithi*, as belonging to Śāka-Samvat 407 current, and as calculated with the basis of Śāka-Samvat 406 expired, ended on a Hindu Thursday, and at such a time that it ended also during the English Thursday, which was the 21st June, A.D. 484, Old Style. — The hours at which the *tithi* ended, according to the different authorities, and as reckoned from mean or from apparent sunrise at Bombay, Ujjain, and Ēraṇ, are given in Appendix II. Table VI.

The second result, **Thursday, the 21st June, A.D. 484**, is the only one that answers to the week-day mentioned in the record. And a reference to Appendix II. Table VI. will shew that it so answers, not only by Prof. K. L. Chhatre's Tables, but also by the *Ārya-Siddhānta*, and by all the other leading authorities. It answers, as is required, to the treatment of the Gupta year as a northern Śāka year; though it does not, in itself, prove conclusively either the exact epoch of the era, or the scheme of the year; for the reason that, being a date in a bright fortnight, this Āshāḍha śukla 12 was the same *tithi*, and fell on the same solar day, represented by the 21st June, all over India, in the southern as well as the northern Śāka-Saṃvat 407 current, and in southern Vikrama-Saṃvat 541 current, as well as in northern Vikrama-Saṃvat 542 current. It gives Śāka-Saṃvat 407 current (A.D. 484-85), as the equivalent of the given current Gupta year. And finally, as it is obtained by applying the resulting year, Śāka-Saṃvat 406, as an expired year, so that the given *tithi* really belongs to Śāka-Saṃvat 407 current, it shews that, in following Albêrûnî's statement and adding two hundred and forty-one, what is really accomplished is the conversion of a given current Gupta-Valabhi year into an expired Śāka year, by which we obtain precisely the basis that is wanted for working out results by Hindu Tables, *viz.* **the last Śāka year expired before the commencement of the current Śāka year corresponding to a given current Gupta-Valabhi year**; and that the running difference between current Gupta-Valabhi and current Śāka years, is two hundred and forty-two.¹

The Verāwal Inscription of Valabhi-Saṃvat 945.

In this connection, I will notice next the Verāwal inscription of the Chaulukya king Arjunadēva, on a stone at the temple of Harsatadēvi at Verāwal, the modern representative of the ancient Sômnāthpāṭan, in Kāthiāwād. This date furnishes a specially crucial test; partly because it is a date in a dark fortnight, and partly because, coming from Kāthiāwād, and belonging to a comparatively late period, and being mentioned in the same record with a Vikrama year, there was a special chance of finding that its details had been confused with, or rather had been subordinated to, the reckoning of the southern Vikrama era, which was, and is, the original national era in Kāthiāwād and the neighbouring country of Gujarāt. It will be seen, however, that this has not happened.

The details of this date (from Dr. Hultzsch's published text, *Ind. Ant.* Vol. XI. p. 242, line 2 ff.) are — śrī-Viśvanātha-pratibaddha-naujananām bôdhaka-rasûla-Mahammada-saṃvat 662 tathâ śrī-nripa-Vikrama-saṃvat 1320 tathâ śrīmad-Valabhi-saṃ 945 tathâ

¹ Dr. R. G. Bhandarkar arrived at the conclusion (*Early History of the Dekkan*, p. 99) that the addition of 241 would turn a past Gupta year into a past Śāka year, and the addition of 242, a past Gupta year into a current Śāka year. This result is due to the general mistake as regards the epoch of the Śāka era (see page 64 above, note 2).—For an instance of the actual use by Hindus of the additive quantity 242, see page 26 above, note 2.

śrī-Sirha-saṁ 151 varshē Ashāḍha va dī 13 Ravāv=ady=ēha iha śrī-Sōma-nāthadēva-pattanē,—“the year 662 of the prophet Mahammada, who is the teacher of the sailors connected with (*the temple of*) the holy (god) Viśvanātha; so also the year 1320 of the glorious king Vikrama; so also the year 945 of the famous (city of) Valabhi; so also the year 151 of the glorious Sirha; in (*this*) year; the month Āshāḍha, the dark fortnight;¹ the (solar) day 13; on Sunday; to-day (*and*) here; here, in the city of the holy god Sōmanātha.”

This gives us, for calculation, Valabhi-Saṁvat 945, current; the month Āshāḍha (June-July); the dark fortnight; the thirteenth solar day of the fortnight, with whatever *tithi*, presumably the thirteenth, fell on it; and Ravivāra, or **Sunday**. And,—as the mention of the year 1320 of the Vikrama era, and of the year 662 of the prophet Muḥammad, which is the year 662 of the well-known Hijra era, and commenced² on Sunday, the 4th November, A.D. 1263, and ended on Saturday, the 23rd October, A.D. 1264, shews that the Valabhi era quoted in this record must have had its starting-point in or about A.D. 319, and must of necessity be the Valabhi era that is mentioned by Al-Bērūnī, —in accordance with the results obtained for the date in the Ēraṇ inscription, the given *tithi* should belong to Valabhi-Saṁvat 945 + 242 = Śāka-Saṁvat 1187 current (A.D. 1264-65): and, in using Hindu Tables, the calculation should be made with the basis of Śāka-Saṁvat 1186 expired.

Before proceeding to the results, however, there are some preliminary points to be noted. The first is, that, as the inscription is specifically connected with a locality in Kāthiawāḍ, the presumption is that the Vikrama year quoted in it, is a southern Vikrama year, commencing with the first day of the bright fortnight of the month

¹ The syllable *va*, in the original, either is an abbreviation of *vadya*, whether alone or in composition with *paksha* or *pakshē*, or stands for *ba*, the abbreviation of *bahula*, similarly either alone or in composition with *paksha* or *pakshē*.—As regards the point that *ba dī*, or *va dī*, and *su dī*, are separate technical abbreviations, not words in themselves, see page 92 (Text and Translations), note 1.—Just as *dī* is sometimes used with *ba* or *va* and *su*, and sometimes is omitted, so in the Nēpāl inscriptions (see Appendix IV, below) the indeclinable *divā*, ‘by day,’ is sometimes used, and sometimes not, in connection with the number of the *tithi*. So also sometimes *dī*, or one of its full forms, *dina*, *dina*, *divasa*, or *divasē*, is used without any specification of the fortnight. The exact meaning of the differences of practice in this respect, is not quite certain; and could only be settled by a large number of calculations. But it seems evident that, when *dī* is used, or any of its full forms, the reference is to the solar day, in conformity with what would naturally be the most ancient reckoning; not to the lunar *tithi*. If, at a subsequent period, the solar days became subject to expansion and repetition, with the lunar *tithis*, then the running number in the fortnight will always be the same for both the lunar *tithi* and the solar day. If not, then the thirteenth *tithi*, for instance, might fall at any time on the twelfth or the fourteenth solar day, as counted without repetition or expansion from the commencement of the fortnight. And, in the differences of expression, there may perhaps be a reference to some such difference in the notation.

² See *Indian Eras*, p. 126.

Kārttika (October-November). This, however, apart from the natural presumption, is rendered absolutely certain by the concomitant mention of the Hijra year; from which, since the month Āshāḍha answers ordinarily to June-July, it is plain,—as was pointed out by Dr. Hultzsch in editing the inscription,¹ and by General Cunningham in commenting on the date,²—that the English date which we have to look for lies in or about June or July, A.D. 1264. This at once removes the possibility of any reference to the northern Vikrama year; since the month Āshāḍha of the northern Vikrama-Samvat 1321 current,³ is represented by June-July of the preceding English year, A.D. 1263. Also, since the period June-July, A.D. 1264, fell in Śaka-Samvat 1187 current, it removes any real necessity of making calculations for Śaka-Samvat 1186 current and 1188 current; the results, however, for these two years will be given, in order to help in setting the general question entirely at rest.

So much, as regards the English equivalent of the given date lying in A.D. 1264, had been clearly pointed out by Dr. Hultzsch and General Cunningham. But nothing further, that I can find, was said about the details of the English equivalent, until just before the time when I first had occasion to consider this date,⁴ when, in a letter dated the 3rd December, 1885, General Cunningham announced to me that the equivalent English date is Sunday, the 25th May,⁵ A.D. 1264.

This result, **Sunday, the 25th May, A.D. 1264**, is, as will be seen below, the correct one. But, in order to explain its full bearing, more is requisite, than simply to state it; especially because it is necessary to shew clearly, in the face of what has elsewhere been written about this date, that this result is not obtained from the mention of Vikrama-Samvat 1320, though it does answer the requirements of that mention; i. e. that it is not the result for a year commencing on the first day of the bright fortnight of the month Kārttika which fell in A.D. 1263; and, consequently, that, even apart from what I have already established, this record proves that Valabhi-Samvat 945 commenced at any rate not with that day.⁶ And here I would remark incidentally, that no argument, of identity between

¹ *Ind. Ant.* Vol. XI. p. 241.

² *Indian Eras*, pp. 50, 53, 63.

³ According to the present Tables, the given Vikrama year 1320 must be interpreted as an expired year; and the indicated current year is, therefore, 1321. This, however, does not make the given Valabhi year an expired year; just as it does not, and can not, convert the given Hijra year into an expired year.

⁴ *Ind. Ant.* Vol. XVI. p. 147 ff.

⁵ The ordinary equivalent of Āshāḍha is June-July. But the dark fortnight of the northern Āshāḍha corresponds to the dark fortnight of the southern Jyēsthā, which month is ordinarily May-June. And this, with the fact that Śaka-Samvat 1187, current, commenced rather early, on Saturday, the 1st March, or Friday, the 29th February, A.D. 1264, is the reason why this dark fortnight of Āshāḍha fell entirely in May.

⁶ As opposed to these results Gen. Cunningham (*Indian Eras*, p. 53) has quoted this record as proving absolutely that Valabhi-Samvat 1 = A.D. 319 (-20); which could only be by taking the epoch as

the two years, can be based on the mere fact that the record mentions both a Valabhi year and a southern Vikrama year. It might just as well be asserted that the mention also of the Hijra year 662, shews that the scheme of the years of that era, too, is identical with the scheme of the southern Vikrama year; whereas,—even apart from the fact that the Hijra year 662 commenced, as stated above, on Sunday, the 4th November, A.D. 1263, while the southern Vikrama-Saṃvat 1320, as an expired year, *i.e.*, more properly, southern Vikrama-Saṃvat 1321 current, commenced on Friday, the 5th October of that same year,¹—everyone knows that these two eras have absolutely nothing in common at all; the Hijra era being a purely Musalmān era. The Verāwal record is simply analogous exactly to scores of documents that are still being turned out in India, in which the date is expressed according to the English and also one or other of the Indian systems; and in which the principal record depends entirely upon the person by whom, and the circumstances under which, it is drawn up. Sometimes it will be the English date; sometimes the Indian. We shall see immediately that, in this Verāwal inscription, the principal record is the Valabhi date; and that the Vikrama date accidentally, as well as the Hijra date naturally, was entirely subordinated to it. Possibly, we may hereafter obtain instances, in which the reverse of this will be found to have been the case. But they will not avail to disprove any of the pointed and unavoidable conclusions, regarding the epoch of the Gupta-Valabhi era and the scheme of its years, which are absolutely forced on us by the circumstances of the present Verāwal date.

The second point to be noted is, that the month Āshāḍha which fell in A.D. 1264,—*i.e.* both the Āshāḍha of northern Śaka-Saṃvat 1187 and northern Vikrama-Saṃvat 1322, and the slightly different Āshāḍha of southern Śaka-Saṃvat 1187 and southern Vikrama-Saṃvat 1321,—was an intercalary month.² The effect of the intercalation was as follows:—The initial day of Śaka-Saṃvat 1187, both northern and southern, and of the

A.D. 318-19, and by treating the years as commencing, from the beginning, on Kārttika śukla 1.—Also (*id.* pp. 50, 63) he treats Vikrama-Saṃvat 1320 as the leading record of the date; and very clearly implies throughout, though he does not actually state, the identity of the scheme of the Valabhi and southern Vikrama years.

¹ Cowasjee Patell's *Chronology*, p. 150.

² See *Indian Eras*, p. 179.—The fact is also proved by K. L. Chhatre's Tables. In C. Patell's *Chronology*, p. 150, the intercalation is entered opposite Śaka-Saṃvat 1186 (expired) and southern Vikrama-Saṃvat 1321 (expired). This is in accordance with a mistake that runs all through his Table I. pp. 94 to 183. The intercalations are placed by him correctly for the Śaka years. But he has omitted to point out that, in applying them to the Vikrama years, which, throughout his Table, are the southern Vikrama years, they must, in consequence of the way in which the years of the two eras overlap, be read off as far as the months Chaitra to Āśvina, both inclusive, are concerned, for the Vikrama year preceding that opposite to which they are entered; at least, I can find no note in his book to that effect.—A reference to Table III. at page 71 above, will shew at once that an intercalation of any month from Chaitra to Āśvina inclusive, for Śaka-Saṃvat 1186 expired, northern or southern, did occur for northern Vikrama-Saṃvat 1321 expired, but southern Vikrama-Saṃvat 1320 expired.

northern Vikrama-Samvat 1322, was Saturday, the 1st March, A.D. 1264, according to General Cunningham,¹ and Friday, the 29th February (the English year being a Leap-year), according to Mr. C. Patell.² With General Cunningham's own initial day, and by his own theory and process,—*vis.* that Āshāḍha kṛishṇa 13 fell on the 87th solar day of the year, from and inclusive of the initial day,—the resulting English date would be Monday, the 26th May, A.D. 1264. Therefore, in arriving at Sunday, the 25th May, he has adopted Mr. C. Patell's initial day, in preference to his own. And I will follow the same course, for the rough purposes for which the initial day may here be utilised. The double Āshāḍha included four lunar fortnights. In northern Saka-Samvat 1187 and northern Vikrama-Samvat 1322, they commenced and ended, theoretically and approximately, on respectively the 75th and 133rd solar days of the year,³ *i.e.* on respectively the 13th May and the 10th July. And, according to the regular northern system, of the four fortnights, the first (dark) belonged to the natural month; the second (bright), and the third (dark), to the intercalated month; and the fourth (bright), to the natural month. But, in southern Śaka-Samvat 1187 and southern Vikrama-Samvat 1321, they commenced and ended, theoretically and approximately, on respectively the 90th and 148th solar days of the Śaka year;⁴ *i.e.* on respectively the 28th May and the 25th July. And, of the four fortnights, if we adopt the present regular southern system, the first (bright), and the second (dark), belonged to the intercalated month; and the third (bright), and the fourth (dark), to the natural month.⁵ It is evident, therefore, that, if we treat the Āshāḍha of this

¹ *Indian Eras*, p. 179.

² *Chronology*, p. 150.

³ See *Indian Eras*, p. 109, and *Chronology*, p. 71.

⁴ *Chronology*, p. 71.

⁵ A verse that is given by Bapu Deva Shastri, in his edition of the *Siddhānta-Sūtrāṅga* of Bhāskarāchārya, p. 49, note, as belonging to the *Brahma-Siddhānta*, indicates a more ancient custom, according to which the first (bright) and the second (dark) fortnights would belong to the natural month; and the third (bright) and the fourth (dark), to the intercalated month. The verse runs—*Mēsh-ādi-sthē savitārī yō yō māsaḥ prapūryatē chāndrah Chaitr-ādyaḥ sa jñeyah eurti-dutvō=dnimāsō=ntyah*,—"whatever lunar month is completed when the sun is standing in Aries and the following (signs), that month is to be known as Chaitra, &c.; when there are two completions, (there is) an intercalated month, (and it is) the latter (of the two)."—Now, intercalated months are held to be inauspicious, and the performance of ceremonies in them is prohibited. Only if, in one and the same year, there are two intercalary months (which are always accompanied by the expunction of a month, which may be one of the two, or a third month), then the first intercalated month is *prastā*, or 'stamped as excellent or approved of,' the second being, as usual, *nindya*, or 'to be looked on as under prohibition.' And the rule attributed to the *Brahma-Siddhānta* would make the intercalated fortnights different, in different parts of India, according to the northern or southern scheme of the year. It must, obviously, have been highly inconvenient, especially on the border-land of the dividing-line between Northern and Southern India, that the prohibition should not be applicable to exactly the same lunar periods. And a change, in accordance with the necessities of the case, was eventually made,—and must have been made long before the period of the present inscription; though, apparently, after the time of the Kaira grant of Dharaśēna IV., of Gupta-Samvat 330, the "second Mārgasira" of which is undoubtedly the intercalated month,—by which the intercalated fortnights of

record as the natural month, the English equivalent, for the given date as referred to the northern year, will be about a month earlier than the English equivalent for the given date as referred to the southern year; and that an English equivalent, answering to the given date as referred indifferently to either the northern or the southern year, can be obtained only by treating the Āshādha of the record as the intercalated month. That we have, however, to look on the given date as belonging to the dark fortnight of the natural Āshādha, is at least to be assumed *prima facie*; partly because the record contains no qualificatory term, indicative of the intercalated month; and partly because of the prohibitive of official, ceremonial, and religious acts in an intercalated month.¹

The results, worked out by Mr. Sh. B. Dikshit from Prof. K. L. Chhatre's Tables, for the natural Āshādha, are — with northern Śaka-Samvat 1186 expired, **Sunday,² the 25th May, A.D. 1264**, for both the thirteenth *tithi* and the thirteenth solar day; and with southern Śaka-Samvat 1186 expired, Tuesday, the 22nd July, A.D. 1264, for the thirteenth *tithi*, but Wednesday, the 23rd July, for the thirteenth solar day;³ and the result for the intercalated Āshādha is Monday, the 23rd June, A.D. 1264, for the thirteenth *tithi*, but Tuesday, the 24th June, for the thirteenth solar day, by both the northern and the southern reckoning, according to the present custom in both parts of the country. Mr. Sh. B. Dikshit has also given me full results, according to both the *Pūrṇimānta* northern system, and the *Amānta* southern system, with Śaka-Samvat 1185 and 1187 expired; in order to present at once all the possible surroundings of the date. These results are—with northern Śaka-Samvat 1185 expired, Tuesday, the 5th June, A.D. 1263, for the thirteenth *tithi*, but Wednesday, the 6th June, for the thirteenth solar day; and with southern Śaka-Samvat 1185 expired, either ⁴ Wed-

the southern month, *vis.* the first and the second of the four, were made to correspond exactly with the intercalated fortnights of the northern month, *vis.* the second and the third of the four.—I have mentioned this earlier custom here, because it is one of the general surroundings of the date. But the question is of no vital importance in this case, because the date is a northern, not a southern one.

¹ See the preceding note. ² The *tithi* ended 13 *ghaṭis*, 30 *palas*, after mean sunrise at Bombay.

³ *i.e.* the thirteenth solar day counted from the commencement of the fortnight, without omitting a solar day with the lunar *tithi* that was expunged (see page 85 above, note 1.)

⁴ The doubt here is because of the interesting discovery that the dark fortnight of the southern Āshādha, and northern Śrāvāṇa, of Śaka-Samvat 1185 current, was a fortnight which, "except, perhaps in some parts far off in the east of India," contained only thirteen solar days; see my general note on this subject, in the *Ind. Ant.* Vol. XVI, p. 81 ff. The full-moon *tithi* of hāḍha, northern and southern, was on Saturday, the 23rd June; and the following new-moon *tithi* of the southern Āshādha, and the northern Śrāvāṇa, was on Friday, the 6th July; which gives thirteen solar days for this dark fortnight. There was an expunction of two *tithis*, and no repetition of a *tithi* to make up for the loss. The authorities differ as to which were the two expunged *tithis*. One of them was early in the fortnight; and Mr. Sh. B. Dikshit has not worked this out, because it does not directly bear upon the date under discussion. The other was either the twelfth, or the thirteenth, or the fourteenth *tithi*; and upon this will depend the question whether the thirteenth *tithi*, if not itself expunged, was Wednesday, the 4th July, or Thursday, the 5th July. Under any circumstances, the thirteenth and last solar day of this dark fortnight, was Friday, the 6th July.

nesday, the 4th July, or Thursday, the 5th July, A.D. 1263, for the thirteenth *tithi*, but, in either case, Friday, the 6th July, for the thirteenth solar day; with northern Śaka-Saṃvat 1187 expired, Saturday, the 13th June, A.D. 1265, for both the thirteenth *tithi* and the thirteenth solar day; and with southern Śaka-Saṃvat 1187 expired, Sunday, the 12th July, A.D. 1265, for the thirteenth *tithi*, but Monday, the 13th July, for the thirteenth solar day. The last is the only other case in which the result includes a Sunday at all. But it is of no practical value; because it is obtained by the treatment of the Śaka year as a southern year, whereas I have already shewn that this is not the treatment which is to be applied; and, still more conclusively, because it would have to be allotted to the southern Vikrama-Saṃvat 1321 expired, whereas the record specifically refers to the preceding year, 1320 (expired).

The true English equivalent of the given date, therefore, really is **Sunday, the 25th May, A.D. 1264**. This result, and this alone, answers all the requirements of the record. It is the equivalent of a date which falls, as recorded, within the limits of southern Vikrama-Saṃvat 1320 (expired); though it is not the equivalent of any day in the month Āshāḍha as referred to that year; for, if it is treated as the equivalent of a date referred to that year (and to southern Śaka-Saṃvat 1186 expired), then, of course, it represents the thirteenth *tithi* and solar day of the dark fortnight of the month Jyēshtha, preceding Āshāḍha. It answers to the specified day of the natural, not the intercalated, month; as is expressly required, partly by the absence, in the record, of any specification of the intercalated month, and partly by the general prohibition regarding intercalated months. Also, as is seen from the particulars given above, it is obtainable only by treating the expired Śaka year, which is the basis of the calculation, as a northern year. Accordingly, it not only bears out in all respects the results obtained from the date in the Êraṇ pillar inscription of Budhagupta, but also goes beyond them. It definitely proves the running difference of two hundred and forty-two years between current Gupta-Valabhl and current Śaka years. It also proves that the true original scheme of the years of the Gupta-Valabhl era,—*vis.* the regular *Pārnimānta* northern scheme, as established at page 76 f. above,—was preserved, in Kāthiāwād, up to at any rate A.D. 1264. It gives Śaka-Saṃvat 1187 current (A.D. 1264-65), as the equivalent of the given current Gupta-Valabhl year. And it definitely proves that the exact epoch of the era was Śaka-Saṃvat 241 expired, or 242 current, corresponding to A.D. 319-20.

This result, therefore, will now be taken, in the place of the result obtained from the date of the Êraṇ pillar inscription of Budhagupta of Gupta-Saṃvat 165, as furnishing the definite standard, on the analogy of which we must calculate all the remaining dates in the Gupta-Valabhl era that supply details for computation.

The Verāwal Inscription of Valabhl-Saṃvat 927.

The third and last date, with the mention of a week-day, that I have to comment on, is contained in an inscription which has not as yet been published, but has been placed at

my disposal, for present purposes, by Dr. Bhagwanlal Indraji, the discoverer of it. The inscription is on the pedestal of an old image, which is now built into the wall of the modern temple of the goddess Harsaṭadēvi at Verāwal. The date, with some important words in the context, (from Dr. Bhagwanlal Indraji's cloth-rubbing) runs — (l. 1) śrīmad-Valabhī-sa[m*]vat 927 varshē Phālguna śu di 2 Saumē || Ady-ēha śrī-Dēvapattanē (l. 4) śrī-Gōvardhana-mūrtti[h*] (l. 5) kārapitā;—in which, unfortunately, there is some doubt as to the proper rendering of the first syllable of the word that gives the name of the week-day. The vowel *au* was undoubtedly formed; though, in the rubbing, the top-stroke is partially filled up, in consequence either of want of depth in the engraving, or of want of care in making the rubbing. And, the consonant presenting the appearance in the rubbing of being *bh*, the natural inclination is to read *Bhaumē*, "on Tuesday." Dr. Bhagwanlal Indraji, however, tells me that, in the original, the consonant is certainly *s*; and the appearance of *bh*, therefore, is due to an imperfection in the rubbing. The reading of the original, accordingly, is to be taken as *Saumē*. But this is not a real word; and it requires to be corrected into either *Sōmē*, "on Monday;" *Bhaumē*, "on Tuesday;" or *Saumyē*, "on Wednesday." It is unfortunate that we should have to make any correction at all, in a point of such importance; especially when so very free a choice is open. But it has to be done. And the calculated results favour the supposition that the reading intended was *Sōmē*, "on Monday." Dr. Bhagwanlal Indraji was of opinion that the intended reading was *Bhaumē*, "on Tuesday;" which, of course, might be supported by assuming carelessness on the part of the engraver, in letting his tool slip in such a way as to give the *bh* a more or less complete appearance of *s*. But, from the appearance of the rubbing, the reading *Sōmē* is equally justifiable, on the assumption that the partial appearance of *bh* in the rubbing, instead of *s*, is due only to a fault in the rubbing, and that the mistake in forming *au* instead of *ō* was discovered before the stroke which turns *ō* into *ar* was completed; this would account for this stroke being so shallow as to cause the blur which almost entirely conceals it in the rubbing. Adopting the reading or correction of *Sōmē*, the translation will be — "the year 927 of the famous (city of) Valabhī; in (this) year; (the month) Phālguna; the bright fortnight; the (solar) day 2; on Monday; to-day; here in the famous (city of) Dēvapattana (this) image of the holy Gōvardhana has been caused to be made."

This gives us, for calculation, Valabhī-Samvat 927, current; the month Phālguna (February-March); the bright fortnight; the second solar day of the fortnight, and presumably the second *tithi*; and Sōmavāra, or Monday. And, on the analogy of the Verāwal inscription of Valabhī-Samvat 945, the given *tithi* should belong to Valabhī-Samvat 927 + 242 = Śaka-Samvat 1169 current (A.D. 1246-47); and the calculation should be made with the basis of Śaka-Samvat 1168 expired.

Mr. Sh. B. Dikshit's calculations, however, made, as before, for a year before and a year after the resulting year, as well as for that year itself, give the following results, in each case for both the second solar day and the second *tithi*, both by Prof. K. L. Chhatre's Tables and by the *Sūrya-Siddhānta*; viz. with Śāka-Samvat 1167 expired, **Monday**,¹ the 19th February, A. D. 1246; with Śāka-Samvat 1168 expired, Saturday,² the 9th February, A. D. 1247; and with Śāka-Samvat 1169 expired, Wednesday,³ the 29th January, A. D. 1248.

The result for Śāka-Samvat 1169, which is the year in which the week-day should presumably prove correct, does not answer at all. If we could understand that the reading intended was *Saumya*, "on Wednesday," then the result for Śāka-Samvat 1170 might be accepted; subject only to the considerations that *Saumyavādra*, though perfectly allowable, is not often used as a synonym for *Budhavādra*, 'Wednesday;' and that the result is later by a year than what it ought to be, and can be arrived at only through accepting an alteration in the reckoning of the Gupta-Valabhi era, precisely the opposite of the alteration which, as shewn at page 72 f. above, was certainly made, in Gujarāt before the date of the Kaira grant of Dharasēna IV. of the year 30. If, on the other hand, we take *Sōmā*, "on Monday," as the intended reading, then the result for Śāka-Samvat 1168 may be accepted, subject only to the consideration that it is earlier by a year than what it ought to be. This result would be quite intelligible, if we could refer the given date to a year commencing with *Mārgaśīrsha*; for then, belonging to Valabhi Samvat 927, it would belong quite regularly to Śāka-Samvat 1168, and its English equivalent would fall quite regularly in A. D. 1246. This, however, as I have stated at page 78 above, is distinctly prevented by a perfectly conclusive obstacle. The only resource that remains, is to hold that, for some reason or other, the date given in this record, like the date in the Kaira grant of Dharasēna IV. of the year 330, was taken from a Gujarāt almanac, and belongs to a year the initial day of which was the *Kārttika śukla 1* preceding the true commencement of Gupta-Valabhi-Samvat 927. This, again, would be perfectly intelligible, if we could only assume that the image, which is probably portable enough, was fashioned, together with the engraving of the inscription, at some place in Gujarāt; and was then transported by a pilgrim to Verāwal. But the objection to this is, that the inscription seems to record distinctly that the image was made at *Dēvapattana*; and *Dēvapattana* is well known as another name of *Sōmnāthpātan*, i.e. the modern Verāwal itself, and it is difficult to understand how the corrupt Gujarāt reckoning of the Gupta-Valabhi era can have been introduced at Verāwal in A. D. 1246, when, as we have already seen from the other Verāwal inscription, of Valabhi-Samvat 945, the true original reckoning was used there up to at

¹ The *tithi* ended, by Prof. K. L. Chhatre's Tables, 29 *ghaṭis*, 59 *palas*, and by the *Sūrya-Siddhānta*, 30 *ghaṭis*, 2 *palas*, after mean sunrise at Bombay.

² Here the times are respectively 8 *ghaṭis*, 33 *palas*, and 9 *ghaṭis*, 25 *palas*.

³ Here the times are respectively 11 *ghaṭis*, 57 *palas*, and 34 *ghaṭis*, 43 *palas*.

least eighteen years later. The explanation, however, is perhaps to be found in the supposition that the inscription was prepared under the personal direction of a pilgrim from Gujarát, who had brought a Gujarát almanac with him.

On the whole, be the explanation what it may, there seems no doubt that the proper result is **Monday, the 19th February, A.D. 1246**. This, however, does not support the running difference of exactly two hundred and forty-two years between current Gupta-Valabhi and current Śaka years; nor, as the given date belongs to a bright fortnight, does it prove anything as to the northern or southern nature of the Gupta-Valabhi year. If it is taken as the result for a date belonging to a year the scheme of which was identical with the scheme of the Śaka year, northern or southern,—*i.e.* as the result for a date in a year which commenced with the Chaitra sukla 1 belonging to Śaka-Samvat 1168 current,—it requires a running difference of two hundred and forty-one years only. While, if it is taken as the result for a date belonging to a year the scheme of which was identical with the scheme of the southern Vikrama years,—*i.e.* as the result, obtained through Śaka-Samvat 1167 expired, for a date in a year which, with the southern Vikrama-Samvat 1303 current, commenced with the following Kārttika sukla 1, still belonging to Śaka-Samvat 1168 current, and falling five months before the true commencement of Gupta-Valabhi-Samvat 927,—then it requires a running difference lying between two hundred and forty-one and two hundred and forty-two. As in the case of the Kaira grant of Dharasēna IV. of the year 330, which has been referred to at page 72 above and is now to be explained in detail, the latter is the way in which I apply the result. And it gives, therefore, the southern Vikrama-Samvat 1303 current (A.D. 1245-46), as the nominal equivalent of the given current Valabhi year. But I have to point out distinctly that the date is not a satisfactory one, since an important correction of some kind or another has to be made, in order to interpret it intelligibly at all; and that in no way does it give a conclusive result, like that of the other Verāwal inscription, of Valabhi-Samvat 945.

The Kaira Grant of the year 330.

The preceding is the last instance, as yet obtained, of the mention of a week-day in a record dated in the Gupta-Valabhi era. There are, however, three inscriptions, containing other interesting details for computation, which will now be noticed, before dealing with the question of the Twelve-year Cycle of Jupiter.

The first of them is a **Kaira grant of Dharasēna IV. of Valabhi**; in which the date (from Dr. Bühler's published text; *Ind. Ant.* Vol. XV. p. 339, line 57) runs — sam 300 30 dvi-Mārgaśira śu 2,—“the year 300 (*and*) 30; the second (month) Mārgaśira; the bright fortnight; (the lunar day) 2.

This gives us, for calculation, Gupta-Samvat 330, current; **an intercalation of the month Mārgaśira or Mārgaśiraba** (November-December), as shewn by the reference

in the text to two months of that name; the bright fortnight of the second Mārgaśirsha; and the second *tithi* or lunar day. And, on the analogy of the Verāwal inscription of Valabhi-Samvat 945, the given intercalated month should belong to Gupta-Samvat $330 + 242 = \text{Śāka-Samvat } 572$ current (A.D. 649-50); and the calculation should be made with the basis of Śāka-Samvat 571 expired.

General Cunningham, however,¹ shews no intercalation in that year; but, in the preceding year, Śāka-Samvat 571, an intercalation of the month Kārttika, which would fall in A.D. 648; and this appears to be quite correct, in accordance with the regulation of intercalations by the actual place of the sun. Looking further into the matter, Dr. Schram, as reported by Dr. Bühler,² found that in A.D. 648 there certainly was an intercalated month, which, according to the present method would be Kārttika, but according to the rule for mean intercalations, would be Mārgaśirsha. So, also, Mr. Sh. B. Dikshit finds, by actual calculation from the *Sūrya-Siddhānta*, that, by mean intercalation, in A.D. 648 there was an intercalated month between the natural Mārgaśirsha and the natural Pausa, which would be named Mārgaśirsha according to the verse *Mēsh-Adi-sthā savitari* &c., that is quoted as belonging to the *Brahma-Siddhānta*;³ though it would be named Pausa according to the present practice. In either case, the two intercalated fortnights are, of course, the same lunar period; the only difference is in respect of the name by which that period should be called. And, in finding that period coupled with the name of Mārgaśirsha, there is the fact, which must be admitted, that, in contra-vention of the usual rule, the grant recorded in this inscription was made in the intercalated month; a deviation for which I cannot find any reason in the record itself. Having regard to this and other points, I asked Mr. Sh. B. Dikshit to also make the necessary calculations on the possibility of the abbreviation *dvi* for *dvītya*, 'the second,' qualifying, not only the word *Mārgasira*, but the whole expression *Mārgasira* *śu* 2; i.e. on the possibility of the intercalation or repetition referring to the *tithi* or lunar day, not to the month; in which case the date might have been referred, quite regularly, to Śāka-Samvat 572. He finds, however, that the second *tithi* of the bright fortnight of Mārgaśirsha of Śāka-Samvat 572, falling in A.D. 649, was not a repeated *tithi*, either by Prof. K. L. Chhatre's Table, or by the *Sūrya-Siddhānta*; and that, on the contrary, by the *Sūrya-Siddhānta*, there is the possibility of this *tithi* having been expunged, in the far eastern parts of India. It is certain, therefore, that the intercalation refers to the month; not to the *tithi*. And it is equally certain that in Śāka-Samvat 571 there was an intercalated month, falling in A.D. 648, which might be named Mārgasira or Mārgaśirsha, and which evidently was actually so named in the almanac that was consulted by the drafter of this record. This being the case, there cannot have been an intercalation of the same month, or in fact of any month at all, in the following year, Śāka-Samvat 572. Therefore, the Mārgaśirsha of this record

¹ *Indian Eras*, p. 158.

² See page 88 above. note 5.

³ *Ind. Ant.* Vol. XV. p. 338.

undoubtedly fell, not in A.D. 649, as should be the case according to the true Gupta Valabhi reckoning, but in A.D. 648; and belonged, for astronomical purposes, to Śāka-Samvat 571, or, according to the popular usage of Gujarāt, to the southern Vikrama-Samvat 706. And, since the localities mentioned in the charter connect it absolutely with a province of Gujarāt,¹ the year 330 of this record must have commenced, like the southern Vikrama-Samvat 706, with the month Kārttika that preceded the true commencement of Gupta-Samvat 330, with Chaitra śukla 1 of Śāka-Samvat 572, according to the original scheme of the years of the era.

The result, therefore, gives the southern Vikrama-Samvat 706 current (A.D. 648-49), as the nominal equivalent of the given current Gupta year. And this date, with that of the Verāwal inscription of Valabhi-Samvat 927, must be allotted to a class of cases, in which the running difference of exactly two hundred and forty-two years between current Gupta-Valabhi and current Śāka years was not maintained, in consequence of a local adaptation of the Gupta-Valabhi year to the scheme of the southern Vikrama year, made in such a way that, as pointed out at page 73 above, each subsequent Gupta-Valabhi year, where this adaptation was applied, commenced five lunations before the true commencement of the year according to the original scheme. The anomaly, however, is natural enough in the present instance, because of the locality to which the record refers itself.

The Nêpāl Inscription of the year 386.

The next inscription that I have to notice, is the Nêpāl inscription of Mānadêva, of the Sūryavamsi or Lichchhavi family of Mānagriha, on the lower part of a broken pillar placed to the left of the door of the temple of the god Chāngu-Nārāyaṇa, about five miles to the north-east of Khāṭmāṇḍu; in which the date (from Dr. Bhagwanlal Indrajī's published text and lithograph; *Ind. Ant.* Vol. IX. p. 163, line 1 f.) runs — samvat 300 80 6 Jyēshtha-m[ā]sa-śukla-pakshē pratipadi 1 [Rō]hīṇī-nakshatra-yukt[ē*] chandramasi m[u]hūrttē praśastē-Bhijiti,—“the year 300 (and) 80 (and) 6; in the bright fortnight of the month Jyēshtha, on the first *tithi* or lunar day, (or in figures) 1; the moon being in conjunction with the Rōhīṇī *nakshatra*; in the excellent *muhūrta* (named) Abhijit.”

The Nêpāl inscriptions were first brought to notice by Dr. Bhagwanlal Indrajī, in the *Ind. Ant.* Vol. IX. p. 163 ff.; and his view of the historical results of them was given in the same Journal, Vol. XIII. p. 411 ff. My own view, originally published in the same Journal, Vol. XIV. p. 342 ff., will be found explained in detail in Appendix IV. below. And all that it is necessary to state here, is, that the earliest inscriptions disclose the use of two eras; *viz.* the so-called Gupta era, and the Harsha era. At the time, however, when Dr. Bhagwanlal Indrajī wrote, the fact that the Gupta era was used in some of these

¹The charter was issued from the victorious camp at Bharukachchha, *i.e.* the modern Broach (Bharuch); and it records the grant of some lands in the Khētaka dhāra, or the territorial division of which the chief town was Khētaka. *i.e.* the modern Kaira (Khōḍā).

records, was not apparent. And it only became clear on Mr. Bendall's discovery of the Gôlmâdhiṭol inscription of the *Mahârāja Śivadēva* I. of Mânagriha, which he published originally in the *Ind. Ant.* Vol. XIV. p. 97 f., and has given gain, with a slight correction in the reading of the date, in his *Journey in Nêpâl and Northern India*, p. 72, and Plate viii. This inscription is dated in the year 316, without any specification of the era. But the clue to the interpretation of the date is given by its mention of the *Mahâsâmantâ Amśuvarman*, as the contemporary¹ of Śivadēva I. Amśuvarman's approximate date, *vis.* about A.D. 637, was very well known from Hiuen Tsiang's mention of him.² And, as the Nêpâl series included three inscriptions of Amśuvarman himself, dated in the years 34, 39, and 44 or 45 of an unspecified era, and another, of Jishnugupta, dated in the year 48, and mentioning Amśuvarman, Dr. Bhagwanlal Indraji very properly referred these dates to the era running from the accession of Harshavardhana of Kanauj, and commencing³ in A.D. 606. This much being quite certain, it follows that the date the year 316 for Śivadēva I., the contemporary of Amśuvarman, must of necessity be referred to a starting-point just about three hundred years before the Harsha era. And the era which exactly meets the requirements of the case is the Gupta era; for, $316 + \text{A.D. } 319-20 = \text{A.D. } 635-36$; which is in due accordance with the recorded dates that we have for Amśuvarman in the Harsha era, representing from A.D. 639 to 649 or 650.

As regards the present inscription of Mânadēva its palæography, as well as a general consideration of the historical results, shews that the year 386, quoted in it, belongs to the same series with the year 316 that is quoted in the Gôlmâdhiṭol inscription of Śivadēva I. And, accordingly, this record gives us, for calculation, Gupta-Samvat 386, current; the month Jyêshṭha (May-June); the bright fortnight; the first *tithi* or lunar day; the **Rôhini nakshatra** or lunar mansion; and the **Abhijit muhūrta** or thirtieth part of the day and night. And, on the analogy of the Verâwal inscription of Valabhi-Samvat 945, the given *tithi* should belong to Gupta-Samvat $386 + 242 = \text{Śaka-Samvat } 628$ current (A.D. 705-706); and the calculation should be made with the basis of Śaka-Samvat 627 expired.

Making the calculations by the *Sûrya-Siddhânta*, and applying the results to the longitude of Khâtmandu, Mr. Sh. B. Dikshit finds that, with the basis of Śaka-Samvat 627 expired, the given *tithi*, belonging to Śaka-Samvat 628 current, ended on Tuesday,

¹ This is also recorded in the other inscription of Śivadēva I., No. 5 of Dr. Bhagwanlal Indraji's Nêpâl series, *Ind. Ant.* Vol. IX. p. 168 ff. But, unfortunately for the general chronological results arrived at by him from those inscriptions,—which involved the application of the Vikrama era for the interpretation of such of the Nêpâl dates as belong really to the Gupta era,—the date of Śivadēva I. is there broken away and lost.

² See Beal's *Buddh. Rec. West. World*, Vol. II. p. 81; also *Ind. Ant.* Vol. XIII. p. 422, and Vol. XIV. p. 345.

³ On this point see a note in Appendix IV. below.

the 28th April,¹ A.D. 705, at 57 *ghaṭīs*, 12 *palas*, after sunrise; that there was the *Kṛittikā nakshatra* up to 11 *ghaṭīs*, 3 *palas*, after sunrise, and then the *Rōhiṇī nakshatra*, which continued up to 11 *ghaṭīs*, 18 *palas*, after sunrise on the next day, Wednesday; and that, consequently, the *Abhijit muhūrta*, being the eighth in order among the *muhūrtas*, and beginning after the expiration of fourteen *ghaṭīs* after sunrise, occurred, as required by the record, while the *Rōhiṇī nakshatra* was current. He also finds that the same conditions of the *nakshatra* and the *muhūrta* did not occur, if the given *tithi* is treated as belonging to Śaka-Samvat 627 or 629 current:

The result, therefore, answers, as is required, to the running difference of two hundred and forty-two years between current Gupta-Valabhi and current Śaka years; and to the treatment of the Gupta year as a northern Śaka year. And it gives Śaka-Samvat 628 current (A.D. 705-706), as the equivalent of the given current Gupta year. But, like the result for the date in the *Ēraṇ* pillar inscription of Budhagupta, it does not, in itself, prove conclusively either the exact epoch of the era, or the scheme of the year; for the reason that, being a date in a bright fortnight, this *Jyēshṭha śukla 1* was the same *tithi*, and ended on the same solar day, represented by the 28th April, all over India, in the southern as well as the northern Śaka-Samvat 628, and in southern Vikrama-Samvat 762, as well as in northern Vikrama-Samvat 763.

The Mōrbi Grant of the year 586.

The last date that I have to notice from the present point of view, is contained in the **Mōrbi grant of Jāiṅka**, from *Kāṭhiawād*, published by Dr. R. G. Bhandarkar in the *Ind. Ant.* Vol. II. p. 257 f. The record includes two dates. In line 16 f., in connection with the making of the grant, we have (from the published lithograph)—*pañch-āśītyā yutē-titē samānām śata-panchakē 1 Gōptē dadāv-adō nṛipaḥ s-ōparāgē-rkka-maṇḍalē 11*,—"five centuries of years, together with eighty-five (*years*), having passed by, the king gave this (*charter*) at (*the village of*) Gōpta, when the disc of the sun was eclipsed;" in which the year is expressly coupled with a word meaning "expired." And in line 19 f., in connection with the writing of the charter, we have—*samvat 585 Phālguna su(śu) di 5*,—"the year 585; the month Phālguna; the bright fortnight; the (solar) day 5;" without any indication whether the year is an expired one, or current. The eclipse is also mentioned in line 3, in the words — *mārttaṇḍa-maṇḍal-āśrayiṇi Svavbhānō (read Svarbbhānau)*,—"while *Svarbbhānu* (*i.e.* *Rāhu*, the personified ascending node) is resting on the disc of the sun."

There is some difficulty in disposing finally of the whole bearing of this record, owing to the fact that the first plate was lost sight of, without being procured for

¹ Śaka-Samvat 628 current commenced rather early, on, approximately, Sunday, the 1st March, A.D. 705. And hence the reason why the month *Jyēshṭha*, which ordinarily answers to May-June, commenced on the 28th April, and of course ended before the end of May.

examination at all; and now, even the second plate also, the published one, has been mislaid and is not forthcoming. And I have to point out that, in the second part of the verse, Dr. R. G. Bhandarkar read *Gauptē*, instead of *Gōptē*; and translated "five hundred and eighty-five years of the Guptas having elapsed." The lithograph, however, shews distinctly that the original has *Gōptē*; and it is only by the correction of *δ* into *au* that the name of the Guptas can be introduced into the passage.¹ But, even then, the adjective *Gauptē* occupies an irregularly detached place, which any skilful composer would have avoided, from the noun, *sata-pañchakē*, which it qualifies. While, on the other hand, I have shewn, in my remarks on the nomenclature of the era, at page 19 ff. above, that we have no reason at all to look for the use of such an adjective as *Gaupta*, 'belonging to the Guptas;' and, if we maintain the original reading of *Gōptē*, we have a locative case, which we have every reason to expect in immediate connection with the verb *dadau*, "he gave," and which will then give us the name of the village at which the grant was made. And, until the original first plate of the grant is produced, to prove that *Gōpta* was not the name of the village,² or otherwise to explain the passage, this is the reading and interpretation that I adopt.

In accordance, however, with the palæography of the grant, I see no reason for referring the date to any except the Gupta-Valabhī era; irrespective of the question whether the era is mentioned by name, or not. This record, therefore, gives us, for calculation, an **eclipse of the sun**, which took place on some unspecified date in Gupta-Samvat 586 current, as the original text specifies that the year 585 had expired. And, on the analogy of the Verāwal inscription of Valabhī-Samvat 945, the eclipse should be found in Gupta-Samvat 586 + 242 = Śaka-Samvat 828 current, somewhere between³ the 10th March, A.D. 905, and the 27th February, A.D. 906. Also, it should, presumably, be visible at the place at which the grant was made on the occasion of it. And, though there is nothing, in the existing remnant of the record, to indicate with certainty the exact locality to which it belongs, still there is nothing against the supposition that it really belongs to *Mōrbī* itself, or to that neighbourhood. We have, therefore, to look for a solar eclipse, occurring in Śaka-Samvat 828 current, and visible at *Mōrbī*, or near that town, in the north of *Kāthiawād*.

¹ The mistake of *δ* for *au* does occur in the word *svavbhānō*, for *svarbbhānau*, in line 3 of the grant. But in line 9, in the word *paurva*, the *au* is formed quite correctly and completely.

² We might easily find its present representative in the modern name of *Gōp*, which occurs in the case of a village, in *Kāthiawād*, about seventy-five miles south-west of *Mōrbī*; twenty-five miles south of *Nawānagar* or *Jāmnagar*; and fifty miles east of *Dhinkī*, where there was found the copper-plate grant of *Jākadēva*, which purports to be dated in *Vikrama-Samvat* 794 (see page 62 above, note 1)

³ Of course, as it could only take place at a new-moon conjunction, it did not occur on the given solar day for the writing of the charter.—The limits within which we must look for it, are the first and the last days of Śaka-Samvat 828 current, as given in *Indian Eras*, p. 167.

General Cunningham's Table¹ mentions no solar eclipse, as having occurred during the period defined above. But, by calculations from Prof. K. L. Chhatre's Tables, Mr. Sh. B. Dikshit finds² that there was an eclipse of the sun, on Tuesday, the 7th May, A.D. 905, corresponding to the new-moon *tithi* of the *Pūrṇimānta* northern Jyēshṭha of Śaka-Samvat 828 current, which fully answers the required conditions.³ It was visible at Mōrbi; over almost the whole of Southern India; and in Ceylon. The magnitude, at Mōrbi, was one ninth of the sun's disc; and, in the southern parts of India, greater than this. And the middle of the eclipse, at Mōrbi, was at 12.9 midday of the Mōrbi mean civil time. This eclipse, accordingly, was very distinctly visible at Mōrbi; even if it was not known beforehand, from calculations.

This result, therefore, fully answers to the conditions of the record. It does not, in itself, furnish conclusive proof, either as to the exact epoch of the era, or as to the scheme of the year; for the reason that, if treated as a southern date, the day of the eclipse, represented in that case by the new-moon *tithi* of the *Amānta* southern Vaiśākha, belonged to the southern Śaka-Samvat 828, and to the southern Vikrama-Samvat 962, as well as to the northern Śaka-Samvat 828 and Vikrama-Samvat 963. But it answers, as is required, to the running difference of two hundred and forty-two years between current Gupta-Valabhi and current Saka years; and to the treatment of the Gupta year as a northern Śaka year. And it gives Śaka-Samvat 828 current (A.D. 905-906), as the equivalent of the indicated current Gupta year.

In respect of the given solar day for the writing of the charter, *viz.* the fifth solar day in the bright fortnight of the month Phālguna (February-March), as the name of the week-day is not given, the only test that we can apply is the presumption⁴ that the running number of the lunar *tithi* is the same as that of the solar day; *i.e.* that the fifth lunar *tithi* ended on the fifth solar day of the fortnight. If the year 586, connected with this solar day, is to be taken as expired, as in connection with the eclipse, this should be the case in Śaka-Samvat 828. And, by calculations for that year from Prof. K. L. Chhatre's Tables, Mr. Sh. B. Dikshit finds that the preceding new-moon *tithi*, which was that of the *Pūrṇimānta* northern Phālguna, or the *Amānta* southern Māgha, ended on Monday, the 27th January, A.D. 906; and that the fifth *tithi* of the bright fortnight of Phālguna ended

¹ See *Indian Eras*, p. 213.

² For his calculations, which are based on the apparent longitudes of the sun and the moon, he has taken the latitude and longitude of Mōrbi, which I was not then able to supply to him, as 2° 45' N. and 70° 51' E. I now find that, in Thornton's Gazetteer of India, the figures are 22° 49' N. and 70° 53' E. Mr. Sh. B. Dikshit states, however, that the difference will not palpably affect his results.

³ So also Prof. K. L. Chhatre himself obtained the same eclipse; see Dr. R. G. Bhandarkar's *Early History of the Dekkan*, p. 99, where, with a slight difference of phraseology, the eclipse is given as occurring "on the 30th of Vaiśākha, Śaka 827;" the reference being to the *Amānta* southern month and the expired Śaka year.

⁴ See page 85 above, note 1.

on Saturday, the 1st February, which was the fifth successive solar day. If this date is accepted, then the charter was written nine months after the making of the grant.¹ On the other hand, if the year 585 is here to be taken as current, there should be the same agreement of the lunar *tithi* and the solar day in Śaka-Saṃvat 827. And, for this year, Mr. Sh. B. Dikshit finds that the preceding new-moon *tithi* ended on Thursday, the 7th February, A.D. 925; and that the fifth *tithi* of the bright fortnight of Phālguna ended on Tuesday, the 12th February, which was again the fifth successive solar day. If this date is accepted, then the charter was prepared two months before the actual making of the grant.

It may perhaps be argued, hereafter, in opposition to my results for the exact epoch of the era, that all the Gupta-Valabhi dates are recorded in expired years, whether the fact is distinctly stated or not; and, consequently, that it is as an expired year, not current, that the year 165 of the Êraṇ pillar inscription is equivalent to A.D. 484-85 current, and that the year 585 expired, of the present record, is equivalent to A.D. 904-905 current. In that case, the solar eclipse would have to be found in Gupta-Saṃvat 585+242=Śaka-Saṃvat 827 current, somewhere between² the 21st March, A.D. 904, and the 9th March, A.D. 905. During this period, there were two eclipses of the sun;³ on Saturday, the 16th June, A.D. 904, corresponding to the new-moon *tithi* of the *Pūrṇimānto* northern Āshādha of Śaka-Saṃvat 827 current; and on Saturday, the 10th November, A.D. 904, corresponding to the new-moon *tithi* of the *Pūrṇimānto* northern Mārgaśīrṣa of the same Śaka year. In respect of the first of them, Mr. Sh. B. Dikshit finds that it was not visible anywhere in India; but only in the more northern parts of the earth. This, therefore, cannot be the eclipse intended. In respect of the second of them, he finds that it was visible at Mōrbi; over more than half the northern part of Kāthiāwāḍ; and, to the south, along the coast, as far as Surat, one hundred and seventy miles south-east of Mōrbi, and in the interior, a little further still. And, at Mōrbi, the middle of the eclipse was at 11.54 A.M. of the Mōrbi mean civil time. At Ahmadābād, one hundred and twenty miles east by north from Mōrbi, one twelfth of the sun's disc was eclipsed; and, in the more northern parts of India, a considerably greater surface. But, at Mōrbi itself, the magnitude of the eclipse was very small; extending there to only one twenty-fifth part

¹ There is nothing in the record itself, to indicate whether the writing of the charter preceded, or followed, the making of the grant. The Rājim grant of Tivaradēva, No. 81, page 291, furnishes another similar instance. In that instance, the grant was made on the eleventh *tithi* of Jyēṣṭha (May-June), while the charter was written, or assigned, on the eighth solar day of Kārttika (October-November); and there is nothing to shew specifically whether it was the following, or the preceding, Kārttika. That charter may have been written, or assigned, either five months after, or seven months before, the making of the grant recorded in it.

² See *Indian Eras*, p. 167.

³ See *Indian Eras* p. 213.

of the disc.¹ This eclipse, therefore, setting aside all other considerations, is not in any way as satisfactory as that of the 7th May, A.D. 905.

The use of the Twelve-Year Cycle of Jupiter in Records of the Early Gupta period.

I now come to a still more interesting and important part of my inquiry; *vis.* to the use of the Twelve-Year Cycle of Jupiter in the dates of some of the records of the Early Gupta period.

These dates are found in the inscriptions of the Parivrājaka *Mahārājās* Hastin and Sankshōbha, No. 21, page 93, to No. 25, page 112. And the extreme value of the records, from the present point of view, is due to the fact that in each instance, except in No. 24, page 110,² the date is directly connected with an expression which shews explicitly that, at the time mentioned, the Gupta sovereignty was still enduring; and consequently,—since the figures of the years are naturally referable to the same uniform series with the years quoted in the records of the Early Guptas themselves; and since the palæography of the inscriptions is entirely in favour of such a reference,—which shews also that the dates are recorded in the identical era that was used by the Early Gupta kings.

The evidence derivable from these records has hitherto been completely misapplied; in consequence of the adoption of the view, that the duration of any *samvatsara* or year of this cycle, is the same with that of the years of the Śaka era, from Chaitra śukla 1 to Chaitra krishṇa 15; and that the means of exactly determining the *samvatsaras* of this cycle, are provided by the last remainder obtained from certain rules given by Varāhamihira and others, which in reality only shews what *samvatsara* of the Sixty-Year Cycle of the same planet according to the Northern System, and of the Twelve-Year Cycle according to the mean-sign system, is current at the commencement of any given Śaka or Kaliyuga year, and which does not provide for the determination of the *samvatsaras* on any other given date in the year.³

¹ Mr. Sh. B. Dikshit has not made actual calculations for the village of Gōp (see page 98 above, note 2); but is able to state that both the eclipses, of the 7th May, A.D. 905, and of the 10th November, A.D. 904, were visible there; the circumstances of the former eclipse, in respect of visibility, being more favourable, and those of the latter being less so, at Gōp than at Mōrbi.

² For the possible explanation of the omission in this instance, see page 8 above.

³ See, for instance, *Indian Eras*, p. 26 ff.—This interpretation of the rules in question leaves unutilized, and unexplained, the first remainder, obtained from the division by 3750 according to Varāhamihira's rule, and by 1875 according to the rule of the *Jyōtishṭava*. In connection with the *Jyōtishṭava* rule, however, Warren has shewn (*Kala-Sankalita*, p. 202) how this remainder gives the means of determining the actual commencement of each *samvatsara*.—From the use of some Tables drawn up by Mr. Sh. B. Dikshit, for determining the actual commencement of each *samvatsara* of the Sixty-Year Cycle according to the Northern System, and of each *samvatsara* of the Twelve-Year Cycle

The correct theory of the cycle, according to the requirements of the system actually applied in the records now under consideration, with the proper method of determining each of the *samvatsaras*, has now been demonstrated by Mr. Sh. B. Dikshit, in his paper which is published as Appendix III. below. And, by calculations based on the *Sūrya-Siddhānta*, he has worked out all the results required for a full treatment of the dates in question; giving the full English and Hindu dates throughout, in order that both European and Hindu astronomers may be in a position to easily check his results. In publishing his results, I am confident that no essential errors can be established in them; even though it should be shewn, by more exhaustive calculations, that his longitudes for the heliacal risings of Jupiter are capable of slight corrections.¹ And, as will be seen, his results corroborate, in the most emphatic manner, all that has been established in the preceding pages; first, approximately, from the statements of Albērunī, the Mandasōr inscription of Mālava-Samvat 529 expired, and the Eraṇ pillar inscription of Budhagupta of Gupta-Samvat 165; and then, exactly, by the Verāwal inscription of Valabhi-Samvat 945.

It is not essential, for the most part, to enquire whether any of the dates, which give correct results with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, also give, by coincidence, correct results with any of the suggested earlier epochs. And, indeed, to make any such inquiry systematic and thorough, it would be obligatory to make the calculations, throughout, for at least a dozen years or so before and after the proposed epochs. Such inquiries are certainly unnecessary in respect of any epoch as early as that proposed by Mr. Thomas. It seemed worth while, however, to calculate the dates now under consideration, and to give the results, for the epochs proposed by General Cunningham and Sir E. Clive Bayley; both of whom have dealt with the whole subject on the clear understanding that these dates are recorded in the era that was actually used by the Early Guptas themselves. And it will be seen

according to the mean-sign system, I find that, for the purposes of such rules as that given by Varāhamihira in the *Bṛhat-Samhitā*, viii. 20, 21, the Śaka years must be treated as commencing with the *Mēsha-Samkrānti* or entrance of the Sun into Aries, and not with Chaitra śukla 1, though the latter is the initial day that is required for the notation of *tithis*. For instance, by Varāhamihira's rule, the Viśvāvasu *samvatsara* of the Sixty-Year Cycle was current at the commencement of Śaka-Samvat 748 current (A.D. 825-26); and, by Gen. Cunningham's extension of the rule (*Indian Eras*, p. 27), the Mahā-Āśvayuja *samvatsara* of the Twelve-Year Cycle was current on the same date. In Śaka-Samvat 748, the *Mēsha-Samkrānti* occurred on the 21st March, A.D. 825; and Chaitra śukla 1 ended on the 22nd February. The Viśvāvasu *samvatsara* of the Sixty-Year Cycle according to the Northern System, and, with it, the Mahā-Āśvayuja *samvatsara* of the Twelve-Year Cycle by the mean-sign system, actually commenced on the 15th March; and thus they were current at the *Mēsha-Samkrānti*, but not on Chaitra śukla 1. And the same will often happen when the *samvatsaras* are commencing shortly before the *Mēsha-Samkrānti*. This application of such rules as that given by Varāhamihira, is, in fact, the natural one; though it may not be apparent at first sight. For, the *Mēsha-Samkrānti* is a very definite point in the year, whereas, Chaitra śukla 1 is always shifting backwards and forwards by about eleven and nineteen days at a time, and its circumstances could not be met by any such hard-and-fast rules.

¹ See, e.g., page 110 below, note 1.

that, with the same heliacal-rising system that is applied to prove the epoch of A.D. 319-20, the results, as a whole, emphatically fail. In calculating the details with these two epochs, as with the epoch that I am proving, the Gupta year has been treated as a Śaka year, commencing with Chaitra śukla 1, and with the *Pārnimānta* northern arrangement of the lunar fortnights. In some of the cases in which, by this treatment, and with these two epochs, the results fail, more favourable results might be obtained by adopting a year commencing with, either the preceding, or the following, Kārttika śukla 1; and by slightly varying the proposed epochs accordingly. But a full consideration of the details will shew that, with neither of these two epochs, as they stand, and probably with no epochs in any way approximating to them, is there any method of bringing out perfectly uniform results throughout.

It might, however, be claimed that General Cunningham's epoch, or Sir E. Clive Bayley's, or even both of them, could be proved, for the present records, by the other system of the Twelve-Year Cycle; according to which the *samvatsaras* are determined by the passage of Jupiter among the signs of the zodiac; and which is, in fact, the system that they have sought to apply in support of their theories. The results, therefore, according to this system also, will be given. It will be seen that it is not the system which applies to the epoch that I am proving; inasmuch as it gives correct results in only two cases out of the four by which any absolute proof can be established;¹ *viz.* in the case of the grant B. dated in Gupta-Samvat 163, and in the case of the grant C. dated in Gupta-Samvat 191. As regards General Cunningham's and Sir E. Clive Bayley's epochs, it has always been recognised that this system fails in the case of the grant B. dated in Gupta-Samvat 163, unless the given year is deliberately altered from 163 to 173. As there is really no justification for this alteration of the original text,² the failure of the system even in this instance alone, is enough to shew that the proposed epochs are not sustainable by means of it. But further, though the fact has not hitherto been recognised, the system fails also in respect of another of the records. Thus, in the case of the grant C. dated in Gupta-Samvat 191, the given *samvatsara* really was current at the commencement of the given year, in accordance with the rules applied by General Cunningham, and accepted by Sir E. Clive Bayley, from which, however, it was not properly to be inferred that it was current through the whole of the same year; but it came to an end, and was followed by the next *samvatsara*, with General Cunningham's epoch, nearly three and a half months, and with Sir E. Clive Bayley's epoch, nearly seven months, before the sub-

¹ The date in the Bhumard pillar inscription, E. below, furnishes no definite proof in itself; because the current Gupta year is not mentioned in it; and consequently the given *samvatsara* could be proved equally well for epochs differing by a year or more, on either side, from the exact epochs that are being considered. We can only test it, in so far as to see whether, under any particular circumstances, the system fails through an omission of the given *samvatsara*.

² See Texts and Translations, page 102, note 1.

sequent given date in that year. In fact, out of the four leading dates on which any arguments can be based, with these two epochs this system gives correct results only in respect of the grant A. dated in Gupta-Samvat 156, and the grant D. dated in Gupta-Samvat 209. And, as with the heliacal-rising system, so with this system also, a full consideration of the details will shew that, even by adopting a scheme for the Gupta year other than the scheme of the northern Śaka year, with neither of these two epochs is there any method of bringing out uniform results throughout.

A.—The Khôh Grant of the year 156.

The first inscription is one of the Khôh grants of the Mahârâja Hastin, No. 21, page 93; in which the date (line 1 ff.) is — *shatpāñchāś-ōttarē-bda-satē Gupta-nripa-rājya-bhuktau Mahā-Vaiśākha-samvatsarē Kārttika-māsa-śukla-paksha-tritīyāyam*, — “in a century of years, increased by the fifty-sixth (year); in the enjoyment of sovereignty by the Gupta kings; in the Mahā-Vaiśākha *samvatsara*; on the third lunar day of the bright fortnight of the month Kārttika.”

This gives us, for calculation, the Mahā-Vaiśākha *samvatsara*, as current on the third *tithi* or lunar day of the bright fortnight of the month Kārttika (October-November) in Gupta-Samvat 156 current. And, on the analogy of the Verāwal inscription of Valabhi-Samvat 945, this should be the case in Gupta-Samvat 156 + 242 = Śaka-Samvat 398 current;¹ in which year the given *tithi* corresponds to Sunday, the 19th October, A.D. 475.

Mr. Sh. B. Dikshit finds (see Table IV. page 105 below, Col. A.) that Jupiter's rising,² next before the given date, took place on Kārttika śukla 1 of the same year, Śaka-Samvat 398 current, corresponding to Friday, the 17th October, A.D. 475; or, by the English calendar, on Saturday, the 18th October.³ His longitude then was

¹ Here, and throughout, the year is treated as a northern year. But the details of these dates do not furnish any actual proof as to the *Pūrṇimānta* or *Amānta* arrangement of the lunar fortnights.

² *i.e.*, throughout, his heliacal rising. But the actual calculation is for his first daily rising after his becoming capable of rising heliacally.

³ Jupiter's daily rising, next after his becoming capable of rising heliacally, takes place about forty-four minutes before sunrise, and therefore in the period during which the Hindu and the English week-days are not identical (see a note in Appendix II. below). In the present case, it took place at the time in question before sunrise on the English Saturday, the 18th October. Kārttika śukla 2 did not end till after sunrise on that day. Consequently, as current *tithis* are not quoted, unless under certain very exceptional conditions not applicable to such occurrences as this, the *tithi* on which he rose was Kārttika śukla 1. And this *tithi*, ending after sunrise on the Friday (and before sunrise on the Saturday), has to be coupled with Friday, the 17th October, as its week-day. Hence the apparent, but not actual, difference of a day, according as we take the Hindu or the English calendar. And a similar difference runs through all the dates of the heliacal risings given below.

TABLE IV.
The Samvatsaras of the Twelve-Year Cycle of Jupiter.

	A	B	C	D	E 1	E 2
inpta year, current	156	163	191	209	189	201
add the difference of	242	242	433	212	242	242
saka year, current	398	405	433	451	431	443
the given samvatsara	Mahā-Vaiśākha	Mahā-Āsvayuja	Mahā-Chaitra	Mahā-Āsvayuja	Mahā-Māgha	Mahā-Māgha
the given date	Kārttika śukla 3	Chaitra śukla 2	Māgha krishna 3	Chaitra śukla 13	Kārttika, 19th day	Kārttika, 19th day
corresponding to	19th October, A.D. 475	7th March, A.D. 482	3rd January, A.D. 511	19th March, A.D. 548	13th October, A.D. 508	2nd October, A.D. 520
Jupiter's preceding rising was on	Kārttika śukla 1 of Saka 398	Vaiśākha krishna 6 of Saka 404	Āsvina śukla 11 of Saka 433	Chaitra śukla 12 of Saka 451.	Śrāvana śukla 15 of Saka 431	Bhādrapada śukla 3 of Saka 443
corresponding to	17th October, A.D. 475	5th April, A.D. 481	29th September, A.D. 510	18th March, A.D. 528	28th July, A.D. 508	2nd August, A.D. 520
English date	18th October	6th April	30th September	19th March	20th July	3rd August
longitude then was	195° 24'	6° 21'	177° 47'	347° 45'	117° 4'	121° 30'
position was in	Vaiśākha	Āsvini	Chitrā	Révatī	Māgha	Māgha
And the samvatsara, which then began, was	Mahā-Vaiśākha	Mahā-Āsvayuja	Mahā-Chaitra	Mahā-Āsvayuja	Mahā-Māgha	Mahā-Māgha
Jupiter's following rising was on	Mārgaśrēsha śukla 13 of Saka 399	Jyēshtha śukla 8 of Saka 405	Mārgaśrēsha krishna 7 of Saka 434	Jyēshtha śukla 3 of Saka 452	Āsvina krishna 13 of Saka 432	Āsvina krishna 1 of Saka 444
corresponding to	15th November, A.D. 476	12th May, A.D. 482	29th October, A.D. 511	26th April, A.D. 529	29th August, A.D. 509	3rd September, A.D. 521
English date	16th November	13th May	30th October	27th April	30th August	4th September
longitude then was	225° 35'	40° 34'	202° 41'	24° 36'	147° 40'	152° 11'
position was in	Jyēshthā	Rōhini	Vaiśākha	Kṛittikā	Uttarā-Phalgunī	Uttarā-Phalgunī
And the samvatsara, which then began, was	Mahā-Jyēshtha	Mahā-Kārttika	Mahā-Vaiśākha	Mahā-Kārttika	Mahā-Phalgunā	Mahā-Phalgunā

195° 24'. By both the systems of unequal spaces for the longitudes of the ending-points of the *nakshatras* (see Appendix III. Table IX.), he was then in Viśākhā; and the *samvatsara* which then began (see Appendix III. Table VIII.), must have been named **Mahā-Vaiśākha**.¹ Jupiter's next following rising took place on Mārgaśirsha śukla 13 of Śaka-Samvat 399, corresponding to Monday, the 15th November, A.D. 476; or, by the English calendar, on Tuesday, the 16th November. His longitude then was 225° 35'. By the Brāhma-Siddhānta system of unequal spaces, he was then in Jyēshthā; and the *samvatsara* which then began, must have been named Mahā-Jyēshtha. While, by the Garga system of unequal spaces, he was then in Anurādhā; and the *samvatsara* which then began, must have again been named Mahā-Vaiśākha, which shews that, by this system, there was at this period a repetition of a *samvatsara*. This difference as to the following *samvatsara*, however, does not affect the given date. By both the systems of unequal spaces, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, **the Mahā-Vaiśākha samvatsara was current on the given date**. And the result gives Śaka-Samvat 398 current (A.D. 475-76), as the equivalent of the given current Gupta year.

In connection with the results for this record, the following points have to be noted. In the first place, Mr. Sh. B. Dikshit has described three systems of fixing the ending-points of the *nakshatras*; one of equal spaces; and two of unequal spaces. An examination of Jupiter's longitudes, as given in Table IV., page 105 above, for each rising next before the given dates, will shew that, in all the remaining instances, the current *samvatsara* is proved by all three systems; the only variation is that, in the case of E1, Jupiter's position, at his rising next before the given date, was, by the system of equal spaces, in Āślēshā; but, even then, the current *samvatsara* would be named Mahā-Māgha, as also by the two systems of unequal spaces. So, also, it may be seen that, by all three systems, we have almost the same results in respect of the following *samvatsaras*; the only variation is that, in the case of D., Jupiter's position, at his rising next after the given date, was, by the system of equal spaces, in Bharāṇī, and, accordingly, the *samvatsara* which then began, would again be named Mahā-Āśvayuja; which shews that, by this system, there was a repetition of a *samvatsara* at this period; but this does not affect the *samvatsara* current on the given date. So far, therefore, as those dates are concerned, the correctness of the records might be proved by any of the three systems. The same, however, is not the case in respect of the present record. By the system of equal spaces, Jupiter's position, at his rising next before the given date, was in Svāti; the *samvatsara* which then began, would

¹ I have not been able to obtain the original authority for the use of the prefix *mahā* (*mahat*), 'great'. And it does not occur in connection with the two *samvatsaras* mentioned in the Halsi grants of the Kādamba chieftain Mrigēśavarman: *vis.* the Pausha *samvatsara*, in line 8 of the grant dated in his third year (*Ind. Ant.* Vol. VII. p. 35) and the Vaisakha *samvatsara*, in line 10 of the grant dated in his eighth year (*id.* Vol. VI. p. 24). I use the prefix, however, throughout, in accordance with the custom of the original records now under examination.

be named Mahā-Chaitra; and the Mahā-Vaiśākha *samvatsara* would not begin till Jupiter is rising next after the given date, when, by the same system, his position was in Anurādhā. Accordingly, the system of equal spaces could be applied to the present record, only with a running difference of two hundred and forty-three years between current Gupta and current Śaka years; which would be in contradiction with the fact that, to prove the *samvatsaras* of all the remaining records, it must be applied with the running difference of two hundred and forty-two years. It is evident, therefore, that, in dealing with these records, the system of equal spaces is not the correct one; and that **we have to apply one or other of the systems of unequal spaces.** This, however, is only natural; for they are both more ancient than the system of equal spaces; and, the older the system, the greater the certainty that it is the one in use in the Early Gupta period. Also, the Dēḡgadh inscription of king Bhōjadēva of Kanauj, dated Śaka-Samvat 784, indicates very plainly that one or other of the systems of unequal spaces, if not both of them, continued in use, in what had formed a part of the Early Gupta territory, down to at least the last half of the ninth century A.D.¹ Of the two systems of unequal spaces, whether we are to apply the Brahma-Siddhānta system, or the still more ancient Garga system, cannot at present be decided;

¹ In this inscription, which was brought to notice by Gen. Cunningham in the *Archæol. Surv. Ind.* Vol. X p. 101, and Plate xxxiii. No. 2, and is on a pillar in a detached portico in front of the hall of a temple at Dēḡgadh, about sixty miles to the south-west of 'Jhansi' in Scindia's Dominions in Central India, the date (from an ink-impression; lines 6 ff., 10) runs—*samvat 919 Asva(śva)nyuja-śukla-pakṣa-chaturdaśyān Vrihaspati-dinēna Uttar[ā*]-Bhādrapad[ā*]-nakṣhatrē idam stambham samāptam=iti Sakakāl-śōḍa-sapta-śatāni chatur-aṣṭy-adhikāni 784.*—"the year 919; on the fourteenth *tithi* or lunar day in the bright fortnight of *Āśvayuja*, on the day of *Vrihaspati*; under the *Uttarā-Bhādrapadā nakṣatra*, this pillar was finished, seven centuries of years, increased by eighty-four, of the Śaka era, (or in figures) 784." This gives us, for calculation, *Vikrama-Samvat* 919 and *Śaka-Samvat* 784; the month *Āśvayuja* (September-October); the day of *Vrihaspati* or Jupiter, *i.e.* Thursday; and the *Uttarā-Bhādrapadā nakṣatra*. The date, of course, is a northern date, but, as the given *tithi* is in a bright fortnight, this point is immaterial.—Taking the Śaka year in question as an expired year, Mr. Sh. B. Dikshit has obtained as the English equivalent, by both Prof. K. L. Chhatre's Tables and the *Sāra-Siddhānta*, Thursday, the 10th September, A.D. 862. The *tithi* ended at 56 *ghaṭis*, 34 *palas*, or 22 hrs. 37 min. 36 sec., after sunrise on that day. By the equal-space system of the *nakṣatras*, the moon was in the *Pūrvā-Bhādrapadā nakṣatra* up to 53 *ghaṭis*, 31 *palas*, or 21 hrs. 24 min. 24 sec., after sunrise on the Thursday; and she then entered the *Uttarā-Bhādrapadā nakṣatra*, *i.e.* assuming sunrise at 6 A.M., only 2 hrs. 35 min. 36 sec. before sunrise on the Friday (the time, all through, is for Ujjain, as I have not the exact longitude of Dēḡgadh; taking it, approximately, as 78° 15' E., the time in each case, will be a little less than ten minutes later). This, however, is a highly improbable hour for the completion, as stated in the record, of the pillar on which the inscription is engraved. But, by the unequal-space systems of the *nakṣatras*, the *Pūrvā-Bhādrapadā nakṣatra* ended at about 23 *ghaṭis*, 40 *palas*, or 9 hrs. 28 min., after sunrise on the Thursday; and the moon then entered the *Uttarā-Bhādrapadā nakṣatra*; *i.e.*, roughly, about half past three in the afternoon, leaving ample time, in ordinary working hours, for the completion of the pillar before sunset.—It is evident, therefore, that for the determination of the *nakṣatra* in this record, we have to apply one or other of the systems of unequal spaces.

since, the only variation between them is in respect of the *samvatsara* following the *samvatsara* which was current on the given date of the present record.

Another point is, that, as the following *samvatsara* did not commence till Mārgaśirsha śukla 13 of Śāka-Samvat 399, the Mahā-Vaiśākha *samvatsara* was still current on the given date, Kārttika śukla 3, in Śāka-Samvat 399, as well as in 398, which is the real equivalent for the Gupta year. So, also, it will be seen that, in the case of D., the Mahā-Āśvayuja *samvatsara* was still current on the given date, Chaitra śukla 13, in Śāka-Samvat 452, as well as in 451, which is the true equivalent for the Gupta year of that record. Consequently, these two dates, A. and D., might be used to support a running difference of two hundred and forty-three years between current Gupta and current Śāka years, as well as the true running difference of two hundred and forty-two years. But, apart from the fact that we have not obtained anything else to support such a result, there is no such alternative in respect of B and C., the *samvatsaras* of those records are proved only with the running difference of two hundred and forty-two years. All the four cases together, therefore, not only answer to, but also **prove the running difference of two hundred and forty-two years between current Gupta and current Śāka years.**

A final point is, that, on the analogy of the Kaira grant of Dharasēna IV., of the year 330, and with a year beginning with the month Kārttika next before the commencement of the northern Śāka year, the given date of Kārttika śukla 3, in Gupta-Samvat 156, would belong to Śāka-Samv. 397 current. But it would then fall a year, all but two days, anterior to the commencement of the recorded *samvatsara* on Kārttika śukla 1 of Śāka-Samvat 398. This record, therefore, also **disproves the possibility of our being concerned with the scheme of the southern Vikrama year**, beginning with the month Kārttika next before the commencement of the northern Śāka year.

On the analogy of the same grant, and with a year, northern or southern, beginning with the month Mārgaśirsha next before the commencement of the northern Śāka year,¹ the given date would still belong to Śāka-Samvat 398. The possibility, however, of our being concerned with such a year as this, is disproved by the results for the date of C. below, in Gupta-Samvat 191.

By the mean-sign system, the Mahā-Vaiśākha *samvatsara* did not commence till Vaiśākha śukla 5 of Śāka-Samvat 399 current, corresponding to Wednesday, the 14th April, A.D. 476, and consequently it was not current on the given date. The *samvatsara* then current was Mahā-Chaitra, which commenced on Jyēsthā kṛishṇa 13 of Śāka-Samvat 398, corresponding to Saturday, the 19th April, A.D. 475.

With General Cunningham's epoch of A.D. 166-67, the given date would belong to Śāka-Samvat 245 current; and its English equivalent would be Sunday, the 30th Septem-

¹ See page 78 above.

ber, A.D. 322. Mr. Sh. B. Dikshit finds that Jupiter's rising, next before the given date, took place on Kārttika śukla 13 of Śaka-Samvat 244, corresponding to Friday, the 20th October, A.D. 321; or, by the English calendar, on Saturday, the 21st October. His longitude then was $200^{\circ} 54'$. By all three systems, he was then in Viśākhā; and the *samvatsara* which then began, must have been named **Mahā-Vaiśākha**. Jupiter's next following rising took place on Pausha kṛishṇa 10 of Śaka-Samvat 245, corresponding to Tuesday, the 20th November, A.D. 322; or, by the English calendar, on Wednesday, the 21st November. His longitude then was $231^{\circ} 33'$. By the system of equal spaces, and the Garga system of unequal spaces, he was then in Jyēshṭhā; and, by the Brahma-Siddhānta system of unequal spaces, in Mūla; and, by all three systems, the *samvatsara* which then began, must have been named Mahā-Jyēshṭha. Accordingly, with this epoch, **the Mahā-Vaiśākha samvatsara was current on the given date**. This, however, is a mere coincidence. There is the same coincidence in respect of the date of D.; but not in respect of B. and C.

By the mean-sign system, the Mahā-Vaiśākha *samvatsara* commenced on Phālguna kṛishṇa 15 of Śaka-Samvat 244 current, corresponding to Friday, the 2nd February, A.D. 322; and it was followed by Mahā-Jyēshṭha on Phālguna śukla 6 of Śaka-Samvat 245, corresponding to Tuesday, the 29th January, A.D. 323. Accordingly, with this epoch, and by this system also, **the Mahā-Vaiśākha samvatsara was current on the given date**.

With Sir E. Clive Bayley's epoch of A.D. 190-91, the given date would belong to Śaka-Samvat 269 current; and its English equivalent would be Saturday, the 4th October, A.D. 346. Here, Jupiter's rising, next before the given date, took place on Mārgaśirsha kṛishṇa 3 of Śaka-Samvat 268, corresponding to Tuesday, the 29th October, A.D. 345; or, by the English calendar, on Wednesday, the 30th October. His longitude then was $209^{\circ} 22'$. By all three systems, he was then in Viśākhā; and the *samvatsara* which then began, must have been named **Mahā-Vaiśākha**. Jupiter's next following rising took place on Pausha kṛishṇa 15 of Śaka-Samvat 269, corresponding to Saturday, the 29th November, A.D. 346; or, by the English calendar, on Sunday, the 30th November. His longitude then was $240^{\circ} 17'$. By all three systems, he was then in Mūla; and the *samvatsara* which then began, must have been named Mahā-Jyēshṭha. Accordingly, with this epoch also, **the Mahā-Vaiśākha samvatsara was current on the given date**. This again, however, is a mere coincidence. And again, though there is the same coincidence in respect of the date of D., it does not occur in respect of B. and C.

By the mean-sign system, the Mahā-Vaiśākha *samvatsara* commenced on Kārttika śukla 11 of Śaka-Samvat 268 current, corresponding to Wednesday, the 23rd October, A.D. 345; and it was followed by Mahā-Jyēshṭha on Mārgaśirsha kṛishṇa 3 of Śaka-Samvat 269, corresponding to Sunday, the 19th October, A.D. 346. Accordingly, with

this epoch again, and by this system also, the **Mahā-Vaiśākha samvatsara was current on the given date.**

B.—The Khôh Grant of the year 163.

The next inscription is the other Khôh grant of the Mahârâja Hastin, No. 22, page 100, in which the date (line 1 f.) is — tri-shashty-uttarê-bda-fatê Gupta-nripa-râjya-bhuktau Mah-Âśvayuja-samvatsarê Chaitra-mâsa-śukla-paksha-dvitiyâyâm,—“in a century of years, increased by sixty-three, in the enjoyment of sovereignty by the Gupta kings; in the Mahâ-Âśvayuja *samvatsara*; on the second lunar day of the bright fortnight of the month Chaitra.”

This gives us, for calculation, the **Mahâ-Âśvayuja samvatsara**, as current on the second *tithi* or lunar day of the bright fortnight of the month Chaitra (March-April) in Gupta-Samvat 163 current. And, on the analogy of the Verāwal inscription of Valabhi-Samvat 945, this should be the case in Gupta-Samvat 163 + 242 = Śaka-Samvat 405 current, in which year the given *tithi* corresponds to Sunday, the 7th March, A. D. 482.

Mr. Sh. B. Dikshit finds (see Table IV. page 105 above, Col. B.) that Jupiter's rising, next before the given date, took place¹ on Vaiśākha kṛṣṇa 6 of the preceding year, Śaka-Samvat 404 current, corresponding to Sunday, the 5th April, A. D. 481. or, by the English calendar, on Monday, the 6th April. His longitude then was 4° 21'. By both the systems of unequal spaces,² he was then in Aśvini; and the *samvatsara* which then began, must have been named **Mahâ-Âśvayuja**. Jupiter's next following rising took place on Jyêsthâ śukla 8 of Śaka-Samvat 405, corresponding to Wednesday, the 12th May, A. D. 482; or, by the English calendar, on Thursday, the 13th May. His longitude then was 4° 34'. By both the systems of unequal spaces, he was then in Rôhini; and the *samvatsara* which then began, must have been named Mahâ-Kârttika. I therefore, by both the systems of unequal spaces, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, **the Mahâ-Âśvayuja samvatsara was current on the given date.** And the result gives Śaka-Samvat 405 current (A. D. 482-83), as the equivalent of the given current Gupta year.

In this instance, the given *samvatsara* was not current on the given date in either the preceding year, Saka-Samvat 404, or the following year, Śaka-Samvat 406. The result,

¹ These calculations are not absolutely accurate, but the margin is so wide, that there is no necessity for exact precision in this case. If there should be any difference at all between Jupiter's longitudes as found by Mr. Sh. B. Dikshit, and as capable of being determined with exact precision, it will amount only to a few minutes of arc; and the actual risings of Jupiter could differ from what he gives, only by one or two days, with the result that Jupiter may have risen, in this instance, on Vaiśākha kṛṣṇa 5 or 7.

² Also by the system of equal spaces; but see page 107 above. This point need not be noted in the following instances.

therefore, not only answers to, but also proves, the running difference of two hundred and forty-two years between current Gupta and current Śaka year: s.

On the analogy of the Kaira grant of Dharaséna IV. of the year 330, and with a year beginning either with the month Kārttika, or with the month Mārgaśirsha, next before the commencement of the northern Śaka year, the given date of Chaitra śukla 2, in Gupta-Saṁvat 163, would still belong to Śaka-Saṁvat 405. But, as noted at page 108 above, the results for the date of A. disprove the possibility of our being concerned with the scheme of the southern Vikrama year, beginning with the month Kārttika next before the commencement of the northern Śaka year. And, as will be shewn at page 115 below, the results for the date of C., in Gupta-Saṁvat 191, disprove the possibility of our being concerned with a year, northern or southern, beginning with the month Mārgaśirsha next before the commencement of the northern Śaka year.

By the mean-sign system, the Mahā-Āśvayuja *samvatsara* commenced on Chaitra śukla 8 of Śaka-Saṁvat 404 current, corresponding to Tuesday, the 24th March, A.D. 481; and it was followed by Mahā-Kārttika on Chaitra śukla 15 of Śaka-Saṁvat 405, corresponding to Saturday, the 20th March, A.D. 482. Accordingly, by this system also, the Maha-Āśvayuja *samvatsara* was current on the given date.

With General Cunningham's epoch of A.D. 166-67, and with the original reading of Gupta-Saṁvat 163, the given date would belong to Śaka-Saṁvat 252 current, and its English equivalent would be Monday, the 17th February, A.D. 329. Mr. Sh. B. Dikshit finds that Jupiter's rising, next before the given date, took place on Āshādha kṛishṇa 6 of Śaka-Saṁvat 251, corresponding to Thursday, the 16th May, A.D. 328; or, by the English calendar, on Friday, the 17th May. His longitude then was $47^{\circ} 25'$. By all three systems, he was then in Rōhini; and the *samvatsara* which then began, must have been named Mahā-Kārttika. Jupiter's next following rising took place on Āshādha śukla 10 of Śaka-Saṁvat 252, corresponding to Sunday, the 22nd June, A.D. 329, or, by the English calendar, on Monday, the 23rd June. His longitude then was $82^{\circ} 12'$. By all three systems, he was then in Punarvasu, and the *samvatsara* which then began, must have been named Mahā-Pausha; the intervening *samvatsara*, Mahā-Mārgaśirsha, being omitted. Accordingly, with this epoch, and with the real reading of the text, the Mahā-Āśvayuja *samvatsara* was not current on the given date. For the commencement of the Mahā-Āśvayuja *samvatsara*, we have to go back to Jupiter's rising on Vaiśākha śukla 3 of Śaka-Saṁvat 250, corresponding to Tuesday, the 11th April, A.D. 327, or, by the English calendar, on Wednesday, the 12th April; when his longitude was $11^{\circ} 21'$, and, by all three systems, he was in Āśvini. And thus the given *samvatsara* was current on the same date in the preceding year.—With the same epoch, and with the proposed corrected reading (see Texts and Translations, page 102, note 1) of Gupta-Saṁvat 173, the given date would belong to Śaka-Saṁvat 262 current; and its English equivalent would be Tuesday, the 27th Febru-

ary, A.D. 339. Here, Jupiter's rising, next before the given date, took place on Chaitra sukla 2 of Śaka-Samvat 261, corresponding to Friday, the 10th March, A.D. 338; or, by the English calendar, on Saturday, the 11th March. His longitude then was $339^{\circ} 54'$. By all three systems, he was then in Uttará-Bhādrapadā; and the *samvatsara* which then began, must have been named Mahā-Bhādrapadā. Jupiter's next following rising took place on Jyēshtha kṛishṇa 11 of Śaka-Samvat 262, corresponding to Tuesday, the 17th April, A.D. 339, or, by the English calendar, on Wednesday, the 18th April. His longitude then was $16^{\circ} 34'$. By all three systems, he was then in Bharāṇī; and the *samvatsara* which then began, must have been named Mahā-Āśvayuja. Accordingly, with this epoch, even with the proposed corrected reading, the Mahā-Āśvayuja *samvatsara* was not current on the given date; but only on the same date in the following year.

By the mean-sign system, and with the original reading of Gupta-Samvat 163, the Mahā-Āśvayuja *samvatsara* commenced on Māgha sukla 2 of Śaka-Samvat 249 current, corresponding to Thursday, the 12th January, A. D. 327, and was followed by Mahā-Kārttika on Māgha sukla 9 of Śaka-Samvat 250, corresponding to Monday, the 8th January, A.D. 328; and consequently it was not current on the given date. The *samvatsara* then current was Mahā-Mārgaśīrsha, which commenced on Phālguna kṛishṇa 1 of Śaka-Samvat 251 current, corresponding to Friday, the 3rd January, A. D. 329.—**With the proposed corrected reading** of Gupta-Samvat 173, the Mahā-Āśvayuja *samvatsara* commenced on Pausha kṛishṇa 9 of Śaka-Samvat 261 current, corresponding to Wednesday, the 22nd November, A. D. 338; and it was followed by Mahā-Kārttika on Mārgaśīrsha sukla 1 of Śaka-Samvat 262, corresponding to Sunday, the 18th November, A. D. 339. Accordingly, with this epoch, and by this system, **with the proposed corrected reading, the Mahā-Āśvayuja *samvatsara* was current on the given date.** The proposed alteration of the original text, however, cannot be justified

With Sir E. Clive Bayley's epoch of A.D. 190-91, and **with the original reading** of Gupta-Samvat 163, the given date would belong to Śaka-Samvat 276 current, and its English equivalent would be Monday, the 22nd February, A. D. 353. Here, Jupiter's rising, next before the given date, took place on Āshādha kṛishṇa 12 of Śaka-Samvat 275, corresponding to Wednesday, the 27th May, A. D. 352; or, by the English calendar, on Thursday, the 28th May. His longitude then was $57^{\circ} 12'$. By all three systems, he was then in Mṛiga; and the *samvatsara* which then began, must have been named Mahā-Mārgaśīrsha. Jupiter's next following rising took place on Āshādha sukla 13 of Śaka-Samvat 276, corresponding to Thursday, the 1st July, A.D. 353; or, by the English calendar, on Friday, the 2nd July. His longitude then was $91^{\circ} 19'$. By all three systems, he was then in Punarvasu; and the *samvatsara* which then began, must have been named Mahā-Pausha. Accordingly, with this epoch, and with the real reading of the text, the Mahā-Āśvayuja *samvatsara* was not current on the given date. As a matter of fact, the Mahā-Āśvayuja *samvatsara* of

this cycle may have been omitted. Thus, in Śaka-Samvat 273 current, Jupiter's rising took place on Vaiśākha kṛṣṇa 6, corresponding to Friday, the 16th Mareh, A.D. 350; or, by the English calendar, on Saturday, the 17th March. His longitude then was $345^{\circ} 10'$. By all three systems, he was then in Uttarā-Bhādrapadā; and the *samvatsara* which then began, must have been named Mahā-Bhādrapada. His next rising took place on Vaiśākha śukla 10 of Śaka-Samvat 274, corresponding to Monday, the 22nd April, A.D. 351; or, by the English calendar, on Tuesday, the 23rd April. His longitude then was $21^{\circ} 35'$. By the system of equal spaces, he was then in Bharāṇī; and the *samvatsara* which then began, would be named Mahā-Āśvayuja; and there would be an omission of the following *samvatsara*, Mahā-Kārttika. But, by the two systems of unequal spaces, he was then in Kṛttikā; and the *samvatsara* which then began, would be named Mahā-Kārttika; with an omission of the intervening *samvatsara*, Mahā-Āśvayuja. — With the same epoch, and **with the proposed corrected reading of Gupta-Samvat 173** (see Texts and Translations, page 102, note 1), the given date would belong to Saka-Samvat 286 current; and its English equivalent would be Tuesday, the 4th March, A.D. 363. Here, Jupiter's rising, next before the given date, took place on Chaitra śukla 9 of Saka-Samvat 285, corresponding to Thursday, the 21st March, A.D. 362; or, by the English calendar, on Friday, the 22nd March. His longitude then was $350^{\circ} 11'$. By all three systems, he was then in Rēvati, and the *samvatsara* which then began, must have been named **Mahā-Āśvayuja**. Jupiter's next following rising took place on Jyēṣṭha kṛṣṇa 12 of Śaka-Samvat 286, corresponding to Sunday, the 27th April, A.D. 363, or, by the English calendar, on Monday, the 28th April. His longitude then was $26^{\circ} 35'$. By both the systems of unequal spaces, he was then in Kṛttikā; and the *samvatsara* which then began, must have been named Mahā-Kārttika. By the system of equal spaces, he was then in Bharāṇī, and, by this system, the *samvatsara* which then began, must have again been named Mahā-Āśvayuja; which shews that, by this system, there was at this period a repetition of a *samvatsara*. Accordingly, with this epoch, and **with the proposed corrected reading, the Mahā-Āśvayuja samvatsara was current on the given date**. This, however, is a mere coincidence. And the proposed correction of the original reading cannot be justified.

By the mean-sign system, and with the original reading of Gupta-Samvat 163, the Mahā-Āśvayuja *samvatsara* commenced on Kārttika kṛṣṇa 1 of Śaka-Samvat 273 current, corresponding to Wednesday, the 3rd October, A.D. 350; and it was followed by Mahā-Kārttika on Kārttika kṛṣṇa 8 of Śaka-Samvat 274, corresponding to Sunday, the 29th September, A.D. 351; and consequently it was not current on the given date. The *samvatsara* then current was Mahā-Mārgaśīrṣha, which commenced on Kārttika kṛṣṇa 15 of Śaka-Samvat 275 current, corresponding to Thursday, the 24th September, A.D. 352.—**With the proposed corrected reading** of Gupta-Samvat 173, the Mahā-Āśvayuja *samvatsara* commenced on Bhādrapada śukla 7 of Śaka-Samvat 285 current.

corresponding to Tuesday, the 13th August, A.D. 362, and it was followed by Mahā-Kārttika on Bhādrapada śukla 12 of Śaka-Samvat 286, corresponding to Saturday, the 9th August, A.D. 363. Accordingly, with this epoch again, and by this system also, **with the proposed corrected reading, the Mahā-Āśvayuja samvatsara was current on the given date.** But the proposed alteration of the original text cannot be justified.

C.—The Majhgawām Grant of the year 191.

The next inscription is the **Majhgawām grant of the Mahārāja Hastin**, No. 23, page 106, in which the date (line 1 f.) is — *eka-navaty-uttarā-bda-śatē Gupta-nripa-rāja-bhuktau śrīmatī pravardhamāna-Mahā-Chaitra-samvatsarē Māgha-māsa-bahula-paksha-tridīyāyām*, — “in a century of years, increased by ninety-one; in the enjoyment of sovereignty by the Gupta kings, in the prosperous augmenting Mahā-Chaitra *samvatsara*; on the third lunar day of the dark fortnight of the month Māgha.” And at the end, in line 21, the date is repeated as—*Māgha dī 3*, — “(the month) Māgha; the (solar) day 3.”

This gives us, for calculation, the **Mahā-Chaitra samvatsara**, as current on the third *tithi* or lunar day of the dark fortnight of the month Māgha (January-February) in Gupta-Samvat 191 current. And, on the analogy of the Verāval inscription of Valabhi-Samvat 945, this should be the case in Gupta-Samvat 191 + 242 = Śaka-Samvat 433 current; in which year the given date corresponds to Monday, the 3rd January, A.D. 511.

Mr. Sh. B. Dikshit finds (see Table IV. page 105 above, Col. C) that Jupiter's rising, next before the given date, took place on Āśvina śukla 11 of the same year, Śaka-Samvat 433, corresponding to Wednesday, the 29th September, A.D. 510, or, by the English calendar, on Thursday, the 30th September. His longitude then was $177^{\circ} 47'$. By both the systems of unequal spaces, he was then in Chitrā; and the *samvatsara* which then began, must have been named **Mahā-Chaitra**. Jupiter's next following rising took place on Mārgaśīrsha kṛishna 7 of Śaka-Samvat 434, corresponding to Saturday, the 29th October, A.D. 511; or, by the English calendar, on Sunday, the 30th October. His longitude then was $207^{\circ} 41'$. By both the systems of unequal spaces, he was then in Viśākhā; and the *samvatsara* which then began, must have been named **Mahā-Vaiśākhā**. Therefore, by both the systems of unequal spaces, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, **the Mahā-Chaitra samvatsara was current on the given date.** And the result gives Śaka-Samvat 433 current (A.D. 510-1), as the equivalent of the given current Gupta year.

In this instance, again, as in B above, the given *samvatsara* was not current on the given date in either the preceding year, Śaka-Samvat 432, or the following year, Śaka-Samvat 434. Here again, therefore, the result not only answers to, but also **proves, the running difference of two hundred and forty-two years between current Gupta and current Śaka years.**

On the analogy of the Kaira grant of Dharasēna IV., of the year 330, and with a year beginning with the month Kārttika next before the commencement of the northern Śāka year, the given date of Māgha kṛishṇa 3, in Gupta-Samvat 191, would belong to Śāka-Samvat 432. It would then fall about eight months and a half before the commencement of the recorded *samvatsara* on Āśvina śukla 11 of Śāka-Samvat 433. This record, therefore, like A. above, **disproves the possibility of our being concerned with the scheme of the southern Vikrama year**, beginning with the month Kārttika next before the commencement of the northern Śāka year.

Again, on the analogy of the same grant, and with a year beginning with the month Mārgaśīrsha next before the commencement of the northern Śāka year, the given date would similarly belong to Śāka-Samvat 432; and would similarly fall about eight months and a half before the commencement of the recorded *samvatsara*. This record, therefore, also **disproves the possibility of our being concerned with a year, northern or southern, beginning with the month Mārgaśīrsha** next before the commencement of the northern Śāka year.

By the mean-sign system, the Mahā-Chaitra *samvatsara* commenced on Mārgaśīrsha śukla 1 of Śāka-Samvat 433 current, corresponding to Thursday, the 18th November, A. D. 510, and it was followed by Mahā-Vaiśākha on Mārgaśīrsha śukla 8 of Śāka-Samvat 434, corresponding to Monday, the 14th November, A. D. 511. Accordingly, by this system also **the Mahā-Chaitra samvatsara was current on the given date.**

With General Cunningham's epoch of A. D. 166-67, the given date would belong to Śāka-Samvat 280 current, and its English equivalent would be Tuesday, the 16th December, A. D. 357. Mr. Sh. B. Dikshit finds that Jupiter's rising, next before the given date, took place on Mārgaśīrsha śukla 4 of the same year, Śāka-Samvat 280, corresponding to Sunday, the 2nd November A. D. 357; or, by the English calendar, on Monday, the 3rd November. His longitude then was $213^{\circ} 31'$. By all three systems, he was then in Anurādhā; and the *samvatsara* which then began, must have been named Mahā-Vaiśākha. Jupiter's next following rising took place on Pausha kṛishṇa 2 of Śāka-Samvat 281, corresponding to Friday, the 4th December, A. D. 358; or, by the English calendar, on Saturday, the 5th December. His longitude then was $244^{\circ} 49'$. By the system of equal spaces, and by the Garga system of unequal spaces, he was then in Mūla; and the *samvatsara* which then began, must, according to these two systems, have been named Mahā-Jyēshtha. By the Brahma-Siddhānta system of unequal spaces, he was then in Pūrvā-Ashāḍha; and the *samvatsara* which then began, must, according to this system, have been named Mahā-Āshāḍha; the intervening *samvatsara*, Mahā-Jyēshtha, being omitted. Accordingly, with this epoch, the Mahā-Chaitra *samvatsara* was not current on the given date. For the commencement of the Mahā-Chaitra *samvatsara*, we have to go back to Jupiter's rising on Kārttika kṛishṇa 7 of Śāka-Samvat 279, corresponding to

Thursday, the 3rd October, A.D. 356, or, by the English calendar, on Friday, the 4th October; when his longitude was $183^{\circ} 33'$, and, by all three systems, he was in Chitrā. And thus the given *samvatsara* was current on the same date in the preceding year.

By the mean-sign system, the Mahā-Chaitra *samvatsara* commenced on Āśvina kṛishṇa 11 of Śāka-Samvat 279 current, corresponding to Saturday, the 7th September, A.D. 356; and it was followed by Mahā-Vaiśākha on Āśvina śukla 3 of Śāka-Samvat 280, corresponding to Wednesday, the 3rd September, A.D. 357; and this again was followed by Mahā-Jyēshtha on the intercalated Āśvina śukla 10 of Śāka-Samvat 281, corresponding to Sunday, the 30th August, A.D. 358. Accordingly, with this epoch, and by this system also, the Mahā-Chaitra *samvatsara* was not current on the given date; and the *samvatsara* that was current, was Mahā-Vaiśākha.

With Sir E. Clive Bayley's epoch of A.D. 190-91, the given date would belong to Śāka-Samvat 304 current; and its English equivalent would be Monday, the 20th December, A.D. 381. Here Jupiter's rising, next before the given date, took place on Mārgaśirsha śukla 8 of the same year, Śāka-Samvat 304, corresponding to Thursday, the 11th November, A.D. 381; or, by the English calendar, on Friday, the 12th November. His longitude then was $222^{\circ} 8'$. By all three systems, he was then in Anurādhā; and the *samvatsara* which then began, must have been named Mahā-Vaiśākha. Jupiter's next following rising took place on Māgha kṛishṇa 8 of Śāka-Samvat 305, corresponding to Wednesday, the 14th December, A.D. 382; or, by the English calendar, on Thursday, the 15th December. His longitude then was $254^{\circ} 1'$. By all three systems, he was then in Pūrva-Āshādhā; and the *samvatsara* which then began, must have been named Mahā-Āshādhā; the intervening *samvatsara*, Mahā-Jyēshtha, being omitted. Accordingly, with this epoch also, the Mahā-Chaitra *samvatsara* was not current on the given date. For the commencement of the Mahā-Chaitra *samvatsara*, we have to go back to Jupiter's rising on Kārttika kṛishṇa 12 of Śāka-Samvat 303, corresponding to Sunday, the 11th October, A.D. 380; or, by the English calendar, on Monday, the 12th October; when his longitude was $191^{\circ} 2'$, and, by all three systems, he was in Svāti. And thus the given *samvatsara* was current on the same date in the preceding year.

By the mean-sign system, the Mahā-Chaitra *samvatsara* commenced on the intercalated Āshādhā śukla 8 of Śāka-Samvat 303 current, corresponding to Thursday, the 28th May, A.D. 380; and it was followed by Mahā-Vaiśākha on Jyēshtha śukla 15 of Śāka-Samvat 304, corresponding to Monday, the 24th May, A.D. 381; and this again was followed by Mahā-Jyēshtha on Āshādhā kṛishṇa 6 of Śāka-Samvat 305, corresponding to Friday, the 20th May, A.D. 382. Accordingly, with this epoch also, and by this system again, the Mahā-Chaitra *samvatsara* was not current on the given date; and the *samvatsara* that was current, was Mahā-Vaiśākha.

D.—The Khôh Grant of the year 209.

The next inscription is the **Khôh grant of the Mahârâja Samkshôbha**, No. 25, page 112, in which the date (line 1 ff.) is—*navô-ttarê=bda-šata-dvayê Gupta-nripa-râjya-bhuktau śrîmatî pravardhamâna-vijaya-râjyê Mah-Âšvayuja-samvatsarê Chaitra-mâsa-šukla-paksha-trayôdašyâm*,—"in two centuries of years increased by nine; in the enjoyment of sovereignty by the Gupta kings; in the glorious augmenting and victorious reign; in the Mahâ-Âšvayuja *samvatsara*; on the thirteenth lunar day of the bright fortnight of the month Chaitra." And at the end, in line 24, the date is repeated as—*Chaitra di 20 7*,—"the month Chaitra, the (solar) day 20 (and) 7."

This gives us, for calculation, the **Mahâ-Âšvayuja samvatsara**, as current on the thirteenth *tithi* or lunar day of the bright fortnight of Chaitra (March-April) in Gupta-Samvat 209 current. And, on the analogy of the Verâwal inscription of Valabhî-Samvat 945, this should be the case in Gupta-Samvat 209 + 222 = Śaka-Samvat 451 current; in which year the given *tithi* corresponds to Sunday, the 19th March, A.D. 528.

Mr. Sh. B. Dikshit finds (see Table IV. page 105 above, Col. D.) that Jupiter's rising, next before the given date, took place on Chaitra śukla 12 of the same year, Śaka-Samvat 451, corresponding to Saturday, the 18th March, A.D. 528; or, by the English calendar, on Sunday, the 19th March; *i.e.* at the dawn immediately before the making of the grant.¹ His longitude then was $347^{\circ} 45'$. By both the systems of unequal spaces, he was then in Rêvatî; and the *samvatsara* which then began, must have been named **Mahâ-Âšvayuja**. Jupiter's next following rising took place on Jyêshtha śukla 3 of Śaka-Samvat 452, corresponding to Thursday, the 26th April, A.D. 529; or, by the English calendar, on Friday, the 27th April. His longitude then was $24^{\circ} 36'$. By both the systems of unequal spaces, he was then in Kṛittikâ; and the *samvatsara* which then began, must have been named Mahâ-Kârttika. Therefore, by both the systems of unequal spaces, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, **the Mahâ-Âšvayuja samvatsara was current on the given date**. And the result gives Śaka-Samvat 451 current (A.D. 528-29), as the equivalent of the given current Gupta year.

As a matter of fact, the Mahâ-Âšvayuja *samvatsara* was still current on the given date, Chaitra śukla 13, in the following year, Śaka-Samvat 452; as well as in Śaka-Samvat 451, which is the real equivalent for the given Gupta year. Consequently, this record might be used to support a running difference of two hundred and forty-three years between current Gupta and current Śaka years; as well as the true running difference of two hundred and forty-two years. But this possibility has been disposed of, in my remarks on the date of A., in Gupta-Samvat 156, at page 108 above.

¹ For this same reason, probably, the given date was specially selected for making the grant; since, the commencement of a *samvatsara* is regarded by Hindus as a very auspicious occasion.

On the analogy of the Kaira grant of Dharasēna IV. of the year 330, and with a year beginning either with the month Kārttika, or with the month Mārgaśīrṣha, next before the commencement of the northern Śāka year, the given date of Chaitra śukla 13, in Gupta-Saṁvat 209, would still belong to Śāka-Saṁvat 451. But the results for the dates of both A. and C. above, at pages 108 and 115, disprove the possibility of our being concerned with the scheme of the southern Vikrama year, beginning with the month Kārttika next before the commencement of the northern Śāka year. And the result for the date of C. also disproves the possibility of our being concerned with a year, northern or southern, beginning with the month Mārgaśīrṣha next before the commencement of the northern Śāka year.

By the mean-sign system, the Mahā-Āśvayuja *samvatsara* did not commence till Āṣvina śukla 3 of Śāka-Saṁvat 451 current, corresponding to Saturday, the 2nd September, A.D. 528; and consequently it was not current on the given date. The *samvatsara* then current was Mahā-Bhādrapada, which commenced on Bhādrapada kṛṣṇa 11 of Śāka-Saṁvat 450, corresponding to Tuesday, the 7th September, A.D. 527.

With General Cunningham's epoch of A.D. 166-67, the given date would belong to Śāka-Saṁvat 298 current; and its English equivalent would be Monday, the 2nd March, A.D. 375. Mr. Sh. B. Dikshit finds that Jupiter's rising, next before the given date, took place on Vaiśākha kṛṣṇa 12 of Śāka-Saṁvat 297, corresponding to Wednesday, the 26th March, A.D. 374; or, by the English calendar, on Thursday, the 27th March. His longitude then was $355^{\circ} 11'$. By all three systems, he was then in Rēvatī; and the *samvatsara* which then began, must have been named Mahā-Āśvayuja. Jupiter's next following rising took place on Jyēsthā kṛṣṇa 1 of Śāka-Saṁvat 298, corresponding to Sunday, the 3rd May, A.D. 375; or, by the English calendar, on Monday, the 4th May. His longitude then was $31^{\circ} 49'$. By all three systems, he was then in Kṛttikā, and the *samvatsara* which then began, must have been named Mahā-Kārttika. Accordingly, with this epoch, **the Mahā-Āśvayuja samvatsara was current on the given date.** This, however, is a mere coincidence. As we have seen at page 109 above, there is the same coincidence in respect of the date of A.; but it does not occur in respect of B. and C.

By the mean-sign system, the Mahā-Āśvayuja *samvatsara* commenced on Śrāvaṇa kṛṣṇa 12 of Śāka-Saṁvat 297 current, corresponding to Monday, the 23rd June, A.D. 374; and it was followed by Mahā-Kārttika on Āshāḍha śukla 4 of Śāka-Saṁvat 298, corresponding to Friday, the 19th June, A.D. 375. Accordingly, with this epoch, and by this system also, **the Mahā-Āśvayuja samvatsara was current on the given date.**

With Sir E. Clive Bayley's epoch of A.D. 190-91, the given date would belong to Śāka-Saṁvat 322 current; and its English equivalent would be Sunday, the 6th March,

A.D. 399. Here Jupiter's rising, next before the given date, took place on Vaiśākha śukla 3 of Śaka-Samvat 321, corresponding to Tuesday, the 6th April, A.D. 398; or, by the English calendar, on Wednesday, the 7th April. His longitude then was $5^{\circ} 28'$. By all three systems, he was then in Aśvinī; and the *samvatsara* which then began, must have been named **Mahā-Āśvayuja**. Jupiter's next following rising took place on Āshādha kṛishna 7 of Śaka-Samvat 322, corresponding to Friday, the 13th May, A.D. 399; or, by the English calendar, on Saturday, the 14th May. His longitude then was $41^{\circ} 42'$. By all three systems, he was then in Rōhini; and the *samvatsara* which then began, must have been named Mahā-Kārttika. Accordingly, with this epoch also, **the Mahā-Āśvayuja samvatsara was current on the given date**. This again, however, is a mere coincidence. And again, though there is the same coincidence in respect of the date of A., it does not occur in respect of B. and C.

By the mean-sign system, the Mahā-Āśvayuja *samvatsara* commenced on Chaitra śukla 10 of Saka-Samvat 321 current, corresponding to Sunday, the 14th March, A.D. 398; and it was followed by Mahā-Kārttika on Vaiśākha kṛishna 2 of Śaka-Samvat 322, corresponding to Thursday, the 10th March, A.D. 399. Accordingly, with this epoch again, and by this system also, **the Mahā-Āśvayuja samvatsara was current on the given date**.

E.—The Bhumarâ Pillar Inscription.

The last inscription of this series is the **Bhumarâ pillar inscription of the Mahārâjas Hastin and Śarvanâtha**, No. 24, page 110, in which the date (line 7 ff.) is — Mahā-Mâghê samvatsarê Kārttika-mâsa divasa 10 9,—“in the Mahā-Mâgha *samvatsara*; the month Kārttika: the (solar) day 10 (and) 9.”

This gives us, for calculation, the **Mahā-Mâgha samvatsara**, as current on the nineteenth solar day of the month Kārttika (October-November); but the current year of the Gupta era is not given. The only guide, therefore, in determining the approximate Gupta year, for which the calculations should be made, is the fact that this inscription shows that the Parivrâjaka *Mahârâja* Hastin was, at the time of this record, contemporaneous with the *Mahârâja* Śarvanâtha of Uchchakalpa. For the *Mahârâja* Hastin, we have the extreme recorded dates of Gupta-Samvat 156 and 191; while, for the *Mahârâja* Śarvanâtha, we have similarly the dates of the years 193 and 214; and for his father, Jayanâtha, the latest date of the year 177, all of which may have to be referred to the Gupta era. If so, the Mahā-Mâgha *samvatsara* in question,—on the assumption that what should be its regular place in the series was not affected by any omissions and repetitions, subsequent to the Mahā-Vaiśākha *samvatsara* which was current on Kārttika śukla 3 in Gupta-Samvat 156,—must be found in or about Gupta-Samvat 189 or 201; with a preference in favour of the year 189, because of the early date of the year 156 for the *Mahârâja* Hastin.

For Gupta-Samvat 189 + 242 = Śaka-Samvat 431 current, the given date, *viz* the nineteenth day of the month Kārttika, corresponds to Monday, the 13th October, A.D. 508. Mr. Sh. B. Dikshit finds (see Table IV. page 105 above, Col. E1) that Jupiter's rising, next before the given date, took place on Śrāvāṇa śukla 15 of the same year, Śaka-Samvat 431, corresponding to Monday, the 28th July, A.D. 508; or, by the English calendar, on Tuesday, the 29th July. His longitude then was $117^{\circ} 4'$. By both the systems of unequal spaces, he was then in Maghā; and the *samvatsara* which then began, must have been named **Mahā-Māgha**. Jupiter's next following rising took place on Āśvina kṛishṇa 13 of Śaka-Samvat 432, corresponding to Saturday, the 29th August, A.D. 509; or, by the English calendar, on Sunday, the 30th August. His longitude then was $147^{\circ} 49'$. By both the systems of unequal spaces, he was then in Uttarā Phalgunī; and the *samvatsara* which then began, must have been named Mahā-Phālguna. Therefore, by both the systems of unequal spaces, in Gupta-Samvat 189, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, **the Mahā-Māgha samvatsara was current on the given date**. And this result gives Śaka-Samvat 431 current (A.D. 508-509), as the equivalent of the possible current Gupta year.

Again, for Gupta-Samvat 201 + 242 = Śaka-Samvat 443 current, the given date, *viz* the nineteenth day of the month Kārttika, corresponds to Friday, the 2nd October, A.D. 520. Here, Mr. Sh. B. Dikshit finds (see Table IV. page 105 above, Col. E2) that Jupiter's rising, next before the given date, took place on Bhādrapada śukla 3 of the same year, Śaka-Samvat 443, corresponding to Sunday, the 2nd August, A.D. 520, or by the English calendar, on Monday, the 3rd August. His longitude then was $121^{\circ} 30'$. By both the systems of unequal spaces, he was then in Maghā, and the *samvatsara* which then began, must have been named **Mahā-Māgha**. Jupiter's next following rising took place on Āśvina kṛishṇa 1 of Śaka-Samvat 444, corresponding to Friday, the 3rd September, A.D. 521; or, by the English calendar, on Saturday, the 4th September. His longitude then was $152^{\circ} 17'$. By both the systems of unequal spaces, he was then in Uttarā-Phalgunī, and the *samvatsara* which then began, must have been named Mahā-Phālguna. Therefore, by both the systems of unequal spaces, in Gupta-Samvat 201 also, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, **the Mahā-Māgha samvatsara was current on the given date**. And this result gives Śaka-Samvat 443 current (A.D. 520-21), as the equivalent of the possible current Gupta year.

The results for these two years, Gupta-Samvat 189 and 201, answer, as is required, to the running difference of two hundred and forty-two years between current Gupta and current Śaka years. But they do not, in themselves, prove it; for the reason that the current Gupta year itself is not mentioned in the record. The important point is, that in neither of these two cycles was the Mahā-Māgha *samvatsara* omitted.

If the dates in the grants of the *Mahārājas* of Uchchakalpa are to be referred to the Kalachuri era,¹ then the Mahā-Māgha *saṃvatsara* of this record will be earlier by either one or two cycles than the first of the two years given above. Here, again, in respect of the actual epoch no absolute proof can be derived from this record; and the only important point is, to ascertain that the Mahā-Māgha *saṃvatsara* was not omitted in either of the two cycles in question. Mr. Sh. B. Dikshit finds that, in Gupta-Saṃvat 165 + 242 = Śaka-Saṃvat 407 current, Jupiter's rising took place on Śrāvaṇa śukla 10, corresponding to Thursday, the 19th July, A.D. 484; or, by the English calendar, on Friday, the 20th July. His longitude then was 108° 19'. By both the systems of unequal spaces, he was then in Āślēshā; and the *saṃvatsara* which then began, and which was current through the whole month of Kārttika in the same year, must have been named **Mahā-Māgha**. Again, in Gupta-Saṃvat 177 + 242 = Śaka-Saṃvat 419 current, Jupiter's rising took place on Bhādrapada kṛishṇa 13, corresponding to Wednesday, the 24th July, A.D. 496; or, by the English calendar, on Thursday, the 25th July. His longitude then was 112° 48'. By the Brahma-Siddhānta system of unequal spaces he was then in Maghā, and by the Garga system, in Āślēshā; and, by both systems, the *saṃvatsara* which then began, and which was current through the whole month of Kārttika in the same year, must have been named **Mahā-Māgha**. Therefore, by both the systems of unequal spaces, in Gupta-Saṃvat 165 and 177 also, with the running difference of two hundred and forty-two years between current Gupta and current Śaka years, the **Mahā-Māgha saṃvatsara was current on the given date**, and was not omitted. And these results give either Śaka-Saṃvat 407 current (A.D. 484-85) or 419 current (A.D. 496-97), as the equivalent of the possible current Gupta year.

By the mean-sign system, in Gupta-Saṃvat 166 + 242 = Śaka-Saṃvat 408 current, the Mahā-Māgha *saṃvatsara* commenced on Chaitra śukla 5, corresponding to Thursday, the 7th March, A.D. 485; and it was current through the whole month of Kārttika in the same year; being followed by Mahā-Phālguna on Chaitra śukla 12 of Śaka-Saṃvat 409, corresponding to Monday, the 3rd March, A.D. 486. Again, in Gupta-Saṃvat 177 + 242 = Śaka-Saṃvat 419 current, the Mahā-Māgha *saṃvatsara* commenced on Phālguna kṛishṇa 12, corresponding to Thursday, the 16th January, A.D. 497; and it was current through the whole month of Kārttika in Gupta-Saṃvat 178; being followed by Mahā-Phālguna on Māgha śukla 4 of Śaka-Saṃvat 420, corresponding to Monday, the 12th January, A.D. 498. Again, in Gupta-Saṃvat 189 + 242 = Śaka-Saṃvat 431 current, the Mahā-Māgha *saṃvatsara* commenced on Pauṣha kṛishṇa 3, corresponding to Wednesday, the 26th November, A.D. 508; and it was current through the whole month of Kārttika in Gupta-Saṃvat 190; being followed by Mahā-Phālguna on Pauṣha kṛishṇa 9 of Śaka-Saṃvat 432, corresponding to Sunday, the 22nd November,

¹ See page 8 above.

A.D. 509 And thus, by this system also, in Gupta-Samvat 166, 178, and 190 **the Mahâ-Mâgha samvatsara was current on the given date.** But this was not the case in the next cycle. In Gupta-Samvat 201 + 242 = Śaka-Samvat 443 current, the Mahâ-Mâgha *samvatsara* commenced on Kârttika sukla 9, corresponding to Tuesday, the 6th October, A.D. 520, and falling four, five, or six days after the nineteenth day of the month, and it was followed by Mahâ-Phalguni on Kârttika kṛṣṇa 1 of Śaka-Samvat 444, corresponding to Saturday, the 2nd October, A.D. 521, and falling seventeen, eighteen, or nineteen days before the nineteenth day of the month. Thus, though the given *samvatsara* was not omitted, the given day did not fall within the limits of its duration.

With General Cunningham's epoch of A.D. 166-67, Mr. Sh. B. Dikshit finds that, for Gupta-Samvat 188 + A.D. 166-67 = A.D. 354-55 = Śaka-Samvat 277 current, in which year the English equivalent of the given date would be Saturday, 8th October, A.D. 354, Jupiter's rising, next before the given date, took place on Bhâdrapada kṛṣṇa 12 of the same year, Śaka-Samvat 277, corresponding to Tuesday, the 2nd August, A.D. 354, or, by the English calendar, on Wednesday, the 3rd August. His longitude then was $122^{\circ} 59'$. By all three systems, he was then in Mâgha, and the *samvatsara* which then began, must have been named Mahâ-Mâgha. Jupiter's next following rising took place on Āśvina sukla 12 of Śaka-Samvat 278, corresponding to Sunday, the 3rd September A.D. 355, or, by the English calendar, on Monday, the 4th September. His longitude then was $153^{\circ} 34'$. By all three systems, he was then in Uttarâ-Phalguni, and the *samvatsara* which then began, must have been named Mahâ-Phalguni. Accordingly, with this epoch, and with Gupta-Samvat 188 as the intended current year, **the Mahâ-Mâgha samvatsara was current on the given date.** This result, however, does not help to prove the epoch, because the record does not specify the current Gupta year, and, by taking a different Gupta year, the same result can be obtained for a different epoch.

Again, for Gupta-Samvat 199 + A.D. 166-67 = A.D. 365-66 = Śaka-Samvat 288 current, in which year the English equivalent of the given date would be Wednesday, the 5th October, A.D. 365, Jupiter's rising, next before the given date, took place on Śrâvana sukla 1 of the same year, Śaka-Samvat 288, corresponding to Wednesday, the 6th July, A.D. 365, or, by the English calendar, on Thursday, the 7th July. His longitude then was $95^{\circ} 56'$. By all three systems, he was then in Pushya, and the *samvatsara* which then began, must have been named Mahâ-Pausha. Jupiter's next following rising took place on Bhâdrapada sukla 15 of Śaka-Samvat 289, corresponding to Monday, the 7th August, A.D. 366, or, by the English calendar, on Tuesday, the 8th August. His longitude then was $127^{\circ} 24'$. By both the systems of unequal spaces, he was then in Pûrvâ-Phalguni; and the *samvatsara* which then began, must have been named Mahâ-Phalguni; the intervening Mahâ-Mâgha *samvatsara* being omitted. But, by the system of equal spaces, he was

then in Maghâ; and the **Mahâ-Mâgha samvatsara** then commenced, and was current on the given date in Gupta-Samvat 200. Jupiter's next following rising took place on Āśvina kṛishṇa 12 of Śaka-Samvat 290, corresponding to Friday, the 7th September, A.D. 367, or, by the English calendar, on Saturday, the 8th September. His longitude then was $157^{\circ} 42'$. By all three systems, he was then in Uttarâ-Phalgunî, and the *samvatsara* which then began, must have been named Mahâ-Phâlguna, and it was a repeated *samvatsara* by the two systems of unequal spaces but an ordinary *samvatsara* by the system of equal spaces.

By the mean-sign system, in Gupta-Samvat 188 + A.D. 166-67 = A.D. 354-55 = Śaka-Samvat 277 current, the Mahâ-Mâgha *samvatsara* commenced on Āśvina śukla 13, corresponding to Friday, the 16th September, A.D. 354; and it was current through the whole month of Kârttika in the same year, being followed by Mahâ-Phâlguna on Kârttika kṛishṇa 3 of Saka-Samvat 278, corresponding to Tuesday, the 12th September, A.D. 355. And again, in Gupta-Samvat 200 + A.D. 166-67 = A.D. 366-67 = Śaka-Samvat 289 current, the Mahâ-Mâgha *samvatsara* commenced on Bhâdrapada śukla 3, corresponding to Thursday, the 27th July, A.D. 366, and it was current through the whole month of Kârttika in the same year, being followed by Mahâ-Phâlguna on Śrâvana śukla 10 of Śaka-Samvat 290, corresponding to Monday, the 23rd July, A.D. 367. And thus, with this epoch, and by this system, the **Mahâ-Mâgha samvatsara** was current on the given date in Gupta-Samvat 188 and 200. The results, however, do not in themselves prove anything definite as to the proposed epoch, for the reason that the current Gupta year itself is not mentioned in the record and by taking different Gupta years, the same results would be obtained with a different epoch.

With Sir E. Clive Bayley's epoch of A.D. 190-91, Mr. Sh. B. Dikshit finds that, for Gupta-Samvat 187 + A.D. 190-91 = A.D. 377-78 = Śaka-Samvat 300 current, in which year the English equivalent of the given date would be Sunday, the 22nd October, A.D. 377, Jupiter's rising, next before the given date, took place on Bhâdrapada kṛishṇa 4, of the same year, Śaka-Samvat 300, corresponding to Tuesday, the 11th July, A.D. 377; or, by the English calendar, on Wednesday, the 12th July. His longitude then was $100^{\circ} 32'$. By all three systems, he was then in Pushya, and the *samvatsara* which then began, must have been named Mahâ-Pausha. Jupiter's next following rising took place on Bhâdrapada śukla 3 of Saka-Samvat 301, corresponding to Sunday, the 12th August, A.D. 378, or, by the English calendar, on Monday, the 13th August. His longitude then was $131^{\circ} 50'$. By both the systems of unequal spaces, he was then in Pûrvâ-Phalgunî, and the *samvatsara* which then began, must have been named Mahâ-Phâlguna, the intervening Mahâ-Mâgha *samvatsara* being omitted. But, by the system of equal spaces, he was then in Maghâ; and the **Mahâ-Mâgha samvatsara** then commenced, and was current on the given date in Gupta-Samvat 188. Jupiter's next following rising took place on Āśvina śukla 15 of Saka-Samvat 302, corresponding to Thursday, the 12th September

A.D. 379; or, by the English calendar, on Friday, the 13th September. His longitude then was $162^{\circ} 0'$. By all three systems, he was then in Hasta; and the *samvatsara* which then began, must have been named Mahā-Phālguna; and it was a repeated *samvatsara* by the two systems of unequal spaces, but an ordinary *samvatsara* by the system of equal spaces.

Again, in Gupta-Samvat 199 + A.D. 190-91 = A.D. 389-90 = Śaka-Samvat 312 current, in which year the English equivalent of the given date would be Wednesday, the 10th October, A.D. 389, Jupiter's rising, next before the given date, took place on Śrāvana śukla 6 of the same year, Śaka-Samvat 312, corresponding to Sunday, the 15th July, A.D. 389; or, by the English calendar, on Monday, the 16th July. His longitude then was $104^{\circ} 51'$. By all three systems, he was then in Pushya; and the *samvatsara* which then began, must have been named Mahā-Pausha. Jupiter's next following rising took place on Āśvina kṛishna 4 of Śaka-Samvat 313, corresponding to Friday, the 16th August, A.D. 390; or, by the English calendar, on Saturday, the 17th August. His longitude then was $135^{\circ} 57'$. By all three systems, he was then in Pūrvā-Phalgunī; and the *samvatsara* which then began, must have been named Mahā-Phālguna; the intervening Mahā-Māgha *samvatsara* being omitted.

By the mean-sign system, in Gupta-Samvat 188 + A.D. 190-91 = A.D. 378-79 = Śaka-Samvat 301 current, the Mahā-Māgha *samvatsara* commenced on Āshādha kṛishna 10, corresponding to Wednesday, the 6th June, A.D. 378; and it was current through the whole month of Kārttika in the same year; being followed by Mahā-Phālguna on Āshādha śukla 1 of Śaka-Samvat 302, corresponding to Sunday, the 2nd June, A.D. 379. Again, in Gupta-Samvat 200 + A.D. 190-91 = A.D. 390-91 = Śaka-Samvat 313 current, the Mahā-Māgha *samvatsara* commenced on Jyēshtha kṛishna 2, corresponding to Wednesday, the 17th April, A.D. 390, and it was current through the whole month of Kārttika in the same year; being followed by Mahā-Phālguna on Jyēshtha kṛishna 8 of Śaka-Samvat 314, corresponding to Sunday, the 13th April, A.D. 391. And thus, with this epoch also, and by this system, **the Mahā-Māgha samvatsara was current on the given date** in Gupta-Samvat 188 and 200. But here, again, the results do not in themselves prove anything definite as to the proposed epoch; for the reason that the current Gupta year itself is not mentioned in the record; and, by taking different Gupta years, the same results would be obtained with a different epoch.

Summary of Results.

I have now examined all the dates, at present known, referable to the Gupta-Valabhī era, that furnish details for computation. And it only remains to sum up the results established by the preceding inquiries.

Albérūni tells us that there was an era, known both as the Gupta era and the Valabhī era, the years of which were to be converted into years of the Śaka era by

adding, according to his most explicit statement, two hundred and forty-one years to the Gupta-Valabhi dates. This fixes the starting-point of the era, approximately, as having occurred when Śaka-Samvat 241 had expired, and, by the epoch of the well-known Śaka era, when A.D. 319-20 was current; leaving only the determination of the exact epoch by the calculation of recorded dates. And, as regards a special point in his statements, of extreme importance, with the help of Prof. Wright, we have now obtained a translation which,—if it does not actually mean only that the Early Gupta kings had exercised so powerful a sway that, even when their dynasty came to an end, the era that had been used by them still continued in use,—is yet fully capable of that interpretation. At any rate, this translation frees us from the obligation under which we lay, by reason of M. Reinaud's rendering of the same passage, of connecting the establishment of an era with the extermination of the dynasty, and of placing the period of the Early Gupta supremacy anterior to A.D. 319, and the termination of it in that year. And the most that can be said against it, is, that it is the literal rendering of an ambiguous original, the real meaning of which must be determined by extraneous considerations.

The Mandasôr inscription of Mâlava-Samvat 529 expired shews that we must look to somewhere about A.D. 319 for the starting-point of the era in which are recorded the dynastic dates of Kumâragupta and the other kings of the Early Gupta dynasty, and any others that are to be referred to the same uniform series with them.

The dates in the records of the Early Guptas themselves, as far as the time of Skandagupta, do not afford details for computation. But, clearly belonging to the same uniform series of years, is the date contained in **the Êraṇ pillar inscription of Budhagupta**. And converting this date into a Śaka date, in the manner indicated by Albêrûni, we have found that, the resulting Śaka year being taken as an expired year, the details work out quite correctly.

Such dates, also, are those contained in **the records of the Parivrâjaka Mahârâjas**; which, moreover, include a specific declaration that the Gupta sovereignty was then still continuing. And, calculating them in precisely the manner that is indicated by the results for the date in the Êraṇ pillar inscription, we have obtained equally correct and uniform results. Also, the latest of these records, the Khôh grant of the *Mahârâja Samkshôbha*, No. 25, page 112, shews that the Gupta sovereignty continued for at least two hundred and nine years. And this fact is amply sufficient to explain why,—whatever may have been its historical origin,—the era used in all these records should eventually come to be popularly known as the Gupta era.

Such dates, again, are those contained in **the inscriptions of Śivadêva I. and Mânadêva of Nêpâl**. And, that the first of them is recorded in the era in question, is shewn by the dates, in the Harsha era, for Amśuvarman, the contemporary of Śivadêva I.; while, with the same treatment, the details of the second of them work out quite correctly.

Such another date is that contained in **the Mōrbi grant of Jāinka**. And the details of this, again, work out correctly with the same treatment

Such a series of dates, too, is that contained in **the records of the Valabhi family**. And, with a slight modification, due to a change in the scheme of the year, easily explainable, the same treatment gives correct results for the date in the Kaira grant of Dharasēna IV. of this family, of the year 330; the only one, at present, that affords exact details for calculation. Also, these records give us a succession of twelve generations, commencing with the *Sēndpati* Bhatārka, and ending with king Śīlāditya VII., with dates ranging from the year 207 to the year 447. For the first six or seven generations, the members of this family were only feudatory *Sēndpatīs* and *Mahārājas*, without the authority to establish an era of their own. And, as a matter of fact, the date of the year 207 for the *Mahārāja* Dhruvasēna I., in the second generation, proves that the era did not run from the rise to power of his father Bhatārka, the founder of the family, but must have been adopted from some outside source. While, on the other hand, the long duration of this family, coupled with the fact that several of their charters were issued from the city of Valabhi itself,¹ and all of them belong either to that vicinity or to the neighbouring parts of Gujarāt, is amply sufficient to explain why the era used by them should eventually come to be popularly known, in those parts, as the Valabhi era.

And, finally, undeniable instances of the actual use of an era known as the Valabhi era, as late as the thirteenth century A.D., are furnished by **the Verāwal inscriptions** dated in Valabhi-Samvat 927 and 945. For the details of the earlier of these two dates, correct results can be obtained by applying the same slightly anomalous treatment that applies to the date in the Kaira grant of Dharasēna IV. of the year 330. The latter of them, however, goes far beyond this. Not only does it fix the epoch of the era approximately, and in accordance with Albérūnī's statement, through the concomitant mention of the equivalent Vikrama and Hijra years; but also the details of it are such as to prove that the epoch of the era was exactly when Śaka-Samvat 241 had expired, and A.D. 319-20 was current. And it has furnished, in fact, the exact analogy, in accordance with which all dates in the Gupta-Valabhi era, that follow the true and original northern scheme of its years, have to be tested.

All this uniform agreement of results cannot be attributed to mere coincidence. But we must take it now, as a settled matter, that all the dates in question belong to one and the same era, running from the epoch of A.D. 319-20. And, irrespective of the question

¹ e.g. the grants of Dhruvasēna I., of the year 207 (*Ind. Ant.* Vol. V. p. 204), of Gubasēna, of the year 248 (*id.* Vol. V. p. 206, and *Archæol. Surv. West. Ind.* Vol. III. p. 93), of Dharasēna II., of the year 252 (*Ind. Ant.* Vol. VII. p. 68; Vol. VIII. p. 301; Vol. XV. p. 187; and No. 30 below p. 164); of Śīlāditya I., of the year 286 (*Four. Bo. Br. R. As. Soc.* Vol. XI. p. 359, and *Ind. Ant.* Vol. XIV. p. 327), and of the year 290 (*Ind. Ant.* Vol. IX. p. 237); of Dhruvasēna II., of the year 310 (*id.* Vol. VI. p. 12); and of Dharasēna IV., of the year 326 (*id.* Vol. I. p. 14, and *Four. Bo. Br. R. As. Soc.* Vol. X. p. 66).

whether the era was actually established by the Early Guptas themselves, we must refer the rise of the Early Gupta power to somewhere about A.D. 319, instead of placing the period of their supremacy anterior to that year, and their downfall in it.

A few concluding words, however, seem necessary as to the exact years of the Christian era, which represent respectively the epoch or year 0, and the commencement or first current year, of the Gupta-Valabhi era.

Taking the years quoted in the records without qualification, as current years, we have obtained the following results,¹—by the Êraṇ pillar inscription of Budhagupta, Gupta-Saṃvat 165 current = A.D. 484-85 current,² by the Parivrājaka grants, 156 current = A.D. 475-76 current,³ 163 current = A.D. 482-83 current,⁴ 191 current = A.D. 510-11 current,⁵ and 209 current = A.D. 528-29 current;⁶ by the Népāl inscription of Mānadēva, 386 current = A.D. 705-706 current,⁷ and by the Verāwal inscription of Arjunadēva, 945 current = A.D. 1264-65 current.⁸ And all these equations give the uniform result of Gupta-Valabhi-Saṃvat 0 = A.D. 319-20 current, or more precisely, by the Śaka year, the period⁹ from the 9th March, A.D. 319, to the 25th February, A.D. 320, and Gupta-Valabhi-Saṃvat 1 current = A.D. 320-21 current, or more precisely, by the Saka year, the period from the 26th February, A.D. 320, to the 15th March, A.D. 321.

The results obtained from the Kaira grant of the year 330 and the Verāwal inscription of Valabhi-Saṃvat 927, differ slightly from the above, and are—Gupta-Valabhi-Saṃvat 330 current = A.D. 648-49 current,¹⁰ and Valabhi-Saṃvat 927 current = A.D. 1245-46 current.¹¹ In these two instances the difference is due to a local alteration of the true and

¹ I exclude the Bhumarā pillar inscription, as proving nothing definite, because the Gupta year is not given in it.

² Or, more precisely, by the Śaka year, as commencing with Chaitra śukla 1, the period (see *Indian Eras*, p. 153) from the 14th March, A.D. 484, to the 2nd March, A.D. 485.—The dates given in these notes are quoted as approximately correct, they may, or may not, be the exact dates.

³ Or, in the same way, the period from the 21st February, A.D. 475, to the 11th March, A.D. 476.

⁴ Or, in the same way, the period from the 6th March, A.D. 482, to the 22nd February, A.D. 483.

⁵ Or, in the same way, the period from the 25th February, A.D. 510, to the 15th March, A.D. 511.

⁶ Or, in the same way, the period from the 8th March, A.D. 528, to the 24th February, A.D. 529.

⁷ Or, in the same way, the period from the 1st March, A.D. 705, to the 20th March, A.D. 706.

⁸ Or, in the same way, the period from the 1st March, A.D. 1264, to the 19th March, A.D. 1265.

⁹ Here I owe the initial and ending dates, which it was desirable to have exactly, to Mr. Sh. B. Dikshit.

¹⁰ Or, more precisely, by the southern Vikrama year, as commencing with Kārttika śukla 1, the period (see C. Patell's *Chronology*, p. 122) from the 24th September, A.D. 648, to the 12th October, A.D. 649.

¹¹ Or, in the same way, the period from the 23rd October, A.D. 1245, to the 12th October, A.D. 1246.

original scheme of the Gupta year; made in such a way that each subsequent year commenced with the Kārttika śukla 1 immediately preceding the true commencement of the year with Chaitra śukla 1. And for these two dates, and any that may be found hereafter to belong to the same class, we have to apply the equations of Gupta-Valabhi-Samvat 0 = A.D. 318-319 current, or more precisely, by the southern Vikrama year, the period¹ from the 12th October, A.D. 318, to the 30th September, A.D. 319; and Gupta-Valabhi-Samvat 1 current = A.D. 319-20 current, or more precisely, by the southern Vikrama year, the period from the 1st October, A.D. 319, to the 18th October, A.D. 320.

These two instances, however, are purely exceptional ones. And, in the case of all dates in the era referable to the true and original scheme of its years, we have to apply the epoch of A.D. 319-20; and to treat the years of the era as northern years, commencing with Chaitra śukla 1.

The equation between the epoch of the Gupta-Valabhi era and the Christian era, is not intrinsically dependent on any reference to the Śaka era; and it could be established directly by European Tables. In this inquiry, however, it has been established through results that have been worked out from Hindu Tables which are arranged for the Śaka era according to expired years: and, in order to use those Tables, the given Gupta-Valabhi years had to be converted into expired Śaka years. The process, however, has not converted the given Gupta-Valabhi years themselves into expired years. But what has been done has simply been, first, by the addition of a uniform running difference, to obtain the current Śaka year corresponding to each given current Gupta-Valabhi year; and then, in the usual way, to take the immediately preceding Śaka year as the expired year that is required as the basis of the calculation. Thus, the details of the date in the Êraṇ pillar inscription of Budhagupta, which really belong to Gupta-Samvat 165 + 242 = Śaka-Samvat 407 current, have been calculated with the basis of Śaka-Samvat 406 expired; and the details of the other dates in the same way.

Now, in the case of an era used specially by astronomers for their technical processes, as the Śaka era was, since we have to work with expired years, it is natural enough that the Tables should be arranged accordingly. And possibly, after a certain period, and in certain parts of India, we may have to interpret any given year of such an era as an expired year, whether it is expressly denoted as such or not.² But the same rule does not hold good in the case of eras that are not actually used for astronomical processes, though they are quoted in connection with details fixed by such processes.

¹ Here, again, I owe the exact dates to Mr. Sh. B. Dikshit.

² A clear instance of this is furnished by the date in the Dēḡgaḡh inscription of Bhōjadēva (see page 107 above, note 1). By the literal rules of translation, the given Śaka year, 784, has to be interpreted as a current year; but, for the calculation, it has to be applied as an expired year.

Such an era is the Vikrama era.¹ And,—though the expired years of this era might be quoted, as is shewn, for instance, by lines 19 and 21 of the Mandasor inscription of Málava-Samvat 529 expired, No. 18, page 79, and by line 21 of the Kaḍl grant of Jayantasirha of Vikrama-Samvat 1280 expired,²—yet, that, occasionally at least, the current years were used, is proved by the Gwalior Śāsbaḥ temple inscription of Maḥpāla,³ in which we have first in words, the number of years expired, 1149. and then, partially in words and fully in figures, the number of the current year, 1150. Such an era, again, is the Gupta-Valabhl era; or, at least, we have not as yet obtained the slightest indication of its ever having been used by astronomers as the basis of calculations. And, in the absence of the use of any word meaning “expired” in connection with the year in a Gupta-Valabhl date, it is only reasonable that we should follow the ordinary rules of interpretation, and render the original passage as denoting a current year.

In one instance only, among the Gupta-Valabhl dates at present known, is a word meaning “expired” used in connection with the year. This exceptional instance is the Mōrbi grant of Jāinka, in which an eclipse of the sun is recorded as having occurred when the year 585 had passed by. Unfortunately, the month and *tithi*, in and on which the eclipse occurred, are not specified; nor even the week-day. And, as we have seen at page 100 above, it might be possible to identify the solar eclipse of this record with that of the 10th November, A.D. 904. In that case, the given year 585 expired, and the indicated year 586 current, would be equivalent to A.D. 904-905 current. It would then be as an expired year, not a current one, that the year 165 of the Ēraṇ pillar inscription of Budhagupta is equivalent to A.D. 484-85 current; and so on with all the other dates. And we should have to apply, in the case of all dates in the era referable to the true and original scheme of its years, the epoch of A.D. 318-19 current, or more precisely, by the Śaka year, the period⁴ from the 18th February, A.D. 318, to the 8th March, A.D. 319; and, in the case of dates belonging to the same class with those of the Kaira grant of the year 330 and the Verśwal inscription of Valabhl-Samvat 927, the epoch of A.D. 317-18 current, or more precisely, by the Vikrama year, the period from the 23rd September, A.D. 317, to the 11th October, A.D. 318. But we have also seen that the solar eclipse in question can be far more satisfactorily identified with that which occurred on the 7th May, A.D. 905; to do which, we have to take the given year 585 expired, and the indicated year 586 current, as equivalent to A.D. 905-906 current. And this record, therefore, furnishes strong and instructive corroboration of my view that, in the absence of

¹ The present Tables of this era, however, seem to be arranged, like those of the Śaka era, according to expired years. And some of the almanacs quoted in Appendix I. below, give them in the same way.

² *Ind. Ant.* Vol. VI. p. 197.

³ For the full reading and translation of the date see Texts and Translations, page 22, note 5.

⁴ Here, again, I owe the exact initial and ending dates to Mr. Sh. B. Dikshit.

any distinct specification to the contrary, **we must interpret the years in Gupta-Valabhi dates as current years.**

The Origin of the Era.

I have shewn, at page 33 ff. above, that the so-called Gupta era is not one which, due originally to some event occurring only in approximation to A.D. 318, 319, or 320, had its exact epoch determined, for convenience of comparison with the Śaka era, by adopting the expiration of an even number of cycles of the planet Jupiter, either of the Twelve-Year or of the Sixty-Year System. And no other chronological or astronomical considerations suggest themselves, for the selection of the exact epoch that has been proved. **Its origin, therefore, must be found in some historical event, which occurred actually in A.D. 320,** or so closely to that time that, when the scheme of the northern Śaka year was applied, the reckoning of the era was not affected to any appreciable extent. And here, though the point is not conclusive either way, we must bear in mind that, as has been shewn at page 19 ff. above, in the epigraphical references to the era there is nothing at all, at any early period, to connect the name of the Early Guptas with it, especially as the founders of it; and nothing to connect the name of Valabhi with it, until at least nine centuries after its establishment.

We must also bear in mind that it is certain that **the era cannot have been established by any member of the Valabhi family;** the reasons for this being—(1) that, for the first six or seven generations, the members of this family were mere feudatory *Sēndpatis* and *Mahārājas*, without the authority to establish an era of their own;—and (2) that the date of the year 207 for the *Mahārāja* Dhruvasēna I., in the second generation, proves that the reckoning runs from long before the first rise to power of his father, the *Sēndpati* Bhaṭārka, by whom the family was founded.

In the same way, the first two members of the Early Gupta family, Gupta and Ghaṭōtkacha, held only the feudatory rank of *Mahārāja*, and had not the authority to establish an era. The first paramount sovereign in the family was Ghaṭōtkacha's son, Chandragupta I. And, if a Gupta era, truly and properly so called, was devised in his time, then as its starting-point there would have been selected the commencement of his reign, not the date of the rise to power of his first recorded ancestor, the *Mahārāja* Gupta; as was done in the case of the Harsha era, which disregards, not only two generations of *Mahārājas* at the commencement of the genealogy, but even the reigns of two kings, Prabhākaravardhana and Rājyavardhana II., and runs from the commencement of the reign of the third paramount sovereign, Harshavardhana himself. So, also, when the Western Chālukya king Vikramāditya VI. established a new era under the name of the Chālukya-Vikrama-Kāla,¹ he disregarded the reigns of all his ancestors, and made the era date from his own accession

¹ See *Ind. Ant.* Vol. VIII. p. 187 ff.

to the throne. The dates in the Early Gupta records shew clearly that the Gupta era, cannot, under any circumstances, run from the accession of any member of the dynasty later than Chandragupta I. And there are essential difficulties, under any normal conditions, in the way of making the era date from the commencement of his reign; *i.e.* of taking A.D. 320-21 as his first current year. For his great-grandson, Kumāragupta, we have dates in the era, ranging from the year 96 to the year 130 odd;¹ of which we may take, as the latest certain one,² that of the year 129, recorded in the Mankuwār inscription, No. 11, page 45. And, as we ought to assume that Chandragupta I. was at least twenty years old when his reign commenced, this gives us a period of a hundred and forty-nine years, which, spread over four generations, gives to each a duration of thirty-seven years and a quarter, or nearly half as much again as the usually accepted average maximum rate of twenty-five years for a Hindu generation. This, too, is only dealing with the question of generations. If we take the period of a hundred and twenty-nine years only, from the commencement of the reign of Chandragupta I. to nearly the end of that of Kumāragupta,—which gives an average of thirty-two years and a quarter for each of the four reigns,—then, as compared with the average duration, twenty years at the outside, of a Hindu reign, the excess is still more remarkable. And almost exactly the same results are obtained, if, instead of considering four generations and reigns, down to the end of the time of Kumāragupta, we take the latest certain date³ of Chandragupta II., *vis.* the year 93 given in the Śāñchi inscription, No. 5, page 29, and spread the period of ninety-three years over three reigns, or, on the same assumption as regards the age of Chandragupta I., the period of a hundred and thirteen years over three generations. On the question of generations, I will not base any particularly special objection. An analogy for an abnormal average rate might be deduced from the Western Chālukya genealogy,⁴ in which we have Śāka-Samvat⁵ 930 for the commencement of the reign of Vikramāditya V., and Śāka-Samvat 1060 for the end of the reign, and it may safely be assumed the death, of Sōmēśvara III. in the third generation after him. If we take it that Vikramāditya V. was twenty years old in Śāka-Samvat 930, we have one hundred and fifty years for the four generations; or an average of thirty-seven years and a half for each. But, from Śāka-Samvat 930 to 1060, there were six reigns; with an average of twenty-five years, or seven less than we

¹ See page 67 above.

² And it must be very nearly his latest date; for, he had then been reigning for at least thirty-three full years, and we have the date of the year 136 for his son and successor, Skandagupta.—The selection of any later date would, of course, only intensify the force of the argument.

³ The silver coins (see *Ind. Ant.* Vol. XIV. p. 65 l.) seem to give the year 94 or 95; but the latest absolutely certain date is the one that I quote. Here again, the adoption of a later date would only strengthen the argument.

⁴ See my *Dynasties of the Kanarese Districts*, p. 18, Table.

⁵ The exact year was doubtful when I wrote the book referred to in the preceding note; but it has now been established by the Kauthēn grant (*Ind. Ant.* Vol. XVI. p. 15 ff)

should have to allot to each of the four Early Gupta kings in question. And even this result is due chiefly to the extraordinarily long reign of Vikramāditya VI., for fifty-two years, from Śaka-Samvat 997 to 1048. If we take the whole period of the Western Chālukya dynasty, covering one hundred and ninety years, from Śaka-Samvat 895, the first year of Taila II., down to Śaka-Samvat 1084, as the end of the reign and the death of Taila III.,¹ we have ten reigns, with an average duration of just nineteen years each. An average of thirty-two years for four successive reigns of Hindu fathers and sons, seems, from every point of view, an impossibility. And this prevents our making the Gupta era run from the commencement of the reign of Chandragupta I. We must, therefore, accept it as certain that **the Early Guptas only adopted the era of some other dynasty.** And we must look for its origin to some extraneous source.

Now, it is evident that **the Early Guptas rose to power first as feudatory Mahārājas**, the third of whom, Chandragupta I., while holding that same rank, established his independence; so that, his successors maintaining the same position, the paramount titles, and not his original feudatory title, are always coupled with his name in the genealogical passages in their records. And, from the *Mahārāja* Gupta down to Kumāragupta, we have two feudatory governments and four reigns; which, at the average rate of twenty years, almost fill up the period indicated by the latest certain date for Kumāragupta, and, by a coincidence, place the commencement of the government of the *Mahārāja* Gupta very near to A.D. 300. If, then, we could determine the paramount sovereign of whom the *Mahārāja* Gupta was a feudatory, we should have in him the founder of the era; provided we could only shew that his successors also dated their records in it. And the only difficulty then remaining, would be,—When Chandragupta I. and his descendants had asserted themselves as independent sovereigns, by rebellion against their masters, why should they continue to use a purely dynastic era, which had only been running for a short time and had certainly not become an astronomical era, and which would always remind them of the originally subordinate status of their ancestors; instead of establishing a new era of their own, or instead of adopting some well-known era, of general use, which could evoke no reminiscence of a humiliating kind?² The Early Gupta records, however, throw no light on this point; nor can we expect any, unless we obtain inscriptions of the time of the *Mahārājas* Gupta and Ghaṭōtkacha, or of the early years of Chandragupta I. And at

¹ I exclude the short reign of Sōmēśvara IV, from Śaka-Samvat 1104 to about 1111, because there had been meanwhile an interruption of the Western Chālukya power by the Kalachuris of the Dekkan

² An objection of this sort does not apply to the use of the Gupta era by the Valabhī family. The *Sāndpati* Bhaṭārka drove out the invaders who had overthrown the Gupta sovereignty in Western India, and may possibly have been himself the feudatory of some descendant of the original Gupta stock. And when Dharasēna IV, became a paramount sovereign, it was on the disruption of the Kanauj kingdom. At neither point was there any reason for the members of this family to feel any erosion to the Gupta era.

present, in connection with India itself, we know of no king the commencement of whose reign can with any certainty be referred to A.D. 320; and of no historical event to which we can safely allot that date. Nor, while the Early Gupta sovereignty continued, is there any indication of the Gupta era having been used, in India, by any other independent dynasty. The nearest approximation to the year in question that we have, is in the case of the Kalachuri dynasty of Central India; in respect of which certain points in the records of the Parivrājaka *Mahārājas* and the *Mahārājas* of Uchchakalpa do tend to support the actual existence, in the Early Gupta period, of a Kalachuri era, and, consequently, of Kalachuri kings under some earlier name.¹ The Kalachuri dates, however, certainly cannot be referred to the Gupta epoch. And circumstances indicate that the dominion of the Kalachuri kings, at that time, was confined entirely to the more eastern parts of Central India; so that they were only contemporaries of the northern dynasty of which the Early Guptas were at first the servants. Mr. Fergusson's opinion,² again, was in the direction of the era being established, with the foundation of Valabhī as a new capital of Western India, by the Andhra king Gōtamiputra, whom he placed³ between A.D. 312 and 333; the *Mahārāja* Gupta being a feudatory of him or of one of his immediate successors. But the chronology of the Andhras,—who, at the best, seem to have been too essentially a western and southern dynasty to be concerned in any leading way with the history of Northern India,—still remains to be finally determined. And Dr. R. G. Bhandarkar, who has given more consideration to the subject than any one else as yet, places Gōtamiputra about two centuries earlier,⁴ in the period A.D. 133 to 154; and, according to his view of the early chronology, we should have to refer the establishment of the Gupta era to some event connected with either the downfall of the Kshatrapas of Saurāshtra or the history of the Rāshtrakūṭas of the Dekkan. The Kshatrapas, however, certainly did not use the Gupta era. And there is not the slightest particle of evidence that the Rāshtrakūṭas ever had an era of their own. There can be but little doubt that the real paramount lords of the *Mahārājas* Gupta and Ghatōtkacha, and at first of Chandraguptā I. himself, were some of the later Indo-Scythian kings of Northern India, whose duration is certain at any rate up to the time of Samudragupta. These Indo-Scythian kings must have used the Śaka era. But this era, again, had not then become an astronomical era;⁵ and there was, therefore, no special inducement for the Early Guptas to adopt it; but, on the contrary, there was an objection of the kind already indicated. Further, the Vikrama era was not an astronomical era; and the use of it, in those days, under the name of the Mālava era, was probably confined to the different sections of the Mālava tribe, and to territories of which no part was brought under the Early Gupta sway until the time of Samudragupta. And, finally, the Kaliyuga era in all probability was used only

¹ See page 8 ff. above.

² *Jour. R. As. Soc. N. S.* Vol. IV. p. 128 f.

³ *Early History of the Dekkan*, p. 27.

⁴ *id.* p. 122.

⁵ See Appendix I. below

by the astronomers of Ujjain, for purely technical purposes; and was not known at all in the territories in which the Early Guptas first rose to power. In fact, **in India itself there was no already existing era which would recommend itself to the Early Guptas.** And we have next to inquire whether there may have been any such era, beyond the limits of India proper.

By a comparison of the dates of Sivadéva I. and Amśuvarman, at page 95 f. above, I have already shewn, in a general way, that **the Gupta era was in use beyond the north-eastern frontier of India, in Nêpâl;** a fact which is duly corroborated by the results for the date in the inscription of Mānzadéva, of the year 386. We must, therefore, now see what more particular information can be gathered from the epigraphical records of that country.¹

¹ And here we may note that the Kings of Valabhi can have had nothing to do either with the introduction of an era into Nêpâl, or with the borrowing of an era from that country. As I have already had occasion to remark, the members of the Valabhi family, for the first six or seven generations inclusive of Bhatârka, were mere feudatory *Sênâpatis* and *Mahârâjas*; and these members of the family, at any rate, cannot possibly have conquered Nêpâl, or even have extended their territory up to the confines of that country. The first of the family who claimed to be a paramount sovereign is Dharaséna IV. with the dates of 326 and 330; and with the titles of *Paramahattâraka*, *Mahârâjadhirâja*, and *Paramésvara*, in common with all his successors, and also with that of *Chakravartin*, which, not being assumed by any of his successors, may perhaps indicate that his power was more extensive than theirs ever was. Now, in passing, if we refer his first date of 326 to the epoch of A.D. 319-20, the result, A.D. 645-46, brings us to a very suitable period indeed for him to assume the position and titles of a paramount sovereign; *viz.* to the commencement of the anarchy which, as Martwan-lin tells us (*Ind. Ant.* Vol. IX. p. 20) attended the death of Harshavardhana, "the warlike lord of all the region of the north." It ended in the complete disruption, for the time, of the kingdom of Kanauj. Amśuvarman became paramount in Nêpâl, and Âdityaséna in Magadha; and the opportunity was of course taken advantage of by Dharaséna IV., to assert his independence in the west of India. But, to say nothing of the improbability of the thing on other grounds, the fact that Amśuvarman became king of Nêpâl, is in itself enough to prevent our admitting the possibility of a conquest of that country by Dharaséna IV. Referring the same date of 326 to the three earlier proposed epochs, we have respectively A.D. 403, 492, and 516. For these periods there is, perhaps, no particular objection to our assuming, for the sake of argument, that Dharaséna IV. may have extended his power over a considerable portion of Northern India, in the parts nearer to Kâthiâwâd and Gujarât. But the Valabhi charters, in which a conquest so extensive as that of the whole of Northern India up to Nêpâl, or inclusive of that country, would most certainly have been recorded, give not the slightest hint of any such event at any time in the history of the family. In fact, with the exception of the allusion to the overthrow of the Maitrakas by Bhatârka, they give absolutely no detailed information at all in connection with any of the successes claimed by the members of this family; which tends to shew very plainly that, from beginning to end, the Valabhi power was purely local. And, in connection with the earlier proposed epochs, even if Dharaséna IV. did conquer Nêpâl, or Northern India up to the frontier of Nêpâl, and did introduce there the era of A.D. 319-20, the question still remains, and cannot be answered,—Why should he act with such extreme inconsistency as to introduce there this era, which, according to those who have sought to establish those epochs, was not brought into actual use in his own territory; instead of the Gupta era which he himself, and his successors, continued to employ for all the official purposes of their own kingdom?

In Appendix IV. below, I give an account of such of the **inscriptions from Népâl** as have any bearing on the question now under consideration. The actual dates of them range from A.D. 635 to 854; and give a fairly clear idea of the history of the reigning families of the country during that period. They shew two separate houses, ruling contemporaneously, and mostly on equal terms; and each preserving certain distinctive characteristics of its own. One of them was a family, the name of which is not mentioned in the inscriptions, but which in the *Vamsâvali* is called the Thâkurl family, issuing its charters from the house or palace called Kailâsakûtâbhavana, and uniformly using the Harsha era. The other was **the Lichchhavi family**, distinctly so named in the inscriptions, and in the *Vamsâvali* allotted to the Sûryavarnâ or solar lineage, issuing its charters from the house or palace called MAnagriha, and **uniformly using an era with the Gupta epoch.**

That **the Lichchhavi clan or tribe was one of great antiquity and power**, in the direction of Népâl, is shewn by the writings of Fa-Hian and Huen-Tsiang,¹ which connect them with events that preceded the *nirvâna* of Buddha. No exception, therefore, need be taken to the general outlines of the long account in one of the inscriptions, which, so far as the Népâl branch of the tribe is concerned, gives us the first really historical member of it in the person of Jayadêva I., who, by the ordinary allowance of time for each Hindu generation, must be referred to the period A.D. 330 to 355.

Proof of friendly relations between the Early Guptas and the Lichchhavis, at an early time, is given by the marriage of Chandragupta I. with Kumâradêvi, the daughter of Lichchhavi or of a Lichchhavi king. And, that the Lichchhavis were then at least of equal rank and power with the Early Guptas, is shewn by the pride in this alliance manifested by the latter; exhibited in the careful record of the names of Kumâradêvi, and of her father or her family, on some of the gold coins of Chandragupta I., and by the uniform application of the epithet, "daughter's son of Lichchhavi or of a Lichchhavi," to Samudragupta in the genealogical inscriptions. Again, the Allahâbâd pillar inscription shews that, even if Samudragupta did not make Népâl a tributary province, his kingdom extended up to the confines of that country.

There can be no doubt that **the Early G kings must have known the nature and origin of whatever era was being used by their Lichchhavi connections in Népâl.** And the period established for Jayadêva I. approximates so closely to A.D. 320-21, that it needs but little adjustment to place the commencement of his reign actually in that year. This arrangement would give a perfectly intelligible reason for the origin of the era, which was clung to so persistently by his descendants that they continued the use of it for at least two centuries after the introduction of the Harsha era into

¹ See Legge's *Travels of Fâ-Hien*, pp. 71, 76, Beal's *Buddhist Records of the Western World*, Vol. I. pp. xiii, lii. iv. and Vol. II. pp. 67 note, 70, 73, 77 note, 81.

Népál, and its acceptance by their immediate neighbours, the Thákuri family of Kailásakútabhavana. And no objection could be taken by the Early Gupta kings to the adoption of the era of a royal house, in their connection with which they took special pride. I think, therefore, that **in all probability the so-called Gupta era is a Lichchhavi era**, dating either from a time when the republican or tribal constitution of the Lichchhavis was abolished in favour of a monarchy; or from the commencement of the reign of Jayadéva I., as the founder of a royal house in a branch of the tribe that had settled in Népál. But the question of the origin of the era is one, of course, on which further discoveries, especially if any can be made in Népál, may be expected to throw more light.

J. F. FLEET.

4th November 1887.

APPENDIX I.

A Note on the Epoch and Reckoning of the Śaka Era.

Gen. Sir A. Cunningham's Tables,¹ and Ganpat Krishnaji's and Kero Lakshman Chhatre's almanacs, shew the period from the 5th April, A.D. 1886, to the 24th March, A.D. 1887, as corresponding to Śaka-Samvat 1808. So, also, the Śáyana-Pañchāṅg shews the same period, as corresponding to Śaka-Samvat 1808, as the ordinary *nirayana* luni-solar year; the period covered by Śaka-Samvat 1808, as a *śáyana* year, being from the 6th March, A.D. 1886, to the 22nd February, A.D. 1887. For all purposes of calculation, however, this Śaka year has to be taken as "the year 1808, expired;" even if² we were working out the very first day of it, Chaitra śukla 1. The Tables are intended for this application of the number; and there are, in fact, no grounds for doubting that the above period really is equivalent to Śaka-Samvat 1808 expired, and 1809 current. But it is quoted, for all ordinary purposes, simply as Śaka-Samvat 1808. And, if a Hindu were converting "Saturday, the 1st January, A.D. 1887," into its corresponding Hindu date, he would write down, as the result, "Śaké 1808 Pausha śukla saptamī Śanivāra;" in which, not only does he abstain from including any word meaning "expired," but he actually uses, instead even of the crude form Śaka, the Sanskrit locative Śaké, which literally means "in Śaka (1808)," *i.e.* "while Śaka 1808 is current;" and this is the meaning which the mention of the year presents to any Hindu who is not an astronomer, and

¹ The proper method of applying his Tables may perhaps be inferred from his remarks (e.g. *Indian Eras*, pp. 5, 48, 52) that the numbers of the years in Hindu dates refer to years actually elapsed; and that the Hindus count only by completed years. But I am speaking of the meaning which the Tables present to a general reader, at first sight. Thus, anyone turning to his Table XVII. p. 199, —to which there is not attached a note that the Hindu years given therein are expired years,—in order to ascertain the Śaka equivalent of A.D. 1886-87, finds Śaka-Samvat 1808; and naturally takes it as a current year. So, also, with any similar Tables; e.g. those in Mr. C. Patell's *Chronology*. Such Tables would be much more useful for general purposes, if they shewed the current Hindu years opposite the current Christian years, as is done in the case of the *samvatsaras* of the two cycles of Jupiter; leaving it to anyone who has to make a particular calculation, to take the preceding year as the basis of his work. And, in ordinary writing, the current Hindu years should certainly be quoted with the current Christian years.

² Unless with Tables based on the *Māsha-Samkrānti*, or entrance of the sun into Aries, as Prof. K. L. Chhatre's Tables are; in which the Śaka year is practically treated as commencing with the day of the *Māsha-Samkrānti*. With such Tables, for any *tithi* connected with Śaka-Samvat (1809 current and) 1808 expired, up to the *tithi* that coincided with the solar day on which the *Māsha-Samkrānti* occurred, we must work with the basis of even one year still earlier, *viz.* Śaka-Samvat 1807 expired.

who is not acquainted with the technical application of the number of the year. So, also, the same expression is used in the almanacs themselves; thus, in the first two almanacs mentioned above, "Śakē 1808 Vyaya-nāma-samvatsarē," on the title-page; and "Śakē 1808 Chaitra-śukla-pakṣhaḥ," on the top of the page which exhibits the bright fortnight of the month Chaitra; and, in the *Sāyana-Pañchāṅg*, "Śālivāhana-Śakē 1808 Vyaya-nāma-samvatsarah," on the title-page, and elsewhere "amāntaḥ Chaitra-śukla-pakṣhaḥ Śālivāhana-Śakē 1808 Vyaya-nāma-samvatsarah." In the same way, I find, for the same period, "Śakē 1808 Vyaya-nāma-samvatsarē" on the title-page of an almanac published at Pandit Umacharan Mubhatmim's Press at Gwālior; and, for the period from the 17th March, A.D. 1885, to the 4th April, A.D. 1886, "Śālibāhana-Śakē 1807," on the title-page of the *Jōdhpur Chandû-Pañchāṅg* for that year, and "Śri-Samvat 1942 Śakē 1807 Chaitra-śukla-pakṣhaḥ," in *Bapu Deva Shastri's almanac*, prepared at Benares and published at Lakhnau.

Again, in the preliminary passages that introduce the *samvatsara-phala* or '(astrological) results for the year,' and other similar matter, **Ganpat Krishnaji's and K. L. Chhatre's almanacs**, contain the passage — *atha gata-Kaliḥ 4987, śeṣha-Kaliḥ 427013; Svasti; śrīman-nṛīpa-Vikramārka-samay-ātīta-samvat¹ 1942, Hēmalamba-nāma-samvatsarē; tathā śrīman-nṛīpa-Śālivāhana-Śakē 1808, Vyaya-nāma-samvatsarē; asmin varshē rājā chandrah,—*"now the expired (portion of the) Kali (age) (is) 4987 (years); (and) the remainder of the Kali (age) (is) 427013 (years). Hail! In the year 1942 expired from the time of the glorious king Vikramārka,² (and) in the Hēmalamba *samvatsara*; so also in the Śaka (year) 1808 of the glorious king Śālivāhana, (and) in the Vyaya *samvatsara*; in this year, the king (is) the Moon." And, for the *nirayana* year, the *Sāyana-Pañchāṅg* for Śaka-Samvat 1808 has — *Kaliyugasya gata-varshāni 4987; śrīman-nṛīpa-Vikramārka-samvat³ 1943 Vilambi-samvatsarah; śrīman-nṛīpa-Śālivāhana-Śak-ābdah 1808 Vyaya-nāma-samvatsarah; ath-āsmin varshē rājā chandrah,—*"the expired years of the Kaliyuga (are) 4987; in the year 1943 of the glorious king Vikramārka, (there is) the *samvatsara* named Vilambin; (and there is) the year 1808 of the Śaka of the glorious king Śālivāhana, (and) the *samvatsara* named Vyaya; now, in this year, the king (is) the Moon." In these passages, these three almanacs again treat the Śaka year,

¹ i.e. *samvatsarē*, or *samvatsarēshu*.

² It is curious that here the Vikrama year should be distinctly specified as expired, while the Śaka year is not qualified in the same manner; as if a distinction were being made in the methods of reckoning the two eras

³ i.e. *samvatsarē*, or *samvatsarēshu*.—The figures here, and in the Gwālior almanac, 1943, differ from those in Ganpat Krishnaji's and K. L. Chhatre's almanacs, 1942, because the latter quote the southern reckoning, by which each Vikrama year commences with the month Kārttika, seven lunations later than the same year in the northern reckoning; consequently, at the commencement of Śaka-Samvat 1808 (expired), on the first day of the bright fortnight of Chaitra, Vikrama-Samvat 1492 was still running, by the southern reckoning.

apparently, as a current year. The **Gwālīor almanac**, however, which I have quoted above, has — gata-Kalih 4987, śēsha-Kalih 427013; tan-madhyē gata-Śakāḥ 1808, śēsha-Śakāḥ 16192 Svasti, śrī-Vikramārka-rājya-samayād atit samvat¹ 1943, Śāka-gata-varshēshu 1808, chāndra-mānēna Vyaya-nāma-samvat-sarē; Bārhaspatya-mānēna, Śakē 1807 Āśvina-krishna-7 Śukrē sūry-odayād gata-ghaṭṭ-shu 47 palēshu 24 tad-avadhi, Śakē 1808 Āśvina-krishna-14 Bhaumē ghatī[shu*] 46 palē[shu*] 3 tāvat-paryantam, Vilambi-samvatsar-ōllēkhaḥ vidhēyah, tad-agrē Vikārī-samvatsar-ōllēkhaḥ kāryah; Chaitr-ādau rājā chandrah,— “ the expired (*portion of the*) Kali (*age*) (*is*) 4987 (*years*), (*and*) the remainder of the Kali (*age*) is 427013 (*years*); in it, the expired (*portion of the*) Śāka (*era*) (*is*) 1808 (*years*); and the remainder of the Śāka (*era*) (*is*) 16192 (*years*) Hail In the year 1943 expired from the time of the reign of the glorious Vikramārka, (*and*) in the expired Śāka year 1808, (*and*), by the lunar reckoning, in the (*current*) *samvatsara* named Vyaya,²—by the reckoning of Jupiter, the Vilambin *samvatsara* is to be used in writings from the expiration of 47 *ghaṭṭis*, 24 *palas*, from sunrise on Friday, the seventh lunar day of the dark fortnight of Āśvina, in Śāka 1807, up to (*the expiration of*) 46 *ghaṭṭis*, 3 *palas*, (*from sunrise*) on Tuesday, the fourteenth lunar day of the dark fortnight of Āśvina, in Śāka 1808; after that, the Vikārīn *samvatsara* is to be used in writings,—at the beginning of Chaitra, the king (*is*) the Moon ” Passages of a similar kind with those quoted above, occur at the end of each almanac, in connection with the *Samkrāntis*.

In the same passages for the *śalyana* year, Śāka-Samvat 1808, the **Sāyana-Pañchāṅg** does not confine itself to any indefinite expression, but explicitly quotes the Śāka year as a current year; thus — Kaliyugasya samdhyāyā āditah, Śālivāhana-Śak-ārambhakāla-paryantam, Nand-ādr-Indu-guṇa-(3179)-mitāni saura-varshāny-atitāni; pravartamāna-Śālivāhana-Śak-ābdah asht-ōttar-āshtādaśa-(1808)-mitah; amuṁ samvatsaram Narmadāyā dakṣhiṇa-bhāgē Vyaya-nāmnā vyavaharanti, uttara-bhāgē cha Vilambi-nāmnā; ath-āsmin varshē rājā Śānih,—“ from the commencement of the *samdhyā*³ of the Kaliyuga, up to the time of the commencement of the Śālivāhana-Śāka, there expired solar years which are measured by the (nine) Nandas, the (seven) mountains, the (one) moon, and the (three) qualities, (3179); (*and*) the current year of the Śālivāhana-Śāka is measured by eighteen hundred, increased by eight, (1808); on the south side of the

¹ i.e. *atitē samvatsarē*, or *atitēshu samvatsarēshu*.

² The context is “ at the beginning of Chaitra, the king (*is*) the moon,” a little further on. The intervening matter is by way of a parenthesis.

³ *samdhyā*, which is usually translatable by ‘morning or evening twilight,’ means, as applied to any of the four ages, a long period that runs at the commencement of each, before the full development of the age itself. The *samdhyā* of the Kali age is one hundred divine years, equivalent to 36,000 years of men; so that we are still only in this period. The age itself will run for 360,000 years of men. And it will end with a *samdhyā* of 36,000 years of men. These figures make up the total of 432,000 years in the age.

Narmadā, they distinguish this *samvatsara* by the name of Vyaya; and, on the north side, by the name of Vilambin; now, in this year, the king (*is*) Saturn." But, in the corresponding passage in the same almanac for the preceding year, Śaka-Samvat 1807, after giving in the same words the number of the solar years that had expired from the commencement of the *samhāyā* of the Kaliyuga up to the commencement of the Śaka era, the text runs — tatō vartamāna-vatsar-ārambhakāla-paryantam sapt-ōttar-aṣṭādaśa-śata-(1807)-mitāni varshāni gatāni; amuṁ vartamāna-samvatsaram Narmadāyā dakṣiṇē bhāgē Pārthiva-nāmnā vyavaharanti, uttarē bhāgē cha Hēmalamba-nāmnā; ath-āsmin varshē rājā Bhaumaḥ,—“from then, up to the commencement of the current year, there have expired years which are measured by eighteen hundred, increased by seven, (1807); on the south side of the Narmadā, they distinguish this current *samvatsara* by the name of Pārthiva; and, on the north side, by the name of Hēmalamba; now, in this year, the king (*is*) Mars.” In passing, therefore, from Śaka-Samvat 1807 to 1808, a verbal distinction, at least, was made between expired and current years; and the phraseology adopted in the almanac for Śaka-Samvat 1808, has been repeated in the almanac for the next year, 1809. In one instance, A. D. 85-86, the Pārthiva or Hēmalamba *samvatsara*, each current, was treated as equivalent to Śaka-Samvat 1807 expired; while, in the other, A. D. 1886-87, the Vyaya or Vilambin *samvatsara*, each current, and each the next in the cycle after respectively Pārthiva and Hēmalamba, is treated as equivalent to Śaka-Samvat 1808 current. What were the reasons for this change, I do not know; and I will leave it to Mr. Sh. B. Dikshit, one of the editors of the almanac, to explain them elsewhere. But, by the literal interpretation of the phraseology for A. D. 1885-86, and in accordance with the principles of the Tables, that period was equivalent to Śaka-Samvat 1807 expired, (and 1808 current); and A. D. 1886-87 should have been described as being represented by Śaka-Samvat 1808 expired, (and 1809 current).

I have now to quote the fact that, in **Madras**, the same English period, A. D. 1886-87, is actually called Śaka-Samvat 1809, with the same *samvatsara* of the Sixty-Year Cycle, Vyaya, attached to it. There are, it is true, two somewhat varying practices to be found in Southern India. Thus, the **Telugu Siddhānta-Pañchāṅgam**, published, I think, in the Arcot District, gives the luni-solar period from the 5th April, A. D. 1886, to the 24th March, A. D. 1887, as being the Vyaya *samvatsara*, and as corresponding to Śaka-Samvat 1808 expired; and at the commencement, it quotes the expired years throughout; thus — “Kaliyuga-gat-ābdāḥ 4987; Śalivāhana-Śaka-gat-ābdāḥ 1808; Vikramārka-Śaka-gat-ābdāḥ 1943.” But, on the other hand, the **Telugu Calendar**, published at Madras, gives the same luni-solar period, from the 5th April, A. D. 1886, to the 24th March, A. D. 1887, as being the Vyaya *samvatsara*, and as corresponding to Śaka-Samvat

¹ Except for reading *amuṁ vartamāna-vatsaram*, and omitting *atha* before *asmin varshē*, the text is exactly the same in Bapu Deva Shastri's almanac for Śaka-Samvat 1807. I have not been able to obtain a copy of his almanac for the next year.

1809, Kaliyuga-Samvat 4988, and Vikrama-Samvat 1944, which are not specified as either current or expired, but can only be intended as current. And, in the same way, the Tamil *Siriya-Pañchāṅgam*, for the following year, published at Madras, gives the solar period from the 12th April, A.D. 1887, to the 11th April, A.D. 1888, as being the Sarvajit *samvatsara*, and as corresponding to Śaka-Samvat 1810, Kaliyuga-Samvat 4989, and Vikrama-Samvat 1935, which, similarly, are not specified as either current or expired, but can only be intended as current.¹ And, from other indications, there seems to be no doubt that, of these two practices of Southern India, thus illustrated, the popular and generally current one is the latter one, by which the period A.D. 1886-87 is quoted as Śaka-Samvat 1809; the reckoning, in this and the other eras, being thus, at first sight, one year in advance of the customary reckoning of Northern and Western India.

The difference, however, is only an apparent one; and is due to the evident fact that the Madras reckoning has preserved the system of current years, while the other is regulated by expired years. But it is almost always the reckoning of Northern and Western India that is now quoted. And the years of it, though really expired years, are not distinctly and habitually quoted as such. And hence there is a general understanding that, as between the Śaka and the Christian eras, the additive quantity, to be applied to the former, is 78-79;² and that the epoch or year 0 of the Śaka era, is the period from the 3rd March, A.D. 78, to the 20th February, A.D. 79, both included; and its commencement, or first current year, the period from the 21st February, A.D. 79, to the 10th March, A.D. 80, both included.³ This, however, really gives current Christian years,

¹ Here the 3 in the tens place must be a mistake for 4.

² It would appear that the Tamil *Vākyā-Pañchāṅgam*, published at Madras, gives the solar period from the 12th April A.D. 1887, to the 10th April, A.D. 1888, as being the Sarvajit *samvatsara*, and as corresponding to Śaka-Samvat 1809, Kaliyuga-Samvat 4988, and Vikrama-Samvat 1945; all of which are distinctly specified as current. But this cannot possibly be correct, in respect of the Śaka and Kaliyuga years.

³ Thus, even Dr. R. G. Bhandarkar, — through whose "Note on the Śaka Dates and the Years of the Bārhaspatya Cycle, occurring in the Inscriptions" (*Early History of the Dekkan*, p. 105 ff.) my attention was first drawn to the desirability of examining the details of the almanacs, — has written (*id. p.* 99, the italics are his) "191 Gupta *past* + 242 = 433 Śaka *current* + 78 = 511 A.D. *current* 209 Gupta *past* + 242 = 451 Śaka *current* + 78 = 529 A.D. *current*." I myself had the same view, till not very long ago. Other writers could easily be shewn to have lain under the same misconception. And Dr. Burnell even went so far as to say (*South-Indian Palæography*, p. 72, note) "the rough equation for converting this era into the Christian date, is + 78½. The beginning of the year being at the March equinox; if the Śaka *astin*" (*i.e.* expired) "year be mentioned, the equation is + 79½."

⁴ I owe these four dates to Mr. Sh. B. Dikshit. Gen. Cunningham (*Indian Eras*, p. 139) gives from the 14th March, A.D. 78, to the 17th February, A.D. 79; and from the 18th February, A.D. 79, to the 8th March, A.D. 80. But a comparison of his initial days for the epoch and the first year, shews at once that there is some mistake. The 18th February is twenty-four days earlier than the 14th March; whereas the difference should be only eleven days. Mr. C. Patell (*Chronology*, p. 96) does not give the initial day of the epoch; but gives, in the same way, the period from the 18th February, A.D. 79, to the 8th March, A.D. 80, for the first year.

equivalent to expired Śaka years. It is evident from the details given above regarding Śaka-Samvat 1808 and 1809, that, according to the reckoning of the era as fixed by the early astronomers, and as preserved to the present day, the true epoch is A.D. 77-78, and the period from the 3rd March, A.D. 78, to the 20th February, A.D. 79, is in reality the commencement, or first current year; and that, to obtain current Christian years, equivalent to current Śaka years, the true additive quantity is 77-78. But, of course, there is always the possibility that, if ever we obtain a date, with full details for calculation, in a very early Śaka year, or in one of the very earliest of the regnal or dynastic years which afterwards developed into the Śaka era, this exact equation may not hold good; in consequence of the date belonging to a period anterior to the adoption of the era by the astronomers.

The Śaka era is emphatically one of the eras that originated in an extension of regnal or dynastic years. The chief Hindu tradition about it, is, that it was founded in celebration of a defeat of the Śaka king by the king Vikrama or Vikramāditya who is also the supposed founder of the Vikrama era, commencing a hundred and thirty-five years earlier.¹ This tradition is mentioned by Alberŭnt;² but he saw through it so far as to remark "since there is a long interval between the era which is called the era of Vikramāditya and the killing of Śaka, we think that that Vikramāditya from whom the era has got its name is not identical with that one who killed Śaka, but only a namesake of his." And the tradition has now been quite exploded by the Bādāmi cave inscription of the Chalukya king Mangalīśa,³ which is specifically dated "when there have expired five centuries of the years of the installation of the Śaka king (or kings) in the sovereignty." It is certain, from this record, that the real historical starting-point of the era, is the commencement of the reign of some particular king, or kings, of the Śaka

¹ Another tradition (e.g. *Prinsep's Essays*, Vol. II. Useful Tables, p. 154) is that the era dates from the birth of Śālivāhana, king of Pratiśthāna, who opposed Vikramāditya, king of Ujjayīni. But the introduction of the name of Śālivāhana in connection with the era, is of comparatively modern date, the earliest instance that I have succeeded in obtaining, being one of the thirteenth century A.D.; and the epigraphical instances speak of the year as having been 'established, settled, or decided' (*nirṇīta*) by Śālivāhana, but not as running from his birth (see *Ind. Ant.* Vol. XII p. 214 f.).—A passage to the latter effect has been quoted by Prof. Max Müller (*India; What can it teach us?* p. 300 f.) from the *Muhūrtabhuvanāmārtanda* of Nārāyaṇa, which means "in the year measured by three, the (nine) numerals, and the (fourteen) Indras, from the birth of Śālivāhana (i.e. in Śaka-Samvat 1493), in (the month) Tapas (Māgha), this *Mārtanda* was composed."—As Prof. Max Müller has pointed out, in his comments on this passage, it is not exactly wrong to speak of the era as the Śālivāhana-Saka or Śālivāhana era; for there are ample instances in which the Hindus give it that name, in epigraphical records of authority and of some antiquity. At the same time, those instances shew that it was only in comparatively modern times that the name of Śālivāhana came to be connected with the era. And, in all discussions respecting early dates, it is an anachronism and a mistake, to call the era by his name.

² Sachau's *Alberŭnt's India*, Translation, Vol. II. p. 6.

³ *Ind. Ant.* Vol. VI. p. 363 f., and Vol. X. p. 57 ff.

tribe; and, therefore, that the years were originally regnal or dynastic years. Now, such years must run on for a considerable time, before they can develop into a recognised era; and this is undoubtedly the reason why we find the earlier years of every such Hindu era quoted simply by the term *varsha* or *samvatsara*, 'a year,' without any dynastic appellation. Again, such regnal or dynastic years can only come to be quoted as expired years, when they have actually developed into an era which has become recognised, or is sought to be applied, by astronomers for astronomical processes; up to that point, the years, being wanted only for quasi-private dynastic purposes, would certainly be quoted as current years. It is impossible to believe that the first Śaka king decreed, immediately after his coronation, that a new era had been established from that event; that it was to come at once into general use; and that, for the convenience of astronomers, the first year, then running, was to be quoted as an expired year, which, in fact, it would be rather difficult to do. If it were sought to fix the exact chronological position of any public act performed in that first year, it might be referred to the expired years of an earlier era; e.g. of that of the Kaliyuga. 'But, for any reference to the regnal year alone, that act would be recorded as being performed "in the year one," "in the first year," or "while the first year of the reign is current;" as, for instance, "in the first year; while the *Mahārājādhirāja*, the glorious Tōramāṇa, is governing the earth," in line 1 f. of the Êraṇ inscription, No. 36, page 158. This custom would continue so long as the years were simply dynastic years; and perhaps, during the whole of that period, the years might remain purely dynastic years, each of them having for its initial day the anniversary of the original coronation from which they started, irrespective of the initial day of the years of the astronomical era still continuing in use. When, however, astronomers came to adopt them as an astronomical era, they would establish an exact epoch by reckoning back from the dynastic year then current to the last year of the Kaliyuga that had expired when the first current dynastic year commenced; in the course of which, they would simplify matters by allotting to the dynastic years the same scheme, as regards the starting-point of each year, and the arrangement of the fortnights of the months, which belonged to the Kaliyuga in their part of the country. Thus they would fix all the data necessary to enable them to use the new era for astronomical purposes. All that would remain, would be to use its expired years, in accordance with the custom and necessities of their science. The substitution of the Śaka era for the Kaliyuga, for astronomical purposes, seems to have taken place after the time of Āryabhaṭa (born A.D. 476),¹ who used the Kaliyuga, and in or just before the time of Varāhamihira (died A.D. 587),² who used the Śaka era; and probably the apparent difference of one year in the reckonings of the Śaka era will be found to have originated not far from Śaka-Samvat 500. Let us assume that this adoption of the Śaka era was made in Śaka-Samvat 500, equivalent to A.D. 577-78. The astronomers would take it, at starting, as "Śaka-

¹ *Jour. R. As. Soc. N. S. Vol. I. p. 405.*

² *Jour. R. As. Soc. N. S. Vol. I. p. 407.*

Samvat 499, expired ;" and, in quoting it and several subsequent years, would probably be careful to connect with each year a word distinctly meaning "expired." In course of time, however, such precision of expression would come to seem superfluous to them ; and, in issuing their almanacs, they would drop the word "expired," and would write, for instance, simply "Śakē 510 Chaitra-māsa-śukla-pakṣah." It would cause no difference or inconvenience to them ; because any initiate would know that this really designated the bright fortnight of the month Chaitra of Śaka-Samvat 511 current after Śaka-Samvat 510 had expired. The people at large, however, including persons who would use the almanacs for practical purposes without being properly initiated into the application of them, would be thrown back in their reckoning by a year ; and doubtless at first a good deal of inconvenience and confusion might result. But this would soon be forgotten ; or might, for the sake of convenience, be intentionally put aside. And thus they would very quickly arrive at the understanding, by which, in Northern and Western India, Śaka-Samvat 1808 answers, popularly, as a current year, not as an expired year, to the period from the 5th April, A.D. 1886, to the 24th March, A.D. 1887.

Postscript.

In connection with my remarks, on page 140 above, regarding the *Sāyana-Pañchāṅg* for Śaka-Samvat 1807 and 1808, I would add that I had drawn Mr. Sh. B. Dikshit's attention to the circumstances of the case ; and I now find that, in their almanac for Śaka-Samvat 1810 (expired) (A.D. 1888-89), the editors have reverted to the phraseology used in their almanac for Śaka-Samvat 1807 (expired.)

APPENDIX II.

A Method of Calculating the Week-Days of Hindu Tithis and the corresponding English Dates.

BY SHANKAR BALKRISHNA DIKSHIT; BOMBAY EDUCATIONAL DEPARTMENT.

In this paper I purpose to exhibit, according to the system laid down by the late Professor Kero Lakshman Chhatre in his book entitled *Graha-sddhandchhām Kōshjakhām*, or "Tables for Calculating the Places of the Planets," the correct method by which we may determine, for any given Hindu *tithi* or lunar day, the corresponding *vāra* or week-day, and the equivalent English date according to either the Julian or the Gregorian Calendar.

Before detailing, however, the steps of the process, I will explain the principal technical terms which will be used, and which, for the sake of brevity and conciseness, will be retained in their original Sanskrit forms.¹

Explanation of Technical Terms.

The *abdapa*, *lit.* 'lord of a year,' of any particular year, is the conventional term, — in Prof. K. L. Chhatre's book, and others; but not universally, — for the time of the *Mēsha-Samkrānti*, or 'entrance of the Sun into Aries, in that year. The *abdapa* adopted by Prof. K. L. Chhatre is the time of the *spashṭa* or 'apparent,' — *lit.* 'clearly perceived, distinctly visible,' — *Mēsha-Samkrānti*, as ascertained by the method given in the *Sūrya-Siddhānta*;² whereas, in other Hindu works of the same kind, the term *abdapa*

¹ Most of these explanations are my own. Either to reduce the bulk of his book, or for some other reason, Prof. K. L. Chhatre has used the technical terms without explanation, except in the case of a few of the simpler ones; nor does he explain how he obtained certain figures for certain years or the variation for a year.

² English astronomers use the word 'apparent' in all cases in which we use *spashṭa*. 'Apparent,' therefore, is the proper translation of *spashṭa*.

³ There are three schools of astronomers in India. One follows the *Sūrya-Siddhānta*, and is called *Sanrapaksha*; another follows the *Brahma-Siddhānta*, and is named *Brahmapaksha*; while the third follows the *Ārya-Siddhānta*, and is called *Āryapaksha*. The main point on which they differ is the length of the year; but with differences, between each other, of only a few *vipalas* (a *vipala* is the sixtieth part of a *pala*). Another point of difference is, that the number of revolutions of the moon, planets, &c., in a certain period, — for instance in a *Mahāyuga*, — is generally different in each of them. Prof. K. L. Chhatre has adopted, from the *Sūrya-Siddhānta*, only the length of the year, and its starting-point, that is the *Mēsha-Samkrānti*; in almost every other respect he follows none of these three authorities, but has based his Tables on European Tables of planets. As to his Tables relative to *tithis*, however, in the part of his work called *Kala-sddhāna*, see page 149 below, Note 11, and the text above note 1 on page 153.

is used as meaning the time of the Sun's entrance into Aries with reference to his *madhyama* or 'mean' longitude. So, also, the length of the solar year adopted by him is that of the *Sārya-Siddhānta*, which is accepted, in the present day, in most parts of India. It should, however, be borne in mind that the Tables of the sun and the moon, and those of the planets, given by him, are based on European Tables; and that the places of the sun and other heavenly bodies, obtained from his book, are reckoned from the equinoctial point. The starting-point adopted by Hindu astronomers, for reckoning the places of heavenly bodies, coincided, in their opinion, with the equinoctial point about Śāka-Samvat 444 expired (A.D. 522-23). The interval in time between two successive returns of the sun to the vernal equinox,—called "the tropical year,"—amounts at present to 365 days, 14 *ghaṭṭas*, and 31'972 *palas*; while the length of the year, according to the *Sārya-Siddhānta*, is 365 days, 15 *ghaṭṭas*, and 31'523 *palas*. During this time, the sun's motion amounts to one complete revolution from equinox to equinox, plus about 58'688 seconds of arc. The starting-point, therefore, of the Hindu astronomers is at present a little more than twenty-two degrees to the east of the vernal equinox. This difference is called *ayandhāntas*, *lit.* 'degrees of precession;' and the *ayandhāntas* for the present year, Śāka-Samvat 1809 expired (A.D. 1887-88), are 22 degrees, 45 minutes, according to the *Graha-Laghava* of Gaṇeśa Daivajña.¹ As the longitudes of heavenly bodies, reckoned from the equinox, include these *ayandhāntas*, they are called *śāyana*, *lit.* 'possessed of *ayana* or precession.' And the places of heavenly bodies obtained by the method given in the *Sārya-Siddhānta* and other Hindu works, are called, for the sake of distinction, *nirāyana*, *lit.* 'destitute of precession.' The places obtained from Prof. K. L. Chhatre's Tables are *śāyana*. The *tīthi*, however, obtained by either process, is the same; but this is not the case with the *nakṣatra* or 'lunar mansion,' and the *yōga* or 'addition of the longitudes of the sun and the moon.'²

The figures for the *abdapa* are given in Table I. on pp. 10, 11, of Prof. K. L. Chhatre's book, and are expressed in *vāras*, *ghaṭṭas*, and *palas*. Of these, the *vāra*, or week-day, sometimes also called *dina* or *divasa*, or 'solar day (and night),' is counted in regular order from Sunday, as 1, up to Saturday, as 7 or 0; and it is always reckoned by

¹The date of this work is Śāka-Samvat 1442 expired (A.D. 1520-21). At present, all the *Pañcāṅga* (Hindu calendars) in the Dekkan, and in some other parts of India, are prepared from this authority, and from another small work, by the same author, entitled *Tīthi-Chintāmaṇi*, containing the necessary Tables.

²To calculate *tīthi*, only the difference between the longitudes of the moon and of the sun is to be taken. Therefore it matters not whether these longitudes are *śāyana* or *nirāyana*. To find a *nakṣatra*, the *ayandhāntas* must be applied to the moon's longitude obtained from Prof. K. L. Chhatre's Tables. The *Śāyana-Pañcāṅga*, annually published, from Śāka 1806, under the patronage of His Highness the Maharaja Hōlkar, by Mr. Visaji Raghunath Lale of Gwalior, with the aid of Mr. Jansardan B. Modak, B.A. of the Bombay University, of Mysol, and of Mr. Krishnarao Raghunath Bhale of Indre, is based on the *śāyana* system.

the Hindus from sunrise to sunrise. The *vāra* of the *abdāpa* shows the week-day on which the *Māsha-Samkrānti* of the year fell. A *ghaṭi*, also *ghaṭi* and *ghaṭikā*, is the sixtieth division of a mean solar day and night; and it is, therefore, equal to twenty-four English minutes. As a matter of convenience, the word *ghaṭi* is also used for the sixtieth part of a *tithi*; but in that application it is not identical with the sixtieth division of a solar day and night. A *pala* is the sixtieth division of a *ghaṭi*; and is, therefore, equal to twenty-four English seconds. And the *ghaṭis* and *palas* of the *abdāpa* give the time after sunrise, on the particular *vāra*, at which the *Māsha-Samkrānti* took place. Thus, the *abdāpa* of Śaka-Samvat 0 expired, is given (opposite the entry *Māsha-Samkrānti* *vāra* or 'time of the *Māsha-Samkrānti*,' p. 10) as 1 *dina*, 10 *ghaṭis*, 10 *palas*; which indicates that the *Māsha-Samkrānti* then took place on Sunday, and 10 *ghaṭis* and 10 *palas*, or four hours and four minutes, after sunrise. The solar year adopted by Prof. K. L. Chhatre is equal to 365 *days*, 15 *ghaṭis*, 31'52 *palas*. Dividing 365 by 7 (the number of days in a week), the remainder is 1. And so, if in one year the Sun enters Aries at the time of sunrise on a Sunday, then, in the following year, he will come to Aries on Monday, and 15 *ghaṭis*, 31'5 *palas*, after sunrise. Therefore, the variation in the *abdāpa* in one year is given (p. 10, col. 3, under *vāra*) as 1 *day*, 15 *ghaṭis*, 31'5 *palas*; the decimals being supplied from column 2, in which is given the number of days, corresponding to the number of years in column 1.

The word *tithi* denotes the thirtieth part of a lunation or lunar month; that is, as applied to the ecliptic circle, it denotes exactly the one-thirtieth part of that circle, *viz.* twelve degrees; but, taken as an apparent *tithi*, and applied to the period of a lunation, it may be the exact thirtieth part of that period, or it may vary from fifty to sixty-six *ghaṭis* as subdivisions of a solar day. If the word *tithi* requires to be rendered into English, it is best represented by 'lunar day.' Of the thirty *tithis* of each month, fifteen belong to the bright fortnight, or period of the waxing moon, and fifteen to the dark fortnight, or period of the waning moon. The fifteenth *tithi* of the bright fortnight is called *pūrṇimā*, *pūrṇamāsī*, or *paurṇamāsī*, *iit.* 'that which has the full-moon, or that on which the month is completed;' and the fifteenth *tithi* of the dark fortnight is called *amāvāsī*, *iit.* 'that on which there is the dwelling-together (of the sun and moon).' At the end of the *amāvāsī*, the sun and the moon are together; that is, they have the same longitude. When the moon, moving towards the east, leaves the sun behind by twelve degrees of longitude, then ends the first *tithi*, which is technically called *pratipad* or *pratipadd*. So, a *tithi* is the time which the moon takes to out-go the sun by twelve degrees. With the exception of the *pratipadd*, the *tithis* are denoted by the regular ordinal numerals, *dvitīyā*, *trīthya*, &c., up to *chaturdāśī*, 'the fourteenth.' The *pūrṇimā* and *amāvāsī* are called sometimes by their own special names, and sometimes *pañcodaśī*, 'the fifteenth,' but the *amāvāsī* is generally entered in *Pañcodaśī* as the thirtieth *tithi*.

even in Northern India, where the dark fortnight of the month precedes the bright.¹ In *Pañchāṅgs*, the *ghaṭis* and *palas* of *tithis* are given; and, by them, it is to be understood that the *tithis* end so many *ghaṭis* and *palas* after sun-rise. In general, the expression *tithi* means the end of a *tithi*; not its beginning, or its duration.

The term *tithi-suddhi*, *lit.* 'the subtraction of *tithis*,' denotes the number of *tithis* that elapse from the beginning of the month Chaitra (March-April) up to the time of the *Mśha-Samkrānti*. In Prof. K. L. Chhatre's Tables, this term is used to shew the number of *tithis*, calculated from the difference between the moon's mean longitude and the sun's apparent longitude, that elapse from the beginning of Chaitra to the time of the sun's *spashṭa* or 'apparent' *Mśha-Samkrānti*.² Thus, for Śaka-Samvat 0 expired, at the time of the *Mśha-Samkrānti* the sun's mean longitude was 11 signs, 20 degrees, 46' 1 minutes (p. 46); and the apparent longitude obtained from it, according to the method given by Prof. K. L. Chhatre, is 11 signs, 22 degrees, 38' 9 minutes. The moon's mean longitude at that time was 4 signs, 25 degrees, 42' 4 minutes (p. 87). The difference between the longitudes of the sun and the moon,—the sun's longitude being subtracted from that of the moon,—is, therefore, 5 signs, 3 degrees (= 153 degrees), 35 minutes. Then $153^{\circ} 3' 5 + 12 = 12 + (9^{\circ} 3' 5 + 12)$ *tithis*; that is, 12 *tithis*, and about 45 *ghaṭis* and 14 *palas*, had elapsed. This, therefore, is given as the *tithi-suddhi* for Śaka-Samvat 0 expired. In one solar year, the mean *tithis* are 371, and 3 *ghaṭis*, 53' 4 *palas*. Dividing 371 by 360, the remainder, 11 *tithis*, 3 *ghaṭis*, 53' 4 *palas*, is given as the variation in the *tithi-suddhi* in one year (p. 10, col. 4).

The *tithis* obtained from the mean places and mean motions of both the sun and the moon, are *madhyama* or 'mean' *tithis*. So, also, those calculated from the apparent place and motion of the sun and the mean place and motion of the moon,—as in the case of the *tithi-suddhi* and the mean solar equivalents of *tithis* given in Table III. pp. 13-19, col. 2,—may be called mean *tithis* and not apparent. But the *tithis*, &c., given in our *Pañchāṅgs* are always *spashṭa* or 'apparent';³ that is, they are calculated from the apparent places and motions of the sun and the moon. The *spashṭa-tithi* differs from the *madhyama-tithi* sometimes by nearly twenty-five *ghaṭis*; and this is chiefly owing to the fact that the moon's apparent longitude differs from her mean longitude sometimes by about five degrees.⁴ Many corrections have to be applied to the mean place of the

¹ In astronomical works, it is always the *Amānta* southern arrangement of the lunar fortnights that is actually taken for calculations.

² In the *Siddhānta-Sīromani* and other works, the term *tithi-suddhi* is used in the sense of the number of *tithis*, calculated from the mean places of the sun and the moon, that elapse from the beginning of Chaitra to the time of the sun's *madhyama* or 'mean' *Mśha-Samkrānti*.

³ Though not always in the strictest sense. I say so, because, in practice, extreme accuracy is not, and cannot be, sought. But, in theory, they are required to be 'apparent' in the strictest sense.

⁴ According to European Tables, the difference is sometimes about eight degrees

moon in order to find her apparent place; but only one of these, called *phala-samskāra*, which is 'the equation of the centre,' is taken into account by Hindu astronomers:¹ and this, as given by them, amounts to a little more than five degrees at the greatest. This correction varies according to the moon's *kēndra* or 'anomaly;' which is taken to be her distance from apogee.² From this correction is calculated the correction in time to be applied to the mean *tithi*; it is named *parākhyā*; and it is given in Table IV., on p. 20, in the column headed *parākhyā*. It evidently varies according to the moon's *kēndra*. One revolution of the moon's *kēndra* is completed in 27 days, 33 *ghaṭṭas*, 16' 56 *palas*. This period is called *nichhōchcha-māsa*;³ and is known to English astronomers by the name of the 'anomalous month.' This period, converted into *tithis*,⁴ is equal to 27 *tithis*, 59 *ghaṭṭas*, 33' 36 *palas*; that is, nearly and practically, 28 *tithis*. It is converted into *tithis* for the sake of convenience; since, the variation in the *kēndra* is one *tithi* of *kēndra* in one *tithi* of time; and it is called *tithi-kēndra*, or 'the anomaly of the *tithi*, expressed in *tithis*.' The moon's mean *kēndra* at the *Mēsha-Samkrānti* of Śaka-Samvat 0 expired, was 10 signs, 19 degrees, 58' 8 minutes (p. 87). This, converted into *tithis*, is equal to 24 *tithis*, 52 *ghaṭṭas*, 50 *palas*;⁵ and this is given (p. 10) as the *tithi-madhyama-kēndra*, or 'mean anomaly of the *tithi*,' at the time of the *Mēsha-Samkrānti* of Śaka-Samvat 0 expired. It shews that so many *tithis* and parts of a *tithi* had elapsed, up to that *Mēsha-Samkrānti*, from the moon's preceding arrival at her apogee. The variation in the moon's *kēndra*, in one solar year, is 3 signs, 2 degrees, 6' 2 minutes (p. 87, col. 3). This, changed into *tithis* by the rule of three, *vis.*— $360^{\circ} : 92^{\circ} 6' 2'' :: ti. 27, gh. 59, p. 33' 36 : ti. 7, gh. 9, p. 42$,—is given, therefore, as the variation in the *tithi-kēndra* in one year (p. 10, col. 5).

A few other points and terms will be explained, as we proceed with the following example.

To find the Week-Day of a given Tithi.

The process will be best illustrated, step by step, by actually working out an example. And, at Mr. Fleet's request, I take, as my example, the date of Śaka-Samvat 406

¹ The amount of this correction, adopted by Prof. K. L. Chhatre, in finding out *tithis* in his *Kāla-siddhānta* Tables (pp. 1 to 30 of his book), is nearly the same as that adopted by ancient Hindu astronomers. Therefore, the *tithis* obtained by his method, as described above, should agree very closely with those obtained from the methods prescribed in Sanskrit works. But, in the *abdhāpa* and other elements, the *Sūrya-Siddhānta* and other authorities themselves slightly differ, one from the other. And, accordingly the difference will be sometimes about five or six *ghaṭṭas*. There are, also, some other minute causes of difference.

² In European astronomical works, the anomaly is reckoned from perigee or perihelion; but in Hindu works it is reckoned from apogee or aphelion.

³ In this term *nichhōchcha* means 'perigee;' and *uchchha*, 'apogee.' And *nichhōchcha-māsa* is the period in which the moon comes from perigee or apogee to the same point again.

⁴ One *tithi* is equal to 0'9843599572 of a mean solar day.

⁵ 360 : 329'58"8 :: *ti.* 27, *gh.* 59, *p.* 33'36 : *ti.* 24, *gh.* 52, *p.* 50.

expired (A.D. 484-85); the month Āshādha (June-July); the bright fortnight; the twelfth tithi.

From Table I. p. 10, write down (see Table V. on page 151 below), in three separate columns, three quantities, for Śaka-Samvat 0 expired, which are technically called the *kabhēpaka* or 'additive quantities'; *vis.* in (a) the *abdapa*, enter *vāras* 1, *ghaṭks* 10, *palas* 10; in (b) the *tithi-suddhi*, enter *tithis* 12, *ghaṭks* 45, *palas* 14; and in (c) the *tithi-madhyama-kēndra*, enter *tithis* 24, *ghaṭks* 52, *palas* 50. Below each of them respectively, in its proper column, enter, from the same Table, the *bhēda* or 'variation' for the component parts of the given Śaka year; *vis.* for 400, in (a) *vāras* 6, *gh.* 30, *p.* 9'3, in (b) *tithis* 15, *gh.* 55, *p.* 49'2, and in (c) *tithis* 9, *gh.* 24, *p.* 45; and for 6 years, in (a) *vāras* 0, *gh.* 33, *p.* 9'1, in (b) *tithis* 6, *gh.* 23, *p.* 20'2, and in (c) *tithis* 14, *gh.* 58, *p.* 39.

Now, as the given year is anterior to Śaka-Samvat 1622 expired, a correction, to be arrived at from Table II. p. 12, is to be applied, and is always to be added, in respect of the *tithi-suddhi* and the *tithi-madhyama-kēndra*. The reason for this correction, is this. As explained above, the *tithi-suddhi* and the *tithi-madhyama-kēndra* depend respectively on the mean longitude and the mean anomaly of the moon. But the moon's mean motion is not always the same. Therefore, to her mean longitude and mean anomaly, obtained from the general Table of annual variation in them (Table III. p. 87 f., cols. 2, 3), a correction (Table IV. p. 89 f., cols. 2, 3) is to be applied. Thus, for Śaka-Samvat 0 expired, the correction in the moon's mean longitude is 44 seconds, and that in the *kēndra* is 2 degrees, 55 seconds (p. 90). These, turned into *tithis*, are 3 *ghaṭks*, 40 *palas*, with regard to the *tithi-suddhi*; and 14 *ghaṭks*, with regard to the *tithi-kēndra*. These figures, therefore, are given as the correction in respectively the *tithi-suddhi* and the *tithi-kēndra* for Śaka-Samvat 0 expired. In the Table, this correction is given for intervals of 1000 years each. Taking first the *tithi-suddhi*, the correction for Śaka-Samvat 0 expired, is *gh.* 3, *p.* 4c; and the correction for Śaka-Samvat 1000 expired, is *p.* 32. Therefore, deducting the latter from the former, the difference, *gh.* 3, *p.* 8, or 188 *palas*, is the variation of correction in 1000 years.¹ Then, by the Rule of Three,—1000 years : 406 years :: 188 *palas* : 76 *palas*. And 76 *palas* are *gh.* 1, *p.* 16. As the quantities are decreasing ones, this is to be subtracted from *gh.* 3, *p.* 40, for Śaka-Samvat 0 expired. And the remainder gives us, as the sufficiently approximate correction for Śaka-Samvat 406 expired, *gh.* 2, *p.* 24, to be added in (b). Similarly, the correction for the *tithi-madhyama-kēndra*, worked out in the same way, is *gh.* 9, *p.* 8, to be added in (c).

¹ The decimals in the *palas* of (a) the *abdapa* are taken from the *ahargana*, or total number of solar days of the solar year, in col 2.

² Properly speaking, this variation is for Śaka-Samvat 500 expired, midway between Śaka-Samvat 0 and 1000. It should be reduced first for the year midway between Śaka-Samvat 0 and the given year; in this instance 406. But there is no absolute necessity for such exact precision.

TABLE V.

Calculation of the Week-day of a given Tithi.

Saka-Samvat 406 expired = A. D. 484-85 current.

Āshāḍha (June-July); the bright fortnight; the 12th tithi; Saraguruvāra (Thursday).

(a) Abdya.	(b) Tithi-oddhi.	(c) Tithi-madhya-śodra.
vāra gh. p.	tithi gh. p.	tithi gh. p.
Saka-Samvat 0 expired (p. 10) 1 10 10 12 45 14 24 52 50
Add variation for 400 Saka years (p. 11) 6 30 9'3 15 55 49'3 9 24 45
Add variation for 6 Saka years (p. 10) 0 33 9'1 6 23 30'2 14 58 39
Add correction for a date prior to Saka-Samvat 1622 expired 0 2 24 0 9 8
Week-day and time of the <i>Mśha-Samvṛanti</i> of Saka-Samvat 406 expired 1 13 28'4	<i>tithi-dhruva</i> and <i>bhukta-tithi</i> .. 5 6 47'4	21 25 22
	From one <i>tithi</i> . 1 0 0	
	Deduct <i>bhukta-tithi</i> 0 6 47	Add, from (b) the <i>bhḍgya-tithi</i> ... 0 53 13
	<i>bhḍgya-tithi</i> ... 0 53 13	<i>tithi-spashṭa-kāndra</i> 22 18 35
<i>ghaṭṭis</i> and <i>palas</i> only, from above 0 13 28	Deduct as many <i>palas</i> as there are <i>ghaṭṭis</i> in the <i>bhḍgya-tithi</i> .. 0 0 53	
Add, from (b), the mean solar day 0 52 20	Mean solar day . 0 52 20	
<i>tithi-bhḍga</i> 1 5 48		
Add:—		
expired <i>tithis</i> :—		
Chaitra 15		
Vaiśākha 30		
Jyēshṭha 30		
Āshāḍha 26		
101		
minus, from (b), <i>tithi-dhruva</i> 5		
expired <i>tithis</i> from end of Chaitra <i>śukla</i> 5 96		
solar equivalent of 96 <i>tithis</i> (p. 14) 94 17 36		
95 23 24		
Add <i>parādhya</i> , obtained from (c) <i>tithi-spashṭa-kāndra</i> of Āshāḍha <i>śukla</i> 12 0 24 19		
Days elapsed up to end of apparent Āshāḍha <i>śukla</i> 12 95 47 43		
Add week-day of <i>Mśha-Samvṛanti</i> of Saka-Samvat 406 expired 1		
Reduce to weeks 7)96 (13		
91		
Reminder, the 5th day, is Thursday 5	Result; Thursday.	

Now add together the respective quantities in (a) (b) and (c), bearing in mind that, in doing so, when the *vāras* in (a) the *abdapa* exceed 7, or any multiple of 7, only the remainder, above 7 or its multiple, is to be brought to account, because there are 7 *vāras* or week-days in each week; and that, when the *tithis* in (b) the *tithi-suddhi* and in (c) the *tithi-madhyama-kēndra* exceed 30 and 28 respectively, or any multiple of them, only the remainders above 30 and 28, or their multiple, are to be taken notice of, because there are 30 *tithis* in one lunar month, and, as nearly as possible, 28 *tithis* in one revolution of the *tithi-kēndra*.

We thus obtain in (a) the *abdapa*, *vāras* 1, *gh.* 13, *p.* 28⁴. The first quantity, of the days, shews that the week-day on which occurred the *Mēsha-Samkrānti* of the given year, Śāka-Samvat 406 expired, was Sunday. And the remaining quantities shew that the *Mēsha-Samkrānti* took place at the end of *gh.* 13, *p.* 28 4, after sunrise on that Sunday. The small decimal which we have here, as also in (b) the *tithi-suddhi*, under the *palas*, may be disregarded in the following steps of the process

In (b) the *tithi-suddhi*, we obtain *tithis* 5, *gh.* 6, *p.* 47.4. From this we learn that, when the *Mēsha-Samkrānti* of the given year, Śāka-Samvat 406 expired, occurred, 5 mean *tithis* of the month Chaitra were completed, and also 6 *ghaṭis* and 47 *palas* of the 6th *tithi* had elapsed. The number of completed *tithis*, here 5, is technically called the *tithi-dhruva* or 'constant of the *tithi*;' because, when it has been determined for any given year, it remains uniform or constant in working out any example in that same year. And the remainder, here *gh.* 6, *p.* 47, is called the *bhukta-tithi* or 'elapsed portion of the (current) *tithi*.'

Subtracting the *bhukta-tithi*, *gh.* 6, *p.* 47, from 1 *tithi* or 60 *ghaṭis*, the remainder, *gh.* 53, *p.* 13, gives the portion of the 6th *tithi* that was still to run. This is technically called the *bhōgya-tithi*, *lit.* '(that portion of) the *tithi* which is still to be enjoyed.'

In (c), the *tithi-madhyama-kēndra*, we obtain *tithis* 21, *gh.* 25, *p.* 22. This gives us the moon's *kēndra*, reduced to *tithis*, at the time of the *Mēsha-Samkrānti* of the given year, Śāka-Samvat 406 expired.

To this, the *bhōgya-tithi*, viz. *gh.* 53, *p.* 13, is to be added. And the result, *tithis* 22, *gh.* 18, *p.* 35, is the *kēndra* at the end of the 6th *tithi* of Chaitra. This is called the *tithi-spaṣṭa-kēndra* or 'apparent *kēndra* of the *tithi*.'

Next, by subtracting from the *bhōgya-tithi*, viz. *gh.* 53, *p.* 13, as many *palas*, 53, as there are *ghaṭis* in it,¹ we convert it into a mean solar day, with the result of *gh.* 52, *p.* 20.

¹ i.e. by subtracting the sixtieth part. This proportion is taken for the sake of easy calculation. Properly speaking, to convert a *tithi* into a solar day, the sixty-fourth part should be subtracted; because one mean *tithi* is equal to 984353 of a solar day, i.e., as nearly as possible, sixty-three sixty-fourths of a solar day. The difference, however, does not introduce any material error.

Add this *gh.* 52, *p.* 20, to the *ghatis* and *palas* only of (a) the *abdāpa*. The result, *vāra* 1, *gh.* 5, *p.* 48, shews that the 6th mean *tithi* of Chaitra ended with *gh* 5, *p.* 48, after sunrise on the following day, Monday, after the day of the *Mēsha-Samkrānti*, Sunday. This quantity, *vāra* 1, *gh.* 5, *p.* 48, is called the **tithi-bhōga**, *lit.* 'the enjoyment or duration of the *tithi*;' and it is the end of the *tithi-dhruva*, increased by one *tithi*. It is, of course, a mean *tithi*. And it shews that *days* 1, *gh.* 5, *p.* 48, had elapsed, from sunrise on the day of the *Mēsha-Samkrānti*, up to the end of Chaitra *śukla* 6 as a mean *tithi*.

We have now to bring into consideration the **number of tithis elapsed** up to the commencement of the given *tithi*. And, in doing this, we must of course take account of any intercalary month that there may be, preceding the given *tithi*, in the given year.

In our example, however, the result in (b) the *tithi-suddhi*, is less than nineteen *tithis*. And a reference to Table VI. *p.* 22, — which would enable us to determine the intercalary month approximately, if there were one, — shews us that there was, therefore, no intercalary month at all in the given year, Śaka-Samvat 406 expired. The explanation of this, is, that when the *tithi-suddhi* is less than nineteen, it shews that the *samkrānti* in Chaitra occurred within the first nineteen *tithis* of that month. And, as, generally, the solar months are longer than the lunar months, the *samkrāntis* of the sun. *i.e.* his passage from one sign of the zodiac into the next, occur continuously later in each successive lunar month. But, when the *samkrānti* in Chaitra falls within the first nineteen *tithis*, no *samkrānti*, up to the end of the year, can go beyond the thirtieth *tithi* of any lunar month; and, therefore, no month will be intercalary.

Consequently, from the beginning of Chaitra, up to the commencement of the given *tithi*, Āshāḍha *śukla* 12, there had elapsed only the usual number of one hundred and one *tithis*; *viz.* in the bright fortnight of Chaitra, 15, in Vaiśākha, 30; in Jyēshtha, 30; and in Āshāḍha, 15 in the dark fortnight, and 11 in the bright.¹ From this number of *tithis*, 101, we subtract the *tithi-dhruva*, 5. And the remainder, 96, is the number of *tithis* elapsed from the end of Chaitra *śukla* 5 up to the end of Āshāḍha *śukla* 11. But the *tithi-bhōga*, which we have already arrived at, is the end of Chaitra *śukla* 6; and the same number of *tithis*, 96, expire from the end of Chaitra *śukla* 6 up to the end of Āshāḍha *śukla* 12. Therefore, adding to the *tithi-bhōga* the solar equivalent, now to be introduced, the result will bring us to the end of the given *tithi*, Āshāḍha *śukla* 12.

Turning to Table III. *p.* 14, we find that the **equivalent, in mean solar days**, of 96 *tithis*, is *days* 94, *gh.* 17, *p.* 36. And, adding this to the *tithi-bhōga*, the result, *days* 95, *gn.* 23, *p.* 24, gives the interval that had elapsed, from sunrise on the day of the *Mēsha-Samkrānti* up to the end of Āshāḍha *śukla* 12 as a mean *tithi*.

¹ We are dealing with a northern date; and that is why the *tithis* are counted in this way. If we were dealing with a southern date, the enumeration would be, in Chaitra, 30, in Vaiśākha, 30; in Jyēshtha, 30; and in the bright fortnight of Āshāḍha, 11. The total is the same, 101, since a bright fortnight is concerned.

Now, however, we have to determine the **spashta-tithi**, or apparent *tithi*. For this purpose, we require the *parākhyā*-correction, which is to be ascertained through the *tithi-kēndra*.

Turning again to Table III. p. 14, we find that the variation in the *tithi-kēndra* for 96 *tithis* is *tithis* 12, *gh.* 1, *p.* 20. Enter this in (c), below *tithis* 22, *gh.* 18, *p.* 35, which we have already arrived at as the *tithi-kēndra* at the end of Chaitra śukla 6. Add the two quantities together; and the result, — excluding 28 *tithis*, as before, — is *tithis* 6, *gh.* 19, *p.* 55; which is the *tithi-spashta-kēndra* at the end of the given *tithi*, Āshādha śukla 12.

With this argument, we turn to Table IV. p. 20, for the *parākhyā*-correction. In this Table, the correction is given for *tithis* and *ghatīs*, at intervals of ten *ghatīs*. Thus, for the *tithi-spashta-kēndra*, *tithis* 6, *gh.* 10, the *parākhyā* is *gh.* 24, *p.* 10; and for *tithis* 6, *gh.* 20, it is *gh.* 24, *p.* 19. The difference, 9 *palas*, is shewn in the last column of the Table, and would serve to calculate the exact *parākhyā* for the *tithi-spashta-kēndra*. But here it is sufficiently close for our purposes to take the *parākhyā* as *gh.* 24, *p.* 19.

Under (a) the *abdapa*, enter this *parākhyā* below the sum of the *tithi-bhōga* and the solar equivalent of 96 *tithis*, and, — as is indicated by the sign plus at the top of col. 1 in Table IV., — add it to that sum.

The result, *vāras* 95, *gh.* 47, *p.* 43, gives the number of days, and parts of a day, that had elapsed, from sunrise on the day of the *Mēsha-Samkrānti*, up to the end of the apparent Āshādha śukla 12. To the days, 95, add 1, the week-day of the *Mēsha-Samkrānti*. Divide the sum, 96, by 7, and the result is 13 weeks, and 5 days over; which shews that the current week-day of Āshādha śukla 12 was the fifth day in the week; that is **Thursday**. The remaining quantities, *gh.* 47, *p.* 43, shew the time after sunrise, on that Thursday, on which the given *tithi*, Āshādha śukla 12, ended.

The Tables in Prof. K. L. Chhatre's book, however, are adapted to the **meridian of Bombay**. The *ghatīs* and *palas*, therefore, of a *tithi* worked out by the method exhibited above, are for Bombay; and are to be reckoned from mean sunrise at Bombay. When the *tithi* is required for any other particular place, the difference of longitude in time (one degree = ten *palas*) is to be added or subtracted, according as the place is east or west of Bombay. In the present instance, as I learned after first working it out, the above Śaka date was selected in consequence of its being the equivalent of the date, in Gupta-Samvat 165, recorded in the pillar inscription of Budhagupta at Êraṇ in the Central Provinces. We have therefore now to determine the *tithi* for Êraṇ itself. The longitude of Bombay is 72° 51'; and that of Êraṇ is 78° 15'; both east of Greenwich. Êraṇ, therefore is 5 degrees, 24 minutes, east from Bombay. Adding (5° 24' × 10 =) 54 *palas* to 47 *ghatīs* and 43 *palas*, which we have obtained above for Bombay, the *tithi* at Êraṇ is *gh.* 48, *D.* 37, reckoned from mean sunrise on the same day, **Thursday**.

The above result is sufficient for all practical purposes. But it is further to be noted that the *tithis* in our *Pañchāṅgs* are intended to be given from apparent sunrise. In practice, however, so much minuteness is not always and everywhere attempted; at least, in the present day, in the Dekkan. For this reason, it seems, Prof. K. L. Chhatre has not noticed this point in his method exhibited above. But I will now give the *tithi* in question from apparent sunrise at Êraṇ. Without going through the process, which is rather too complicated to be given in the present paper, I will state only the result, that the apparent sunrise at Êraṇ, on the day in question, took place *gh.* 1, *p.* 56, before the mean sunrise; the latitude of Êraṇ used in the process, being $24^{\circ} 5'$. Adding, therefore, *gh.* 1, *p.* 56, to the above result from mean sunrise, we get *gh.* 50, *p.* 33, reckoned from apparent sunrise, as the time at which the given *tithi*, Āshāḍha śukla 12, ended at Êraṇ on the Thursday.

Before dismissing this part of the subject, I would point out that the calculation of a *tithi*, by the above method, is not of necessity absolutely accurate, according to the present absolutely accurate European Tables of the sun and the moon. Absolute accuracy, in this sense, could be ensured only by working from the actual places or longitudes of the sun and the moon, to be determined in strict accordance with the method prescribed for that purpose. The *tithi* obtained by the method exhibited above, will differ, sometimes by as much as ten *ghaṭis*, from that which would be obtained from the apparent places of the sun and the moon, actually calculated from Prof. K. L. Chhatre's Tables for the sun and the moon. The difference, however, at full-moon and new-moon will be very small, one *ghaṭi* at the greatest; and it reaches its maximum on the eighth *tithi* of the bright and of the dark fortnight. But, in respect of this second possible method of Prof. K. L. Chhatre, it must be stated that we have nothing to do with it in dealing with Hindu *tithis*; for the reason that, with the exception of the *phala-samskāra*, the corrections introduced by him in finding the apparent longitude of the moon, were not taken into account by ancient Hindu astronomers.

And, on the other hand, the method exhibited above being in close agreement with Hindu works, it may be claimed that the *tithi* obtained by it will differ but very little from the *tithi* obtained by the method prescribed in the *Sūrya-Siddhānta* and other Hindu works. The difference¹ will amount to five or six *ghaṭis* at the utmost; and that in but very few cases.

In order, however, that no room may be left for doubt, I have also calculated the *tithi* in the present example actually by the *Āryabhaṭīya* or *Ārya-Siddhānta* of the first Āryabhaṭa, the *Brahma-Siddhānta* of Brahmagupta, the *Sūrya-Siddhānta*, the *Siddhānta-*

¹ See page 149 above, note 1.

Sīrōmani, and the *Ārya-Siddhānta* of the second Āryabhata.¹ I calculated it first for Ujjain, i.e. for the Hindu meridian, reckoning from the mean sunrise there; and then turned it into the *tithi* for Ēran. The longitude of Ujjain is $75^{\circ} 43'$ east of Greenwich. I have also calculated the *ghatis* and *palas* from the apparent sunrise at Ēran, and all the results are given in Table VI., on the upper part of page 157 below. From them we see that **the tithi fell on a Thursday,**² according to all the authorities.

¹ i.e. the work that is usually called the *Laghu-Ārya-Siddhānta*.—There are two distinct and separate works, each bearing the name of Āryabhata as its author. The one published by Dr Kern contains one hundred and eighteen verses in the Āryā metre, and is called *Āryabhatīya* in general and by the author himself; but it may, and justly so, be called *Ārya-Siddhānta*, and it is called so by many Hindu astronomers. The date of this work is Saka-Samvat 421 expired (A. D. 499-500). The other, which, I believe, has not yet been printed, contains about six hundred and twenty-five verses in the Āryā metre, divided into eighteen chapters. The date of it is not given. But, from internal evidence, I find that it is later than the *Brahma-Siddhānta* of Brahmagupta (Śaka-Samvat 550 expired, A. D. 628-29); and there is a reference to it in the *Siddhānta-Sīrōmani* (Śaka-Samvat 1072 expired; A. D. 1150-51). Its date, therefore, lies somewhere between these two limits. In the first verse of it, the author calls himself Āryabhata; and his work, a Siddhānta, without *Laghu* or any other epithet. In a manuscript copy of it, I find that it is named *Mahā Siddhānta* at the end of some chapters, and *Laghu-Ārya-Siddhānta* at the end of others. For the sake of distinction and convenience, it is better to call the authors of these two works, the first and the second Āryabhata. The numbers of the revolutions of the planets &c. given, as belonging to the *Ārya-Siddhānta*, in the Rev. E. Burgess' Translation of the *Sūrya-Siddhānta* and in some instances those given by Prinsep (*Prinsep's Essays*, Vol. II. Useful Tables, v. 153) as belonging to the same authority, belong really to the second Āryabhata. Probably, when these gentlemen wrote, they had not themselves seen the Siddhānta of the first Āryabhata. Gen. Sir A. Cunningham, also, was not, it seems, aware of the two different Āryabhatas, when he wrote (*Indian Eras*, p. 88) "according to Warren the number of days assigned by Āryabhata to a Mahāyuga of 4,320,000 years is 1,577,917,500 in the south of India and 42 more in the MSS. preserved in Bengal". Of these two numbers, the former belongs to the first, and the latter to the second, Āryabhata.

² i.e. on a Hindu Thursday.—It must be borne in mind that the Hindu week-day is reckoned, with the solar day and night, from sunrise to sunrise, as stated at page 146 f. above, but the English week-day, and the civil date coupled with it, from midnight to midnight. In comparing Hindu and English dates, the only course is to take mean sunrise and mean midnight (6 0 A.M. and 12 0 P.M. respectively), and to give, as the English equivalent, that week-day, with its civil date, which is actually running during these eighteen hours, when of course the same week-day is running in India, i.e. the week-day which is identical for the greater part by both the English and the Hindu reckonings. And, if the difference in mean time between Greenwich and Ujjain, viz. 5 hours, 2 minutes, 52 seconds (using the same longitude for Ujjain, $75^{\circ} 43'$, taken from Keith Johnston's Atlas, that is used by Mr. Sh. B. Dikshī for his calculations in this paper and for the *Sāyana-Pāñchāṅg*) be taken into consideration, of course the week-days of the two places are absolutely identical, except for the space of 57 minutes, 8 seconds, or 2 *ghatis*, 22·8 *palas*, at the end of the Hindu week-day, during that time, while at Ujjain a Hindu Thursday for instance, is still running, at Greenwich the week-day will be Friday. Owing to this, there may sometimes be a nominal discrepancy in the resulting English week-day for a given *tithi*, but the instances will be few and far between, as very few *tithis* will be found to end so late after sunrise; and the discrepancy will be confined mostly to such occurrences as the heliacal rising of Jupiter (see, for instance, the double dates which it has been necessary to quote at page 104 ff. above). In the present case, not one of the ending-points of the given *tithi* falls within the debatable period; either for Ujjain, or for Ēran, which is appreciably to the east of Ujjain.—J. F. F.]

TABLE VI.

The Times, after Sunrise, of the ending of a given Tithi.

Śaka-Saṃvat 406 expired = A.D. 484-85 current.

Āshāḍha (June-July); the bright fortnight; the 12th tithi; Suraguruvāra (Thursday).

The Time, after Sunrise, at which the Tithi ended.	By K. L. Chhatre's method exhibited above.	By the Arya-Siddhānta of the first Āryabhaṭa.	By the Brahma-Siddhānta of Brahma-gupta.	By the Śūrya-Siddhānta.	By the Siddhānta-Sūramani.	By the Arya-Siddhānta of the second Āryabhaṭa.
	gh. p.	gh. p.	gh. p.	gh. p.	gh. p.	gh. p.
Reckoned from mean sunrise at Bombay ..	47 43	49 19	49 46	50 42	52 52	54 24
„ „ „ „ „ Ujjain ...	48 12	49 48	50 15	51 11	53 21	54 51
„ „ „ „ „ Eraṇ ...	48 37	50 13	50 40	51 36	53 46	55 18
„ „ „ „ „ apparent sunrise at Eraṇ ..	50 33	52 9	52 36	53 32	55 42	57 14

TABLE VII.

Calculation of the English Date of a given Tithi.

Śaka-Saṃvat 400 expired = A.D. 484-85 current.

Āshāḍha (June-July); the bright fortnight; the 12th tithi; Suraguruvāra (Thursday).

	lays	gh.	p.
Date of the <i>Māsha-Samkrānti</i> in March of A.D. 0 (p. 30)	13	59	10
Add variation for 400 years A.D. (p. 30)	3	30	9
„ „ 84 years A.D. (p. 27)	0	44	7
Date of the <i>Māsha-Samkrānti</i> in March of A.D. 484	18	13	26
Add days elapsed from the <i>Māsha-Samkrānti</i> up to the given <i>tithi</i> , from col. (a) of the previous process	95		
			113
Deduct number of days in completed months from the 1st March:—			
March	31		
April	30		
May	31		
			02
Remainder is the current day of the next month, and the current day of the given <i>tithi</i> ..	21		
			Result; 21st June, A.D. 484

If, by the calculations detailed above, we find that a certain *tithi* ended nearly at the end of a Hindu day,—for instance, fifty-seven *ghatīs* after sunrise on a Sunday; *i.e.* three *ghatīs* before sunrise on Monday,—there may be the possibility that it really ended shortly after sunrise on the following day, Monday. And, on the other hand, if our results shew that a certain *tithi* ended shortly after the commencement of a Hindu day,—for instance, three *ghatīs* after sunrise on a Sunday,—there may be the possibility that it really ended shortly before the termination of the preceding day, Saturday.

In dealing with a particular record that, on a certain week-day, there was a certain *tithi*, we can only be sure of absolute accuracy in our results, if we can ascertain, so as to apply, the actual authority and method used by the author of the calendar which the drafter of that record consulted in preparing his statement. The method exhibited above, however, may be safely relied on for all practical purposes.

To find the English Date for a given Tithi.

The materials for this process are to be found in Prof. K. L. Chhatre's book, in Table IX. on page 27, and in Table XI. on page 30.

The English date answering to the given Hindu date in our present example, has obviously to be worked out according to the Julian Calendar, or Old Style; being long anterior to A.D. 1752, when the Gregorian Calendar, or New Style, was introduced.

From the heading of Table XI. p. 30, we find that, in A.D. 0, the Hindu *Mēsha-Samkrānti* occurred on the 13th March, and *gh.* 59, *p.* 10, after sunrise (civil time). Enter these quantities (see Table VII. on the lower part of page 157 above). And below them, enter the *bhēda* or variation for the component parts of the given current year A.D., in this instance A.D. 484-(85), which is always obtained by adding A.D. 78-(79) to the given expired Śaka year; *viz.* for 400, *days* 3, *gh.* 30, *p.* 9, from Table XI.; and for 84, *days* 0, *gh.* 44, *p.* 7, from Table IX.

Add these quantities together. The result, for, A.D. 484, is *days* 18, *gh.* 13, *p.* 26. And this shews that, in A.D. 484, the Hindu *Mēshu-Samkrānti* occurred on the 18th March, and 13 *ghatīs* and 26 *palas*¹ after sunrise.

Add 95, which we have already ascertained, in the previous process, under (a) the *abāpā*, to be the number of days that had elapsed from sunrise on the day of the *Mēsha-Samkrānti*, up to sunrise on the day on which the given *tithi* ended. The sum, 113, gives the number of days up to, and inclusive of, the given *tithi*, from, and inclusive of, the 1st March.

¹The *ghatīs* and *palas* ought to agree with the *ghatīs* and *palas* of the *abāpā* of Śaka-Samvat 406 expired, in col. (a) of the previous process. Here there is a difference of 24 *palas*; which shews that there is a small mistake somewhere in the Tables.

From this sum subtract the number of days in as many entire months as were completed within the total of 113 days; *viz.* in the present instance, in March, 31 days; in April, 30; and in May, 31; total, 92.

The remainder, in this instance 21, gives the current day of the next month, corresponding to the given *tithi*. The result, therefore, in the present instance, is the **21st June, A.D. 484**, Old Style. The identification of this date with the week-day previously obtained for the given *tithi*, may be verified by any of the ordinary means available. For instance, from General Sir A. Cunningham's *Indian Eras*, Table II. p. 98, we find that the 1st January, A.D. 484, Old Style, was a Sunday. And then, turning, as the given year was a Leap-year, to the right-hand side of his Table I. p. 97, we find that the 21st June of the same year was a **Thursday**, as required.

(of time), then the so-called setting or rising of Jupiter, *i.e.* his heliacal setting or rising, takes place.

To such a system, as is taught in this verse of Varāhamihira, and by no less than eleven other authorities, as will be seen further on, of determining the commencement of a *samvatsara* of the Twelve-Year Cycle, and of naming it, from Jupiter's heliacal-rising, I would give the name of **the heliacal-rising system**, in order to distinguish it from the other system in which the duration and name of a *samvatsara* of the Twelve-Year Cycle are determined from the particular sign of the zodiac in which Jupiter stands with reference to his mean longitude, and which latter system, to be mentioned more fully, further on, I would name **the mean-sign system**.

Now, the years of the Sixty-Year Cycle of Jupiter and of the Twelve-Year Cycle according to the mean-sign system, are determined by his mean longitude,¹ which sometimes differs from his apparent longitude by as much as fifteen degrees. But, as the disappearance or reappearance of Jupiter is no imaginary thing, it is evident that it can be calculated, and is to be calculated, only according to Jupiter's actual place, that is, his apparent longitude (or right ascension), and not from his mean longitude. And, consequently, the beginning of each *samvatsara* of the Twelve-Year Cycle according to the heliacal-rising system, depends on **Jupiter's apparent longitude** at the time of his heliacal rising.

One revolution of Jupiter, in the zodiac, is completed in about twelve years, and, in twelve years, there are twelve revolutions of the sun (that is, of the earth). So that, in this period of about twelve years, there are only eleven conjunctions of the sun and Jupiter. Therefore, in twelve years there are only eleven heliacal risings of Jupiter.² The interval between two risings is generally 299 days. And thus, in each cycle of the heliacal-rising system, **there are only eleven samvatsaras in twelve years**; the duration of each being about 400 days, and one *samvatsara*, determined by the circumstances of the particular cycle, being altogether omitted.

The **names of the lunar months** are used as the names of the *samvatsaras* of the Twelve-Year Cycle of Jupiter. And the names of these months are given to the *samvatsaras*, in accordance with the particular *nakshatra* in which Jupiter's heliacal rising takes place. Of the twenty-seven *nakshatras*, two are assigned to each of nine of the twelve months; and three to each of the remaining three months. The rule for this is given in the *Bṛihat-Samhitā*, viii. 2, — varshāni Kārttik-ādīny-āgnēyād bha-dvay-ānuyōgīni | kramaśas tri-bham tu pañchamam upāntyam antyam cha yad varsham ||,—“the years Kārttika and others (*that follow*) combine two *nakshatras*, from (*the nakshatra*) belonging

¹ The mean longitude of a heavenly body is the longitude of an imaginary body, of the same name, conceived to move uniformly with the mean motion of the real body.

² In his note on the *Sūrya-Siddhānta*, xiv. 17 (see the Rev. E. Burgess' Translation, p. 271), Prof. Whitney says that Jupiter “would set and rise heliacally twelve times in each revolution, and each time about a month later than before.” But this is evidently a mistake.

APPENDIX III.

The Twelve-Year Cycle of Jupiter.

BY SHANKAR BALKRISHNA DIKSHIT; BOMBAY EDUCATIONAL DEPARTMENT.

The names of the *samvatsaras*, or years, of the **Twelve-Year Cycle of Jupiter**, are determined in accordance with the following rule in the *Bṛihat-Samhitā* of Varāhamihira, *adhyāya* viii. verse 1, — *nakshatrēna sah-ōdayam upagachchhati yēna dēvapati-mantri¹ I tat-samjñam vaktavyam varsham māsa-kramēn-aiva H.* — 'with whatever *nakshatra* (Jupiter) the counsellor of (Indra) the lord of the gods attains (*his*) rising, the year is to be spoken of (*as*) having the appellation of that (*nakshatra*), in accordance with the order of the months.'

Here, by the word *udaya*, 'rising,' we have to understand, not the daily rising of Jupiter, but his **heliacal rising**. Jupiter becomes invisible for some days before and after his conjunction with the sun. The sun's daily motion is faster than that of Jupiter. So, when the sun in his course comes near Jupiter, the latter becomes invisible, on the west side of the horizon, and he is then said to set. He remains from twenty-five to thirty-one days in this state of invisibility. And, when he is left behind by the sun, he again becomes visible, in the east, and then he is said to rise. Generally, in India, when the interval between the daily settings or risings of the sun and Jupiter amounts to forty-four minutes

¹ The reading that I give, is from an old manuscript in my possession. But the commentator, Utpala, explains the verse with the reading—*nakshatrēna sah-ōdayam astam vā yēna yāti sura-mantri¹*,— 'with whatever *nakshatra* (Jupiter) the counsellor of the gods attains (his) rising or setting.' It is curious that the text, in my manuscript copy, stands as given above. The copyists, however far they might go wrong in ordinary transcribing, could not, unless intentionally, turn the letters *mastam vā yēna yāti sura*, if they were original at all, into *mupagachchhati yēna dēvapati*. And Utpala himself gives the note—*Rishiputr-ādibhish udaya-nakshatra-māsa-samjñā-kramēna varsham jñātavyam ity-uktam*,—"it is said by Rishiputra and others, that the year is to be known according to the order of the name of the month of the *nakshatra* of the rising (of Jupiter)." Also, all the other authorities, which I find giving the rule of naming the years of the cycle according to the risings of Jupiter, make each year take its name from only the rising of the planet, not from its setting.—[The reading in the text above, is the one adopted by Kern, in his edition of the *Bṛihat-Samhitā*, p. 47. His translation (*Jour. R. As Soc* N. S. Vol. V. p. 45) is—"each year (during which Jupiter completes a twelfth part of his revolution) has to bear the name of the lunar mansion in which he rises; the years follow each other in the same order as the lunar months." Both in his *Various Readings*, p. 6, and in the note to his translation, he notices the reading *sah-ōdayam astam vā yēna yāti sura-mantri¹*. But he points out that "the comparison of the MSS leaves little doubt that this reading is a correction, suggested by the remark of Utpala, that, in case the planet should set in one and rise in another *nakshatra*, only that name must be taken which agrees with the order of the month—J. F. F.]

TABLE VIII.

Regulation of the Names of the Samvatsaras from the Nakshatras.

Names and Grouping of the Nakshatras.	Names of the Months to be allotted to the Samvatsaras
Kṛittikā; Rōhiṇī	Kārttika
Mṛiga; Ārdrā	Margaśr̥ṣha
Punarvasu; Pushya	Pausha
Āślāhā; Maghā	Māgha
Pūrvā-Phalgunī; Uttarā-Phalgunī; Hasta	Phālguna
Chitrā; Svāti	Chaitra
Viśākhā; Anurādhā	Vaiśākha
Jyēṣṭhā; Mūla	Jyēṣṭha
Pūrvā-Aśādhā; Uttarā-Aśādhā; (Abhijit)	Āśādhā
(Abhijit); Śrāvāna; Dhanishṭhā	Śrāvāna
Śatatārakā; Pūrvā-Bhādrapadā; Uttarā-Bhādrapadā	Bhādrapada
Rēvatī; Aśvini, Bharanī	Āsvina (Āsvayuja)

to Agni (*as the starting-point*), in regular succession; but that year which is the fifth, (*or*) the last but one, or the last, has three *nakshatras*."² And, from this and similar authorities, we obtain the results exhibited in Table VIII. above, for the naming of the *samvatsaras* from the *nakshatras*.³

Now, the twenty-seventh part of the ecliptic circle is called a *nakshatra*. And 360 degrees, divided by 27, gives 13 degrees, 20 minutes (of arc). Therefore, according to such a division of the circle into equal parts, there is this much distance from the beginning of one *nakshatra* to the beginning of the next following. And, when the longitude of a heavenly body exceeds *nil*, but does not exceed 13 degrees, 20 minutes, it is said to be in Aśvini; and so on. The longitudes of the ending-points of all the *nakshatras*, on the **system of equal spaces**, are given in the last column but two

¹ *i.e.* from Kṛittikā. Agni is the regent of the *nakshatra* Kṛittikā, which was, at one time, the first in order of the lunar mansions.

² [Kern's text is the same. His translation is—"the years Kārttika and following comprehend two lunar mansions beginning with Kṛittikā, and so on, in regular succession, except the fifth, eleventh, and twelfth years, to each of which appertain three asterisms."—J. F. F.]

³ I should state, however, that there is a little difference of opinion on this point. Utpala, the commentator on the *Bṛihat-Samhitā*, has discussed it at length, and arrived at the conclusion which is exhibited in Table VIII. In the ancient and modern works that I have referred to, I find ten authorities,—and such ancient names as those of Vṛiddha-Garga and Kaśyapa among them,—giving the rule regulating the names of the *samvatsaras* of the Twelve-Year Cycle by the *nakshatras*. Out of these ten, Garga (not Vṛiddha-Garga), and Parāśara, as quoted by Utpala,—but these two only,—hold that the tenth and eleventh months, Śrāvāna and Bhādrapada, have three *nakshatras* each, *viz.* Śrāvāna, Dhanishṭhā, and Śatatārakā, are assigned to Śrāvāna; and Pūrvā-Bhādrapadā, Uttarā-Bhādrapadā, and Rēvatī, to Bhādrapada; and, consequently, Āsvina has only Āsvini and Bharanī.

in Table IX. on page 165 below. And generally, whenever we meet with a *nakshatra* spoken of with reference to the place of a heavenly body, that *nakshatra* is to be taken in the above sense.

There is, however, a **second method of determining the nakshatras** with reference to the places of heavenly bodies. And, though it has now gone almost out of use, yet it was undoubtedly prevalent to a great extent in early times, and was much made use of, on important religious occasions at least. The chief feature of it is, that the space on the ecliptic allotted to each *nakshatra* is not equal. Fifteen *nakshatras* are held to be of an equal average space; but six, of one and a half times the average; and six others, of only half the average.

One system of unequal spaces, according to this method, is referred to in some of the verses from the *Garga-Samhitā*, which are quoted by Utpala in his commentary on the *Bṛihat-Samhitā*. The commentary, with the passages quoted in it, runs — tathā cha Gargaḥ | Uttarās cha tath-Ādityam Viśākhā, ch-aiva Rōhiṇī | ētāni śhaṭ adhyardha-bhōgāni || Paushn-Āsvi-Kṛittikā-Sōma-Tishya-Pitrya-Bhag-āhvayāḥ Sāvitra-Chitr-Ānūrādhā Mūlam Tōyam cha Vaishṇavam Dhanishth-Ājāikapāch ch-aiva sama-vargah prakṛitah | ētāni pañchadaśa sama-bhōgāni || Yāmy-Aindra-Raudra-Vāyavya-Sārpa-Vāruṇa-samjñitāḥ | ētāni śhat ardha-bhōgāni ||,—“ and so Garga (*says*), ‘the Uttarās (*i.e.* Uttarā-Phalgunī, Uttarā-Ashādhā, and Uttarā-Bhādrapadā), and Āditya (Punarvasu), Viśākhā, and also Rōhiṇī;’ these six (*are*) of one-and-a-half times (*the average*) longitude. ‘(*The nakshatras*) of which the names are Paushṇa (Rēvatī), Āsvi (Āsvini), Kṛittikā, Sōma (Mṛiga), Tishya (Pushya), Pitrya (Maghā), and Bhaga (Pūrvā-Phalgunī), (*and also*) Sāvitra (Hasta), Chitrā, Ānūrādhā, Mūla, Tōya (Pūrvā-Ashādhā), and Vaishṇava (Śravaṇa), (*and*) Dhanishthā, and also Ājāikapād (Pūrvā-Bhādrapadā); (*this class of nakshatras*) is called the equal class;’ these fifteen (*are*) of equal (*average*) longitude. ‘(*The nakshatras*) which have the appellations of Yāmya (Bharanī), Aindra (Jyēsthā), Raudra (Ārdṛā), Vāyavya (Svāti), Sārpa (Āślēshā), and Vāruṇa (Śatātṛakā);’ these six (*are*) of half (*the average*) longitude.” In this system, which I would name **the Garga system of unequal spaces**, the number of the *nakshatras* is twenty-seven, as usual. The average space of a *nakshatra*, therefore, is 13 degrees, 20 minutes; a one-and-a-half space is 20 degrees; and a half space is 6 degrees, 40 minutes. The longitudes of the ending-points of all the *nakshatras*, according to this system, are given in the last column but one in Table IX. on page 165 below; and the entries of $\frac{1}{2}$ and $1\frac{1}{2}$ in the sub-column, mark the spaces which differ from the average space. Nārada and Vasishṭha give this system in the same way as Garga. It seems to have originated in the fact that the distances between the chief stars, called *yōga-tārā*, of the different *nakshatras*, are not equal. The distance is naturally expected to be 13 degrees, 20 minutes. But, in some cases it is less than 7 degrees; while in others it is more than 20 degrees. However, be the reason of the system what it may, there is no doubt that it was extensively in use in ancient times. And, that either it,

TABLE IX.
Longitudes of the Ending-points of the Nakshatras.

Order of the Nakshatras	System of Equal Spaces.		Systems of Unequal Spaces.							
			Garga System			Brahma-Siddhanta System.				
	deg.	min.	seca	...	deg.	min.	sec.	deg.	min.	sec.
Aśvini	13°	20'	0"	...	13°	20'	0"	13°	10'	35
Bharani	26	40	0	½	20	0	0	19	45	52½
Kṛittikā	40	0	0	.	33	20	0	32	56	27½
Rōhiṇī	53	20	0	1½	53	20	0	52	42	20
Mṛiga	66	40	0		66	40	0	65	52	55
Ārdrā	80	0	0	½	73	20	0	72	28	12½
Punarvasu	93	20	0	1½	93	20	0	92	14	5
Pushya	106	40	0	..	106	40	0	105	24	40
Āślēshā	120	0	0	½	113	20	0	111	59	57½
Maghā	133	20	0	.	126	40	0	125	10	32½
Pūrvā-Phalgunī	140	40	0	...	140	0	0	138	21	7½
Uttarā-Phalgunī	160	0	0	1½	160	0	0	158	7	0
Hastā	173	20	0	...	173	20	0	171	17	35
Chitrā	186	40	0	...	186	40	0	184	28	10
Svāti	200	0	0	½	193	20	0	191	3	27½
Viśākhā	213	20	0	1½	213	20	0	210	49	20
Anurādhā	226	40	0	...	226	40	0	223	59	55
Jyēshthā	240	0	0	½	233	20	0	230	35	12½
Mūla	253	20	0	...	246	40	0	243	45	47½
Pūrvā-Ashādhā	266	40	0	...	260	0	0	256	56	22½
Uttarā-Ashādhā	280	0	0	1½	280	0	0	276	42	15
(Abhijit)			(Balance)			280	56	30
Śravaṇa	293	20	0	...	293	20	0	294	7	5
Dhanishthā	306	40	0	...	306	40	0	307	17	40
Śatatārakā	320	0	0	½	313	20	0	313	52	57½
Pūrvā-Bhādrapadā	333	20	0	..	326	40	0	327	3	32½
Uttarā-Bhādrapadā	346	40	0	1½	346	40	0	346	49	25
Révatī	360	0	0	...	360	0	0	360	0	0

or the very similar system of the *Brahma-Siddhanta*, explained below, was still in use, at least on important occasions, up to A.D. 862, is proved by the Deōgadh inscription of Bhōjadēva of Kanauj; the results for which, calculated by me, have been exhibited by Mr. Fleet at page 107 above, note 1.

Another system of unequal spaces is given in the *Brahma-Siddhanta*,¹ chapter xiv. verses 45 to 53. In its leading feature, it is the same with Garga's system; but it differs a little from Garga's, in introducing Abhijit, in addition to the twenty-seven *nakshatras*. The moon's daily mean motion,—13 degrees, 10 minutes, 35 seconds,—is taken as the average space of a *nakshatra*. And, as the total of the spaces thus allotted to the

¹ By this name, is to be understood, throughout this paper, the *Siddhanta* by Brahmagupta

usual twenty-seven *nakshatras*, on a similar arrangement of unequal spaces, amounts to only 355 degrees, 45 minutes, 45 seconds, the remainder,—4 degrees, 14 minutes, 15 seconds,—is allotted to Abhijit, as an additional *nakshatra*, placed between Uttarā-Ashādhā and Śravaṇa. This system, which I would name the **Brahma-Siddhānta system of unequal spaces**, is best explained by Bhāskarāchārya,¹ in his *Siddhānta-Śirōmaṇi*, Part iii., chapter 2 (Grahagaṇitaspashṭādhikāra), verses 71 to 74. His text, and his own commentary on it, are as follows, — sthūlaṁ kṛitaṁ bh-ānyanam yad ētaj jyōtirvidāṁ saṁvyavahāra-hētōh || 71 || Sūkshmaṁ pravakshyē-tha muni-praṇitaṁ vivāha-yātr-ādi-phala-prasiddhyai | adhyardha-bhōgāni shad atra taj-jñāh prōchur Viśākh-Āditibhadhrvāṇi || 72 || Shad ardhā-bhōgāni cha Bhōgi-Rudra-Vāta-Āntak-Īndra-ādhipa-Vāruṇāni | śēshāny-atah pañchadaś-aika-bhōgāny-uktō bha-bhōgah śāsi-madhyā-bhuktiḥ || 73 || Sarv-arksha-bhōg-ōnita-chakra-liptā Vaiśv-āgrataḥ syād Abhijid-bha-bhōgah | 74 || *Commentary.*— Iha yan nakshatr-ānyanam kṛitaṁ tat sthūlaṁ lōka-vyavahār-ārtha-mātraṁ kṛitaṁ || Atha Pulīsa-Vasishtha-Garg-ādibhir yad vivāha-yātr-ādau saṁyak-phala-siddhyartham kathitaṁ tat sūkshmaṁ idānīm pravakshyē || Tatra shad adhyardha-bhōgāni | Viśākhā Punarvasu Rōhini-Uttarā-trayam | atha shad ardhā-bhōgāni | Āślēsh-Ārdra Svāti Bharani Jyēsthā Śatabhishak | ēbhyaḥ śēshāni pañchadaś-aika-bhōgāni || Bhōga-pramānam tu śāsi-madhyā-bhuktiḥ 790 35 | adhyardha-bhōgah 1185 52½ | ardhā-bhōgah 395 17½ || Sarv-arksha-bhōgair ūnitānām chakra-kalānām yach chhēsham sō-Bhijid-bhōgah 254 15 || *Translation.*—" This bringing out of *nakshatras* (i.e. the method of finding *nakshatras*, with their *ghatis* and *palas*) which has been made (in the preceding verses), (is) rough, (and is only) for the practical purposes of astrologers. Now I will explain the accurate (method) taught by [Pulīsa, Vasishṭha, Garga, and other] sages, for the purpose of securing [good] results in the case of a marriage, a journey, &c On this point, those who are versed in that (branch of the science) say, that six (*nakshatras*) have (each) a space which is one-and-a-half (times of the average space) ; (viz.) Viśākhā, Aditubha (Punarvasu), and the *dhrūvas* (Rōhīni, Uttarā-Phalguni, Uttarā-Ashādhā, and Uttarā-Bhādrapadā). And six have a half space (each) ; (viz.) those the lords of which are Bhōgin, Rudra, Vāta, Antaka, and Indra, and Vāruṇa [Āślēshā, Ārdra, Svāti, Bharani, Jyēsthā, (and) Śatabhishaj (Śatatārakā)] The remaining fifteen (*nakshatras*) have one space (each). The (average) space of a *nakshatra* is declared to be the (daily) mean motion of the moon [790' 35" (= 13° 10' 35")]. [A one-and-a-half space (is) 1185' 52½" (= 19° 45' 52½")]. A half space (is) 395' 17½" (= 6° 35' 17½")]. The space of the *nakshatra* Abhijit, (which comes) next after Vaiśva (Uttarā-Ashādhā), is [the remainder, 254' 15" (= 4° 14' 15"), of] the minutes of the whole circle, diminished by the spaces of all the (other) *nakshatras*." The longitudes of the ending-points of all the *nakshatras* according to this system, are given in the last column of Table IX, on page 165 above. And, as before,

¹ The system explained by Bhāskarāchārya, now given, is just the same as that in the *Brahma-Siddhānta*. It seems unnecessary, therefore, to give the verses from the *Siddhānta* itself.

TABLE X.
Details of two Twelve-Year Cycles of Jupiter.

Saka-Samvat, expired.	English Date.	Longitude of Jupiter.	Nakshatra.	Month and Name of the Samvatsara.	
1780	Adhika-Jyeshtha sukla 10	7th June, 1858 . . .	41° 47'	Rohini	Karttika
1781	Ashadha sukla 14	13th July, 1859 . . .	77 2	Punarvasu	Pausha
1782	Śrāvana kṛishna 13	15th August, 1860 . . .	110 20	Aslēshā	Māgha
1783	Bhādrapada sukla 13	16th September, 1861 . . .	141 38	Uttarā-Phalgunī	Phālguna
1784	Āsina kṛishna 9	17th October, 1862 . . .	171 55	Chitrā	Chaitra
1785	Kārttika sukla 6	16th November, 1863 . . .	201 32	Viśākha	Vaiśākha
1786	Mārgaśrīsha kṛishna 3	16th December, 1864 . . .	232 3	Mūla	Jyeshtha
1787	Māgha sukla 2	18th January, 1866 . . .	263 48	Uttarā-Ashādhā	Ashādhā
1788	Māgha kṛishna 4	22nd February, 1867 . . .	298 0	Dhanishthā	Śrāvana
1790	Chaitra sukla 5	29th March, 1868 . . .	334 3	Uttarā-Bhādrapadā	Bhādrapada
1791	Adhika-Vaiśākha kṛishna 10	6th May, 1869 . . .	10 27	Āsini	Āsina
1792	Jyeshtha sukla 14	12th June, 1870 . . .	46 39	Rohini	Karttika
1793	Śrāvana sukla 1	18th July, 1871 . . .	81 47	Punarvasu	Pausha
1794	Śrāvana kṛishna 1	19th August, 1872 . . .	114 45	Maghā	Māgha
1795	Bhādrapada kṛishna 14	20th September, 1873 . . .	145 53	Uttarā-Phalgunī	Phālguna
1796	Āsina sukla 11	21st October, 1874 . . .	175 52	Chitrā	Chaitra
1797	Kārttika kṛishna 8	20th November, 1875 . . .	205 36	Viśākha	Vaiśākha
1798	Pausha sukla 1	16th December, 1876 . . .	235 21	Mūla	Jyeshtha
1799	Pausha sukla 15	15th January, 1878 . . .	267 22	Uttarā-Ashādhā	Ashādhā
1800	Phalgunā sukla 6	27th February, 1879 . . .	302 46	Dhanishthā	Śrāvana
1801	Phālguna kṛishna 10	4th April, 1880 . . .	339 0	Uttarā-Bhādrapadā	Bhādrapada
1803	Vaiśākha sukla 12	11th May, 1881 . . .	15 30	Bharanī	Āsina

the entries of $\frac{1}{2}$ and $1\frac{1}{2}$ in the previous sub-column, mark the spaces which differ from the average space.

Now, the additional nakshatra *Abhijit*, introduced in this system, is not taken into account among the *nakshatras* from which the names of the months are derived.¹ The question, therefore, occurs,—What name is to be given to the *samvatsara*, when Jupiter rises in *Abhijit*? It can be solved thus. *Abhijit* is considered to be composed of the last quarter of *Uttarā-Ashādhā*, and the first fifteenth part of *Śrāvana*. This is stated in the following verse of *Vasishtha*, as quoted in the commentary, called *Pīyūshadhārā*, on the *Muhūrta-Chintāmaṇi*;—*Abhijid-bha-bhōgam ētad Viśvōdēv-āntya-pādam akhilaṃ tat I ādya-chatasrō nādyō Haribhasya*,—“this (*is*) the longitude of *Abhijit*; the whole last quarter of *Viśvōdēva* (*Uttarā-Ashādhā*), (*and*) the first four *ghaṭis* (*i.e.* the fifteenth part) of *Haribha* (*Śrāvana*).” And other later authorities give the same rule. A quarter of a *nakshatra* is 3 degrees, 20 minutes, and a fifteenth part is 53 minutes, 20 seconds, and the sum of the two amounts to 4 degrees, 13 minutes, 20 seconds. In other words, *Abhijit* consists of nineteen parts; of which, the first fifteen come from, and properly belong to, *Uttarā-Ashādhā*; and the last four come from, and properly belong to, *Śrāvana*. And the name of the *samvatsara* is to be determined as *Ashādhā* or *Śrāvana*, according to the particular part of *Abhijit* in which Jupiter rises.

As a practical illustration of the application of the rules, I give in Table X. above, a list, in which the dates of the heliacal risings of Jupiter are shewn for twenty-

¹ See the verse *varshāni Kārttikādāni, &c.*, at page 162 above.

four years, from Śaka-Samvat 1780 to 1803 (expired),¹ with Jupiter's apparent longitudes at the time, and his *nakshatras* determined from those longitudes. The dates of the risings of Jupiter are taken from ordinary *Pañchāngs* in my possession, printed in different Presses at various places. The lunar months in which the risings took place, are all given by the *Amānta* southern reckoning.² The longitude of Jupiter at each rising, is calculated from his longitude, given in the *Pañchāngs*, at some stated interval; for instance, of seven or fifteen days. In naming the *nakshatras*, the Brahma-Siddhānta system of unequal spaces, in the last column of Table IX. on page 165 above, is the one that has been resorted to. In the last column, the months, that is, the names of the *samvatsaras* which then began, are given. It will be seen, that Mārgaśirsha is omitted in each of these two cycles. Other *samvatsaras* also may be omitted, in the same way, according to the circumstances of the particular cycle.

From this Table X. it will be seen that, from one rising of Jupiter to another, the motion of the planet amounts to from 30 to 36 degrees. By the systems of unequal spaces, some months, and the *samvatsaras* which are named from them, have the average space of one and a half *nakshatras*: that is, about 20 degrees only; they are Mārgaśirsha, Māgha, Chāitra, and Jyēsthā; and these are **the samvatsaras that are most apt to be omitted**. For example, in Śaka-Samvat 1780 expired, when Jupiter rose, he was in Rōhiṇī. The following rising took place in Punarvasu; that is, from the first rising, he passed entirely through Mṛga and Ārdra, before the next rising occurred. And, therefore, Mārgaśirsha was omitted. Again, by these two systems, Śrāvāna contains the average space of two *nakshatras*; that is, about 26 degrees, 40 minutes; and, therefore, it also is liable to be omitted. Kārttika, Pausha, Vaiśākha, Āshādhā, and Āśvina, contain the average space of two and a half *nakshatras* each; that is, about 33 degrees; and will but rarely be omitted. And Phālguna and Bhādrapada, containing not less than 40 degrees each, will never be omitted. So also, by the system of equal spaces, the nine months that contain two *nakshatras* each (excluding Abhijit), are sometimes likely to be omitted. But the remaining three, *viz* Phālguna, Bhādrapada, and Āśvina, containing three *nakshatras* each, will never be omitted.

On the other hand, sometimes it is possible that a *samvatsara* may be repeated. By either system of unequal spaces, this may happen in respect of Kārttika, Pausha, Phālguna, Vaiśākha, Āshādhā, Bhādrapada, and Āśvina; but, by the system of equal spaces, only in respect of Phālguna, Bhādrapada, and Āśvina. And, whenever a *samvatsara* is repeated, then two *samvatsaras* will be omitted in the same cycle; one, under ordinary circumstances; and one, on account of the repetition.

¹ Out of these years, in Śaka-Samvat 1789 expired, and again in 1802 expired, no heliacal rising took place.

² See page 148 above, note 1.

In the preceding remarks, my object has been to explain concisely the system of the Twelve-Year Cycle of Jupiter that is based on his heliacal risings; and the three methods for determining the *nakshatra* with which the heliacal rising takes place. I have now to make a few observations of a more general kind; and to introduce the eleven other authorities of which I have spoken at page 162 above. Before doing so, however, I must refer more fully to another system, which also has been incidentally mentioned, of naming the *samvatsaras* of the Twelve-Year Cycle according to Jupiter's passage from one sign of the zodiac into another, with reference to his mean longitude.

The rule for that which I have named the **mean-sign system**, is thus given by Āryabhaṭa in his *Ārya-Siddhānta* or *Āryabhaṭṭya*, Kālakriyāpāda, verse 4,—Guru-bhagaṇā rāsi-guṇās tv-Āśvayuj-ādyā Gurōr abdhāh,—“the revolutions of Jupiter, multiplied by the signs (twelve), (are) the years of Jupiter, the first of which is Āśvayuja.” And it is given, in very similar words, by Brahmagupta, in his *Brahma-Siddhānta*, adhyāya xiii. verse 42,—Guru-varshāny-Āśvayujād dvādaśa-guṇitā Gurōr bhagaṇāh. In this rule, the revolutions (*bhagaṇa*) are meant to be taken from the beginning of the Kalpa, or of a Mahāyuga. But, for practical purposes, we need not go back so far. One Twelve-Year Cycle is completed in one revolution. And, therefore, we can determine the *samvatsara* for a given year, or for any given date in it, by taking Jupiter's signs, including the current sign, of the current revolution, and counting from Āśvayuja. In this system, the signs are intended to be taken, and in practice are taken, according to Jupiter's mean longitude. Now, suppose that on a certain day Jupiter's mean longitude is 9 signs and 12 degrees; i.e. that he is in the tenth sign. Then, counting from Āśvayuja, we have Āshāḍha, as the current *samvatsara* for the given day.¹

The names of the *samvatsaras* of the **Sixty-Year Cycle** also,—according to that which is usually called the northern system, but which is, in reality, the only truly astrono-

¹ In his treatment of the Twelve-Year Cycle (*Indian Eras*, p. 26 ff.), Gen. Sir A. Cunningham opens the subject by quoting Kern's translation (see page 161 above, note 1) of the same verse in the *Bṛihat-Saṃhitā* which I use for the same purpose. But, for the rest, he altogether ignores the force of the reference to Jupiter's rising, and treats the subject as if the heliacal-rising system, described by me above, did not exist at all. What he has deduced from the verse, is only the mean-sign system, which the verse does not really refer to at all; and in respect of which he is wrong in making the *samvatsaras* of both the Twelve-Year and the Sixty-Year Cycle, begin and end with the lunisolar years. The rules that he applies give, at the best, only the *samvatsaras* of the Twelve-Year Cycle by the mean-sign system, and of the Sixty-Year Cycle, that are current at the commencement of a given solar year; they do not provide for the essential point in both the cycles, *vis.* the determination of the exact day on which a given *samvatsara* of either cycle commences—I have not had an opportunity of seeing the writings of Davis and Warren on this subject. But, with all due deference, I may safely say that the Twelve-Year Cycle by the heliacal-rising system, has hitherto remained quite unknown to European scholars.—I would take this opportunity of remarking that I can find no authority for the introduction, in Kern's translation, of the bracketed words “(during which Jupiter completes a twelfth part of his revolution).” Jupiter completes a twelfth part (*rāsī*) of his revolution in about three hundred and sixty-one days; while the interval between two of his heliacal risings is about four hundred days.

mical system of it, and was current, as is shewn by many epigraphical quotations of it, in Southern India also,—are determined by Jupiter's mean place. And the rule is thus given in the *Sūrya-Siddhānta*, i. 55,—dvādaśa-ghnā Gurōr yāta-bhaganā vartamānakaiḥ | rāsibhiḥ sahitāḥ śuddhāḥ shashtyā syur Vijay-ādayaḥ ||,—“the expired revolutions of Jupiter, multiplied by twelve, (*then*) increased by the current signs (*of the current revolution*), (*and then*) divided by sixty, are (*i.e.* the remainder is) (*the samvatsaras counted from*) Vijaya as the first.” In fact, the Sixty-Year Cycle, and the Twelve-Year Cycle of the mean-sign system, are quite identical with regard to the day of the commencement of each *samvatsara*; and, consequently, with regard also to its duration, which, according to Jupiter's mean motion as given in the *Sūrya-Siddhānta*, is 361 days, 1 *ghaṭī*, 36 *palas*. The Twelve-Year Cycle of the mean-sign system, therefore, with regard to its other details, may be most properly described with the Sixty-Year Cycle, which I shall treat of fully on a separate occasion. And I have introduced the present brief mention of it, only because references to it are unavoidable in the following observations.

The eleven authorities for the heliacal-rising system, in addition to the *Bṛihat-Samhitā*, of which I have spoken, are as follows;—(1) **Parāśara** says—Kṛittikā-Rōhiṇīsh-ūditē kshuch-chhastr-āgni-vriṣṭi-vyādhi-prābalyam Chitrā-Svātīyōr uditē nṛipa-sasya-varsha-kshēm-ārōgya-karaḥ.—(2) **Garga** says—pravās-āntē sah-arkshēn: hy-uditō yuga-pach charēt | tasmāt kālād ṛiksha-pūrvō Gurōr abdah pravartatē ||.—(3) **Kaśyapa** says—samvatsara-yugē ch-aiva shashty-abdē'-ngirasas sutaḥ | yan-nakshatr-ōdayam kuryāt tat-samjñam vatsaram viduḥ ||.—(4) **Rishiputra** says—yasmin tishṭhātī nakshatrē saha yēna pravardhatē | samvatsaras sa vijñēyas tan-nakshatr-ābhidhānakāḥ ||.—(5) Also, in the following, Rishiputra quotes **Vasishṭha** and **Atri**, in addition to Parāśara, who is separately referred to above,—Tishy-ādika-yugam prāhur Vasiṣṭh-Ātri-Parāśarāḥ | Bṛihaspatē tu Saumy-āntam sadā dvādaśa-vārshikam || Udētī yasmin māsē tu pravās-ōpagatō-ngirāḥ | tasmāt samvatsaraḥ.—(6) In the **Samāsa-Samhitā**, a short work by Varahamihira, we have¹—Gurur udayati nakshatrē yasmin tat-samjñitāni varshō-ni.—(7) **Bṛihaspati**, as quoted in the *Kiraṇḍavali*, a commentary by Dādābhāi on the *Sūrya-Siddhānta*, says—yadā Gur-ūdāvō bhānōr Gurōr abdas tad-āditah.—(8) In the **Nārada-Samhitā**, Guruchārādhyāya, we have — yad-dhishny-ābh; uditō Jivas tannakshatr-āhva-vatsaraḥ.—(9) In the **Muhūrta-Tattva**, Guruchāra, verse 7, we have — dvy-ṛikshō-Gnēḥ Kārttikāt try-ṛiksha ishu-ravi-Sivō-bd:ḥ sa yēn-ōdit-Ējvah.—(10) In the **Jyōtishadarpaṇa**, adhyāya v., we have — yasmin abhyuditō Jivas tan-

¹ From this, it appears that the *samvatsaras* of the Sixty-Year Cycle also, were originally determined by the heliacal risings of the planet. And corroboration of this is afforded by a verse of Varāhamihira, quoted further on. The above verse of Kaśyapa, evidently applies to the Twelve-Year Cycle also.

² I have taken this, and the preceding five quotations, from Utpala's commentary on the *Bṛihat-Samhitā*.

nakshatrasya vatsarah. — It is unnecessary to translate these ten quotations; as the general purport of all of them is the same; *vis.* that "a *samvatsara* is to be named after that *nakshatra* in which Jupiter attains his rising."—(11) In the remaining authority, the *Sūrya-Siddhānta*, the rule appears to be a little different from that of all the other authorities; though the general features are the same. And, for this reason, though the work is one of the earliest, I have quoted it last. The rule is given in the verse—*Vaiśākh-ādishu kṛṣṇṇe cha yōgaḥ pañchadaśe tithau I Kārttik-ādīni varshāni Gurōr ast-ōdayāt tathā* ||,—“and the years Kārttika and others (*that follow*) (*are to be named*) from the rising, after setting, of Jupiter,¹ according to the occurrence (*of Kṛttikā and other nakshatras*)² on the fifteenth *tithi* in the dark fortnight of Vaiśākha and other (*months that follow*).” The application of this rule seems to be thus:—The years are to be named, according as Kṛttikā and other *nakshatras*,—evidently those in which the sun and the moon stand,—occur on the *amāvāsya* of Vaiśākha and others, immediately preceding or following³ the day on which Jupiter rises; that is, on whatever day Jupiter may rise, the *nakshatra* on either the preceding, or the following, *amāvāsya*, gives the name to the *samvatsara*. This rule seems to have been alluded to, though not in the name of the *Sūrya-Siddhānta*, by Utpala; but it is rejected by him. It may possibly have been occasionally in use; but it certainly does not apply to the Gupta records.

Now, all these quotations distinctly refer, in some form or another, to **the rising of Jupiter**; which it is impossible to understand as meaning anything but his **heliacal-rising**. And, if the rising referred to is the heliacal-rising, then no astronomer can deny that, in the period of about twelve solar years, there are only eleven conjunctions of Jupiter

¹ I should remark that Raṅganātha, one of the best commentators on the *Sūrya-Siddhānta*, explains this verse with the understanding, into which he seems to have been led by Utpala's comments on the *Bṛhat-Samhitā*, viii. 1, that *ast-ōdayāt* means “from the setting or rising.” He adds, however, — *idānīm udaya-varsha-vyavahārō ganakair ganyatē*,—“at the present time, the practice of (naming) the year by the rising, is taken into account by astronomers.” For the sake of consistency, it is justifiable to translate the expression *ast-ōdayāt* as I have translated it above; and the use of the compounded base in the singular, supports that translation. I also find that Dādābhāṭ, in his commentary on the *Sūrya-Siddhānta*, explains it in the same way; his words being — *tath-āstīd udaya-kālē Gurōr tad-yukta-nakshatra-samjñō Gurōr abhō jñeyah*,—“so the year of Jupiter is to be known as having the appellation of that *nakshatra* with which he is joined at the time of (his) rising after setting.”—[There can be no doubt that *ast-ōdayāt* is used here in the sense of “from the rising after setting;” compare such compounds as *supti-ōtthita*, ‘having arisen from sleep;’ *lit.* ‘having slept and then having risen.’—J. F. F.]

² These words, in connection with *yōgaḥ*, have to be supplied from the preceding verse, in which the result exhibited in Table VIII. page 163 above, is given.

³ Which of the two, cannot be determined from the context; and I can find no commentator who has explained the point properly. I myself think that the following *amāvāsya* is intended. But seems that Utpala, in his allusion to this rule, takes the preceding *amāvāsya*.

and the sun, and consequently eleven heliacal risings of the planet. And, this fact being established, the interval of about four hundred days between two successive risings, —the same period, for the duration of each *samvatsara*,—the omission of one *samvatsara* in each cycle of twelve years,—and all the other points described by me,—follow of necessity

It will, doubtless, have been noticed that I have not been able to give any quotations from the first *Āryabhaṭa* (born A.D. 476) or *Brahmagupta* (born A.D. 598), in support of the heliacal-rising system. And it might be sought to base some argument against its existence, on the grounds that these two early authorities, who moreover may be said to be the originators of two of the three schools of astronomers in India, are silent about it, though they do give the mean-sign system. But the facts only prove the early existence and use of the mean-sign system; which I do not seek to deny. They do not prove, either that the heliacal-rising system did not exist; or that, having existed, it had gone out of use in their time. To take another instance, *Āryabhaṭa* and *Brahmagupta* give no rule for finding the *samvatsaras* of the Sixty-Year Cycle; but, to say that this cycle was not known to either of them, would hardly be sensible. The mean-sign system for the Twelve-Year Cycle is undoubtedly early. But the heliacal-rising system is earlier still. Among the authorities quoted above, the *Sūrya-Siddhānta*:¹ is as early a work as the *Āryabhaṭīya*, if not earlier. And, that *Parāśara*, *Garga*, and *Kaśyapa*, are earlier than *Āryabhaṭa*, cannot be denied. *Utpala* quotes a verse of *Garga*, which, with some proposed emendations, I give as it stands in my manuscript copy,—*evam Āśvayujāṅ ch-aiva Chaitraṅ ch-aiva Bṛihaspatiḥ | samvatsarō(ṛam) nāma(ṛsa)yatē saptaitēda (? saptaty-abda)-satē-dhikē ||*² This verse seems to refer to the mean-sign system; though I can say nothing definitely about it, without seeing the context; of which I have not the opportunity at present. But, supposing that it does refer to the mean-sign system, still it is not unfavourable to the heliacal-rising system; for the same *Utpala* also quotes a verse of the same *Garga*, given at page 170 above, in which *Garga* says—"when Jupiter, after dwelling together (*with the sun*),³ rises and walks along with a *nakshatra*, then commences the year of Jupiter, of which the first part (*of the name*) is the (*name of that*) *nakshatra*."

Not only that **the heliacal-rising system** is very early, but that it alone **is the original system of the Twelve-Year Cycle**, is self-evident. The heliacal rising of Jupiter is a natural phenomenon. No scientific apparatus is needed for the observation of it; nor are

¹ To say that the *Sūrya-Siddhānta* is a work of *Varāhamihira*, is simply a mistake. I cannot enter into this point at present; but would refer any who hold that view, to *Varāhamihira's Pañcha-Siddhāntikā*, and to *Kern's Preface* to his edition of the *Bṛihat-Samhitā*.

² [Gen. Cunningham also has quoted this verse (*Archæol. Surv. Ind.* Vol. X. p. 114); and in such a way, his authority giving *nāyātē*, where Mr. Sh. B. Dikshit's MS. gives *nāmāyātē*, as to shew that, in the second half of it, we certainly have to read *nāyātē saptaty-abda-satē*.—J. F. F.]

³ *pravṛtāntē* may be translated by "after having completed his journey;" *i.e.* having completed a revolution of some kind or another.

any calculations required.¹ But such is not the case with the passing of Jupiter from one sign of the zodiac into another. No kind of apparatus can determine Jupiter's mean longitude. It is to be found only by calculations, the rules for which must have been established after observations carried on during a very long time; to lay down the means of determining Jupiter's mean yearly or daily motion, is not a thing that can be accomplished in a few years. It seems, therefore, quite evident that the system of naming the *samvatsaras* after the *nakshatras* in which Jupiter rises, *i.e.* the heliacal-rising system, is the only original one.

So much, as regards the antiquity of the heliacal-rising system. Let us now look into its somewhat later use. Varāhamihira is later than Āryabhaṭa. And his verse with which I have opened my account of the Twelve-Year Cycle, undoubtedly refers to this system. So, also, another of his verses, in the *Bṛihat-Saṃhitā*, viii. 27, points to the same thing. It runs—*ādyam Dhanishṭhām samabhiprapannō² Māghē yad-āyaty-udayam Surējyah I*

¹ The phenomenon, moreover, is one to which much attention has always been paid in India. Even in the present day, almost all the Hindu *Pañchāngs* give the dates of the heliacal rising and setting of Jupiter. This is for religious purposes; since, when Jupiter is invisible, some duties and ceremonies, such as investiture with the sacred thread, marriage, pilgrimages, &c., are not to be performed; and the dates in question are necessary, in order to know when he is visible, and when he ceases to be so. In *Pañchāngs* printed in Mahrāshṭra, the custom of naming the *samvatsaras* after the months is not in use; in fact, the Twelve-Year Cycle is now almost unknown to the people at large of the Dekkan. But in a *Pañchāng* prepared by Jwālāpati Siddhānti, and printed in the Jñānasrīyōdaya Press at Madras, I find that the author, in the *samvatsara-phala*, after giving the two *samvatsaras* of the Sixty-Year Cycle, according to the northern and the southern reckoning, goes on to say—*saravatra Gur-ādāya-vasit (Chaitr-āddō grāhyah*,—"all over (India) a (certain) year (*i.e.* such *samvatsaras* as Chaitra, &c.), which depends on the rising of Jupiter, is to be taken;" from which it is evident that some such rising-system, as that described above, is followed in this *Pañchāng* from Madras. Also, in the *Chandu-Pañchāng*, prepared for the meridian of Jōdhpur in Mārṭwād, and used there and by Mārṭwāḍis in other parts of India, the *samvatsaras* are named as Chaitra-Varsha, Vaisākha-Varsha, &c.; the system adopted in that *Pañchāng*, however, for naming the *samvatsaras*, is the mean-sign system.

² The reading that I give, is from my manuscript copy. But, *s* and *f* being very liable to confusion, the reading *ādyam Dhanishṭh-āmsam abhiprapannō*, which is given in some printed copies, may also be of some authority. By calculation, however, I find that Jupiter does not always stand just at the beginning of Dhanishṭhā, at the time of his rising at the commencement of the Prabhava *samvatsara*. And I think, therefore, that the reading which I give, is the author's original reading. I take *ādyam* to qualify the word *nakshatram* understood. And Varāhamihira calls the *nakshatra* in question "the first," because his opinion was, I think, that Dhanishṭhā was the first *nakshatra* of the Sixty-Year Cycle, as it was of the Five-Year Cycle of the Vēdānga-Jyautishā [see its verse—*svar ākramit sōm-ārhan yadō sākanā sa-Vāsava syāt tad-ādi-yugam Māghah*,—"when the moon and the sun, being in (the *nakshatra*) Vāsava (Dhanishṭhā), go together in the heavens, then there is the beginning of the Yuga (and of the month) Māgha"], which two he intends to reconcile.—[Kern would seem to have known only the reading *ādyam Dhanishṭh-āmsam*. His translation (*Four. R. As. Soc. N. S. Vol. V. p. 49 l.*), which follows also the reading of *pravartat* for *prapadyat*, is—"when Jupiter, on reaching the first quarter of Dhanishṭhā, rises in the lunar month of Māgha, then begins the first year of the cycle of sixty, named Prabhava, a year salutary to all beings." And he adds the

shashty-abda-pûrvaḥ Prabhavaḥ sa namnā prapadyatē bhûta-hitas tad-âbdaḥ II.—“when Jupiter, having come to the first (*nakshatra*) Dhanishṭhâ, attains (*his*) rising in (*the month*) Mâgha, then commences that year, beneficial to beings, which is named Prabhava, the first of the sixty years.” Now, in eighteen centuries from the beginning of the Śaka era, the Prabhava *samvatsara* has occurred thirty times. And, by approximate calculations, I find that Varāhamihira's assertion, though not quite correct, is nearly so by the heliacal-rising system. Out of the thirty occasions, Jupiter rose, according to the *Amānta* southern arrangement of the fortnights,¹ twenty-six times in the month of Mâgha; three times early in Phâlguna; and once in Pausha, nearly at the end of it. And, on many occasions he rose in the Dhanishṭhâ *nakshatra*; and on some, in Śravaṇa. The assertion, however, is not correct for the mean-sign system. According to that system, at the commencement of the Prabhava *samvatsara*, which always begins when Jupiter, by his mean longitude, enters Kumbha or Aquarius, he evidently always stands in the middle of Dhanishṭhâ.² But the Prabhava *samvatsara* may begin, and as a matter of fact I find by calculation that it has begun, in any of the twelve months; as will be shewn when I treat of the Sixty-Year Cycle. It is evident, therefore, that the verse in question supports the heliacal-rising system. Moreover, the word *udaya* itself is used in it. It might be argued that Varāhamihira's rule (*Brihat-Samhitâ*, viii. 22; *ĕk-aikam abdēshu nav-âhatēshu*, &c.) for finding the *nakshatra* of Jupiter, has reference to his mean longitude; and, consequently, that it gives the mean-sign system. But it is absurd to suppose that so learned an astronomer as he, stating the rule that a *samvatsara* is to be named from the *nakshatra* in which Jupiter rises, did not know that the *nakshatra*, at the time of his rising, can be determined only from his apparent longitude. The reason why he gives a rule for finding the mean longitude only, is, in my opinion, this:—Anyone conversant with Hindu mathematical astronomy, knows how tedious a task it is to find the mean longitude of a planet from the *ahargana*, or number of elapsed days, counted from the beginning of the Kalpa or of a Yuga. But, when once it has been found, it is much less tedious to calculate, from it, the apparent longitude by the general rules. So, Varāhamihira, I think, gives a simple rule for finding the mean longitude of Jupiter on a given day, and leaves to the astronomer the calculation of the apparent longitude. Or, it may also be said, as the difference between the mean and the apparent longitudes of Jupiter, on the day of his heliacal-rising, is not very much,—sometimes about five degrees, and sometimes nearly nil, as I have found from several calculations,—Varāhamihira gives the simple rule for rough practical purposes only; leaving it to the

note—“cf Davis, *Asiatic Researches*, Vol. III. p. 220. The word *amīa* also means ‘degree,’ but is here rendered by ‘quarter,’ according to Utpala, who explains it by *pāda*.”—J. F. F.]

¹ See page 148 above, note 1.

² The sign Kumbha commences in the middle of Dhanishṭhâ, and ends at the end of the third quarter of Pûrvâ-Bhâdrapadâ.

astronomer to make more detailed calculations, when absolute accuracy is required. But, even supposing that the said verse of Varāhamihira implies the mean-sign system, it will only prove that he gives both systems.

Let us now turn to the **more modern period**. Of the authorities quoted above in support of the heliacal-rising system, the *Muktārta-Tattva* and the *Jyōtishadarpaṇa* are comparatively modern. The author of the first is the father of the well-known Gaṇeśa Daivajña, the author of the *Grahaḍghaṇa*; and, therefore, its date is about Śaka-Saṃvat 1420 expired (A.D. 1498-99); and it was written at Nandgaum on the western coast, about forty-five miles south of Bombay. The date of the second, as I have determined from certain data in it, is Śaka-Saṃvat 1479 expired (A.D. 1557-58); and it was written at Koṇḍapalli, somewhere in the Kaṇṇāṭaka country. And, in addition to these two, a third, reference to the heliacal-rising system has been given above, at page 171 note 1, from Raṅganātha's commentary on the *Sūrya-Siddhānta*. The date of this commentary is Śaka-Saṃvat 1525 expired (A.D. 1603-1604); and it was written at Benares. These details suffice to shew that the heliacal-rising system is referred to in works of a modern period, and belonging to different parts of the country.

It is true that **the use of the Twelve-Year Cycle is rare**. This is shewn by the fact that some astronomical works do not refer to it, in either system, though it would not have been beyond their sphere to do so; and by the fact that, out of many hundreds of inscriptions, only seven have been found, mentioning the *samvatsaras* of it.¹ But, if the use of the heliacal-rising system is rare, the use of the mean-sign system is still more so. The *samvatsaras* mentioned in the four records of the Early Gupta period, which give full details for calculation, are proved to belong to the heliacal-rising system. And, while I have been able to quote no less than eleven authorities referring to that system, a distinct reference to the mean-sign system is to be found in only two; *viz.* Ārvabhaṭa and Brahmagupta, as quoted above. If to these we add an interpolated verse in the *Siddhānta-Śiromaṇi*, and also hold that Garga and Varāhamihira give the system, even then the number comes to only five.² And, in about eight of such works as would be expected to refer to the system, of a date later than A.D. 1478, which I have examined, I find a reference to it in none at all.

Looking to **the present time**, if the mean-sign system is used in one part of the country, the heliacal-rising system is used in another;³ while, in others, both systems are almost, if not quite, unknown. The mean-sign system is doubtless the more convenient

¹ *viz.* the five records of the *Mahārājās* Hastin and Samkshobha; and the two grants of the Kadamba chieftain Mṛigēśavarman, referred to at page 106 above, note 1.

² A verse containing a reference to the system, is given, as belonging to Śrīpati, in Pandit Bapu Deva Shastri's edition of the *Siddhānta-Śiromaṇi*, p. 13, note; but I do not find it in the *Ratnamālā* of Śrīpati.

³ See page 173 above, note 1.

of the two; since the duration of the *samvatsara*, roughly three hundred and sixty-one days, approaches so near to that of the solar year; and the omission of a *samvatsara* occurs only once in about eighty-five years. And this point of convenience seems to be the reason for which the system was invented by the astronomers. But, as both the systems are given in astronomical works, both of them must certainly have been actually used. And such will always be the case, as long as those works exist.

APPENDIX IV.

The Chronology of the Early Rulers of Nêpâl.

The inscriptions which give the matter for this Appendix all belong to Khâtmandu and its vicinity, and consist of fifteen collected by the late Dr. Bhagwanlal Indraji, and published by him and Dr. Bühler in the *Ind. Ant.* Vol. IX. p. 163 ff.; and of four obtained by Mr. Bendall, of which the most important one was published originally in the *Ind. Ant.* Vol. XIV. p. 97 f., and has been reprinted in his *Journey in Nêpâl and Northern India*, p. 72 ff. and Plate viii., with the first publication of the other three, p. 74 ff. and Plates ix. x. and xi.

The historical results of the former set were discussed at length by Dr. Bhagwanlal Indraji in his paper entitled "Some Considerations on the History of Nêpâl," edited by Dr. Bühler, and published in the *Ind. Ant.* Vol. XIII. p. 411 ff. His results, however, are unfortunately vitiated by a radical error; *vis.* the reference of one series of the dates to the Vikrama era, instead of to the Gupta era nearly four hundred years later. This was due, partly to the misinterpretation of an important verse in the inscription of Jayadêva II. of Harsha-Samvat 153; and partly to the want of the key-note supplied by Mr. Bendall's inscription of Gupta-Samvat 316. And it was, of course, the publication of this last inscription that led me to look carefully into the whole matter, and at length to hit upon the fundamental mistake, without a recognition of which it might still be argued that Mr. Bendall's date of 316, for Śivadêva I. and Amśuvarman, stands alone in belonging to the Gupta era, and that, in spite of it, Dr. Bhagwanlal Indraji was right in referring the other larger dates to the Vikrama era.

Taking the inscriptions in question in regular chronological order, the dates and other important points are as follows:—

A.—Mr. Bendall's inscription No. 1; *Ind. Ant.* Vol. XIV. p. 97 f., and *Journey in Nêpâl*, p. 72 ff. and Plate vii.—The charter recorded is issued from the house or palace called Mânagriha (line 1). The inscription is one of the *Bhaññdraka* and *Mahârâja*, the illustrious¹ Śivadêva I. (l. 2 f.), the banner or glory of the Lichchhavikula.² And it records a grant made by him on the advice, or at the request,³ of the *Mahâśmanta* Amśuvarman (l. 6 f.). The *Dâtaka* is the *Svâmin* Bhôgavarman (l. 15).⁴ The date

¹ *etl.*

² *Lichchhavi-kula-kêtu*, line 2.

³ *mahâśmant-Amśuvarmanâ vijñâpîtâna mayâ*; line 6-7.

⁴ This person would seem to be Amśuvarman's sister's son, who is mentioned in inscription E. below.—He must not be confused with Śivadêva II.'s father-in-law, the Maukhari Bhôgavarman, who is mentioned in inscription R. below, and was at least a full generation later.—See page 180 below, note 3, on another point.

(l. 15), in numerical symbols here and throughout the series, is (Gupta)-Samvat 316, Jyaisht̥ha-sukla-divā-daśamyām; which, with the epoch of A.D. 319-20, answers, approximately, to the 3rd May, A.D. 635.

B.—Dr. Bhagwanlal Indrajī's inscription No. 5; *Ind. Ant.* Vol. IX. p. 168 f.—The charter is issued from *Mānagriha* (line 1). The inscription is one of the *Bhaṭṭāraka* and *Mahārāja*, the illustrious *Śivadēva I.* (l. 2 f.), the banner of the *Lichchhāvika*. It recorded some act, the details of which are broken away and lost, done by him, as in inscription A., on the advice, or at the request, of the *Mahāsāmanta*, the illustrious *Aśuvarman* (l. 8 f.).¹ The date, and the name of the *Dātaka*, are broken away and lost in line 11 ff.

C.—Dr. Bhagwanlal Indrajī's inscription No. 6; *Ind. Ant.* Vol. IX. p. 169 f.—The charter is issued from the house or palace called *Kailāsakūṭabhavana* (line 1). The inscription is one of the *Mahāsāmanta*, the illustrious *Aśuvarman* (l. 2). The *Dātaka* is the *Mahāsarva[daṇḍa]yaka* Vikra[masēna] (l. 14).² The date (l. 14) is (Harsha)-Samvat 34, Jyaisht̥ha-sukla-daśamyām; which, with the epoch³ of A.D. 605-606, answers, approximately, to the 18th May, A.D. 639.

¹ As in page 177 above, note 3.

² This is the name as completed by Dr. Bhagwanlal Indrajī. But, if we accept it as correct, we must be careful not to confuse this person with the *Rājaputra* Vikramasēna who was the *Dātaka* of inscription S. below, more than two hundred years later.—I have not seen the original rubbing of this inscription.

³ This epoch is taken from Mr. Sh. B. Dikshīt's calculation of the date in the Dighwā-Dubault grant of the *Mahārāja* Mahēndrapāla. At the end (*Ind. Ant.* Vol. XV. p. 113, line 14) we have, for the assignment of the charter, the year 155, Māgha śu di 10; and from line 12 we learn that, when making the grant, the *Mahārāja* had bathed on the occasion of the *Kumbha-Samkrānti* or entrance of the Sun into Aquarius. The epoch of the era is fixed approximately by a statement of Alberūnī (*Alberūnī's India*, Translation, Vol. II. p. 5), to the effect that, in a Kaśmirī almanac, he had read that Harshavardhana was six hundred and sixty-four years later than Vikramāditya. Subject to some doubt as to whether Alberūnī is speaking of the epoch of the era, or of its first current year, and as to whether the Vikrama year indicated by him is to be taken as current or as expired, this statement indicates, approximately, Śaka-Samvat 528 expired, and 529 current (A.D. 606-607), as the epoch or year 0 of the era. And this is the epoch selected by Gen. Cunningham (*Indian Eras*, pp. 64 f., 157 ff.), on the authority of Alberūnī's statement. By calculations based on the *Sērya-Siddhānta*, however, Mr. Sh. B. Dikshīt finds that an epoch one year earlier than this is required, in order that the details of the date in the Dighwā-Dubault grant may work out correctly. Thus, with the basis of Harsha-Samvat 155 + Śaka-Samvat 527 expired = Śaka-Samvat 682 expired, the *Kumbha-Samkrānti* occurred at 43 *ghaṭis*, 40 *palas*, on Monday, the 19th January, A.D. 761; and the ninth *tithi* of the bright fortnight of Māgha ended about four hours later, at 53 *ghaṭis*, 15 *palas*, on the same day. Or, by the *Ārya-Siddhānta*, the times were, for the *Samkrānti*, 42 *ghaṭis*, 30 *palas*; and for the *tithi*, 52 *ghaṭis*, 41 *palas*. In both cases, the *ghaṭis* and *palas* are from mean sunrise at Ujjain. And he adds the note—"the *puṇyakhāla* or meritorious time for performing religious duties in connection with a *samkrānti*, is, according to some authorities, from sixteen *ghaṭis* before, to sixteen *ghaṭis* after, the time of the *samkrānti*; and, according to others, in the case of some *samkrāntis*, from ten to

D.—Mr. Bendall's inscription No. 2; *Journey in Népal*, p. 74 f., and Plate ix.—The charter is issued from **Kailāsakūṭabhavana** (line 1). The inscription is one of an illustrious *Mahāśmanta*, whose name is effaced, but may with tolerable certainty be restored as **Aṁśuvarman** (l. 2). And it records the grant of two fields, for the purpose of providing for the repairs of some building. The *Dātaka* (l. 17) is the *Mahābalādhyakṣha* Vindusvāmin. The date (l. 16) is (Harsha)-Sāmvat 34, prathama-Pausha-śukla-dvityāyam; which should answer,¹ approximately, to the 3rd December, A.D. 639.

E.—Dr. Bhagwanlal Indrajī's inscription No. 7; *Ind. Ant.* Vol. IX. p. 170 f.—The charter is issued from **Kailāsakūṭabhavana** (line 1). The inscription is one of the illustrious **Aṁśuvarman** (l. 5), to whom no formal titles are allotted here. It mentions

sixteen or even forty *ghaṭṭs* before the *samkrānti*, up to the time of the *samkrānti*, and, in the case of the other *samkrāntis*, from the time of the *samkrānti*, up to from ten to sixteen or even forty *ghaṭṭs* after it. But generally, when a *samkrānti* occurs at midnight,—as it did, roughly, in the present instance,—the *punyakhāla* is held to be on the following day. And, in the present case, there is every probability of the bathing &c. having been performed on the following day, *i.e.* on Māgha śukla daśamī.—With other years, the given *samkrānti* cannot be brought into accordance with the given day and *tithi*. Thus, with Śaka-Sāmvat 680 expired, the *samkrānti* occurred six or seven days after the given *tithi*, on the *Pārnimānta* Phālguna kṛishṇa 2; with 681 expired, on the *Pārnimānta* Phālguna kṛishṇa 13; with 683 expired, on the *Pārnimānta* Phālguna kṛishṇa 5; with 684 expired, on Māgha śukla 1; and with 685 expired, on Māgha śukla 12. It is certain, therefore, that the correct English equivalent is the one obtained with Śaka-Sāmvat 682 expired. And, taking the given Harsha year as a current year, and treating it as having the same scheme with the northern Śaka year, the epoch is Śaka-Sāmvat 527 expired, or A.D. 605-606 current; and 528 years have to be added, to convert current Harsha years into current Śaka years, and 527, to convert them into expired Śaka years as the basis of calculations. The commencement or first current year of the era, is A.D. 606-607 current.—I should remark, as I did when editing the grant, that a slight doubt may be felt as to the value of the third numerical symbol, in the units place, which I interpret as 5. And the exact epoch would be varied, by allotting a different value to this symbol. But the choice lies only between 4, 5, and 3. I do not think that any authority can be found for interpreting it as 4. And, if it were interpreted as 8, then the epoch of the era would be A.D. 602-603; and its first current year would be A.D. 603-604, for which year, as the commencement of the reign of Harshavardhana, there seems to be no authority whatever.—I should also point out that the next inscription, D. below, of Harsha-Sāmvat 34, refers to an intercalation of the month Pausha; and that Prof. Adams of Cambridge, and Prof. Schram of Vienna, as reported by Dr. Bühler in the *Ind. Ant.* Vol. XV. p. 338 (see also *Journey in Népal*, p. 76), obtained a mean intercalation of Pausha in A.D. 640; which would necessitate the adoption of A.D. 606-607 as the epoch. But this intercalation remains to be examined in detail; and, for the present, I have only a note by Mr. Sh. B. Dikshīt that, according to the verse *Mēsh-ādi-sthē savitāri &c.* (see page 88 above, note 5), the intercalated period should be called Mārgaśr̥ṣha; and that, in calling it Pausha, exactly the contrary is done of the process by which we obtain Mārgaśr̥ṣha as the name of the intercalated period that is referred to in the Kaira grant of Dharasēna IV. of the year 330 (see page 93 ff. above).—The question will, I hope, be treated more fully by Mr. Dikshīt hereafter. Meanwhile, for present purposes, I adopt A.D. 605-606 as the epoch.

¹ As regards the equivalent English date, however, see a remark, in the preceding note, on the indicated intercalary nature of this month Pausha.

Aṁśuvarman's sister Bhōgādēvi, who was the wife of the *Rājaputra* Śūrasēna,¹ and the mother of the illustrious Bhōgavarman² and Bhāgyādēvi. It records certain orders addressed by Aṁśuvarman to the officials of the Western Province (*paśchim-dhikarāṇa-vṛttibhujāḥ*, lines 5-6; and *paśchim-dhikarāṇa*, line 14), in connection with three *linga* forms of the god Śvara or Śiva. The *Dātaka* is the *Yuvarāja* Udayadēva.³ The date (l. 22) is (Harsha)-Sāmvat 39, Vaiśākha-śukla-divā-daśamyaṁ; answering, approximately, to the 24th April, A.D. 644.

F.—Dr. Bhagwanlal Indrajī's inscription No. 8; *Ind. Ant.* Vol. IX. p. 171.—This is not a formal charter, issued from any specified place. It simply records that, by the favour of the illustrious Aṁśuvarman (line 2), a *praṇālī* or 'conduit' was caused to be built by the *Vārta*⁴ Vibhuvvarman, for the increase of his father's religious merit. The date (l. 1) is (Harsha)-Sāmvat⁵ 44 or 45, Jyēshtha-śukla, which has its equivalent in the month of May or June, A.D. 649, or May, A.D. 650.

G.—Dr. Bhagwanlal Indrajī's inscription No. 9; *Ind. Ant.* Vol. IX. p. 171 f.—The charter is issued from *Kailāsakūṭabhavana* (line 3 f.). The inscription is one of the illustrious *Jishnugupta* (l. 4). It records that, at the request of the *Sāmanta* Chandrarvarman, a *tilamaka* or 'water-course,' which had been constructed by the *Bhaṭṭāraka* and *Māhārāja-dhirdāja*, the glorious Aṁśuvarman (l. 6 f.), was made over by Jishnugupta to Chandrarvarman, to be repaired; &c. The *Dātaka* (l. 21) is the *Yuvarāja*, the illustrious Vishnugupta. The date (l. 21) is (Harsha)-Sāmvat 48, Kārtika-śukla-2; answering, approximately, to the 30th September, A.D. 653.—Lines 1 and 2 of this inscription mention *Mānagriha*,⁶ and, in connection with it, the *Bhaṭṭāraka* and *Māhārāja Dhruvadēva*; but the passage is much mutilated, and does not in itself suffice to explain the connection between Dhruvadēva and Jishnugupta.⁷

¹ The original is somewhat damaged, but it has undoubtedly *ś* in the first *akshara* of this name; not *ś* as given by Dr. Bhagwanlal Indrajī in his text and translation. And the spelling is the same in line 3 of an inscription of the Śūrasēna family published by him in the *Ind. Ant.* Vol. X. p. 34 ff. But very probably *ś* is the more correct spelling; especially as line 8 of the present inscription mentions the *linga* named Śrābhōgēvara.

² See page 177 above, note 4.

³ The dates seem to prevent the identification of this person with the Udayadēva of the Thākurl family, mentioned in inscription R. below.—He was perhaps a Lichchhavi, as suggested by Dr. Bhagwanlal Indrajī. If so, in this Lichchhavi *Dātaka* of a Thākurl charter, we have an instance parallel to the Thākurl *Dātaka* of a Lichchhavi grant, suggested in page 177 above, note 4.

⁴ Dr. Bhagwanlal Indrajī took *Vārta* as a family or tribal name. It seems more likely, however, that, as suggested by himself, it is an official title, synonymous with the *vṛttibhuj* of inscription E. above; and that the correct form is *vārta* (with the double *r*) from *vṛtti*.

⁵ The second symbol is doubtful; but it is either 4 or 5.—I have not seen the original rubbing of this inscription.

⁶ The two syllables *māns*, immediately after *svasti*, are clear enough in the original rubbing, though they hardly shew in the lithograph, and were not given by Dr. Bhagwanlal Indrajī in his text.

⁷ The purport of it, however, must have been the same as in the next inscription H.

H.—Dr. Bhagwanlal Indraji's inscription No. 10; *Ind. Ant.* Vol. IX. p. 173 f.—The charter is issued from **Kailāśakūṭabhavana** (line 6). The inscription is one of the illustrious **Jishnugupta** (l. 7). The details are much mutilated; but the subject is a *tilamaka* or 'water-course,' which had been constructed by the *Mahāsmanta*, the illustrious **dēva**. The name of the *Dātaka*, and the date, have peeled off and are lost.—Lines 3 and 4 of this inscription again mention **Mānagriha**, and, in connection with it, the *Bhaṭṭāraka* and *Mahārāja*, the illustrious **Dhruvadeva**, the banner of the **Lichchhavikula**. Between *mānagriha* and *dita-chitta* in line 4, there are four (or perhaps five) *aksharas* which are much damaged, and are quite uncertain even in the rubbing; but the *ha* (not *hd*) is distinct enough; and this, and the whole construction, shews that we have here,—not *Mānagrihāt*, the formal ablative of issue,—but the base *Mānagriha*, as the first member of a compound, ending with *santati*, that qualifies *śrī-Dhruvadeva*, and means something like "who belonged to a lineage which had its thoughts [gladdened by residing] at *Mānagriha*." As regards the connection between *Dhruvadeva* and *Jishnugupta*,—in line 5, after *śrī-Dhruvadeva*, Dr. Bhagwanlal Indraji read *purassara sakala*, and interpreted the passage as shewing that *Jishnugupta* acknowledged *Dhruvadeva* as his lord paramount. The interpretation is possibly correct; though the text may equally well mean nothing more than a courteous reference by *Jishnugupta* to one whose position was equal to his own. But, from the rubbing, the proper reading is certainly *purassara-sakala*, in composition. The whole passage, in fact, from *Mānagriha*, line 4, down to *mānasa*, lines 5-6, is one continuous compound, meaning, in the latter part, that *Jishnugupta*'s mind had been brought into a state of contentment by devising the means of freeing from calamity all the people headed by *Dhruvadeva*, &c. And the expression *Dhruvadeva-purassara-sakalajana* is analogous in its purport to the *sa-nripatēr-jjagatō (hitāya)*, " (for the welfare) of the world (i.e. of all the people), together with the king," of line 2 of inscription M. below.

I.—Dr. Bhagwanlal Indraji's inscription No. 11; *Ind. Ant.* Vol. IX. p. 174.—This is not a formal charter, issued from any specified place. It simply records certain grants made in the augmenting victorious reign of the illustrious **Jishnugupta** (line 9). The era-date, if any was recorded, is lost with lines 27 ff.

J.—Mr. Bendall's inscription No. 3; *Journey in Népāl*, page 77 ff. and Plate x.—The charter is issued from **Kailāśakūṭabhavana** (line 1). The king's name is lost, somewhere in lines 2 to 7. The inscription provides for the worship of the god *Vajrēśvara* (l. 17), and other religious matters. The *Dātaka* (l. 28) is the *Bhaṭṭāraka*, the *Yuvarāja* *Skandadeva*. The date (l. 29) is (Harsha)-Samvat 82, *Bhādrapada śukla-divā*; which has its equivalent in the month of August, A.D. 687.

In the original rubbing, *śrī* is *ve.v* distinct at the beginning of line 14. Two *aksharas* are illegible between it and *dēva*.

K.—Dr. Bhagwanlal Indrajī's inscription No. 1; *Ind. Ant.* Vol. IX. p. 163 ff.—This furnishes the following short genealogy:—**Vṛishadēva** (line 8):—his son **Śamkaradēva** (l. 12), with a reference in lines 9 and 10 to other sons, who, however, are not mentioned by name;—**Śamkara's** son, **Dharmadēva** (l. 16), who with justice [governed] a great hereditary kingdom (*kula-kram-āgatam rājyam mahat*, line 17), and whose wife was **Rājyavati**;—and **Dharmadēva's** son **Mānadēva** (l. 20), who was appointed to reign by his mother on his father's death. The inscription then records that **Mānadēva** made an expedition to the East, and reduced to obedience some "roguish," ill-behaved, or rebellious *Sāmantas* there; and then went back to the West, where also he heard of misdoings on the part of a *Sāmanta*. Here, unfortunately, the available part of the inscription terminates, the rest being buried underground. The date (l. 1 f.) is (Gupta)-*Saṃvat* 386, *Jyēṣṭha-māsa-śukla-pakṣhē pratipadi* 1 *Rōhiṇī-nakṣhatra-yuktē chandramasi muhūrtē praśastē*=*Bhijiti*; the exact equivalent of which, as we have seen at page 95 ff. above, is Tuesday, the 28th April, A.D. 705.

L.—Dr. Bhagwanlal Indrajī's inscription No. 12; *Ind. Ant.* Vol. IX. p. 174 ff.—The charter is issued from **Kailāsakūṭabhavana** (line 1). The inscription is one of the *Paramabhāṭṭāraka* and *Mahārājādhirāja*, the glorious **Śivadēva II.** (l. 3). The *Dātaka* (l. 23) is the *Rājaputra* **Jayadēva**. The date (l. 23) is (Harsha)-*Saṃvat* 119, *Phālguna-śukla-divā-daśamyām*; answering, approximately, to the 20th February, A.D. 725.

M.—Dr. Bhagwanlal Indrajī's inscription No. 2; *Ind. Ant.* Vol. IX. p. 166 f.—This is not a formal charter, issued from any specified place. It simply records that, by the favour of the illustrious 'king' **Mānadēva** (line 1), a certain **Jayavarman** erected a *linga* named **Jayēśvara**, for the welfare of the world, (*i.e.* of all the people), together with the king,¹ and endowed it with a permanent endowment.² The date (l. 1) is (Gupta)-*Saṃvat* 413, equivalent to A.D. 732-33, without any further details.

N.—Dr. Bhagwanlal Indrajī's inscription No. 13; *Ind. Ant.* Vol. IX. p. 176 f.—This inscription is very much damaged.³ The name of the palace whence the charter was issued, is lost. And the king's name is illegible in line 3; but, as it is preceded by the titles of *Paramabhāṭṭāraka* and *Mahārājādhirāja*, the name was probably that of **Śivadēva II.**, as in inscription L. above; and Dr. Bhagwanlal Indrajī filled up the *lacuna* in that way. This is a Buddhist inscription. The *Dātaka* (line 36) is the *Bhāṭṭāraka*, the illustrious, or perhaps the venerable, **Śivadēva**. The date (l. 37) is somewhat doubtful;⁴ but

¹ *sa-nripatēr-jagatō hīdya*; line 2.

² *akṣhaya-nivī*; line 2.

³ I have not seen the rubbing of this inscription.

⁴ In Śaka-Saṃvat 672 current, or 671 expired, the month *Jyēṣṭha* was intercalary (see *Indian Eras*, p. 161, and *Chronology*, p. 126). And the absence of any hint of this in the present record, would, if the reading of the second numerical symbol as 40 could be established, be a point in favour of the year being Śaka-Saṃvat 671 current, or 670 expired; which is in accordance with the epoch of A.D. 605-606.

Dr. Bhagwanlal Indrajī read it as (Harsha)-Samvat 143, Jyaisht̥ha-śukla-divā-trayōdaśyām; answering, approximately, to the 25th May, A.D. 748. There is, however, the possibility that the second numerical symbol is 20 or 30, instead of 40.

O.—Dr. Bhagwanlal Indrajī's inscription No. 14; *Ind. Ant.* Vol. IX. p. 177 f.—All the introductory part of this inscription, recording the palace whence the charter was issued and the name of the king, is broken away and lost. The *Dātaka* (line 17) is the *Yuvarāja* Vijayadēva. The date (l. 17) is (Harsha)-Samvat 145, Paus̥ha-śukla-divā-tritriyāyām; answering, approximately, to the 6th December, A.D. 750.—Dr. Bhagwanlal Indrajī, taking Vijayadēva as a "vicarious" name of Jayadēva II., allotted the inscription, chiefly on this account, to Śivadēva II. As far as the date goes, the inscription may be one either of him, or of **Jayadēva II.** But Vijayadēva cannot be a "vicarious" name of Jayadēva II. Occasional instances may be cited, in which the special terminations of names vary; thus, the Vasantasēna of inscription P. below, appears in R. line 10, and in the *Vamśdvali*, as Vasantadēva; and Jayadēva I. of R. line 8, perhaps appears in the *Vamśdvali* as Jayavarman. But even this is rare enough. And, apart from the substitution of *birudas* or secondary titles, the only epigraphical instance that I can quote, of any variation in the first and really distinctive part of a king's name, is to be found in line 46 ff. of the *Kauṭhēn grant*¹ of the Western Chālukya king Vikramāditya V., of Śāka-Samvat 930, where the Daśavarman of other inscriptions is called Yaśovarman. But that instance is not a very satisfactory one.² And in the present case there is not any metrical exigency, as there is in the places where the name of Daśavarman occurs, to justify any variation. If the present inscription is one of Śivadēva II., then Vijayadēva was another son of his; if, as seems to me more probable, it is one of Jayadēva II., then Vijayadēva was a son of the last-mentioned person.

P.—Dr. Bhagwanlal Indrajī's inscription No. 3; *Ind. Ant.* Vol. IX. p. 167.—The charter is issued from **Mānagriha** (line 1). The inscription is one of the *Mahārāja*, the illustrious **Vasantasēna**.³ The *Dātaka* (l. 21) is the *Sarvadāndānyaka* and *Mahāpratīhāra* Ravigupta. The date (l. 20 f.) is (Gupta)-Samvat 435, Aśvayujī śukla-divā-1; answering, approximately, to the 23rd September, A.D. 754.

Q.—Mr. Bendall's inscription No. 4; *Journey in Nēpal*, p. 79 f. and Plate xi.—This is not a formal charter, issued from any specified place; nor does it give any king's name. It only records a grant by a private person to a *Pāñchaka* or Committee. The date (line 1) is (Harsha)-Samvat 151, Vaiśākha-śukla-dvitrīyāyām; answering, approximately, to the 8th April, A.D. 756.

R.—Dr. Bhagwanlal Indrajī's inscription No. 15; *Ind. Ant.* Vol. IX. p. 178 ff.—This is not a formal charter, issued from any specified place. The inscription, which gives a

¹ *Ind. Ant.* Vol. XVI. p. 23.

² See *id.* p. 19 f.

³ In inscription R. below, line 10, he is called Vasantadēva.

good deal of genealogical information, to be commented on below, is one of **Jayadēva II.** (line 14), who also had the second name or *biruda* of Parachakrakāma (l. 18). The object of it is to record that he caused a silver water-lily to be made, for the worship of Śiva under the name of Paśupati; and that it was worshipped and installed by his mother Vatsadēvi. The **date** (l. 35) is (Harsha)-Samvat 153, Kārttika-śukla-navamyām; answering, approximately, to the 16th October, A.D. 758.

S.—Dr. Bhāgwanlal Indrajī's inscription No. 4; *Ind. Ant.* Vol. IX. p. 168.—The commencement of the inscription, recording the place whence the order was issued and the king's name, is broken away and lost. And the inscription, therefore, is of importance only as indicating the period during which the era that is referred to in it, continued to be used. The *Dātaka* (line 17) is the *Rājaputra* Vikramasēna.¹ The **date** (l. 18) is (Gupta)-Samvat 535, Śrāvāṇa-śukla-divā-saptamyām; answering, approximately, to the 1st July, A.D. 854.

When Dr. Bhāgwanlal Indrajī summed up, according to his view of them, the historical results of his inscriptions, Mr. Bendall's inscription No. 1, A. above, was not known; and the only available clue was the mention, in B. C. E. F. and G., of Amśuvarman, who was evidently to be identified with the king of that name who was reigning during, or shortly before, Hiuen Tsiang's visit to Northern India, in or about A.D. 637. Acting on this identification, he very properly referred the dates of (C.) 34, (E.) 39, (F.) 44 or 45, (G.) 48, (L.) 119, (N.) 143 (?), (O.) 145, and (R.) 153, to the era dating from the commencement of the reign of Harshavardhana of Kanauj in A.D. 606 (or 607)

Mr. Bendall's discovery of the Gōlmāḍhiṭṭl inscription, furnished the key-note for the interpretation of the whole matter. For, mentioning Amśuvarman as the contemporary of Śivadēva I., and giving for the latter the date of the year 316, it shews that this date, and all belonging to the same uniform series, must be referred to an era commencing just about three centuries before the Harsha era; i. e. to the so-called Gupta era, with the epoch of A.D. 319-20; for then the year 316 + A.D. 319-20 = A.D. 635-36, which is in the closest possible accordance with the first recorded date of Amśuvarman, in A.D. 639.

But, when Dr. Bhāgwanlal Indrajī wrote, nothing was certain about the other larger dates of (K.) 386, (M.) 413, (P.) 435, and (S.) 535; except that all the circumstances of the case shewed that they were not of the same series with the smaller dates belonging to the Harsha era. And, after examining the theory of the Śaka era, commencing A.D. 78, and rejecting it on the grounds that even this was not early enough, Dr. Bhāgwanlal Indrajī finally referred them to the Vikrama era commencing B.C. 58.

Curiously enough, the Nēpāl *Vamśdvali* states that Vikramāditya came to Nēpāl, and established his era there. And, as we have seen at page 74 f. above, an offshoot of the Vikrama era certainly was introduced into Nēpāl in A.D. 880. But the statement of the *Vamśdvali* refers to the time of the predecessor of Amśuvarman; i. e. to the end of the

¹ See page 178 above, note 2.

sixth, or the beginning of the seventh, century A.D. And Dr. Bhagwanlal Indraji shewed¹ that the statement is certainly quite wrong as regards the name of the king and the particular era intended; and that what it probably contains, is a reminiscence of the conquest of the country by Harshavardhana of Kanauj, and the adoption of the Harsha era as the result. This statement, therefore, can have influenced him but little, if at all, in his assignment of the above-mentioned dates to the Vikrama era.

The real grounds for his doing so,—grounds which, in spite of the existence of the date of (Gupta)-Sārvvat 316 for Śivadēva I. and Amśuvarman, still require to be cleared away, in order that we may properly adjust the whole of the early chronology of Nēpāl,—are to be found in his erroneous treatment of R., the inscription of Jayadēva II. of (Harsha)-Sārvvat 153.

Starting with a mythological genealogy, this inscription carries the descent from the god Brahman (line 3), through Sūrya or the Sun,² Manu, Ikshvāku, and others, down to Raghu, Aja, and Daśaratha (l. 6). After Daśaratha, there were eight kings, in lineal succession of sons and sons' sons, who are passed over unnamed; and then there was the illustrious Lichchhavi (l. 6). Then comes verse 6, which records that "even still," at the time of the writing of the inscription, "there exists a family which bears the pure second name of Lichchhavi;"—svachchharṭ Lichchhavi-nāma vi(bi)hrad-āparam vañśaḥ, (l. 7). Dr. Bhagwanlal Indraji, in his lithograph, text, and translation, gave *aparḥ vañśaḥ* "a new race which bears the pure name Lichchhavi." But, on examining his original rubbing, I find that the real reading is *āparam (nāma)*, "another name, a second name;"—not *aparḥ (vañśaḥ)*, "another race, a new race." This verse, therefore, is of some interest, in shewing that,—in addition to the appellation of Lichchhavi or Lichchhavikula, the latter of which actually occurs in inscriptions A. B. and H. above,—the family had another original name, which, however, is not recorded. After Lichchhavi there came some kings, who again are passed over unnamed, and the number of whom is illegible³ at the end of line 7 and the beginning of line 8; and then the illustrious king Supuṣhpa (l. 8) was born at the city of Pushpapura.⁴ After him, "omitting in the interim (to mention the names of) twenty-three kings," there was another⁵ king, the famous

¹ *Ind. Ant.* Vol. XIII. p. 421 f.

² In accordance with this, the *Vamīdvali* enters the historical Lichchhavis of this inscription as members of a Sāryavamśi family.

³ But the number was probably twelve, as *hitv-ḍpa[rḍa-ḍvadaśa]* seems to suit best the metre and such traces as are discernible in the rubbing.

⁴ *i.e.* Pātāliputra, the modern Patna in Bihār; *Ind. Ant.* Vol. IX. p. 180, note 44.—This part of the inscription, therefore, relates to a period antecedent to the settlement of the Lichchhavis in Nēpāl.

⁵ As no previous Jayadēva. with whom this one could be contrasted, is mentioned in the inscriptions, *āparam* seems to introduce another branch of the Lichchhavi family, not directly descended from Lichchhavi and Supuṣhpa.

Jayadēva I. (l. 8), who was treated by Dr. Bhagwanlal Indraji as the first really historical member of the family, and the founder of the Nēpal branch of it,¹ and on the Vikrama-Samvat theory, was placed about A.D. 1. After this "victorious" Jayadēva I., and again "omitting in the interim (*to mention the names of*) eleven kings," the inscription gives the first unbroken succession of names that it contains; *vis.*—**Vṛishadēva** (l. 9);—his son, **Śamkaradēva**;—his son, **Dharmadēva**;—his son, **Mānadēva** (l. 10);—his son, **Mahidēva**;—and his son, **Vasantadēva**. The first four of these names have already been made known by inscription K. above; and the sixth, in the form of Vasanta-sēna, by inscription P. And these six kings plainly belong to the family, the genealogy of which forms the subject of all the preceding part of the inscription; *vis.* the Lichchhavikula.

Then follows, in lines 10 and 11, the eleventh verse, which was entirely misunderstood by Dr. Bhagwanlal Indraji, and which, through that misunderstanding, led to the erroneous reference of the larger dates of his inscriptions to the Vikrama era. He read this verse—*asy-āntarē-py-Udayadēva iti kshitiśāj-jātās-trayōdaśa [tata]ś-cha Narēndradēvaḥ mān-ōnnatō nata-samasta-narēndra-mauli-mālā-rajō-nikara-pāmsula-pādapiṭṭhah*; and translated—"afterwards came thirteen (*rulers*), sprung from king **Udayadēva** (l. 10),² and then **Narēndradēva** (l. 11), who was proud, and whose footstool was covered with the dust from the row of diadems worn by numerous prostrated kings." With the exception that the original has *pāmsula*, not *pāmsula*, the reading and translation of the second half of the verse represent the original correctly. It is the first half that has not been properly treated. In the first place, *asy-āntarē* does not mean 'afterwards,' or 'after him.' The literal meaning of *antara* is 'an interval;' and in *anantaram* it helps to make up the equivalent of 'afterwards,' only from its meaning in the first place 'no interval after.' But, standing without the negative particle, *antara* can have only the meaning of 'interval;' and it is used twice before by the composer of this inscription, in lines 8 and 9, distinctly in that sense. *Asy-āntarē* can only mean "in an interval of this;" and, supplying *vanśasya*, from the *vanśah* of line 7, in apposition with *asya*, we have "in an interval, *i.e.* at an intervening point, of this (*lineage that has just been detailed*)."³ The expression plainly introduces some names, in respect of which it is intended to be conveyed that they are of another family or branch; and that the last of them comes contemporaneously with or immediately after the name of Vasantadēva, the last mentioned of the immediately preceding succession, and the first comes at some unspecified point intervening between Vṛishadēva and Vasantadēva. In the second place. Dr. Bhagwanlal Indraji's reading of *kshitiśāj-jātās* cannot be maintained. In the two syllables *jjātās*, the rubbing shews distinctly the double *jj*, of which, in the lithograph, the lower one is only sketched in faintly, as if it were doubt-

¹ *Ind. Ant.* Vol. XIII. p. 424.

² Or, again,—"after him (Vasantadēva), followed thirteen, sprung from the lord of the earth called Udayadēva;" *Ind. Ant.* Vol. XIII. p. 425, note.

ful; but the second is as distinctly *ta*, not *tā*, as is in fact shewn in the lithograph. There is a slight abrasion mark between the *ta* and the following *akshara*, which does not appear in the lithograph; but the rubbing shews most distinctly that this mark is no remnant of a half-obiterated *ā*, and that the stroke for *ā*, for which in fact there is no room, never was engraved here. The reading of the original, in short, is *jātas*, the nominative singular; not *jātās*, the nominative plural. This is the first objection to the more serious error, the introduction of *trayōdaśa*, 'thirteen,' immediately after *jātas*. The second is, that, of the six following *aksharas* which are read *s-trayōdaśa* [*tata*], the only parts that can be pronounced with any certainty, are *s*, as part of the first, and, at the beginning of line 11, *da*, the third, which is well preserved and unmistakable. The others are hopelessly injured and unrecognisable; and,—with the exception that the first probably had a *t* below the *s*; and that the second looks more like *thā* (*tathā*), or *dā* (*tadd*), or *pō* (*tapō*), than *yō*,—it is quite impossible, even from the rubbing, to say what they may be. But the culminating and final objection to the reading of *trayōdaśa* [*tata*]*ś-cha* is, that, in the passage, as thus read, there is no such word as *vyatītya*, *vihāya*, *hivā*, or *tyaktvā*, "having passed over or omitted (*to mention the names of*)," which we have in lines 4, 6, 7, 8, and 9, where, in each case, a specified number of kings is passed over; and that the metre does not allow of our introducing any such word. The *lacuna* at the end of line 10 and the beginning of line 11 render it, as I said, impossible to decide what the original reading may have been. But the whole structure of the passage leaves no doubt whatever that the original contained nothing but an epithet, or perhaps two, of Narēndradēva; and that, so far from thirteen rulers having intervened between him and Udayadēva, he was the son of Udayadēva.

Narēndradēva's son was Śivadēva II. (line 12), who married Vatsadēvi, of the family of the Maukharis who abounded in strength of arm,¹ the daughter of the illustrious Bhōgavarman, and the daughter of the daughter of "the great" Ādityasēna, the lord of Magadha (l. 13). And their son was the Rāja, the illustrious Jayadēva II. (l. 14), also called Parachakrakāma (l. 18), whose wife was Rājyamati, of the family of king Bhagadatta or of the Bhagadatta kings (l. 16), the daughter of Harsha, king of Gauḍa, Ōdra: &c., and Kalinga, and Kōśala (l. 15). The rest of the inscription details the beauty of the silver water-lily which Jayadēva II. caused to be made, and how it was worshipped and installed by his mother Vatsadēvi; and then concludes with the date.

Dr. Bhagwanlal Indraji's acceptance of Udayadēva as the successor of Vasantadēva, and insertion of thirteen rulers between him and Narēndradēva, led of necessity to the reference of the dates for Mānadēva of (K.) 386 and (M.) 413, and for Vasantadēva of (P.) 435, to the Vikrama era. It is unnecessary to repeat his calculations in full. But, starting with fifteen names between Vasantadēva and Śivadēva II., or nineteen from Māna-

¹ The original has *dāt vā(bā)hu-va(bā)-ādhyā-Maukhari-kulā śrīvarma &c.*; not *kula-śrī-varma*, in composition, as in the published text.

déva to Śivadéva II. (both included), all of which denote "*generations of kings, not reigns of collaterals*,"¹ and taking twenty-one years as the smallest possible average for these generation-reigns, he found that no era later than the Vikrama era would meet the requirements of the case; and that that era would meet them. For, on the Vikrama-Samvat theory, Mánadeva's first date represented A.D. 329; the interval from this to A.D. 759, the date of Jayadéva II., was 430 years; and this, divided by nineteen gave about twenty-two years and three-quarters as the average for each generation-reign. This was all right enough from his point of view.

But let us now take the matter from the correct point of view; *vis.* that Udayadéva did not come after Vasantadéva. This frees us at once from the necessity, under which Dr. Bhagwanlal Indraji laboured, of forcing Vasantadéva and his ancestors back to such early times; and leaves us at liberty to follow the analogy of inscription A., and to refer his date and Mánadeva's to the Gupta era. The result is, that we have for Vasantaséna the date of (P.) A.D. 754, just synchronous with the dates of perhaps (O.) A.D. 750, and certainly (R.) A.D. 758, for Jayadéva II., exactly what inscription R. seeks to convey; and we have for Mánadeva, the grandfather of Vasantaséna, the dates of (K.) A.D. 705 and (M.) A.D. 732-33, just about one generation before Jayadéva II.'s father Śivadéva II., for whom we have the dates of (L.) A.D. 725 and probably (N.) A.D. 748 (?).

Here the question naturally suggests itself:—As Udayadéva and his descendants were not successors and descendants of Vasantaséna, who were they? I think the answer is perfectly plain:—That they were successors of Amśuvarman; and, though not his direct lineal descendants, belonged, like him, to the family which in the *Vamsāvali* is called the Thākuri family

Inscription R., in fact, furnishes another instance of the double government of Népāl, to which Dr. Bhagwanlal Indraji drew attention in the case of Śivadéva I. and Amśuvarman; and which is illustrated in the most pointed way throughout these inscriptions.* We have two separate families, ruling contemporaneously and mostly on equal terms, but each preserving certain distinctive characteristics of its own.

On the one side (see Table XI. page 189 below), we have the Lichchhavikulā of the inscriptions,—the Sūryavamsī family of the *Vamsāvali*,—issuing its charters from the house or palace called Mánagriha; and using the Gupta era. To this family belong inscriptions A. B. K. M. P. and S.; and it was represented in A.D. 635 by

¹ *Ind. Ant.* Vol. XIII. p. 425.

* So also in later times. See, for instance, the colophon of a manuscript of the *Aśvasāhasrīkī-Prajāpāramitā* (Bendall's *Catalogue of Buddhist MSS.* p. 4), dated in Népāl-Samvat 128 (A.D. 1007), which speaks of the double rule of Nirbhaya and Rudradéva; and another manuscript bearing the same title (*id.* p. 151), dated in Népāl-Samvat 135 (A.D. 1015), which speaks of the government being enjoyed, half by Bhōjadéva and Rudradéva, and half by LakshmiKamadéva.

TABLE XI.
List of the Early Rulers of Népál.

THE LICCHAVI OR SŪRYAVAMŚI FAMILY OF MĀNAGRĪHA.	THE TĪHĀKURĪ FAMILY OF KAILĀSAKŪTABHAVANA.	
	1. Jayadēva I.—About A.D. 330-355. 2. 3. 4. 5. 6. } Names not re- 7. } corded in the 8. } inscription. } A.D. 355-630. 9. 10. 11. 12.	
Śivadēva I., <i>Mahārāja</i> .—A.D. 635.	13. Vṛṣhadēva.—About A.D. 630-655.	Amśuvarman, <i>Mahāsamanā</i> , and afterwards <i>Mahārājādhirāja</i> .—A.D. 635, 639, 644, and 649 or 650.
Dhruvadēva, <i>Mahārāja</i> .—A.D. 653.	14. Śaṅkaradēva, son of preceding.—About A.D. 655-680.	Jishnugupta. — A.D. 653.
	15. Dharmadēva, son of preceding.—About A.D. 680-704	Udayadēva. — About A.D. 675-700.
	16. Mānadēva, son of preceding.—A.D. 705 and 732.	Narēndradēva, son of preceding. — About A.D. 700-724.
	17. Mahādēva, son of preceding.—About A.D. 733-753.	Śivadēva II., <i>Mahārājādhirāja</i> , son of preceding. — A.D. 725 and 748 (?).
	18. Vasantasēna, or Vasantadēva, <i>Mahārāja</i> , son of preceding.—A.D. 754.	Jayadēva II., <i>Rāja</i> , son of preceding.—A.D. 750 (?) and 758.

Śivadēva I., (in A.D. 653 by Dhruvadēva),¹ in A.D. 705 and 732-33 by Mānadēva, and in A.D. 754 by Vasantasēna or Vasantadēva.

And, on the other side, we have a family, the name of which is not given in the inscriptions hitherto brought to notice, but which in the *Vamsāvali* is called the Tīhākurī family; issuing its charters from the house or palace called Kailāsakūtabhavana; and using the Haraha era. To this family belong inscriptions C. D. E. F. G. H. I. J. L. N. O. Q. and R.; and it was represented in A.D. (635),² 639, 644, and 649 or 650, by Amśuvarman, in A.D. 653 by Jishnugupta. in A.D. 725 and 748 (?) by Śivadēva II., and in A.D. 750 (?) and 758 by Jayadēva II.

From the fact that each of the two families issued its charters from a palace, not a town, and the fact that all the inscriptions are either at Khātīmāṇḍu itself, or close in the neighbourhood, the two palaces of Mānagrīha and Kailāsakūtabhavana appear to

¹ From Jishnugupta's inscription, G.

² From inscription A of Śivadēva I.

have been in the immediate vicinity of each other, in different divisions of one and the same ancient capital. And, though the inscriptions give no specific information on this point, from the fact that the order of Amśuvarman, recorded in inscription E., is issued to the officials of the western province, and from the way in which, in inscription K., Mānadēva is described as marching to the east and reducing to obedience the rebellious *Sāmantas* there, and then returning to the west, it seems pretty clear that the Lichchhāvika or *Sūryavāhī* family had the government of the territory to the east of the capital; and the *Ṭhākuri* family, of the territory to the west of it.

Dr. Bhagwanlal Indrajī treated Amśuvarman as if he was at first the feudatory of Śivadēva I. There is, however, nothing in the inscriptions to support this. The inscriptions of Śivadēva I., it is true, record acts that were done by him "on the advice," or "at the request," of Amśuvarman; but this expression, though often used in respect of feudatories and officials, does not of necessity imply any state of subordination. And, whereas Śivadēva I. uses in respect of himself only the feudatory title of *Mahārāja*, in his own inscriptions he allots to Amśuvarman the equal title of *Mahāsāmanta*; not simply *Sāmanta*, as represented almost throughout by Dr. Bhagwanlal Indrajī. Śivadēva I. and Amśuvarman were only co-ordinate feudatories of a paramount sovereign, *vis.* Harshavardhana of Kanauj. During the time when Amśuvarman was a *Mahārājādhirāja* or paramount sovereign, as recorded in inscription G., the Lichchhavis must have been feudatory to him. This was after his inscription C. of A.D. 639. His other two inscriptions E. and F., which give him no titles except that of *śrī*, "the illustrious, or the glorious," perhaps belong to a transitional period, when he hesitated about adopting the paramount title, and yet was unwilling to use a feudatory title any longer. He probably assumed the paramount rank and title, on the death of Harshavardhana; when, as Matwan-lin tells us,¹ the kingdom of Kanauj fell into a state of anarchy, and the minister *Nāfo-ti-a-la-na-shun* usurped the supreme power. And Amśuvarman is probably the king of Nēpāl, who came with seven thousand horsemen to help the Chinese general Wang-hiwentse who defeated the usurper. In the time of Dhruvadēva and Jishnugupta, it is possible that the *Ṭhākuri* family may to a certain extent have acknowledged the Lichchhavis as superior to them. But Śivadēva II. again had the paramount title and rank; and the Lichchhavis were then, of course, again the feudatories of the *Ṭhākuri* family. Finally, the fact that the Lichchhavi genealogy is given in the *Ṭhākuri* inscription R., coupled with the use by Jayadēva II. in this inscription of no title but that of *Rāja* (line 14), with the epithet *śrī*, 'the illustrious,' may perhaps indicate that at this latter time the *Ṭhākuris* again acknowledged a certain amount of superiority on the part of the Lichchhavis. Or it may be nothing more than another expression of the mutual courtesy of the two families, already exhibited in the inscriptions of Śivadēva I. and Jishnugupta.

¹ *Ind. Ant.* Vol. IX. p. 20.

In the **Lichchhavi family**, the earliest name for which we have as yet a definite date, is that of **Śivadēva I.**, A.D. 635. And either Śivavṛiddhivarman, No. 14 in the *Vamśāvali* list of the Sūryavamśi family, or Śivavarman, No. 16 in the same, seems to be intended for him. The next name is that of **Dhruvadēva**, A.D. 653, who is not given or represented in the *Vamśāvali*. The connection between Śivadēva I. and Dhruvadēva, is not as yet explained. But they probably belonged both to one branch of the family; though, from their not being mentioned in inscription R., certainly not to the same branch with Vasantadēva and his ancestors. Their contemporaries of the Thākuri family were respectively Amśuvarman and Jishnugupta. They were followed by another branch of the same family, introduced about A.D. 630 (not A.D. 260, as proposed by Dr. Bhagwanlal Indraji) by **Vṛishadēva**, who was the contemporary of Śivadēva I.; and represented, as far as definite dates go, by **Mānadēva** in A.D. 705 and 732-33 (not A.D. 329 and 356), and by **Vasantasēna** or Vasantadēva in A.D. 754 (not A.D. 378). The six names from Vṛishadēva to Vasantasēna, are given correctly in the *Vamśāvali*, as Nos. 18 to 23 of the Sūryavamśi family. If inscription R. is to be accepted throughout, this branch of the family was founded by **Jayadēva I.** He is doubtless the person who is intended by Jayavarman, No. 3 in the *Vamśāvali* list of the Sūryavamśi family. And, calculating back fifteen generations, at the average rate of twenty-five years, from Mānadēva, whose generation is represented by his recorded dates, we have for Jayadēva I. the initial date of about A.D. 330 (not A.D. 1). But, if Vṛishadēva was a direct lineal descendant of Jayadēva I., it is rather peculiar that the composer of inscription R., writing only five generations after him, was unable to give the names of the persons, only eleven in number, who intervened before him and after Jayadēva I. It would seem, therefore, that, though the number of generations may be accepted, there was at this point a break in the direct succession.

In the **Thākuri family**, the earliest name is that of **Amśuvarman**, with the extreme dates of A.D. 635 and 649 or 650; and the next is that of **Jishnugupta**, A.D. 653. Amśuvarman is mentioned in the *Vamśāvali*, under exactly the same name, as the founder of the Thākuri family; but Jishnugupta's name is not given or represented. The connection between them is not as yet explained. They were followed by **Udayadēva** (about A.D. 675, not A.D. 400) and his descendants, who, from there being no mention of Amśuvarman and Jishnugupta in inscription R., plainly belonged to another branch of the family. Udayadēva was contemporaneous with Dharmadēva of the Lichchhavi family; he is not mentioned in the *Vamśāvali*, being certainly not the Udayadēvarman, No. 24 in the *Vamśāvali* list of the Sūryavamśi family. His son, **Narēndradēva**, is possibly the person intended by Narēndradēva, No. 7 in the *Vamśāvali* list of the Thākuri family. His son, **Śivadēva II.**, A.D. 725 and 748 (?), is not mentioned in the *Vamśāvali*. His son, **Jayadēva II.**, A.D. 750 (?) and 758, is possibly the person intended by Jayadēva, No. 11 in the *Vamśāvali* list of the Thākuri family.

into the next line; intermediate divisions, rendered unavoidable here and there by printing necessities have been made only where absolutely necessary for neatness in the arrangement of the Texts.

A double hyphen is used to separate words in a sentence, which in the original are written as one word, being joined together by the euphonic rules of *sandhi*. Where this double hyphen is used, it is to be understood that a final consonant, and the following initial vowel or consonant-and-vowel, are in the original expressed by one complex sign. Where it is not used, it is to be understood of the orthography of the original, that, according to the stage of the alphabet, the final consonant either has the modified broken form, which, in the oldest stages of the alphabet, was used to indicate a consonant with no vowel attached to it, or has the distinct sign of the *virāma* attached to it; and that the following initial vowel or consonant has its full initial form. In the transcription of ordinary texts, the double hyphen is probably unnecessary; except where there is the *sandhi* of final and initial vowels. But, in the transcription of epigraphical records, the use of this sign is unavoidable, for the purpose of indicating exactly the palæographical standard of the original texts.

The **avagraha**, or sign which indicates the elision of an initial *a*, is but rarely to be met with in inscriptions, and does not occur at all in the present series. Where it does occur, I find it most convenient to represent it by its own *Dēvanāgarī* sign.

So also, practice has shewn that it is more convenient to use the ordinary *Dēvanāgarī* marks of punctuation; than to substitute the English signs for them.

Ordinary brackets are used for corrections and doubtful points; and **square brackets**, for letters which are damaged and partially illegible in the original, or which, being wholly illegible, can be supplied with certainty. An asterisk attached to letters or marks of punctuation in square brackets, indicates that those letters or marks of punctuation were omitted altogether in the original. As a rule, it is more convenient to use the brackets, than to have recourse to footnotes; as the points to which attention is to be drawn, attract notice far more readily. But notes are given instead, when there would be so many brackets, close together, as to encumber the text and render it inconvenient to read. When any letters in the original are wholly illegible and cannot be supplied, they are represented, in metrical passages, by the sign for a long or a short syllable, as the case may be; and, in prose passages, by points, at the rate, usually, of two for each *akṣara* or syllable.

APPENDIX V.

System of Transliteration.

The system of transliteration followed in this volume, except in respect of modern Hindu personal names, in which absolute purism is undesirable, and in respect of a few Anglicised corruptions of names of places, sanctioned by long usage, is this —

Sanskrit.	Kanarese.	Transliteration.	Sanskrit.	Kanarese.	Transliteration.
अ	अ	a	ख	ख	ja
आ	आ	ā	घ	घ	jha
इ	इ	i	च	च	ña
ई	ई	ī	छ	छ	ṭha
उ	उ	u	ज	ज	ḍa
ऊ	ऊ	ū	झ	झ	ḍha
ए	ए	ri	ञ	ञ	pa
ऐ	ऐ	ṛi	ट	ट	ta
—	—	lṛi	ठ	ठ	tha
ए	ए	e	ड	ड	da
ऐ	ऐ	ai	ढ	ढ	dha
—	—	o	ण	ण	na
अं	अं	ō	त	त	pa
अः	अः	au	थ	थ	pha
<i>Visarga</i>	<i>Visarga</i>	ḥ	द	द	ba
<i>Jihvāntya, or</i>			ध	ध	bha
<i>old Visarga be-</i>			न	न	ma
<i>fore ॠ and ॡ</i>	—	h	प	प	ya
<i>Upadhāntya, or</i>			ब	ब	ra
<i>old Visarga be-</i>	—	ḥ	भ	भ	ra
<i>fore ॠ and ॡ</i>			म	म	la
<i>Anusvāra</i>	<i>Anusvāra</i>	ṁ	य	य	la
<i>Anundāhā</i>	—	ka	र	र	va
क	क	kha	ल	ल	śa
ख	ख	ga	व	व	sa
ग	ग	gha	श	श	ha
घ	घ	ṅa	स	स	
च	च	cha	ह	ह	
छ	छ	chha			

A single hyphen is used to separate words in composition, as far as it is desirable to divide them. It will readily be seen where the single hyphen is only used in the ordinary way, at the end of a line, as divided in the original Text, to indicate that the word runs

THE GUPTA INSCRIPTIONS.

TEXTS AND TRANSLATIONS.

No. I; PLATE I.

ALLAHABAD POSTHUMOUS STONE PILLAR INSCRIPTION OF SAMUDRAGUPTA.

THIS inscription appears to have been first brought to the notice of the public in 1834, when, in the *Journal of the Bengal Asiatic Society*, Vol. III. p. 118 ff., Captain A. Troyer published his reading of the text and a translation of it, accompanied by a lithograph (*id.* Plate vi.), which was reduced by Mr. James Prinsep from a copy commenced by a brother of Lieutenant T. S. Burt, of the Engineers, finished by a Munshi, and revised by Lieutenant Burt himself.—In the same volume, p. 257 ff., the Revd. Dr. W. H. Mill, working from the same lithograph, published a revised version of the text and translation; followed, at p. 339 ff., by a supplementary paper containing the first genealogical tree of the dynasty. His version, however, though it was an improvement on that of Captain Troyer, still fell very far short of exhibiting the original completely or accurately; especially in his failing, like Captain Troyer, to recognise that the inscription is a posthumous one; in his misreading lines 11 and 21, in such a way as to introduce into the translation and genealogical tree, without any foundation whatever in the original, the independent princess Samhārikā, with a daughter, name unknown, who was the wife of Samudragupta, other mothers-in-law of the same king, and a royal issue expected at the date of the inscription; and in his treatment of line 30, where, instead of *āchakshāna iva bhuvō bāhur-ayam-uchchhritāḥ stambhāḥ*, "this lofty column (*is*) as it were an arm of the earth, proclaiming (the fame of Samudragupta)," he read *rōma-charmanah ravi-bhuvō bāhur-ayam-uchchhritāḥ stambhāḥ*, and translated "of this child of the Sun, though clothed in hairy flesh, this lofty pillar is the arm," which led him to refer Samudragupta and his dynasty to the Solar Race, a mistake that sometimes seems to have been not even yet completely eradicated.—In 1837, in the same *Journal*, Vol. VI. p. 969 ff., Mr. James Prinsep gave a fresh and much improved lithograph of the inscription and its alphabet (*id.* Plate lv.), reduced from impressions on cloth and paper made by Captain Edward Smith, of the Engineers; and, with it, his own version of the text and translation.¹ His rendering of the inscription still failed to represent the original with any real approach to accuracy and completeness. But it was a very great improvement on the two versions that had preceded it; especially in avoiding the leading mistakes of Dr. Mill, pointed out above. And it has remained the standard version up to the present time; except that in 1872

¹ The translation is reprinted in Mr. Thomas' edition of Prinsep's *Essays on Indian Antiquities*. Vol. I. p. 233 ff.

in the *Journal of the Bombay Branch of the Royal Asiatic Society*, Vol. IX. p. cxvii. ff., Dr. Bhau Daji notified, from a copy on cloth made by Dr. Bhagwanlal Indrajī, some corrections in the historical part, in the names of the kings and countries conquered by Samudragupta.¹

The round monolith sandstone column, thirty-five feet in height, on which this inscription is, dates from the third century B.C., as is shewn by the famous edicts of Aśoka on it. It now stands in a conspicuous position inside the Fort at Allahābād (properly Ilahābād), the seat of Government of the North-West Provinces. It is doubtful, however, whether the column was originally erected at this place, or whether, as has been suggested by General Cunningham,² it was first set up at the ancient Kauśāmbī, now represented by the village of Kōsam³ on the left bank of the Jamnā, about twenty-eight miles west by south from Allahābād; and, being still at that place when the present inscription was engraved, was afterwards moved from there to Allahābād by one of the early Musalmān kings of Dehli, just as the two Aśoka columns now at Dehli were brought there from original positions at Mēraṭh and in the Siwālik hills. The points in favour of the latter supposition are (1) that the column contains a short Aśoka edict addressed to the rulers of Kauśāmbī,⁴ and (2) that the Chinese pilgrim Hiuen Tsiang makes no mention of this column in his account of *Po-lo-ye-kia*, i.e. Prayāga or Allahābād.⁵

The writing, which covers a space of about 6' 8" broad by 5' 4" high, commences on the north of the column, towards the north-east, and in the longest part, line 30, runs all round the column, except for a space of about 1' 9". The bottom line is about 6' 0" above the point where the column starts from its present pedestal. There is a large crack in the column, from above the first word of the first line, and extending down to the beginning of the fourteenth. And the upper part of the inscription has suffered very much, partly from some of the mediæval inscriptions, which are so abundant on the column, being engraved on and between the original lines here, and partly from the peeling off of the surface of the stone in several places. But nothing of a historical nature appears to have been lost; except, perhaps, after the mention of Nāgasēna in line 13, and in connection with the mention of Pushpapura in line 14. A few letters, again, have been damaged or destroyed by the peeling off of the stone near the beginning of line 23, and in the centre of lines 23, 24, 31, and 32; but, except in line 32, the letters can be supplied without any doubt. The really important part of the inscription, the historical and genealogical passages commencing with line 19 and ending in line 30, is fortunately in a state of

¹ This notice was published in 1872; but it was read before the Society two years earlier, on the 11th August 1870. It records that Dr. Bhau Daji submitted to the Society a revised facsimile, text, and translation, of the inscription; but they do not appear to have been ever published, or to be now forthcoming. His suggestions were perhaps more correct in his own notes, than in the form in which they stand printed in the Journal.

² *Corpus Inscriptionum Indicarum*, Vol. I. p. 39.

³ The 'Kosam and Kosim Kheraj' of maps; about eight miles to the south of Karārī, the chief town of the Karārī Parganā in the Manjhanpur or Mānjhandpur Tahsil or Sub-Division of the Allahābād District. Indian Atlas, Sheet No. 88. Lat. 25° 20' N.; Long. 81° 27' E.

⁴ *Corp. Inscr. Indic.* Vol. I. pp. 39, 126, 141, and Pl. xxii.; see also after the end of line 10 of the present inscription in the Plate now published.

⁵ Beal's *Buddhist Records of the Western World*, Vol. I. p. 230 ff.; Stanislas Julien's *Hiouen Tsiang*, Vol. II. p. 276 ff.—At the same time, it must be noted that Hiuen Tsiang also makes no mention of any such column in his immediately following account of *K'ien-shang-mi* or Kauśāmbī.

excellent preservation, and is decipherable without the slightest doubt from beginning to end.—The size of the letters (by which I mean, here and throughout, the height of such letters as *cha, da, pa, ma, ba, va, &c.*, which are formed entirely within the limits of, so to speak, the lines of writing, without any projections above or below) varies from $\frac{1}{16}$ " to $\frac{1}{4}$ ". As regards the palæography of this and the other inscriptions in the volume, this division of the subject is so extensive as to require a separate treatise to itself; and I cannot here do more than touch in a general way on such special points as call for particular notice. The characters of the present inscription belong to what it has been customary to call the Gupta Alphabet. This, however, like all other similar dynastic appellations, is an unsatisfactory and misleading term. In the first place, these characters were not confined to the inscriptions of the Early Gupta dynasty; for they were used, with slight modifications, but not such as to affect their essential nature, on the coins of the later Indo-Scythian kings of the Panjāb. Even in respect of a character of such leading importance as the letter *m*,—though some of these coins exhibit what is called the Indo-Scythic form,¹ in distinction from the *m* of the northern Gupta inscriptions. yet, on one coin which I had the advantage of examining in General Cunningham's collection, and which has on it the name of Samudra,² the *m* that is used is the so-called Gupta *m*, somewhat later than the *m* of the present inscription, but of exactly the same shape with the *m* of *mahārāja* in line 8 (to choose a clear example) of the Mathurā inscription of Chandragupta II., No. 4 below, Plate iiiA. And in the second place, the inscriptions of the Early Guptas themselves were by no means written exclusively in this alphabet. To say nothing of the frequent use of the Indo-Scythic *m* on Samudragupta's coins,—illustrated, for

¹Setting aside the few exceptional instances that we have of irregular usage, confined, I think, entirely to coins, this letter is in itself sufficient to shew, for the whole period covered by the inscriptions in this volume, whether the characters of a particular record belong to the northern or to the southern class of alphabets. The *m* of the Indo-Scythic inscriptions, a good representation of which may be seen in the word *mahārājasya* at the beginning of the Mathurā inscription of Huvishka of the year 39 (*Archæol. Surv. Ind.* Vol. III. Pl. xiv. No. 1), is simply a stiff angular development of the *m* of the Aśoka period. This particular form was not confined, however, to the Indo-Scythian records. We have it, in all its angularity, in the word *svāmi* in the Sāñchi pillar inscription, No. 73 below, Plate xliiA; and, with very little modification, in the early inscriptions from Nāsik and that neighbourhood published in the *Archæol. Surv. West. Ind.* Vol. IV. Plates xlv. ff. And in the slightly modified form, with simply the angles rounded off, which it must have had in the earliest stages of development of the southern alphabets, we have it throughout the Sāñchi inscription of Chandragupta II., No. 5 below, Plate iiiB., e.g. in *mahāvīhār*, line 1; the Gaṅgadhār inscription of Viśavavarma, No. 17 below, Plate x., e.g. in *apratimāna*, line 4; and the Mandasār inscription of Kumārāgupta and Bandhuvārman, No. 18 below, Plate xi., e.g. in *dhavanam-ida-m-udrān*, line 23. While, in a more modified form, which must have been of later development, though the instances in this volume happen to be of earlier date, we have it throughout the Ēraṅ inscription of Samudragupta, No. 2 below, Plate iiA., e.g. in *samara*, line 2; and throughout the Udayagiri cave inscription of Chandragupta II. of the year 82, No. 3 below, Plate iiB., e.g. in *mahārāja*, at the beginning of line 2.—The *m* of the inscription now under notice must also be simply a development of the Aśoka *m*, arrived at by forming the left part of the letter in a different way, viz. by one unbroken movement, leading gradually to its being separated entirely from the right part, which then eventually assumed a straight form, instead of curved. And, though the instances in this volume happen to be of later date, undoubtedly the form that we have in, for instance, *mahārāja*, in line 8 of the Mathurā inscription of Chandragupta II., No. 4 below, Plate iiiA., must have preceded the form used in the inscription now under notice.

²The three components of the name are written one above the other, inside the spear and under the left arm of the king, on the obverse; and they are practically identical with the components of the same name on the coin of Samudragupta given by Mr. V. A. Smith in *Jour. Beng. As. Soc.* Vol. LIII. Part I. Pl. ii. No. 6.

instance, by the coins given by Mr. V. A. Smith in the *Four. Beng. As. Soc. Vol. LIII. Part I. Plate ii. Nos. 3, 7, 9, 10, and 11*,—we meet with at least two perfectly distinct alphabets in their inscriptions, in addition to the one now under notice. The *Ēraṅ* inscription of Samudragupta, No. 2 below, Plate iiA., and the Udayagiri cave inscription of Chandragupta II. of the year 82, No. 3 below, Plate iiB., are in a 'box-headed' and 'nail-headed' variety of the Central India alphabet, which has hitherto been called the *Nerbudda Alphabet* and the *Vākātaka Alphabet*, and which, in addition to the very distinctive form of *m*, has all the leading characteristics of the southern alphabets. The *Sāñchi* inscription of Chandragupta II., again, No. 5 below, Plate iiiB., is distinctly in the characters of the southern alphabets. And the *Junāgaḍh* rock inscription of Skandagupta is in a somewhat later modification of the *Saurāshṭra* or *Kāthiāwāḍ* alphabet, exhibited with all its leading characteristics in the inscription of Rudradāman, on the same rock, of which we have a lithograph in the *Archaeol. Surv. West. Ind. Vol. II. p. 128, Plate xiv*. It is perfectly plain that the alphabets varied, not according to dynasties, but according to localities; and, in establishing any system of comparative palæography, we must select territorial, not dynastic, names. I would propose calling the alphabet of the inscription now under notice, the *general North India Alphabet* of the fourth century A.D. The characters include two letters which, after the Pāli period, lay for a long time in disuse in the southern alphabets, and were not revived for a considerable time after the present period; *viz.* the lingual *d*, as distinct from the dental *ḍ*, exhibited in *kṛīḍatā*, line 14, *ḍavḍka*, line 22, and *vṛīḍita*, line 27; and the lingual *ḍh*, exhibited in *virūḍha*, line 18. On the other hand, in the *l* which occurs in *vyḍhuḍita*, line 8, *kaurḍjaka* for *kairāḍjaka*, line 19, *saīmhaḍjaka*, line 23, and *laḍita*, lines 27 and 30, they include a letter which properly belongs exclusively to the southern alphabets and languages; and its occurrence here seems to furnish an unconscious piece of evidence to the effect that some, at least, of the conquests attributed to Samudragupta in the south of India, were actual facts; in the other inscriptions in this volume, this letter occurs only in the word *āḍi*, 'a bee,' in line 1 of the *Tuḍām* rock inscription, No. 67 below, Plate xlA. In *sḍbhā*, line 18, *viḍhnugḍpa*, line 19, and *gḍ-sata*, line 25, the vowel *ḍ* is formed in rather a peculiar way, which, so far as the right-hand stroke is concerned, is followed also in the vowel *ḍ* as attached to the same consonants, *e.g.* in *ḍāsana*, lines 23 and 24, and *gḍḍgām*, line 31. In respect of *r* in combination with a following *y*, we have to notice that, as in the case of other consonants, the *y* is doubled, and the *r* is written above the line, *e.g.* in *viryya*, line 13; whereas, in a somewhat later development of this alphabet in Central India, it became the custom, as in the case of *y* in conjunction with other letters, to write the *r* on the line, with a single *y* attached below it, *e.g.* in *marḍḍdayā*, line 6-7, and *kuryat*, line 12, of the *Majhgawān* plates of the *Mahārḍja* Hastin, No. 23 below, Plate xiv. The characters also include, in the numbering of the verses, forms of the **numerical symbols** for 3, 4, and 8; the intervening symbols are destroyed.—The **language** is Sanskrit; and the inscription is in verse as far as the end of line 16, and the rest in prose.—In respect of **orthography**, the only points that call for notice are (1) the doubling of *k*, in conjunction with a following *r*, *e.g.* in *parḍḍkrama*, line 17, *kkriyā*, lines 27 and 28, and *vikkrama*, line 30; (2) the doubling of *ḍh* (by *ḍ*, as required by the rules), in conjunction with a following *y* and *v*, in *aḍḍḍhya*, line 16, and *sḍḍḍhu-asḍḍhu*, line 25; and (3) the use of the southern *l*, in the instances pointed out a few lines above.

The inscription is non-sectarian, being devoted entirely to a recital of the glory, conquests, and descent, of the **Early Gupta** king **Samudragupta**. It is not dated; but, as it describes Samudragupta as deceased, it belongs to the time of his son and

successor **Chandragupta II.**, and must have been engraved soon after the accession of the latter. Its great value lies in the abundant information which, in the conquests attributed to **Samudragupta**, it gives us as to the divisions of India, its tribes, and its kings, about the middle of the fourth century A.D. This, however, is a subject for detailed treatment in the historical chapters which will form the second part of this volume.

In connection with **Samudragupta**, there is mentioned, in line 14, a city named **Pushpapura**, which is spoken of in such a way as to indicate apparently that it was his capital. **Pushpapura**, **Pushpapuri**, and **Kusumapura**, all meaning 'the town or city of flowers,' were names of **Pāṭaliputra**, which is now represented by the modern **Patna** in Bihār, on the Ganges; the original city, **Pāṭaliputra** itself, stood on the opposite south bank of the river, at the place where, in ancient times, the **Śoṇ** used to flow into it. The antiquity of the name **Kusumapura** is vouched for by **Hiuen Tsiang**,¹ who speaks of the city under both names,—*K'u-su-mo-pu-lo*, or *Keu-su-mo-pu-lo*, which he also explains by the Chinese *Hwa-kong* or *Hwa-kung*, 'flower-palace,' and *Hiang-hu-kong-sh'ing*, 'city or royal precinct of the scented flower;' and *Po-ch'a-Ji-tsu-ch'ing*, 'the city of **Pāṭaliputra**.' He tells us that **Kusumapura** was the more ancient name of the two. And, though I cannot find any early authority for it apart from the present passage, there is no reason for declining to think that the synonym **Pushpapura** was in use in early days, quite as much as it was at the time when the *Daśakumāracharita* and other books, which give us this form and **Pushpapuri**, were written. This passage, therefore, may furnish good grounds for locating **Samudragupta's** capital at **Pāṭaliputra**. At the same time, I have to draw attention to the following points, as requiring consideration in determining this question. (1) Until the time of **Skandagupta**, no inscriptions of this dynasty have been found anywhere in the neighbourhood of **Pāṭaliputra**.² (2) Though **Pāṭaliputra** is mentioned, under its own proper name, in two of the inscriptions³ of **Chandragupta II.**, yet neither of these passages connects the city with him, as his capital. And (3) **Hiuen Tsiang**⁴ mentions another ancient **Kusumapura**,—for which the synonym **Pushpapura** would be equally acceptable,—far distant, and quite distinct, from **Pāṭaliputra**. He tells us that the old capital of **Kanyākubja**, or **Kanauj**, was originally called **Kusumapura**. And, though he is not absolutely specific on the point, yet the way in which he describes how the town came to be invested with the name of **Kanyākubja**, seems to indicate that he understood **Kusumapura** to be the ancient name of the very site which, in his time, was called **Kanyākubja**. A capital here, or anywhere in this neighbourhood, would be far more in accordance with the localities at which all the earlier inscriptions of the dynasty exist; and still more so with the selection of a column either at **Allahābād** or at **Kauśāmbi**, to contain the record of the conquests of **Samudragupta**, by whom the power of the family was brought to maturity and was placed on an extensive footing. It is a matter for regret that the last *pāda* of the verse that mentions **Pushpapura**, is so hopelessly illegible; it evidently contained a reference to some river, which might have

¹ *Buddh. Rec. West. World*, Vol. II. p. 83 li.

² I exclude intentionally, of course, the spurious **Gayā** grant of **Samudragupta**, No. 60 below, Plate xxxvii.

³ The **Udayagiri** cave inscription, No. 6 below, Plate ivA. l. 4; and the **Gaḥwā** inscription of the year 88, No. 7, Plate ivB. l. 12.

⁴ *Buddh. Rec. West. World*, Vol. I. p. 207.

made the point quite clear. As it is, we must look for the clue in the identification of the **Kōta** family, tribe, or dynasty, which is mentioned in the same verse. But, for this name, I have not as yet succeeded in obtaining any other reference.

TEXT.¹

- 1 [Yah²] kulyaiḥ svai ātasa

 2 ya(?)sya(?)
 [11*] [1]
 3 Pu(?)mv
 tra
 4 sphā(?)ra-dva(?) kshaḥ sphuṭ-
 ḍḍhva[m]sita pravīta [11*] [2]
 5 Yasya³ prañi-ānushaṅg-ōchita-sukha-manasaḥ śāstra-tattv-ārtha-bhartuḥ [— —]
 stabdh-ō[— — — —]ni[— — — —]n-ōchchri[— — — —]
 6 [sa]t-kāvya-śrī-virōdhān-budha-guṇita-guṇ-āñi-āhatān-ēva kṛtvā v[i]dval-lōkē
 vi[— — —]sphuta-bahu-kavitā-kṛtti-rājyam bhunakti [11*] 3
 7 [Ā]ryyō⁴ h-lty-upaguhya bhāva-pisunair-utkarṇitai rōmabhiḥ sabhyēsh-
 ūchchvasitēshu tulyakulaja-mān-ānan-ōdykshī[ta]ḥ
 8 sa[ē]ha-vyālulitēna bāshpa-gurupā tattv-ēkshipā chakshushā yaḥ pitr-
 ābhīhitō ni[r]iksh[y]a nikhī[lān] pāhy-ēva[m]-[u]rv[ṣ]im-iti [11*] 4
 9 [Dṛi]shṭvā⁴ karmmāny-anēkāny-amanuja-sadṛisāny-adbhut-ōdbhinna-harshā
 bh[ā]vair-āsvādāya[— — — — —] [kē]chit
 10 vīry-ōttapātś-cha kēchich-chharaṇam-upagatā yasya vṛttē pranāmē-
 py-art[i]ḥ(?)[— — — — —] [11*] [5]
 11 Saṅgrāmēshu⁶ sva-bhuja-vijitā nityam-uchch-āpakārāḥ śvaḥ-śvō māna-
 pra[— — — — —]
 12 tōsh-ōttuṅgaiḥ sphuṭa-bahu-rasa-sneha-phullair-mmanōbhiḥ paśchāttāpam
 va[— — — — —]ma[m(?)] sy[ā]d-vasa(?)nta[m(?)] [11*] [6]
 13 Udvelī-ōdita-bāhu-vīrya-rabhasād-ēkēna yēna kshaṇād-unmūly-Āchryuta-
 Nāgasēna-g[— — — — —]
 14 daṇḍair-grāhayat-aiva Kōta-kula-jaṁ Puṣhp-āhvayē kṛtātā sūryē
 nē[— — — — —]taṭa[— — — — —] [11*] [7]
 15 Dharmma²-prāchhira-bandhaḥ śāsi-kara-suchayaḥ kṛttayāḥ sa-pratānā vaidu-
 shyam tattva-bhēdi praśama[— — — —]juku[—]y k[—]mu(?)t[—]t-ārtham(?)
 16 addhyēyāḥ śukta-mārggaḥ kavi-mati-vibhav-ōtsāraṇam ch-āpi kāvyam kō nu
 syād-yō-sya na syād-guṇa-mati-v[i]dushām dhyāna-pātram ya ēkaḥ [11*] 8
 17 Tasya vividha-samara-fat-āvatarāṇa-dakshasya sva-bhuja-bala-parākkram-aika-
 bandhōḥ parākkram-ānkasya paraśu-śara-śanhu-śakti-prās-āsi-tōmara-

¹ From the original column.

² The first four lines, containing the first two verses, are almost entirely destroyed; and the few letters that remain of them do not suffice to shew what the metres were.

³ Metre, Sragdharā.

⁴ Metre, Sragdharā.

⁵ Metre, Śārdūlavikṛḍita.

⁶ Metre, Śārdūlavikṛḍita.

⁷ Metre, Mandākrāntā.

⁸ Metre, Sragdharā.

- 18 bhindipāla-n[ā]rācha-vaitastik-ādy-anēka-praharāna-virūḍh-ākula-vraṇa-ṣat-āṅka-
śobhā-samuday-ōpachita-kāntatara-varshmanah
- 19 Kausalaka-Mahēndra-Māh[ā*]kāntāraka-Vyāghrarāja-Kaurājaka'-Maṅ-
ṭarāja-Paiṣṭapuraka-Mahēndra-giriKauṭṭūraka-Svāmidatt'-Airāṇḍa-
pallaka-Damana-Kāñchēyaka-Vishṇugōp-Āvamuktaka-
- 20 Nilarāja-Vaiṅgēyaka-Hastivarmma-Pālakkak-Ōgrasēna-Daivārāshtraka-
Kubēra-Kausthalapuraka-Dhanañjaya-prabhṛiti-sarvva-dakṣhiṇāpatha-
rāja-grahaṇa-mōksh-ānugraha-janita-pratāp-ōnmiśra-māhābhagyasya
- 21 Rudradēva-Matila-Nāgadatta-Chandravarmma-Gaṇapatināga-Nāgasēn-
Āchyuta-Nandi-Balavarmm-ādy-anēk-Āryyāvartta-rāja-prasabh-ōddharan-
ōdvṛitta-prabhāva-mahataḥ parichārakṛita-sarvv-ātavika-rājasya

¹ Read *kairāḷaka*, for which the word in the text is obviously a mistake.—The text, as it stands, would give "the country, or city, of Kurāḷa;" but, though *kurāḷa* occurs in the sense of 'a light bay horse with black legs,' it is not known as the name of a country or a city. *Kēraḷa*, on the other hand, is so well known as one of the countries in the south of India, that it would be strange if it were omitted in a passage like the present one; and it is easy to see how the engraver, or perhaps the writer from whose draft he engraved, formed *kaurājaka*, by mistake for *kairāḷaka*, through a stroke on the right of the top of the *k* in *kai* and of the *ra*.

² This is not altogether an easy passage to deal with. In the first instance,—coming immediately after the mention of the city of Piṣṭapura, which is the modern Piṭṭapuram (the 'Pittapooram' of the Indian Atlas, Sheet No. 94; Lat. 17° 6'; Long. 82° 18'), the chief town of the Piṭṭapuram Zamindār or Estate, twelve miles north by east of 'Cocanada' in the Gōḍavari District in the Madras Presidency,—the syllables *mahēndragiri* suggest at once a reference to the famous Mahēndra mountain in the Gañjām District, among the Eastern Ghats, the 'Mahendragiri' of maps (Indian Atlas, Sheet No. 108; Lat. 18° 58' N.; Long. 84° 26' E.), which is mentioned in other early inscriptions; for instance, as Mahēndrāchala, in lines 1 and 3 of the two 'Chicacole' grants of the *Mahārāja* Indravarma (Ind. Ant. Vol. XIII. pp. 120, 123). And this tempts us to divide the passage thus, *Paiṣṭapuraka-Mahēndragiri-Kauṭṭūraka-Svāmidatta*, and to translate "Svāmidatta of Piṣṭapura and of Koṭṭūra on Mahēndragiri."—Another rendering that might suggest itself is "Svāmidatta of Piṣṭapura, Mahēndragiri, and Koṭṭūra;" which, in fact, except in respect of his mistake of Kudura, for Koṭṭūra, was adopted by Dr. Bhu Daji (*Jour. Bo. Br. R. As. Soc.* Vol. IX. p. cxviii.) But this is not admissible, because it would require *mahēndragirika* in the text, instead of *mahēndragiri*; and, though it is possible to find the final *ka* in the text as it stands, yet this would give us as the next word, instead of Koṭṭūra (Koṭṭūr), which is a Drāviḍian name of frequent occurrence, Oṭṭūr, for which I can find no authority at all, or Hoṭṭūr (if we assume an omission of the initial *h*), which occurs, but not in connection with any place of importance.—If *mahēndragiri* is to be taken as one word, and as denoting the mountain, the translation that I have noted above is the one that must be adopted. And it might be supported by the fact that we have a Kottūr on almost the same range of hills as that to which the Mahēndragiri belongs; viz. the 'Kailaskotta and Kylascottah' of the map (Indian Atlas, Sheet No. 107; Lat. 19° 14'; Long. 83° 36' E.), which represents Kailāsa-Koṭṭa or Kailāsa-Koṭṭūr, and seems to be a place of importance.—But the objection to this interpretation is, that none of the other kings' names, mentioned in this inscription, are coupled with more than one locality. This leads us to connect Svāmidatta with Koṭṭūra only, and to find the name of another king in connection with Piṣṭapura.—The first inclination then might be, to divide the text thus, *Paiṣṭapuraka-Mahēndragiri-Kauṭṭūraka-Svāmidatta*; and to translate, "Mahēndragiri of Piṣṭapura, and Svāmidatta of Koṭṭūra." But, though *giri* or *gīr* is a very common termination of proper names in the present day, my experience is, that it is used only as a religious title, and is affixed only to the names of Gōsāvis; and even among them it would seem to be confined to one particular division of the Daśanāmi-Gōsāvis (see H. H. Wilson's Works, Rost's edition, Vol. I. p. 202; Molesworth's Marāṭh Dictionary, s. v. *gīr*; and Monier Williams' Sanskrit Dictionary, s. v. *giri*). I think, therefore, that, in the absence of any other analogous instance, it would in all probability be incorrect to accept it as a suitable termination for a king's name.—I accordingly divide this passage thus, *Paiṣṭapuraka-Mahēndra-giri-Kauṭṭūraka-Svāmidatta*; and translate, "Mahēndra of Piṣṭapura, and Svāmidatta of Koṭṭūra on the hill." And this *Giri-Koṭṭūra*, or "Kottūra on the hill," may either be found in the

- 30 bhavana-gaman-āvāpta-lalita-sukha-vicharāṇām-āchakṣhāṇa iva bhuvō bāhur-
 ayam-uchchhritāḥ stambhāḥ [1*] yasya 1¹ pradāna-bhujavikkrama-
 praśama-śāstravāky-ōdayair-uparyupari-sañchay-ōchchhritam-anēka-mārggah
 yaśah
- 31 punāti bhuvana-trayaṁ Paśupatēr-jjaṭ-āntar-guhā-nirōdha-parimōksha-śṭghram-iva
 pāṇḍu Gāngam p[ayah] [11] Ētach-cha kāvyam-ēśhām-ēva bhāṭṭāraka-
 pādānām dāsasya samlpa-parisarppaṇ-ānugrah-ōnmlita-matēḥ

the fourth century A.D. (2) that, in the well-known name of the Buddhist saint Upagupta (e.g. *Buddh. Rec. West. World*, Vol. I. p. 182; Vol. II. pp. 88, 93, 273), we have a precisely similar instance of a past participle, meaning 'hidden, concealed,' standing by itself as a proper name; as also, in its feminine form, Upaguptā, in line 5 of the Aśṭgadh seal of Śarvavarman, No. 47 below, Plate xxxA. (3) that, when *śrī* is an integral part of any proper name of importance, it was customary to emphasise it and prevent the possibility of doubt, by inserting the honorific prefix before it; thus, *mahādēvyām śrī-Srīmatyām-utpannah*, "begotten on the *Mahādēvi*, the glorious Śrīmat," in line 2 of the Dēś-Varaṇārī inscription of Jīvitagupta II., No. 46 below, Plate xxixB.; *śrī-Srīpathāyām puri*, "at the famous city of Śrīpathā," in verse in line 6 of the Byānā inscription of Vikrama-Saṁvat 1100 (*Ind. Ant.* Vol. XIV. p. 10); and *śrī-Srīpathāyām*, "at the famous Śrīpathā," in prose in the Byānā inscription of Vikrama-Saṁvat 1503 (*id.* Vol. XV. p. 239). The analogy would require here the reading of *mahārāja-śrī-Srīgupta-pīṣapaurasya*; which, however, does not once occur in the Early Gupta inscriptions. And (4) the word *gupta* does not appear at all in the name of Ghaṭōtkacha in the next generation; it is only in the case of his son, Chandragupta I., and the successors of the latter, that the word is of necessity only an integral part of a fuller name.—There is, therefore, no objection, but on the contrary every reason, to read the present name as simply Gupta.—The possibility remains, however, of its being an abbreviation of some fuller original name, other than Śrīgupta. And on this point I will produce here a note with which Dr. Bühler has favoured me:—"I should say the name of the founder of the family was Gupta, not Śrīgupta in the sense of *śrīyā guptāḥ* " (protected by the goddess Śrī). The name Rakshita occurs repeatedly among Brāhmins and Buddhists; "and means the same thing. The origin of such names as Datta, Gupta, Rakshita, &c." [the two first of these are well-known surnames in Bengal in the present day] "must, I think, be sought for in the habit of the Hindus of shortening their names by giving only the first part or the second. The former practice is alluded to by Kātyāyana, in a Vārttika on Pāṇini, vii. 3, 45, where he teaches that, when the "second part of a compound is left out, the *a* is to remain unchanged before the feminine termination " *ā*; thus, the feminine form of Dēvadattaka is Dēvadattikā; but, if Dēvaka is substituted for "Dēvadattaka, then the feminine is to be Dēvakā, not Dēvikā. The second shortening also is common; thus, we have *udbhī* for *mṛiganūbhī*, 'musk;' *idā* for *haritīdā*, a kind of tree; *vāllī* for " *khalvāllī*, 'the post of a threshing-floor;' and Bhāmā for Satyabhāmā, a proper name. From "these facts it would seem that Datta, Gupta, &c., are abbreviations of longer names."—The only epigraphical instance that I can quote, of the omission of the first part of a proper name, is the use of Śarman for Dhruvaśarman in line 11 of the Bilsāḍ inscription of Kumāragupta, No. 10 below, Plate v. But instances of the omission of the second part of a name are common enough. Thus, we have the use of Samudra on some of Samudragupta's gold coins, e.g. *Jour. Beng. As. Soc.* Vol. LIII. Part I. Pl. ii. Nos. 3, 4, 5, and p. 173;—of Chandra and Kumāra, for Chandragupta II. and Kumāragupta, in the same series;—of Vikrama and Mabēndra, for their full titles Vikramāditya and Mabēndraditya, illustrated partly in the same series, and partly in Kumāragupta's silver coins (*Ind. Ant.* Vol. XIV. p. 66);—of Śārdūla and Ananta, for Śārdūlavarman and Anantavarman, in the Barābar and Nāgarjunī Hill inscriptions, No. 48 below, Plate xxxB. ll. 1, 4, 5, and No. 49, Plate xxxiA. ll. 1, 8;—of Kākustha and Mṛigēśa for Kākusthavarman and Mṛigēśavarman in one of the Hālśī grants (*Ind. Ant.* Vol. VI. p. 28, ll. 3, 4);—of Harsha, for Harshavardhana of Kanauj, e.g. in the Kautshēm grant of Vikramāditya V. (*id.* Vol. XVI. p. 22, l. 26);—of Vikrama, for the Western Chālukya king Vikramāditya VI., e.g. in one of the Nārēgal inscriptions (*Jour. Bo. Br. R. As. Soc.* Vol. XI. p. 226, l. 24);—and of Padma and Sōrya, for Padmapāla and Sōryapāla, in the Gwālīor inscription of Mahāpāla (*Ind. Ant.* Vol. XV. p. 36 ff., ll. 1, 9, 22, 58.)

¹ This mark of punctuation is unnecessary.

9

-

h

h

h

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

- 32 Khādyatapakīkasya mahādāṇḍānyaka-Dhruvabhūti-putrasya sādihivigrahika-kumārāmātya-ma[hādāṇḍānyaka]-Harishēpasya sarva-bhūta-hita-sukhāy-āstu 1(II)
- 33 Anuṣṭhitam cha paramabhāṭṭāraka-pād-anudhyātēna mahādāṇḍānyaka-Tilabhāṭṭakēna 1(II)

TRANSLATION.

(Line 29).—This lofty column (*śū*) as it were an arm of the earth,¹ proclaiming the fame,—which, having pervaded the entire surface of the earth with (*its*) development that was caused by (*his*) conquest of the whole world, (*has departed*) hence (*and now*) experiences the sweet happiness attained by (*his*) having gone to the abode of (Indra) the lord of the gods,²—of the *Mahārājādhirāja*,³ the glorious⁴

¹ By taking an alternative meaning of *ucchhritak*, we might translate—"This column has been erected, as if it were an arm of the earth," &c. But this would include the assumption that the column had fallen, and was set up again in the time of Chandragupta II.; and in that case *śhūpīṣṭh* would have been a better word to use than *ucchhritak*, and the word would have stood better after, instead of before, *śambhah*. It seems best to adopt a translation that does not bind us to either view.—Prinsep considered it to be proved that the column had fallen, and was set up again expressly to display the present inscription. His grounds for this opinion (*Jour. Beng. As. Soc.* Vol. VI. p. 967 f.) are, that there are several names on it which he considered to be in characters of a type intermediate between those of the Aśoka and the Gupta inscriptions, and one of which, at least, it would have been exceedingly inconvenient, if not impossible, to have cut while the column was erect. But this particular name, with several of the others referred to by him, is in characters that are certainly of considerably later date than the Gupta inscription; and none of the names are in characters that are any earlier than the inscription.

² *i.e.* on his death.—Compare the expression in line 23 f. of the Kārdā grant of Kakka III. of Śaka-Samvat 894,—“and when (his) elder brother, the glorious Kṛṣṇnarājadeva, had ascended to the skies, as if from a desire to conquer the realm of Indra” (*Jour. Ant.* Vol. XII. pp. 265, 268); compare also line 14, verse 30, of the Gwālior inscription of Mahāpāla of Vikrama-Samvat 1150 (*id.* Vol. XV. pp. 37, 43).—Padmapāla, still a youth, through the adversity of fortune, obtained a seat [on the lap] of Saṅkrandana (Indra.)”

³ *Mahārājādhirāja*, *lit.* ‘supreme king of *Mahārājas*’ (see page 15 below, note 4), is one of the titles indicative of supreme paramount sovereignty, and is the only expression that properly and fully answers to our idea of a ‘king.’ I use it and all other technical titles and terms, without translation, because, if only for the sake of uniformity and convenience of comparison, it is much better to use them in this way, than to attempt to render them into English by expressions which must always vary according to the idiosyncracies of the translators, and which can never suffice to give exact and complete equivalents for the original titles.—The present title, *Mahārājādhirāja*, in somewhat later times, is almost always coupled with two others, *Paramēśvara*, ‘supreme lord,’ and *Paramabhāṭṭāraka*, ‘most worshipful one;’ *e.g.* in line 50 ff. of the Alīnā grant of Śīlāditya VII., No. 39 below, Plate xxv. And the connection of the three titles was so constant, that a Rīwā grant (unpublished) of Trailōkyamalla, dated Vikrama-Samvat 1297, considers it unnecessary to give all three titles in full, and contents itself with describing him as *paramabhāṭṭārak-śy-ādī-rājāval-tray-ōpāta*, ‘possessed of the three kingly titles (*lit.* succession) commencing with *Paramabhāṭṭāraka*.’—Other titles of paramount sovereignty, occurring in this series, are *Rājādhirāja* and *Chakravartin*.

⁴ *śrī*, ‘fortune, majesty, glory,’ and *śrīmat*, ‘possessed of fortune, majesty, glory,’ are words of constant occurrence as honorific prefixes to the names of persons, gods, places, &c. I render them by ‘glorious,’ in the case of paramount sovereigns and their wives; ‘illustrious,’ of feudatories and other ordinary persons; ‘saintly,’ of priests, teachers, &c.; ‘holy,’ of gods; and ‘famous,’ of towns, &c.—The usual rule seems to have been, to use *śrī* before a consonant, and *śrīmat* before a vowel; thus *śrīAmad-Indrabala-sāndr* *śrī-Naunadibhāgya tanaya-prōpāta* *śrī-Mahādīva-Tlovarājā*, in the Rājīm grant of the Rājā Tlovarādēva, No. 81 below, Plate xiv. l. 16 ff. But instances of deviation from this occur; thus, without *sandhi* or the euphonic joining of vowels, *śrī-Ādityasūadēva*, in the Shāhpur image inscription, No. 43 below, Plate xxixA. l. 2 l., and *śrī-Ādityasūadēvas* and *śrī-*

Samudragupta,¹—

(L. 1.)—[Who] by his own kinsmen
;—whose;—

(L. 3.)—[Who]
 twanging (of the bow-string) burst open and
 scattered dishevelled;—

(L. 5.)—Whose happy mind was accustomed to associate with learned people;—
 who was the supporter of the real truth of the scriptures; firmly fixed
; —who, having overwhelmed, with the (force of the) commands of the col-
 lective merits of (his) learned men, those things which obstruct the beauty of excellent
 poetry, (still) enjoys, in the world of the wise, the sovereignty of the fame (produced) by
 much poetry, and of clear meaning;—

(L. 7.)—Who, being looked at (with envy) by the faces, melancholy (through the
 rejection of themselves), of others of equal birth, while the attendants of the court breathed
 forth deep sighs (of happiness), was bidden by (his) father,—who, exclaiming “Verily
 (he is) worthy,” embraced (him) with the hairs of (his) body standing erect (through plea-
 sure) (and thus) indicati ot (his) sentiments, and scanned (him) with an eye turning

ljjdavyam, in the D66-*Baran* inscription of Jivitagupta II., No. 46 below, Plate xxixB., lines 2 f. and 5 f.; and, on the other hand, *paramahatfdraka-mahdrjddhiraja-parambvara-iramat-Suvarnavarshadva-prsthuvalabha-iramad-Vallobhanarendradva*, used in respect of the Rāsh-trakūta king Gōvinda V in his Sāhgll grant (*Ind. Ant.* Vol. XII. p. 251, l. 39 f.); and numerous other instances —It has been suggested that only *irī*, not *irīmat*, is used in the case of paramount sovereigns. But this is not the case. In addition to the passage noted above in connection with Gōvinda V., we have *parambvara-iramad-Avantivarman*, in the D66-*Baran* inscription, l. 15; *iramad-Ādityavarma-prsthuvalabha-mahdrjddhiraja-parambvara*, applied to the Western Chalukya king Ādityavarman in his Karṇūl grant (*Jour. Bo. Br. R. As. Soc.* Vol. XVI. p. 234, l. 12 f.); *paramahatfdraka-mahdrjddhiraja-parambvara-iramad-Dhārdvarshadva*, applied to the Rāsh-trakūta king Dhruva, in the Waṇi grant of Gōvinda III. (*Ind. Ant.* Vol. XI. p. 159, l. 33 f.); *iramad-Amoghavarsha-Nripatunga*, used of king Amoghavarsha I. of the same dynasty, in his Sirūr inscription (*id.* Vol. XII. p. 219, l. 16); *iramad-Vikramāditya-iramat-Tribhuvanamalladva*, used of the Western Chālukya king Vikramāditya V., in his Kauthētīn grant (*id.* Vol. XVI. p. 24, l. 73); and many other examples of the same usage.

¹As regards the termination *gupta*, the *Vishnu-Purāna*, Book iii. Chap. 10, verse 9, says—“(The termination) *īarman* is prescribed for a Brāhmaṇ; *varman* belongs to a Kshatriya; (and) a name characterised by *gupta* or *dśsa* is approved of in the case of (respectively) a Vaiśya and a Śūdra.” The commentary in the Bombay edition gives, as examples, Sōmasārman, Indravarman, Chandragupta, and Śivadāsa. (See also F. E. Hall’s edition of H. H. Wilson’s Translation, Vol. III. p. 99 f.)—So also in the *Mānavadharmasūtra*, ii. 31 (Burnell’s Translation, p. 20), a rule of the same tendency is laid down, though without specifying any particular terminations.—On this authority, it has been suggested that the Early Guptas were not of high rank, being at the best of the Vaiśya caste; and that this is the reason why they felt such pride in their alliance with the Lichchhavis, as shewn by the record of the name of Kumārādēvī and of her family on some of the gold coins of Chandragupta I., and by the epithet, “daughter’s son of Lichchhavi (or of a Lichchhavi king),” that is always applied to Samudragupta in the genealogical passages.—No doubt some such rules as those prescribed by the *Vishnu-Purāna* and *Mānavadharmasūtra*, were followed more or less in early times. But, as instances of deviation from them, we have the name of the well-known astronomer Brahmagupta, who it can hardly be doubted was a Brāhmaṇ; and Dāsarvarman occurs, as the name of a Brāhmaṇ, in line 36 of the Nerūr grant of Vijayāditya, dated Śaka-Samvat 627 (*Ind. Ans.* Vol. IX. p. 131; *Indian Inscriptions*, No. 20); and doubtless numerous similar instances might be found, if proper indexes were available.

round and round in affection, (*and*) laden with tears (*of joy*), (*and*) perceptive of (*his noble*) nature,—[to govern of a surety] the whole world;¹—

(L. 9.)—Whose some people (*were accustomed to*) taste with affection, displaying exceeding great joy when they beheld (*his*) many actions that resembled nothing of a mortal nature; (*and*) whose protection other people, afflicted by (*his*) prowess, sought, performing obeisance,;—

(L. 11.)—[Whose] doers of great wrong, always conquered by his arm in battle, to-morrow and to-morrow pride
. repentance, with minds filled with contentment (*and*) expanding with much clearly displayed pleasure and affection, the spring (?);—

(L. 13.)—By whom,—having, unassisted, with the force of the prowess of (*his*) arm that rose up so as to pass all bounds, uprooted **Achyuta** and **Nâgasêna**
.—(*by whom*), causing him who was born in the family of the **Kôtas** to be captured by (*his*) armies, (*and*) taking his pleasure at (*the city*) that had the name of **Pushpa**, while the sun the banks;—

(L. 15.)—(*Of whom it used to be said*),—"The building of the pale of religion; fame as white as the rays of the moon, (*and*) spreading far and wide wisdom that pierced the essential nature of things; calmness; the path of the sacred hymns, that is worthy to be studied; and even poetry, which gives fre- vent to the power of the mind of poets; (*all these are his*); (*in short*) what (*virtue*) is here that does not belong to him, who alone is a worthy subject of contemplation for those who can recognise merit and intellect?";—

(L. 17.)—Who was skilful in engaging in a hundred battles of various kinds;²—whose only ally was the prowess of the strength of his own arm;—who was noted for prowess;³—whose most charming body was covered over with all the beauty of the marks of a hundred confused wounds, caused by the blows of battle-axes, arrows, spears, pikes, barbed darts, swords, lances, javelins for throwing, iron arrows, *vaitastikas*,⁴ and many other (*weapons*);—

(L. 19.)—Whose great good fortune was mixed with, so as to be increased by (*his*) glory produced by the favour shewn in capturing and then liberating **Mahendra** of

¹This verse seems to indicate that Chandragupta I. specially selected Samudragupta, from among several brothers, to conquer the land and to succeed him on the throne.—A clear indication of some such custom of selection is afforded by the epithet *tat-parigrihita*, "accepted (as his favourite son and chosen successor) by him (Samudragupta)," which is always applied to Chandragupta II. in the genealogical passages; e.g. in line 9-10 of his Mathurâ inscription, No. 4 below, Plate IIIA.—And, that occasionally the widow of a deceased king selected his successor, is perhaps indicated by the way in which, in one of the Nêpâl inscriptions (*Ind. Ant.* Vol. IX. pp. 164, l. 18 ff. and 165, v. 8 ff.), Râjyavati, the widow of Dharmadêva, is described as bewailing the uselessness of her own life after her husband's death, and as directing her son, Mânadêva, to reign, that she may follow her deceased lord.

²With this expression, compare the legend on some of Samudragupta's gold coins,—*Samara-sata-vitata-vijayâ jita* *dêvâ jayati*; see, for instance, *Jour. Beng. As. Soc.* Vol. LIII. Part I. Pl. II. Nos. 3, 4, 5.

³With this expression and the preceding, compare the word *parâdramakâ*, 'prowess,' on the reverse of the coins referred to in the preceding note.

⁴This word is not explained in the dictionaries. It must be a derivative from *vitasti*, 'a long span, measured by the extended thumb and little finger.'

Kósala, Vyāghrarāja of Mahākāntāra, Maṅṭarāja of Kēraja,¹ Mahēndra of Pīṣṭapūra² Svāmīdatta of Kōṭṭāra on the hill,³ Damana of Ēraṇḍapalla, Vīahṇugōpa of Kāñchi, Nīlarāja of Avamukta, Hastivarman of Veṅgi, Ugrasēna of Palakka,⁴ Kubēra of Dēvarāshtra, Dhanamjaya of Kusthalapūra, and all the other kings of the region of the south;⁵—

(L. 21.)—Who abounded in majesty that had been increased by violently exterminating Rudradēva, Matīla, Nāgadatta, Chandrarvarman, Gaṇapatīnāga, Nāgasēna, Achyuta, Nandin, Balavarman, and many other kings of (the land of) Āryāvarta;⁶—who made all the kings of the forest countries⁷ to become (*hīn*) servants;—

¹ See page 7 above, note 1.

² and ³ See page 7 above, note 2.—As regards the introduction of the mountain Mahēndragiri in this passage, Gen. Cunningham (*Archaeol. Surv. Ind.* Vol. IX. p. 10) accepted it, and identified the mountain with the conical hill close to Mahiyar (the 'Maihar, Meyhar, Meyhere, Myhere, and Myhir,' of maps, &c.; Lat. 24° 16' N.; Long. 80° 47' E.), the chief town of the Mahiyar State, a little to the south of Uchaharā, in the Baghēlkhaṇḍ division of Central India. Mahiyar may perhaps be derived from Mahēndragiri; but, under any circumstances, this identification cannot be upheld.

⁴ Or perhaps Pālakka, with the long vowel *ā* in the first syllable.

⁵ *dakṣiṇpātha*, *lit.* 'the path or road of the south; the southern road,' was the technical expression for Southern India.—The analogous technical expression for Northern India was *uttarapātha*, *lit.* 'the path or road of the north; the northern road.' It does not occur in the present series. But it is of constant use in connection with the great king Harshavardhana of Kanauj, e.g. *samarasasakta-sakalottarapāthēvara-ivā-Harshavardhana*, 'the glorious Harshavardhana, the warlike lord of all the region of the north,' in line 8 of the Nerūr grant of the Western Chalukya king Vijayāditya, dated Śaka-Samvat 622 (*Ind. Ant.* Vol. IX. p. 127); and, in line 20 f. of the same grant, it is contrasted with the *dakṣiṇpātha*, which is there mentioned under the synonym of *dakṣiṇidēś*, 'the southern quarter or region.'—A perhaps better known name of Northern India is Āryāvarta, 'the abode of the Āryas, or excellent or noble people,' which occurs in line 21 of the present inscription.—In the *Mānavadharmasūtra*, ii. 22 (Burnell's Translation, p. 18) Āryāvarta is defined as the land between the Himālaya and Vindhya mountains, extending to the eastern and to the western sea. But a more precise division between the *uttarapātha* and the *dakṣiṇpātha* is given by the poet Rājasekhara, who, in the *Bālarāmāyana*, Act 6 (see V. Sh. Apte's *Rājasekhara: his Life and Writings*, p. 21), speaks of the river Narmadā (the 'Nerbudda'), which rises in, and runs along close to the south of, the Vindhya range, as "the dividing-line of Āryāvarta and the *dakṣiṇpātha*."

⁶ *i.e.* "of northern India;" see the preceding note.

⁷ Compare the passage in line 8 f. of the Khōh grant of the Mahārāja Saṅkshobha, No. 25 below, Pl. xvB, describing his ancestor Hastin as ruling over his hereditary kingdom of Dabhāll, together with the eighteen forest kingdoms.—I have not been able to trace any definition of the terms *āvanīka-rāja*, 'forest-kings' or 'kings of forest countries,' and *āvat-rājya*, 'forest-kingdoms'; much less to obtain any enumeration of the eighteen forest-kingdoms referred to in connection with the Mahārāja Hastin. But Hastin's territories lay in the direction of Bundēlkhaṇḍ, Baghēlkhaṇḍ, Rīwā, and other neighbouring parts of the Vindhya range. And I notice that the term *ṅīndhy-ḍpav*, 'the forests of the Vindhya mountains' (which are so often referred to in one of the customary imprecatory verses used in inscriptions), is given by Monier Williams, in his Sanskrit Dictionary as seeming to have denoted originally the whole extent of country from near Mathurā to the Narmadā. This area corresponds pretty closely with the modern term Central India; and the separate divisions of it would be very suitably represented by the general term 'forest-countries' or 'forest-kingdoms.'—Somewhat similar terms, *vana-rāshtra*, 'forest-countries,' and *vana-rājya*, 'forest-kingdoms,' occur in the *Bṛīkaṭ-Samhitā*, xiv. cv. 29, 30. But the countries there spoken of, lay in the north-east division of India, as mapped out by Varahamihira; and they are, at any rate, not the countries referred to in connection with the Mahārāja Hastin.

(L. 22.)—Whose imperious commands were fully gratified, by giving all (*kinds of*) taxes and obeying (*his*) orders and coming to perform obeisance, by the frontier-kings¹ of Samatata, Davāka, Kāmarūpa, Nēpāla, Karttipura, and other (*countries*), and by the Mālavas, Ārjunāyanas, Yaudhēyas, Mādrakas, Abhiras, Prārjunas, Sanakānikas,² Kākas, Kharaparikas, and other (*tribes*);—

(L. 23.)—Whose tranquil fame, pervading the whole world, was generated by establishing (*again*) many royal families, fallen and deprived of sovereignty;—whose binding together of the (*whole*) world, by means of the amplitude of the vigour of (*his*) arm, was effected by the acts of respectful service, such as offering themselves as sacrifices, bringing presents of maidens, (*giving*) Garuda-tokens,³ (*surrendering*) the enjoyment of their own territories, soliciting (*his*) commands, &c., (*rendered*) by the Daivaputras, Shāhis, Shāhānushāhis, Śakas, and Muruṇḍas, and by the people of Sindhāla and all (*other*) dwellers in islands;—who had no antagonist (*of equal power*) in the world;⁴—who, by the overflow of the multitude of (*his*) various virtues adorned by a hundred good actions, rubbed out the fame of other kings with the soles of (*his*) feet;—who, being incomprehensible, was the spirit that was the cause of the production of good and the destruction of evil;—who, being full of compassion, had a tender heart that could be won over simply by devotion and obeisance;—who was the giver of many hundreds of thousands of cows;—

(L. 26.)—Whose mind busied itself with the support and the initiation, &c., of the miserable, the poor, the helpless, and the afflicted;—who was the glorified personification of kindness to mankind;—who was equal to (the gods) Dhanada and Varuṇa and Indra and Antaka;⁵—whose officers were always employed in restoring the wealth of the various kings who had been conquered by the strength of his arms;—

(L. 27.)—Who put to shame (Kaśyapa) the preceptor of (Indra) the lord of the gods, and Tumburu and Nārada, and others, by (*his*) sharp and polished intellect and

¹ *pratyanta-nripātī*.—This may denote either the kings within the frontiers of Samatata and the following countries, i.e. the 'neighbouring kings' of those countries, or the kings or chieftains just outside the frontiers of them. Upon the interpretation that is accepted, will depend the question whether Samudragupta's empire included those countries, or whether it only extended up to, and was bounded by, their frontiers.

² See page 8 above, note 1.

³ *garuṣṭmad-anka*.—Whether the bird be Garuda or not, we have here, I consider, a distinct allusion to the 'bird-standard' on some of the coins of Samudragupta and his successors; see, for instance, the coins given by Mr. V. A. Smith in the *Four. Beng. As. Soc. Vol. LIII. Part I. Plate II. Nos. 3, 4, 5, 14, Plate III. Nos. 1, 2, 3, 9, 10, 11, Plate IV. Nos. 4, 5, 7*; see also *id.* p. 131 f., and *Ind. Ant. Vol. XIV. pp. 93, 179*.—*garuṣṭmat* is explained in dictionaries as meaning 'a bird in general,' as well as denoting 'the bird Garuda.' But its most usual and special signification is 'Garuda,' as, for instance, in line 7 of the Rājim grant of the Rājā Tīvarādēva, No. 81 below, Plate XIV.

⁴ Three of the habitual expressions of the Early Gupta records, applied always and only to Samudragupta,—*vis.* the present one; "who was equal to (the gods) Dhanada and Varuṇa and Indra and Antaka," which we have here in line 26; and "whose fame was tasted by the waters of the four oceans," which occurs, for instance, in line 1 of the Bhitārī pillar inscription of Skandagupta, No. 13 below, Plate VII,—are applied, curiously enough, to the Chalukya chieftain Vijayarāja of Gujārāt, in line 5 f. of his Kaira grant of the year 394 (*Ind. Ant. Vol. VII. p. 248*). The only difference is that, in the second epithet, the reading there is *sama-prabhūva*, instead of simply *sama*.—Of the present epithet, the latter part, *apratirakta*, was used on some of Samudragupta's coins; e.g. *Four. Beng. As. Soc. Vol. LIII. Part I. Pl. II. No. 6*.

⁵ See the preceding note.

choral skill and musical accomplishments;—who established (*his*) title of 'king of poets' by various poetical compositions that were fit to be the means of subsistence of learned people;—whose many wonderful and noble deeds are worthy to be praised for a very long time;—

(L. 28.)—Who was a mortal only in celebrating the rites of the observances of mankind, (*but was otherwise*) a god, dwelling on the earth;—who was the son of the son's son¹ of the *Mahārāja*,² the illustrious Gupta;—who was the son's son of the

¹ Nārada is regarded as the inventor of the *veṅa* or lute; and, with this reference to him and to the musical accomplishments of Samudragupta, we have to compare the coins of the 'lyrist type' (see, for instance, *Four. Beng. As. Soc.* Vol. LIII. Part I. Pl. ii. Nos. 7, 8), which represent Samudragupta playing the lute.

² Compare lines 6 and 16 of this inscription.—The title *Avarāja*, 'king of poets,' answering somewhat to our 'poet laureate,' is still in use in Native States.

³ The English terms 'grandson' and 'great-grandson' are applicable to female as well as male descent, and are therefore not suitable for use in translations from the Sanskrit. The Hindus were almost always most careful about using properly discriminating terms, e.g. *pañtra* for a grandson through a son, and *dauhitṛa* for a grandson through a daughter; the status of the two lines of descent differed even more than in European countries; and, in translating, it is necessary to preserve the distinction accurately.—I will quote an instance in proof. In translating line 12 f. of No. 15 of his Nēpal inscriptions, Dr. Bhāgwānlal Indrajī (*Ind. Ant.* Vol. IX. p. 181) spoke of "Vatsadēvi . . . the daughter of illustrious Bhōgavarman . . . and the grand-daughter of great Ādityasēna, the illustrious lord of Magadha." From this, Gen. Cunningham (*Archaeol. Surv. Ind.* Vol. XV. p. 163) naturally enough treated Bhōgavarman, who belonged really to the Maukhari family, as a son, instead of a son-in-law, of Ādityasēna. This mistake could not have occurred, if *dauhitṛi* had been properly rendered by 'daughter's daughter,' instead of vaguely 'grand-daughter.'—The words that are fairly translatable by 'grandson' and 'great-grandson' are *naptri* and *pranaptri*. They both occur in the grants of the *Mahārājas* Hastin and Saṅkshobha, Nos. 21 to 23 and 25 below; and *naptri* occurs in line 5 of the Bhumā.ā pillar inscription, No. 24 below, Pl. xvA. But the use of them is rare.

⁴ *Mahārāja*, *lit.* 'great king,' appears to have been, in somewhat earlier times, one of the titles of paramount sovereignty. Thus, it is used, by itself, by Kanishka, Huvishka, and Vāsudēva, who, there is every reason to believe, were paramount sovereigns, in their inscriptions of the years 9, 39, and 83 (*Archaeol. Surv. Ind.* Vol. III. p. 31, Pl. xiii. No. 4; p. 32, Pl. xiv. No. 9; and p. 34, Pl. xv. No. 16); and, in conjunction with the higher title of *Rājātīrāja*, 'superior king of kings,' by the same three kings in their inscriptions of the years 11, 47, and 87 (*Ind. Ant.* Vol. X. p. 326; *Archaeol. Surv. Ind.* Vol. III. p. 33, Pl. xiv. No. 12, and p. 35, Pl. xv. No. 18). So also, in conjunction sometimes with the same word and sometimes with *Rājārāja*, 'king of kings,' the two together representing the Greek *basileus basileon*, it was used, in Prakrit, on the bilingual coins of earlier date; e.g. in conjunction with *Rājātīrāja*, on the coins of Hemokadphises (Gardner and Poole's *Catalogue of Coins of the Greek and Scythic Kings of Bactria and India*, p. 124 ff.), and, in conjunction with *Rājārāja*, on the coins of Ases (*id.* p. 73 ff.). And, before then, it was used by itself, to represent the Greek *basileus*, at a time when apparently the fuller title of *basileus basileon* had not been introduced; e.g. on the coins of Hermæus (*id.* p. 62 ff.).—But, in the Early Gupta and subsequent periods, *Mahārāja* was habitually used simply as a technical official title, indicative no doubt of considerable rank and power, but applied only to feudatories, not to paramount sovereigns.—From the way in which the two titles are applied uniformly to Samudrasēna and his ancestors in the Nirmaḅ grant, No. 80 below, Plate xlv., the title *Mahāsāmānta*, *lit.* 'great chief of a district,' appears to have been exactly co-ordinate with that of *Mahārāja*.—A third title, *Mahāsēnāpati*, *lit.* 'great lord of the army,' seems to have denoted equal rank with these two; since it is coupled with *Mahārāja* in the fragmentary Bijayagadh inscription of the Yaundhēyas, No. 58 below, Plate xxxviB., and also in the Wallā clay seal of Pushyēna (*Ind. Ant.* Vol. XII. p. 274 f.).—And three other offices, *viz.* those of *Mahāprasthāra*, *Mahādāndyaka*, and *Mahāhārtihritika*, would seem to have been sometimes held by *Mahārājas* and *Mahāsāmāntas*; since we find all five titles applied to Dhruvasēna I. of Valabhī in line 13 f. of the Wallā grant of Gupta-Samvat 216 (*Ind. Ant.* Vol. IV. p. 105).

⁵ As regards this name, see page 8 above, note 3.

Mahārāja, the illustrious *Ghaṭōtkacha*;—who was the son of the *Mahārājādhirāja*, the glorious *Chandragupta* (I.), (*and*) the daughter's son of *Lichchhavi*,¹ begotten on the *Mahādēvi*² *Kumārādēvi*;—

(L. 30.)—(*And*) whose fame,—ever heaped up higher and higher by the development of (*his*) liberality and prowess of arm and composure and (*study of*) the precepts of the scriptures,—travelling by many paths, purifies the three worlds, as if it were the pale yellow water of (the river) *Gangā*, flowing quickly on being liberated from confinement in the thickets of the matted hair of (the god) *Paśupati*.³

(L. 31.)—And this poetical composition,—(*the work*) of the *Khādyatāpākika*,⁴ the son of the *Mahādandanāyaka*⁵ *Dhruvabhūti*, the *Sāmdhivigrahika*⁶ and *Kumārādēvi*,⁷ the *Mahādandanāyaka* *Harishēna*, who is the slave of these same feet of the

¹ Or "of a *Lichchhavi* (king)."—The present is the more usual form of the name. But the variant *Lichchhivi*, with the vowel *i* instead of *a* in the second syllable, occurs in line 3 of the *Bhitari* pillar inscription of *Skandagupta*, No. 13 below, Plate vi.; in line 5 of the spurious *Gayā* grant of *Samudragupta*, No. 60 below, Plate xxxvii.; and in the *Mānavadharmasāstra*, x. 22 (Burnell's Translation, p. 308), where a *Lichchhivi*, with others, is defined as the offspring of a degraded member of the *Kshatriya* caste.

² *Mahādēvi*, lit. 'great goddess,' appears to have been always a technical title of the wives of paramount sovereigns; though, in somewhat later times than that of the present inscription, it was also sometimes applied to the wives of *Mahārājas*, e.g. throughout the *Kārttalā* grant of *Jayanātha*, No. 26 below, Plate xvi.—As applied to the wives of paramount sovereigns, we have it again in the present volume, in conjunction with *Paramabhadrīśvī* and *Rājñī*, in the *Mandār Hill* inscriptions of *Adityasēna*, Nos. 44 and 45 below, and throughout the *Dēv-Varāṅk* inscription of *Jivitagupta* II., No. 46 below, Plate xxixB. In other series it occurs, for instance, as part of the name of *Ākamahādēvi*, the queen-consort of the Western *Chalukya* king *Vikramāditya* II., in some of his *Paṭṭadakal* inscriptions (*Ind. Ant.* Vol. X. p. 164 ff.); and as the title of *Gāmuḍdabbe*, the wife of the *Rāshtrakūṭa* king *Gōvinda III.*, in line 5 of the grant of *Sāka-Samvāt 726* (*id.* Vol. XI. p. 127).

³ When, under the circumstances referred to in the note on line 3 f. of the *Mandaśr* inscription of *Yaśōdharman* and *Viśhuvardhana*, No. 35 below, Plate xxii, the river *Ganges* was about to descend from heaven to earth,—in order to break the force of its fall, the god *Śiva* (*Paśupati*) received it in the matted hair coiled above his forehead and projecting like a horn; and its waters wandered there for a thousand years, before they eventually reached the earth.

⁴ It is doubtful whether this is a tribal or family name, or an official title. The etymology of it is not apparent.

⁵ *Mahādandanāyaka*, lit. 'great leader of the forces,' is a technical military title.—The officer who held this rank was the superior of the *Dandanāyakas*, or 'leaders of the forces.' This latter title occurs, for instance (together with that of *Piriyadandanāyaka*, which is the Old-Kanarese translation of the Sanskrit *Mahādandanāyaka*), in line 17 ff. of the *Balaḡāṭve* inscription of *Sankamādēva* (*Ind. Ant.* Vol. V. p. 46).—We constantly meet with *Dandanātha*, *Dandādhipati*, *Dandāśa*, and *Dandāśvara*, as synonyms of *Dandanāyaka*.—Prinsep translated *Mahādandanāyaka* in the present inscription by 'administrator of punishments (magistrate)' and 'criminal magistrate'; and this rendering has sometimes been adopted by other translators. As *danda* means 'fine' and 'rod (of chastisement),' as well as 'army, forces,' the titles in which it occurs are capable of being explained as either judicial or military. But, that they are employed in the inscriptions as military titles, is shewn (1) by the way in which the words *Chamāndātha*, *Chamāpa*, *Chamāpati*, &c., in which *chamā* means only 'army,' are occasionally used as synonyms for *Dandanāyaka*, &c., e.g. in line 33 ff. of the *Kargudari* inscription of *Vikramāditya* VI. and *Tailapa* II. (*Ind. Ant.* Vol. X. p. 252), where the *Dandādhipati* and *Dandādhipa* *līvarayya* is also called *Chamāpa*; and (2) by the definition of the *Dandanāyaka* *Kāvaṇayya* as *samastō-sēn-ogrēśvara*, or 'leader of the whole army,' in line 19 of the *Balaḡāṭve* inscription referred to above.

⁶ *Sāmdhivigrahika*, lit. 'an officer for peace and war,' is a technical official or military title. Other synonymous titles were *Sāmdhivigrahādhipā* (e.g. *Ind. Ant.* Vol. VII. p. 70, line 17 f.); *Sāmdhivigrahādhiparandhikrīta* (e.g. *id.* Vol. IV. p. 175, line 18); and *Sāmdhivigrahin* (e.g. *id.* Vol. VIII. p. 20, where it is coupled with *Mahāpradhēna* and *Dandanāyaka*).—The next grade above this was that of the *Mahāsāmdhivigrahika*, whose title occurs, for instance, in line 29 f. of the *Khōh* grant of the *Mahārāja* *Hastin* of the year 163, No. 22 below, Plate xiii.

⁷ *Kumārādēvi*, lit. 'counselor of the prince,' is another technical official title.—The next grade above it was that of the *Mahākumārādēvi*, who is mentioned, for instance, in line 33 of the *Bhāgalpur* grant of *Nārāyaṇapāla* (*Ind. Ant.* Vol. XV. p. 306.)

Bhaṭṭāraka,¹ (and) whose mind is expanded by the favour of constantly walking about in (his) presence,—let it be for the welfare and happiness of all existing beings!

(L. 33.)—And the accomplishment of the matter has been effected by the *Mahādāṇḍānyaka Tilabhṭṭāka*, who meditates on the feet² of the *Paramabhṭṭāraka*.³

¹ It is somewhat doubtful whether this title here denotes Samudragupta, or his successor; but on the whole, *śhām*, 'these,' being used, not *śśhām*, 'those,' the passage seems to have a strictly present sense, and to refer to Chandragupta II.; contrast *tasya*, 'of him, of that one,' which is used to denote Samudragupta in line 17 above, but which I have had, for convenience, to render in the translation by the relative pronoun.—*Bhaṭṭāraka*, *lit.* 'one who is entitled to reverence or homage,' is another technical kingly title. In somewhat later times, it seems to have belonged properly to feudatory *Mahārājas*; thus, it is coupled with the name of the *Mahārāja Śivadēva* I. in two of the Nēpāl inscriptions (*Ind. Ant.* Vol. IX. p. 168, No. 5, line 2, and Vol. XIV. p. 98, line 2), and with the name of the *Mahārāja Dhruvadēva* in the same series (*id.* Vol. IX. p. 173, No. 10, line 4, where the syllables *mahā*, at the end of the line, are omitted in the published text). So, also, we find the feminine form, *Bhaṭṭārīkā*, used as the termination of the names of wives of *Mahārājas*; *e.g.* in line 3 f. of the Aśrīgadh seal of Śarvavarman, No. 47 below, Plate xxxA., and in line 4 of the Nirmāṇ grant of the *Mahārāja* and *Mahāśānta* Samudrasēna, No. 8c below, Plate xlv.—As applied to paramount sovereigns, the fuller and more usual title is *Paramabhṭṭāraka*, as in line 33 of this inscription (see also page 10 above, note 3). But other instances occur in which the shorter title is used; *e.g.* in line 6 of No. 9 of the Nēpāl inscriptions (*Ind. Ant.* Vol. IX. p. 172), Amśvarman has the titles of *Bhaṭṭāraka* and *Mahārājādhirāja*; in line 17 ff. of the Wokkalēri grant of Kirtivarman II. (*id.* Vol. VIII. p. 26 f.), the Western Chalukya kings Vikramāditya I. and his successors, down to Kirtivarman II., all have the titles of *Mahārājādhirāja*, *Paramāvara*, and *Bhaṭṭāraka*. And we have the same title in Old-Kanarese inscriptions, in the abbreviated, or perhaps original, forms of *Bhaṭṭāra* and *Bhaṭṭāra*; *e.g.* in line 2 f. of the Mahākūta inscription of the Western Chalukya king Vijayāditya (*id.* Vol. X. p. 103), in which he has the titles of *Mahārājādhirāja*, *Paramāvara*, and *Bhaṭṭāra*; and in line 2 of the Paṭṭadakal inscription of the Rāshtrakūta king Dhruva (*id.* Vol. XI. p. 124), in which he has the titles of *Mahārājādhirāja*, *Paramāvara*, and *Bhaṭṭāraka*.—In the sense of 'reverend,' *bhaṭṭāraka* was also a priestly title; *e.g.* it is applied to the Jain priest Kumudachandra, in line 2 of the Nēsargi inscription (*id.* Vol. X. p. 129, note 16).—And, in the sense of 'worthy of worship; sacred,' it was also applied to gods; *e.g.* to Paśupati (Śiva), in line 1 of No. 6 of the Nēpāl inscriptions (*id.* Vol. IX. p. 169); to the Sun, in line 15 of the Khōh grant of the *Mahārāja* Śarvanātha, No. 28 below, Plate xviii.; and to Varuṇavāsin (the Sun), in line 13 of the Dēō-Baranpār inscription of Jvita Gupta II., No. 46 below, Plate xxixB.

² *pāda-anudhyāta*.—This is a customary technical term, used of the relations between a paramount sovereign and his feudatory chieftains, officials, &c.; *e.g.* in the Udayagiri cave inscription No. 3 below, Plate iiB., the *Mahārāja*, who makes the gift, is described as meditating on the feet of Chandragupta II.—It is also applied to the relations between parents and their children; *e.g.* in line 18 of the Rājim grant, No. 81 below, Plate xlv., the *Rāja* Tivarādēva is described as meditating on the feet of his mother and father. It is also used in connection with kingly successions, whether the natural relationship is that of fathers and sons, or of elder and younger brothers; *e.g.* throughout the Kārtalāl grant of the *Mahārāja* Jayanātha, No. 26 below, Plate xvi.; and in lines 2 and 8 of the grant of the *Mahārāja* Vinayakapāla (*Ind. Ant.* Vol. XV. pp. 140, 141), who is described as meditating on the feet of his father, Mahēndrapāla, and of his elder brother, Bhōja II. And it is also used in respect of the worship of gods; *e.g.* in line 3 of the grant of the Eastern Chalukya king Amma II. (*Ind. Ant.* Vol. XIII. p. 249), the Chalukyas are described as meditating on the feet of the god Svāmi-Mahāśēna.—In one solitary instance, line 33 f. of the Khārēpāṭaṅ grant of Śaka-Samvat 930 (*Jour. Bo. Br. R. As. Soc.* Vol. I. p. 218), *anudhyāta* occurs without *pāda* preceding it, and the Śilāhāra chieftain Rattārāja is described as *śrī-Satyātrayaśō-anudhyāta*, 'meditating on the glorious (king) Satyātraya.' But the omission of *pāda* here is probably due only to carelessness on the part of the drafter of the record.

³ *i.e.* Chandragupta II.—*Paramabhṭṭāraka*, *lit.* 'one who is supremely entitled to reverence or homage,' is one of the technical titles indicative of supreme sovereignty (see page 10 above, note 3).—I have found one instance in which it is also used as a priestly title, in line 43 of an inscription of Śaka-Samvat 1172 at Mamdāpur in the Belgaum District (*Indian Inscriptions*, No. 1), where it is applied to a Śaiva priest named Vimalasiva or Vimalasāmbhu.—The feminine form, *Paramabhṭṭārīkā*, was one of the titles of the wives of paramount sovereigns; *e.g.* in the Mandār Hill inscriptions of Adityasēna, Nos. 44 and 45 below.

No. 2; PLATE IIA.

ERAN STONE INSCRIPTION OF SAMUDRAGUPTA.

THIS inscription, which has not been previously edited, was discovered in 1874-75 or 1876-77 by General Alexander Cunningham, R.E., C.S.I., C.I.E., then Director-General of the Archaeological Survey of India, and was first brought to notice by him in 1880, in the Reports of the *Archæological Survey of India*, Vol. X. p. 89.

Ēran,¹ the ancient Airikīpa,² is a village on the left bank of the Binā, eleven miles to the west by north from Khurāl,³ the chief town of the Khurāl Tahsil or Sub-Division of the Sāgar⁴ District in the Central Provinces. The inscription is on a red-sandstone squared block, that was found a short distance to the west of the well-known ruined temple of the Boar,⁵ at which there is the inscription of Tōramāpa, No. 36 below. The original stone is now in the Imperial Museum at Calcutta.

The writing, which covers the entire front of the stone, about 9½" broad by 3' 1" high, is in a state of fairly good preservation; but it does not give a very clear lithograph, in consequence of the whole surface of the stone being full of holes more or less large. It is only a fragment; six entire lines, as shewn by the numbering of the verses, have been broken away and lost at the top of the stone, and an indefinite number at the bottom; and also an entire *pāda* of each successive verse, has been broken away and lost at the commencement of lines 25 ff. In addition to this, from one to three letters have been destroyed at the commencement of each extant line, as far as line 24, by whetting tools on the edge of the stone. As far as line 24, each line contains one *pāda* of a verse; but the following lines contained originally two *pādas* each; this shews that the inscription was of an irregular shape, with probably some sculptures on the proper right side of the stone above the first halves of lines 24 ff.—The average size of the letters is about ½". As indicated especially by the form of *m*, the characters belong to the southern class of alphabets; and I should be inclined to name them a variety, with southern characteristics, of the Central India alphabet of the period. The particular type used in this inscription is further represented in the present volume by the Udayagiri cave inscription of Chandragupta II. of the year 82, No. 3 below, Plate iiB.; the Ārang plates of Mahā-Jayarāja. No.

¹ The 'Airan, Ehrin, Eran, and Erun,' of maps, &c. Indian Atlas, Sheet No. 52 Lat 24° 5' N, Long. 78° 15' E.—The name is now written and pronounced both Ēran and Ēran; but, as is shewn by the ancient name, Airikīpa, the first form, with the lingual *ṣ*, is the correct one.—The name is not unique; for the maps shew another 'Eran' seven miles almost due west of Bhēṣā, and another thirteen miles to the north-east of Bhēṣā.

² So far as the passage in line 25 of the present inscription goes, we might take this name as either Airikīpa or Ērikīpa, in consequence of the euphonic absorption of the final *a* of *vishaya*. But the real form of the name is shewn by line 7 of the Boar inscription of Tōramāpa, No. 36 below, Plate xxiiiA., where we have *vishayam-minn=Airikīn*, without any *śaddhi* or joining of vowels.—The autonomous copper coins of the Aśoka period, found at Ēran, give us an earlier Pāli or Prākṛit form of the name, which is either Erakāṣa or Erakāṣa; but the last syllable is not very distinct in the specimens available for examination (*Archæol. Surv. Ind.* Vol. XIV p. 149, and Plate xxxi. Nos. 17 and 18.)

³ The 'Khorye, Khurai, Korai, Kurai, and Kurāi,' of maps, &c.

⁴ The 'Sāgar and Saugor' of maps, &c.

⁵ *Archæol. Surv. Ind.* Vol. X. Plates xxxA. and xxviA.

40, Plate xxvi.; the Rāyपुर plates of Mahā-Sudēvarāja, No. 41, Plate xxvii.; the Vakāṭaka inscriptions, Nos. 53 to 56, Plates xxxiii. xxxiv. and xxxv.; and the Rājim plates of Tivara dēva, No. 81, Plate xlv. The chief characteristic of it is the peculiar 'box-headed' tops of the letters, formed by sinking four short strokes in the shape of a square and leaving a block of stone or copper in the centre of them. We have a variation of this characteristic, represented in this volume by the Majhgawān plates of the *Mahārāja* Hastin of the year 191, No. 23, Plate xiv., in which the tops of the letters, instead of being 'box-headed' or square, are 'nail-headed' or triangular, with the apex of the triangle downwards.¹ And the present inscription contains a mixture of both types; the 'nail-headed' tops can be seen in, for instance, *prithu-rāghav-ādyāh*, line 8, and *samudraguptāh*, line 10; and the 'box-headed' tops in, for instance, *bahu-putra-pautra*, line 19, and *samara-karma parākkram-ādāham*, line 21. Owing to the nature of the substance worked on, in the case of inscriptions on stone, except those on a large scale, these centre blocks would obviously be very liable to injury; in the actual process of engraving, as well as from the wear and tear of time. The result is that, though these two characteristics of this alphabet are usually very well preserved and are very recognisable in the copper-plates, in the stone inscriptions they are preserved, so as to be clearly recognised in this series of Plates, only in the large-scale Nachnē-kī-talāt inscriptions of the *Mahārāja* Prithivishēna, Nos. 53 and 54, Plate xxxiiiA. and B. In the present inscription I cannot find a single instance in which there is enough left of the triangular or the square centres of the tops of the letters, to shew distinctly in the lithograph. It is, in fact, quite possible that, in inscriptions of this scale on stone, the engraver was not very particular about leaving the centre-blocks at all; an indifference about this is certainly observable even in the Chammak plates of the *Mahārāja* Pravarasēna II., No. 55, Plate xxxiv., through nearly the whole of which the tops of the letters were scooped out hollow, without any centre-blocks at all. The characters include, in the numbering of the verses, forms of the numerical symbols for 2, 3, 4, 5, 6, and 7.—The language is Sanskrit; and the inscription is in verse throughout.—In respect of orthography, the only points that call for notice are (1) the use of the guttural nasal, instead of the *anusvāra*, before *h*, in *paribṛiṅhaṇa*, line 26; and (2) the doubling of *k* and *dh*, in conjunction with a following *r*, in *vikkrama*, line 1, and *parākkrama*, lines 17 and 21; and in *dāhrutam*, line 12.

The inscription is one of the Early Gupta king *Samudragupta*, whose name is recorded in line 10. From the occurrence of the word *bahūva* in line 9, the first part of the inscription probably mentioned some of his ancestors. But, that the inscription did not extend to the time of any of his successors, is shewn by the fact that none of their names can be fitted into any of the places where letters are illegible in lines 11 to 24, consequently, the prowess, &c., described in these lines are those of *Samudragupta*; and this description is immediately followed by the mention of the erection, at the city of *Airikīpa*, i.e. *Éran*, of something or other of which the stone was either a portion or the separate record. The lacunæ here leave us without any clue as to what was erected, and in connection with what form of religion. But, judging from its shape and appearance,

¹ Mr. C. Bendall has obtained two specimens of triangular-headed characters, one of them in Népāl, in which, differing from the present forms, the apex of the triangle is placed uppermost; see his *Journey in Népāl*, p. 54 f. He appears to have named them 'point-headed' or 'arrow-headed' characters.—Quite recently, Mr. J. Robinson, C.E., of Gayā, has sent me, for examination, another very interesting specimen of a variety of the same characters in an inscription on the bottom plate of a brass image of Buddha.

the stone is part of a temple. And General Cunningham has suggested that, if it was attached to any of the existing ruins, it belonged most probably to the temple with a colossal figure of Vishṇu,¹ immediately on the north of the temple of the Boar. The date of the inscription, if any was recorded, is broken away and lost.

TEXT.²

(Lines 1 to 6, containing the whole of the first verse and the first half of the second, are entirely broken away and lost.)

7	[---] ³	suvarṇa-dānē
8	[---]ritā	nripatayaḥ Prithu-Rāghav-ādyāḥ [11 ⁴] 2
9	[---]	babhūva Dhanad-Āntaka-tusṭi-kōpa-tulyaḥ ⁵
10	[---]ma-nayēna	Samudraguptaḥ [1 ⁶]
11	[---]pya	pārthiva-gaṇas-sakalaḥ prithivyām
12	[---]sta(? sva)-rājya-vibhava-ddhutam - āsthitō - bhūt [11 ⁶] 3	
13	[---]na	bhakti-naya-vikkrama-tōshitēna
14	[yō]	rāja - śabda - vibhavair - abhishēchan - ādyaiḥ [1 ⁶]
15	[---]nitaḥ	parama-tusṭi-puraskritēna
16	[---]vō	nripatir-aprativāryya-vīryyaḥ [11 ⁶] 4
17	[---]sya	pauruṣa-parākkrama-datta-śulkā
18	[hasty - a]śva - ratna - dhana - dhānya - samṛiddhi - yukta [1 ⁶]	
19	[---]n-grihēshu	muditā bahu-putra-pautra-
20	[sa]nkrāmiṇī	kula-vadhūḥ vratinī nivishṭā [11 ⁶] 5
21	[Yas]y-ōrjītam	samara-karma parākkram-ēddham ⁷
22	[---]	yaśaḥ su-vipulam-paribambhramti [1 ⁶]
23	[---]ni	yasya npavaś-cha raṇ-ōrjītanī ⁸
24	[sva]pn-āntarēshv-api	vichintya paritrasanti [11 ⁶] 6
25	[---] [---]pta(?)ḥ	sva-bhōga-nagar-Airikīpa-pradēśē [1 ⁶]
26	[---] [---]	[sam]sthāpitas-sva-yaśasaḥ paribrīhan(n)-ārttham [11 ⁶] 7
27	[---] [---]vō	nripatir-āha yadā [---] [1 ⁶]

(The rest of the inscription is entirely broken away and lost.)

TRANSLATION.

(Lines 1 to 6, containing the whole of the first verse and the first half of the second, are entirely broken away and lost.)

(Line 7.)— in giving gold [by whom] Prithu and Rāghava and other kings [were outshone.]

¹ *Archaeol. Surv. Ind.* Vol. X. p. 89, and Plates xxvB. and xxviB.

² From the original stone.

³ Metre, Vasantatilaka, throughout.

⁴ With this exception, the lines of this inscription, as far as line 24, contain exactly a *pāda* of each verse. Lines 25 ff. contained exactly two *pādas* of each verse.


⁵ Or perhaps *charan-ōrjītanī*.

CORPUS INSCRIPTIONUM INDICARUM.

Vol. III

A—Eran Inscription of Samudragupta

Plate II



B—Udayagiri Cave Inscription of Chandragupta II.—The Year 82



(L. 9).— there was **Samudragupta**, equal to (the gods) Dhanada and Antaka in (*respectively*) pleasure and anger;¹ by policy; (*and*) [by whom] the whole tribe of kings upon the earth was [overthrown] and reduced to the loss of the wealth of their sovereignty;—

(L. 13).—[Who], by satisfied by devotion and policy and valour,—by the glories, consisting of the consecration by besprinkling, &c., that belong to the title of 'king,'—(*and*) by combined with supreme satisfaction,— (*was*) a king whose vigour could not be resisted;—

(L. 17).—[By whom] there was married a virtuous and faithful wife,² whose dower was provided by (*his*) manliness and prowess; who was possessed of an abundance of [elephants] and horses and money and grain; who delighted in the houses of ; (*and*) who went about in the company of many sons and sons' sons;—

(L. 21).—Whose deeds in battle (*are*) kindled with prowess; (*whose*) very mighty fame is always circling round about; and whose enemies are terrified, when they think, even in the intervals of dreaming, of (*his*) that are vigorous in war;—

(L. 25).— in a place in **Airikipa**,³ the city of his own enjoyment has been set up, for the sake of augmenting his own fame

(L. 27).— when the king said

*(The rest of the inscription is entirely
broken away and lost.)*

No. 3; PLATE II B.

UDAYAGIRI CAVE INSCRIPTION OF CHANDRAGUPTA II. THE YEAR 82.

THIS inscription appears to have been first brought to notice in 1854 by General Cunningham, in his *Bhilsa Topes*, p. 150 f., where he published his reading of the text, and a translation of it, accompanied by a lithograph (*id.* Plate xxi. No. 200).—In 1858, in his edition of Prinsep's *Essays*, Vol. I. p. 246 f. note 4, Mr. Thomas published his own reading of the text, accompanied by a translation by Professor H. H. Wilson.—And, finally, in 1880, in the *Archaeol. Surv. Ind.* Vol. X. p. 50, General Cunningham published his revised reading of the text, and a revised translation of it, accompanied by a fresh lithograph (*id.* Plate xix.)

¹ Compare the customary expression, "equal to (the gods) Dhanada and Varuna and Indra and Antaka," in line 26 of No. 1 above, page 8. See also page 14 above, note 4.

² Samudragupta's wife was Dattadévi; but the metre prevents her having been mentioned by name in this verse.

³ See page 18 above, note 2.

⁴ The lacunæ in this verse render it impossible to say whether here, and below, *sva*, 'his own,' refers to Samudragupta, or to some feudatory of his, who may have been mentioned here.

Udayagiri¹ is a well-known hill, with a small village of the same name on the eastern side of it, about two miles to the north-west of Bhêlsâ,² the chief town of the Bhêlsâ Tahsil or Sub-Division of the Îsâgadh³ District in the dominions of Scindia (properly Sîndé) in Central India. On the eastern side of the hill, a little to the south of the village, and almost on the level of the ground, there is a cave-temple, which, from its containing this inscription, General Cunningham has named "the Chandragupta Cave."⁴ The inscription is on the upper part of a smoothed and countersunk panel, about 2' 4½" broad by 1' 6" high, over two figures,—one of the four-armed god Vishnu, attended by his two wives; and one of a twelve-armed goddess, who must be some form of Lakshmi, the consort of Vishnu, rather than, as suggested by General Cunningham, Mahishâsurî, *i.e.* Durgâ, the consort of Śiva,—which are sculptured on the face of the rock, outside the cave and a few feet to the north of the entrance to it.

The writing, which covers a space of about 2' 3½" broad by 4½" high, is in a state of fairly good preservation; the surface of the rock has peeled off in some places; but no letters are entirely destroyed, except the *g* of *chandragupta* in line 1, and, in line 2, the first *akshara* of the name of the *Mahârâja* whose gift is recorded.—The average size of the letters is about ⅙". The characters belong to the southern class of alphabets, and give another specimen of the 'box-headed' variety, peculiar to Central India, which I have commented on at page 18 f. above; but in this inscription, again, there are no instances in which enough remains of the square centre of the tops of the letters to shew distinctly in the lithograph. In *âshâdha*, line 1, they include an adaptation from the northern alphabets; *vis.* the separate sign for the lingual *dh*, which, in the early southern alphabets, was represented, together with its unaspirated form *d*, by the same character as the dental *d*. They also include, in line 1, forms of the numerical symbols for 2 and 80.—The language is Sanskrit; and the inscription is in prose.—In respect of orthography, the only point that calls for notice, is the doubling of *dh* in conjunction with a following *y*, in *anuddhyâta*, line 1.

The inscription refers itself to the reign of the Early Gupta king **Chandragupta II.** It is dated, partly in numerical symbols and partly in words, in the year⁵

¹ The 'Udaygiri and Udegiri' of maps, &c. Indian Atlas, Sheet No. 53 Lat. 23° 32' N.; Long. 77° 50' E.

² The 'Bhilsa and Bhelsa' of maps, &c.

³ The 'Isagarh' of maps.

⁴ *Archæol. Surv. Ind.* Vol. X. p. 49 ff. and Plates xvi. and xvii.

⁵ Whether "current" or "expired," is not specifically stated. But the locative case is used, and, there being no word signifying "expired" in apposition with it, the natural sense of it is "in the year eighty-two," *i. e.* "while the year eighty-two is current."—It is often asserted that the ancient Hindus always expressed their dates in expired years. And, according to this, we should understand *atitâ*, 'having gone by, having passed by,' or any similar word, in apposition with *samvatsarâ* in the present passage, and translate accordingly.—No doubt, in making calculations, the Hindus worked, as Europeans must work, with the number of expired years as a basis. But this is quite a different question from that of their method of expressing the dates; as, also, is the question whether they did not sometimes by mistake quote years as current which were really expired, and the reverse, and even occasionally quote, as current, or even as expired, years that were still to come. And, as a very clear and pointed instance of the record of a date in current years, we have the Gwâliar Śkubahû temple inscription of Mahlâpâla, dated Vikrama-Samvat 1150, which gives (*Ind. Ant.* Vol. XV. p. 41; vv. 107, 108; l. 40) first, in words, the number of years expired, and then, partially

eighty-two (A.D. 401-2), and on the eleventh lunar day of the bright fortnight of the month Āshāḍha (June-July). The cave appears to be a Vaiṣṇava cave; and this must, therefore, be a Vaiṣṇava inscription. And the object of it is to record the gift or dedi-

in words and fully in figures, the number of the current year,—*Ēkādāśav-attīṣhu samvatsara-tatīṣhu cha l ek-ōna-pañchādīati cha gatīshv-abbēshu Vikramdt || Pañchādī ch-Āsvirō māś kṛishna-pakshē nrip-ōjāyāḍ t rachitē Manikanthēna prāstir-viyam-ujjvalē || Ankat-ēpi 1150 || Āvina-bahula-pañchamyām*,—“and when eleven centuries of years had passed by, and (in addition) fifty years, less by one, had gone, from (the time of) Vikrama; and in the fiftieth (year); in the month Āsvina; in the dark fortnight; by order of the king, this brilliant eulogy was composed by Maṅikaytha; or, in figures, (in the year) 1150, on the fifth lunar day of the dark fortnight of Āsvina.”—Excluding special and capricious instances, the inscriptions disclose the following general and systematic constructions in the expression of dates.—(1) The use of the nominative singular or plural, unaccompanied by any verb or participle. Instances of this are somewhat rare. But I can quote (a) the Mathurā image inscription (No. 70 below, Pl. xID. l. 2), *samvatsarah 200 30*; (b) the Goa grant of Satyāśraya-Dhruvarāja-Indravarman (*Jour. Bo. Br. R. As. Soc.* Vol. X. p. 365, l. 17 ff.), *pravardhamāna-vijaya-rājya-samvatsaram vimśatitamam Śaka-kālāḥ-pancha varsha-satānu dvātrīmiḍni*; (c) the Dighwā-Dubaulf grant of the Mahārāja Mahēndrapāla (*Ind. Ant.* Vol. XV. p. 113, l. 4), *samvatsrā* (i.e. *samvatsarāḥ*) *100 50 5 Māgha su* (d) the Bengal Asiatic Society's grant of the Mahārāja Vināyakapāla (*id.* Vol. XV. p. 141, l. 17), *vanvatsrō* (i.e. *samvatsarō*), for either *samvatsarah* or *samvatsarāḥ*) *100 80 8 Phālguna ba di 9*; and (e) the second date in the ‘Deogarh’ inscription of Bhōjadēva of Gwālior, dated Vikrama-Samvat 919 and Śaka-Samvat 784 (*Archaeol. Surv. Ind.* Vol. X. p. 101, and Pl. xxxiii. No. 2, l. 10), *Śaka-kāl-āḍa-sapta-satāni chatur-aṣṭy-adhīḍni 784*. And, for early times, we may compare, though they relate to years of government, instead of eras, (f) the nominative in the Banawāsi Prākṛit inscription of Hārīḍputra-Śātakarṇi (*Ind. Ant.* Vol. XIV. p. 333, l. 1), *vaṣṭ Hārīṣputasa Sātākarnisa savachharām 10 8 Hōmāmīḍna pakshē 7 divasa 1*; (g) the nominative in the Rājim grant of the Rāja Tivarādēva (No. 81 below, Pl. xlv. l. 35 f.), *pravardhamāna-vijaya-rājya-samvatsaru 9 Kārttika divasu aṣṭamu 8*; and the crude form in (h) the Arāng grant of the Rāja Mahā-Jayarāja (No. 40 below, Pl. xxvi. l. 24), *pravardhamāna-vijaya-samvatsara 5 Mārgaśira 20 5*, and (i) the Rāypur grant of the Rāja Mahā-Sudēvarāja (No. 41 below, Pl. xxvii. l. 27), *pravardhamāna-vijaya-samvatsara 10 Māgha 9*. Compare also, for later times, the crude form in (j) the ‘Dewal’ inscription of Lalla of the Chhinda family (*Archaeol. Surv. Ind.* Vol. I. Pl. li. l. 24), *samvatsara-sahasra 1049 Māghā ba di 3 Gurudīn*; in (k) a Kōlāpur inscription of Siṅghana II. (*Indian Inscriptions*, No. 47, l. 1 f.), *Śa-Śaka 1157 Manmatha-samvatsarō Śrāvāṇa bahula 30 Gurau*; and in numerous other instances.—(2) The use of the nominative singular or plural, in apposition with an ordinal adjective, which, again, usually qualifies the name of the *samvatsara*, of the sixty-years cycle, in the genitive case. This is a Drāviḍian method, in constant use in Southern India. As typical and leading instances, I will quote, in respect of the nominative singular, (a) a Balāghāṭve inscription of Bijjala (*Pāli, Sanskrit, and Old-Kanarese Inscriptions*, No. 183, l. 62), *Śaka-varsham 1080neya Bahudhānya-samvatsarada Pushyada punnamī Sōmavērad-uttarāyānasamkrānti-vyatīpāta-sōmagrahanad-andu*; and, to illustrate a numerous class of instances in which the crude form is used to represent the nominative singular, (b) a Balāghāṭve inscription of Sōmēśvara II. (*Ind. Ant.* Vol. IV. p. 209, l. 30 ff.), *Śaka-varsha 997neya Rākshasa-samvatsarada Pushya sūddha 1 Sōmavērad-andin-uttarāyānasamkrānti-parva-nimittam*, and, in respect of the nominative plural, (c) the grant of Gōvinda III. (*id.* Vol. XI. p. 126, l. 1 ff.), *Śaka-nripa-kāl-āṭta-samvatsara-satangaḥ-ēḷ-nūy-irpatt-āyaneḥ Subhānu embḥ varshadd Vaid-khamāsa-kṛishnapaksha-pañchamī Brihaspativōram-āgi*, and (d) the Adaraguñchi inscription of Kōtṭiga or Khotṭiga (*id.* Vol. XII. p. 236, l. 7 ff.), *Śaka-nripa-kāl-āṭta-samvatsara-satangaḥ-ēṣṭu nūya tomhātta-māraṇya Prajāpati-samvatsaram saluttam-vre tad-varsh-dbhyantrād-Āsvayujōd-ama-vōce Ādityavōdra śārya-grāhāṇa*.—(3) The use of the locative singular or plural, with the corresponding locative, in apposition, of *atirānta*, *atīta*, *gata*, *nivṛtta*, *prayāta*, *samātīta*, *ryatīta*, *yōta*, or any similar word, signifying ‘elapsed, or gone by’. Thus, in respect of the locative singular, (a) the first date of the Mandasōr inscription of Kumāragupta and Bandhuvarman (No. 18 below, Pl. xi. l. 19), *Malavāndm gaṇa-sthityā yātē ita-chatushtayē t tri-navaty-adhīḍ-bānām-ritau śūrya-gḥana-svāntē || Sahasya-māsa-śuklasya prāstē-hni trayōdasē*, and (b) the Sāmāngad grant of

cation,—by a *śāhārdja* of the **Sanakānika**¹ tribe or family, who was a feudatory of Chandragupta II., but whose name, in line 2, is now illegible,—of, evidently, the two groups of sculptures above which it is engraved.

Dantidurga (*Ind. Ant.* Vol. XI. p. 112, l. 30 f.), *pañcha-saptaty-adhika-Sakabāla-samvatsara-sata-shaṣṭi vyatīte samvat 675 pai(?)ṣṭ or pau)hachchhikṣyē Māgha-māsa-ratha-saptamyām tuld-purusha-sthite*. And, in respect of the locative plural, (c) the Bādāmi cave inscription of Maṅgalā (*Ind. Ant.* Vol. VI. p. 363, ll. 6 f., 11), *Saka-nripati-rājyādbhishhka-samvatsarshv-atikrāntīshu pañchasa-īatīshu mahā-Kārttika-paurṇamāsya*; (d) the Harihar grant of Vinayāditya (*id.* Vol. VII. p. 302, l. 23 ff.), *śhōdai-ōttara-shaṣṭi-chhatīshu Saka-varshshv-atītiṣhu pravardhamāna-vijaya-rājya-samvatsarē chaturdaś vartamān Kārttika-paurṇamāsya*; and (e) the Kauthēn grant of Vikramāditya V. (*id.* Vol. XVI. p. 24, l. 61 f.), *Saka-nripa-kāl-ōlita-samvatsara-īatīshu navasu trīmad-adhikēshu gatiṣhu 930 pravartamāna-Saumya-samvatsarē paurṇamāsyaīm sōmagrahāna-parvāni*.—(4) The use, as in the present instance, of the simple locative single or plural, without any participle signifying 'elapsed or gone by,' in apposition. Thus, in respect of the locative singular, (a) the Gūnda inscription of the *Kshatrapa* Rudrasīdha (*Ind. Ant.* Vol. X. p. 157, l. 3), *varshē dvay-uttara-īatē sam 200 2 Vaiśākha-suddha-pañchamī-Dhanya-tithau Śravana-nakshatra-muhūrtē*; (b) a Mathurā inscription of Vāudēva (*Archaeol. Surv. Ind.* Vol. III. p. 35, and Pl. xv. No. 20, l. 1), *samvatsarē 90 8 Varsh-māś 4 dva sē 10*; (c) the Majhgawān grant of the *Mahārāja* Hastin (No. 23 below, Pl. xiv. l. 1 f.), *ōka-navaty-uttar-ōda-īatē Gupta-nripa-rājya-bhuktay īrīmāi pravardhamāna-MahāChaitra-samvatsarē Māghamāsa-bahulapaksha-trītyāyām*; and (d) the Allnā grant of Śīlāditya VII. (No. 39 below, Plate xxv. l. 77 f.), *samvatsara-sata-chaturshayē sapta-chaturīmīad-adhikē Jyēshtha-suddha-pañchamyām anкатаḥ samvat 400 40 7 Jyēshtha su 5*. And, in respect of the locative plural, (e) the Wāpi grant of Gōvinda III. (*Ind. Ant.* Vol. XI. p. 159, l. 46 f.), *Saka-nripa-kāl-ōlita-samvatsara-īatīshu saptasu trīmad-adhikēshu Vyaya-samvatsarē Vaiśākha-sita-paurṇamās-ōmagrahāna-mahāparvāni*; and (f) the Pāṭṇa grant of Bhīma II. (*id.* Vol. XI. p. 71, l. 17 ff.), *īrīmad-Vikramāditya-ōpādīta-samvatsara-īatīshu dvādasaisi shaṣṭi-panchād-uttarēshu Bhādrapadāmāsa-kṛshṇapaksh-ārdhyāyām Bhaumavōrē-tr-ākkatō-pi samvat 1256 laukika Bhādrapada ba dī 15 Bhaumē*.—And (5) the use of the abbreviations *sam* and *samvat*, standing alone, and not explained by a full record in words as they are in instances (3, b) and (4, a, d, f) above. This method, however, throws no light on the question now under discussion; and the use of these abbreviations will form the subject of a separate note.—Now, in the cases illustrated by the examples given under (2) above, it can hardly be disputed that current years are intended; the very construction,—e.g. in (2, a) "Monday, the full-moon day of (the month) Pūshya of the Bahudhānya samvatsara, (which is) the 1080th Śaka year,"—prevents any other interpretation. And, in the examples given under (1), it is difficult to see how, without imagining an elliptical construction for which no actual example can be quoted as authority, the nominative case could be used to denote any but the current year. With these examples, and the plain record of the Gwalior inscription, before us, when we find that in a certain class of instances (3, a to e) the locative case is uniformly coupled with a word distinctly meaning 'expired or gone by' in apposition, whereas in another class of instances (4, a to f) any such word is as uniformly omitted, there is nothing to prevent our giving, but on the contrary every reason to induce us to give, to the simple locative, in the last class of instances, its natural and ordinary meaning of "in such and such a year," i.e. "while such and such a year is current." This is the meaning that is always given to the simple locative in a regnal date; thus, in a Nāsik inscription (*Archaeol. Surv. West. Ind.* Vol. IV. pp. 108, l. 1, 109),—*siri-Pulumyisa samvachharē śhunavēś 19*,—"in the nineteenth (19) year of the illustrious Pulumyī." It has never been attempted to maintain that, in such a record as this, the text means "the nineteenth year having expired." And there is no reason why any such forced interpretation should be put on the simple locative expressing the number of years of an era; especially when we bear in mind that almost every era owes its origin to only an extension of regnal dates, and that the system of expired years can only have been devised when a considerable advance had been made in astronomical science.

¹ In the fourth syllable, the vowel here is the short *i*; but in the same word in the Allahābād pillar inscription, No. 1 above, line 22, page 8, it is long.

TEXT.¹

1 Siddham || Sarivatsarē 80 2 Āshāḍha-māsa-śukl-ē(ai)kādaśyam |
 paramabhaṭṭāraka-mahārājādhi²-śrī-Chandra[*g*]upta-pād-ānuddhyātasya |³
 2 mahārāja-Chhagalaga-pautrasya mahārāja-Vishṇudāsa-putrasya Sanakā-
 nīkasya mahār[āja]-. . . dha(?)lasy-āyam dēya-dharmmaḥ ||

TRANSLATION.

Perfection has been attained!¹ In the year 80 (*and*) 2, on the eleventh lunar day of the bright fortnight of the month Āshāḍha,—this (*is*) the appropriate religious gift² of the Sanakānīka,³ the Mahārāja . . . dhala (?),—the son's son of the Mahārāja Chhagalaga; (*and*) the son of the Mahārāja Vishṇudāsa,—who meditates on the feet of the Paramabhaṭṭāraka and Mahārājādhirāja, the glorious Chandragupta (II.)

No. 4; PLATE IIIA.

MATHURA STONE INSCRIPTION OF CHANDRAGUPTA II.

THIS inscription, which has not been previously edited in full, was discovered in 1853 by General Cunningham, and was first brought to notice by him in his first Archæo-

¹ From the original stone.

² Read *mahārājādhirāja*.—With the reading of this inscription, which may perhaps be, not an omission by the engraver, but a conventional abbreviation of the full title, we may compare *marajama*, i. e. *mahārājādhi*, for *mahārājādhirāja*, on one of the silver coins of Skandagupta (*Ind. Ant.* Vol. XIV. p. 66 f.)

³ This mark of punctuation is unnecessary.

siddham.—On the analogy of an inscription (*Archzol. Surv. Ind.* Vol. V. Plate xlii.), which commences *Siddhiḥ Śrīh Samvat, &c.*,—to which we may add another inscription (*Four. Beng. As. Soc.* Vol. XXIX. p. 18, and Vol. XXX. p. 13) commencing *Siddhiḥ Samvat, &c.*—Dr. Bühler (*Ind. Ant.* Vol. X. p. 273) takes *siddham*, at the commencement of inscriptions, as a nominative case standing by itself, and translates it by 'success.' But it seems to me to be clearly the remnant of some such phrase as *siddham bhagavatā*, "perfection or success has been attained by the Divine One," analogous to the *jitam bhagavatā*, "victory has been achieved by the Divine One," of, for instance, the Gadhwā inscription of Kumāragupta, No. 8 below, Plate ivC., and the grant of the Pallava Yuvamahārāja Vishṇugōpavarman (*Ind. Ant.* Vol. V. p. 51). We may also compare *jitam Vishṇunā* in the Tuān inscription, No 67 below, Plate xiA. And we have the remnant of another analogous expression, in *driśhtam*, "sight (*i.e.* clearness of perception in religious matters) has been attained (by the Divine One)," at the commencement of, for instance, the Chammak and Siwan plates of the Mahārāja Pravarasēna II., Nos. 55 and 56 below, Plates xxxiv. and xxxv.—In his remarks referred to above, Dr. Bühler tells us that, in the *Mahābhāshya* (Kielhorn's edition, pp. 5, 6) *siddham* is quoted as a *mangala* or 'auspicious invocation;' and refers us to some remarks, supporting this, by Dr. R. G. Bhandarkar in *Ind. Ant.* Vol. V. p. 346.—As helping to illustrate the meaning, 'perfection,' by which I render *siddham*, I would refer to the use of *siddha* by the Jains to denote their saints who have attained *siddhi* or 'perfection or final beatitude,' and who are invoked, under this epithet, in, for instance, the Udayagiri inscription of the year 106, No 31 below, Plate xxxviiiA. line 1

⁴ *dēya-dharma*; *lit.* ' (a gift of) religion, which is proper to be given.'—Monier Williams, in his Sanskrit Dictionary, renders it by 'the duty of giving, charity, beneficence;' Dowson, by 'votive offering' (e.g. *Four. R. As. Soc. N. S.* Vol. V. p. 184); and Bühler and Bhagwanlal Indraji, by 'meritorious gift, or benefaction' (e.g. *Archzol. Surv. West. Ind.* Vol. IV. p. 83).

⁵ See page 8 above, note 1.

logical Report, which, originally printed in 1863 as a supplement to the *Journal of the Bengal Asiatic Society*, Vol. XXXII. pp. iii. to cxix., was in 1871 reprinted, with the addition of Plates, as *Archæol. Surv. Ind.* Vol. I., in which the inscription is noticed on p. 237.—Subsequently, in 1873, in the *Archæol. Surv. Ind.* Vol. III. p. 37, and Plate xvi. No. 24, he published a reduced lithograph of it, shewing the completion of the lines as arranged by him.

The inscription is on a red-sandstone fragment, about 10" broad by 11½" high, cracked across the lower proper right corner, which was found, with its face downwards, forming part of the pavement immediately outside the Katrā gateway at Mathurā,¹ the chief town of the Mathurā District in the North-West Provinces. The original stone is now in the Provincial Museum at Lahôr.

The writing, which covers the entire front of the stone, about 10" broad by 11½" high, is in a state of very fair preservation. It is only a fragment; the first line has been almost entirely destroyed, and an indefinite number of lines have been entirely broken away and lost at the bottom of the stone; and, in addition to this, from one to nine *aksharas* have been broken away and lost at the commencement of the lines, and from one to five at the ends of the lines, except in lines 8 and 9.—The size of the letters varies from $\frac{3}{8}$ " to $\frac{1}{2}$ ". The characters belong to the northern class of alphabets. They are of radically the same stock with those of the Allahâbâd posthumous pillar inscription of Samudragupta, No. 1 above, but with several essential differences in details; the most noticeable of these are (1) the very marked curve in the left downward stroke of *m*, which I have noticed, at page 3 above, as belonging originally to an earlier form of this letter than that which occurs in the Allahâbâd inscription; (2) a slanting straight stroke, instead of a circular loop, at the bottom of the left downward stroke of *s*; and (3) the formation of the lower part of *h* entirely to the right, instead of its sloping downwards only slightly to the right and then turning up very markedly to the left.—The language is Sanskrit; and the extant portion of the inscription is in prose throughout.—The orthography does not present anything calling for remark.

The inscription is one of the Early Gupta king Chandragupta II. His name does not occur in the portion that is extant. But the instrumental case *putrēna* in line 9, immediately after the mention, in the genitive case, of Samudragupta, shews that the genealogy was continued down to, and ended with, his son and chosen successor, whose name came in line 11 or 12, and who is known from the subsequent records to have been Chandragupta II.; and that the subject of the inscription was an act of the latter. The date of the inscription, if any was recorded, and the subject of it, were in the portion that has been broken away and lost.

TEXT.²

- | | | | |
|---|---|---------------------------------------|----------------------------|
| 1 | | [Sarvva-râj-ôchhêttuh | prithiv]y[âm=apratiratha]. |
| 2 | [sya | chatur-udadhi-sali]l-âsvâdita-ya[sasô | Dha]. |
| 3 | [nada-Varun-êndr-ântaka-sa]masya | Krîtânta-[paraśôh] | |
| 4 | [nyây-âgat-ânêka-gô]-hiranya-kôti-prada[sya | | chir-ô]. |

¹ *Katrâ* is the common word used in that part of the country for 'an enclosed market-place.'

² The 'Matra, Muthra, and Muttra.' of maps, &c. Indian Atlas, Sheet No. 50. Lat. 27° 30' N.; Long. 77° 43' E.

³ From the original stone.—The passages that have been broken away are supplied from the Allahâbâd posthumous pillar inscription of Samudragupta, No. 1, lines 24, 26, 28, and 29, page 8 above, and from lines 1 to 4 of the Bhitari pillar inscription of Skandagupta, No. 13 below, Plate vii.

5	[tsann - ásvamedh - áharttur-mma]hárāja - śrī - Gupta - prapau[t]r[asya]
6	[mahárāja-śrī-Ghaṭōtka]cha-pautrasya mahárājādhir[āja]-
7	[śrī-Chandragupta-pu]trasya Lichchhavi-dauhitrasya mahā[dé]-
8	[vyām Kumāra]d[é]vyām-utpannasya mahárājādhirā-
9	[ja-śrī-Sa]mudraguptasya putrēna tat-parigri-
10	[hi]t[é]na mahādēv[y]ām Dat[t]adēv[y]ām=ut[p]an[n]jē-
11	[na ¹ paramabhāgavatēna mahárājādhirāja-śrī]-
12	[Chandraguptēna].....

(The rest of the inscription is entirely broken away and lost.)

TRANSLATION.

(Line 8).—By him who is the son,—accepted by him,² (and) begotten on the Mahādēvi Dattadēvi,— of the Mahárājādhirāja, [the glorious] Samudragupta,—

(L. 1).—[Who³ was the exterminator of all kings;⁴ who had no antagonist (of equal power)] in the world; [whose fame was] tasted [by the waters of the four oceans⁵];

¹ I add these two lines in order to shew the continuation of the construction of this record.

² See page 12 above, note 1.

³ i.e. Samudragupta.

⁴ *sarva-rāj-śchchēttī*.—In the nominative case, *sarva-rāj-śchchēttī*, this epithet occurs on the reverse of some gold coins, hitherto always classed in the Early Gupta series (see *Four. Beng. As. Soc. Vol. LIII. Part I, p. 169 f.*, and *Pl. in. No. 1*; also *Archæol. Surv. West. Ind. Vol. II. p. 36*, and *Pl. vii. No. 1*), which have on the obverse the name of Kācha, in the place where the king's name usually stands on coins, with the marginal legend *kāchō gām=avajitya karmabhir=uttamair=jayati*, "Kācha, having conquered the earth, is victorious by (his) most excellent deeds," and which have always been attributed to the Mahárāja Ghaṭōtkacha, the grandfather of Samudragupta.—But, in the first place, the name on these coins is distinctly Kācha, and nothing more; and *kācha*, which means 'glass, crystal; the string of a balance, alkaline salt, black salt, wax; &c.,' is a totally different word from *utkacha*, 'having the hairs (of the body) standing erect (through pleasure),' which is the second component of the name of Ghaṭōtkacha. Secondly, Ghaṭōtkacha, being only a feudatory Mahárāja, was not entitled to issue a coinage in his own name. And thirdly, the epithet *sarva-rāj-śchchēttī* on the reverse, is, in the inscriptions, always applied to Samudragupta, and to him only.—There is nothing distinctive in this epithet, sufficient to shew that it belonged only to the Early Gupta dynasty (and, in that dynasty, to Samudragupta). Nor, I think, is it absolutely certain that these coins belong to the Early Gupta series. But the general appearance of them, with the legends on them, justifies such an opinion. And, if they are Early Gupta coins, then they must be attributed to Samudragupta, not to Ghaṭōtkacha; and Kācha must, in that case, be a personal and less formal name of Samudragupta; and with it we may compare such instances as Śāba, 'cadaverous, of a dark yellowish colour, tawny; the young of any animal,' used as a second name of Vīrasēna, a minister of Chandragupta II. (No. 6 below, Plate IV. line 4); Vyāghra, 'a tiger,' applied to a Jain named Rudrasōma (No. 15 below, Plate IX. A.); and Permādi (also Parmādi, Parmāḍi and Paramardi), a name of the Western Chālukya king Vikramāditya VI. (*Four. Bo. Br. R. As. Soc. Vol. XI. pp. 225, l. 9, 253, l. 14*; Bühler's *Vikramānkadēvacharita*, *Introd. p. 30, note 2*; and *Rājataranginī*, vii. 1122, 1124).—The only other instances, known to me, in which the name Kācha occurs, are in the case of two rulers or chieftains, Kācha I. and Kācha II., mentioned in one of the inscriptions in the Ajāpā caves (*Archæol. Surv. West. Ind. Vol. IV. p. 129, lines 4, 6*), belonging to a period that is at any rate appreciably later than that of the Early Guptas.

⁵ i.e. "whose fame extended up to the shores of the four oceans."—Jambudvīpa, or the central division of the known world, including India, was supposed to be surrounded on all sides by the ocean.

who was equal to (the gods) [Dhanada and Varuṇa and Indra and Antaka]; who was [the very axe] of (the god) Kṛitānta;¹ who was the giver of [many] millions of [lawfully acquired cows] and gold; [who was the restorer of the *āsvamedha*-sacrifice,² that had been long in abeyance];—

(L. 5.)—Who³ was the son of the son's son of the *Mahārāja*, the illustrious **Gupta**; the son's son of [the *Mahārāja*, the illustrious] **Ghatōtkacha**; (and) the son of the *Mahārājadhīrāja* [the glorious **Chandragupta (I.)**], (and) the daughter's son of **Lichchhavi**, begotten on the *Mahādēvī Kumārādēvi;—*

(L. 11.)—[By him,⁴ the most devout worshipper of the Divine One,⁵ the *Mahārājadhīrāja*, the glorious **Chandragupta (II.)**],

(The rest of the inscription is entirely
broken away and lost.)

¹ *Kṛitānta-parāsu*.—This is another of the formal epithets which are always applied to Samudragupta, and to him only. In the nominative case, *Kṛitānta-parāsuḥ*, it occurs on the reverse of some of his gold coins; see, for instance, *Four. Beng. As. Soc.* Vol. III. Part I. p. 177 f., and Pl. ii. No. 11.

² A ceremony which centred in a horse, and was concluded after the selected steed had been turned loose for a year to roam about at will, guarded by armed men. The ceremony appears to have ended sometimes in the actual immolation of the horse, but sometimes only in keeping it bound during the celebration of the final rites. The successful celebration of a hundred *āsvamedhas* was supposed to raise the sacrificer to a level with the god Indra.—The present epithet, *āsvamedh-dhārtri*, is another of those which are always applied to Samudragupta, and to him only. With it we have to compare the legend *āsvamedha-parākramah*, "he who has displayed prowess by a horse-sacrifice," on some of the gold coins which are attributed to Samudragupta; see, for instance, *Four. Beng. As. Soc.* Vol. LIII. Part I. p. 175 ff., and Pl. ii. No. 9; and *Archæol. Surv. West. Ind. Vol. II.* p. 37 f., and Pl. vii. No. 4

³ i.e. Samudragupta.

⁴ See page 27 above, note 1.


⁵ *paramabhṛgavata*; *lit.* 'a most devout worshipper of (the god) Bhagavat.'—This epithet is supplied from the subsequent inscriptions, and the coins of Chandragupta II. himself.—It is a technical sectarian title, analogous to *paramamhīvara* (e.g. No. 38 below, line 2), *paramasaugata* (e.g. No. 52 below, line 8), *paramavaishnava* (e.g. lines 1 and 1 of the Dighwā-Dubaulf grant of the *Mahārāja* Mahēndrapāla; *Ind. Ant.* Vol. XV. p. 112), *paramapūjapata* (e.g. line 8 of the Verāwal inscription of Arjunadēva; *id.* Vol. XI. p. 242), and *paramadivata* (e.g. line 1 of the Nēpāl inscription of Vasantaśena; *id.* Vol. IX. p. 167, No. 3). Other similar epithets, but not formed in quite the same way, are *paramabrahmanya* (e.g. line 39 of the grant of Amma II.; *id.* Vol. VII. p. 16), *paramādityabhakta* (e.g. No. 38 below, line 10); and *paramabhagavatībhakta* (e.g. lines 1, 1, 3, 3, 6, and 7 of the Dighwā-Dubaulf grant referred to above); also *atyantamhīvara* and *atyantasvāmi-mahābhairavabhakta*, e.g. No. 55 below, lines 9 and 4; and *atyantabhagavadbhakta*, in No. 19 below, line 6, and No. 36, line 4.—*Bhagavat*, 'venerable, revered, sacred, divine, holy,' was used as a title of priests, e.g. lines 5 and 6 of a Paṭṭadakal inscription of Vijayāditya and Vikramāditya II., where it is applied to two *Āchāryas* (*Ind. Ant.* Vol. X. p. 165, No. 101); and also of any saintly personage, e.g. line 12 of No. 23 below, where it is applied to Vyāsa, the arranger of the *Vēdas*. And it was also used as an epithet of any god or object of worship; thus, it is applied to Buddha, in line 6 of No. 62 below; to Viṣṇu, in line 6 of No. 32 below; to Śambhu (Śiva) in line 5 of No. 7 below; to Svāmi-Mahāśena (Kārttikēya), in line 7 of No. 10 below; to Varuṇavāsin (the Sun), in line 13 of No. 46 below; and to Jitēndra, in line 1 of the Aihole Mēguti inscription of Pulikēśin II. (*Ind. Ant.* Vol. VIII. p. 241). But it seems to belong most particularly to the god Viṣṇu (see, for instance, the *Viṣṇu-Purāna*, vi. 5; Hall's edition of H. H. Wilson's Translation, Vol. V. p. 211 ff.), and to denote him whenever there is nothing in the context to give it any other application; and, as well-known instances of its use in this way, we may quote *Bhagavadgītā*, the name of an episode of the Mahābhārata devoted entirely to the subject of devotion to Viṣṇu as Kṛishṇa; *Bhṛgavata*.

A—Mathura Inscription of Chandragupta II



SCALE .27

B—Sanchi Inscription of Chandragupta II—The Year 93



No. 5; PLATE III B.

SANCHI STONE INSCRIPTION OF CHANDRAGUPTA II.

THE YEAR 93.

THIS inscription was first brought to notice in 1834, in the *Four. Beng. As. Soc.* Vol. III. p. 488 ff., where a lithograph of it was published (*id.* Plate xxviii.), reduced by Mr. James Prinsep from a copy by Mr. B. H. Hodgson. This lithograph was not accompanied by any details of the contents of the inscription; and it is a very imperfect one; especially in shewing no traces whatever of the first six or seven letters of each line, all the way down.—And in 1837, in the same Journal, Vol. VI. p. 451 ff., Mr. Prinsep published his reading of the text, and a translation of it,¹ accompanied by a lithograph, reduced from copies on cloth and paper made by Captain Edward Smith, of the Engineers (*id.* Plate xxv.)

Sāñchi, or **Sāchi**,² is a village about twelve miles to the north-east of Diwāṅgañj, the chief town of the Diwāṅgañj Tahsil or Sub-Division of the Native State of Bhōpāl or Bhōpāl³ in Central India. It is sometimes called Sāñchi-Kāñkhēḍā, through its name being coupled with that of another small village immediately on the north of it.

The writing, which covers a space of about 2' 6½" broad by 1' 9" high, is on the outer side of the top rail in the second row, outside and on the south side of the eastern

Purāṇa, the title of one of the Purāṇas, dedicated especially to the glorification of Vishṇu; and *Bhāgavata*, which occurs in line 7 of the Khōh plates of the *Mahārāja Jayanātha* of the year 177, No. 27 below, Plate xvii., and is, to the present time, the name of one of the Vaishnava sects.—It may be taken, therefore, that *Paramabhāgavata* is exclusively a Vaishnava title.

¹ The translation is reprinted in Thomas' edition of Prinsep's *Essays*, Vol. I. p. 246.

² Indian Atlas, Sheet No. 53. Lat. 23° 28' N.; Long. 77° 48' E.—The 'Sachin, Sacha Kana Kheyra, and Sachi Kanakera,' of maps, &c.—The name is pronounced both Sāñchi and Sāchi; but with a preference, as far as my observation went, for the nasalised form. The alternative forms have already been pointed out by Gen. Cunningham in *Bhilsa Topes*, p. 181, where he suggests that the name is most probably only the spoken form of the Sanskrit *sānti*, 'tranquillity, calmness,' &c.—since the term *sānti-samgha*, 'the community of tranquillity,' occurs in the *Aśoka* inscription at Sāñchi (*Bhilsa Topes*, p. 259 ff. and Plate xix. No. 177); and since the Chinese transcribed *sānti* by *sā-chi*. But the ancient name of Sāñchi, at least from the *Aśoka* to the Gupta period, was Kāñkāñḍā (see page 31 below, para. 5); and this seems to indicate that the name Sāñchi is of comparatively modern introduction. Also, though I could not find the places on the map, I was informed that there are at least two other villages in the neighbourhood, named Sāñchi or Sāchi, with no Buddhist remains at them. And thus,—with the analogous names of Kāñchi-Kāñkhēḍā, a village about one and a half miles to the south-west of Sāñchi (in which *kāchi* is either an Urdu, or a Rāṅgañj or local vernacular, word, meaning 'gardener'), and of Māchi, a village somewhere in the same neighbourhood, which I noticed in a local topographical map, but cannot now find again in the Indian Atlas,—suggests that Sāñchi or Sāchi is probably a vernacular name, connected in no way with the Sanskrit.

³ This name is written and pronounced Bhōpāl by Musalmāns, and Bhōpāl by Hindus. It has been suggested that it is a corruption of *Bhōj-pāl*, 'the tank or embankment of king Bhoja.' But I think it is far more likely that the original and correct name is Bhōpāl, from the Sanskrit *bhōpāla*, 'a king, or the king.' The State, however, is a Musalmān State; and Bhōpāl is the form of the name that has been established by long official usage.

gateway of the Great *Stūpa*.¹ The inscription is very well preserved, with the exception that two or three letters are destroyed and quite illegible near the commencement of each line as far as line 8.—The average size of the letters is $\frac{1}{4}$ ". The characters belong to the southern class of alphabets, and approximate most closely to, in the present volume, those of the Mandasōr inscription of Kumāragupta and Bandhuvarman, No 18 below, Plate xi., and, elsewhere, those of the Aihole Mēguṭi inscription² of the Western Chalukya king Pulikēsin II. of Śaka-Saṃvat 556 (A.D. 634-35). They include, in line 11, forms of the numerical symbols for 3, 4, and 90.—The language is Sanskrit; and the inscription is in prose throughout.—In respect of orthography, the only point that calls for notice is the use of the dental *s*, instead of the *visarga* or the *upadhāniya*, in conjunction with *p*, in *yaśas-patīka*, line 4.

The inscription refers itself to the reign of the Early Gupta king Chandragupta II. Its date, in numerical symbols, is the year³ ninety-three (A.D. 412-13), on the fourth day, without any specification of the lunar fortnight, of the month Bhādrapada (August-

¹ *Stūpa*, 'a heap or pile of earth; any heap or pile or mound,' is the technical name of a certain kind of Buddhist monument, consisting of a mound, more or less elaborate, and with or without masonry work, erected over sacred relics of Buddha and his followers.—The English corruption, *Topc*, is from the Prakṛit form *thūpa*.—In the country round Sāñchi, I found the popular term for a *Stūpa* to be *bitā* (Hindī, *bitaurā*), which means literally 'a heap of dried cowdung-cakes to be used as fuel.' The great *Stūpa* at Sāñchi is known as *Sās-bahū kā bitā*, "the heap of dried cowdung-cakes of the mother-in-law and her daughter-in-law." And with this name we may compare *Sās-bahū kā dēhrā*, "the temple of the mother-in-law and her daughter-in-law," which is the popular name of the temple at Gwālior in which there is the long Sanskrit inscription of the Kachchhapaghāta prince Mahāpāla, dated Vikrama-Saṃvat 1150 (*Ind. Ant.* Vol. XV p. 33 ff.)

² *Ind. Ant.* Vol. VIII. p. 241 ff., and the accompanying plate.

³ The text has the abbreviation *sam*, which may stand either for the crude form *samvatsara*, 'a year,' or for any declensional case that can be used in expressing a date (see page 22 above, note 5). The same remark applies to the form *samvat*, which occurs, for instance, in *samvat 100 go 1 Śrāvana ba di 7*, in line 2 of the Éraṇ posthumous pillar inscription of Gōparāja, No. 20 below, Plate xiiiB.—It was formerly thought that the word *samvat* was used only in connection with the Vikrama era commencing B.C. 57. But fuller experience has shewn that both the forms are used freely in respect of the years of any era whatsoever.—They are used sometimes by themselves, as in the present passage, and in the instance quoted above for *samvat*; and sometimes in composition with the name of the era; as, for instance, in the Ambarṇath inscription of the chieftain Māmvāni (*Jour. Bo. Br. R. As. Soc.* Vol. IX. p. 219, and Vol. XII p. 329, l. 1), *Śaka-samvat 782 Jyēshtha śuddha 9 Śukrā*, and in the Sōmnāth-Pāthan inscription of Arjunādēva of Anhilvād (*Ind. Ant.* Vol. XI. p. 242, l. 2 ff.), *Mahamada-samvat 662 tathā śrī-ṅripa-Vikrama-sam 1320 tathā śrī-nad. Valabhi-sam 945 tathā śrī-Simhasam 151 varshē Aśhādha va di 13 Ravasu*.—The form *samvat* represents the genitive plural, *samvatsarānām*, in such passages as *Śaka-ṅripa-kāl-ālitā-samvatsara-satēshv=ashtasu chatur-navaty-adhikēshv=ankatak samvat 894 &c.*, in the Karda grant of the Rāshtrakūṭa king Kakka III (*Ind. Ant.* Vol. XII p. 266, l. 47 f.), as contrasted with *Śaka-ṅripa-kāl-ālitā-samvatsara-satēshv=ashtasu pañcha-pañchāsād-adhikēshv=ankatō=pi samvatsarānām 855 &c.*, in the Sāngli grant of Gōvinda V. of the same dynasty (*id.* Vol. XII. p. 251, l. 44 f.); the latter is the only passage that I know of, in which the full genitive case occurs in connection with the numerals. And it evidently stands for the full locative singular and plural respectively, in such passages as *Samvat pañcha-saptaty-adhika-dvādāsa-sat-ānkē 1275 &c.*, in the Chārwā inscription of Dēvapāla of Dhārā (No. 10 of the separate publications of the Archaeological Survey of Western India, p. 111, l. 4), and in *Śaka-samvat ēka-navaty-adhikana-va-satēshu samvat 991 &c.*, in the Bassein grant of Śēupachandra II. (*Ind. Ant.* Vol. XII. p. 120, l. 24 f.)—Monier Williams, in his Sanskrit Dictionary, gives *samvat* as an indeclinable; and of course it properly is so. I am able, however, to quote two epigraphical instances, of modern date, in which it is used as a declinable; (1) in verse 30 of Dr. Bhagwanlal Indrajī's Nēpāl Inscription, No. 19, of Trāṭajamalla, dated Nēpāla-Saṃvat 778 (A.D. 1658-59); *Nēpālē samvatē=smīn=kaya-giri-munibhik*

September). 't is a Buddhist inscription, and the object of it is to record the grant, by **Amrakārdava** or **Āmrakārdava**, the son of **Undāna**, and apparently an officer of **Chandragupta II.**, of a village, or an allotment of land, called **Īśvaravāsaka**, and a sum of money, to the *Ārya-Saṃgha*, or community of the faithful, at the great *vihāra* or Buddhist convent of **Kākanādabōta**, for the purpose of feeding mendicants and maintaining lamps.

The **Kākanādabōta** convent is, of course, the Great *Stūpa* itself. The name is partially destroyed in the present inscription; but it is legible in full in line 2 of the other *Sāñchi* inscription of the year 131, No. 62 below, Plate xxxviiiB. It is not quite certain what meaning is to be allotted to *bōta* in this name; but it is probably another form of *pōta*, 'the foundation of a house.'¹ The rest of the name, **Kākanāda**, *lit.* 'the noise of the crow,' is the ancient name of *Sāñchi* itself. This is shewn by its occurring in at least two of the inscriptions of the *Aśōka* period in the neighbourhood, to which my attention was directed by Dr. Bhagwanlal Indrajī; thus, (1) an inscription on the outside of the east gate of the great *Stūpa* at *Sāñchi* (*Bhilsa Topes*, p. 241, and Plate xvi. No. 39) should evidently be read *Kākanādyē bhagavato pamāna-lathi*, 'the measuring-staff (?) of (Buddha), the Divine One, at **Kākanāda**;' and (2) the inscription on the top of the lid of the steatite casket found in *Stūpa* No. 2 at 'Andher' (*id. p.* 347, and Plate xxix. No. 7) should plainly be read *Sapurisasa Gōtiputasa Kākanāda-Pabhāsana Kōḍiṇa-gōtasa*, '(the relics) of the virtuous *Prabhāsana* of **Kākanāda**, the *Gōtiputra*, of the *Kauḍiṇya gōtra*.'

TEXT.

- 1 Siddham* [11*] **Kā[kanā]dabōta**-sn-mahā-vihārē śīla-samādhi-prajñā-guṇa-
bhāvit-ēndriyāya parama-puṇya-
2 kri . . . tāya chatur-ddig-abhyāgatāya śramaṇa-puṅgav-āvasathāy-Āryya-
saṅghāya mahārājādhi-
3 rā[ja-ś]r[ī]-**Chandragupta**-pāda-prasād-āpyāyita-ilvita-śādhanaḥ anujīvi-satpurusha-
sadbhāva-
4 vri[ttim(?)] jagati prakhyapayan aneka-samar-āvāpta-vijaya-yaśas-patākha
Sukuli-dēśa-Na-
5 abṭi vāstavya Undāna-putr-**Amrakārdavo** Maja-Śarabhaṅ-
Amrārāta-rājakula-mōlya-kṛ-
6 tam(?) ya . . . **Īśvaravāsaka** pañcha-maṇḍalyā[r*] prapitayā
dadāti pañcha-vimśatis(ñ)-che dānā-

sanjivati &c. (*Ind. Ant.* Vol. IX. p. 191); and (2) in an unpublished *Chamb* inscription which contains several dates in the *Vikrama-Saṃvat* ad *Lōkākṛta*, commencing with *Vikrama-Saṃvat* 1915 (A.D. 1838-59); in line 11 f. we have *Sanjivati 34 Śrāvana-pra^o 17 lat sanjivati 36 ad Śrāvana-suddha* &c.

¹ In the present series of inscriptions, *bōta* or *vōta* occurs again (1) as part of a proper name in *Rākabōta*, in line 8 of No. 27, Plate xvii. below; and (2) as a territorial name, in the *Vōta santika* in line 6 f. of No. 29, Plate xixA. below.—Monier Williams, in his *Sanskrit Dictionary*, gives *pōta*, *bōta*, and *vōta*, in the sense of 'a woman with a beard; a hermaphrodite; a female servant or slave.'—And we have *Bōtaka*, as a proper name, in line 25 of No. 38 below, Plate xxiv.

* From the original stone.

¹ In the original, this word, which is very much damaged and hardly recognisable, stands above the first two *akṣaras* of line 1.

² These two *akṣaras* are supplied from line 2 of the *Sāñchi* inscription of the year 131, No. 62 below, Plate xxxviiiB., in which they are quite distinct.

- 7 rān [I*] Ta[d-da]tta- yād-arddhēna mahārājādhirāja-śrī-
Chandraguptasya Dévarāja itī pri-
8 ya-nām y. tasya¹ sarvva-guṇa-saṃpattayē yāvach-chandr-ādityau
tāvāt-pancha bhikshavó bhūmja-
9 tām ratna-grihē [cha di]pakó jvalatu [I*] mama ch-āpar-ārdhdhāt-pañch-
aiva bhikshavó bhūmjatām ratna-grihē cha
10 dipaka itī [II*] Tad-ētat-pravṛittam ya uchchhindyāt-sa gó-brahma-batyayā
sanyuktó bhavēt-pañchabhiś=ch-āna-
11 ntaryyair=itī [II*] Sam² 90 3 Bhādrapada di³ 4 [II*]

TRANSLATION.

Perfection has been attained! To the community of the faithful⁴ in the holy great *vihāra* of **Kākanādbōta**,—in which the organs of sense (*of the members of it*) have been subdued by the virtues of (*good*) character, religious meditation, and wisdom; which deeds of the very highest religious merit; which has come together from the four quarters of the world; (*and*) which is the abode of most excellent *Śramanas*,—having prostrated himself in an assembly of five persons,⁵ **Amrakārdava**,⁶ the son of Undāna,—whose means of subsistence have been made comfortable by the favour of the feet of the *Mahārājādhirāja*, the glorious **Chandragupta (II.)**; who is publishing in the world the amiable behaviour of the virtuous people who are the dependents (*of the king*); who has acquired banners of victory and fame in many battles; (*and*) who is an inhabitant of (the town of) **Nashti** in the **Sukuli dśa**,⁷—gives (the village or

¹We might very suitably supply the lacunæ by reading *Dévarāja itī priya-nām*=[*dmātyō bhavāt*]=*[ś]tasya*.

²See page 30 above, note 3.

³I.e. *āna*, *dinh*, *divasa*, or *divasā*. And the word properly denotes the solar day, from sunrise to sunrise, with which a week-day name would be coupled; not the lunar *tithi*, which may coincide with, or more or less may differ from, the solar day and week-day.

⁴*Ārya-Saṃgha*.

⁵*pañcha-maṇḍalī* is evidently the same as the *Pañchāli*, *Pañchāyat*, or *Pañch*, of modern times, the village-jury of five (or more) persons, convened to settle a dispute by arbitration, to witness and sanction any act of importance, &c.—Compare *pañchāli* (perhaps a mistake of the engraver for *pañchāli*), which seems to be used in the same sense, in line 16 of Bhagwanlal Indrajī's Nēpāl Inscriptions, No. 10 (*Ind. Ant.* Vol. IX. p. 173).—So also *pañchālika*, in No. 4 of the same series, line 11 (*id.* p. 168), No. 7, lines 13 and 15 (p. 170), and No. 13, line 20 (p. 177), seems to mean the members of certain *Pañchāyats* which are in each instance specified by name.

⁶Or *Amrakārdava*.

⁷*dśa*, 'a region, country, province, &c.' is a technical territorial term, the exact meaning and bearing of which have not yet been determined. So, also, *khaṇḍa*, 'a section'; *maṇḍala*, 'a circle, district, arondissement, province, &c.'; *vāśīśra*, 'a kingdom, district, country, region, &c.'; and *vishaya*, 'a country, region, district, province, &c.'—*dśa* is sometimes used as a synonym of *maṇḍala*. Thus, in line 7 of a grant of Amma II. of about Śaka-Saṃvat 867 or A.D. 945-46 (*Ind. Ant.* Vol. VII. p. 16), and in line 6 of another grant of the same (*id.* Vol. VIII. p. 74), the kingdom of the Eastern Chalukyas is called the *Vengī dśa*. While, in line 17 of a grant of Amma I. (*id.* Vol. VIII. p. 79), and in line 8 of another of Bhīma II. (*id.* Vol. XIII. p. 213), it is called the *Vengī maṇḍala*. These charters record grants made in the Pennātavāḍī, Guḍrāvāra, and Pāgunavara *vishayas*; which would point to *vishaya* being a subdivision of a *dśa* or *maṇḍala*. And this is in accordance with line 5 of the Kapālēsvar grant of Mahā-Bhavadgupta (*id.* Vol. V. p. 55, where the correct reading is *vishayīya-Raṇḍagrāma*), recording a gift of the village of Raṇḍagrāma belonging to the Pōvā or Yōvā *vishaya* in the Kōtālā *dśa*. On the other hand, in line 4 of the Tērdā inscription of Śaka-

allotment of) *Īśavaravāsaka*, purchased with the endowment¹ of Maja and Śarabhaṅga and Amrarāta² of the royal household,³ and (also gives) twenty-five *dāndras*.

(Line 7.)—From [the interest of the *dāndras*⁴] given by him,—with half, as long as the moon and the sun (*endure*), let five *Bhikshus* be fed, and let a lamp burn in the jewel-house,⁵ for the perfection of all the virtues of the familiar name of *Dēvarāja*,⁶ of the *Mahārājādhirāja*, the glorious *Chandragupta* (II.); and with the other

Saṃvat 1046 or A.D. 1124-25 (*id.* Vol. XIV. p. 16), the terms *dēśa* and *viśaya* are both applied to the division of India that is best known as Bharatākhaṇḍa or Bharatākshētra, and also to the Kāṇḍī Three-thousand District in the Kanarese country; which would point to *dēśa* and *viśaya* being synonymous.—*Khaṇḍa* occurs in another grant (unpublished) of Mahā-Bhavgupta, recording a gift of the village of Arkigrāma belonging to the Tulumba *khaṇḍa* in the Kōśala *dēśa*; which points to *khaṇḍa* being a subdivision of a *dēśa*, and perhaps synonymous with *viśaya*.—*Mandala* occurs also in line 8 of the grant of Mahēndrapāla of Harsha-Saṃvat 155 or A.D. 761-62 (*id.* Vol. XV. p. 112), recording the gift of a village belonging to the Vālyikā *viśaya*, which lay in the Śrāvastī *maṇḍala*. And this, again, points to a *maṇḍala* being subdivided into *viśayas*.—As regards *rāshtra* and *viśaya*, there were two classes of officials called *Rāshtrapati* and *Viśayapati*, *lit.* 'lords' or 'chiefs' of *rāshtras* and *viśayas*. And, on the one hand, such passages as those in line 8 f. of the Kaira grant of Vijayarāja of the year 394 (*id.* Vol. VII. p. 248), and in line 8 of the Kāvī grant of Jayabhāta of the year 486 (*id.* Vol. V. p. 114), which mention first the *Viśayapati*, then the *Rāshtrapati*, and then the *Grāmamahattara* or 'village-headman,' point, as indicated by Dr Bühler in editing the Kāvī grant, to the *viśaya* being a larger division than the *rāshtra*; as also such expressions as "the cultivators, headed by the *Rāshtrakūḍja* ('headman of the *rāshtra*'), dwelling in the Pennātavādī *viśaya*," in line 39 f. of the grant of Amma II. of about Śaka-Saṃvat 867, referred to above. But, on the other hand, exactly the opposite of this is indicated by such passages as those in line 28 f. of the Sāmāṅgaḍ grant of Dantidurga of Śaka-Saṃvat 675 or A.D. 753-54 (*id.* Vol. XI. p. 112), in line 35 f. of the Waṇi grant of Gōvinda III. of Śaka-Saṃvat 730 (*id.* Vol. XI. p. 159), and in line 60 of the Kauthēṣ grant of Vikramāditya V. of Śaka-Saṃvat 930 (*id.* Vol. XVI. p. 24), in which first the *Rāshtrapati* is mentioned, then the *Viśayapati*, and then the *Grāmakūta* or 'village-headman.' While finally, such expressions as "the Karmarāshtra *viśaya*," in line 12 of the grant of the second year of Viśhuvardhana II. (*id.* Vol. VII. p. 187), and "the Gōparāshtra *viśaya*," in line 17 of the Nirpaṇ grant of Nāgavardhana (*id.* Vol. IX. p. 124), point to *rāshtra* and *viśaya* being synonymous terms.—The subject requires further elucidation. And, as in the case of regal and official titles, it is much better to use the original Sanskrit words, than to render them by such terms as *Zilla*, *Talukā*, &c., which are of modern invention, and which cannot possibly be satisfactory equivalents, even if they should happen to approach to the relative meanings.

¹ *mūlva*, *lit.* 'an original sum,' is equivalent to *akshaya-nīvī*, *lit.* 'a capital sum that is not to be wasted,' which is of constant use in early inscriptions, and occurs for instance in No. 12, below, Plate viB., line 26, and No. 62, Plate xxxviiiB., lines 3 and 8.

² Or *Āmrarāta*. *rājakula*.

³ I supply these words, where the original has been effaced, on the analogy of line 3 f. of the Śāśchi inscription of the year 131, No. 62 below, Plate xxxviiiB.

⁴ This is the literal meaning of *ratna-griha*. It seems to denote the *Stūpa* itself, as the abode of the three *ratnas* or 'jewels or precious things,' *vis.* (1) Buddha, (2) *Dharma*, the Law or Truth, and (3) *Saṃgha*, the community or congregation.

⁵ Prinsep translated this passage so as to make *Dēvarāja* another name of Chandragupta II. This may be correct. But we have no other authority for giving him this second name. And the lacunæ in the line render it impossible to say with any certainty whether it denotes him, or some officer of his.—If the suggestion that I have made above (page 32, note 1) for filling up the lacunæ, should be accepted, the translation would be—"for the perfection of all the virtues of him who, having the familiar name of *Dēvarāja*, is a minister of the *Mahārājādhirāja*, the glorious Chandragupta."

half, which is mine,¹ let the same number of five *Bhikkhus* be fed, and (*let*) a lamp (*burn*), in the jewel-house.

(L. 10.)—Whosoever shall interfere with this his arrangement,—he shall become invested with (*the guilt of*) the slaughter of a cow or of a Brahman,² and with (*the guilt of*) the five sins that entail immediate retribution!³

(L. 11.)—The year 90 (*and*) 3; (the month) Bhādrapada; the day 4.

No. 6; PLATE IVA

UDAYAGIRI CAVE INSCRIPTION OF CHANDRAGUPTA II.

THIS inscription appears to have been discovered by General Cunningham, and was first brought to notice by him in 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 51 f., where he published his own version of the text, and a translation of it by Rājā Siva Prasad, accompanied by a lithograph (*id.* Plate xix.).—This rendering of the inscription has remained the standard version up to the present time, except that in 1882, in the *Ind. Ant.* Vol. XI. p. 312, Dr. E. Hultzsch pointed out some errors in the last line as published.

The inscription is on the back wall, a little to the left as one enters, inside a cave at **Udayagiri**,⁴ in Scindia's Dominions in Central India, which is known as the "Tawā Cave," from the resemblance of the large flat stone, on the top of the rock in which it is excavated, to a gigantic *tawā*, or 'griddle for baking cakes.

The writing, which covers a space of about 3' 7" by 1' 2", has suffered a good deal from the peeling off of the surface of the rock on which it is engraved; but the general purport of it remains complete, and nothing of a historical nature appears to have been lost.—The size of the letters varies from $\frac{3}{4}$ " to $1\frac{1}{4}$ ". The characters belong to the northern class of alphabets, and are of radically the same type with those of the Allahābād posthumous pillar inscription of Samudragupta, No. 1, p. 1 ff. above, Plate i. They include in the numbering of the verses, forms of the numerical symbols for 1, 2, 3, 4, and 5.—The language is Sanskrit; and, except for the opening word *siddham*, the inscription is in verse throughout, and the verses are numbered.—In respect of orthography, the only point that calls for notice is the use of the *jikhvāmāliya* and *upadhāntiya* in *śāh-kaviḥ-pāṭali*, line 4.

The inscription refers itself to the time of the Early Gupta king Chandragupta II., whose name is recorded in line 1. As no date is given, there might be some doubt as to whether the Chandragupta mentioned here is the first or the second of the name. But the standard of the characters, as compared with those of the Allahābād inscription, which was engraved in the time of Chandragupta II.,—and the fact that the inscripitor records that the Chandragupta mentioned in it came in person to Udayagiri, coupled with the existence at Udayagiri of the inscription of the year 82, No. 3, p. 21 ff. above, which

¹ It is not quite apparent who is speaking here; but probably Amrakārdava is intended.

² *brāhman*; see Childers' Pāli Dictionary, s.v. *brāhmd*.

³ *viz.* matricide, parricide, killing an *Arhat*, shedding the blood of a Buddha, and causing division among the priesthood (see Childers' Pāli Dictionary, s.v. *pañchanantariyarammam* and *abhihāṇam*.)

⁴ See page 22 above, and note 1.

is proved by its date to be one of Chandragupta II.,—shew that the king mentioned here is **Chandragupta II.**, not his grandfather, Chandragupta I. It is a Śaiva inscription; and the object of it is to record the excavation of the cave as a temple of the god Siva, under the name of Śambhu, by the order of a certain **Virasēna**, otherwise called **Śāba**,¹ who was one of the ministers of Chandragupta II

TEXT.²

- 1 Siddham³ [II*] Yad⁴-a[m]tarjyōtir-arkk-abham-urvyām [— — — — —
— — — — —]vyāpi **Chandragupt-ākhyam-adbhumam** [II*] 1
- 2 Vikram-āvakra-ya-krtā dāśya-nyagbhūta-pārtthiv[ā] [— — —]māna-sahraktā
dharmma[— — — — —] [II*] 2
- 3 Tasya rājādhiraj-arshēr-achinty-ō[— — —]rmanah anvaya-prāpta-sāchivyo
vyā[priya-san]dh[i]-v[i]grahah [II*] 3
- 4 Kautsā-Śāba iti khyātō Virasēnah kul-ākhyayā śabdārtha-nyāya-lōka-
jñāh-kaviḥ-Pāṭaliputrakah [II*] 4
- 5 Kritsna-prithvi-jay-artthēna rājñ-aiv-ēha sah-āgataḥ bhaktyā bhagavataś-
Śambhōr-gguhām-ētām-akārayat [II*] 5

TRANSLATION.

Perfection has been attained! which shines⁵ like the sun,⁶ radiant with internal light, upon the earth, pervades (and) has the appellation of **Chandragupta (II.)**, (and is) wonderful ;—

(Line 2.)—Bought by the purchase-money of [whose] prowess, [the earth], in which (all other) princes are humiliated by the slavery (imposed on them by him), gratified by religion.

(L. 3.)—He who holds the position, acquired by hereditary descent, of being a minister of that same saintly sovereign,⁷ possessed of inconceivable, (and) [has been appointed to] (the office of *arranging*) peace and war; (vis.)—

¹ See page 27 above, note 4, for some similar instances of second names.

² From the original stone.

³ In the original this word stands in the margin, opposite the commencement of line 3.

⁴ Metre, Ślōka (Anuṣṭubh) throughout.

⁵ From the use, in line 5, of the imperfect past tense *akārayat*, 'he caused to be made,'—and from the natural length of time required for the completion of the cave, before the inscription could be engraved inside it,—a considerable time must have elapsed between the visit of the king and his minister, and the engraving of the inscription. But there seems no special reason for supposing that the work was not all finished during the lives of Chandragupta II. and Virasēna. Accordingly, in translating, I have given a present sense to the contents of lines 1 to 4.

⁶ There seems to be intended a play on the words 'sun' and 'moon,' the latter of which (*chandra*) forms part of the king's name.

⁷ *Rājādhirāja*; *lit.* 'supreme king of *Rājas* or kings.'—This was, in earlier times, one of the technical titles of paramount sovereignty. In its Pāli or Prākṛit form of *Rajadhiraja*, it occurs as the representative of the Greek *basileus basiloon*, sometimes by itself, e.g. on some of the coins of Maues (Gardner and Poole's *Catalogue of the Coins of the Greek and Scythic Kings of India in the British Museum*, p. 68 ff., Nos. 4, 5, 9, 11, and 17); and sometimes in conjunction with *Maharaja* (*Mahārāja*), e.g. on some of the coins of Ases (*id.* p. 85 ff., Nos. 138, 140, and 157). And another almost identical title, *vis. Rājātirāja, lit.* 'superior king of *Rājas* or kings,' occurs in the same

(L. 4).—He who, belonging to the Kautsa (*gōtra*) is well-known under the name of Śāba, (*but is called*) Virasēna by (*his*) family-appellation;—who knows the meanings of words, and logic, and (*the ways of*) mankind;—who is a poet;—and who belongs to (*the city of*) Pātaliputra,—

(L. 5).—He came here, accompanied by the king in person, who was seeking to conquer the whole world; and, through devotion towards the divine (*god*) Śambhu, he caused this cave to be made.

No. 7; PLATE IVB.

GADHWA STONE INSCRIPTION OF CHANDRAGUPTA II. THE YEAR 88.

THIS inscription, and the following two inscriptions of Kumāragupta, Nos. 8 and 9, are on a stone that was discovered in 1871-72 by Rājā Siva Prasad, and were first brought to notice by General Cunningham in his Archæological Reports.

Gadhwa,¹ which means literally 'a fort,' is the name of several villages in the Arail and Bārā Parganās in the Karchhanā Tahsil or Sub-Division of the Allahābād District in the North-West Provinces. The particular **Gadhwa**, where these inscriptions were found, is in the Bārā Parganā, eight miles to the west by south from Bārā, and one and a half miles south of the village of Bhatgaḍh.² It is entered in the map simply as a "Fort."³ The stone containing the inscriptions was found built into the wall of one of the rooms of a modern dwelling-house inside the enclosure of the fort; and is a rectangular sandstone fragment, measuring about 9½" broad by 4" thick and 2' 6¼" high. It is now in the Imperial Museum at Calcutta.

The stone is inscribed on three faces,—on the front, as it stands in the Museum, and on the two sides. It is entire towards the bottom; but the top of it, containing two or three lines of writing, has been broken away and lost. In addition to this, the sides now contain only about half of each line of the inscriptions engraved on them; and this, with the unfinished roughness of the present back of the stone, shews that about half of it has been pared away, in adapting it to some other purpose than that for which it was originally intended.

sense of paramount sovereignty, but coupled also with *Mahārāja*; e.g. in the Mathurā inscription of Hōvishka of the year 47 (*Archæol Surv. Ind.* Vol. III. p. 33, No. 12, and Plate xiv.), and in the Mathurā inscription of Vasudēva of the year 87 (*id.* p. 35, No. 18, and Plate xv.). But, by the Early Gupta period, these two titles appear to have been permanently supplanted, for technical purposes, by the fuller form of *Mahārājādhirāja* (see page 10 above, note 3). The form *Rājādhirāja* cannot be traced at all. And *Rājādhirāja* occurs only in metrical passages, where it was inconvenient or impossible to introduce the prefix *mahā*; thus, in addition to the present passage, in line 6 of the Mandasōr inscription of Yasōdharman and Vishṇuvardhana, No. 35 below; in line 62 of the Alfnā grant of Śīlāditya VII., No. 39 below; and, in the derivative *rājādhirājya*, in line 24 of the Junāgaḍh rock inscription of Skandagupta, No. 14 below, in line 2 of which we also have, again for metrical reasons, another variety of the title, viz. *Rājādhirāja*.


¹ The 'Garhwa' and 'Gurhwa' of maps, &c.

² The 'Barah' of maps.

³ The 'Badgarh, Bhatgarh, and Budgudh' of maps, &c.


⁴ Indian Atlas, Sheet No. 88. Lat. 25° 13' N.; Long. 81° 38' E.

A.—Udayagiri Cave Inscription of Chandragupta II




SCALE .14


B.—Gadhwa Inscription
of Chandragupta II
The Year 88



C.—Gadhwa Inscription
of Kumaragupta



D.—Gadhwa Inscription
of Kumaragupta
The Year 98



On the front of the stone, towards the top, traces are visible of eleven lines of writing, each of about thirteen letters, in characters of the same period with those of the inscriptions that I now publish. But no part of this inscription, which seems to have been quite distinct from those on the sides, can be read; and the traces of it that remain are not worth being lithographed.

The inscription of Chandragupta II. now published, is on the upper part of the present proper left side of the stone, and the writing covers a space of about 4" broad by 1' 4½" high. It was originally brought to notice, in 1873, by General Cunningham, who published his reading of the text of lines 10 to 17 in the *Archæol. Surv. Ind.* Vol. III. p. 55, with a lithograph of the whole (*id.* Pl. xx. No. 1). The first two entire lines, and the last half of each of the remaining lines, have been broken away and lost. The remnant of the inscription, however, is fairly well preserved and easy to read.—The average size of the letters is $\frac{1}{8}$ ". The characters belong to the northern class of alphabets, and are of the same type with those of the Allahâbâd posthumous pillar inscription of Samudragupta, No. 1, p. 1 ff. above, Plate i. They include, in lines 11, and 16, forms of the numerical symbols for 8, 10, and 80.—The language is Sanskrit; and the inscription is in prose throughout.—In respect of orthography, the only point requiring notice is the doubling of *y* and *v* after the *anusvâra*, in *samyukta*, line 9, and *samvatsarâ*, line 11.

In the first part of the inscription, lines 1 to 9, the date and the name of the king are entirely broken away and lost. So also the name in the second part. But, in the latter part, lines 10 to 17, we have the date, in numerical symbols, of the year eighty-eight (A.D. 407-8). And this, coupled with the epithet *paramabhâgavata* in line 10, followed by the beginning of the title *Mahârâjâdhirâja*, shews that the inscription, in this part, certainly belongs to the time of the Early Gupta king Chandragupta II. And the first part is so plainly engraved by the same hand,—and is, moreover, not separated by any dividing line,—that it must certainly be allotted to the same reign. So little remains of the two parts of this inscription, that the form of religion to which they belong cannot be determined; nor can the object of them; except that each part records a gift of ten *dândras*, apparently as a contribution to the perpetual maintenance of a *saltra*, or charitable hall or almshouse.

In line 12 we have a mention of the city of *Pâtaliputra*, the modern *Patna* in Bihâr; but there is nothing to indicate, of necessity, that it is mentioned as a capital of Chandragupta II.

TEXT.¹

First Part.

- 1 [Paramabhâgavata²-mahârâjâdhirâja-śrî-Chandragupta-râjya]-
 2 [samvatsarâ]³ [asyârah]
 3 divasa-pûrvvâyâh⁴

¹ From the original stone.

² This first line is entirely broken away and lost; but, from the date in line 11, there can be no doubt that the name and titles of Chandragupta II. have to be filled in here, as also in line 10.—In the second line, remnants are visible of the first four or five *aksharas*, including one or two numerical symbols; but not enough of them remains to shew with any certainty what the latter are.

³ To be corrected into *râjyâ samvatsarâ*; see page 38 below, note 3.

⁴ Supply *tithau*.

- 4 ka-Mātrīdāsa-pra[mukha] [puṇy-ā]-
 5 pyāyan-ārttham rachi[ta] [sa]-
 6 dā-sat[t^o]ra-sāmānya(nya)-brāhma[ṇa]
 7 dīnārair-ddaśabhiḥ 10 [11]
 8 Yas-ch-ainam dharmma-skanda(ndha)¹m [vyuchchindyāt-sa
 pañcha-mahāpātakaiḥ sam]-
 9 yyukta[h^o] syād-iti 1(11)

Second Part.

- 10 Paramahāgavatā - mahā[rājādhirāja - śrī - Chandragupta - ra] -
 11 jya-samvatsarē² 8o 8 [asyāṁ divasa]-
 12 pūrvvāyām³ Pātā(talīput[ti]ra [grī]-
 13 hasthasya bharyā y
 14 .-ātma-puṇy-ōpachay-[ārttham]
 15 sadā-sattra-sāmānya-b[rāhmaṇa]
 16 dīnārāḥ daśa 10 [11] [Yas-ch-ainam
 17 dharmma-skanda(ndha)n. vyuchchindyāt-t-sa pañcha
 mahāpātakaiḥ samyuktaḥ syād-iti [11]

TRANSLATION.

First Part.

[In the reign of the most devout worshipper of the Divine One, the *Mahārājādhirāja* the glorious **Chandragupta (II.)**; in the year] ;
 [on this] (*lunar day*), (*specified*) as above by the day (*&c.*):—

(Line 3).— headed by Mātrīdāsa for the purpose of
 increasing [the religious merit] fashioned the Brāhmaṇa
 of the community of a perpetual almshouse by ten *dānāras*, (*or in
 figures*) 10.

(L. 8).—*Āna* whosoever [shall interfere with] this branch of religion,—[he] shall
 become invested [with (*the guilt of*) the five great sins⁴] |

Second Part.

(L. 10).—In the reign⁵ of the most devout worshipper of the Divine One, the
Mahārājādhirāja, [the glorious **Chandragupta (II.)**]; in the year 80 (*and*) 8;
 [on this] (*lunar day*), (*specified*) as above [by the day, (*&c.*):—

¹ In line 17 below, the reading is again *skandam*. But this is undoubtedly a mistake for *skandham*, which we have distinctly in the same imprecation in line 12 of the Gadhwa inscription, No. 64 below, Plate xxxixB. — We also have a similar expression, *puṇya-skandham*, in line 9 of the Kahānā pillar inscription of Skandagupta, No. 15 below, Plate ixA.

² Read *rdjyā samvatsarē*; see note 5 below.

³ Supply *tithau*.

⁴ The *pañcha mahāpātānāni*, or 'five great crimes, are—slaying a Brāhmaṇ; drinking intoxicating liquor; theft (of the gold belonging to a Brāhmaṇ); adultery with the wife of a spiritual preceptor; and associating with any one guilty of these crimes; see the *Mānavadharmasūtra*, ix. 235, and xi. 55 to 59; Burnell's Translation, pp. 287, 331.

⁵ The original, if accepted as it stands, would have to be translated "in the year eighty-eight of the reign of Chandragupta." But the numerals, both here and in the still more pointed instances given below, show that the expression cannot possibly refer to regnal years.—This method of expres-

(L. 12.)—..... **Pāṭaliputra** the wife of the householder [for the purpose] of adding to (*her*) own religious merit the Brahmins of the community of a perpetual almshouse ten *dīndras*, (or in figures) 10.

(L. 16.)—[And whosoever] shall interfere with [this] branch of religion,—[he shall become invested with (*the guilt of*) the five great sins]!

No. 8; PLATE IV C.

GADHWA STONE INSCRIPTION OF KUMARAGUPTA.

THIS is another of the inscriptions on the stone discovered by Rājā Siva Prasad, in 1871-72, at **Gadhwa**,¹ in the Allahābād District in the North-West Provinces. It was first brought to notice, in 1873, by General Cunningham, who published his reading of the text in the *Archaeol. Surv. Ind.* Vol. III. p. 55, accompanied by a lithograph (*id.* Plate xx. No. 1).

This inscription is on the lower part of the proper left side of the stone, immediately below the preceding inscription of Chandragupta II., No. 7 above, from which it is separated only by a line across the stone.

The last half of each line has been entirely broken away and lost. The remnant of the **writing**, however, covering a space of about 4" broad by 10" high, is fairly well preserved and easy to read.—The average **size** of the letters is about $\frac{1}{4}$ ". The **characters** belong to the northern class of alphabets, and are of precisely the same type as those of the preceding inscription, No. 8, being probably engraved by the same hand. They include, in lines 3 and 6, forms of the **numerical symbol** for 10.—The **language** is Sanskrit; and the inscription is in prose throughout.—The **orthography** presents nothing calling for remark.

The **inscription** refers itself to the reign of the **Early Gupta** king **Kumāragupta**. The date, however, except in respect of the day, is broken away and lost. So little remains of the inscription that the form of religion to which it belongs cannot be determined; nor can the object of it; except that it seems to record two gifts,—one of ten *dīndras*, and

sion was a very common one in early times; and is due, of course, to the fact that the early years of most eras were regnal years, and that, after the death of the founder of each era, the expression was continued mechanically in the case of his successors.—As similar instances, we have in the present series of inscriptions, (1) line 6 of the Bilsāḍ pillar inscription of Kumāragupta, No. 19 below, Plate v., "in the year ninety-six of the augmenting victorious reign of Kumāragupta;" (2) line 3 of the Indōr grant of Skandagupta, No. 16 below, Plate ix B., "while the year one hundred, increased by forty-six, of the augmenting victorious reign of Skandagupta, is current;" and (3) line 1 of the Gadhwa inscription of the year 148, No. 66 below, Plate xxxix D., "in the year one hundred, increased by forty-eight, of the augmenting victorious reign of;" and in other series, (4) line 2 f. of the Gānda inscription of Rudrasīkha (*Ind. Ant.* Vol. X. p. 157), "in the year one hundred, increased by two, or in figures 100 and 2, of the *Mahākshatrapa*, the *Sodmin* Rudrasīkha;" and (5) line 1 of a Mathurā inscription of Vāsudēva (*Archaeol. Surv. Ind.* Vol. III. p. 35, and Pl. xv. No. 20), "in the year 90 and 8 of king Vāsudēva."—In every passage like those of this series, a suitable expression and translation are at once arrived at by the very simple emendation of reading *rājya-samvatsarī* instead of *rājya-samvatsarī*.

¹ See page 36 above, and note 1.

the other of an uncertain number,—as a contribution to the perpetual maintenance of a *sattra*, or charitable hall or almshouse.

TEXT.¹

1	Jitañ bhagavatā	Pa[ramabhāgavata ² -mahārājādhirāja]-
2	śrī-Kumāragupta-rājya-[samvatsarē ³]
3	divasē 10 [asyāñ divasa-pūrvvāyām]
4
5 sadā-sat[t*]ra-sā[mānya]
6	[da]ttā dīnārāñ 10 ta(?)
7	ti sattre cha dīnārās=tray ⁴ [II]
	[Yāś=ch=ainam dharmma-skandham vyuchchhi]-	
8	ndyāt=sa pañcha-mahāpā[takaiñ samyuktah syād=iti	[II]
9	Gōyindā Lakshmā

TRANSLATION.

Victory has been achieved by the Divine One! In the reign⁵ of [the most devout worshipper of the Divine One, the *Mahārājādhirāja*], the glorious **Kumāragupta**; [in the year]; on the day 10, [on this (*lunar day*), (*specified*) as above by the day (&c.)]:—

(Line 3.)—..... [the community of] a perpetual almshouse there were given ten *dīnāras* and in the almshouse three *dīnāras*

(L. 7)—[And whosoever shall interfere with this branch of religion],—he [shall become invested] with (*the guilt of*) the five great sins!

(L. 9)—Gōyindā, Lakshmā,

No. 9; PLATE IVD.

GADHWA STONE INSCRIPTION OF KUMARAGUPTA.
THE YEAR 98.

THIS is the last of the inscriptions on the stone discovered by Rājā Siva Prasad, in 1871-72, at **Gadhwa**⁶ in the Allahābād District in the North-West Provinces. It was not noticed when the stone was first discovered; but was afterwards found, on clearing away the lime under which it was hidden, by General Cunningham, who then, in 1880, published his reading of the text in the *Archæol. Surv. Ind.* Vol. X. p. 9, with a lithograph (*sd.* Plate v. No. 1.)

¹ From the original stone.

² This epithet is completed from line 5 of the Bilsad pillar inscription of Kumāragupta, No. 10 below, and line 5 f. of the Bhitār pillar inscription of Skandagupta, No. 13 below.

³ Read *rājyē* [*samvatsarē*]; see page 38 above, note 5.

⁴ This may be completed into either *trayaś*, *trayōdaśa*, *trayōvīñśati*, or any other numeral commencing with *trayaś*.

⁵ See page 38 above, note 5.

⁶ See page 36 above, and note 1.

This inscription is on the upper part of the proper right side of the stone. Almost the whole of the first line, and the first half of each of the remaining lines, has been entirely broken away and lost. The remnant of the **writing**, however, covering a space of about 4" broad by 9" high, is fairly well preserved and easy to read.—The **size** of the letters varies from $\frac{1}{4}$ " to $\frac{1}{2}$ ". The **characters** belong to the northern class of alphabets, and are of precisely the same type as those of the preceding two inscriptions, Nos. 7 and 8, being probably engraved by the same hand. They include, in the date, forms of the **numerical symbols** for 8 and 90.—The **language** is Sanskrit; and the inscription is in prose throughout.—The **orthography** presents nothing calling for remark.

The name of the king is broken away and lost in the first half of line 2. But the **inscription** is dated, in numerical symbols, in the year ninety-eight (A.D. 417-18); and this shews that the record must belong to the time of the **Early Gupta** king **Kumâragupta**. So little remains of it, that the form of religion to which it belonged, cannot be determined; nor can the object of it; except that it records a gift of twelve *dîndras*, apparently as a contribution to the perpetual maintenance of a *sattra*, or charitable hall or almshouse.

TEXT.¹

1	[Jitam bhagavatâ Para]mabh[â]gavata-[mahârajâdhi]-
2	[râja-âri-Kumâragupta-râjya-samvatsa]rê ² 90 8
3 [asyâm divasa]-pûrvvâyâ ³ m ⁴ patâ
4 né(?)n-âtma-puny-ôpa[cha]-
5	[y-ârttham] kâltyam sadâ-sat[t]ra-
6 kasya talakanivansê(?) ..
7 tya(?)m dînârâh dvâdaśa
8 sy-âmkur-ôdbha(?)sta-chchha
9 [sam]yukta[h ⁵] ⁶ syâd=iti 1(11)

TRANSLATION.

[Victory has been achieved by the Divine One!] [In the reign⁷] of the most devout worshipper of the Divine One, [the *Mahârajâdhirâja*, the glorious **Kumâragupta**]; in the year 90 (and) 8;; [on this] (*lunar day*), (*specified*) as above by the day (&c.);—

(Line 3)— [for the purpose] of adding to (*his*) own religious merit (*to endure*) for the same time with
a perpetual almshouse twelve *dîndras*

(L. 9.)— shall become invested with

¹ From the original stone.

² To be corrected into *râjya samvatsarâ*; see page 38 above, note 5.

³ Supply *tîkshu*.

⁴ The measure of the lines of this inscription seems to shew that it did not contain here the full formula of the preceding two, Nos. 7 and 8.

⁵ See page 38 above, note 5.

No. 10; PLATE V.

BILSAÐ STONE PILLAR INSCRIPTION OF KUMARAGUPTA.
THE YEAR 96.

THIS inscription was discovered in 1877-78 by General Cunningham, and was first brought to notice by him in 1880, in his reading of the text, and translation of it, published in the *Archæol. Surv. Ind.* Vol. XI. p. 19 f., accompanied by a lithograph (*id.* Plate viii.)

Bilsaḍ or **Bilsaṇḍ**¹ is a village,—consisting of three parts, called respectively Bilsaḍ-Puvāyām, or Eastern Bilsaḍ; Bilsaḍ-Pachhayām, or Western Bilsaḍ; and Bilsaḍ-Patti,² or Bilsaḍ Suburb,—about four miles towards the north-east of Allgañj,³ the chief town of the Allgañj Tahsil or Sub-Division of the Ēṭā⁴ District in the North-West Provinces. At the south-west corner of Bilsaḍ-Puvāyām, or the eastern division of the town, there are four broken red-sandstone monolith columns,—two of them, towards the west, round; and two of them, towards the east, square. Each pair of columns stands almost due north and south; and the two western columns are both inscribed. The inscription now published is on the eastern side of the northern column of the west pair.

On the eastern side of the southern column of the west pair, there is also an inscription, which, as shewn by the remains of it, was a duplicate copy of that on the northern column; but it was arranged somewhat differently, being, as counted by General Cunningham, in sixteen somewhat shorter lines, instead of thirteen. From General Cunningham's ink-impression, hardly any appreciable portion of this second inscription remains, except the second and third lines, and lines 12 to 16; and these are not in sufficiently good order to be lithographed, though they are of use in supplying more clearly a few letters which are doubtful in the two verses at the end of the inscription on the northern column. In this second inscription, line 2 begins with the *svādīta-yasasō* of line 1 of the one now published;—line 3, with the *gat-ānka* of line 2;—line 12, with about the *parshadd* of line 9;—line 13, with the *kaubērachchanda* of line 10;—line 14, with the [*sa*]ṭra of line 11;—line 15, with the . . . *subhā* of line 12;—and line 16, with the *yēn-āpūruva* of line 13.

With this pair of duplicate inscriptions, we may compare the duplicate inscriptions of Yaśódharman on the two columns at Mandasōr, Nos. 33 and 34 below. But Yaśódharman's pillars were *jayastambhas* or 'columns of victory,' not connected with any building; whereas the two inscribed Bilsaḍ pillars seem to have had a direct connection with a temple, now ruined, the remains of which must be hidden under the rubbish that has accumulated over the site,—*viz.* the temple of the god Svāmi-Mahāsēna, or Kārttikēya, referred to in the inscription.

The writing of the inscription now published covers a space of about 2' 1½" broad by 1' 10½" high. The first four lines are almost entirely destroyed, and a good deal of

¹ The 'Beelsur and Bilsar' of maps, &c. Indian Atlas, Sheet No. 68. Lat 27° 33' N.; Long. 79° 16' E.—The name is written and pronounced optionally with or without a nasal in the second syllable; compare Aphaḍ, and Aphaṇḍ, in the case of the inscription of Ādityasēna, No. 42 below.

² The 'Beelsurpowa, Beelsurpucha, and Beelsurputtee,' of maps.

³ The 'Alliganj and Ulleegunje' of maps, &c.

⁴ The 'Ēeta, Etah, and Eytuh,' of maps, &c.

damage has been done to the rest; but nothing of a historical nature seems to have been lost.—The average size of the letters is about $\frac{1}{4}$ ". The characters belong to the northern class of alphabets; but they present a very pointed difference from the characters of the same class in the preceding inscriptions, in respect of the very marked *mātrās* or prolonged horizontal top-strokes of the letters.—The language is Sanskrit; and the inscription is in prose as far as the end of line 9, and the rest in verse.—In respect of orthography, the only point that calls for notice is the doubling of *t*, in conjunction with a following *r*, e.g. in *puttrasya*, line 4.

The inscription refers itself to the reign of the Early Gupta king Kumāragupta. It is dated, in words, in the year ninety-six (A.D. 415-16), but without any specification of the month and day. It belongs to the Saiva form of worship; and the object of it is to record the accomplishment by a certain Dhruvaśarman, at a temple of the god Kārttikēya under the name of Svāmi-Mahāsēna, of certain works, viz. (1) the building of a *pratāḥī*, or 'gateway with a flight of steps,' (2), the establishment, apparently, of a *sattra* or chantable hall or almshouse; and (3) the erection of the column with the inscription on it, to record the above acts.

TEXT.¹

- 1² [Sarvya-rāj-ōchchhētṭuṇ prithivyām-a-pratirathasya chatur-uda]dhi-
salil-āsvādita-yaśasō
2 [Dhanada-Varuṇ-Ēndr-Āntaka-samasya Kṛitānta-paraśōh nyāy-āgat-Ānēka-gō-
hī]raṇya-kōṭi-pradasya chir-ōtsann-āsvamedh-āharttuḥ
3 [mahārāja-śrī-Gupta-prapauttrasya mahārāja-śrī-Ghaṭōtkacha-pauttrasya ma]hā-
rājādhirāja-śrī-Chandragupta-puttrasya
4 Lichchhavi-dauhi[ti]r[asya mahādēvyām Kumāradēvyām-utpannasya
mahārā]jādhirāja-śrī-Samudragupta-puttrasya⁴
5 mahādēvyām Dattadēvyām-utpannasya svaya[m-a-pratirathasya] [parama]-
bhāgavatasya mahārājādhirāja-śrī-Chandragupta-puttrasya⁵
6 mahādēvyām Dhruvadēvyām-utpannasya mahārājādhirāja-śrī-Kumāra-
guptasy-ābnivarddhamāna-vijaya-rājya-samvatsarē⁶ śhaṇ-navatē [1*]

¹ As pointed out by Gen. Cunningham, *pratāḥī*, according to the Dictionaries, means 'a broad way; a high-street; a principal road through a town.' But the meaning of 'gateway' was given to him by a Paṇḍit. And that the word has the meaning in the present inscription of 'a gateway with a flight of steps,' seems to be shewn by the comparison of the *pratāḥī* with a *svarga-spānd* or 'flight of steps, or ladder, leading to heaven,' and by its being described as "white with the radiance of pieces of crystalline gems (in the stones of which it was constructed)."

² From Gen. Cunningham's ink-impression; so also the lithograph. The passages that are illegible in lines 2 to 3 are supplied from No. 1, lines 24, 26, 28, and 29, page 8 above, and from the Bhitārī pillar inscription of Skandagupta, No. 13 below, Plate vii., lines 1 to 3.

³ Probably *siddham* stood here.

⁴ Read *Samudraguptasya puttrasya*, the separate genitive *Samudraguptasya* being required in apposition with the genitives ending in *prapauttrasya*, *pauttrasya*, *putrasya*, *dauhitrasya*, and *utpannasya*, in line 3 i.—Here, and in line 5, the drafter of the inscription seems to have been led into his mistake through following blindly the *Chandragupta-puttrasya*, which is quite correct, at the end of line 3.

⁵ Read *Chandraguptasya puttrasya*, the separate genitive *Chandraguptasya* being required in apposition with the genitives *utpannasya*, *apratirathasya*, and *paramabhāgavatasya* in this line.—See the preceding note.

⁶ Read *rājyē samvatsarē*, see page 38 above, note 5.

- 7 *Asyān=divasa-pūrvvāyām¹ bhagavatas=trailōkya-tē;as=sambhāra-samtat-ādbhuta-mūrttēr=Brahmaṇya-dēvasya*
- 8 *nivāsinaḥ Svāmi-Mahāsēnasy-āyatanē=smin=Kārttayug-āchāra-saddharma-vartm-ānuṣāyina* ,
- 9 . *āta* [pa]rshadā mānitēna **Dhruvaśarmmaṇa**
karma mahat-kṛit-ēdam² I(II)
- 10 *Kṛit[v]ā³ [— — ā]bhīrāmān muni-vasati[∪ —] svargga-sōpana-r[ū]pām I⁴ kaubērachchhanda-bimbām sphāṭika-maṇi-dal-ābhāsa-gaurām⁵ prāṭōllm I*
- 11 *pr.sād-āgr-ābhīrōpaḥ guṇa-vara-bhavanān [dharmma-sa(?)]ttram yathāvat I punyēshv-ēv-ābhīrāmān vrajati śubha-matis-tāta-Śarmma⁶ dhruvō-stu I(II)*
- 12 *[—]ā[—][—]sya⁷ [∪ —]śubh-āmṛita-vara-prakhyāta-labdhā bhui I [—]ē[—]ē bhaktir-ahna-sat[t⁸]va-samatā kas-tam na sampūjyēt I*
- 13 *yēn-āpūrvva⁹-vibhūti-sañchaya-chayaiḥ [—]ai[—][∪ — — ∪ —]ḥ I tēn-āyam Dhruvaśarmmaṇā¹⁰ sthira-varas¹¹-[st]ambh-ōch[chr]ayaḥ kāritaḥ I(II)*

TRANSLATION.

(Line 6).—In the ninety-sixth year, (*and*) in the augmenting victorious reign⁹ of the *Mahārājādhirāja*, the glorious **Kumāragupta**,—

(L. 5).—Who is the son, begotten on the *Mahādēvī Dhruvadēvī*, of the *Mahārājādhirāja*, the glorious **Chandragupta (II.)**, who was himself without an antagonist (*of equal power*); who was a most devout worshipper of the Divine One; (*and*)

(L. 4).—Who¹⁰ was the son, begotten on the *Mahādēvī Dattadēvī*, of the *Mahārājādhirāja*, the glorious **Samudragupta**,—


(L. 1).—[Who¹¹ was the exterminator of all kings; who had no antagonist (*of equal power*) in the world]; whose fame was tasted by the waters [of the four oceans]; [whc was equal to (the gods) Dhanada and Varuṇa and Indra and Antaka; who was the very axe of (the god) Kṛitānta]; who was the giver of [many] millions of [lawfully acquired cows and] gold; who was the restorer of the *atvamēdha*-sacrifice, that had been long in abeyance; (*and*)

(L. 3).—[Who¹² was the son of the son's son of the *Mahārāja*, the illustrious **Gupta**;—the son's son of the *Mahārāja*, the illustrious **Ghaṭōtkacha**];—(*and*) the son of the *Mahārājādhirāja*, the glorious **Chandragupta (I.)**, (*and*) the daughter's son of **Lichchavi**, begotten on the *Mahādēvī Kumāradēvī*;—

(L. 7).—On this (*lunar day*), (*specified*) as above by the day (*etc.*),¹³—at this temple of the divine (god) Svāmi-Mahāsēna, whose wondrous form is covered over with the accu-

¹ Supply *tithau*.² Read *kṛitam=idam*.³ Metre, Sragdharā.⁴ Here, and below, the marks of punctuation at the end of the first and third *pādas* of each verse are unnecessary.⁵ The reading is *gaurām*, instead of the usual form *gaurīm*, also in the original duplicate of this inscription on the other column.⁶ Metre, Śārdūlavikṛāṭita.⁷ These four *aksharas* are supplied from the ink-impression of the duplicate inscription, in which they are quite distinct.⁸ We should expect *sthīrataras*; but the duplicate inscription also reads *sthīra-varas*.⁹ See page 38 above, note 5.¹⁰ *i.e.* Chandragupta II.¹¹ *i.e.* Samudragupta.¹² *i.e.* Samudragupta.¹³ The day and other details, however, are not specified.

21880. Final inscription of Namaragaputa — in the year 90.



2
4
6
8
10
12

W. G. S. P. PHOTO-L.

7. 11. 11. 11. 11. 11.

mulation of the lustre of the three worlds; who is the god Brahmaṇya; (*and*) who resides at—this great work has been accomplished by **Dhruvaśarman**, who follows the path of the customs of the Kṛita age, and of the true religion, (*and*) who is honoured by the assembly

(L. 10.)—Having made a gateway,¹ charming, (*and*) the abode of saints, (*and*) having the form of a staircase leading to heaven, (*and*) resembling a (*pearl*)-necklace of the kind called *kaubracchhanda*, (*and*) white with the radiance of pieces of crystalline gems;—(*and having made*), in a very proper manner, a [religious] almshouse(?), the abode of those who are eminent in respect of virtuous qualities; resembling in form the top part of a temple;—he, the virtuous-minded one, roams in a charming manner among the items of religious merit (*that he has thus accumulated*); may the venerable Śarman endure for a long time!²

(L. 12.)—This lofty pillar,³ firm and excellent, has been caused to be made by that same **Dhruvaśarman**, whose piety, having acquired the excellent reputation of nectar on the earth, is so highly esteemed by all perfect beings that there is no one who would fail to worship him; (*and*) by whom by means of the abundance of (*his*) unprecedented accumulation of superhuman power.

No. II; PLATE VIA.

MANKUWAR STONE IMAGE INSCRIPTION OF KUMARAGUPTA. THE YEAR 129.

THIS inscription was discovered in 1870 by Dr. Bhagwanlal Indrajī, and appears to have been first brought to notice by General Cunningham in 1880, in the *Archæol. Surv Ind.* Vol. X. p. 7, where he published his reading of the text, accompanied by a lithograph (*id.* Plate IV. No. 2.).—And, in 1885, Dr. Bhagwanlal Indrajī published his own reading of the text, and a translation of it, in the *Four. Bo. Br. R. As. Soc.* Vol. XVI. p. 354.

Mankuwar⁴ is a small village near the right bank of the Jamnā, about nine miles in a south-westerly direction from Arail or Arayal, the chief town of the Arail Parganā in the Karchhanā Tahsil or Sub-Division of the Allahābād District in the North-West Provinces. The inscription is on the front of the pedestal of a seated image of Buddha, which, when it came to the notice of General Cunningham, was in a garden at Mankuwar, belonging to the Gōśāl of Dēōriyā⁵ or Dēwariyā; and it appears to be still there. But it was said to have been originally discovered in a brick mound between the five rocky hillocks called Pañch-Pahāḍ, a short distance to the north-east of Mankuwar. The image represents Buddha, seated; wearing a plain cap, fitting close to the head, with

¹ *pratīḥ*; see page 43 above, note 1.

² This is a play on the meaning of the first part of his name, *dhrūva*, 'immovable, stable, enduring.'—For the use of the second part, to represent the whole name, see page 8 above, note 3.

³ *īḥ*. "this loftiness of a pillar."

⁴ The 'Mankūār and Munhowar' of maps, &c. Indian Atlas, Sheet No. 88 Lat. 25° 19' N.; Long. 81° 35' E

⁵ The 'Deoriya and Deorya' of maps, &c; about a mile to the north-west of Mankuwar.—Bhagwanlal Indrajī writes the name 'Devaliā.'

long lappets on each side; and naked to the waist, and clad below in a waist-cloth, reaching to the ankles. The first line of the inscription is at the top of the pedestal, immediately below the image. Then comes a compartment of sculptures, containing in the centre, a Buddhist wheel; on each side of the wheel, a man seated in meditation, and facing full-front; and, at each corner, a lion. Then follows the second line of the inscription, at the bottom of the pedestal.

The writing, each line of which covers a space of about 1' 7" broad, by $\frac{3}{4}$ " high in the first line, and 1" in the second, is in a state of excellent preservation.—The size of the letters varies from $\frac{1}{4}$ " to $\frac{3}{8}$ ". The characters belong to the northern class of alphabets, and approximate very closely to those of the Allahâbâd posthumous pillar inscription of Samudragupta, No. 1, p. 1 ff. above, Plate 1. They include, in line 2, forms of the numerical symbols for 8, 9, 10, 20, and 100.—The language is Sanskrit; and the inscription is in prose.—The orthography presents nothing calling for remark.

The inscription refers itself to the reign of the Early Gupta king Kumâragupta. For some reason or other, it gives him the subordinate feudatory title of *Mahârâja*, instead of the paramount title of *Mahârâjâdhirâja*. But we know of no feudatory chieftain of the name of Kumâragupta; and the date fits exactly into the period of Kumâragupta, of the Early Gupta dynasty; and there can be no doubt that he is the person referred to. The use of the subordinate title may perhaps be due to carelessness or ignorance on the part of the drafter of the inscription. Or possibly it may indicate an actual historical fact, the reduction of Kumâragupta, towards the end of his life, to feudal rank by the Pushyamitras and the Hūnas, whose attacks on the Gupta power are so pointedly alluded to in the Bhitari inscription of Skandagupta, No. 13 below.¹ The date of the inscription, in numerical symbols, is the year one hundred and twenty-nine (A.D. 448-49), and the eighteenth day, without any specification of the fortnight, of the month Jyêshtha (May-June). It is a Buddhist inscription; and the object of it is to record the installation of the image on the pedestal of which it is engraved.

TEXT.²

1 Ôm³ Namô Budhâna⁴ [1*] Bhagavatô⁵ samyak-sambuddhasya sva-mat-
âviruddhasya iyam pratimâ pratishthâpitâ bhikshu-Buddhamitrêna

¹ We may compare the rather doubtful legend on one of Skandagupta's coins,—*Mahârâja-Kumâraputra-paramamâhâditya-mahârâja-Skanda*; see *Ind. Ant.* Vol. XIV p. 67.

² From the ink-impression.


³ As was usual throughout the whole of the period covered by this volume, this word is represented by a symbol, not by actual letters.—Ôm is not of very frequent occurrence at the commencement of Buddhist inscriptions. But another instance is afforded by line 1 of the Shêrgadh (Kôth) inscription of the *Sâmanta Dêvadatta* (*Ind. Ant.* Vol. XIV p. 45)

⁴ Read *buddhânâm*; unless *budhâna*, as also the following *bhagavatô*, is to be regarded as a Prakrit form used through carelessness.—This use of the genitive after *nama* is not usual. But we have other instances, e.g. in the Khandagiri rock inscription, which commences *Namô arahamitnam namô sava-sidhnam* (*Corp. Inscr. Ind.* Vol. I. p. 98, and Pl. xvii.);—in the two early inscriptions quoted by Bühler in *Ind. Ant.* Vol. X. p. 273, the first of which, from Amarâvatî (Fergusson's *Tree and Serpent Worship*, Pl. xciv. No. 3), commences *Sidham Namô bhagavatô*, and the second, from Mathurâ (*Archæol. Surv. Ind.* Vol. III, p. 35, and Pl. xv. No. 20) *Siddham Namô arahatô Mahôvrasya*;—and in the Amarâvatî *Stûpa* inscription, which commences *Sidham Namô bhagavatô svasatutamasa Budhasa* (*Archæol. Surv. South. Ind.* Vol. 3, p. 12, No. 12B., and Plate iii.; see also other instances on pp. 8, 18, 45, 47, 52, 53, 54, of the same volume).

⁵ Read *bhagavatô*.


B—Bihar Pillar: Inscription of Skandagupta

A—Nankuwar Image Inscription of Kumargupta—The Year 129



SCALE .50

2
4
6
8
10
12
14
16
18
20
22



SCALE 25

W. GRIGGS, PHOTO-LITH.

2 Samvat¹ 100 20 9 mahārāja-śrī-Kumāraguptasya rājyē Jyēshṭha-māsa
di 10 8 sarva-duḥkha²-prahān(n)-ārttham [11³]

TRANSLATION.

Om⁴ Reverence to the Buddhas!⁵ This image of the Divine One, who thoroughly attained perfect knowledge, (and) who was never refuted in respect of his tenets, has been installed by the *Bhikṣhu* **Buddhamitra**,—(in) the year 100 (and) 20 (and) 9; in the reign of the *Mahārāja*,⁶ the glorious **Kumāragupta**; (in) the month Jyēshṭha; (on) the 8th day 10 (and) 8,—with the object of averting all unhappiness.

No. 12; PLATE VI B.

BIHAR STONE PILLAR INSCRIPTION OF SKANDAGUPTA.

THIS inscription appears to have been discovered by Mr. Ravenshaw, and to have been first brought to notice by him in 1839, in the *Four. Beng. As. Soc.* Vol. VIII. p. 347 ff.; from his remarks it appears that the column was originally found in front of the northern gate of the old fort of Bihār, but had been subsequently removed and set up "in a reversed position, with its base in the air, and its summit in the ground," a little to the west of the same gate, where it was afterwards found, fallen, by General Cunningham.—In 1866, in the *Four. Beng. As. Soc.* Vol. XXXV. pp. 269 ff. and 277 f., Dr. Rajendralala Mitra published his reading of the text, with a lithograph, from a baked clay impression made by Major C. Hollings, and sent to the Society in 1861.—And in 1871, in the *Archæol. Surv. Ind.* Vol. I. p. 37 f. and Plate xvii., General Cunningham published his own lithograph of the inscription.

Bihār⁷ is the chief town of the Bihār Sub-Division of the Patna District in the Bengal Presidency. The broken red-sandstone column on which the inscription is, was eventually removed by Mr. A. M. Broadley, Magistrate of Bihār, and was set up on a brick pedestal opposite the Bihār Court-House,⁸ where it still stands. Mr. Broadley perpetuated

¹ See page 30 above, note 3.

² Read *duḥkha*

³ *Om* is an auspicious exclamation, used at the beginning of books, &c. It is made up of the three letters *a*, *u*, and *m*; and in later times it was looked upon as a mystic name for the Hindu triad, and as representing the union of the three gods, Vishnu (*a*), Śiva (*u*), and Brahman (*m*).—The efficacy of the exclamation is detailed in the *Mānavadharmasāstra*, ii. 74-85 (Burnell's Translation, p. 25 ff.)

⁴ With this plural, compare the mention of four Buddhas in the Sāfici inscription of the year 131, No. 62 below, Plate xxxviii B.; and also *Bhagavatām samyaksambuddhānām Buddhānām*, "of the divine Buddhas, who thoroughly attained perfect knowledge," in line 22 of the Wall grant of Dhruvasēna I. (*Ind. Ant.* Vol. IV. p. 105).

⁵ See page 46 above, para. 4.

⁶ The 'Behar and Bihar' of maps, &c. Indian Atlas, Sheet No. 103. Lat. 25° 11' N.; Long 85° 33' E.—The proper form of the name, which is by no means an uncommon one for villages in Northern and Central India, is of course Bihār, with the vowel *i* in the first syllable, from the Sanskrit *viḥāra*, 'a Buddhist (and Jain) temple or convent,' and this is the form that is used by the people of the Patna District.—The Sanskrit name, *Vihāra*, occurs in line 9-10 of the 'Pessera' inscription, now stored in the collection at Bihār, where the place is called "Vihāra, the city of the glorious Yaśōvarman" (*Four. Beng. As. Soc.* Vol. XVII. p. 492 ff.)

⁷ *Archæol. Surv. Ind.* Vol. XI. p. 192 f.

the inverted position of the column, upside down; and also disfigured it with an English inscription, printed in full by General Cunningham, a few letters of which appear in the lithograph now published. Also, the column, as placed by Mr. Broadley, stands now in the middle of a house, the roof of which is supported by it; and the last eight lines of the inscription, shewn in Dr. Rajendralala Mitra and General Cunningham's lithographs, are now completely hidden, and rendered quite inaccessible, by a wooden structure placed on the top, i.e. the proper bottom, of the pillar, in order to connect it with the roof.

The writing originally extended, in the First Part, lines 1 to 13, over four of the faces of the column, as is shewn by the metres of the extant portion; and in the Second Part, line 14 ff., over three faces, as is shewn by the number of letters lost in each line. The extant portion, now lithographed, covers a space of about 1' 4" broad by 3' 5" high, and is in a state of fairly good preservation.—The size of the letters varies from $\frac{1}{8}$ " to $\frac{1}{4}$ ". The characters belong to the northern class of alphabets, and approximate closely to those of the Allahâbâd posthumous pillar inscription of Samudragupta, No. 1, p. 1 ff. above, Plate i. They include, in lines 3 and 11, forms of the numerical symbols for 3, 5, and 30.—The language is Sanskrit; and the inscription is in verse as far as line 10, and the rest in prose.—In respect of orthography, the only points that call for notice are (1) the use of the dental nasal, instead of the *anusvâra*, before *ś*, in *ansa*, lines 11 and 13; (2) the doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *chakkrl*, line 10 (but not in *vikramēna*, line 3), and *pauttrasya*, line 17; and (3) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyâta*, line 22.

The first part of the inscription, which is not dated, mentions the Early Gupta king Kumâragupta, and seems to have recorded the name of his wife, which is not given in any of the other inscriptions; her name, however, is lost in the part that has peeled off. But this part of the inscription seems to belong, like the second, to the time of his son and successor Skandagupta, from the mention of apparently a village named Skandaguptabaṭa, in line 11. This part of the inscription records the erection of the column, which in line 10 is called a *yûpa* or 'sacrificial post,' apparently by some minister whose sister had become Kumâragupta's wife. And the inscription further recorded certain shares in the village of Skandaguptabaṭa (?), and in another *agrahâra*, the name of which is lost. From the mention of Skanda, or Kârttikēya, and the divine Mothers, in line 9, this part of the inscription seems to have belonged to the Śaiva form of worship, in its Śākta or Tāntrika development.¹

The second part, which also contains no date, is a record of Skandagupta. Not enough of it remains to shew the form of religion to which it belonged, or to indicate clearly its purport.

¹ Compare the undoubted instance of this, in the same period, in the Gangdhâr inscription of Visuvarman, No. 17 below.—The *mâtaraḥ* or *mâtrigana*, 'the divine Mothers,' are 'the personified energies (*śakti*) of the principal deities.' They are closely connected with the worship of the god Śiva. Originally they were seven in number,—Brâhmī or Brâhmîṇī, Vnuṣṭavī, Mâhêsvarī, Kaumârī Vârâhī, Aindrī or Indrâṇī or Mahêndrī, and Châmuṇḍâ,—as representing the Pleiades, the seven mothers or nurses of Kârttikēya, the son of Śiva. Afterwards the number was increased to eight, nine, sixteen, and various other figures. The chief object of the Śākta or Tāntrika worship now is Pârvatī, Durgâ, or Mâhêsvarī, the wife and female energy of Śiva; especially under the name of Jagadambâ, 'the mother of the universe.'—Not long after this period, Svâmi-Mahâsēna, or Kârttikēya, and the divine Mothers, "the seven mothers of mankind," appear as special objects of worship, and tutelary deities, of the Early Kadambas (e.g. *Ind. Ant.* Vol. VI. p. 27), and of the Early Chalukyas (e.g. *Ind. Ant.* Vol. VII. p. 162; Vol. VI. p. 74; and Vol. XIII. p. 137 f.)

TEXT.¹

First Part.

- 1 [— —]h³ nri³-chandra Indrānuja-tulya-vīryō guṇair-a-tulyaḥ
[∪ ∪ — ∪ — —] [11]
- 2 [— —] [ta]sy⁴=āpi sūnur=bhuvi svāmi-nēyaḥ khyātaḥ sva-
kīrttyā [∪ ∪ — ∪ — —] [11]
- 3 [— —] [sva]s⁵=aiva yasy=ātula-vikramēna Kumāragup[t]ē[na]
[∪ — ∪ — —] [11]
- 4 [— —] p[i]tri(tr)ṁś=cha jēvāṁś=cha hi havya-kavyaiḥ sadā
nriśāṁsy-ādi[∪ — ∪ — —] [11]
- 5 [— ∪ —] [a]chīkarad⁷=dēvanikēta-maṇḍalaṁ kshitāv-an-aupamya-
[∪ — ∪ — —]
- 6 ba(?)tē(?)⁶ kila stambha-var-ōchchhri(chchhra)ya-prabhāśē
tu maṇḍa [11]
- 7 bhir-vriksḥānām kusuma-bhar-ānat-āgra-śum(?)ga(?)-vyālamba-
stavak [11]
- 8 [— —] Bhadrāryayā⁸ bhāti grihaṁ navābhra-nirmmōka-
nirmu[cta ∪ — ∪ — —] [11]
- 9 [— —] Skanda-pradhānair=bhuvi mātriḥiś=cha lōkān=sa
su(?)shya(?)[∪ ∪ — ∪ — —] [11]
- 10 [— — ∪] yūp-ōchchhrayam=ēva chakkre [11*] Bhadrāry-ādi-
.....
- 11 [Ska(?)ndaguptaba]tē anśāni 30 5 tā(?)mrakaṭāku(?)ḥ
kala [11]
- 12 pituḥ sva-mātur=yyady=astu hi dushkṛtaṁ bhajatu
tanē [11]
- 13 k-āgrahārē anśāni 3 An.antasēnēn=ōpa [11]

Secunda Pars.

- 12 [Sarvva-rāj-ōchchhē]ttuḥ¹⁰ pri(pri)thivyām=a-pratirathasyz
15 [chā⁹ur-udadhi-salil-āsvādita-yaśasō Dhanada-Varuṇ-Ē]ndr-Antaka-
samasye Kṛitān⁹

¹ As far as line 25, from the ink-impression; the rest, partly from Gen. Cunningham's lithograph, and partly from the lithograph published with Dr. Rajendralala Mitra's reading.

² The first two entire *pādas*, and parts of the third *pādas* of most of the verses, have peered off and are lost all the way down.

³ Metre, Upēndravajrā.

⁴ Metre, Indravajrā

⁵ The metre is faulty here: since the *vi* of *ōkavi*, which should remain short, is lengthened by the following *sv*.

⁶ Metre, Upēndravajrā; and in the next verse.

⁷ Metre, Vatsāstha

⁸ Metre, apparently Giti; and in the next verse.

⁹ Metre, Indravajrā; and in the following two verses.

¹⁰ The passages that are lost in lines 14 to 22, are supplied from No. 1, lines 24, 26, 28, and 29, page 8 above, and from the Bhitārī pillar inscription of Skandagupta, No. 13 below, Plate vii lines 1 to 6. The sectarian epithet of Skandagupta, in line 23, is supplied from line 24, and from his silver coins (see *Ind. Ant.* Vol. XIV. p. 66 f.)

- 16 [paraśōḥ nyāy-āgat-ānēka-gō-hiraṇya-kōṭi-pradasya chir-ō]tsann-
 āsvamēdh-āharttuḥ
- 17 [mahārāja-śrī-**Gupta**-prapauttrasya mahārāja-śrī-**Ghatō**]tkacha-
 pauttrasya mahārāja-
- 18 [dhirāja-śrī-**Chandragupta**-puttrasya **Lichchhavi**-dauhitrasya
 ma]hā-dēvyām **Kumāradēvyām**-utpannasya
- 19 [mahārājādhirāja-śrī-**Samudraguptasya** putra]s=tat-parigrihitō
 mahādēvyām
- 20 [**Dattadēvyām**-utpannaḥ svayam=a-pratirathah para]mabhāgavatō
 mahārāja-
- 21 [dhirāja-śrī-**Chandraguptas**-tasya puttras=tat-pād-ānuddhyā]tō
 mahādēvyām **Dhruvadēvyām**-
- 22 [utpannaḥ paramabhāgavatō mahārājādhirāja-śrī-**Kumāraguptas**-
 tasya] puttras=tat-pād-ānuddhyātah
- 23 [paramabhāgavatō mahārājādhirāja-śrī-**Ska**]ndaguptaḥ [II*]
 24
 parama-bhāgavatō
- 25 [mahārājādhirāja-śrī-**Sikandaguptaḥ**]
 [vai]shayik-**Ājapuraka**-sā(?)mai(?)-
- 26 grā. ka
 [ak]shaya-nivi grāma-kshētram
- 27 kr
 uparika-kumārāmātya-
- 28 ngikula(?)h(?)
 vani[ja*]ka-pādīt-ārīka-
- 29 [ā]grahārtika-
 śaulkika-gaulmik-āsanyām śra(?)-
- 30 vās[i]k-ādīn=asmat-prāsād-
 ōpajivinah
- 31 [samājñāpayāmi] **varmmapā** vijñāpitō-sm; mama
 pitāmahēna
- 32 namē bhatta-Guhilasvāmīna
Bhadra[r]yyakā
- 33 m. g. p[r]ati ā. āgrōkaya
 nākaya-

(The rest of the inscription had been broken away and lost,
 before the time when it was discovered.)

TRANSLATION.

First Part.

... a very moon of a man; equal in prowess to (the god Vishnu) the
 younger brother of Indra; unequalled in respect of virtuous qualities:

(Line 2.)—... moreover, his son, docile towards (his) master on the earth;
 renowned, ... by his own fame.

(L. 3.)—... whose sister, indeed, [was espoused] by **Kumāragupta**, of
 unequalled prowess.

(L. 4.)—..... both the deceased ancestors and the gods, with the oblations proper for each of them;¹..... always things that are injurious to man, &c.

(L. 5.)—..... caused to be made a group of temples, not [rivalled by] anything else that could be compared with it in the world.

(L. 6.)—..... assuredly in which is beautiful with the erection of (*this*) best of columns.

(L. 7.)—..... of the trees the groups of fig-trees and castor-oil plants, the tops of which are bent down by the weight of (*their*) flowers.

(L. 8.)—..... by (*the presence of*) Bhadrāryā, the house shines the sky laden with fresh clouds.

(L. 9.)—..... headed by (the god) Skanda, and by the divine Mothers, on the earth, mankind

(L. 10.)—..... [he] made, indeed, the erection of (*this*) sacrificial post Bhadrāryā and others in (the village (?) called) **Skandaguptabata** (?), 30 (*and*) 5 shares

(L. 12.)—..... if there be any misdeed on the part of (*his*) father (*or*) his mother, let him share

(L. 13.)—..... in the *agrahāra* of 3 shares by Anantasēna

Second Part.

(L. 14.)—..... The son of the *Mahārājādhirāja*, the glorious **Samudragupta**,—who was the exterminator [of all kings]; who had no antagonist (*of equal power*) in the world; [whose fame was tasted by the waters of the four oceans]; who was equal to (the gods) [Dhanada and Varuṇa] and Indra and Antaka; [who was the very axe] of (the god) Kṛitānta; [who was the giver of many millions of lawfully acquired cows and gold]; who was the restorer of the *atvamēdha*-sacrifice, that had been [long] in abeyance; [who was the son of the son's son of the *Mahārāja*, the illustrious **Gupta**]; who was the son's son of [the *Mahārāja*, the illustrious] **Ghaṭōtkacha**; (*and*) who was [the son] of the *Mahārājādhirāja*, [the glorious **Chandragupta** (I.), (*and*) the daughter's son of **Lichchavi**], begotten on the *Mahādēvī Kumārādēvī*,—

(L. 19.)—(*was*) the most devout worshipper of the Divine One, the *Mahārājādhirāja*, [the glorious **Chandragupta** (II.)],—who was accepted by him;² [who was begotten on] the *Mahādēvī* [**Dattadēvī**]; (*and*) [who was himself without an antagonist (*of equal power*).]

(L. 21.)—[His son], who meditated on [his feet], (*and*) [who was begotten] on the *Mahādēvī Dhruvadēvī*, (*was*) [the most devout worshipper of the Divine One], [the *Mahārājādhirāja*, the glorious **Kumārāgupta**].

(L. 22.)—[His] son, who meditated on his feet, (*is*) [the most devout worshipper of the Divine One, the *Mahārājādhirāja*, the glorious] **Skandagupta**.

¹ *lit.* "with the *havya* (the oblation to the gods) and the *śavya* (the oblation to deceased ancestors)."

² *l.s.* by Samudragupta; see page 12 above, note 1.

(L. 24.)—[1], the most devout worshipper of the Divine One, [the *Mahārājādhirāja*, the glorious *Skandagupta*, issue a command] of the town of *Ajapura* in the *vishaya* a perpetual endowment a village-field the *Uparika*,¹ the *Kumārāmātya* acquired by the merchant in the seat (of office) (?) of the *Āgrahārika*,² the *Saulkika*,³ and the *Gaulmika*⁴ and others who subsist on Our favour :—

(L. 31.)—" I have been requested by *varman*,—' By my father's father, by the *Bhāṣṭa* *Guhilasvāmin*. belonging to *Bhadrāryā* "

No. 13; PLATE VII.

BHITARI STONE PILLAR INSCRIPTION OF SKANDAGUPTA.

THE column containing this inscription appears to have been discovered in 1834 by Mr Tregear ; but the inscription itself was not observed till a short time afterwards, when General Cunningham found it, on clearing away the earth from the lower part of the shaft. The discovery was announced in 1836, by Mr. James Prinsep, in the *Four Beng As. Soc. Vol. V. p. 661*. And the inscription was first brought to notice in 1837, in the same Journal, Vol. VI. p. 1 ff., where the Rev. W. H. Mill published his reading of the text, and a translation of it, accompanied by a lithograph (marked *1d.* Vol. V. Plate xxxii.), reduced by Mr. Prinsep from a copy made by General Cunningham.⁵—In 1871, in the *Archæol Surv. Ind.* Vol. I. p. 98 and Plate xxx., General Cunningham published another lithograph of the inscription.—In 1875, in the *Four. Bo. Br. R. As. Soc.* Vol. X. p. 59 ff., Dr. Bhau Daji published a revised reading of the text, and a translation of it, accompanied by a lithograph, from a hand-copy made by Dr. Bhagwanlal Indrajī.⁶—And finally, in 1885, in the *Four. Bo Br. R. As. Soc.* Vol. XVI. p. 349 ff., Dr. Bhagwanlal Indrajī has given his own reading of the text, and a translation of it, with another lithograph reduced from his hand-copy.

Bhitari⁷ is a village about five miles to the north-east of Sayyidpur,⁸ the chief town of the Sayyidpur Tahsil or Sub-Division of the Ghazipur⁹ District in the North-West Provinces. The red-sandstone column on which the inscription is, stands just outside the

¹ *Uparika* is a technical official title, the exact purport of which is not known, and a suitable rendering of which cannot be offered at present.

² *Āgrahārika* is a technical official title, denoting probably 'an officer in special charge of an *agrahāra*.'

³ *Saulkika* is a technical official title, which might be rendered by some such term as 'superintendent of tolls or customs (*fulka*).'

⁴ *Gaulmika* is a technical official title, which might be rendered by 'superintendent of woods and forests (*gulma*).'

⁵ The translation is reprinted in Thomas' edition of Prinsep's *Essays*, Vol. 1. p. 242 f.

⁶ This paper was not published till 1875, but it was read before the Society four years earlier, on the 13th April 1871.

⁷ The 'Bhitari, Bhitree, Bhitrf, and Bhitari,' of maps, &c. Indian Atlas, Sheet No. 103. Lat. 25° 35' N.; Long 83° 17' E.

⁸ The 'Saidpur and Sydpoor' of maps, &c.

⁹ The 'Ghazeepoor' of maps.

village, on the south side. The inscription is on the eastern face of the square base of the column; and the bottom line is only a few inches above the level of the ground.

The **writing**, which covers a space of about 2' 4½" high by 2' 2½" broad, has suffered very much from the effects of the weather; also the stone has peeled off in a few places; and there is a crack running vertically down the inscription, near the left side. With care, however, nearly the whole of the inscription is legible, on the original stone, with certainty; and nothing of a historical nature seems to be lost.—The **size** of the letters varies from ¼" to ⅞" The **characters** belong to the northern class of alphabets, and, though more squarely cut, are of the same type with those of the Mathurā inscription of Chandragupta II., No. 4, p. 25 ff. above, Plate iiiA.—The **language** is Sanskrit; and the inscription is in prose as far as the middle of line 6, and the rest in verse.—In respect of **orthography**, we have to notice (1) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *vanśa*, lines 7, 13, and 14; (2) the doubling of *ś*, in conjunction with a following *r*, in *vikkramēna* and *kkramēna*, line 9; (3) the doubling of *ś*, under the same circumstances, in *pautrasya*, line 3 (but not in *prapautrasya*, line 2; *putras*, line 4; and other places); and (4) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, line 5

The **inscription** is one of the **Early Gupta** king **Skandagupta**. It is not dated. It belongs to the Vaishnava form of religion; and the object of it is to record the installation of an image of the god Vishṇu, under the name of Śāringin or "the wielder of the bow of horn named Śāringa," and the allotment, to the idol, of the village, not mentioned by name, in which the column stands.

TEXT.¹

- 1 [Siddham*] [I]* [Sar]vva-rāj[ō]chchh[ē]ttuh prithivyām=a-pratirathasya catur-
udadhi-sahl-[ā]svādita-yaśasō Dhanada-Varuṇ-Endr-[Ā]ntaka-sa[masya]
- 2 Kritānta-parasōṅ nyāy-āgat-[ā]nēka-gō-hiranya-k[ō]ṭi-pradasya chir-ō[ṭ]ṣann-
āsvamēdh-āhartur=mahārāja-śrī-Gupta-prapautra[ṣya]
- 3 mahārāja-śrī-Ghatōtkacha-pautrasya mahārājādhirāja-śrī-Chandragupta-
paurasya Lichchhivi-cauhitrasya mahādēvyām Kum[ā]rad[ē]vyā-
- 4 m=utpannasya mahārājādhirāja-śrī-Samudraguptasya putras=tat-pariṅghitō
mahādēvyām-Dattadēvyām=utpannaḥ svayam=a-pratirathaḥ
- 5 paramabhāgavato mahārājādhirāja-śrī-Chandraguptas=tasya putras=tat-pād-
anuddhyātō mahādēvyām Dhruvadēvyām=utpannaḥ parama-
- 6 bhāgavato mahārājādhir[ā]ja-śrī-Kumāragnptas=Tasya [I*] Prathita*-prithu-
mati-svabhāva-śaktēḥ prithu-yasasah prithivipatēḥ prithu-śrīḥ
- 7 pi[tri]-pa[r]jigata-pādapadma-vartti prathita-yaśāḥ prithivipatiḥ sutō=yam [I*]
Jagati* bhu[ja]-bal-ādyō(dhyō) Gupta-vanś-aika-viraḥ prathita-vipula-
- 8 dhāmā nāmataḥ Skandaguptaḥ sucharita-charitānām yēna vrittēna vrittam
na vihatam-amal-ātmā tāna-dhīdā(?)-vinttaḥ [I*] Vinaya-
- 9 bala-suntair=vvikkramēna kkrāmēna pratidinam=abhiyōgād-īpsitam yēna
la[b]dhvā svabhimata-vijigīśhā-prōdyatānām parēśhām prāni-
- 10 hta iva lē[bhē sa]mvidhān-ōpadēśah [I*] Vichalita-kula-lakshmi-stambhanāy-
ōdyatēna kshītitala-śayanīyē yēna nīdā triyāmā samu-

¹ From the original column:


² There are some faint marks above the *anusvāra*, which seem to be remnants of this word; but it is not quite certain.

* Metre, Pushpītāgrā.

* Metre, Mālinī; and in the next four verses.

CORPUS INSCRIPTIONUM INDICARUM.

Bhleri Pillar inscription of Skandagupta



(L. 5.)—His son (*was*) the most devout worshipper of the Divine One, the *Mahā-rājādhirāja*, the glorious *Kumāragupta*, who meditated on his feet, (*and*) who was begotten on the *Mahādevī Dhruvadēvi*.

(L. 6.)—The son of him, the king, who was renowned for the innate power of (*his*) mighty intellect (*and*) whose fame was great, (*is*) this (*present*) king, by name *Skandagupta*, who possesses great glory; who subsisted (*like a bee*) on the wide-spreading waterlilies which were the feet of (*his*) father;¹ whose fame is spread far and wide;—who is amply endowed with strength of arm in the world; who is the most eminent hero in the lineage of the *Guptas*; whose great splendour is spread far and wide; by whom, practising (*good*) behaviour, the conduct of those who perform good actions is not obstructed; who is of spotless soul; (*and*) who is well disciplined in the understanding of musical keys(?) :—

(L. 8.)—By whom,—having, with daily intense application, step by step attained his object by means of good behaviour and strength and politic conduct,—instruction in the art of disposition (*of resources*) was acquired, (*and*) was employed as the means of (*subduing his*) enemies who had put themselves forward in the desire for conquest that was so highly welcome (*to them*) :—

(L. 10.)—By whom, when he prepared himself to restore the fallen fortunes of (*his*) family, a (*whole*) night was spent on a couch that was the bare earth; and then, having conquered the *Pushyamitras*,¹ who had developed great power and wealth, he placed (*his*) left foot on a foot-stool which was the king (*of that tribe himself*) :—

(L. 11.)—The resplendent behaviour of whom, possessed of spotless fame,—inherent, [but increased] by and patience and heroism which are emphatically unequalled, (*and*) which destroy the efficacy of the weapons (*of his enemies*),—is sung in every region by happy men, even down to the children :—

(L. 12.)—Who, when (*his*) father had attained the skies, conquered (*his*) enemies by the strength of (*his*) arm, and established again the ruined fortunes of (*his*) lineage; and then, crying “the victory has been achieved,” betook himself to (*his*) mother, whose eyes were full of tears from joy, just as *Kṛishṇa*, when he had slain (*his*) enemies, betook himself to (*his mother*) *Dēvaki* :—

(L. 14.)—Who, with his own armies, established (*again*) (*his*) lineage that had been made to totter (*and*) with his two arms subjugated the earth, (*and*) shewed mercy to the conquered peoples in distress, (*but*) has become neither proud nor arrogant,

¹ This expression is very analogous in its purport to the *tat-pād-ānuahyāta* of line 5 above. Compare *Amōghavarshadēva-pādapānkaja-bhramara*, “a bee at the waterlilies which are the feet of *Amōghavarshadēva*,” in line 17 f. of the *Sīrūr* inscription of *Sāka-Saivāt 788* (*Ind. Ant.* Vol. XII. p. 219.)

² The second syllable of this name, like the rest of the inscription, is damaged. But, as regards the lower component,—comparing it with the subscript *y* of this inscription, e.g. in *pradasya*, line 2, and *dauhitrasya*, line 3; and contrasting it with the subscript *p*, e.g. in *tat-parigrhitō*, line 4, and *tat-pādā*, line 5,—it is plainly *y*. This passage, therefore, shews that the correct form of the first part of this name is *pushya*, not *pushpa*; a point which *Dēvanāgarī* manuscripts have not sufficed, and cannot suffice, to settle. And it bears out the *Prākṛit* form, *Pāsamitta*, of the name of the early king *Pushyamitra*, the contemporary of *Patañjali*, in the passages given by Dr. Bühler from the *Prākṛit Gāthās* according to *Mērutunga*, *Dharmasāgara*, and *Jayavijayagaṇi* (*Ind. Ant.* Vol. II. p. 362 f.)—*Pushyamitra* is the correct form according to Prof. Weber also (*Sanskrit Literature*, p. 223, note 237).

though his glory is increasing day by day; (and) whom the bards raise to distinction with (their) songs and praises:—

(L. 15.)—By whose two arms the earth was shaken, when he, the creator (of a disturbance like that) of a terrible whirlpool, joined in close conflict with the Hūnas; . . . among enemies arrows proclaimed just as if it were the roaring of (the river) Gangā, making itself noticed in (their) ears.

(L. 17.)— . . . the fame of his father
 (Saying to himself that) an image of some kind or other [should be made], he, the very celebrated one, made this image of that (famous) (god) Śarṅgin, [to endure as long as the moon and stars may last]. And, having here installed this (god),¹ he, whose commands are well-established, has allotted this village (to the idol), in order to increase the religious merit of (his) father.²

(L. 19.)—Accordingly, this image of the Divine One, and (this village) which has been here agreed to,³—both of these, he, the pious-minded one, has assigned for (the increase of) the religious merit of (his) father.

No. 14; PLATE VIII.

JUNAGADH ROCK INSCRIPTION OF SKANDAGUPTA. THE YEARS 136, 137, AND 138.

THE discovery of this inscription appears to have been first announced in 1838, by Mr. James Prinsep, in the *Four. Beng. As. Soc.* Vol. VII. p. 347 f.—In 1844, in the *Four. Bo. Br. R. As. Soc.* Vol. I. p. 148, there was published a lithograph of it, reduced from a copy, made by General Sir George LeGrand Jacob, Mr. N. L. Westergaard, and a Brāh. man assistant, which had been submitted to the Society two years previously.—In 1862, in the same Journal, Vol. VII. p. 121 ff., Dr. Bhau Dajī published his reading of the text, and a translation of it, accompanied by a lithograph reduced from a cloth tracing made in 1861 by Dr. Bhagwanlal Indrajī—And in 1876, Dr. Bhau Dajī's text and translation, the latter revised by Professor Eggeling, were reprinted in the *Archæol. Surv. West. Ind.* Vol. II. p. 134 ff. accompanied by a slightly reduced reproduction of the original lithograph from Dr. Bhagwanlal Indrajī's copy (*id.* Plate xv.)

Junāgadh⁴ is the chief town of the Junāgadh Native State in the Kāthiawād⁵ Penin-

¹ Or, perhaps, "having here set up this (pillar)."

² It was through reading *mahēsa-prīta-gupta*, "the Gupta attached to, or beloved of, Śiva," instead of *ēnam sa vidadhē pituh*, line 18,—and through failing to see that *pitari divam = uplētē*, "when (his) father had attained the skies," line 12, refers to the death of Kumāragupta,—that Dr. Mill came to speak of "a young prince, a minor at the date of this inscription," and to suggest that he was probably the Mahēndragupta (*sic.*, but in reality Mahēndrāditya, a title of Kumāragupta), whose name occurs on some of the coins of the dynasty. This double mistake in Dr. Mill's genealogy was repeated by Mr. Thomas in his Gupta genealogy (*Archæol. Surv. Ind.* Vol. II, p. 19). And Mahēndragupta's name is also given in Mr. Fergusson's last list (*Cave-Temples of Western India*, p. 191).

³ Or perhaps, "and (this column) which stands here."

⁴ The 'Joonaghur, Junagad, Junagarh, and Junagurh,' of maps, &c. Indian Atlas, Sheet No. 13. Lat 21° 31' N, Long 70° 36' E.

⁵ The 'Kathiawar and Kattywar' of maps, &c.

sula in the Bombay Presidency. The city itself, or its ancient representative, is spoken of in this inscription; but its ancient name is not given. The name occurs, however, in line 1 of Rudradāman's inscription,¹ as **Girinagara**, or 'the city of, or on, the hill.' This name subsequently passed over to the mountain itself, **Girnār**, which in the inscriptions is called **Ūrjayat**; and this fact rather tends to indicate that the ancient city stood, not where the modern town stands, but closer up to the mountain, and perhaps on the rising ground at the foot of it. The inscription is on the north-west face of a large granite boulder, containing also fourteen Aśoka edicts and a long inscription of the *Mahākshatrapa* Rudradāman, now under a shed specially built to protect it, about a mile to the east of the town, and at the commencement of the gorge that leads to the valley which lies round the mountain Girnār.

The **writing**, which covers a space of about 10' 6" broad by 7' 3" high is in a state of fairly good preservation; and it is only in line 22 ff., where the rock has actually peeled off, that there are any extensive lacunæ in the inscription. It is, however, not very easy to read; owing partly to the irregular, and occasionally rather shallow, nature of the engraving; partly to the roughness of the rock, and the way in which the natural marks of it mix themselves up a good deal with the letters; and partly to the fact that at several places the engraver, in consequence of unusual irregularities of the surface, passed over considerable portions of the rock and left them blank.²—The **size** of the letters varies from about $\frac{1}{8}$ " to $\frac{1}{4}$ ". The **characters** belong to the southern class of alphabets; but the type is a later development of that which was used in the inscription of the *Mahākshatrapa* Rudradāman on the same rock;³ it may be called the Saurāshṭra or Kāthiāwāḍ alphabet of the fifth century A.D. One of its most marked characteristics is the way in which the subscript *y* is represented by the full form of the letter, not, as in other alphabets, by a curtailment of it; e.g. in *buddhyā*, line 5; *vyasani*, line 6; and *nydyā*, line 8.—The **language** is Sanskrit; and, except for the opening word *siddham*, and a few words in line 23, the entire inscription is in verse.—In respect of **orthography** we have to notice (1) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *vanśa*, line 24; (2) the doubling of *dh* in conjunction with a following *y*, in *buddhyā*, line 5; and (3) the indifference about the doubling of consonants in conjunction with a preceding *r*; e.g. the consonant is doubled in *Arttham*, line 1, *Arttir*, line 2, and *darppā*, line 3; but not in *vīryā*, line 2, *paryanta*, line 3, *sarvān*, line 5, *Arjavau*, line 7, and *Arjanā-rthasya*, line 8.

The first part of the inscription refers itself to the reign of the **Early Gupta** king **Skandagupta**; and, after an invocation of the god Vishṇu and five verses in praise of the reigning king, it narrates how he appointed a certain **Parṇadatta** to govern his territories in the **Surāshṭras** or the **Kāthiāwāḍ country**. In his turn, Parṇadatta appointed his son, **Chakrapālita**, to govern the city at which the inscription is. The inscription then proceeds to its real object; *viz.* to record that, "making the calculation in the reckoning of the **Guptas**,"⁴ in the year one hundred and thirty-six (A.D. 455-56),

¹ *Archæol. Surv. West. Ind.* Vol. II. p. 128.

² These blank spaces lie especially on each side of the large natural fissure running almost down the centre of the inscription.

³ *Archæol. Surv. West. Ind.* Vol. II. p. 128, Pl. xiv.

⁴ As is quite clear even in the lithograph with which Bhau Daji worked, the correct reading here (line 15) is *Gupta-prahād gaganānā vidhāya*; not *Guptasya kālā[d] = gaganānā vidhāya*, "counting from the era of Gupta," as it was taken to be by Bhau Daji and was afterwards specifically confirmed

at night, on the sixth day of the month Praushthapada (August-September), the lake **Sudarāna** (formed in the valley round the foot of Girmār, by an ancient embankment across the gorge, near where the inscription is) burst in consequence of excessive rain. The date, here, and in the two passages further on, is expressed fully in words, not in numerical symbols. The restoration of the breach, by renewing the embankment, was effected under the orders of **Chakrapālita** after two months' work, in the year one hundred and thirty-seven (A.D. 456-57).

The second part, line 24 to the end, seems to have mentioned **Skandagupta** and **Parnadatta** again, in passages in line 24 that are now illegible. And then, in accordance with the general Vaishṇava tendency indicated by the opening invocation of the whole inscription, it goes on to record that, in the one hundred and thirty-eighth year, in the time or reckoning of the **Guptas** (A.D. 457-58), **Chakrapālita** caused to be built a temple of the god Vishṇu under the name of Chakrabhrit or the 'bearer of the discus.' After this, the inscription ends with two verses, of which not enough now remains to shew their purport.

TEXT.¹

First Part.

1 Siddham [11*] Śriyam²=abhimata-bhōgyām naika-kāl-āpanitām tridaśapati-
sukh-ārtham yō Balēr-ājahāra | kamala-nīlayanāyāh śāśvatam dhāma
Lakshmyāh

by Thomas (*Four. R. As. Soc. N. S. Vol. XIII. p. 538*).—In the present series of inscriptions, this passage, and the genitive plural *Guptānām*, governed apparently by *kāla*, in line 27 below, are the only ones that tend in any way to connect the name of the Guptas with the era used by them. But not either of them suffices to shew that the era was established by the Guptas themselves; or even that it had, at this time, received the accepted name of "the Gupta era." And, what the wording of the first of them really shews, is simply that the date was being recorded in an era which was not the one in customary use in that part of the country.—The only other passage of a similar tendency is the date in line 16 f. of the Mōrbi copper-plate grant of Jāiṅka, as it has always been accepted up to now in accordance with Dr. R. G. Bhandarkar's reading and translation,—*Pamch-āśītyā yut=śil samānām śata-pamchakāś | Guptā dādū=ād nripah s-ōparāgē-rkka-mamādal 11*;—"five hundred and eighty-five years of the Guptas having elapsed, the king granted this, when the disc of the sun was eclipsed" (*Ind. Ant. Vol. II. p. 258*).—But this rendering takes no notice of the fact that the real reading, in line 17, is not *guptā* at all, but *gōptā*. It is only by the correction of *ō* into *au* that the name of the Guptas can be introduced into this passage. But we may with just as much reason correct *gōptā* into *gōptā*, 'to the protector, i.e. the local governor' (compare this word in line 6 of the present inscription); and this is even more sustainable; for the word is entirely separated from the date in the preceding half of the verse, and it stands immediately before the word *dadau*, 'he gave,' in connection with which we have every reason to look for a dative (or some other) case. Or, again, without any correction at all, we may translate "the king gave this (charter) at (the village of) Gōpta;" and thus obtain a village-name that may quite reasonably be taken as the ancient form of the modern Gōp, which occurs, for instance, in Kāthiāwād, about seventy-five miles south-west of Mōrbi, twenty-five miles south of Nawānagar or Jāmnagar, and fifty miles east of Dhiniki, where there was found the copper-plate grant (genuine or spurious, as may be settled hereafter) of a king Jāikādēva, dated Vikrama-Samvat 794 (*Ind. Ant. Vol. XII. p. 151 ff.*).—I must not be understood as disputing in this note, that the Mōrbi date is recorded in the era that had been used by the Guptas. My object is only to shew that there is nothing in the passage containing the date, that compels us to connect the name of the Guptas with it. The difficulty in disposing finally of the whole bearing of the Mōrbi inscription, is, that the first plate was lost sight of before it was procured for examination at all; and now, even the second plate also, the published one, has been mislaid and is not forthcoming.

¹ From the original stone.

² Metre, Mālinī; and in the next two verses.

- 2 sa jayati vijit-ārttir-Vvishṇur-atyantā-jishṇuḥ || Tad-anu jayati śaśvat śrī-
parikshipta-vakṣbhāḥ sva-bhuja-janita-vīryō rājarājādhirājāḥ | śarapati-
- 3 bhujagānām māna-darpp-ōtphaṇānām pratikṛiti-Garuḍ-ājñā[m] nirvviśh[m]
ch-āvakarttā || Nripati-ḡuṇa-nikētaḥ **Skandaguptaḥ** prithu-śrīḥ chatur-
udadhi-ja(?)l(?)-āntām sphlta-paryanta-dēśām |
- 4 avanim-avanat-ārir-yaḥ chakār-ātma-samsthār. pitari sura-sakhitvaṁ
prāptavaty-ātma-śaktyā || Āpi¹ cha jitam-[ē]va tēna prathayamti
yaśāmsi yasya nipavō-pi āmūla-bhagna-darpā niva²
Mlōchchha-dēśēshu ||
- 5 Kramēṇa³ buddhyā nipuṇam pradhārya dhyātvā cha kṛtsnān-ḡuṇa-dōsha-
hētūn | vyapētya sarvān-manujēndra-putrām-llakshmlḥ svayam yam
varayām-chakāra || Tasmin⁴-nripē śāsati n-aiva kaśchid-dharmād-
apētō manujaḥ prajāsu |
- 6 ārttō daridrō vyanal kadaryō danḍ[yō*] na vā yō bhṛīṣa-plḍitaḥ syāt ||
Ēvam sa jivā prithivīm samagrām bhagn-āgra-darpā[n] dvishataś-cha
kṛtvā | sarvvēshu dēśēshu vidhāya gōptri(ptrī)n samchintayā[m-ā]sa
bahu-prakāram || Syāt-kō-nurūpō
- 7 matimān-vini(m)itō mēdhā-smṛitibhyām-anapēta-bhāvāḥ | saty-ārjav-audārya-
nay-ōpapannō mādhyura-dākshīṇya-yaśō-nvitaś-cha || Bhaktō-nuraktō nri-
v[i]ś[ē]sha-yuktaḥ sarvv-ōpadhābhīś-cha viśuddha-buddhiḥ | ānṛṇya-
bhāv-ōpatag-āntarātmāḥ⁵ sarvvasya lōkasya hitē pravṛittaḥ ||
- 8 Nyāy-ārijanē-rthasya cha kaḥ samarthaḥ syād-arjitasy-āpy-atha rakshaṇē
cha | gōpāyitasy-āpi [cha] vṛiddhi-hētau vṛiddhasya pātra-pratipādānāya ||
Sarvvēshu bhṛityēshv-āpi samhatēshu yō mē praśishyān-nikhilān-
Surāshṭrān | ān jñātam-ēkaḥ khalu **Parpadattō** bhārasya tasy-
ōdvahanē samarthaḥ ||
- 9 Ēvam viniśchitya nrip-ādhipēna naikān-ahō-rātra-gaṇān-śva-matyā | yaḥ
samniyuktō-rthanayā kathamchit samyak-**Surāshṭr-āvani-pālānāya** ||
Niyujya⁶ dēvā Varuṇam pratichyām svasthā yathā n-ōnmanasō
babbhūvu[h] [l] pūrvvatarasyām diśi **Parpadattam** niyujya rājā
dhṛitimāms-tath-ābhūt | (||)
- 10 Tasy-ātmajō hy-ātmaja-bhāva-yuktō dvidh-ēva ch-ātm-ātma-vaśēna nītaḥ |
sarvvātman-ātm-ēva cha rakshaṇiyō nity-ātmavān-ātmaja-kānta-
rūpaḥ | (||) Rūp-ānurūpair-lalitair-vichitraiḥ nitya-pramōd-ānvita-sarva-
bhāvāḥ | prabuddha-padmākara-padmavaktro nṛṇām śaranyāḥ śaraṇ-
āgatānām | (||)
- 11 Abhavat⁷-bhūvi **Chakrapālītō**-śāv-iti nāmnā prathitaḥ priyō janasya |
śva-ḡuṇair-an-upaskritair-udātt[ai]ḥ pitaram yaś-cha viśēshayām-chakāra | (||)
Kāhamā⁸ prabhutvaṁ vinayō nayaś-cha śauryam vinā śaurya-
mah-[ā ?]rchchanam cha | vā(?)kya(?)m damō dānam-ādīnatā cha

* Metre, Aryā.

* nirvachanā.

* Metre, Upajāti of Indravajrā and Upēndravajrā.

* Metre, Indravajrā; and in the next six verses.

* Read ātmā.

* Metre, Upajāti of Indravajrā and Upēndravajrā; and in the next two verses.

* Metre, Vaitālyā-Aupachchhandasika.

* Metre, Upajāti of Indravajrā and Upēndravajrā; and in the next three verses.

the completely victorious one,—who, for the sake of the happiness of (Indra) the lord of the gods, seized back from (the demon) Bali the goddess of wealth and splendour, who is admitted to be worthy of enjoyment, (and) who had been kept away from him for a very long time!¹

(Line 2).—And next, victorious for ever is the supreme king of kings over kings, whose breast is embraced by the goddess of wealth and splendour; who has developed heroism by (the strength of his) arms; and who plucked (and utilised) the authority of (his local) representatives, who were so many Garuḍas, (and used it as) an antidote against the (hostile) kings, who were so many serpents, lifting up their hoods in pride and arrogance;²—**Skandagupta**, of great glory, the abode of kingly qualities, who, when (his) father by his own power had attained the position of being a friend of the gods,³ bowed down his enemies, and made subject to himself the (whole) earth, bounded by the waters of the four oceans, (and) full of thriving countries round the borders of it;—whose fame, moreover, even (his) enemies, in the countries of the **Mlêchchhas** having (their) pride broken down to the very root, announce with the words—"verily the victory has been achieved by him;"—(and) whom the goddess of fortune and splendour of her own accord selected as her husband, having in succession (and) with judgment skilfully taken into consideration and thought over all the causes of virtues and faults, (and) having discarded all (the other) sons of kings (as not coming up to her standard.)

(L. 5).—While he, the king, is reigning, verily no man among his subjects falls away from religion; (and) there is no one who is distressed, (or) in poverty, (or) in misery, (or) avaricious, or who, worthy of punishment, is over-much put to torture.

(L. 6).—Thus having conquered the whole earth, (and) having destroyed the height of the pride of (his) enemies, (and) having appointed protectors in all the countries, he cogitated in many ways,—“Among all my servants put together, who is there, who—suitable; endowed with intellect; modest; possessed of a disposition that is not destitute of wisdom and memory; endowed with truth, straightforwardness, nobility, and prudent behaviour; and possessed of sweetness, civility, and fame;—loyal; affectionate; endowed with many characteristics; and possessed of a mind that (has been tried and) is (found to be) pure by all the tests of honesty; possessed of an inner soul pervaded by (the inclination for) the acquittance of debts and obligations; occupied with the welfare of all mankind;—capable both in the lawful acquisition of wealth, and also in the preservation of it, when acquired, and further in causing the increase of it, when protected, (and able) to dispense it on worthy objects, when it has been increased,—shall govern all my (countries of the) **Surâhtras**? I have it; (there is) just one man, **Paradatta**, competent to bear this burden.”

¹ The legend is that the demon Bali, or Mahâbali, by his austerities acquired the dominion over the three worlds, and caused annoyance and anxiety to the gods. Vishnu then became incarnate as a dwarf, appeared before Bali, and asked for as much land as he could cover with three strides. Bali assented to his request, and Vishnu with two strides recovered the heavens and the earth, but, in commiseration for Bali, who then humbled himself, left him the dominion over the lower regions below the earth.

² Garuḍa, the servant and vehicle of Vishnu, half man and half bird, was the special enemy and destroyer of the serpent-race.—There is possibly a secondary allusion to Skandagupta having overthrown some kings of the well-known Nāga or serpent-lineage.

³ i.e. "had died."

(L. 9.)—(And it was *this same Parṇadatta*) who, with pressing (and) with difficulty, was appointed by the lord of kings, who had thus deliberated in his mind for many days and nights, to protect in a proper manner the land of the *Surāshṭras*. (And) just as the gods became comfortable, (and) not disturbed in mind, when they had appointed Varuṇa to the western point of the compass, so the king was easy at heart, when he had appointed *Parṇadatta* over the region of the west.

(L. 10.)—His son,—possessed of a filial disposition; his own self, as it were, reduplicated; well trained by self-control; worthy to be protected, as if it were his own self, by the all-pervading spirit; always self-possessed; endowed with a naturally beautiful form; having a disposition the whole of which was always pervaded with joy through a variety of charming actions that were in accordance with (*his*) beauty; having a waterlily of a face that resembled a bed of waterlilies in full bloom; the refuge of men who came to him for protection,—was *this same one* who is renowned on the earth under the name of *Chakrapālita*; who is beloved of the people; and who confers distinction upon (*his*) father by his own noble qualities which are everything except unpolished:—

(L. 11.)—In whom all these qualities dwell to a marked degree, (and) without ever wandering away (from him),—*vis.* patience; lordship; modesty; and good behaviour; and heroism without (*too*) great an estimation of prowess; eloquence (?); self-control; liberality; and high-spiritedness; civility; the acquittance of debts and obligations; and freedom from empty-headedness; beauty; and reprobation of things that are not right; absence of astonishment; firmness; and generosity. Even in the whole world there is no one to be found, in whom a comparison with his virtues may be made; verily he has become, in all entirety, the standard of comparison for men who are endowed with virtuous qualities.

(L. 12.)—(And it was *he*) who was appointed by (*his*) father, after testing in person (*the existence in him of*) these same qualities mentioned above, and higher ones even than them; and who then accomplished the protection of (*this*) city in a way that quite distinguished him above his predecessors. Relying upon the process of his own two excellent arms (?), not on the pride of any other man, he subjected no one in this city to any anxiety; and he punished wicked people. Even in this time which is a mean one, he failed not to maintain confidence in the people, together with the inhabitants of the city; and, by carefully inquiring into faults, he has charmed all the citizens, together with and children. And he has made (*his*) subjects happy by conversations addressed with smiles, and marks of honour, and presents; by free and reciprocal entering into (*each other's*) houses; (and) by carefully nourishing the family ceremonies of affection. Endowed with the highest piety, affable, pure, (and) in a suitable manner devoted to charity, he has, even without any conflict between religion and wealth, applied himself to such pleasures as may be attained at the proper time. What wonder is there in the fact that he, [born] from *Parṇadatta*, is possessed of such proper behaviour?; can heat ever be produced from the moon, which is cold like a string of pearls or like a waterlily?

(L. 15.)—Then, in due course of time, there came the season of clouds, bursting asunder with (*its*) clouds the season of heat, when much water rained down unceasingly for a long time; by reason of which (the lake) *Sudarśana* suddenly burst,—making the calculation in the reckoning of the *Guptas*,¹ in a century of years, increased by thirty and

¹ See page 57 above, note 4.

also six more, at night, on the sixth day of (the month) Praushṭhapada. And these (*other rivers*) which take their source from (the mountain) **Raivataka**,¹ (*and also*) this **Palāsini**, beautiful with (*its*) sandy stretches,—(*all of them*) the mistresses of the ocean,—having dwelt so long in captivity, went again, in due accordance with the scriptures, to their lord (*the sea*). (*And*) having noticed the great bewilderment, caused by the excess of rain, (the mountain) **Ūrjayat**, desirous of appropriating the wives of the mighty ocean, stretched forth as it were a hand, consisting of the river (**Palāsini**), decorated with the numerous flowers that grew on the edges of (*its*) banks.

(L. 17.)—[Then on all sides] the people fell into despair, discussing how they should act; and, spending the whole night awake in vain, in great anxiety they reflected,—“Here in a moment, (the lake) **Sudaršana** has (*by the overflowing of its waters*) assumed an unpleasing appearance² towards all the people, (*as if it were*) a man (?); having the appearance of the ocean, quite full of water, can it ever (*again*) become pleasing of aspect,?”

(L. 18.)— he³ having become and displaying the height of devotion towards his father, (*and*) holding in full view, for the welfare of the king and of the city also, religion, which has such auspicious results,—in a century of years, increased by thirty and seven others also, attentive to the sacred writings whose majesty is well known. Then, having sacrificed to the gods with oblations of clarified butter and with obeisances; and having gratified the twice-born with (*presents of*) riches; and having paid respect to the citizens with such honours as they deserved, and to such of (*his*) servants as were worthy of notice, and to (*his*) friends with presents,—in the first fortnight of the month belonging to the hot season,⁴ on the first day, he, having practised (*all the above*) respectful observances for two months, made an immeasurable expenditure of wealth, and, [built an embankment] a hundred cubits in all in length, and sixty and eight in breadth, and seven (?) men's height in elevation, of two hundred cubits. (*Thus*), having done honour to the kings, he laboriously built up, with a great masonry work, properly constructed, the lake **Sudaršana**, which is renowned as not being evil by nature, so that it should last for all eternity,—agitated by the defiance of the ruddy-geese which display (*their*) beauty along the edges of the firmly-built embankment, and by the settling down (*in its waters*) of the herons and the swans pure waters; on the earth the sun and the moon.

(L. 23.)—And may the city become prosperous; full of inhabitants; cleansed from sin by prayers sung by many hundreds of Brāhman; [and free from] drought and famine for a hundred years [Thus] ends the composition of the description of the restoration of (the lake) **Sudaršana**.

Second Part.

(L. 24.)— of him (**Skandagupta**), who destroyed the pride of (*his*) haughty enemies; who is of great glory; who is the banner of his lineage; who is the lord

¹ Raivataka is the hill opposite to Ūrjayat or Girnār.

² There is a play on the words *su-daršana* 'having a good appearance,' and *dur-daršana* 'having a bad appearance.'

³ i.e. Chakrapālita.

⁴ Grishma, the hot season, consists of the two months Jyēṣṭha (May-June) and Āṣāḍha (June-July). The name of one or the other of them is now illegible in this line.

of the whole earth; whose pious deeds are even more wonderful than his supreme sovereignty over kings;

(L. 24.)—..... (**Parnadatta**), the protector of the island, and the leader of great of armies for the subjugation of (*his*) enemies.

(L. 25.)—By his son, who is endowed with his own good qualities, (*and*) whose life is devoted to (*the worship of*) the feet of (the god) Gōvinda,; —by him, who causes the citizens to bow down by his own prowess, having there attained... .. and the feet, which are like waterlilies, of (the god) Vishṇu, with a great expenditure of wealth and time [there was built a temple] of that famous (god Vishṇu) who carries the discus, enemies, (*and*) who became (*incarnate and*) human by the exercise of his own free will. (*Thus*) by **Chakrapālita**, who is of a straightforward mind, there has been caused to be built a temple of (the god) Chakrabhrit, in a century of years, together with the thirty-eighth (*year*), the time of the **Guptas**.¹

(L. 27.)—..... uprisen, as it were, of the mountain **Ūrjayat**, shines as if displaying (*its*) lordship on the forehead of the city.

(L. 28.)—And another on the forehead obstructing the path of the birds, is resplendent

No. 15; PLATE IXA.

KAHAUM STONE PILLAR INSCRIPTION OF SKANDAGUPTA.

THE YEAR 141.

THIS inscription appears to have been discovered by Dr. Francis Buchanan (Hamilton),—whose Survey of the Provinces, subject to the Presidency of Bengal, was commenced in 1807 and was continued during seven years, and whose manuscript results were transmitted in 1816 to the Court of Directors of the East India Company,—and to have been first brought to notice in his reports, from which Mr. Montgomery Martin compiled, and in 1838 published, the book entitled *Eastern India*, in which the inscription is noticed in Vol. II. p. 366 f., with a reduced lithograph (*id.* Plate v. No. 2).—In the same year, in the *Four. Beng. As. Soc.* Vol. VII. p. 37 f., Mr. James Prinsep published his reading of the text, and a translation of it,² accompanied by a lithograph (*id.* Plate i.) reduced from a copy made by Mr. D. Liston.—In 1860, in the *Four. Amer. Or. Soc.* Vol. VI. p. 530, Dr. FitzEdward Hall published his reading of the first verse of the inscription, and a translation, which was subsequently revised and reprinted in the *Four. Beng. As. Soc.* Vol. XXX. p. 3, note.—In 1871, in the *Archæol. Surv. Ind.* Vol. I. p. 93 f. and Plate xxx., General Cunningham published another lithograph, reduced from his own impression.—And finally, in 1881, in the *Ind. Ant.* Vol. X. p. 125 f., Dr. Bhagwanlal Indraji published his revised reading of the text, and a translation of it, accompanied by a lithograph reduced from an impression made by him when he visited Kahāum in 1873.

¹ See page 57 above, note 4.

² The translation is reprinted in Thomas' edition of Prinsep's *Essays*, Vol. I. p. 250.

Kahāuh or **Kahāwah**,¹ the ancient **Kakubha** or **Kakubhagrāma** of this inscription, is a village about five miles to the west by south of Salampur-Majhauil,² the chief town of the Salampur-Majhauil Parganā in the Dēoriyā or Dēwariyā³ Tahsil or Sub-Division of the Gōrākhpur District in the North-West Provinces. The grey-sandstone column on which the inscription is, stands a short distance on the north of the village.⁴

Of the **sculptures** on the column, the most important are five standing naked figures, —one in a niche on the western face of the square base; and one in a niche on each side of the square block immediately below the circular stone with an iron spike in it, which, the original pinnacle having been lost, now forms the top of the column. As appears to have been first fully recognised by Dr. Bhagwanlal Indrajī, these are distinctly Jain images. He suggested that they represent the five favourite *Tīrthamkaras*,—Ādinātha, Śāntinātha, Nēminātha, Pārśva, and Mahāvira. And they are in all probability the five images of *Ādikartṛis*, or Jain *Tīrthamkaras*, referred to in the inscription itself.

The **writing**, which covers a space of about 2' 2½" broad by 1' 8" high, is on the three northern faces of the octagonal portion of the column; and the bottom line appears to be about 7' 6" above the level of the ground. It is evidently in a state of excellent preservation throughout.—The **size** of the letters varies from ¼" to ⅞". The **characters** belong to the northern class of alphabets, and are of the same type with those of the Allahābād posthumous pillar inscription of Samudragupta, No. 1, p. 1 ff. above, Plate i.—The **language** is Sanskrit; and, except for the opening word *siddham*, the inscription is in verse throughout.—In respect of **orthography**, the only points that call for notice are (1) the use of the dental nasal, instead of the *anusvāra*, before *ś*, in *vanśa*, line 2, and *itrinsat*, line 4; and (2) the usual doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *chakkrē*, line 9 (but not in *sakrō*, line 3), and *puttrō*, line 6.—My lithograph has been prepared from a lithograph of the same kind, handed to me by Dr. Burgess, from which was prepared the opposite lithograph, with the letters in black on a white ground, published with Dr. Bhagwanlal Indrajī's paper. One or two letters, imperfect in that lithograph, have been cleared out on the authority of General Cunningham's ink-impressions, which, though not adapted for complete reproduction, sufficed for this purpose.

The **inscription** refers itself to the reign of the **Early Gupta** king **Skandagupta**. It is dated, in words, in the year one hundred and forty-one (A.D. 460-61); and in the month *Jyēśhṭha* (May-June); but without any specification of the day of the month or fortnight. As is shewn by the images in the niches of the column, as well as by the tenour of the record itself, this is distinctly a Jain inscription. And the object of it is, to record that a certain **Madra** set up five stone images of *Ādikartṛis* or *Tīrthamkaras*,—i.e. apparently the five images in the niches of the column,—and the column itself, at the village of **Kakubha** or **Kakubhagrāma**, i.e. **Kahāuh**.

¹ The 'Kahaon, Kahong, Kangho, and Kuhaon, of maps, &c. Indian Atlas, Sheet No. 103. Lat. 26° 16' N.; Long. 83° 55' E.

The 'Sullempoor-Mujhowlee' of maps.

³ The 'Deorya' of maps.

⁴ For a full description, with drawings, of the column and other remains at Kahāuh, see *Archaeol. Surv. Ind.* Vol. I. p. 91 ff. and Plate xxix., and *id.* Vol. XVI. p. 129 f. and Plate xxix.

TEXT.¹

- 1 Siddham² [11³] Yasy⁴-ôpasthâna - bhûmir-nripati - âata - âirah⁴ - pâta - vât - âvadhûtâ
 2 Guptânâh vanâ-jasya pravisrita - yaâasas-tasya sarvv - ôttam - arddhêh
 3 râjyê âakr-ôpamasya kshiti-pa-âata-patêh Skandaguptasya sântê
 4 varshê ttrinâd-dâs-aik-ôttaraka-âatatamç Jyêshtha - mâsi prapannê 1(11)
 5 Khyâtê-smin-grâma-ratnê Kakubha iti janais-sâdhu-samsarga-pûtê 1⁴
 6 puttrô yas-Sômilasya prachura-guâa-nidhêr-Bhaâtisômô mahât[m]â
 7 tat-sûntê Rudrasôma[h⁵] prithula-mati-yaââ Vyâghra ity-anya-samjñô 1⁴
 8 Madras-tasy-âtmajô-bhûd-dvija-guru-yatishu prâyaâah prtimân-yaâ 1(11)
 9 Punya-skandham sa chakkrê jagad-idam-akhilam samsarad-vikshya bhîtô
 10 ârêyô-rttham bhûta-bhûtyai pathi niyamavatâm-arhatâm-âdikarttrin
 11 pañch-êndrâm(n) sthâpayitvâ dharanidharamayân-sannikhâtas-tatô-yam
 12 âaila-stanbhaâ su-chârur-giri-vara-âikhar-âgr-ôpamaâ kirtti-karttâ [11⁶]

TRANSLATION.

Perfection has been attained! In the tranquil⁷ reign of **Skandagupta**, whose hall of audience is shaken by the wind caused by the falling down (*in the act of performing obeisance*) of the heads of a hundred kings; who is born in the lineage of the **Guptas**; whose fame is spread far and wide; who excels all others in prosperity; who resembles (the god) **âakra**; (*and*) who is the lord of a hundred kings;—in the one hundredth year, increased by thirty and ten and one; the month **Jyêshtha** having arrived;—

(Line 5.)—In this jewel of a village, which is known by people under the name of **Kakubha**, (*and*) which is pure from association with holy men,⁸—(*there was*) the high-minded **Bhaâtisôma**, who (*was*) the son of **Sômila**, that receptacle of many good qualities. His son (*was*) **Rudrasôma**, of great intellect and fame, who had the other appellation of **Vyâghra**.⁹ His son was **Madra**, who (*was*) especially full of affection for **Brâhmanas** and religious preceptors and ascetics.

¹From Gen. Cunningham's ink-impression, together with the lithograph from which my lithograph is reduced.

²In the original, this word is in the margin; the *si* opposite the commencement of line 2, and the *ddham* opposite, and partly above, the commencement of line 3.

³Metre, Sragdharâ, throughout.

⁴The mark in the original after this *visarga* would seem to be an accidental slip of the engraver's tool, rather than intended for a mark of punctuation, which is not required here.

⁵and ⁶. In each case, the mark of punctuation is unnecessary.

⁷*idntê*. — It is unnecessary to explain in detail the interpretation of this word. The difficulty is,—not the correct rendering of it, which is perfectly obvious,—but to comprehend how it ever came to be read *idntê*, and to be interpreted by "of the repose, *i.e.* death," *i.e.* "after the decease (of Skandagupta);" or, being read *idntê* correctly, to comprehend how it ever came to be interpreted as meaning "(the empire of Skandagupta) being quiescent," or "(the empire of Skandagupta) being extinct (for the hundred and forty-first year)."—The correct interpretation appears to have been first pointed out by **Bhau Daji**; "in the year one hundred and forty-one, in the peaceful reign of Skandagupta" (*Jour. As. Soc. Br. R. As. Soc.* Vol. VIII. p. 246.)

⁸The proper context is—"(*there was*) **Madra**;" who is mentioned in line 8. The intervening genealogical matter is by way of a parenthesis.

⁹For some similar instances of second names, see page 27 above, note 4.

(L. 9).—He, being alarmed when he observed the whole of this world (*to be ever*) passing through a succession of changes, acquired for himself a large mass of religious merit. (*And by him*),—having set up, for the sake of final beatitude (*and*) for the welfare of (*all*) existing beings, five excellent¹ (*images*), made of stone,² (*of*) those who led the way³ in the path of the *Arhats* who practise religious observances,—there was then planted in the ground this most beautiful pillar of stone, which resembles the tip of the summit of the best of mountains, (*and*) which confers fame (*upon him*).

No. 16; PLATE IX B.

INDOR COPPER-PLATE INSCRIPTION OF SKANDAGUPTA. THE YEAR 146.

THIS inscription was discovered in 1874 by Mr. A. C. L. Carleyle, First Assistant to the Director-General of the Archaeological Survey of India; and was first brought to notice, in the same year, in the *Four. Beng. As. Soc.* Vol. XLIII. Part I, p. 363 ff., where a lithograph of it was published, prepared by General Cunningham (*id.* Plate xix.), accompanied by a version of the text, and a translation of it, by Dr. Rajendralala Mitra.

The inscription is on a copper-plate which was found in a small stream at **Indor**, the ancient **Indrapura** and **Indrâpura** of the inscription, a large and lofty mound about five miles to the north-west of Dîbhâl,⁴ the chief town of the Dîbhâl Parganâ in the Anupshahar⁵ Tahsil or Sub-Division of the Bulandshahar District in the North-West Provinces. Until recent years, Indôr was a small inhabited village; but it is now only a *khadd*, or deserted mound, and is not shewn in maps. I obtained the original plate, for examination, from the possession of General Cunningham.

The **plate** is a single one, inscribed on one side only, measuring about $8\frac{1}{2}$ " by $5\frac{1}{2}$ " at the ends and $5\frac{1}{2}$ " in the middle. The edges of it are here and there slightly thicker than the surface of the plate, with small depressions inside them at the same places; but there does not seem to have been any intention of purposely fashioning the edges thicker all round, so as to serve as a rim to protect the writing.⁶ The surface of the plate is in some places

¹ *indrân*.—Bhagwanlal Indrajî, in his published version, first pointed out the kind of meaning to be given to this word here


² *lit.* 'made of (the substance of) mountains.'

³ *âdikartîrîn*; *lit.* 'originators'—Bhagwanlal Indrajî first pointed out the correct meaning of this word, as referring here to five of the *Tîrthamkaras* or sanctified teachers of the Jains.


⁴ The 'Daobhai, Dhubhai, Dibai, and Dubhaee,' of maps, &c. Indian Atlas Sheet, No. 67. Lat. $28^{\circ} 12' N.$; Long. $78^{\circ} 18' E.$ —The position of Indôr, with reference to Dîbhâl, is shewn in the sketch map given in *Archæol. Surv. Ind.* Vol. XII. Plate i

⁵ The 'Anoopshuhur and Anupshahr' of maps, &c.

⁶ Dr. Burnell allotted the earliest instances of arranging for the preservation of the writing on copper-plates, by beating up the margins round the plates and then flattening the edges, to the ninth or tenth century A.D. (*South-Indian Palæography*, p. 92). But there are plenty of earlier instances, in the south, as well as in the north of India. These raised rims were obtained, at first, by thickening the plates at the edges, in the process of fashioning them. Afterwards, it became customary to beat the plates out quite smooth, and then to turn them up at the edges and fuse them together at the corners; and some of the Eastern Chalukya plates, made in this way, have raised rims a good quarter of an inch high.



B.—Indo: Plate of Skandagupta—The Year 146



a good deal corroded by rust; the inscription, however, with care, is legible with certainty throughout. The plate is fairly thick; but the letters, being rather deeply engraved, shew through distinctly on a great part of the back of it. The engraving is clean and well executed; the majority of the letters, however, shew, as usual, marks of the working of the engraver's tool.—There is no hole in the plate for a ring with a seal on it; nor are there any indications of a seal having been soldered on to it, as,—from the instance of the spurious Gayā grant of Samudragupta, No. 60 below, Plate xxxvii.; illustrated also, in the present series by the Aśirgaḍh seal of Śarvavarman, No. 47 below, Plate xxxA., and the Sōnpat seal of Harshavardhana, No. 52 below, Plate xxxiiB.; and, elsewhere, by the Dighwā-Dubauil grant of the *Mahārāja* Mahēndrapāla¹ and the Bengal Asiatic Society's grant of the *Mahārāja* Vināyakapāla,²—seems to have been the early custom in the north of India.—The weight of the plate is 1 lb. 2 oz.—The average size of the letters is between $\frac{1}{4}$ " and $\frac{1}{8}$ ". The characters belong to the northern class of alphabets, and in essential details are of the same type with those of the Mathurā inscription of Chandragupta II., No. 4, p. 25 ff. above, Plate iiiA. The initial *i* has an entirely different form from that of the other northern type; contrast it in *indrapura* and *iś*, line 8, with *iva* in Plate i. page 9 above, line 30, and *iti* in Plate ixA. page 67, line 7. In line 10, we have a form of the numerical symbol for 2.—The language is Sanskrit, and all the formal part of the inscription, from *paramabhattāraka*, line 3, to *samakāliyam*, line 10, is in prose. From a linguistic point of view, we have to notice the affix *ka*, in *chandrāpuraka*, line 5, *indrāpuraka*,³ line 6, and especially *pratishthāpitaka*, line 7. It is a weaker form, without *vyiddhi* of the vowel in the first syllable, of the *ka* with which the adjectives of locality, used in lines 19 and 20 of the Allahābād posthumous pillar inscription of Samudragupta, No. 1, page 7 above, are formed; and it is the origin of the modern Hindi genitive terminations *kā*, *kē*, and *kī*, and of similar declensional forms. Other instances of it are given by No. 25 below, Plate xvB. line 13, *kāritaka*; No. 26 Plate xvi. line 10, *utpadyamānaka*; No. 27, Plate xvii. line 9, *pratishthāpitaka*, and line 12, *utpadyamānaka*; No. 28, Plate xviii. line 13, *anumōditaka*, line 14, *uparīkhitaka* and *pratishthāpitaka*, and line 18, *utpadyamānaka*; No. 29, Plate xixA. line 10, *uparīkhitaka* and line 15, *utpadyamānaka*; No. 31, Plate xx. line 9, *utpannaka*, lines 9 and 16 *utpadyamānaka*, and line 11, *kāritaka*; No. 41, Plate xxvii. line 11, *atīśrīṣṭaka*; and No. 62, Plate xxxviiiB. line 4, *pravīṣṭaka*.—In respect of orthography, we have to notice (1) the use of the guttural nasal, instead of the *anusvāra*, before *ś* and *h*, in *chatvāriṅśad*, line 3 f., and *sinha*, line 6; (2) the doubling of *k*, and usually of *t*, in conjunction with a following *r*, e.g. in *apakkramana*, line 8 f., and *pautraḥ*, line 5, (but not in *putrā* in the same line); and (3) the doubling of *v* after the *anusvāra*, in *samvatsara*, line 3.

The inscription refers itself to the reign of the Early Gupta king Skandagupta, whose feudatory, the *Vishayapati*⁴ Śarvanāga, was governing Antarvēdi⁵ or the country

¹ *Ind. Ant.* Vol. XV. p. 105 ff.

² *id.* p. 138 ff.

³ As regards these two words, Monier Williams, in his Sanskrit Dictionary, gives *puraka* as another form of *पुरा*, 'a city'; but refers only to 'Arghāṣṭapuraka' as an authority for the word. This city, however, only owes its existence to one of the early misreadings of *Manārāja-Paishāpuraka* in line 19 of the Allahābād inscription, No. 1, page 7 above.

⁴ *Vishayapati* is a technical official title, meaning 'the lord, or governor, of a *vishaya*'—See p. 32 above, note 7.

⁵ Antarvēdi may perhaps also denote any Doab or region between two rivers of repute and sanctity.—It also means, as an adjective, 'belonging to the inside of the sacrificial ground.'—It occurs,

lying between the Ganges and the Jamnā. It is dated, in words, in the year one hundred and forty-six (A.D. 465-66); and in the month Phālguna (February-March), but without any specification of the day of the month or fortnight. It is an inscription of solar worship; and the object of it is to record a perpetual endowment, by a Brāhmaṇ named **Dēvavishṇu**, for the purpose of maintaining a lamp in a temple of the Sun at **Indrapura** or **Indrāpura**, i.e. the modern **Indōr**. This mention of the place, under its ancient name, connects the record satisfactorily with the locality in which the plate was found.

TEXT.¹

Sole Plate.

- 1 Siddham [I¹] Yam² viprā vidhi-vat-prabuddha-manasō dhyān-aika-tānā(na)-stuvah³ yasy-āntam tridaś-āsuraṅ na vividur-nn-ōrdhvam na tiryā-
- 2 g-gaūḥ(ṛ) yam lōkō bahu-rōga-vēga-vivaśah samsṛitya chētō-labhaḥ pāyād-vah sa jagat-pidhā'na-putā-bhid-raśmy-ā-
- 3 karō bhāskarah || Paramabhaṭṭāraka-mahārājādhirāja-śri-**Skandaguptasy**-ābhivarddhamāna-vijaya-rājya-samvatsara-śatē⁴ shach(t)-chatvā-
- 4 [ri⁵]nsād-uttaratamē Phālguna-māsē . tat-p[ā⁶]da-pariṅghitasya vishayapati-**Sarvvanāgasy**-Āntarvedyām bhōg-ābhividdhayē vartta-
- 5 mānē [I¹] **Chandrāpuraka**-Padmā-chāturvīdyā-sāmānya-brāhmaṇa-**Dēva-vishṇur**-Ddēva-putrō Hanitrāta-pauttraḥ Ḍḍḍika-prapauttraḥ satat-āgnihō-
- 6 tra-[ch⁷]chhandōgō Rānāyanī(ni)yō Varshagāṇa-sagōttira **Indrāpuraka**-vaṅgibhyām kshattriy-Āchalavarma-Bhri(bhru)kuṇṭhasinhābhyaṁ-adhishtā(shthā)-
- 7 nasya prāchyām diś-**Indrapur**-ādhishtānā-mādāyātā-lagam-ēva pratishthāpitaka-bhagavatē savitrē dlp-ōpayōjyam-ātma-yaśō-
- 8 bhividdhayē mūlyam prayachchhati⁸ [I¹] **Indrapura**-nivāsinyās-tailika-śrēnyā Jivanta-pravarāyā itō-dhishtānād-apakkrama
- 9 na-sampravēśa-yathāsthirāyāḥ ājasrikam grahapatēr-dvija-mūlyā-dattam-Anayā tu śrēnyā yad-abhagna-yōgam
- 10 prattha(tham)-m-ārḥ-āvya[va⁹]chchhinna-samstham dēyam tailasya tulyēna¹⁰ paladvayam tu² a chandr-ārka-samakālyam [I¹]

as the name of a village, in 'Anterbed,' about thirty miles west of Uchaharā, in the Indian Atlas, Sheet No. 70; Lat. 24° 25' N.; Long. 80° 13' E. And we also have it in Antarvēdi, Antaravēdi, or Antravēdi, the name of a shrine at the mouth of the Vasishṭha branch of the river Gōdāvarī, seven miles south of Narsāpur, in the Narsāpur Tālukā or Sub-Division of the Gōdāvarī District.

¹ From the original plate.

² Metre, Śārdūlavikrīḍita.

³ The form *stū* is rather unusual; the customary form being *stūt*. But Dr. Bühler has given me the analogous instance of *dyata-stū*, which is mentioned by Kātyāyana in his comments on Pāṇini, iii, 2, 76. The meaning of *dyata-stū* is not given in the *Mahābhāṣya*; but Monier Williams explains it by 'panegyrist.'

⁴ This is rather an anomalous *akshara*; but it can mean nothing but *dād*.

⁵ Read *rājyē samvatsara-tat*; see p. 38 above, note 5.—Gen. Cunningham (*Archæol. Surv. Ind.* Vol. XII. p. 40) considered that there is a faint trace of the vowel *ē* of *rājyē*; but the vowel was not engraved.

⁶ Read *prayachchhati*.—That the marks after *ti* are the *visarga*, and not marks of punctuation, is shown by the form of the *visarga* throughout this inscription, and, contrasted with it, the marks of punctuation after *bhāskarah*, l. 3, and at the end of the inscription.

⁷ *tulyēna* seems to be a mistake for *tulyāna*.

⁸ i.e. *tulyēna* (*tulyāna*).

- 11 Yô¹ vyakkraméd²-dāyam-imam nibaddham gô-ghnô guru-ghnô dvija-
ghâtakāḥ saḥ³ taiḥ pātakai[h⁴]
12 pañchabhir-anvitô-dhar-gachchhên⁵-naraḥ s-ôpanipātakaiḥ-ch-êti ||

TRANSLATION.

Perfection has been attained! May that Sun, the rich source of rays that pierce (*the darkness which is*) the envelope of the earth, protect you,—whom Brāhman, of enlightened minds, (*have recourse to*)⁶ according to due rite, (*and thus become*) the utterers of praises in meditation, which are directed solely to him; whose limit, either vertically or from side to side, neither the gods nor the demons could ascertain; (*and*) by having recourse to whom, mankind, when they have lost control of themselves through much disease and agitation of the mind, acquire consciousness (*again*)!

(Line 3).—In the augmenting victorious reign⁷ of the *Paramabhaṭṭaraka* and *Maharājādhirāja*, the glorious *Skandagupta*; in the year one hundred, increased by forty-six; (*and*) while the month Phālguna is current for the increase of the enjoyment, in (*the land of*) *Antarvêdī*, of the *Vishayapati Śarvanāga*, who has been accepted (*with favour*) by his⁸ feet;—

(L. 5).—The Brāhman *Dēvavishṇu*, who belongs to the community of *Chaturvêdīns* of Padmā of the town of *Chandrôpura*,—who is the son of Dēva, (*and*) the son's son of Hanitrāta, (*and*) the son of the son's son of Duḍika; who always recites the hymns of the *agnihôtra*-sacrifice;⁹ who belongs to the *Rāpāyanīya* (*sākhā*); (*and*) who is of the *Varshagana gôtra*,—for the increase of his own fame gives an endowment, (*of which the interest is*) to be applied to (*the maintenance of*) a lamp for the divine Sun, which has been established (*in a temple*) by the Kshatriyas Achalarvarman and Bhrukupṭhasiṅha, merchants of the town of *Indrāpura*,¹⁰ on the east of the settlement, (*and*) actually touching¹⁰ of the settlement of the town of *Indrapura*.

(L. 8).—This gift of a Brāhman's endowment of (*the temple of*) the Sun, (*is*) the perpetual property of the guild of oil-men, of which *Jivanta* is the head, residing at the town of *Indrapura*, as long as it continues in complete unity, (*even*) in moving away from this settlement. But there should be given by this guild, for the same time as the moon and the sun endure, two *palas*¹¹ of oil by weight, (*or in figures*) by weight 2, uninterrupted in use, (*and*) continuing without any diminution from the original value.

(L. 11).—Whosoever shall transgress this grant that has been assigned,—that man, (*becoming as guilty as*) the slayer of a cow, (*or*) the slayer of a spiritual preceptor, (*or*)

¹ Metre, *Indravajrā*.

² Read *yô vikkrāméd*; or, better, *yô-tikkraméd*.

³ Read *sa*.

⁴ Read *dhô gachchhên*.

⁵ Supply *samirīya*, from the third *pāda* of the verse.

⁶ See page 38 above, note 5.

⁷ *i.e.* *Skandagupta's*.

⁸ *agnihôtra*, 'an oblation to the god Agni, consisting chiefly of milk, oil, and sour gruel, offered every morning and evening; the maintenance of the sacred fire.'

⁹ Here, line 6, the vowel of the second syllable is long; in lines 7 and 8 below, it is short.

¹⁰ The meaning of *māhāyāta* is not apparent.

¹¹ *pala*, a particular weight, = 4 *svarnas* (gold-pieces), or 64 *māshas* (beans); see the *Mānavadharmasūtra*, viii. 135, Bunnell's Translation, p. 200.

the slayer of a Brāhman, shall go down (*into hell*), invested with (*the guilt of*) those (*well-known*) five sins,¹ together with the minor sins.²

No. 17; PLATE X.

GANGDHAR STONE INSCRIPTION OF VISVAVARMAN. THE YEAR 480.

THIS inscription, which is now published for the first time, was brought to my notice in 1883, through a photograph sent to me by Colonel W. Muir, then Political Agent at Kōṭā in Central India.

Gāṅgdhār³ is a village about fifty-two miles south-west of Jhālrāpāṭan, the chief town of the Jhālāwād⁴ State in the Western Mālwa division of Central India. The inscription is on a stone-tablet standing under a tamarind-tree about a mile to the north of the village; evidently on the site of an old ruined temple.

At the top of the stone there is some **sculpture**, which I cannot quite make out in the rough drawing of it that was brought to me with the ink-impression; but it is probably a sixteen-leaved waterlily.—The **writing** covers the entire front of the stone, about 2' 0³/₈" high by 3' 8" broad. Twelve letters are broken away and lost in the first part of line 1; eleven in line 2; three in line 3; and two or three all the way down from there as far as line 36. In lines 4 to 36, however, it is in most cases easy to supply what has been lost. In lines 37 to 40, again, from three to six letters are broken away at the beginning, and from two to four at the end of each line. The inscription was thus of a somewhat irregular shape, lines 1 to 6 and 37 to 41 being rather longer than lines 7 to 36; which looks as if the stone on which it was engraved was a panel in the wall of a temple.—The **size** of the letters varies from about $\frac{3}{8}$ " to $\frac{5}{8}$ ". The **characters** belong to the southern class of alphabets; and give a specimen of what may be called the Western Mālwa alphabet of the fifth century A.D. They include, however, in *khadga*, line 5, and in several other places, not merely a separate form of the lingual *d*, as distinct from the dental *d*, in accordance with the custom of the northern alphabets, but a quite unique form of it, which does not occur in any other early inscription that I know of, and which is the clear prototype of the modern Dēvanāgarī form of this letter. They also include the very rare initial *au*, in *aupamyā*, line 6.—The **language** is Sanskrit; and except for the words *siddhir-astu* at the end, the inscription is in verse throughout.—In respect of **orthography**, we have to notice (1) the use of the *jihvdmūlīya*, e.g. in *chakitaiḥ-kriyatā*,

¹ i.e. the *pañcha mahāpātakāni*; see page 38 above, note 4

² The *upanipātakāni*,—or more usually *upapātakāni*, the longer form being used in this verse for the sake of the metre,—are sins of the second degree, such as killing a cow, sacrificing for those for whom sacrifices ought not to be made, &c. &c.: see the *Mānavadharmasūtra*, xi. 60 to 67, Bunnell's Translation, p. 332 f.

³ The 'Gangrar, Gungra, and Gungurar,' of maps. Indian Atlas, Sheet No. 35. Lat. 23° 56' N.; Long. 75° 41' E.—The modern name must be connected with Gargara, the ancient name, according to line 23 of this inscription, of the small river, now called 'Kalisind,' on which it stands. But it is not apparent how the dental *dh* came to be introduced into it; nor why it appears as *r* in the corrupt English forms.

⁴ The 'Jhalawar, Jhallawar, and Jhallowar., of maps, &c.

line 11, and *subhujā-khadga*, line 26; (2) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *vaśā*, line 29, and *antumān*, line 35; but not in *vaśā* in line 2; (3) the frequent doubling of *k*, *g*, *t*, and *p*, in conjunction with a following *r*, e.g. in *vikkramēna*, line 8; *samaggrām*, line 4; *vittrasta*, line 13; and *appratimēna*, line 4; and of *bh*, in *vyabhāra*, line 9; and (4) the same in respect of *kh*, *t*, *bh*, and *s*, in conjunction with a following *y*, e.g. in *prakhhyāta*, line 2, and *vikkhyāpāyan*, line 26; *bhṛitīya*, line 4, and *prattiyasta*, line 14; *abhyudyata*, line 15; and *yassya*, lines 11, 12, 14, 16, and 31.

The inscription is of the time of a prince named **Viśvavarman**. It is dated, in words, when four hundred and eighty years had expired, i.e. in the four hundred and eighty-first year, on the thirteenth day of the bright fortnight of the month Kārttika (October-November).¹ The era is not specified in this record; but of course the date

¹The passage containing the date, line 19 f., is not an easy one to deal with. — The date of four hundred and ninety-three, given in the next inscription, for Visvavarman's son Bandhuvvarman, shews that the number of the centuries in the present passage must be four. And the reading that I give is exactly in accordance with the appearance of the original. But there are the objections, (1) that it is a violation of the metre, since it gives us, in *chaturshu*, an amphibrach where a dactyl is required; and (2) that it leaves *kṛitīshu*, 'made, done, performed,' as a superfluous and rather unmeaning word, unless we somewhat strain its meaning by giving it the sense of 'fully completed (years).—In the sense of '(years) accomplished, i.e. expired,' *kṛitīshu* occurs in line 1 of the Byānā inscription of Vishuvardhana, of the year 428, No. 59 below, Plate xxxviC. But, though this use of it is unusual, it is justifiable there, as it is not accompanied by *yātīshu*, 'having gone by,' or any similar word.—My first inclination about the present passage was, that *kṛitīshu* was used in the sense of 'made, effected, established by;' and that the three *aksharas* preceding it contained the name of the founder of the era. But Dr. R. G. Bhandarkar, with whom I discussed the passage, was of opinion that *kṛita* could not be used in such a sense; and I am not able to quote anything opposed to his opinion. Moreover, that interpretation would have left us without any word to specify the centuries of the date.—My next inclination was to read *cha tsapu-kṛitīshu*, which would satisfy the metrical requirements, and may be justified by the appearance of the original; and to look upon *tsapu* as intended for a vocalisation of the numerical symbol for four hundred; "made by (the utterance of) *tsapu*." The very peculiar expression, *sāttarapādēshu*, which follows, seemed to point to something of this kind being intended. And Dr. Bühler has given an instance of a pronunciative value being certainly allotted to the symbol for four (*Ind. Ant.* Vol. VI. p. 47 f.). But to this interpretation there are the objections, (1) that the word *cha* would be rather superfluous and unmeaning; and (2) that the symbol for four hundred does not resemble the syllables *tsapu*. — Dr. Bhandarkar also suggested that the word 'four' is expressed by *kṛita* (in *kṛitīshu*). But this would leave the preceding two or three *aksharas* altogether unexplained. And, though *Kṛita*, as the name of the first of the four ages, is capable, on the numerical-word system, of being used to represent the number four, this system was not in use in inscriptions in India at this early time. The period of the invention of the system in question still remains to be determined. That the use of it was known to Varāhamihira (died A.D. 587; *Jour. R. As. Soc. N. S.* Vol. I. p. 407), is shewn by his employing, in the *Bṛihat-Samhitā*, viii. 20, 21, the words Rudra for 'eleven,' Rāma for 'three,' *aga* (mountain) for 'seven,' and *sara* (arrow) and *vishaya* (object of sense) for 'five.' And it has been supposed that it was used by Āryabhaṭa (born A.D. 476; *id.* p. 405); but Dr. Bhau Daji (*id.* p. 404) has pointed out, from his own MS., that the half-verse in question, the only apparent instance, giving the number of the revolutions of the planet Jupiter in numerical words, is not really Āryabhaṭa's (a point that is supported also by the metre; for the two lines together make up a verse in the Upagīti metre; whereas Āryabhaṭa used the Āryā metre, and the first line is the second half of a verse in that metre); but is an addition, in all probability by Utpala or Bhaṭṭōpala (about A.D. 966; *id.* p. 410). The earliest epigraphical instances, at present available, are, in Cambodia, the Bayang inscription, dated Śaka-Samvat 526 (A.D. 604-5) and 546 (Barth's *Inscriptions Sanscrites du Cambodge*, p. 36, line 11), where the dates are expressed by the (five) arrows (of Kāmadēva), Dasra (one of the two Aśvināu), and the (six) flavours, and by the (five) senses, the (four) oceans, and the (six) seasons; and, in India

- 11 [śōbhā]ḥ ||(1) yassy-āri-kāminī-mukhāmburūhair-bbalasya pūrvvāḥ pratāpa-
chakitāḥ-kriyatē prāṇamāḥ || Ratn-ōdgama-dyuti-
- 12 [vira]ḥjīta-kūla-tālair-uttrasta-nakkra-makara-kshata-ph[ē]na-mālaiḥ ||(1) chaṇḍ-
ānil-ōddhata-taraṅga-samasta-hastair-yyassy-ā-
- 13 [rṇṇavai]r-api balāni namahkriyantē || Bhūr-uddhri(dddhri)ta-druma-
vikampita-sāila-kīla-vittrasta-vidruta-mṛiga-dvija-sūnya(nya)-gu-
- 14 [lmā] [l] yassy-ōnnata-praviṣham[j]kri(kri)ta-rājamārggā ssaīnya²-prayāṇa-samayē
vinimajjat-iva || Pratyasta-mauli-
- 15 [ma]ṇi-raśmi-nakha-prabh-āndhair-abbhyudyat-āñjalitayā śabal-āgragaṇḍaiḥ ||(1)
vidyādharaiḥ ppriyatamā-bhujā-pāśa-ba-
- 16 [ddhair-yya]ssy-ādarād-divi yāśā[m]si namahkriyantē || Agrē-pi yā(yō)
vayasi samparivarttamānaś-śāstr-śausāra-pari-
- 17 [varddhitā]-suddha-baddhīḥ ||(1) śaḍ-dharma-mārggam-iva rājasu darsa-
yishyan-rakṣā-vidhim Bharata-vaj-jagataḥ-karōtī || Tasmīn-pra-
- 18 [śāsa]ṭi mahīm-nṛipati-pravṛtē svarggam yathā surapatāv-amita-prabhāvē ||(1)
n-ābhūō-adharmma-niratō vyaśan-ānitō
- 19 [vā lōkē] kadāchana janas-sukha-vaṅjītō vā || Yātēshu chatu[r]shu³
kri(kri)tēshu śatēshu śatēshu sausaishvā(? śhṭhā)śta-śōttarapādēshv-iha vatsa-
- 20 [rēshu] ||(1) śuklē trayōdaśa-dīnē bhuvī Kārttikasya māśasya sarvva-jana-
chitta-sukh-āvahasya || Nīl-ōtpala-pra-
- 21 [śrīta-rē]ṇv-arūp-āmbu-kṛpē bandhōka-bāṇa-kusum-ō[j]*vala-kānan-āntē ||(1)
nidrā-vyapāya-samayē Madhusūdanasya kā-
- 22 [lē prabu]ddha-kumud-āgara-suddha-tārē || Vāpi-tadāga-surasadmasabh-ōdupāna⁴-
nānāvidh-ōpavana-saḥkrama-dīrgḥik[ā]-
- 23 [bhīḥ] ||(1) sē(i)śhṭām-iv-ābharāṇa-jātibhir-aṅganām svām yō Garggarā-
tata-puram sakka(ma)lañ-chakāra || Rāñhas-tritīyam-iva chakshur-udā-
- 24 [ra-vṛitti]r-ddēva-dvijāti-guru-b[ā]ndhava-sādhu(?)-bhaktāḥ ||(1) [ra]i[ḥ]* stutē
cha vinay[ē⁵] vyavahāra-hīnē yō-pakshapāta-rahītō nidadh[au]
- 25 [sva-chint]ām || Sarvvasya jīvitam-a-nityam-a-saravach=cha doā-chalām-anu-
vichintya tathā vibhūtim ||(1) nyāy-āga[tē]-
- 26 [na vi]bhavēna parāñ-cha bhaktim vikkyāpayann-upan chaktra-gadā-
dharasya || Pīna⁶-vyāyata-vṛitta-lambi-subhujāḥ-khadga-vraṇ[ai]-
- 27 [r-añki]tāḥ ||(1) karṇ-ānta-pratisarpamāna(na)-nayana[h*] gyā(śyā)m-āvadāta-
chchhaviḥ ||(1) darpp-āvishkri(śhkri)ta-sō(śā)ra-śattru-mathanō dushṭh(śhṭ)-
śśva-
- 28 [—] ball ||(1) bhaktyā ch-āsuhrīdāñ-cha bāndhava-samō dharmm-ārttha-
kām-ōditāḥ || Praññā-sauryya-kul-ōdgatō diśi-
- 29 [diśi] prakhyāta-vṛyyō vaśī ||(1) puttṛē Vishṇubhatē tathā Haribhatē
sambaddha-vaśā-kriyāḥ ||(1) ēta-

¹ The final long *i* of *kāminī* is shortened for the sake of the metre.

² Read *ssīnya*.

³ See page 73 above, note 1.

⁴ Read *ssamyśhu=śīta*; which, however, entails another violation of the metre, since *śīta*, 'the eightieth,' gives us an *anpībrach* where an *antibacch* is required.—We might satisfy the requirements of the metre by reading *ssamyś=śhī-śīta*, which would give the 'eighty-eighth (year).' But this would also give us a locative singular, *ssamyś*, where the locative plural, *ssamyśhu*, is required in apposition with *śāśha*.

⁵ Read *śāpāna*, or *śāpāna*.

⁶ Metre, Śārdūlavikṛdita; and in the next verse.

- 30 [t-pāpa]path-āvarōdhi vipulā śrī-vallabhē(bhai)r-ātmaiaih ||(1) Vishṇō[h*]
sthānam-akārayad-bhagava-
- 31 'tas-śrī]mān-**Mayūrāksakaḥ** || Kailāsa¹-tuṅga-sikhara-ppratimasya yassya
driṣṭv-ākri(kṛi)tiṃ pra-
- 32 [moditai]r-vvadan-āravindi(ndai)u ||(1) vidyādharāḥ ppriyatamā-sahitāḥ su-
śōbbham-ādarsī(rsa)-bimba-
- 33 [m=iva] yānty-avalōkayantāḥ || • Yān²-driṣṭvā sura-sundarī-kara-taja-
vyāghriṣṭa-prishṭha-kshaṇam ||(1) prattyā
- 34 [vartta]na-śaṅkinō, ratha-hayān-ākri(kṛi)ṣhya chañchat-saṭān ||(1) puṇy-ōdarka-
mati-prabhāva-munibhis-saṃ
- 35 [stō]yamānō-mbarō ||(1) samrajy-āñjali-kōṭṭalan³-nata-śirā bhītaḥ prayatṭy-
anśumān || Mātri(trī)ḥā⁴-cha
- 36 [pramu]dita-ghan-ātyartha-nihradīnām ||(1) tāntr-ōdbhūta-prabala-pavan-ōd-
varttit-āmbhōnidhīnām ||(1)
- 37 — — — — —]gatam-idam dākinī-saṃprakīrṇam ||(1) vēśm-ātyugraṃ
nripati-sachivō-kārayat-punya-hētōḥ || Pātālō⁵ [— — —]
- 38 [— —]ratibhir-gguptam bhujāṅg-ō[pa*]maih ||(1) śīta-svādu-viśuddha-bhūri-
salilam sōpāni(na)-māl-ōjj[*]valam ||(1) da(?)[— — —]
- 39 [— — —]gahanam kshtrōdadhī-sparddīnam ||(1) kōpañ-ch-ainam-akārayad-
gupa-nidhiḥ śrīmān-**Mayūrāksakaḥ** || Yāvach⁶-ch[— — —]
- 40 [— — —] sāgarā ratnavantō nānā-gulma-druma-vanavatī yāvad-urvī sa-
śai(?)lā ||(1) yāvach-ch-ēndur-ggraha-gaṇa-chitam vyōma bhā[śika]-
- 41 [rōti tā]vat-krttir-bbhavatu vipulā śrī-**Mayūrāksakasy**-ēditī⁷ Siddhir-
astu ||(1)

TRANSLATION.

..... the arm of (the god) Vishṇu ;
..... the serpentine movements of the trunk of (Airāvata) the
elephant of (Indra) the lord of the gods

(Line 2).—Born in a lineage of rulers of the earth who were possessed of renowned
prowess and fame
beautiful there was the illustrious king **Naravarman**, the famous one ;—
who pleased the gods with sacrifices, the saints with observances of a noble nature

..... (his) servants with honourable
treatment that was unequalled in the world, and the whole earth with excellent achieve-
ments ;—[who] the appliances of elephants and horses

..... in [battle-fields] which were full of the rays of (his) sword ; (and whose)
enemies, losing the power of motion through fear, are destroyed (by simply) seeing his face
in the van of war.

(L. 5).—[His son⁸] magnanimous ; equal to Brihaspati in
intellect ; possessed of a countenance like the full-moon ; the standard of comparison, as it

¹ Metre, vasantatilaka.

² Metre, Sārdūlavikṛḍita.

³ Read *samkuchy-āñjali-kutmalan*

⁴ Metre, Mandākrāntā.

⁵ Metre, Sārdūlavikṛḍita.


⁶ Metre, Mandākrāntā.

⁷ The composer, or the writer, seems to have become confused here between *Mayūrāksakasy* & *iti*, which is the correct reading, and *Mayūrāksakasya syād-iti*.

⁸ Or possibly " [his younger brother]" ; see page 74 above, note 4.

CORPUS INSCRIPTIONUM INDICARUM.

Gangdhar Inscription of Visvavarman —The Year 480



were, for (even) Rāma and Bhagīratha; on the earth, (was) Viśvavarma;—who surpassed (the mountain) Mēru in firmness, Vaiśya in hereditary virtue, the moon in development of lustre, (the god) Viṣṇu in strength, and the most unendurable fire of universal destruction in brilliance, and (Indra) the lord of the gods in prowess;—who, when he grasps (his) weapon, cannot be gazed upon even for a moment by (his) enemies, whose eyes are blinded by fear, just like a sun, which, turning back upon (its) course, has an unendurable form and a brilliant and terrible lustre that is heightened by rising in a cloudless sky;—to whom obeisance is performed by the waterlilies which are the faces of the lovely women of (his) enemies, frightened beforehand by (hearing of) the prowess of (his) strength, (and now) destitute of ornaments, moist on the cheeks with the water of the tears that cling there, (and) deprived of beauty by having their wearing of adornments stopped;—whose forces, moreover, have reverence done to them by [the oceans], the palmyra-trees on the shores of which are beautified by the lustre of the production of jewels (from the waters); the rows of the foam on which are broken through by the terrified sharks and marine monsters; (and) all of whose hands, which are their waves, are shaken about by a fierce wind;—at the time of the journeying forth of whose army, the earth has (its) thickets emptied of the beasts and birds which flee away from fear of the lances that uproot the trees and make the mountains tremble, and, having (its) highways made uneven by protuberances, sinks down as it were (under the tread of his troops);—whose reputation has respect paid to it in a reverential manner in the sky by the Vidyādhara, bound in the fetters of the arms of (their) mistresses, who are blinded by the radiance, directed towards (them), of the rays of the jewels in (his) diadem, (and) the upper parts of whose cheeks are shaded by the lifting up of (their) joined hands in the act of respectful salutation;—and who, even when he was still in early youth, nourished (his) pure intellect by following the sacred writings, and now effects the protection of the world like Bharata, pointing out, as it were, the path of the true religion among kings. While he, the king, the bravest among kings, is governing the earth, just as (Indra) the lord of the gods, of unmeasured majesty, (governs) the heavens, there is never any one [among mankind] who delights in wickedness, [or] is beset by misfortune, or is destitute of happiness

(L. 19.)—And when four hundred fully-complete auspicious years,¹ together with the eightieth (year), had here gone by; on the bright thirteenth day of the month Kārtika which brings happiness to the thoughts of all mankind;—in the season² which abounds with waters that are of a reddish-brown colour with the pollen that is discharged from the blue waterlilies; when the skirts of the groves are radiant with the flowers of the *bandhūka*³ and *śāpa*⁴-trees; when there is the time of the awakening from sleep of (the god) Madhusūdana;⁵ (and) when the stars are as pure as a bed of waterlilies in full bloom;—

(L. 22.)—He who has adorned (his) city on the banks of the Gargarā with irrigation wells, tanks, and temples and halls of the gods, drinking-wells, and pleasure-gardens of

¹ See page 73 above, note 1; and page 75, note 4.

² *i.e.* Śarad, the autumn, consisting of the two months Āsvayuja (September-October) and Kārtika (October-November).

³ *bandhūka*; 'a shrub bearing a red flower; Pentapetes Phœnicea; Terminalia Tomentosa.'

⁴ *śāpa*; 'the blue-flowering Barleria.'

⁵ Viṣṇu, who sleeps during the four months of the rainy season. His slumber commences on the eleventh day of the bright fortnight of the month Āshāḍha (June-July), and ends on the eleventh day of the bright fortnight of Kārtika (October-November).

various kinds, and causeways, and long pools, just as if (*he were adorning his own*) beloved wife with different sorts of ornaments; he who is, as it were, the third eye of the king; who is of noble behaviour; who is devoted to gods, Brāhmaṇs, spiritual preceptors, relations, and holy men; and who, (*by nature*) not free from partiality (*for this particular virtue*), has (*always*) applied (*his*) thoughts to courteous behaviour, destitute of litigation, which is applauded by the sacred writings;—he who, having reflected that the life of every man lasts not for ever and is full of feebleness, and that prosperity is as unstable as a swing, is displaying, by means of (*his*) lawfully acquired riches, the most extreme devotion towards (the god Vishṇu) who bears the discus and the club;¹—he who has two handsome arms that are muscular and long and round and pendulous; who is [marked] with the wounds of swords; whose eyes stretch to the tips of (*his*) ears; who is possessed of a clear skin like that of a young woman of tender age; who destroys (*his*) enemies when they display energy through pride; who is powerful; who through devotion behaves like a relation towards (*his*) enemies; who is experienced in (*the combined pursuit, without mutual conflict, of*) religion and wealth and pleasure:—

(L. 28.)—He, the illustrious **Mayūrāśhaka**,—who is sprung from a family possessed of wisdom and prowess; whose heroism is renowned in every region; who holds himself under control; (*and*) who has accomplished, in his son Vishṇubhaṭṭa and also Haribhaṭṭa, the duty of (*continuing his*) lineage,—caused to be built by his sons, the favourites of great good fortune, this shrine of the divine (god) Vishṇu, which blocks up the path of sin,—seeing the aspect of which, resembling the lofty peak of (the mountain) Kailāsa, the Vidyādharas, accompanied by their mistresses, come and gaze into it with happy faces that are like waterlilies, as if it were the very lustrous surface of a mirror;—(*and*) seeing which (*aspect*), at the moment when the surface (*of the roof*) has been polished by the palms of the hands of the lovely women of the gods, the sun, who in the sky is praised in chorus by the saints possessed of superhuman power of mind resulting from religious merit, reins in his chariot-horses with (*their*) tossing manes, which think (*from the reflection*) that they are returning towards (*themselves*), and, joining (*his hands*) together (*so that they resemble*) an expanding bud in respectful salutation, runs away in fear with bent-down head.

(L. 35.)—Also, for the sake of religious merit, the counsellor of the king caused to be built this very terrible abode, (*and*) filled full of female ghouls, of the divine Mothers, who utter loud and tremendous shouts in joy, (*and*) who stir up the (*very*) oceans with the mighty wind rising from the magic rites of their religion.

(L. 37.)—And the illustrious **Mayūrāśhaka**, the receptacle of virtuous qualities, caused to be made this well, which is protected by in the lower regions, resembling serpents; which possesses much water, cool, and sweet, and pure; (*and*) which rivals the ocean.

(L. 39.)—As long as the oceans are full of jewels; as long as the earth, with (*its*) mountains, abounds with many thickets and trees and woods; and as long as the moon lights up the sky that is inlaid with the host of the planets;—so long let the fame of the illustrious **Mayūrāśhaka** remain abundant! Let there be success!

¹This compound combines two well-known names of Vishṇu,—Chakradhara, and Gadādhara.

No. 18; PLATE XI.

MANDASOR STONE INSCRIPTION OF KUMARAGUPTA
AND BANDHUVARMAN.

THE MALAVA YEARS 493 AND 529.

THIS inscription, which I published, for the first time, in 1886, in the *Ind. Ant.* Vol. XV. p. 194 ft., was discovered through information given by the late Mr. Arthur Sullivan, who, in 1879, sent to General Cunningham, from Mandasor, a hand-copy of the fragmentary pillar inscription of Yaśodharman, No. 34 below, Plate xxiC. I saw this copy in 1883, and, recognising in it the name of Mihirakula, sent my copyists, in March 1884, to take impressions of this fragment and of any other inscriptions that they might find. In the search made by them, they discovered the present inscription, and also the entire duplicate copy of the pillar inscription of Yaśodharman, No. 33 below, Plate xxiB., which had escaped the notice of Mr. Sullivan.

Mandasor,¹ or more properly **Dasor**, the ancient **Dasapura**,² on the north or left

¹ The 'Mandesar, Mandesor, Mandesur, Mandisore, Mandosar, Mandaur, Mundesor, and Mundesoor,' of maps, &c. Indian Atlas, Sheet No. 35. Lat. 24° 3' N.; Long. 75° 8' E.

² Dasor is the name by which, in preference to Mandasor, the town is habitually spoken of by the villagers and agriculturists of the locality and neighbourhood, and even as far as Indor. And in some bilingual *sanads* or warrants, of about a century and a half ago, I found this form, Dasor, used in the vernacular passages, while the Persian passages of the same documents give the form Mandasor. So also, Pāṇḍits still habitually use the form Dasapura in their correspondence; a practice with which we may compare the use, also by Pāṇḍits, of Ahipura and Nakhapura for respectively Sampgaum and Ugargol in the Belgium District; except that it is doubtful whether these are original Sanskrit names, or only pedantic Sanskrit translations of original vernacular names.—The local explanation of the name is, that the place was originally a city of the Purāṇic king Dasaratha. But, on this view, the modern name should be Dasarathor. The true explanation evidently is that,—just as now the township includes from twelve to fifteen outlying hamlets or divisions; Khilchpur, Jankupurā, Rāmpuriā, Chandrapurā, Bālagafi, &c.,—so, when it was originally constituted, it included exactly ten (*daśa*) such hamlets (*purā*).—As regards the fuller form of Mandasor, by which alone the town is known officially and is entered in maps, I cannot at present explain the origin of it. But Dr. Bhagwanlal Indraji suggested to me that it may perhaps represent Manda-Dasapura, "the distressed or afflicted Dasapura," in commemoration of the overthrow of the town, and the destruction of the Hindu temples in it, by the Musalmāns, in memory of which, even to the present day, the Nāgar Brāhmins of the place will not drink the water there. And, as tending to support this suggestion, I would mention that one of the Pāṇḍits whom I questioned on the spot, gave me Mannadasor as another form of the name. Another suggestion, by Mr. F. S. Growse, is that the name combines the two names of Mad and Dasapura; the former of them (see *Ind. Ant.* Vol. XV. p. 195) being the name of a village, also called Afzalpur, about eleven miles south-east of Mandasor, from which, it is said, were brought, from ruined Hindu temples, the stones that were used in the construction of the Musalmān fort at Mandasor. The true explanation, whatever it may be, would probably be found in the *Dasapura-Māhātmya*, which is extant, but which I did not succeed in obtaining for examination.—In addition to the present inscription, the ancient Sanskrit name, Dasapura, occurs also in line 9 of an early Nāsik inscription of Ushavadāta (*Archæol. Surv. West. Ind.* Vol. IV. p. 99, and Plate lii. No. 5); and in another inscription at Mandasor itself, dated (Vikrama)-Sainvat 1321 (A.D. 1264-65) Guru(vāra) or Thursday, the fifth day of the bright fortnight of the month Bhādrapada, which is on a white stone built into the wall on the left hand inside the inner gate of the eastern entrance of the Fort.—Under the same name, the place is also mentioned, in connection with Avanti (Ujjain), in the *Brhat-Saṁhitā*, xiv. vv. 11-16 (Kern's Translation, *Jour. R. As. Soc. N. S.* Vol. V. p. 83).

bank of the river Śīwanā,¹ is the chief town of the Mandasor District of Scindia's Dominions in the Western Mālwa division of Central India. The inscription is on a stone slab, apparently rather good and dark sand-stone, built into the wall on the right hand half-way down a small flight of steps leading to the river in front of a mediæval temple of the god Śīva, under the name of Mahādēva, at the Mahādēva-Ghāt, which is on the south bank of the river, just opposite the Fort, and, I think, in the limits of the hamlet of Chandrapurā.

The writing covers, except for a margin of about half an inch, the whole front of the stone, about 2' 7 $\frac{1}{2}$ " broad by 1' 4 $\frac{1}{4}$ " high. It has been a good deal worn away about the centre of the stone; and also the stone is chipped at several places round the edges; but only a few letters here and there are really illegible, and these can in each case be easily supplied.—The average size of the letters is about $\frac{1}{4}$ ". The characters belong to the southern class of alphabets; but they include two letters borrowed from the northern alphabets; *vis.* the separate form of the lingual *ḍ*, as distinct from the dental *d*, *e.g.* in *tadit*, line 6, and *chāḍḍ*, line 17; and also the rare lingual *dh*, *e.g.* in *ḍrīḍha*, lines 9 and 11. They give a very good specimen of what may be called the Western Mālwa alphabet of the fifth century A.D.—The language is Sanskrit; and, with the exception of the opening *siddham* and the concluding words in line 24, the entire inscription is in the *verse*.—In respect of orthography we have to notice (1) the occasional use of the *jihvāmūlīya* and *upadhānīya*; *e.g.* in *jagatah-kshaya*, line 1; *ganaiḥ-kham*, line 8, *pravṛṣṭītaiḥ-pushṇḍī*, line 2; and *abhiśāmrāḥ-pṛyāt*, line 3; but not, for instance, in *avabhugnaiḥ kvachit*, line 5; *paraḥ kṛipand*, line 14; *rajaḥ-piṅgaritaiḥ*, line 5; and *pratimnīṭāḥ pramudītā*, line 9; (2) the occasional doubling of *t*, *dh*, and *bh*, in conjunction with a following *r*; *e.g.* in *chitrēna*, line 12; *rōddhṛa*, line 18; and *abbhṛa*, line 6; (3) the same of *th* and *dh*, with a following *y*; *e.g.* in *patthya*, line 9; and *svaddhyāya*, line 8; and (4) the same of *dh*, with a following *v*; *e.g.* in *addhōḍḍī*, line 3.

The inscription refers itself to the reign of a king named Kumāragupta, who, from the description of him in line 13 as sovereign of the whole earth, can be no other than the well-known Kumāragupta of the Early Gupta dynasty. Under him, the governor at Daśapura was Bandhuvarman, the son of Viśvavarman. The inscription belongs throughout to the solar form of worship. It narrates, in the first place, how a number of silk-weavers immigrated from the Lāṭa *vishaya*, or central and southern Gujarāt, into the city of Daśapura; and how some of the band took up other occupations, while those who adhered to their original pursuit constituted themselves into a separate and flourishing guild. And it then proceeds to record that, while Bandhuvarman was governing at Daśapura, the guild of silk-weavers built at that city a temple of the Sun, which was completed when, in words, four hundred and ninety-three years had elapsed, "by (*the reckoning from*) the tribal constitution of the Mālavas,"² and therefore when the four hundred and ninety-fourth year (A.D. 437-38) was current, on the thirteenth day of the bright fortnight of the month Sahasya (December-January). Afterwards, under other kings, part of this temple fell into disrepair. And then it was restored by the same guild, when, in words, five hundred and twenty-nine years had elapsed, and therefore when the five hundred and thirtieth year (A.D. 473-74) was current, on the second lunar day of the bright fortnight of the month Tapasya (February-March). This second date is, of

¹ The 'Sau, and Seu,' of maps.

² See the Preface.

course, the year in which the inscription was actually composed and engraved; since we are told at the end that it was all composed by Vatsabhāṭṭi, and the engraving throughout is obviously the work of one and the same hand.

TEXT.¹

- 1 [Sid]dh[a]m [I] Y[ō] v[rit] [t*]y-a[r]ttham-upāsyatē sura-ganais=siddhais=cha
siddhy=artthibhir=ddhyān-aik-āgra-parair=vvidhēya-vishayair=mmōksh-artthibhir
=yyōgibhiḥ I bhaktyā tlvra-tapōdhanais=cha munibhis=śāpa-prasāḍa-
kshamair=hētur-yyō jagatah=kshay-ābhuyadayayōh=pāyāt=sa vō bhāskarah I(II)
Tat[t*]va-jñāna-vidō=pi yasya na vidur=brahmarsha-
- 2 yo=bhyudyatāh=kritsnam yaś=cha gabhastibhiḥ pravīṣṭaiḥ=push[n]āti lōka-
trayam I gandharv-āmara - siddha - kinnara - narais = samstūyatē = bhyutthiro
bhaktēbhyaś=cha dadāti yō=bhilaṣhitam tasmai savitrē nauḥ I(II)
Yāḥ²=pratyaham prativibhāty=udayāchalēndra-vistīmṇa-tunga-śikhara-śkhalit-
āmsu-jālah kshib-ānganā-
- 3 jana-kapōla-tal-ābhitāmraḥ=pāyāt=sa vas=su-k[ī]raṇ-ābharanō vivasvān f(II)
Kusumā³-bhar-ānata-taruvara-dēvakulasabhā-vihāra-ramaṇi(nī)yaḥ I Lāta-
vishayān=nag-āvrita-śailāj=jagati prathita-śilpāh I(II) Te⁴ dēva pārtthiva-
guṇ-āpahritāḥ prakāśam=adhdv-ādi-jāny-a-vuralāny=asukhā-
- 4 ny=apāsyā I jāt-ādarā **Daśapuram** prathamam manōbhir=anv=āgatās-
sa-suta-bandhu-janās=samētya II Mattēbha-ganda-tata-vichyuta-dāna-bindu-
sikt-ōpal-āchala-sahasra-vibhūśhā(sha)pāyāh [I*] pushp-āvanimra-taru-manda-
vatamsakāyā bhūmēḥ=paran=tilaka-bhūtan-īdan- kramēna II Tat⁵-ōttha-
vriksha-chyuta-
- 5 naika-pushpa-vichitra-tlr-ānta-jalāni bhānti I praphulta-padm-ābharānīni yatra
sarāmsi kāraṇḍava-samkulāni II Vilōla-vichī-chalit-āravinda-patad-rajah-
piṇjaritais=cha hamsaiḥ I sva-kēsar-ōdāra-bhar-āvabhugnaiḥ kvachit-
sarāmsy=amburuhais=cha bhānti I(II) Sva-pushpa-bhār-āvanatair=
nnagēndrair=mada-
- 6 pragalbh-āli-kula-svanais=cha I ajasra-gābhiś=cha pur-ānganābhir=vvānāni yasmin-
samalamkṛitāni II Chalāt⁶-patākāny=abalā-sanāthāny=atyarttha-suklāny=adhik-
ōnnatāni I taḍil-latā-chitra-sit-ābbhra-kūṭa-tuly-ōpamānāni grhāni yatra II
Kailāsa⁷-tunga-śikhara-pratimāni ch=ānyāny=ābhānti dirggha-valabhi-
- 7 ni sa-vēdikāni I gāndharvva-śabda-mukharāni(ni) nivishṭa-chitra-karmmāni lōka-
kadali-vana-śōbhitāni II Prāsāda⁸-mālābhir=alamkṛitāni dharām vidāryy-
aiva samutthitāni I vimāna-mālā-sadṛśāni yatra grhāni pūrṇ-ēndu-
kar-āmalāni II Yad⁹=bhāty=abhiramyā-sarid-[d*]vayēna chapal-ōraminā
samupagōḍham

¹ From the ink-impression.² Metre, Śārdūlavikṛīṭita; and in the next verse³ Metre, Vasantatilaka.⁴ Metre, Āryā.⁵ Metre, Vasantatilaka; and in the next verse.⁶ Metre, Upēndravajrā; and in the next two verses.⁷ Metre, Upajāti of Indravajrā and Upēndravajrā.⁸ Metre, Vasantatilaka.⁹ Metre, Upajāti of Indravajrā and Upēndravajrā.¹⁰ Metre, Āryā

- 8 rahasi kucha-śālinibhyām Pṛti-Ratibhyām Smar-āṅgam-iva || Satya¹-kshamā-dama-śama-vrata-śauca-dhairyya-svādhdhyāya-vṛitta-vinaya-sṭhiti-bud-dhy-upētaiḥ | vidyā-tapō-nidhibhir-a-smayitais-cha viprair-yyad-bhrājatē graha-gaṇaiḥ-kham-iva pradīptaiḥ || Atha² samētya niranara-saṅgatair-aharahaḥ-pravijjimbhita-
- 9 sauhṛidāḥ [1*] nripatibhis-suta-vat-pratim[ā]nitāḥ pramuditā nyavasanta sukham purē || Śravaṇa³-[su]bhaga[m] dh[ā]nurvvoidya[m] dṛiḍham pariniṣṭhitāḥ sucharita-śat-āsaṅgāḥ-kēchid-vichitra-kathā-vidāḥ | vinaya-nibhṛitās = samyag - dharmma - prasāṅga - parāyanaḥ = priyam = a - parusham patthyam ch-ānyē kshamā bahu bhāshitum ||
- 10 Kēchit⁴-sva-karmmany-adhikās-tath-ānyair-vvijñāyatē jyōtisham-ātmavadbhiḥ | adyāpi ch-ānyē samara-pragalbhāḥ-kurvanty-arjṇām-a-hitam pra-sahya I(II) Prājñā⁵ manōjña-vādhaveḥ prathit-ōru-varṣā varṣ-ānurūpa-charit-ābharaṇās-tath-ānyē | satya-vratāḥ prapayinām-upakāra-dakṣhā visrambha-
- 11 [pūrva]m=aparē dṛiḍha-sauhṛidās=cha || Vijita⁶-vishaya-saṅgair-ddharmma-ślāis=tath-ānyair-m[ri]dubhir-adhika-sat[t*]vair-llōkayātr-āmarais=cha | sva-kula-tilaka-bhūtēnā nētra-subhagēnā | yais-sakalam-idaṁ kṣhititalam-alam-kṛitāḥ paṭṭa-vastrēna || Tāruṇya⁷-kānty-upachitō-pi suvarṇahāra-tāmbūla-pushpa-vidhinā sama-
- 12 [lambkri]tō=pi | nārī-janaḥ priyam-upaiti na tāvad=agryā(śryā)ḥ yāvan-na paṭṭamaya-vastra-y[u]gāni dhattē || Sparśa[va]tā⁸ varṇāntara-vibhāga-chittreṇa nētra-subhagēnā | yais-sakalam-idaṁ kṣhititalam-alam-kṛitāḥ paṭṭa-vastrēna || Vidyādharī⁹-ruchira-pallava-karṇapūra-vāt-ērit-isthiratarām pravichintya
- 13 [lō]kām | mānushyam-artha-nichayāms-cha tathā viśālāms-tēshām śubhā matir-abhūd-achalā tatas-tu || Chatus¹⁰-samudr-ān[t]ja-vilōla-mēkhalām Sumēru-Kailāsa-brihat-payōdharām | van-ānta-vānta-sphuṭa-pushpa-hāsinim Kumāraguptē¹¹ prithivīḥ praśāsati || Samāna¹²-dhīś-Śukra-Brihas-patibhyām lalāma-bhūtō bhuvī
- 14 pārtthivānām | rapēshu yaḥ Pārttha-samāna-karmmā babhūva gōptā nripa-Viśvavarmmā¹³ || Dīn¹⁴-ānukampana-pārah kṛipān-ārtta-vargga-sandh[ā]-pradō-dhika-dayātur-anātha-nāthāḥ | kalpa-drumaḥ prapayinām-abhayam pradās=cha bhītasya yō janapadasya cha bandhur-āsit || Tasy¹⁵=ātmajāḥ sthairya-nay-ōpananō bandhu-priyō
- 15 bandhur-iva prajānām | bandhv-artti-harttā nripa-Bandhuvarmmā¹⁶ dvid-dripta-paksha-kshapap-aika-dakṣhāḥ || Kāntō¹⁷ yuvā rapa-paṭur-vvinay-ānvitās=cha rāj-āpi sann-upasitō na madaiḥ smay-ādyaiḥ | śrīṅgāra

¹ Metre, Vasantatilaka² Metre, Hariṇ.³ Metre, Vasantatilaka.⁴ Metre, Vasantatilaka.⁵ Metre, Vasantatilaka.⁶ Metre, Vasantatilaka.⁷ Metre, Upēndravajrā.⁸ Metre, Indravajrā.⁹ Metre, Drutavilambita.¹⁰ Metre, Indravajrā.¹¹ Metre, Mālini.¹² Metre, Āryā.¹³ Metre, Varṣāstha.¹⁴ Metre, Vasantatilaka.¹⁵ Metre, Vasantatilaka.¹⁶ Metre, Vasantatilaka.

- mūrttir-abhibhāty-an-alamkṛitō=pi rūpeṇa yāh-kusumachāpa iva dvitīyaḥ ||
Vaidhavya¹-tīvra-vyasana-kshatānām
- 16 smri(smṛi)tvā yam-adyāpy-ari-sundarīṇām | bhayād-bhavaty-āyata-lōchanānām
ghana-stan-āyāsa-karāḥ prakampāḥ || Tasmīn²-ēva kshītipati-vri(vrī)shē
Barddhuvarmma³-udārē samyak-sphītam Daśapuram-idam pālayaty-
unnat-āmsē | śilp-āvāptair-ddhana-samudayaḥ paṭṭavāyair-udāram
śrēṇibhūtair-bbhavanam-atulam kārītam
- 17 dīpta-raśmēḥ || Vistīrṇa⁴-tuṅga-śikharam śikhari-prakāśam-abhyudgat-ēndv-
amala-raśmi-kalāpa-gauram | yad-bhāti paśchima-purasya nivishṭa-
kānta-chōḍāmaṇi-pratisaman-nayan-abhiramam || Rāmā-sanātha-[ra]chanē
dara-bhāskar-āmsu-vahni-pratāpa-subhagē jala-līna-mnē | chandrāmsu-
harmyatala-
- 18 chandana-tālavṛnta-hār-ōpabhōdha(ga)-rahitē hima-dagdha-padmē || Rōddhra-
priyamgu-taru-kundalatā-vikōśa-pushp - āsava - pramud[ī]t - āli - kal - ābhīrāmē |
kālē tushāra-kaṇa-karkkaśa-śīta-vāta-vēga-pranṛita-lavall-nagan-aikaśākhē ||
Smara⁵-vaśaga-tarūrajana-vallabhānganā-vipula-kānta-pln-ōru-
- 19 stana-jaghana-ghan-ālingana-nirbhartsita-tuhina-hima-pātē || Mālavānām⁶
gana-sthityā yāt[ē] śata-chatuṣṭayē | tri-navaty-adhikē-bdānām-ri(ri)tau
sēvya-ghana-svanē || Sahasya-māsa-śuklasya praśastē=hnī trayōdaśē |
maṅgal-āchāra-vidhinā prāsādō=yam nivēśitaḥ || Babunā samatītēna
- 20 kālēn-ānyaiś=cha pārtthivaiḥ | vyaśṛiyat-aika-dēśō=sya bhavanasya tatō-
dhunā || Sva-yāśō-v[rī](vrī)ddhayē sarvva=aty-udāram-udārayā saṁskā-
ritam-idam bhūyaḥ śrēṇyā bhānumatō grīham || Aty⁷-unnatam-
avadātam nabha[h]-sprīśann-iva⁸ manōbaraiḥ śikharaiḥ | śaśi-bhānvōr-
abhyudayēshv-amala-mayūkh-āyaṭana-
- 21 bhūtām || Vatsara-śatēshu pāmchasya viśamty⁹-adhikēshu navasu ch-
ābdēshu | yātēshv-abhiramya-Tapasya-māsa-śukla-dvītīyāyām || Spashtair¹⁰-
aśōkataru-kētaka-simdivāra-lōlātīmuktakalatā-madayantikānām | pushp-
ōdgamair-abhinavair-adhigamya nōnam-aikyam vijimbhita-śarē Hara-
pū(dhū)ta-dēhē ||
- 22 Madhu¹¹-pāna-mudita-madhukara-kul-ōpagta-nagan(n)-aika-prithu-sākhē | kālē
nava-kusum-ōdgama-damtura-kāmta-prachura-rōddhrē || Śaśin-ēva nabhō
vimalarā kaus[t]ubha-maṇin-ēva Śārngiṇō vakshaḥ | bhavana-varēṇa
tath-ēdam puram-akhilam-alamkṛitam-udāram || Amalina¹²-śaśi-
- 23 lēkhā-damturam piṅgalānām parivahati samūham yāvad-Isō jaṭānām |
vikāṭa-kamala-mālām=amsa-saktām cha Śārngī bhavanam-idam-udāram

¹ Metre, Upajāti of Indravajrā and Upēndravajrā.

² Metre, Mandākrāntā.

³ Metre, Vasantatilaka; and in the next two verses.

⁴ Metre, Āryā.

⁵ Metre, Śīlka (Anuśtubh); and in the next three verses.

⁶ Metre, Āryā; and in the next verse.

⁷ *sprīśan* is the nominative singular of the masculine; whereas the neuter *sprīśat*, in apposition with *grīham*, is what is required. This, however, would not suit the metre. The only emendation that suits the metre, is to alter the construction and read *nabhāḥ sprīśat=iva*.

⁸ Read *vīkṣaty*.

⁹ Metre, Vasantatilaka.

¹⁰ Metre, Āryā; and in the next verse.

¹¹ Metre, Mālinī.

śāśvatan-tāvad-astu || Śrēny¹-adēśēna bhaktyā cha kārītam
bhavanam ravēḥ | pūrvā ch-ēyam² prayatnēna rachitā
Vatsabhāṭṭinā ||

24 Svasti karṭri-lēkhaka-vāchaka-śrōtṛibhyaḥ || Siddhir-astu ||

TRANSLATION.

Perfection has been attained! May that Sun protect you,—who is worshipped by the hosts of the gods for the sake of existence, and by the Siddhas³ who wish for supernatural powers, (*and*) by ascetics, entirely given over to abstract meditation (*and*) having worldly attractions well under control, who wish for the final liberation of the soul, and, with devotion, by saints, practising strict penances, (*who wish to become*) able to counteract curses; (*and*) who is the cause of the destruction and the commencing (*again*) of the universe! Reverence to that Sun,—whom (*even*) the Brāhmanical sages, though they knew the knowledge of the truth (*and*) exerted themselves, failed to comprehend; and who nourishes the whole of the three worlds with (*his*) rays diffused in all directions; who, when he is risen, is praised by Gandharvas,⁴ gods, Siddhas, Kinnaras,⁵ and Naras,⁶ and who grants (*their*) desires to those who worship (*him*)! May that Sun, decorated with glorious beams, protect you,—who shines, day after day, with the mass of (*his*) rays flowing down over the wide and lofty summit of the lordly mountain of dawn, (*and*) who is of a dark-red colour like the cheeks of intoxicated women!

(Line 3)—From the district of *Lāṭa*, which is pleasing with choice trees that are bowed down by the weight of (*their*) flowers, and with temples and assembly-halls of the gods, and with *vihāḥ* *is*, (*and*) the mountains of which are covered over with vegetation, to (*this*) city of *Daśapura* there came, full of respect,—first, in thought; and afterwards (*in person*) in a band, together with (*their*) children and kinsmen,—men who were renowned in the world for (*skill in their*) craft (*of silk-weaving*), and who, being manifestly attracted by the virtues of the kings of the country, gave no thought to the continuous discomforts produced by the journey and its accompaniments. And in course (*of time*) this (*city*) became the forehead-decoration of the earth, which is adorned with a thousand mountains whose rocks are besprinkled with the drops of rut that trickle down from the sides of the temples of rutting elephants, (*and*) which has for (*its*) decorative ear-ornaments the trees weighed down with flowers. Here⁷ the lakes, crowded with *kārandava*-ducks, are beautiful,—having the waters close to (*their*) shores made variegated with the many flowers that fall down from the trees growing on the banks, (*and*) being adorned with full-blown waterlilies. The lakes are beautiful (*in some places*) with the

¹ Metre, Ślōka (Anuṣṭubh).

² Supply *prastitih*.—See page 87 below, note 10.

³ Siddhas; semi-divine beings, supposed to be of great purity and holiness, and said to be specially characterised by the possession of the eight supernatural faculties. Their habitation is in the sky, or in the middle region between the earth and the sky.

⁴ Gandharvas; the celestial musicians.

⁵ Kinnaras; mythical beings, with a human figure and the head of a horse, reckoned among the Gandharvas, and celebrated as musicians.

⁶ Naras; mythical beings, allied to the Gandharvas and Kinnaras.

⁷ The original has, as far as line 8, the relative construction, which I have changed, for convenience of translation, into the absolute.

swans that are engaged in the pollen that falls from the waterlilies shaken by the tremulous waves; and in other places, with the waterlilies bent down by the great burden of their filaments. Here the woods are adorned with lordly trees, that are bowed down by the weight of their flowers and are full of the sounds of the flights of bees that hum loudly through intoxication (*caused by the juices of the flowers that they suck*), and with the women from the city who are perpetually singing. Here the houses have waving flags, (*and*) are full of tender women, (*and*) are very white (*and*) extremely lofty, resembling the peaks of white clouds lit up with forked lightning. And other long buildings on the roofs of the houses, with arbours in them, are beautiful,—being like the lofty summits of (the mountain) Kailāsa; being vocal with songs (*like those*) of the Gandharvas; having pictured representations arranged (*in them*); (*and*) being adorned with groves of waving plantain-trees. Here, cleaving asunder the earth, there rise up houses which are decorated with successions of storeys; which are like rows of aerial chariots; (*and*) which are as pure as the rays of the full-moon. This (*city*) is beautiful (*through*) being embraced by two charming rivers,¹ with tremulous waves, as if it were the body of (the god) Śmāra (*embraced*) in secrecy by (*his wives*) Prti and Rati, possessed of (*heaving*) breasts. Like the sky with the brilliant multitudes of planets, it shines with Brāhmins endowed with truth, patience, self-control, tranquillity, religious vows, purity, fortitude, private study, good conduct, refinement, and steadfastness, (*and*) abounding in learning and penances, and free from the excitement of surprise.

(L. 8.)—So assembling together, (*and*) day by day received into greater friendship by (*their*) constant associates, (*and*) honourably treated like sons by the kings, in joy and happiness they settled in (*this*) city. Some of them (*became*) excessively well acquainted with the science of archery, (*in which the twanging of the bow is*) pleasing to the ear; others, devoting themselves to hundreds of excellent achievements, (*became*) acquainted with wonderful tales; and others, unassuming in (*their*) modesty (*and*) devoted to discourses of the true religion, (*became*) able to say much that was free from harshness (*and yet was*) salutary. Some excelled in their own business (*of silk-weaving*); and by others, possessed of high aims, the science of astrology was mastered; and even to-day others of them, valorous in battle, effect by force the destruction of (*their*) enemies. So also others, wise, possessed of charming wives, (*and*) belonging to a famous and mighty lineage, are decorated with achievements that befit (*their*) birth; and others, true to (*their*) promises (*and*) firm in friendship with the accompaniment of confidence, are skilled in conferring favours upon (*their*) intimates. (*And so*) the guild shines gloriously all around, through those who are of this sort, and through others who,—overcoming the attachment for worldly objects; being characterised by piety; (*and*) possessing most abundant goodness,—(*are*) very gods in an earthly habitation.

(L. 11.)—(*Just as*) a woman, though endowed with youth and beauty (*and*) adorned with the arrangement of golden necklaces and betel-leaves and flowers, goes not to meet (*her*) lover in a secret place, until she has put on a pair of coloured silken cloths,—(*so*) the whole of this region of the earth, is (*almost superfluously*) adorned through them, (*as if*) with a silken garment, agreeable to the touch, variegated with the arrangement of different colours, (*and*) pleasing to the eye.

¹ Of these rivers, one, of course, is the Śiwanā, on the north bank of which the town stands. The other must be the 'Sumli,' which now flows into the Śiwanā about three miles to the north-east of the town.

(L. 12.)—Having reflected that the world is very unsteady, being blown about by the wind like the charming ear-ornaments, (*made of*) sprigs, of the women of the Vidyā-dharas; (*and similarly*) the estate of man; and also accumulations of wealth, large (*though they may be*),—they became possessed of a virtuous (*and*) stable understanding; and then:—

(L. 13.)—While Kumāragupta was reigning over the (*whole*) earth, whose pendulous marriage-string is the verge of the four oceans; whose large breasts are (the mountains) Sumēru and Kailāsa;¹ (*and*) whose laughter is the full-blown flowers showered forth from the borders of the woods;—

(L. 13.)—There was a ruler, king Viśvavarman,² who was equal in intellect to Śukra and Bṛihaspati, who became the most eminent of princes on the earth; (*and*) whose deeds in war were equal to (*those of*) Pārtha;—who was very compassionate to the unhappy; who fulfilled his promises to the miserable and the distressed; who was excessively full of tenderness; (*and*) who was a very tree of plenty to (*his*) friends, and the giver of security to the frightened, and the friend of (*his*) country;—

(L. 14.)—His son (*was*) king Bandhavarman, possessed of firmness and statesmanship; beloved by (*his*) kinsmen; the relative, as it were, of (*his*) subjects; the remover of the afflictions of (*his*) connections; pre-eminently skilful in destroying the ranks of (*his*) proud enemies. Handsome, youthful, dexterous in war, and endowed with humility, king though he was, yet was he never carried away by passion, astonishment, and other (*evil sentiments*); being the very incarnation of erotic passion, he resembled in beauty, even though he was not adorned with ornaments, a second (Kāmadēva) armed with the bow that is made of flowers. Even to-day, when the long-eyed lovely women of (*his*) enemies, pained with the fierce pangs of widowhood, think of him, they stagger about through fear, in such a way as to fatigue (*their*) firm and compact breasts.

(L. 16.)—While he, the noble Bandhavarman, the best of kings, the strong-shouldered one,³ was governing this city of Daśapura, which had been brought to a state of great prosperity,—a noble (*and*) unequalled temple of the bright-rayed (Sun) was caused to be built by the silk-cloth weavers, as a guild, with the stores of wealth acquired by (*the exercise of their*) craft;—(a temple) which, having broad and lofty spires, (*and*) resembling a mountain, (*and*) white as the mass of the rays of the risen moon, shines, charming to the eye, having the similarity of (*being*) the lovely crest-jewel, fixed (*in its proper place*), of (*this*) city of the west.

(L. 17.)—In that season⁴ which unites men with (*their*) lovely mistresses; which is agreeable with the warmth of the fire of the rays of the sun (*shining*) in the glens; in

¹ The context is "a noble (*and*) unequalled temple of the bright-rayed (Sun) was caused to be built" &c., in line 16; all that intervenes, is by way of a parenthesis.

² Conf. *Bṛihat-Saṃhitā*, xliii. 35, where the earth is described as having the mountains of sunrise and sunset for lips, and the Himālaya and Vindhya for breasts.—Compare also line 34 of the *Alṅkā* grant of Śīlāditya VII. of the year 447, No. 39 below, Plate xxv., where the Sahya and Vindhya mountains are called the breasts of the earth.—Similes of this kind doubtless varied in accordance with the extent of the kingdoms in which the inventors of them resided.

³ This, again, is a second parenthesis, the real context of the preceding verse being the description of Bandhavarman in line 14 ff.

⁴ *i.e.* 'high-shouldered.'

⁵ *i.e.* Hēmana, the cold weather, consisting of the months Mārgaśrīṣa (November-December) and Pauṣa or Sahasya (December-January).

which the fishes lie low down in the water; which (*on account of the cold*) is destitute of the enjoyment of the beams of the moon, and (*sitting in the open air on*) the flat roofs of houses, and sandal-wood perfumes, and palm-leaf-fans, and necklaces;—in which the waterlilies are bitten by the frost; which is charming with the humming of the bees that are made happy by the juice of the full-blown flowers of the *rôdhra*¹ and *priyangu-plants*² and the jasmine-creepers; in which the *lavall-trees*³ and the solitary branches of the *nagand-bushes*⁴ are made to dance with the force of the wind that is harsh and cold with particles of frost;—(*and*) in which (*the cold induced by*) the falling of frost and snow is derided by the close embraces of the large and beautiful and plump and bulky breasts and thighs of young men and (*their*) mistresses, completely under the influence of love;—when, by (*the reckoning from*) the tribal constitution of the **Mâlavas**, four centuries of years, increased by ninety-three, had elapsed; in that season when the low thunder of the muttering of clouds is to be welcomed (*as indicating the approach of warmth again*);—on the excellent thirteenth day of the bright fortnight of the month Sahasya,—this temple was established, with the ceremony of auspicious benediction.

(L. 19.)—And, in the course of a long time, under other kings, part of this temple fell into disrepair; so now, in order to increase their own fame, the whole of this most noble house of the Sun has been repaired again by the munificent corporation;—(this temple) which is very lofty (*and*) pure; which touches the sky, as it were, with (*its*) charming spires; (*and*) which is the resting-place of the spotless rays of the moon and the sun at (*their*) times of rising. Thus, when five centuries of years, increased by twenty, and nine years had elapsed; on the charming second lunar day of the bright fortnight of the month Tapasya;—in the season⁵ when (Kamadêva), whose body was destroyed by Hara, develops (*his number of five*) arrows by attaining unity with the fresh bursting-forth of the flowers of the *asôka*⁶ and *hêtaka*⁷ and *sinduvôdra-trees*,⁸ and the pendulous *atimuktaka-creeper*,⁹ and the wild-jasmine;—when the solitary large branches of the *nagand-bushes* are full of the songs of the bees that are delighted by drinking the nectar; (*and*) when the beautiful and luxuriant *rôdhra-trees* swing to and fro with the fresh bursting forth of (*their*) flowers,—the whole of this noble city was decorated with (*this*) best of temples; just as the pure sky is decorated with the moon, and the breast of (the god) Śârngin with the *kaustubha-jewel*. As long as (the god) Îśa wears a mass of tawny matted locks, undulating with the spotless rays of the moon (*on his forehead*); and (*as long as*) (the god) Śârngin (*carries*) a garland of lovely waterlilies on his shoulder;—so long may this noble temple endure for ever!

(L. 23.)—By the command of the guild, and from devotion, (*this*) temple of the Sun was caused to be built; and this (*eulogy*)¹⁰ that precedes was, with particular care, compos-

¹ *rôdhra*, also *idôhra*; the tree *Symplocos Racemosa*.

² *priyangu*; a medicinal plant and perfume; *Panicum Italicum*; *Sinapis Ramosa*; saffron.

³ *lavall*; the *Averrhoa Acida*.

⁴ *nagand*; the *Cardiospermum Halicacabum*.

⁵ *i.e.* Śîśîra, the cool or dewy season, consisting of the months Mâgha (January-February) and Phâlguna or Tapaśya (February-March).

⁶ *asôka*; the tree or shrub *Jonesia Asôka*.

⁷ *hêtaka*; the tree *Pandanus Odoratissimus*.

⁸ *sinduvôdra*; the tree or shrub *Vitex Negundo*.

⁹ *atimuktaka*; a certain creeper, tree, or shrub, with apparently white flowers.

¹⁰ *prâśasti*.—This was the customary technical term applied to inscriptions on stone. It has to be supplied here; but it is of constant occurrence; *e.g.* in line 27 of the Apsad inscription at

ed by Vat'abhaṭṭi. Hail to the composer and the writer, and those who read or listen (*to it!*)
Let there be success!

No. 19; PLATE XIIA.

ERAN STONE PILLAR INSCRIPTION OF BUDHAGUPTA. THE YEAR 165.

THIS inscription was discovered in 1838 by Captain T. S. Burt, of the Engineers, and was first brought to notice in the same year, in the *Four. Beng. As. Soc.* Vol. VII. p. 633 f. when Mr. James Prinsep published his reading of the text, and a translation of it,¹ accompanied by a lithograph (*id.* Plate xxxi.), reduced from an ink-impression made by Captain Burt.—In 1861, in the same Journal, Vol. XXX. p. 17 ff., Dr. FitzEdward Hall published his revised reading of the text, from the original pillar, and a translation of it.—And finally, in 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 82, General Cunningham, in reprinting Dr. Hall's translation, pointed out that the *aksharas* in line 3,—in which Mr. Prinsep had found a reference to the Surāshṭras; and which Dr. Hall read as *samsurabhā*, and translated by "chosen land of the gods,"—were in reality a repetition of the date in numerical symbols, as had, in fact, been suggested, though without particularisation, by Dr. Hall himself, in the *Four. Beng. As. Soc.* Vol. XXXI. p. 127, note.

This is another inscription from Ēraṇ² in the Khurāl Sub-Division of the Sāgar District in the Central Provinces. It is on the west face towards the bottom of the lower and square part of a large monolith red-sandstone column, which stands near the well-known group of temples about half a mile to the west of the village, and which seems from its position to be specially connected with a small double temple that General Cunningham has named the "Lakshmi Temple,"³ separated by the intervening "Vishṇu Temple" from the "Varāha Temple," or temple of the Boar, at which there is the well-known inscription of Tōramāṇa, No. 36 below.

The writing, which covers a space of about 2' 6½" broad by 1' 7½" high, has suffered a good deal in places from the weather; but on the original column the whole inscription can be read with certainty, except a few letters at the proper left side that have been quite worn away by sharpening tools on the edge of the stone. The bottom line of the inscription is about 3' 3" above the plinth from which the column rises.—The size of the letters varies from ½" to ¾". The characters belong to the northern class of alphabets; they approximate in some respects to the type of the Allahābād posthumous pillar inscription of Samudragupta, No. 1 above, Plate i., and in others to that of the Mathurā inscription of Chandragupta II., No. 4, Plate iiiA.; but they also present some developments and differences that must be attributed partly to their somewhat later age, and partly to the particular locality to which the inscription belongs. I should be inclined to name them a variety, with northern characteristics, of the Central India alphabet of towards the end of the fifth

Ādityasēna, No. 42 below, Plate xxviii.—The only instance that I can quote of its use to denote a copper-plate charter, is in line 20-21 of the 'Chicacole' grant of the *Mahārāja* Indravarman of the year 128 (*Ind. Ant.* Vol. XIII, p. 121).

¹ The translation is reprinted in Thomas' edition of Prinsep's *Essays*, Vol. I. p. 249.

² See page 18 above, and note 1.

³ *Archæol. Surv. Ind.* Vol. X. p. 87, and Plates xxv. and xxvi.

century A.D. The letter *r*, as the first part of a compound consonant, is formed sometimes within the top line of the writing, e.g. in *arṇava*, line 1, and sometimes above it, e.g. in *paryyāṅka*, in the same line. The characters include, in line 3, forms of the numerical symbols for 5, 60, and 100.—The language is Sanskrit; and the inscription is in verse as far as line 4, and the rest in prose.—In respect of orthography, the only point that calls for notice is the constant doubling of *t*, in conjunction with a following *r*, e.g. in *maitrāyaṅya*, line 5; *puttrēna*, line 6; and *pittrōh*, line 8.

The inscription refers itself to the reign of **Budhagupta**, whose feudatory, the **Mahārāja Surasimichandra**, was governing the country lying between the river **Kālindī**, or the **Jamnā**, and the **Narmadā**. It is dated, completely in words, and partly in numerical symbols, in the year one hundred and sixty-five (A.D. 484-85), on the twelfth lunar day of the bright fortnight of the month **Āshāḍha** (June-July), and on **Suraguruvāra** or Thursday. It is a **Vaiṣṇava** inscription. And the object of it is to record the erection of the column, which is called a *dhvaja-stambha* or 'flag-staff' of the god **Viṣṇu**, under the name of **Janārdana**, by a **Mahārāja** named **Mātrivishṇu** and his younger brother, **Dhanyavishṇu**.

TEXT.¹

- 1 Jayatī² vibhuś-chatur-bhujaś=chatur-arṇava-vipula-salila-paryyāṅkaḥ jagataḥ
sthity-utpatti-nyāy-ādi³].
- 2 hētur=Ggaruḍa-kētuḥ [11*] Śatē pañcha-shashty-adhikē varshāṅām bhūpatau
cha **Budhaguptē** | Āshāḍha-māsa-ś[ukla]-
- 3 dvādaśyārth Suragurōr=ddivasē 1(11) Sam 100 60 5 [11*] **Kālindī**⁴.
Narmadayōr=mmadhyam pālayati lōkapāla-guṇair-jjagati mahār[āja].
- 4 śriyam=anubhavati **Surasimichandrē** cha 1(11) Asyām sarvatsara-māsa-
divasa-pūrvvāyām⁵ sva-karm-ābhiratasya kratu-yāj[ī]ṅ[naḥ]
- 5 adhīta-svādhyāyasya vipr-ā-shēr=Mmaitrāyaṅya-vriṣhabhasy=Endravishṇōḥ pra-
puttrēna pitur=guṇ-ānukāriṇō Varuṇav[ī]ś[nōḥ]
- 6 puttrēna pitaram-anu-jātasya sva-vamśa-vridhhi-hētōr=Harivishṇōḥ puttrēn-
ātyanta-bhagavad-bhaktēna Vidhātur-icchchayā svayamvaray=ēva r[ā]ja-
- 7 lakshmy-ādhitgatēna chatuḥ-samudra-pariyanta-prathita-yaśasā akshina-māna-
dhanēn-ānēka-śatru-samara-jishṇunā mahārāja-**Mātrivishṇun[ā]**
- 8 tasy-aiv=ānujēna tad-anuvidhāyin[ā] tat-prasāda-parigrī[hi]tēna **Dhanya-
vishṇunā** cha | mātri(ta)pittrōḥ puṇy-āpyāyan-ārtham=ēsha bhagavataḥ 1⁶
- 9 puṇyajan-ārddanasya Janārdanasya dhvaja-stambhō=bhyuchchhritāḥ [11*]
Svasty-astu gō-brāhmaṇa-p[u]rōgābhyaḥ sarva-prajābhya iti 1(11)

¹ Compare *dhvaja*, 'standard,' as applied to the Mōharaulf column, in line 6 of No. 32 below, Plate xxiA.

² From the original stone.

³ Metre *Āryā*; and in the next verse.—In the first *pāda* of this, and of the second verse, we have the proper number of twelve syllabic instants; but they are not arranged in accordance with the usual rule for this metre.

⁴ I have adopted Dr. Hall's suggestion for supplying the effaced letters. In the last legible syllable, part of the subscript *y* is quite distinct, and the consonant above it seems to be a broken *n*. and the requirements of both the metre and the sense are properly met by supplying *yādi* for the effaced syllables.

⁵ This *śikshā* is somewhat damaged; but it is very distinctly *śud* Prinsep's reading of *trayāśyāṅka* is proved to be wrong by the metre, if by nothing else.

⁶ Metre, *Āryā*.

⁷ Supply *tithau*.

⁸ This mark of punctuation is unnecessary.

TRANSLATION.

Victorious is the lord, the four-armed (god Vishṇu)—whose couch is the broad waters of the four oceans; who is the cause of the continuance, the production, and the destruction, &c., of the universe; (and) whose ensign is Garuḍa!

(Line 2.)—In a century of years, increased by sixty-five; and while **Budhagupta** (is) king; on the twelfth lunar day of the bright fortnight of the month Aśhāḍha; on the day of Suraguru;¹ (or in figures) the year 100 (and) 60 (and) 5:—

(L. 3.)—And while **Suraśmichandra** is governing, with the qualities of a regent of one of the quarters of the world,² (the country that lies) between the (rivers) **Kālindi** and **Narmadā**, (and) is enjoying in the world the glory of (being) a **Mahārāja**;—

(L. 4.)—On this (lunar day), (specified) as above by the year and month and day;—by the **Mahārāja Mātrivishṇu**, who is excessively devoted to the Divine One; who, by the will of (the god) Vidhātṛi, was approached (in marriage-choice) by the goddess of sovereignty, as if by a maiden choosing (him) of her own accord (to be her husband); whose fame extends up to the borders of the four oceans; who is possessed of unimpaired honour and wealth; (and) who has been victorious in battle against many enemies;—who is the son of the son's son of Indravisṇu, who was attentive to his duties; who celebrated sacrifices; who practised private study (of the scriptures); who was a Brāhman saint; (and) who was the most excellent (of the followers) of the Maitrāyaṇya (śākhā);—who is the son's son of Varuṇavisṇu, who imitated the virtuous qualities of (his) father;—(and) who is the son of Harivishṇu, who was the counterpart of (his) father in meritorious qualities,³ (and) was the cause of the advancement of his race;—

(L. 8.)—(By him) and by his younger brother **Dhanyavisṇu**, who is obedient to him, (and) has been accepted with favour by him,—this flag-staff of the divine (god) Janārdana, the troubler of the demons,⁴ has been erected, for the purpose of increasing the religious merit of (their) parents.

(L. 9.)—Let prosperity attend all the subjects, headed by the cows and the Brāhman!

¹ i.e. "on Thursday."—Suraguru, 'the preceptor of the gods,' is another name of Brihaspati, from which latter name the day takes its customary appellation of Brihaspativāra.

² *lōkapāla*.—The *lōkapālas*, or guardians of the points of the compass, are sometimes reckoned as eight, viz. 1, Indra, of the east; 2, Agni, of the south-east; 3, Yama, of the south; 4, Nirṛiti, or sometimes Sūrya, of the south-west; 5, Varuṇa, of the west; 6, Vāyu, of the north-west; 7, Kubēra, of the north; and 8, Iāna, or sometimes Chandīa, and sometimes Pṛithivī, of the north-east;—and sometimes as four, viz. Nos. 1, 3, 5, and 7, above.


³ *pitarām=anu-jātasya*.—Dr. Hall explained this expression in the *Four. Beng. As. Soc. Vol. XXX.* p. 139, note, by a passage quoted in the *St. Petersburg Dictionary from the Pañchatantra*; viz.—

Jātaḥ putrō=nujātas=cha atijātas=tath=eva cha |
 apajātas=cha lōkē=smin=mantavyāḥ śāstra=vēdibhiḥ ||
 Mātri-tulya-guṇō jātas=tv=anujātaḥ pituḥ samah |
 atijātō=dhikas=tasmād=apajātō=dham-ādhamah ||

"By those who know the scriptures, (sons) are to be understood among men as being a *jāta* son, or an *anu-jāta*, or an *atijāta*, or an *apajāta*. A *jāta* (is) one whose virtues are equal to (those of his) mother; an *anu-jāta* (is) equal to (his) father (in virtue); an *atijāta* surpasses that (father); (and) an *apajāta* (is) altogether inferior (to him.)"


⁴ *punyaḥana*, lit. 'a good, pious, or virtuous man,' also denotes 'a class of supernatural beings, a fiend, a goblin, a demon.'

A.—Eran Pillar Inscription of Bodhagupta.—The Year 165.



SCALE 25

B.—Eran Posthumous Pillar Inscription of Goparaja.—The Year 191



No. 20; PLATE XII B.

ERAN POSTHUMOUS STONE PILLAR INSCRIPTION
OF GOPARAJA.
THE YEAR 191.

THIS inscription, which has not previously been published, was discovered in 1874-75 or 1876-77 by General Cunningham, and was first brought to notice by him in 1880, in the *Archaeol. Surv. Ind.* Vol. X. p. 89 f.

It is another inscription from **Ēraṇ**,¹ in the Khurāl Sub-Division of the Sāgar District in the Central Provinces. It is on a small pillar, afterwards converted into a *linga* or phallic emblem of Śiva, which stands under some tall trees near the left bank of the Bīnā, about half a mile to the south-east of Ēraṇ, and half-way between it and the neighbouring village of Pēhēlējpur.² The original lower part of the pillar is now broken away and lost; the remnant of it is about 3' 11" high and 1' 6" in diameter. The bottom part is octagonal; and the inscription is at the top of this octagonal part, on three of the eight faces, each of which is about 7" broad; the bottom line is about six inches above the level of the ground. Above this, the pillar is sixteen-sided. Above this, it is again octagonal; and the faces here have sculptures of men and women, who are probably intended for the Gōparāja of the inscription, and his wife and friends; the compartment immediately above the centre of the inscription, represents a man and a woman, sitting, who must be Gōparāja and his wife. Above this, the pillar is again sixteen-sided. Above this, it is once more octagonal; and on two of the faces here, there are the remains of a quite illegible inscription of four lines, in characters of the same type with those of the inscription now published. Above this, the pillar curves over in sixteen flutes or ribs, into a round top. The pillar was converted into a *linga*, by fitting an ablu-tion-trough to it; this was attached over the part where the inscription lay; and it was only by the breaking of it, that the greater part of the inscription was disclosed to view.

The **writing**, which covers a space of about 1' 9" broad by 11" high, has suffered a good deal from the weather, and from the sharpening of tools on the edges of the stone; but, on the original pillar, it is fairly legible almost throughout; and the only historical items that have been lost are, in line 2, the name of Gōparāja's grandfather, and of the family to which he belonged.—The **size** of the letters varies from $\frac{3}{8}$ " to $\frac{5}{8}$ ". The **characters** belong to the northern class of alphabets, and, though not quite so well formed, are of almost precisely the same type with those of the Ēraṇ pillar inscription of Budhagupta, No. 19 above, Plate xii A. The letter *r*, as the first part of a compound consonant, is formed within the top line of the writing in *pārtha*, line 5, and *bhāryā*, line 7; but above it in *sārdham*, line 5. The characters include, in line 2, forms of the **numerical symbols** for 1, 7, 90, and 100.—The **language** is Sanskrit; and, the inscription is in prose as far as the end of the date, in line 2, and the rest in verse.—In respect of **orthography**, the only points that call for notice are (1) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *vanśa*, lines 1 and 4; and (2) the doubling of *k* and *t*, in conjunction with a following *r*; e.g. in *vikkṛanta* and *puttra*, line 3.

¹ See page 18 above, and note 1.

² The 'Pahlehpur' of Gen. Cunningham's map (*Archaeol. Surv. Ind.* Vol. X Pl. xxiii.)

The inscription, which does not refer itself to the reign of any particular king, is dated, in both words and numerical symbols, in the year one hundred and ninety-one (A.D. 510-11) on the seventh lunar day of the dark fortnight, and solar day¹ of the month, of Śrāvāṇa (July-August). It is a non-sectarian inscription; the object of it being only to record that, in the company of a powerful king named Bhānugupta, a chieftain or noble named Gōparāja came to the place where the pillar was set up, and fought a battle; that Gōparāja was killed; and that his wife accompanied him, by cremating herself on his funeral pyre.²

TEXT:

- 1 Om Saṃvatsara-śatē ēka-navaty-uttarē Śrāvāṇa-bahula-paksha-sap[t]amy[Arh]
 2 saṃvat 100 90 1 Śrāvāṇa ba⁴ di 7 11 [—]la(P)ksha⁵-vaṃśād-
 utpannō [— —]
 3 rāj-ēti-viśrutāḥ tasya puttrō-ti-vikkrāntō nāmnā rāj-ātha Mādhavaḥ 11
 Gōparāja[h]
 4 sutas-tasya śrīmān-vikhyāta-pauruṣaḥ Śarabharāja-dauhittiraḥ sva-vaṃśa-
 tilakō-dhu(?)nā(?) [11]
 5 Śr⁶-Bhānuguptō jagati pravīrō rājā mahān-Pārtha-samō-ti-śūrah tēn-ātha
 sarddhan-tv=iha Gōpar[ā]j[ō]

¹The day is indicated as a solar day, as well as lunar, by the use, in the numerical-symbol record, of *di*, the abbreviation of *dina*, *dinē*, *dīvasa*, or *dīvasē*, in addition to, in the fuller record, *saptamī*, which denotes the lunar *tithi*.—The abbreviation *di* is preceded by *ba*, which stands for *bahula-paksha* or *bahula-pakshē*. Sometimes, instead of *ba*, we have *va*; e.g. in line 17 of the Bengal Asiatic Society's grant of the *Mahārāja* Vināyaka-pāla, *saṃvatsrō* (sic) 100 80 8 *Phālguna va di 9* (*Ind. Ant.* Vol. XV. p. 141); in which case *va* may, according to the general orthography of the particular record, stand for *ba*; or it may be an abbreviation of *vadya*, which is a synonym of *bahula*, and is of common enough use in the present day, though it was not so in ancient times. The corresponding method of denoting the bright fortnight, is by the use of the abbreviation *śu*, which represents *śukla* or *śuddha*, similarly in composition with *paksha* or *pakshē*; e.g. in line 14 of the Bōdh-Gayā inscription of Mahānāman, No. 71 below, Plate xliA., *saṃvat 200 60 9 Chaitra śu di 8*.—These abbreviations, *śu di* and *ba di* or *va di*, are often quoted as if they were words in themselves (*śudi*, *badi*, *vadi*), meaning respectively 'the bright fortnight' and 'the dark fortnight.' And Monier Williams, in his Sanskrit Dictionary, gives *vadi* as an indeclinable word, meaning 'in the dark half of a month'; with the remark that, according to some, it stands for *badi*, and is a contraction of *bahula-dina*; but with an intimation of his own opinion that it represents *vadya*. But I doubt whether the Hindus themselves, even when using the abbreviations, look on them as words. And it is worth noting that Molesworth and Candy's *Marāṭhī Dictionary*, which is very comprehensive, does not include these expressions, either as abbreviations, or as words. Even if a modern practice of treating these abbreviations as words, should be proved, it is an erroneous practice. By origin, the syllables are nothing but distinct and separate abbreviations, of which the first denotes the fortnight of the month, and the second, the day of the month or fortnight. And this is the point of view from which they have to be looked at, in dealing with any ancient records.

²*i.e.*, according to the colloquial expression, she became *Sati* ('*Suttee*').—With this early instance of the cremation of widows, we may compare the indication of the same practice that is given in Bhagwanlal Indrajī's Nēpāl inscription No. 1, of Mānādēva (*Ind. Ant.* Vol. IX. p. 164, line 7 *l.*, and p. 165), when Rājyavati, the widow of Dharmadēva, bids her son Mānādēva take up the government, in order that she may follow her deceased husband to the other world. This instance belongs to about A.D. 705 (see *id.* Vol. XIV. pp. 344, 350).—As noted by Gen. Cunningham, there are several other *Sati*-pillars, but of much later date, at Erāp.

³ From the original stone.

⁴ *i.e.* *bahula-paksha*.

⁵ Metre, Śiōka (Anushubh); and in the next verse.

⁶ Metre, Indravajrā; and in the following verse.

6 mittrān=uva(?)tyā(?)ra(?) kil=ānuyātaḥ || Kṛitvā [cha*] y[u]ddham su-
mahat-prak[ā]śam svarggam gatō divya-narē(?)[ndra-kalpah]
7 bhakt-ānuraktā cha¹ priyā cha kāntā bh[ā]r[y]=ā[va]lag[n]=ānugat-
āg[n]i-r[ā]śim ||

TRANSLATION.

Om! In a century of years, increased by ninety-one; on the seventh lunar day of the dark fortnight of (the month) Śrāvana; (or in figures) the year 100 (and) 90 (and) 1; (the month) Śrāvana; the dark fortnight; the day 7:—

(Line 2.)—(There was) a king, renowned under the name of . . . rāja, sprung from the . . . laksha(?) lineage; and his son (was) that very valorous king (who was known) by the name (of) Mādhava.

(L. 3.)—His son was the illustrious Gōparāja, renowned for manliness; the daughter's son of the Śarabha king; who is (even) now(?) the ornament of (his) lineage.

(L. 5.)—(There is) the glorious Bhānugupta, the bravest man on the earth, a mighty king, equal to Pārtha, exceedingly heroic; and, along with him, Gōparāja followed (his) friends (and came) here. [And*] having fought a very famous battle, he,² [who was but little short of being equal to] the celestial [king (Indra)], (died and) went to heaven; and (his) devoted, attached, beloved, and beauteous wife, in close companionship, accompanied (him) onto the funeral pyre.

No. 21; (No PLATE)

KHOH COPPER-PLATE INSCRIPTION OF THE
MAHARAJA HASTIN.

THE YEAR 156.

THIS inscription appears to have been discovered, about 1852, by Colonel Ellis, Political Agent at Nāgaudh, and was first brought to notice in 1858, in Mr. Thomas' edition of Prinsep's *Essays*, Vol. I. p. 251 f., by Professor H. H. Wilson's translation, combining both this and the next inscription of the year 163, from Mr. Thomas' reading of the texts. —In 1861, in the *Jour. Beng. As. Soc.* Vol. XXX. p. 6 ff., Dr. Fitz-Edward Hall published his reading of the text, and a translation of it, from the original plates.—And in 1879, in the *Archaeol. Surv. Ind.* Vol. IX. p. 11, No. 1, General Cunningham, in partially reprinting Dr. Hall's translation, substituted a close approximation to the correct interpretation of the date, agreeing with Professor H. H. Wilson and differing from Dr. Hall; and also gave a lithograph of the passage containing the date (*id.* Plate iv. No. 1.)

The inscription is on some copper-plates that were found somewhere in the valley near the village of Khōh,³ about three miles south-west of Uchaharā,⁴ the present capital

¹ The metre is faulty here, as the *cha*, which should remain short, is lengthened by the following double consonant, *pr*.

² Gōparāja.

³ The 'Kho' of maps. It should be in the Indian Atlas, Sheet No. 89, but is not shewn there.—*Khōh* means literally 'a cave.'

⁴ The 'Ochairs, Uchahara, Uchara, Uchera, Ucheyra, Unchehra, Unchehra, Unchehrah, Unchera, Urchara, and Urcharah,' of maps, &c. Indian Atlas, Sheet No. 89. Lat. 24° 23' N.; Long. 80° 51' E.—

of the Native State of Nāgaudh or Nāgaundh¹ in the Baghelkhand division of Central India. They were originally deposited in the Library of the Sanskrit College at Benares; but, with the ring and seal, were lost sight of in being transferred from there to the Allahābād Museum, and thence to the Provincial Museum at Lucknow (Lakhnau). I am informed that the second plate has been recently found at Lucknow. But I have not been able to obtain it, or an ink-impression of it, for examination. And I, therefore, edit the inscription here from a hand-copy made by General Cunningham, which, though not suitable for lithography, suffices admirably for reading the text.

The **plates**, two in number, and inscribed on one side only, appear to have been in a state of excellent preservation throughout. From the original accounts, they seem to have been connected as usual by a **ring**, the ends of which were secured in the lower part of a **seal**, the front of which had on it the **legend**, *Śrī-mahārāja-Hastināh*, "of the illustrious *Mahārāja Hastin*," as on the seal of his grant of the year 191, No. 23 below, Plate xiv.—The **characters** belong to the northern class of alphabets, and are of the same type as those of the following inscription of the same *Mahārāja* of the year 163, No. 22 below, Plate xiii. The letter *r* in conjunction with a following *y*, is formed in two ways; in *kāryah*, line 14, and *kurydt*, line 14-15, the *r* is written within the top line of the writing, with only a single *y* below it, as in *kurydt*, line 12, and *sūryadatta*, line 19, of No. 23 below, Plate xiv.; while in *sūryadatta*, lines 10 and 21, and *muryyāddh*, line 12, it is formed above the top line, as in the case of conjunction with other letters, and the *y* is doubled.—The **language** is Sanskrit; and, except for the benedictive and imperative verses in lines 16 to 20, the entire inscription is in prose.—In respect of **orthography**, we have to notice (1) the use of the dental nasal, instead of the *anusvāra*, before *ṣ*, in *vāṣṇa*, line 6; (2) the doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *vakkrd*, line 20; and *sagōtra* and *puttra*, line 9; (3) the doubling of *dh*, in conjunction with a following *y*, in *avaddhyānēna*, line 15; and (4) the occasional use of *ḥ* for *v*, in *sāmbatsarē*, line 2; and *barsha*, line 19.

In addition to 'Uchahara,' Gen. Cunningham uses three other forms, 'Uchahara,' 'Uchahada,' and 'Uchahada,' (*Archæol. Surv. Ind.* Vol IX. p. 5); but, in my inquiries at Satnā, I could not obtain anything in support of them.—He has also proposed (*id.* p. 10) to identify Uchaharā with 'Udyāra,' the supposed capital of Svāmīdatta mentioned in line 19 of the Allahābād pillar inscription, No. 1; but the real reading there (page 7 above) gives Giri-Koṭṭūra, or "Koṭṭūra on the hill."—Uchaharā is probably by no means an unique name; as the maps give an 'Ocharah,' ten miles towards the north-east, an 'Ocharah,' twenty-nine miles north by east, an 'Uchera,' thirty-one miles to the south-east by east, and another 'Uchera,' about fifty-nine miles to the south-east by south, from the place under reference.

¹ The 'Nagode, Nagound, and Nagudh,' of maps, &c. Indian Atlas, Sheet No. 70. Lat. 24° 33' N., Long. 80° 37' E.—On the badges of the Police Sepoys, I found the name written Nāgaud. But the correct form is undoubtedly Nāgaudh, which is sometimes nasalised and pronounced Nāgaundh.—The Rājā is officially called the 'Rājā of Nagode;' and Nāgaudh was formerly the capital of the State. The present capital is Uchaharā. And the Political Agency is now at Satnā, which, in reality the name of a river, has been adopted as the name of the station on the Great Indian Peninsula Railway. The station and the Agency are really in the lands of the village of Bardājlh.—Gen. Cunningham has proposed (*Archæol. Surv. Ind.* Vol. IX. p. 12) to identify Nāgaudh with the Nāgadēya that is mentioned in line 5 of the Kārttālāī plates of the *Mahārāja Jayanātha* of the year 174, No. 26 below. But the name would rather seem to be derived from *nāga-vadha* or *nāga-bandha*, 'the slaughter or the capture of the hooded-serpents or of the Nāga tribe;' whereas Nāgadēya would mean 'the gift to the hooded-serpents, or to the Nāga tribe.'

The inscription is one of the **Parivrājaka**¹ **Mahārāja Hastin**. It is dated, in words, "in the enjoyment of sovereignty by the **Gupta kings**,"² in the year one hundred and fifty-six (A.D. 475-76), in the **Mahā-Vaiśākha samvatsara**,³ and on the third lunar day of the bright fortnight of the month **Kārttika** (October-November). The inscription is non-sectarian, except for the opening invocation of the god **Śiva**, under the name of **Mahādēva**. The object of it is to record the grant, by the **Mahārāja Hastin**, of the village of **Vasuntarashaṇḍika** to **Gōpasvāmin** and other **Brahmans**.

TEXT.⁴

First Plate.

- 1 Namò Mahādēvāya || Svasti Shaṭpañchās-ōttarē-bda-ṣaṭē **Gupta-nripa-**
 2 **rājya-bhuktāu Mahā-Vaiśākha-sāmbatsarē**⁵ 1⁶ **Kārttika-māsa-śukla-paksha-tṛtītyā-**
 3 **yām-asyān-divasa-pūrvvāyām**⁷ **nripatiparivrājaka-kul-ōtpannēna**⁸ **mahā-**
 4 **rāja-Dēvādhyā**⁹-pranaptrā **mā(ma)hārāja-Prabhañjana-naptranā**¹⁰ **mahārāja-**
Dāmōdara-sutēna

¹ *parivrājaka* means literally 'a wandering religious mendicant, an ascetic in the fourth and last religious order or stage of life.'—The compound used in line 3 of the Text, *nripati-parivrājaka*, 'a kingly ascetic,' is of the same class with *rāj-arshi*, 'a royal saint, a saint of royal descent.' Compare also *rājādhirāj-arshi*, 'a saintly sovereign,' which is applied to Chandragupta II. in the Udayagiri cave inscription, No. 6, page 35 above, line 3.—The particular kingly ascetic, from whom Hastin's family derived its origin, was **Susārman** (see No. 25 below, Plate xvB. line 5 f).—The word *parivrājaka* seems to have been adopted as the regular and habitual appellation of the family. At any rate, it furnishes, for distinctive purposes, a convenient and unobjectionable name for it.

² *Gupta-nripa-rājya-bhuktāu*; line 1f.—The same expression occurs in Nos. 22, 23, and 25. It indicates clearly that the Gupta dynasty and sway were still continuing; and of course the date refers to the era used by the Guptas. But there is nothing in the expression, tending to give the era the name of the "Gupta era."—Prof. H. H. Wilson's translation of this date, combined with that of the following inscription, No. 22, (*Prinsep's Essays*, Vol. I, p. 251) was "in the 163rd year of the occupation of the kingdom by the Gupta kings." And this was substantially correct. But he added a note that *bhuktā* or *bhuktāu* might be read *muktā* or *muktāu*, 'from the end or cessation.'—In publishing this translation, Mr. Thomas pointed out that the reading *muktā* or *muktāu* could not possibly be admitted. And, following this, Dr. Hall (*Jour. Beng. As. Soc.* Vol. XXX. pp. 3 f., note, and 6, 12) adopted the reading *bhuktāu* or *bhuktā*, but laid down the dictum that *bhukti*, "if unqualified by a temporal particle, denotes 'possession,' or 'fruition,' only as a thing of the past;" and he then proceeded to translate the passage by "in the year one hundred and fifty-six of the extinction of the sovereignty of the Gupta kings;" and again "one hundred and sixty-three years after the date of the Guptas had been laid to rest."—Gen. Cunningham (*Archæol. Surv. Ind.* Vol. IX. p. 11) gave "in the year one hundred and fifty-six of the enjoyment of sovereignty by the Gupta kings." And this, again, was substantially correct, though not grammatically.—As in the case of *śantē*, in line 3 of the **Kābul** pillar inscription of **Skandagupta** (see page 67 above, note 7), it is impossible to imagine how *bhukti*, *lit.* 'the act of enjoying or eating; enjoyment, eating; fruition, possession, usufruct,' ever came to be applied in the sense of 'extinction;' except under the influence of a preconceived bias, so strong as to prevent entirely the critical consideration which would at once have shown the error.

³ *samvatsara*, 'a year,' is used principally, if not entirely, to denote (as is indicated by the first component, *sam*, 'with, together with') years that have a close connection with those that precede and follow them; i.e. years of cycles, eras, and reigns.—In the present case, the twelve-year cycle of the planet **Jupiter** is referred to.

⁴ From Gen. Cunningham's hand-copy.

⁵ Read *samvatsarē*.

⁶ This mark of punctuation is unnecessary.

⁷ Supply *tithau*.

⁸ This mark of punctuation is unnecessary.

⁹ See page 97 below, note 4. ¹⁰ Read *nuptra*.

- 5 gô-sahasra-hasty-aśva-hiraṇy-āṅka-bhūmi-pradēna guru-pitri-mātri-pôjā-tatparē-
 6 ṇ-ātyanta-dēva-brāhmaṇa-bhaktēna 11¹ naika-samara-śatata²-vijayinā sva-vanś-ā-
 7 mōdakareṇa mahārāja-śrī-Hastinā sva-puṇy-āpyāyan-ārtham-ātmānam sva-
 8 rgga-sōpāna-pañktibhir-ārōha(pa)yatā brāhmaṇa-Vājisinēya³Mādhy-
 9 ndina-Kautsasagōttra-Gōpasvāmi Bhavasvāmi | Sandhyāputra | Divākara
 10 dattaḥ Bhāskaradatta | Sūryyadattasya⁴ Vasuntarashanḍi:ca-grāmō-
 11 tiṣṭiṣṭaḥ || Samantād-garttā uttarē paśchimō(mē)na

Second Plate.

- 12 pūrvva-bhūktā⁵ mā(ma)ryyādāḥ [11*] Samndhyā⁶puttra-pramukhānām
 s-ōdraṅgaḥ s-ōparikaraḥ
 13 a-chaṭa-bhaṭa-prāvēśyaḥ chōra-varjjam [11*] Tad-asmat-kul-ōtthaiḥ mat-
 pādapiṇḍ-ōpajī-
 14 vibhir-vvā kālāntarēshv=api na vyāghātaḥ kāryaḥ [1*] ēvam-ājñāptā⁷
 yō-nyathā ku-
 15 ryāt=tam=aham dēhāntara-gatō=pi mahat-āvaddhyānēna nirddahēd⁸=Uktam
 cha bhagavatā pa-
 16 ram-arshipā veda-vyāsēna | Pūrvvā⁹-dattām dvijātibhyō yatnād-
 rakshya(ksha) Yudhishthirah¹⁰
 17 mahi(h)lām mahimatām¹¹ śrēṣṭha dānāch=chhrēyō=nupālanam¹² [11*]
 Bahubhir-vvasudhā bhukta rā-
 18 jabhiḥ Sagar-ādibhiḥ yasya yasya yadā bhūmis-tasya tasya tadā
 phalam [11*]
 19 Shasṭī=ba(va)rsha-sahasrāṇi svarggē mōdati bhūmi-daḥ āchchhētā
 ch-ānuma-
 20 ntā cha tāny-ēva narakē vasēd=iti || Likhitaṇ=cha¹³ Vakkr-āmātya-
 21 [pra*]naptrā bhōgik-āmātya-Naradatta-naptrā bhōgi¹⁴ka-Ravidatta-puttr[ēna*]
 Sūryya-
 22 dattēn-ōti [1*] Dūtakō Bhāgrahaḥ [11*]

TRANSLATION.

Reverence to (the god) Mahādēva! Hail!¹⁵ In a century of years, increased by the fifty-sixth (year); in the enjoyment of sovereignty by the Gupta kings; in the Mahā-

¹ This mark of punctuation is unnecessary.

² Read śata.

³ Read vājasaneya.

⁴ Read, in composition, Gōpasvāmi-Bhavasvāmi-Sandhyāputtra-Divākaradatta-Bhāskaradatta-Sūryyadattēbhyō.

⁵ Read bhūktā.—F. E. Hall read bhūkti. But the bhūktā (for bhūktā) of Gen. Cunningham's copy, seems preferable.

⁶ Read sandhyā.

⁷ Read either ājñāptā, or ājñāptī.

⁸ Read nirddahyam.

⁹ Metre, Ślōka (Anuṣṭubh); and in the following two verses.

¹⁰ Read yudhishthira.

¹¹ For some various readings here, see page 99 below, note 1.

¹² Read nupālanam, or nupālanam.

¹³ Supply śāsanam, or śāmrāṭśāsanam, in apposition with likhitam; and see page 99 below, note 2.

¹⁴ This gi is omitted in Gen. Cunningham's copy.

¹⁵ svasti; *Iti*, "it is well" (*su asti*).—Like *siddham* (see page 25 above, note 4), this word of constant use as a *mangala*, or 'auspicious invocation,' at the commencement of inscriptions.—

Vaiśākha *saṃvatsara*; on the third lunar day of the bright fortnight of the month Kārttika,—on this (*lunar day*), (*specified*) as above by the day (*&c.*),¹—

(Line 3.)—By the *Mahārāja*, the illustrious **Hastin**,—who is born in the family of a kingly ascetic;²—who is the great-grandson³ of the *Mahārāja Dēvādhyā*;—who is the grandson of the *Mahārāja Prabhatijana*;—who is the son of the *Mahārāja Dāmōdara*;—who is the giver of thousands of cows, and elephants, and horses, and gold, and many lands;—who is earnest in paying respect to (*his*) spiritual preceptor and (*his*) father and mother;—who is extremely devoted to the gods and Brāhman;—who has been victorious in many hundreds of battles;—(*and*) who causes the happiness of his own race,—

(L. 7.)—(*By him*),—for the purpose of increasing his own religious merit, (*and*) in order to cause (*himself*) to ascend by the steps of the ladder that leads to heaven,—the village of **Vasuntarashaṇḍika** is granted to the Brāhman Gōpasvāmin, of the Vāja-saṇēya-Mādhyamīna (*śākhā*) and the Kautsa *gōtra*, and to Bhavasvāmin, Sandhyāputra, Divākaradatta, Bhāskaradatta, and Sūryadatta.

(L. 11.)—On all sides (*there are*) trenches (*of demarcation*);⁴ (*and*) on the north by the west, the boundaries are those that have been previously enjoyed. (*This village is made the property*) of Sandhyāputra and the others, with the *udranga*⁵ and the *upari*—

It also occurs, governing a dative case, at the end of the Mandasōr inscription of Kumāragupta and Bandhuvarman, No. 18, page 84 above, line 24; and as a neuter noun, signifying 'prosperity,' in conjunction with *astu*, 'let there be,' the two together governing a dative, at the end of the Ēran pillar inscription of Budhagupta, No. 19, page 89 above, line 9, and at the end of the Ēraṇ inscription of Tōramāga, No. 36 below, Plate xxiiiA. line 8.

¹ The text (line 3) has *asyān=divasa-pūrvvādyām*, in apposition with which *tithau* has 0 be supplied.—The same expression was used in the Gaḍhwā inscription of Chandragupta II No. 7, page 37 above, line 2 f.; and it occurs in other places also.—But the fuller and more formal expression was *asyām saṃvatsara-māsa-divasa pūrvvādyām*, "on this (lunar day), (specified as above by the *saṃvatsara* (or year) and month and day," which occurs, for instance, in the *Majjagawān* grant of the *Mahārāja* Hastin of the year 191, No. 23 below, Plate xiv, line 2 f. Another variety of the expression is *asyān=divasa-māsa-saṃvatsar-ānupūrvvādyām*, in the Shāhpur image inscription of Adityasēna, No. 43 below, Plate xxixA. line 2.—In the Bilsāḍ pillar inscription of Kumāragupta, No. 10 page 44 above, line 7, we have *asyān=divasa-pūrvvādyām*, without the specification of any details except the year.

² See page 95 above, note 1.

³ In this and the other three formal inscriptions of this family, Nos. 22, 23, and 25 below, *pranapti* and *napti* are used, instead of the more customary and stricter terms, *prapastra*, or 'son of a son's son,' and *pantra*, 'son's son,' see page 15 above, note 3. *Pranapti* and *napti* may denote, at any rate in early times, descendants through a daughter, as well as through a son; and I therefore translate them by the less binding expressions of 'great-grandson' and 'grandson.' We may, however, assume with safety that they are used here to denote descendants through sons.

⁴ F. E. Hall (*Four. Beng. As. Soc.* Vol. XXX. p. 6, and p. 8, note) read this name as *Dēvādhyā*, and rejected H. H. Wilson's reading of *Dvārhyā* (which is evidently a misprint for *Dēvārhyā*, i.e. *Dēvādhyā*) with the remark—"in both inscriptions, the name is most legibly incised; and Mr. Thomas' decipherments bear out my lection unhesitatingly." The fact remains, however, that in all the three inscriptions of Hastin, and in the inscription of Samkshōbha, the name is unmistakably *Dēvādhyā*; as, indeed, would be recognised at once by any careful reader, acquainted with Sanskrit, since *ādhyā* or *ādhyā* is no real word or termination at all; and Prof. H. H. Wilson was right, and Dr. FitzEdward Hall was wrong.

⁵ *garta*; *lit.* 'a hollow, a hole, a cave.

⁶ *udranga* is a technical fiscal term.—Dr. Bühler has brought to notice (*Ind. Ant.* Vol. XII. p. 189, note 39) that in the *Śālvatāksha*, Zacharia's edition, pp. xxix., 260, it is explained by *udhāra*

kara,¹ (and with the privilege that it is) not to be entered by the irregular or regular troops;² (but) with the exception of (the right to fines imposed on) thieves.³

(L. 13.)—Therefore, even in future times, no obstacle (to the enjoyment of this grant) is to be caused by those who are born in Our family, or by my feudatories.⁴ This injunction having been given, he who behaves otherwise,—him I will consume with a great contempt, even when I have passed into another body.

(L. 15.)—And it has been said by the venerable supreme sage,⁵ the arranger of the

and *udgrantha* (? *udgr̥ha*), and thus seems to mean 'the share of the produce collected usually for the king.'—The only passage in which it occurs otherwise than among the technical conditions of a grant, is in connection with Kharagraha II.; e.g. in line 46 of the Alhā grant of Śīlāditya VII. of the year 447, No. 39 below, Plate xxv.—In this passage, as it is given in line 46 of the grant of Śīlāditya III. of the year 352 (*Ind. Ant.* Vol. XI. p. 308), it appears to be spelt with a double *d*, *uddranga*; so also in line 10 of the grant of the Mahārāja Guhasēna of the year 246 (*id.* Vol. IV. p. 175.)

¹ *uparikara* is a technical fiscal term, the meaning of which has not been made clear. But I would suggest that the first component is the Prakrit word *upari* or *upri* (see Molesworth and Candy's Marāthi Dictionary, and Wilson's *Glossary of Indian Terms*), and that the term denotes 'a tax levied on cultivators who have no proprietary rights in the soil.'

² *a-chāta-bhāṭa-prāvṛṣya*; a technical term of constant occurrence.—Dr. Bhagwanlal Indraji (*Ind. Ant.* Vol. IX. p. 175, note 41) takes *chāta-bhāṭa* as meaning *chāṭān prati bhāṭāḥ*, 'soldiers against robbers,' and as denoting the royal police. But, that *chāṭa* is not governed by *bhāṭa*, seems to be made clear by the analogous but differently arranged expression, *a-bhāṭa-chchhātra-prāvṛṣya*, in line 26 of the Chamak grant of the Mahārāja Pravarasēna II., No. 55 below, Plate xxxiv., and in line 27-28 of his Siwan grant, No. 56, Plate xxxv. And, in line 6 of the Goa grant of Satyāstraya-Dhruvarāja-Indravarmān of Śāka-Samvat 532 (*Four. Bo. Br. R. As. Soc.* Vol. X. p. 365), we have the simple expression *a-bhāṭa-prāvṛṣya*.—I follow Dr. Buhler's interpretation (*Ind. Ant.* Vol. V. p. 115 and note).—A slightly different expression, but of exactly the same purport, viz. *bratimshiddha-chāta-bhāṭa-prāvṛṣya* occurs, for instance, in l. 10-11 of the Kapālēsvar grant of Mahā-Bhavagupta (*Ind. Ant.* Vol. V. p. 56).—Other expressions, which help to indicate the bearing of the term, are *samastarājakiyānām-a-prāvṛṣya*, 'not to be entered by any of the king's people,' e.g. in line 17 of the Ilāḥ grant of Dadda II. of Śāka-Samvat 417 (*id.* Vol. XIII. p. 117); and *rāja-svākanām vasatidanda-praynadandau na stah*, in line 97 of the Paithan grant of Rāmachandra of Śāka-Samvat 1193 (*id.* Vol. XIV. p. 318). The latter expression may refer to 'fees' imposed on the king's servants for halting at, or starting from, a village, or it may refer to 'fines,' i.e. 'forced contributions of money or supplies,' obligatory on the holders of villages on such occasions.

³ This elliptical expression, *chōra-varjyam*, *lit.* 'with the exception of thieves,' is explained by the fuller expression *chōra-danda-varjyam*, 'with the exception of fines (imposed) on thieves,' in line 14 of the Khōh grant of the Mahārāja Jayanātha of the year 177, No. 27 below, Plate xvii.

⁴ *mat-pādapind-ōpajivin*; *lit.* 'subsisting on the cakes which are my feet.'—Compare *tat-pādapadm-ōpajivin*, 'subsisting (like a bee) on the waterlilies that are his feet,' which, in later times in the south, became the customary technical expression for the relation of feudatory princes and nobles, and other officials, to their paramount sovereigns; e.g. in line 8 of the Kādarōjī inscription of Śāka-Samvat 997 (*Archæol. Surv. West. Ind.* Vol. III. p. 105).—Compare, also, an expression of very similar purport,—*tat-pādapallav-ōpaiḥbhīttamānga*, 'whose head is adorned with the fresh sprouts that are his feet,'—in line 5 f. of the Baḷajāṁve inscription of Śāka-Samvat 970 (*Ind. Ant.* Vol. IV. p. 179).—See also page 53 above, and note 1.

⁵ Vyāsa; whose name, as well as his epithet of "arranger of the Vēdas," is usually inserted in this passage; e.g. in line 13 of the Majhgawāh grant of the Mahārāja Hastin of the year 191, No. 23 below, Plate xiv.—In line 13 of No. 26 below, Plate xvi., line 14 of No. 27, Plate xvii., line 29 of

Vēdas,—“O Yudhisthira, best of kings,¹ carefully preserve land that has previously been given to the twice-born; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant! The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell!”

(L. 20.)—And (*this charter*)² has been written³ by **Sūryadatta**, the [great*]-grand-

No. 28, Plate xviii., and line 3 of No. 30, Plate xixB., these verses are said to be from the Mahābhārata. And in line 19 of the Khōh grant of the *Mahārāja Saṅkshobha* of the year 214, No. 31 below, Plate xx., it is also added that they are in the *Satasahasri-Samhitā* of the Mahābhārata.—These verses are nearly always attributed, in the inscriptions, to Vyāsa. But, in line 27-28 of the Karṇū grant of the third year of Vikramāditya I. (*Four. Bo. Br. R. As. Soc.* Vol. XVI. p. 337), the verse commencing *Bahubhir-vasudhā bhuktā*, the second in the present inscription, with one other not in this inscription, is allotted to Manu; a point which may be of some interest in connection with Dr. Bühler's discovery (see *Ind. Ant.* Vol. XIV. p. 324) that about one-tenth of Manu's verses occur in the Mahābhārata.

¹ *mahimat*, or *mahimat*, in the sense of a 'king' (*lit.* 'possessed of the earth') is not a dictionary word. But its meaning, based on its etymology, is obvious; and it is further borne out by the various reading *kshtibhrītam*, which occurs in the same verse in line 32 of the Chhārōl grant of a Rāshtrakūta king Kakkā of Śāka-Samvat 679 (*Four. Bo. Br. R. As. Soc.* Vol. XVI. p. 109). Another various reading, in a slight variety of the same verse, is *matimatam*, 'wise, prudent' in line 40 of the Nausārf grant of Jayabhāta II. of the year 456 (*Ind. Ant.* Vol. XIII. p. 79).

² *śāsana*, 'a charter; or *tāmra-śāsana*, 'a copper-charter'—These were the technical terms for conveyances of this kind. The first word, *śāsana*, occurs, for instance, in line 4 of the legend on the seals of the Chammak and Siwanf grants of the *Mahārāja Pravarasēna* II., Nos. 55 and 56 below, Plate xxxiii C, and D. The second, *tāmra-śāsana*, occurs, for instance, in line 10 of the Majhgawān grant of the *Mahārāja* Hastin of the year 191, No. 23 below, Plate xiv.—See also p. 87 above, note 10, where I have given an instance (the only one known to me) of a copper-plate charter being called *prāstāsi*, which word is properly the technical term for an inscription on stone.

³ *likhitam*.—This refers either to the manual drafting of the record, or to the writing of it on the plates, for the guidance of the engraver, who then had to follow the writing and impress it with his tools. And of course it is to be understood, in the case of a high official like Sūryadatta, who in No. 22 below, Plate xiii. line 29 f. has the title of *Mahāsādhivigrahaka*, that the writing was done by one of his clerks; not by himself.—The process of engraving is always denoted by *utkṛnt* (*prāstāsi*), e.g. in line 25 of the Mandasār inscription of Yaśōdharman and Vishnuvardhana, No. 35 below, Plate xxii.; or *utkṛnam* (*śāsanam*), e.g. in line 23 of the Ārang grant of the *Rāja* Mahā-Jayarāja, No. 40 below, Plate xxvi.—It might be thought that *likhitam* may refer to the composition or drawing up of the record. But this part of the process is always denoted by a derivative from the root *kri*, 'to make,' e.g. *prāstāsih kartā*, in line 17 of the Aihole Mēguti inscription of Pulikēsin II. of Śāka-Samvat 556 (*Ind. Ant.* Vol. VIII. p. 242); or *rach*, 'to compose,' e.g. *rachitā* (*prāstāsi*), in line 23 of No. 18 above, page 84. And in line 37 of a grant of Āhanadēva of Vikrama-Samvat 1218 (*Indian Inscriptions*, No. 10), we have the double expression *rachayām-chakāra lilikhā ch-śāsanam mahā-śāsanam*.—Some of the functions connected with a copper-charter are very well indicated in line 46 of the Kapālēsvar grant of Mahā-Bhavagupta, (*Ind. Ant.* Vol. V. pp. 57, 58) where the proper translation (from my own reading of the original) runs,—“This triplicate copper-charter has been written by the illustrious Māhūka,—the son of Priyankarāditya,—a writer (*Kāyastha*) belonging to (the office of) the *Mahāsādhivigrahaka*, the *Rājaka*, the illustrious Malladatta. (This) charter, presented by the lord of Kōśala, by which the village-headman (*Mahattama*) is to be informed,—Puṇḍarikāksha received it (apparently to superintend the engraving), transferred to copper. It has been engraved by Mādhava, the son of Vāsu.”

son of the *Amditya*¹ Vakra; the grandson of the *Bhōgika*² and *Amditya* Naradatta; (and) the son of the *Bhōgika* Ravidatta. The *Dūtaka*³ (is) *Bhāgraha*.⁴

No. 22; PLATE XIII.

KHOH COPPER-PLATE INSCRIPTION OF THE MAHARAJA HASTIN.

THE YEAR 163.

THIS inscription, again, appears to have been discovered about 1852, by Colonel Ellis, Political Agent at Nāgaudh, and was first brought to notice in 1858, in Mr. Thomas' edition of Prinsep's *Essays*, Vol. I. p. 251 f., by Professor H. H. Wilson's translation combining both this and the preceding inscription of the year 156, from Mr. Thomas

¹ *Amditya*, *lit.* 'an inmate of the same house; a counsellor,' is a technical official title.

² *Bhōgika*, *lit.* 'one who enjoys or possesses,' is explained in Monier Williams' Sanskrit Dictionary by 'housekeeper, groom.' In the inscriptions it is a technical official title, possibly connected with the territorial terms *bhōga* and *bhukti*.—If we may judge by the passage in line 8 of the Kāvl grant of Jayabhāṣa II. (*Ind. Ant.* Vol. V. p. 114), the *Bhōgikas* came in rank below the *Sāmantas* and above the *Viśhayapatis*.

³ *Dūtaka*, and occasionally *Dūta* (*e.g.* in line 14 of the Nirmanḍ grant of the Mahāsāmanta and *Mahārāja* Samudrasēna, No. 80 below, Plate xlv.), *lit.* 'a messenger,' is the technical title of an officer employed in connection with formal grants. The term is most commonly used in connection with copper-charters. But there are a few instances in which it occurs in inscriptions on stone, *e.g.* Dr. Bhagwanlal Indrajī's Nēpāl inscriptions, No. 3, line 21 (*Ind. Ant.* Vol. IX p. 167), No. 4, line 17-18 (*id.* p. 168), No. 6, line 13 (*id.* p. 170), &c. And these are sufficient to shew that the *Dūtaka*'s office was to carry, not the actual charter itself, for delivery into the hands of the grantees, but the king's sanction and order to the local officials, whose duty it then was to have the charter drawn up and delivered. And, in accordance with this, there is no mention of any *Dūtaka* when we have such expressions as *ājñā svayam*, "the order (is) (that of the grantor's) own self," *e.g.* in line 19 of the 'Chicacole' grant of the *Mahārāja* Indravarman of the year 128 (*Ind. Ant.* Vol. XIII. p. 121), *sva-mukh-ājñā*, "the order (is) (that of the grantor's) own mouth," *e.g.* in line 24 of the Khōh grant of the *Mahārāja* Samkshōbha, No. 25 below, Plate xvB; *ājñāptih svamukham*, with the same meaning, *e.g.* in line 34 of the Gōdāvarī grant of the *Rāja* Prithivimūla (*Jour. Bo. Br. R. As. Soc.* Vol. XVI. p. 118), and *sva-mukh-ājñāyā utkirnam*, "engraved at the order of (the grantor's) own mouth," *e.g.* in line 23 of the Ārang plates of the *Rāja* Mahā-Jayarāja, No. 40 below, Plate xxvi.—As pointed out by Dr. Kielhorn (*Ind. Ant.* Vol. XIV. p. 161, note 28), *Ājñādāpaka*, *lit.* 'conveyer of orders,' in line 29 of the Ujjain grant of Vākpatirāja of Dhārā (*id.* p. 160) seems to have been another regular title of the same officer; though this is, I think, at present the only instance in which it occurs.—And it is now plain that it is the same office which is referred to in such expressions as *ājñā mahāmahattara-Gaurisarmā*, "the order (is) (conveyed by) the *Mahāmahattara* Gaurisārman," in line 24 of the 'Chicacole' grant of the *Mahārāja* Indravarman of the year 146 (*id.* Vol. XIII. p. 123); *ājñāptis-Siyasarmā*, in line 28 of the 'Pedda-Maddali' grant of Jayasimha I. (*id.* Vol. XIII. p. 138); and *ājñāptih Dāmakirttibhōgakah &c.*, in line 12-13 of the Halsi grant of the eighth year of Mrigēśavarman (*id.* Vol. VI. p. 24 f.).—Line 13 of the Khōh grant of the *Mahārāja* Śarvanātha of the year 197, No. 30 below, Plate xixB, mentions, in addition to the ordinary *Dūtaka*, another *Dūtaka*, sent as a messenger to a second writer, who was ordered to insert certain additional privileges. And this, again, is in favour of my position that the *Dūtaka* carried the orders for the drawing up of a charter, not the charter itself.

⁴ In No. 22 below, Plate xiv. line 30, this name occurs with the short vowel *a* in the first syllable. It is impossible to decide which form is correct, as the first component may be either *bhā*, 'light, splendour, lustre,' or *bha*, 'a star, a planet.'

reading of the texts.—In 1861, in the *Four. Beng. As. Soc.* Vol. XXX. p. 10 ff., Dr. Fitz-Edward Hall published his reading of the text, and a translation of it, from the original plates.—And in 1879, in the *Archæol. Surv. Ind.* Vol. IX. p. 11 f., No. 2, General Cunningham, in partially reprinting Dr. Hall's translation, substituted a close approximation to the correct interpretation of the date, agreeing with Professor Wilson and differing from Dr. Hall; and also gave a lithograph of the passage containing the date (*id.* Plate iv. No. 2.)

The inscription is on another set of copper-plates that were found, with the plates containing the inscription of the same *Mahārāja* Hastin of the year 156, No. 21 above, somewhere in the valley near the village of *Khōh*,¹ in the Nāgaudh State in the Baghelkhand division of Central India. They were originally deposited in the Library of the Sanskrit College at Benares, but were transferred, first to the Provincial Museum at Allahābād, and then to the Provincial Museum at Lucknow, where they now are; but without their ring and seal, which were lost during the transfers.

The plates, which are inscribed on one side only, are three in number. The first two measure about $7\frac{1}{4}$ " by $5\frac{1}{8}$ ", and the third, which was evidently added as an afterthought, when it was found that the inscription could not be completed on the front of the second and that the back of it was not suitable for engraving, about $5\frac{3}{8}$ " by $2\frac{3}{8}$ ". They are quite smooth, the edges being neither fashioned thicker, nor raised into rims. Except, however, for the small piece broken away at the beginning of the third plate, the writing is in a state of excellent preservation throughout. The plates are rather thin; and the letters, being rather deeply engraved, shew through so plainly on the backs of them that even vowel-marks can be read there; and it is evidently owing to this, that the inscription was finished on a third and smaller plate, instead of on the back of the second. The engraving is well executed; but the interiors of the majority of the letters shew, as usual, marks of the working of the engraver's tool.—There is a hole in the upper part² of each plate for a ring, with a seal attached to it; but the ring and seal are not now forthcoming. From the original accounts, the seal appears to have had on it the legend *Sri-Mahārāja-Hastināh*, "of the illustrious *Mahārāja* Hastin," as on the seal of his grant of the year 191, No. 23 below, Plate xiv.—The weight of the three plates is 1 lb. $1\frac{1}{2}$ oz.—The average size of the letters is between $\frac{1}{8}$ " and $\frac{1}{4}$ ". The characters belong to the northern class of alphabets; and the present inscription, with the following, from No. 24, Plate xvA., to No. 31, Plate xx., illustrates what may be called the standard alphabet, with northern characteristics, of Central India, from towards the end of the fifth to the middle of the sixth century A.D. In *sāryadatta*, line 30, on the one hand, and, on the other, in *haryya*, line 20, and *kuryydt*, line 21, we have further illustrations of the two methods of writing *r* in combination with a following *y*, on which I have commented at page 94 above. In *brahmachdrine* and *cha*, line 8, *chāja*, line 16, and *dāndch*, line 23, we have a form of *ch* which belongs properly to a somewhat later period, and to the southern alphabets; but which is perhaps indicative of the current and non-official form of the letter in Central India in this period.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 22 to 28, the inscription is in prose throughout. It has been

¹ See page 93 above, and note 3.

² When the rings are arranged as in these plates, it is customary to find the ring-hole in the bottom of the first plate and the top of the second. But all the grants of this family, and of the *Mahārājas* of Uchchakalpa, as far as Plate xx., have the ring-holes in the top of each plate as here.

engrossed with less care than is usual in epigraphical records of this early date.—In respect of orthography, we have to notice (1) the use of the dental nasal, instead of the *anusndra*, before *ś*, in *vanśa*, line 6; (2) the doubling of *ś*, in conjunction with a following *r*, in *vakśrā*, line 28; (3) the doubling of *t*, under the same circumstances, in *ttri*, line 1; *chaitra*, line 2; and other places; but not in *putrēna*, line 29; (4) the doubling of *dh*, in conjunction with a following *y*, in *maddhyēna*, line 18; but not in *avadhyēna*, line 21; and (5) the use of *v* for *ḁ*, in *lamvōshtha*, line 14.

The inscription is one of the **Parivrājaka Mahārāja Hastin**. It is dated, in words, "in the enjoyment of sovereignty by the Gupta kings," in the year one hundred and sixty-three¹ (A.D. 482-83), in the Mahā-Āsvayuja *samvatsara*, and on the second lunar day of the bright fortnight of the month Chaitra (March-April). Except for the opening invocation of the god Śiva, under the name of Mahādēva, the inscription is non-sectarian. And the object of it is to record the grant, by the **Mahārāja Hastin**, of the *agrāhāra* of **Kōrparika** to certain Brāhmins.

TEXT.²

First Plate.

- 1 Namō Mahādēvāya (11) Svasti Ttri-shashty-uttarē-bda-śatē **Gupta-nripa-**
rāja-bhuktāu
2 Mah-Āsvayuja-sāmvatyārē³ Chaittra-māsa-śukla-paksha-dvity[ā⁴]yām-asy[ā⁴]n-
divasa-
3 pūrvv[ā⁴]yā[ś⁴]n[ā⁴] nripatiparivrājaka-kul-ōtpannēna mahārāja-Dēvādhyā-
pranapt[ī⁴]ā

¹In respect of the date of this inscription, Gen. Cunningham (*Archæol. Surv. Ind.* Vol. IX. pp. 9 and 11, and Vol. X. p. 116) has expressed the opinion that one hundred and sixty-three is a mistake for one hundred and seventy-three. And certainly the record in No. 21, page .95 above, that the year 156 was Mahā-Vaiśākha, leads *primafacie* to the conclusion that 163 would be Mahā-Mārgaśrāha, and that Mahā-Āsvayuja would be (either 161 or) 173; especially since the record of No. 25, page 112 below, that 209 was Mahā-Āsvayuja, points to the names of the *samvatsaras* running in regular succession, without any adjustment by expunction, through this period of fifty-four years. But Gen. Cunningham's suggestion that the apparent error is "a mistake of the engraver, who has written *shasht*" (sic.) "(60) instead of *sapt*" (sic.) "(70), which in Gupta characters might easily happen," takes no account of an additional *akshara* that must then have been omitted altogether. "Increased by seventy-three" would be, not *ttri-sapty-uttarē*, but *ttri-sapty-uttarē*. And it would not be an easy matter for the engraver to turn this full and correct form into *ttri-shashty-uttarē*. Gen. Cunningham's present tables for the twelve-year cycle of Jupiter (*Archæol. Surv. Ind.* Vol. IX. p. 118 ff.; and *Indian Eras*, Table xvii. Col. 10, p. 135 ff.) will have to be re-examined. In this process, with the possibility, which there always is, of the drafters of these epigraphical records making a mistake between current and expired years, it may turn out that this passage really does contain a mistake; which, if it does exist, is more likely to be in the direction of *ttri*, 'three,' having been engraved instead of *dvi*, 'two,' and perhaps of the drafter of the record having also written one hundred and sixty-two, instead of one hundred and sixty-one.—Meanwhile, Dr. Thibaut, who is a competent authority, has recorded his opinion (*Ind. Ant.* Vol. XI. p. 322) that "observation has, as we know, never been the strong point of Hindu astronomers; and if, according to their system, a certain year was to be called Mahā-Chaitra, they would scarcely have hesitated to do so, even if they had found that the name was not justified by Jupiter's actual position." And, until the matter is definitely settled one way or the other, it is better to adhere to the distinct reading of the year one hundred and sixty-three.

² From the original plates.

³ Read *samvatsarē*.

⁴ Supply *tithau*.

- 4 mahārāja-śrī-Prabhāñjana-naptrā mahārāja-Dāmōdara-sutēna gō-sahasra-
 5 hasty-aśva-hirany-ānēka-bhūmi-pradēna guru-pitṛi-mātri-pūja-tanatparēn¹-ā-
 6 tyanta-dēva-brāhmaṇa-bhaktēna naika-samara-śata-vijayinā sva-vanś-amōdaka-
 7 rēna mahārāja-śrī-Hastinā sva-puṇy-āpyāyan-ārtham-Agnisv[ā*]mputra-
 Bharadvāja-
 8 sagōttra-Vāji(ja)sanēyasabrahmacharūpē² Dēvasvāminē³ Śarvasvāminē
 cha
 9 Gōrisvāminē Vāji(ja)sanēya-sabrahmachārīpē Kautsa-sagōttrāya Di-
 10 vākarasvāminē cha Sv[ā*]tisvāminē Vājasanēya-sabrā(bra)hmachārīpē
 Bhārgga-
 11 va-sagōttrāya Varuṇasarmmanah⁴ Bappasvāminē Vāsula-sagōttr[ā*]ya
 12 Kāṭha-sabrahmachārīpē Kumāradēvarēva⁵ Vāji(ja)sanēya-sabrahmachari-
 13 na⁶ Māt[ri*]śarmmah⁷ Nāgaśa[r*]mma Rukharadēvah⁸ Kaudravadēvah⁹
 Vishṇu[*]dēvah¹⁰

Second Plate.

- 14 Dēvanāga Kumārasēna¹¹ Rudrasarmma¹² Dēvadā(?)ṅgarā(?)¹³
 Lamvō(mbō)shṭha Dēdamita¹⁴
 15 Mahadēva Guṇṭhaka ity-ēvam-ādibhyō brāhmaṇēbhy-ōttare paṭṭē
 Kōrppari-
 16 k-āgrāhārah s-ōdraṅgaḥ s-ōparikarah a-chāṭa-bhaṭa-prāvēśyō-tisriṣṭah-
 17 s¹⁵-Tasy-āghāṭah pūrvvēna Kōrpparagartā¹⁶ | uttarēn-Ānimuktakakōpakaḥ
 18 Vaṅgara-grāmakasya dakṣiṇa-p[ā*]rsvē Valaka-maddhyamā¹⁷ vṛikaḥ
 amvrāta-samtāra-
 19 kaḥ¹⁸ [i*] paśchimēna Nāgasarī¹⁹ dakṣiṇēna Balavarmma-parichchēdāḥ [ii*]
 Tad-asma-
 20 [t*]-kul-ōtthair-mmat-pādami(pi)ṇḍ-ōpajivibhir-vvā²⁰ kālāntarēshv-api na
 vyāghātaḥ kāryya[h*] [i*]
 21 ēvam-ājñāpta²¹ yō-nyathā kuryān(t)-tam-aham dēhanāra-gatō-pi mahat-
 āvadhyānē-

¹ Read *pāñj-tatparēn*.—The engraver omitted to cut the *ā* of *jā*; and to cancel the *na*, when he inserted, partly above the line and somewhat small, the *ta* for which *na* had been engraved by mistake

² Read *chārīpē*.

³ First *na* was engraved; and then it was corrected into *sv*, by partial erasure of the upper stroke of the *sv*.

⁴ Read *sarmmanah*.

⁵ Read *dēvaya*.

Read *chārīnē*.

⁶ Read *sarmma*.—From here, down to *ity-ēvam-ādibhyō* in line 15, is properly a compound; but it is spoilt by the three nominative cases at the end of this line, and by the unnecessary mark of punctuation in the next line.

⁷, ⁸, and ¹⁰ Read *dva*.

¹¹ After this *na*, some letter, which is not quite certain, was engraved and then cancelled.

¹² This mark of punctuation is unnecessary.

¹³ Read *dēvadāṅgarāh (?)*.

¹⁴ This is perhaps a mistake for *dēvamitra*.

¹⁵ Read *brāhmaṇēbhyā uttarē*.

¹⁶ Read *tisriṣṭas*.

¹⁷ Read *maddhyamā*.

¹⁸ Read *amvrāta*; and probably *sambhāraka*.

¹⁹ First *svna* was engraved, and then it was corrected into *svō*.

²⁰ Read *ājñāptā* or *ājñāptā*.

- 22 na nirddahéd¹=Uktañ-cha bhagavatá param-arshipá véda-vyáséna [1*]
Púrva²-dattá[m*]
23 dvijátibhyó yatñád-rakshya(ksha) Yudhishthirah³ mah[rm*] mah[i*]matám
śrēshtha dánāc-chhrē-
24 yó⁴-nupálanam I(II) Bahubhir-vvasudhá bhuktá rájabhiḥ Sagar-ádibhiḥ
sa(ya)sya ya-
25 yasya⁴ yadá bhūmis-tasya [tasya*] tadá phalan(m) [II*] Sva-
dattá[m*] para-dattám vá yó haré-
26 ta vasundharāḥ(m) sa viśth[ā*]yá[m*] kṛimir-bhūtvá pitrabhi⁵ saha
pachyaté [II*]

Third Plate.

- 27 Sh[a]śt[im] v[ar]vva(sha)-sahasrañi svarggē módati bhū(bhū)mi-daḥ
āchchhēt[t*]ā
28 ch-ānumant[ā*] ma(cha) t[ā*]ny-ēva narakē vasé[t*] [II*] Likhitañ-
cha⁶ Vakk-ām[ā*]tya-prana-
29 ptranatrā⁷ bhōgika-Naradatta-napt[r*]ā bhōgika-Ravidatta-putrēna(ṇa) mahā-
30 sāndhivigrahika-Suryadatēnaḥ⁸ [1*] Bhagrahō dūtaka[h*] [II*]

TRANSLATION.

Reverence to (the god) Mahādēva! Hail! In a century of years, increased by sixty-three;⁹ in the enjoyment of sovereignty by the Gupta kings; in the Mahā-Aśvayuja *samvatsara*; on the second lunar day of the bright fortnight of the month Chaitra,—on this (*lunar day*), (*specified*) as above by the day (*Śc.*),—

(Line 3).—By the *Mahārāja*, the illustrious *Hastin*,—who is born in the family of a kingly ascetic;—who is the great-grandson of the *Mahārāja Dēvādhyā*;—who is the grandson of the *Mahārāja*, the illustrious *Prabhāñjana*;—who is the son of the *Mahārāja Dāmōdara*;—who is the giver of thousands of cows, and elephants, and horses, and gold, and many lands;—who is earnest in paying respect to (*his*) spiritual preceptor and (*his*) father and mother;—who is extremely devoted to the gods and Brāhmins;—who has been victorious in many hundreds of battles;—(*and*) who causes the happiness of his own race,—

(L. 7).—(*By him*),—for the purpose of increasing his own religious merit,—the *agrāhāra* of *Kōrparika*, in the northern *pañja*,¹⁰ is granted, with the *udranga* and the

¹ Read *nirddahēyam*.

² Read *yudhishthira*.

³ Read *pitribhiḥ*.

⁴ Read *pranaptra*—Mistakes of this kind would occur through the engraver not spacing the *aksharas* out as far as they were spaced in the painted arrangement on the copper. He would thus come to engrave *naptra* (for *naptrā*) two *aksharas* before the place intended for it; and he then ignorantly, and also imperfectly, repeated the *aksharas*, by engraving the painted marks still remaining on the plate.

⁵ Read *sūryadatēna*.

⁶ See page 102 above, note 1.


⁷ *pañja*, as used here, is apparently some technical territorial term. Compare *pañi*, for *paññi*, in line 8 of the Halsi grant of Bhānuvarman (*Ind. Ant.* Vol. VI. pp. 28 and 29, note), which, both in Kanarese and in Marāṭhi, is used for 'a strip of land, a division of a village.' Compare also *paññid* in line 16 of the Kaira grant of Vijayarāja of the year 394 (*id.* Vol. VII. pp. 248 and 250, note 27), and in line 11 ff. of the cancelled grant on the same plates (*id.* p. 252)

⁸ Metre, Ślōka (Anushtubh), and in the following three verses


⁹ Read *yasya*, the engraver repeated the *ya* by mistake.

¹⁰ Supply *śūsanam*.

Khoh Plates of the Maharaja Hastin—The Year 163.



14
16
18
20
22
24
26



2
4
6
8
10
12



28
30

SCALE .68

uparikara, and (with the privilege that it is) not to be entered by the irregular or regular troops, to (certain) Brāhmanas, commencing with Dēvasvāmin, the son of Agnisvāmin, of the Bharadvāja *gōtra* (and) a student of the Vājasaneyā (*śākhā*), and Śarvasvāmin, (and) Gōrisvāmin,—Divākarasvāmin, of the Kautsa *gōtra*, a student of the Vājasaneyā (*śākhā*), (and) Svātisvāmin,—Varuṇasarman, of the Bhārgava *gōtra*, a student of the Vājasaneyā (*śākhā*), (and) Bappasvāmin,—Kumārādēva, of the Vāsula *gōtra*, a student of the Kāṭha (*śākhā*),—(and) Mātrīsarman, a student of the Vājasaneyā (*śākhā*), (and) Nāgasarman, Rukharādēva, Kaudravādēva, Vishṇudēva, Dēvanāga, Kumārasēna, Rudrasarman, Dēvadāhgiras (?), Lambōshṭha, Dēvamitra (?), Mahādēva, (and) Guṇṭhaka.

(L. 17.)—The boundaries of it (are),—on the east, (the boundary-trench or village called) Kōrparagartā; on the north, Animuktakakōṇaka, (and) a *vrīka*-tree¹ in the centre of Valaka on the south side of the village of Vaṅgara, (and) a clump² of *amrāta*-trees;³ on the west, (the tank or village called) Nāgasari; (and) on the south, the *parichchhēda*⁴ of Balavarman.

(L. 19.)—Therefore, even in future times, no obstacle (to the enjoyment of this grant) is to be caused by those who are born in Our family, or by my feudatories. This injunction having been given, he who behaves otherwise,—him I will consume with a great contempt, even when I have passed into another body.

(L. 22.)—And it has been said by the venerable supreme sage, the arranger of the Vēdas,—“O Yudhishṭhira, best of kings, carefully preserve land that has previously been given to the twice-born; (verily) the preservation (of a grant) (is) more meritorious than making a grant! The earth has been enjoyed by many kings, commencing with Sāgara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (of this grant that is now made, if he continue it)! He becomes a worm in ordure, and is tormented together with his ancestors, who confiscates land that has been given, whether by himself, or by another! The giver of land enjoys happiness in heaven for sixty thousand years; (but) the confiscator (of a grant), and he who assents (to an act of confiscation), shall dwell for the same number of years in hell!”

(L. 28.)—And (this charter) has been written by the *Mahāsāmdhivigrahika*⁵ Sāryadatta; the great-grandson of the *Amṛitya* Vakra; the grandson of the *Bhōgika* Naradatta; (and) the son of the *Bhōgika* Ravidatta. *Bhagraha*⁶ (is) the *Dātaka*.

¹ *vrīka*; the *Sebana Grandiflora*.

² Or,—if we keep the original reading of *śamīdraka*,—‘the ferry (at the place) of the *amrāta*-trees.’

³ *amrāta*; the hog-plum, *Spondias Mangifera*.

⁴ *parichchhēda*; *lit.* ‘division, separation,’ is a technical territorial term, the exact purport of which cannot be at present suggested.

⁵ *Mahāsāmdhivigrahika*, *lit.* ‘a great officer entrusted with the arrangement of peace and war,’ is a technical official title denoting an official superior to the *Sāmdhivigrahikas* (see page 16 above, note 6). Another of his titles was *Mahāsāmdhivigrahādāhikārādhipati*, e.g. in line 18-19 of the grant of Gōvinda III. of Śaka-Samvat 726 (*Ind. Ant.* Vol. XI. p. 127.)

⁶ See page 100 above, note 4.

No. 23; PLATE XIV.

MAJHGAWAM COPPER-PLATE INSCRIPTION OF THE
MAHARAJA HASTIN.

THE YEAR 191.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. pp 7 and 13 f., No. 5, where he published a translation of it, with a lithograph of the two passages containing the date (*id.* Plate iv. No. 5),—is on some copper-plates that were discovered in 1870, in ploughing a field at the village of **Majhgawām**,¹ about three miles towards the south-west from Uchaharā, the capital of the Nāgaudh State in the Baghēlkhapṇ division of Central India. I obtained the original plates, for examination, from the possession of the Rājā of Nāgaudh, through the kindness of Major D. W. K. Barr, Political Agent, Satnā.

The plates, which are inscribed on one side only, are two in number, each measuring about $8\frac{1}{8}$ " by $5\frac{7}{8}$ ". They are quite smooth, the edges being neither fashioned thicker nor raised into rims. Except, however, for the small piece broken away at the beginning of the second plate, the inscription is in a state of perfect preservation throughout. The plates are not very thick; and the letters, which are rather deeply engraved, shew through on the backs of them. The engraving is very good, but, as usual, the interiors of many of the letters shew marks of the working of the engraver's tool.—In the upper part of each plate, there is a hole for a ring, with a seal attached to it. The ring and seal are not now forthcoming; but fortunately General Cunningham had preserved a pencil-rubbing of the seal, from which I have been able to give a lithograph. It represents a pointed oval seal, about $2\frac{1}{4}$ " by 1", with the legend *Śrī-mmahārāja-Hastināḥ*, "of the illustrious Mahārāja Hastin."—The weight of the two plates is 1 lb. 14 oz.—The average size of the letters is between $\frac{1}{8}$ " and $\frac{3}{4}$ ". The characters belong to the northern class of alphabets, and are of the peculiar 'nail-headed' type, on which I have commented at page 19 above; thus giving another variety, with northern characteristics, of the Central India alphabet of the period. They include the very rare initial *au*, in *aupamanyava*, line 8. In *kurydt*, line 12, and *sūryadatta*, line 19, we have further illustrations of the first method of writing *r* in combination with a following *y*, on which I have commented at page 94 above. In *chkrēyō*, line 14, *yō*, line 16, *apāntyēshu*, line 17, and *yē*, line 18, we have a form of *y*, differing from the form used throughout the rest of this inscription, e.g. in *dēvāya*, line 1, and *trītiyāyam*, line 2. It belongs properly to a somewhat later development of the northern alphabet, as used in formal official records; and we find it, for instance, throughout the Bōdh-Gayā inscription of Mahānāman, of the year 269, No. 71 below, Plate xliA., but it is perhaps indicative of the current form of the letter in this period.² The characters also include, in lines 20 and 21, forms of the **numerical**

¹This name, given in maps, &c., as 'Majgama, Majgowa, Majhgawan, Mujjowan, Mujgoah, Mujgowan, and Munjgowa,' is a very common one in that part of the country. The present village should be in the Indian Atlas, Sheet No. 89; but it is not entered there, unless 'Moghani' (Lat. $24^{\circ} 22' N.$; Long. $80^{\circ} 47' E.$) is intended for it.

²Read *śrī-mahā*.

³I to quote another early instance, the same form occurs also in *vijaya*, in line 1 of the 'Kondakur grant of the Pallava prince Vijayabuddhavarman (*Ind. Ant.* Vol. IX. p. 101 and Plate); but the cor-

symbols for 1, 3, 90, and 100.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 13 to 18, the entire inscription is in prose.—In respect of orthography, we have to notice (1) the use of the guttural nasal, instead of the *anusvāra*, before *h*, in *siṅha*, line 20; (2) the doubling of *k*, *g*, and *t*, in conjunction with a following *r*, in *vakkra*, line 18; *viggrahika*, line 19; and *chaitra*, line 2, and *pitṛōr*, line 7; but not in other places, e.g. in *sagbtrēbhyaḥ*, line 8; (3) the doubling of *dh*, in conjunction with a following *y*, in *avaddhyanēna*, line 12; (4) the occasional use of *b* for *v*, in *sambatsara*, line 2 (twice), and *sambat*, line 20; and (5) the occasional use of *v* for *b*, in *vrahmaṇa*, line 5, and *vahubhir*, line 14.

The inscription is one of the **Parivrājaka Mahārāja Hastin**. It is dated, both in words and in numerical symbols, "in the enjoyment of sovereignty by the **Gupta kings**," in the year one hundred and ninety-one (A.D. 510-11), in the **Mahā-Chaitra samvat-sara**, and on the third lunar day of the dark fortnight, and the third solar day of the whole month, of **Māgha** (January-February).¹ Except for the opening invocation of the god **Śiva**, under the name of **Mahādēva**, the inscription is non-sectarian. The object of it is to record the grant, by the **Mahārāja Hastin**, at the request of a certain person named **Mahādēvidēva**, of the village of **Vālugarta** to certain **Brāhmins**.

TEXT.¹

First Plate.

- 1 Namō Mahādēvāya ॥ Svasty-Ēka-navaty-uttarē-bda-śatē **Gupta-nṛ pa-**
rājya-bhuktau śrīmati pravarddhamāna²
- 2 Mahā-Chaittra-samba(mva)tsarē Māgha-māsa-bahula-paksha-tritīyāyam-asyā[m³]
samba(mva)tsara-māsa-divasa-pūrvvā-
- 3 yām⁴ [1⁵] Nripatiparivrājaka-kul-ōtpannēna mahārāja-**Dēvādhyā**-pranaptrā
mahārāja-śrī-**Prabhamjana**-naptrā mahā-
- 4 rāja-śrī-**Dāmōdara**-sutēna gō-sahasra-hasty-aśva-hirany-ānēka-bhūmi-pradēna
guru-pitṛi-mātri-pūjā-
- 5 tatparēṇ-ātyanta-dēva-vrā(brā)hmaṇa-bhaktēn-ānēka-samara-śata-vijayinā sva-
vanś-āmōdakarēṇa mahā-
- 6 rāja-śrī-**Hastinā Mahādēvidēva**-sukha-vijñaptiyā **Vālugarttō** nāma grāmah
pūrvv-āghāṭa-parichchhēda-ma-
- 7 ryādāyā s-ōdraṅgaḥ s-ōpanikarō-ch[ā⁶]ta-bhāta-prāvēśyah mātāpitṛōr-
ātmanāś-cha puṇy-ābhivṛiddhayē **Mahādē**.

rect ancient form of the letter is used throughout the rest of this inscription also, e.g. in *yvva*, line 2, and *vijaya*, line 3.

¹The double record of this date is of considerable importance. In line 2, the day is distinctly specified as the third lunar day of the dark fortnight; while, in line 21, in numerical symbols, it is shown as the third day of the month, without any specification of the fortnight. So, again, in No. 23 below, page 114 f., the thirteenth lunar day of the bright fortnight of Chaitra (line 2 f.), is shown in line 24 as the twenty-ninth solar day of the whole month. The four entries together prove that, as might be expected in the case of an era belonging to Northern India, the arrangement of the fortnights of the months of the Gupta year followed the northern custom, with the dark fortnight preceding the bright.

²From the original plates.

³The vowel *ā*, of *mā*, appears to have been engraved and then cancelled here. In Plate xvB, l. 2, the reading is as I transcribe it here.

⁴Supply *titika*.

- 8 vidēva-sukhām cha svargga-sōpāna-pāṅktim-ārōpayatā Aupamanyava-
sagōtrēbhyas-Chhandōga-Kauthuma-
9 sabrahmachāribhyō-mibhya¹ brāhmaṇēbhyāḥ Gōvindasvāmi- I Gōmlka²-
svāmi-Dēvasvāmibhyāḥ putra-pau-
10 tr-ānvay-ōpabhōgyas-tāma-sāsanēn-āgrāhārō-tisriṣṭaḥ chaura-varjjam [I*] Tad-
asmat-kul-ōttthair-mmat-pāda-
11 piṇḍ-ōpajivibhir-vvā kāl-āntarēshv-api na vyāghātaḥ karāṅyaḥ [I*]
ēvam-ājñāptē³, yō-nyathā
12 kuryāt-tam-aham dēhāntara-gatō-pi mahat-āvaddhyānēna nirddahēyam-
Uktam cha bhagavatā parama-

Second Plate.

- 13 [r]sh[ī]ṇā vēda-vyāsēna Vyāsēna II(I) Pūrvva⁴-dattām divijātibhyō yatnād-
raksha Yudhishthira mah[ī]n⁵
14 mahimatām śrēshṭha dānāch-chhrēyō-nupālanam I(II) Va(ba)hubhir-
vvasudhā bhuktā rājabhiḥ Sagar-ādibhiḥ ya-
15 sya yasya yadā bhūmis-tasya tasya tadā phalam [II*] Shashṭim
varsha-sahasr[ā*]ṇi svarggē mōdati bhūmi-dah
16 ākshēptā ch-ānumantā cha tāny-ēva narakē vasēt [II*] Sva-dattām
pura-dattām-bā(vā) yō harēta vasundharām
17 sa vishṭhāyām kkrimir-bhōtvā pitribhiḥ saha majjatē [II*]
A-pāntyēshv-arapyēshu sushka-kōtara-vāsinah
18 krishṇ-āhayō-bhijāyantē pūrvva-dāyam haranti yē II Likhitam⁶ cha
Vakr-āmātya-pranaptri-naptrā⁷
19 bhōgika-Naradatta-pranaptrā Ravidatta-naptrā Sūryadatta-puttrēpa mahā-
sāndhiviggrahika-
20 Vibhudattēn-ēti [I*] Mahāva(ba)lādihkrita-Nāgasinhō dōtakāḥ [II*]
Samba(mva)t 100 90 I
21 Māgha di 3 [II*]

TRANSLATION.

Reverence to (the god) Mahādēva! Hail! In a century of years, increased by ninety-one; in the enjoyment of sovereignty by the **Gupta kings**; in the prosperous augmenting Mahā-Chaitra *samvatsara*; on the third lunar day of the dark fortnight of the month Māgha,—on this (*lunar day*), (*specified*) as above by the *samvatsara* and month and day,⁷—

¹ Read *mibhyō*.

² Read *gōvindasvāmi-gōmlka*.

³ Read *ājñāptē*, or *ājñāptit*.

⁴ Metre, *Ślōka* (Anusṭubh); and in the following four verses.

⁵ Supply *īksanam*.

⁶ This must be a mistake for either *naptri-naptrā*, or *pranaptri-putrēna*; since, as the text stands, it passes over the generation between Vakra and Naradatta.

⁷ See page 97 above, note 1.

Majhgawam Plates of the Maharaja Hastin.—The Year 191.



i

1
2
3
4
5
6
7
8
9
10
11
12

...
...
...
...
...
...
...
...
...
...
...
...

ii

14
16
18
20

...
...
...
...
...

(Line 3).—By the *Mahārāja*, the illustrious *Hastin*,—who is born in the family of a kingly ascetic;—who is the great-grandson of the *Mahārāja Dēvādhyā*;—who is the grandson of the *Mahārāja*, the illustrious *Prabhafjana*;—who is the son of the *Mahārāja*, the illustrious *Dāmōdara*;—who is the giver of thousands of cows, and elephants, and horses, and gold, and many lands;—who is earnest in paying respect to (*his*) spiritual preceptor and (*his*) father and mother;—who is extremely devoted to the gods and Brāhman;—who has been victorious in many hundreds of battles;—(*and*) who causes the happiness of his own race,—

(L. 6).—(*By him*), at the agreeable request of *Mahādēvidēva*, the village named *Vālugarta*, in accordance with the usage of the specification of (*its*) ancient boundaries, with the *udraṅga* and the *uparikara*, (*and with the privilege that it is*) not to be entered by the irregular or the regular troops, is granted as an *agrādāra*, by a copper-charter,—for the purpose of increasing the religious merit of (*his*) parents and of himself, and in order to erect the steps of a ladder leading to heaven, acceptable to *Mahādēvidēva*,—to these Brāhman, of the *Apamanyava gōtra*, students of the *Chhandōga-Kauthuma (śākhā)*, (*viz.*) *Gōvindasvāmin*, *Gōmikasvāmin*, and *Dēvasvāmin*,—to be enjoyed by (*their*) sons and sons' sons, with the exception of (*the proceeds of fines imposed on*) thieves.

(L. 10).—Therefore, even in future times, no obstacle (*to the enjoyment of this grant*) is to be caused by those who are born in Our family, or by my feudatories. This injunction having been given, he who behaves otherwise,—him I will consume with a great contempt, even when I have passed into another body.

(L. 12).—And it has been said by the venerable supreme sage, *Vyāsa*, the arranger of the *Vēdas*,—“O *Yudhishtira*, best of kings, carefully preserve land that has previously been given to the twice-born; (*verily*) the preservation (*of a grant*) is more meritorious than making a grant! The earth has been enjoyed by many kings, commencing with *Sagara*; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! He becomes a worm in ordure, and is tormented together with his ancestors, who confiscate land that has been given, whether by himself or by another! Those who confiscate a previous grant, are born (*again*) as black serpents, inhabiting the dried-up hollows of trees, in desert places destitute of water!”

(L. 18).—And (*this charter*) has been written by the *Mahāśādhivigrahika Vibhudatta*, the son¹ of the great-grandson of the *Amātya Vakra*; the great-grandson of the *Bhōgika Naradatta*; the grandson of *Ravidatta*; (*and*) the son of *Sūryadatta*. The *Mahābaldhikrita*² *Nāgasinha* (*is*) the *Dātaka*. The year 100 (*and*) 90 (*and*) 1; (*the month*) *Māgha*; the day 3.

¹ See page 108 above, note 6.

² *Mahābaldhikrita*, *lit.* ‘a great officer placed at the head of the forces,’ is a technical official title, denoting an officer superior to the *Baldhikrita*.—The latter title, *Baldhikrita*, occurs in line 2 of the *Shāhpur* image inscription of *Ādityasēna*, No. 43 below, Plate xxixA.—A synonym for *Mahābaldhikrita* was *Mahābaldhikṛita*, which occurs in Mr. Bendall's *Nēpal* inscription of *Harsha-Satvat* 34 (*Journey in Nēpal*, p. 75, line 17.)

No. 24; PLATE XV A.

BHUMARA STONE PILLAR INSCRIPTION OF THE
MAHARAJAS HASTIN AND SARVANATHA.

THIS inscription appears to have been discovered by General Cunningham; and was first brought to notice by him, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. pp. 8 f. and 16, No. 9, where he published his translation of it, accompanied by a lithograph (*id.* Plate iv. No. 9.)

Bhumarā¹ is a village about nine miles to the north-west of Uchaharā, in the Nāgaudh State in the Baghelkhand division of Central India. From line 3 of the inscription, the ancient name of the place seems to have been **Āmbliōda**. The inscription is on one of the faces of the bottom and rectangular part of a small red-sandstone pillar, popularly called *thādī-patthar* or "the standing stone," in the lands of this village.

The writing, which covers a space of about 10½" broad by 1' 6½" high, is in a state of very fair preservation throughout.—The size of the letters varies from ⅜" to ⅞". The characters belong to the northern class of alphabets. They include, in line 9, forms of the numerical symbols² for 9 and 10.—The language is Sanskrit; and the entire inscription is in prose.—In respect of orthography, we have to notice (1) the doubling of *ī*, in conjunction with a following *r*, in *putra*, line 5; (2) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, line 2; and (3) the use of *b* for *v*, in *sambatsarā*, line 8.

The inscription is one of the two *Mahārājas Hastin*, of the *Parivrājaka* family, and *Sarvanātha*,³ of *Uchchakalpa*. It is dated, in numerical symbols, on the nineteenth day,⁴ without any specification of the fortnight, of the month *Kārttika* (October-

¹The 'Bhumara and Bumra' of maps. Indian Atlas, Sheet No. 70. Lat. 24° 25' N.; Long. 80° 41' E.—Gen. Cunningham wrote the name 'Bhubhara.' And, at Satnā, it was given to me as 'Bhubhurā.' But my office-people brought back the name as either *Bumarā* or *Bhumarā*, and said that the villagers do not know of any other form of the name. Of these two forms, *Bhumarā* agrees most closely with the names in the maps, and seems to be the correct one.

²I am a little doubtful about the second symbol, which occurs again in line 24 of No. 25 below, Plate xvB, and line 14 of No. 71, Plate xliA. But it resembles most a rather straight and upright form of the symbol for 9. The only other possibilities are 7 or 8.

³For this *Mahārāja*, see Nos. 28, 29, 30, and 31 below.

⁴Other instances will be met with, in the present series, of the number of a day exceeding sixteen, which is the extreme number in a lunar fortnight, bright or dark. And such instances are still more common in other inscriptions.—In such cases, whether there is any mention of a lunar fortnight or not, and also in cases in which the number of the day does not exceed sixteen, and the lunar fortnight is not mentioned, it is sometimes thought that the reference is to the solar, not the luni-solar, months and year. But I do not consider that this necessarily follows. At *Hulgūr*, in the *Bankāpur Talukā* or Sub-Division of the *Dhārwad District*, there is an inscription of the *Yādava* king *Mahādēva* of *Dēvagiri*, in which the date (line 15 ff.) is *Saka-varshada 1189neya Prabhava-samvatsarada Jyēshtha ba 30 Budhavāra sūryagrahanad-andu*, "(the month) *Jyēshtha* of the *Prabhava samvatsara*, which is the 1189th *Saka* year (A.D. 1267-68); the dark fortnight; (the solar day or lunar *tithi*) 30 (of the month); Wednesday; at the time of an eclipse of the sun." And we also have the *Kōṭā* inscription of the *Sāmanta Dēvadatta*, in which the date (*Ind. Ant.* Vol. XIV. p. 351 f.) runs *Samvat 800 70 9 Māgha su di 20*, "the year 800 (and) 70 (and) 9 (A.D. 822-23); (the month) *Māgha*; the bright fortnight; the day 20 (of the month)." Of these, the first is a southern date, according to the arrange-

November), in the Mahā-Māgha *samvatsara*, without any reference to an era. But the choice lies only between Gupta-Samvat 189 and 201; and, as we have for the *Mahārāja Hastin* the early date of the year 156, in No. 21 above, page 93, the preference is in favour of the year one hundred and eighty-nine (A. D. 508-9). The inscription is non-sectarian; the object of it being simply to record the erection, at *Āmblōda*, of a boundary-pillar between the territories of the two *Mahārājas* in question.

One point of importance in connection with this inscription, is that its existence on stone furnishes definite evidence that the *Parivrājaka Mahārājas* and the *Mahārājas* of *Uchchakalpa* really did belong to this part of the country. This is a point on which stone-inscriptions give testimony of a kind that can never be derived from the mere finding, in a certain locality, of copper-plates, which, being small and portable, are always liable to be carried to a considerable distance from the places to which they properly belong,¹ and can only be applied territorially when the places mentioned in them can be identified.

TEXT.²

- 1 Svasti Mahādēva-pād[ā]-
 2 nuddhyātō(ta)-mahārāja-Hasti-
 3 rājyē Āmblō'dē mahārāja-
 4 Śarvvanātha-bhōgē Indana-
 5 naptrā Vāsu-grāmika-puttra-
 6 Śivadāsēna vala-ya-
 7 shti uchchhritah³ [1*] Mahā-
 Māghē
 8 samba(mva)tsarē Kārttika-
 māsa
 9 divasa 10 9 [11*]

TRANSLATION.

Hail! In (*the boundary of*) the kingdom of the *Mahārāja Hastin*, who meditates on the feet of (the god) Mahādēva; at (the village of) *Āmblōda*; (*and*) in (*the boundary*

ment by which the bright half of the month comes first; and the second is a northern date, according to the arrangement by which the dark half comes first. These instances, of course, are exceptional ones. But they suffice to shew that, both in northern and in southern India, down to comparatively late times, the numbering of the solar days and lunar *tithis* of the month up to thirty did occasionally continue alongside of the more usual reckoning by fortnights, in which the lunar *tithis* of each fortnight are denoted by the numbers one to fifteen only, and the solar days by the numbers one to fourteen, fifteen, or sixteen, as the case may be.

¹ A marked instance of the distances to which copper-plates and seals may travel, is afforded by the finding of the seal of the Maukhari Śarvavarman, No. 47 below, at Aśtīgadhī in the Nimāḍ District in the Central Provinces. Its original locality must have been some hundreds of miles to the east of this.

² From the ink-impression.

³ The engraver seems to have first engraved *hīd*, or perhaps *dhīd*, and then corrected it into *sūdd*.

⁴ Read *valaya-yashfir=uchchhritā*. — As regards the correction of *vala* into *valaya*, *vala-yashfi* or *hala-yashfi* gives no meaning; whereas the appropriateness of *valaya-yashfi*, 'boundary-staff or pillar,' is apparent. The mistake arose from the omission to repeat, at the beginning of line 7, the *ya* at the end of line 6.

of) the *bhōga*¹ of the *Mahārāja Śarvanātha*,—(this) boundary-pillar has been set up by *Śivadāsa*, the grandson of Indana, and the son of the *Grāmika*² *Vāsu*;—in the *Mahā-Māgha samvatsara*; the month *Kārttika*; the day 10 (and) 9.

No. 25; PLATE XV B.

KHOH COPPER-PLATE INSCRIPTION OF THE MAHARAJA SAMKSHOBHA.

THE YEAR 209.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. p. 15, No. 7, where he published a translation of it, with a lithograph of the two passages containing the date (*id. Pl. iv. No. 4*),—is on another set of copper-plates that appear to have been found somewhere in the valley near the village of *Khôh*,³ in the *Nāgaudh* State in the *Baghêlkhand* division of Central India. I obtained the original plates, for examination, from the possession of the *Rājā* of *Nāgaudh*, through the kindness of Major D. W. K. Barr.


The plates, which are inscribed on one side only, are two in number, the first measuring about $8\frac{1}{8}$ " by $4\frac{1}{2}$ ", and the second about $8\frac{1}{8}$ " by $4\frac{1}{8}$ ". They are quite smooth, the edges being neither fashioned thicker, nor raised into rims. They have apparently been subjected to the action of fire; but the inscription is in a state of very good preservation throughout. The plates are fairly thick; but the letters are deep, and shew through very distinctly on the backs of them. The engraving is good; but, as usual, the interiors of the letters shew marks of the working of the engraver's tool.—In the upper part of each plate, there is a hole for a ring to connect them. The ring is about $\frac{1}{2}$ " thick and $2\frac{1}{4}$ " in diameter. It had not been cut, when the grant came under my notice; but one end of it had been forced out of the socket of the seal, so that it could be separated from the plates. The seal, in the lower part of which the ends of the ring were originally fused and so secured, is rectangular, about $1\frac{1}{8}$ " by $\frac{1}{2}$ ". It must have had a legend, on a countersunk surface; but it is now perfectly illegible, and not worth reproducing by a lithograph. Also, from the shape of the seal, as contrasted with that of the *Khôh* grant of the *Mahārāja* *Hastin* of the year 191, No. 23 above, Plate xiv., and compared with the seal of the *Khôh* grant of the *Mahārāja* *Śarvanātha* of the year 193, No. 28 below, Plate xviii., it would seem to be a seal of one of the *Mahārājas* of *Uchchakalpa*, rather than of one of the *Parivrājaka Mahārājas*.—The weight of the two plates is 1 lb. $8\frac{1}{2}$ oz., and of the ring and seal, 6 oz.; total 1 lb. $14\frac{1}{2}$ oz.—The average size of the letters is about $\frac{1}{8}$ ". The characters belong to the northern class of alphabets. They include the somewhat rare initial *ḍ*. in *ḍpāni*, line 14. In *kuryāti*, line 17, and in *kāryyāh*, line 16, we have further illustrations of the two methods of forming *r*, in combination with a following *y*, on which I have commented at page 94 above. The characters also include, in line 24, forms of the numerical symbols⁴ for 9 and 20.

¹ *bhōga*, *lit.* 'enjoyment, possession, government,' is a technical territorial term, probably of much the same purport as the *bhuktī* of other inscriptions.



² *Grāmika*, 'a villager, the headman of a village,' is a technical official title corresponding to the modern Kanarese *Gauḍa* and Marāṭhī *Pāḷū*.

³ See page 93 above, and note 3. ⁴ As regards the symbol for 9, see page 110 above, note 2.

A — Bhamburda Pillar Inscriptions of the Maharajas Hastin and Sarvanatha.



B — Khash Plates of the Maharaja Samkshobha.—The Year 209



—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 18 to 23, the inscription is in prose throughout. From a linguistic point of view, we have to notice in *hāritaka*, line 13, the affix *ka*, on which I have commented at page 69 above. — In respect of orthography, we have to notice (1) the use of *b* for *v*, in *sambatsara*, line 3; and (2) the occasional use of *v* for *b*, in *avda*, line 1; *vrdhmana*, line 7; and *vahubhih*, line 19.

The inscription is one of the **Parivrājaka Mahārāja Samkshōbha**. It is dated, in words, "in the enjoyment of sovereignty by the Gupta kings," in the year two hundred and nine (A.D. 528-29), in the Mahā-Aśvayuja *samvatsara*, on the thirteenth lunar day of the bright fortnight of the month Chaitra (March-April); and at the end, in numerical symbols, the date is given again as the twenty-ninth solar day, without any specification of the fortnight, of the same month Chaitra.¹ Judging by the opening invocation of the god Vishnu, under the name of Vāsudēva, it is a Vaishnava inscription. And the object of it is to record the grant, by the **Mahārāja Samkshōbha**, at the request of a certain person named **Chhōdugōmin**, of the village of **Ōpāni** to a temple of the goddess **Pishtapurī**,²—apparently some local form of Lakshmi, the wife of Vishnu.³

One point of importance in this inscription is, that it mentions the **Mahārāja Hastin** as governing the kingdom of **Ḍabhālā**, or possibly Ḍahālā, that had come to him by inheritance, together with all the country included in the **eighteen forest kingdoms**. I cannot identify these eighteen forest kingdoms.⁴ But, in **Ḍabhālā** or Ḍahālā, we have

¹ On the extreme importance of this double record, see page 107 above, note 1.

² Through his identification of *Pishtapura* with the place that he writes 'Pithaora,' and which is entered in maps as 'Pataora' and 'Puttoura,' nine miles north of *Uchchaharā*, Gen. Cunningham (*Archæol. Surv. Ind.* Vol. IX p. 10) identified this goddess *Pishtapurī* with the local goddess *Pataindēvī* of this 'Pithaora.' But this identification will not hold good, if only for the reason that 'Pithaora' is in reality *Pataurā*, probably from *pītri-pura*, 'the town of deceased ancestors'—*Pataurā* and *Pitaurā*, in passing, are evidently common names in that part of the country; as the maps shew 'Patourā,' 'Pitoura,' 'Patora,' and 'Pithoura,' respectively 29 miles west by a little north, 18 miles west, 13 miles north-west, and 24 miles north-west, of *Uchchaharā*.—Of *Pishtapura* we have already had an earlier mention in line 19 of the *Allahābād* pillar inscription, No. 1, page 7 above, as the capital of a king named *Mahendra*, who was conquered by *Samudragupta*, in the *dakshināpatha* or 'region of the south.' And we have another later mention of it, as being conquered by the Western *Chalukya* king *Pulikēsin II.*, in line 13 of the *Aihoḷe Mēguṭi* inscription of *Śaka-Samvat* 556 or A.D. 634-35 (*Ind. Ant.* Vol. VIII pp. 242, 245). It is the modern *Pittāpuram*, the 'Pithāpur and Pittāpooram' of maps, &c. (*Indian Atlas Sheet No. 94*; Lat. 17° 6' N., Long. 82° 18' E.), twelve miles north by east of 'Coconada' in the *Gōdāvarī* District in the *Madras Presidency*. It is the chief town of a *Zamindārī*, or Estate of the same name; and the remains at it shew that it is a place of considerable antiquity (see *Sewell in Lists of Antiquities, Madras*, Vol. I. p. 23 f.)—The *Pishtapurī* of this inscription must be a local form of some more famous and original goddess at *Pishtapura* itself. She is mentioned again, under the slightly different name of *Pishtapurikādēvī*, in line 12 of No. 29 below, Plate xix A, and in line 11 of No. 31 below, Plate xx.; and the latter passage shews that her local shrine was at a place named *Mānapura*, which may perhaps be the modern 'Manpor, Manpora, and Mānpur,' of maps about forty-seven miles towards the south-east from *Uchchaharā*.

³ Thus seems to be shewn (1) by the general Vaishnava tendency of the present inscription; and (2) by the fact that,—whereas in the year 177 the village of *Dhāvashandikā* was allotted by the *Mahārājā Jayanātha* for the purposes of a temple of the god Vishnu, under the name of *Bhagavat* or the Divine One (No. 27 below, Plate xvii.),—subsequently half of this same village was set apart, by a grant of the *Mahārājā Śarvanātha*, for the purposes of a temple of the goddess *Pishtapurikādēvī* (No. 29 below, Plate xix A.)

⁴ See page 13 above, note 7.

undoubtedly the older form of **Dāhala**, Dāhāla, Dahāla, or Dahalā, which seems to represent the modern **Bundēlkhaṇḍ**, and which was in later times a province of the Haihayas or Kalachuris of Tripura near Jabalpur, whose original capital was Kālāñjara in Bundēlkhaṇḍ. This, therefore, is another item of evidence connecting the Parivrājaka *Mahārājyas* with this part of the country.¹

TEXT.²

First Plate.

- 1 Ōm Namō bhagavatē Vāsudēvāya || Svasti Nav-ōttarē=vda(bda)-śata-dvayē
Gupta-nripa-r[ā*]jya-bhuktau
- 2 śrīmati pravarddhamāna-vijaya-rājyē Mah-Āśvayuja-sa[rn*]vatsarē Chaitra-māsa-
sukla-
- 3 paksha-trayōdaśy[A*]m=asyām sarnba(va)tsara-māsa-divasa-pūrvvayā[rn*]³ [1*]
Chaturddaśa-vidyāsthāna-vidi-
- 4 ta-paramārthasya Kapilasy=[ai*]va mah-arshēḥ sarvva-tat[t*]va-jñasya
Bharadvāja-sagōtrasya nripa-
- 5 pi⁴parivrājaka-**Susarmmaṇah** kul-ōtpannēna mahārāja-śrī-**Dēvādhyā**-putra-
pranaptrā mahārā-
- 6 ja⁵-śrī-**Prabhāñjana**-pranaptrā mahārāja-śrī-**Dāmōdara**-naptrā gō-sahasra-
hasty-aśva-hirany-ānēka-
- 7 bhūmi-pradasya guru-pitri-mātri-pūjā-tatparasy-ātyanta-dēva-vrā(brā)hmaṇa-
bhaktasy-ānēka-samara-
- 8 śata-vijayinah s-**ashtādas-ātavi-rājy**-abhyantaram **Dabhā(Phā)lā**-rājam-
anvay-āgatam samaḍi⁶
- 9 pālayipnō(shnō)r=anēka-guṇa-vikhyāta-yaśasō mahārāja-grī(śrī)-**Hastinaḥ**
sutēna
- 10 varṇ-āśrama-dharmma-sthāpanā-niratēna paramabhāgavatēn-ātyanta-pitri-
bhaktēna sva-varṇ-
- 11 ś-āmōdakarēṇa mahārāja-śrī-**Sarkshōbhēna(ṇa)** mātāpitrōr-ātmanas-cha
puny-ābhi-
- 12 viriddhaya⁷ **Chhōḍugōmi**-vijñāptyā tam-ēva cha sva[r*]gga-sōpāna-pamktim-
ārōpaya-

Second Plate.

- 13 tā bhagava⁸tyāḥ Pishtapuryāḥ kārītaka-dēvakulē va(ba)li-charu-sat[t*]r-
ōpayō-

¹ It is perhaps worth mentioning, that there is in this neighbourhood a station on the Allahābād-Jabalpur railway, called Dabhaurā (the 'Dabhura' and 'Daboora' of maps), about fourteen miles east of Māñikpur, and fifty miles east by north of Kālāñjara

² From the original plates.

³ Supply *isthan*.

⁴ Read *nripatis*.—In the second syllable, first *t* was engraved, and then it was corrected into *pa*.

⁵ This *ja* was first omitted, and then inserted in the margin of the plate.

⁶ Some correction or other is required here; but it is not apparent what was intended; possibly, however, *samyak*, *sampads*, or *sapadi*. I do not suggest *samadhipālayishnōr*, because I cannot find any authority for the composition of *sam* and *adhi* with *pā*, 'protect'.—In the third syllable, *dī* was certainly engraved; but the *i* may perhaps have been cancelled.

⁷ Read *Abhivṛiddhaya*.

⁸ The mark over this *va* is only a fault or rust-hole in the copper. There are several other similar faults or rust-holes in these two plates; e.g. after *sy-ārddham* in line 15.

- 14 g-ārthaḥ(m) khanda-sphuṭita-saṁskār-ārthañ=cha **Maṇināga-pēthē** **Opāni-**
grāma-
- 15 sy-ārdhana. chōra-drōhaka-varjjah(m) tāmra-śāsanēn-ātisriṣṭam [1*] tad-
asmat-kul-ōtthau(tthai)ḥ ma-
- 16 t-pādapiṇḍ-ōpajivibhir=vvā kālāntarēshv=api na vyāghātaḥ kāryyaḥ [1*]
ēvam-ājñā-
- 17 pta¹ yō=nyatūā kuryāt=tam=aham dēhāntara-gatō=pi mahat=āvadhyanēna
nirddahēyam [11*]
- 18 Uktar² cha bhagavatā param-arshipā vēda-vyāsena Vyāsēnaḥ³ [1*]
Pūrvva⁴-dattām dvijātibhyō
- 19 yatnād=raksha Yudhishthirah⁴ mahim=mahimatā[m*] śrēṣṭha dānāch-
chhrēyō=nupālanah(m) [11*] Va(ba)hubhiḥ
- 20 vasudhā bhuktā rājabis=Sagar-ādibhiḥ yasya vasya yadā bhūmis-
tasya tasya tadā
- 21 phalam [11*] Shashṭim varsha-sahasrāni svarggē mōdati bhūmi-dah
ākshēptā ch=ānumantā cha tāny-ē-
- 22 va narakē vasēt [11*] Bhūmi⁵-pradānān=nā(na) param pradānam dānād-
viśiṣṭam paripālan=chha⁶
- 23 sarvvē=tisriṣṭā[m*] paripālya bhūmi[m*] nripā Nṛig-ādyas=tridivam
prapannāḥ || Likhitam⁷=cha
- 24 Jivita-naptrā Bhujangādasa-putr-**Ēśvaradāsen-ēti** [1*] Sva-mukh-ājñā [1*]
Chaitra di 20 9 [11*]

TRANSLATION.

Om! Reverence to the divine (god) Vāsudēva! Hail! In two centuries of years, increased by nine; in the enjoyment of sovereignty by the **Gupta kings**; in the glorious augmenting and victorious reign; in the Mahā-Aśvayuja *samvatsara*; on the thirteenth lunar day of the bright fortnight of the month Chaitra,—on this (*lunar day*), (*specified*) as above by the *samvatsara* and month and day;

(Line 3.)—By the *Mahārāja*, the illustrious **Saṁkshōbha**,—who is born in the family of the kingly ascetic **Sūsarman**, who had learned the whole truth of the fourteen sections of science;¹ who was a great sage, (*being*) indeed (*an incarnation of*) Kapila; who knew all the first principles; (*and*) who was of the **Bharadvāja gōtra**;—who is the great-grandson of the son of the *Mahārāja*, the illustrious **Dēvādhyā**;—who is the great-grandson of the *Mahārāja*, the illustrious **Prabhañjana**;—who is the grandson of the *Mahārāja*, the illustrious **Dāmōdara**;—who is the son of the *Mahārāja*, the illustrious **Hastin**, who was the giver of thousands of cows, and elephants, and horses, and

¹ Read either *ājñaptē*, or *ājñaptā*.² Read *vyāsena*.³ Metre, Ślōka (Anuṣṭubh); and in the following two verses.⁴ Read *yudhishthira*.⁵ Metre, Upajāti of Iṅdravajrā and Upēndravajrā.⁶ Read *paripālanā=cha*.⁷ Read *likhitam*.—And supply *śāsanam*.⁸ *chaturdāsa-vidyāstikha*; viz. the four Vēdas, the six Vēdāngas, the Purāṇas, the Mīmāṁsā system of philosophy, the Nyāya system, and Dharma, or law.

gold, and many lands; who was earnest in paying respect to (*his*) spiritual preceptor and (*his*) father and mother; who was extremely devoted to the gods and Brāhmins; who was victorious in many hundreds of battles; who sought to govern properly the kingdom of **Dabhāla**,¹ which had come (*to him*) by inheritance, together with (*all the country*) included in the **eighteen forest kingdoms**; (*and*) whose fame was renowned through many good qualities;—who is intent upon establishing the religious duties of the castes and the different periods of life;—who is a most devout worshipper of the Divine One;—who is extremely devoted to (*his*) ancestors;—(*and*) who causes the happiness of his own race,—

(L. 11.)—(*By him*),—for the purpose of increasing the religious merit of (*his*) parents and of himself,—at the request of **Chhōḍugōmin**, and (*with the object of*) causing him to ascend the steps of the ladder that leads to heaven,—half of the village of **Ōpāni**, in the **Maṇināga pēṭha**,² is granted by a copper-charter, with the exception of (*the right to fines imposed on*) thieves and mischief-doers, for the purpose of observing the *bali*, *charu*, and *sattra*,³ at the temple, which (*he*) has caused to be built, of the divine (goddess) **Pishtapuri**, and for the purpose of renewing whatever may become broken or torn.

(L. 15.)—Therefore, even in future times, no obstacle (*to the enjoyment of this grant*) is to be caused by those who are born in Our family, or by my feudatories. This injunction having been given, he who behaves otherwise,—him I will consume with a great contempt, even when I have passed into another body

(L. 18.)—And it has been said by the venerable supreme sage, Vyāsa, the arranger of the Vēdas,—“O Yudhishtira, best of kings, carefully preserve land that has previously been given to the twice-born; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant! The earth has been enjoyed by many kings, commencing with **Sagara**; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents to (*an act of confiscation*), shall dwell for the same number of years in hell! (*There is*) no gift better than a gift of land, and the preservation (*of a grant*) (*is*) better than making a grant; all kings, commencing with **Nṛiga**, have attained heaven, (*by*) preserving land that had been granted!”

(L. 23.)—And (*this charter*) has been written by **Isvaradāsa**, the grandson of **Jlṛita**, (*and*) the son of **Bhujamgadāsa**. The order (*is that*) of his own⁴ mouth. (*The month*) **Chaitra**; the day 20 (*and*) 0.

¹ Or possibly **Dabhāla**, but the second syllable, though rather badly formed, seems to be *dhā*, rather than *hā*.

² *pēṭha*, a technical territorial term, represented in modern **Marāṭhī** by *pēṭā*. Another form of it, *venṭha*, occurs in line 30-31 of the **Harihar** grant of **Bukkarāya** of **Sālivāhana-Sāka 1276** (*Your. Bo. Br. R. As. Soc.* Vol. XII. p. 347); and we also have *venṭheya* or *penṭheya* in line 24 of the **Harihar** inscription of **Achyutarāya** of **Sālivāhana-Sāka 1460** (*Ind. Ant.* Vol. IV. p. 331).

³ *bali* is the offering of ghee, grain, rice, &c., to the gods and all creatures of every description; *charu*, the oblation of rice, barley, and pulse boiled with butter and milk, for the deceased ancestors; and *sattra*, the giving of alms and refuge. They are three of the *pañca-mahāyajña*, or ‘five great sacrifices,’ which are usually (*e.g.* in line 27 f. of the **Māliya** grant of the **Mahārāja Dharasēna II.**, No. 28 below, Plate xxiv) enumerated as *bali*, *charu*, *vaiśvadeva* (the offering to all deities), *agnihotra* (see page 71 above, note 8), and *atithi* (hospitality; the *sattra* of the present inscription).—The *sattra*-rite was the special object of the *sattra*, or ‘charitable hall or almshouse,’ which is mentioned for instance, in No. 7, line 6, page 38 above.

⁴ **Samkshōbha**’s. These words imply that he employed no *Dātaka* to convey the orders to the local officials, but gave them in person; see page 100 above, note 7.

No. 26; PLATE XVI.

KARITALAI COPPER-PLATE INSCRIPTION OF THE
MAHARAJA JAYANATHA.

THE YEAR 174.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. p. 12. f. No. 3, where he published a translation of it, with a lithograph of the two passages containing the date (*id.* Plate iv. No. 5),—is from some copper-plates that were found, about 1850, in a small receptacle inside a ruined temple of the god Vishṇu, in his incarnation as the Boar, at Kāritalāi,¹ a village about twenty-three miles north-east of Muḍwārā,² the chief town of the Muḍwārā Tahsil or Sub-Division of the Jabalpur District in the Central Provinces. I obtained the original plates, for examination, from the possession of General Cunningham.

The plates, which are inscribed on one side only, are two in number, the first measuring about $9\frac{1}{8}$ " by $6\frac{3}{8}$ ", and the second $9\frac{1}{8}$ " by $6\frac{1}{8}$ ". The edges of them are here and there fashioned slightly thicker than the inscribed surfaces, with corresponding depressions inside them, so as to serve as rims to protect the writing; and the inscription is in a state of excellent preservation throughout. The plates are fairly thick; but the letters are deep, and shew through on the backs, so clearly that in many places they can be read there. The engraving is good; but the interiors of many of the letters shew marks of the working of the engraver's tool.—In the upper part³ of each plate, there is a hole for a ring to connect them. But the ring, and the seal attached to it, are not forthcoming.—The weight of the two plates is 2 lbs. 7 oz.—The average size of the letters is about $\frac{1}{4}$ ". The characters belong to the northern class of alphabets; and the present inscription, with the five that follow, and with No. 22 above, Plate xiii., No. 24, Plate xvA., and No. 25, Plate xvB., illustrates what may be called the standard alphabet, with northern characteristics, of Central India, from towards the end of the fifth to the middle of the sixth century A.D. The characters include the rather rare initial *ḍ*, in *ḍghadēva*, line 1, and the equally rare *jh*, in *ajjhitaḍḍoṭ*, line 5; also, in lines 24 and 25, forms of the numerical symbols for 4, 10, 70, and 100.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 14 to 21, the inscription is in prose throughout. From a linguistic point of view we have to notice, in *uṣṭadyamānaka*, line 10 f., the affix *ka*, which I have commented on at page 69 above.—In respect of orthography, we have to notice (1) the use of the dental nasal, instead of the *anusvāra*, before *ṣ*, in *vāṣa*, line 10; (2) the constant doubling of *ṣ*, in conjunction with a following *r*, e.g. in *puṣṣra*, line 2; *saḡṣṣṭra*, line 7; and *tṣṣṭā*, line 20; and (3) the occasional use of *ḍ* for *v*, in *sambatsara*, line 21, and *sambat*, line 24.

The inscription is one of the *Mahārāja Jayanātha*; and the charter recorded in it is issued from the city or hill called *Uchchakalpa*.⁴ The date of the writing of the

¹The 'Karitalai and Kareetullae' of maps. Indian Atlas, Sheet No. 89. Lat. $24^{\circ} 3' N.$; Long. $80^{\circ} 46' E.$

²The 'Moorwari, Moorwarra, and Murwāra,' of maps, &c.

³See page 101 above, note 2.

⁴The 'literal meaning,' that which is but little short of being a high place,' points perhaps rather to the name being properly that of a hill; but of course with a town on it.

charter is given, in both words and numerical symbols, as the year one hundred and seventy-four, and the fourteenth day, without any specification of the fortnight, of the month Āṣāḍha (June-July). There is no information given as to the era. But the Bhumarā pillar inscripior. of the *Mahārājas* Hastin and Śarvanātha, No. 24 above, page 110, shews that the Parivrājaka *Mahārājas* and the *Mahārājas* of Uchchakalpa were contemporaries; and, therefore, that the era of the latter must be the same with that of the former, which is distinctly indicated as being the **Gupta** era. And the result, accordingly, for the present date, is A.D. 493-94. The inscription is non-sectarian; the object of it being only to record the grant, by the *Mahārāja Jayanātha*, to a Brāhmaṇ, of the village of **Chhandāpallikā** in the **Nāgadēya**¹ *santaka*.²

TEXT.³

First Plate.

- 1 Om Svasti **Uchchakalpān**-mahārāja-**Ūghatēvas**-tasya puttras=tat-pād-
ānudhyātō mahā-
- 2 dēvyām. **Kumāradēvyām**-utpannō mahārāja-**Kumāradēvas**-tasya puttras-
tat-pād-[ā*]nudhyātē(tō)
- 3 mahadēvyām **Jayasvāmīnyām**-utpannō mah[ā*]rāja-**Jayasvāmī** tasya
puttras=tat-pād-[ā*]nudhyātē(tō)
- 4 mah[ā*]dēvyā[r̄m*] **Rāmadēvyām**-utpannō mahārāja-**Vy[ā*]ghras**-tasya
puttras=tat-pād-ānudhyātō mahā-
- 5 dēvyām-**Ajjhitadēvyām**-utpannō mahārāja-**Jayanāthah** kusall **Nāgadēya**-
santaka-**Chha**-
- 6 **nī āpallikāyām** brāhmaṇ-ādin=kuṭumbīnaḥ kārūkāmś=cha samājñāpayati [I*]
Vadatarām=bō⁴-stu
- 7 yath=aisha grāmō mayā sva-puṣy-ābhivṛddhavē Kanvasagōttra-Vāja-
sanēyaMādhyā-
- 8 ndina-brāhmaṇa-Mittrasvāmīnaḥ s-ōdraṅgaḥ s-ōparikaraḥ a-chāṭa-bhaṭa-
prāvēśyaḥ
- 9 chōra-varjītō=tisrishtas=Tē yūyam=asya samuchita-bhāgabhōga-kara-pratyāy-
ōpa-
- 10 nayam kaka(ri)shyatha ājñā-sravana-vidhēyās=cha bhavishyatha [I*] Yē
ch=āsmad-vanś-ōtpadya-
- 11 mānaka-rājānas=tair-iyam dattir=nna vilōpy-ānumōdanīyā samuchita-rāj-ā-
- 12 bhāvya-kara-pratyāyā na grāhyāḥ [I*] Yaś=ch=aimām dattim lōpayēt
sa pafichabhiḥ

¹ As regards Gen. Cunningham's desire to identify Nāgadēya with the modern Nāgaodb, see page 94 above, note 1.

² *santaka* is a technical territorial term, the exact meaning of which is not apparent. It is perhaps identical in etymology with the Prākṛit *santaka*, 'belonging to,' in *asmat-santaka*, 'belonging to Us,' which occurs in the Vākātaka inscriptions, No. 55 below, line 21, and No. 56, line 23.—In No. 29 below, line 7, we have the slightly different form, as a territorial term, of *santika*.

³ From the original plates.

⁴ Read *rāj-angha*.

Read *vidīlam* vñ.

Second Plate.

- 13 mahāpātakair-upapātakaiś=cha sahyukta[ḥ*] syān(d)=Uktaṁ cha Mahā-
bhāratē bhagavatā
- 14 Vyāsēna [I*] Sva¹-dattām para-dattām vā yatnād-raksha Yudhishthira
mahīm-mahīmatām śrēṣṭha
- 15 dānāc=chhrēyō=nupālanam [II*] Bahubhir=vvasudhā bhuktā rājabhīḥ
Sagar-ādibhīḥ yasya
- 16 yasya yadā bhūmis=tasya tasya tadā phalaṁ [II*] Prāyēṇa hi
narēndrānām vidyatē n=ā-
- 17 śubhā gatih pūyāntē tē tu satataṁ prayacnchhantō vasun-
dharām [II*] Shashti-varsha-sahasrā-
- 18 ni svarggē mōdati bhūmi-daḥ āchchhētā ch-ānumantā cha tāny-ēva
narakē vasēt [II*]
- 19 Āsphōṭala(ya)nti pitarah pravalganti pitāmahaḥ, bhōmi-dō=sma[*]-kulē
jātaḥ sa nō(nah)
- 20 ttrātā bhavishyati [II*] Sarvva-sasya-samriddhān-tu yō harēta vasun-
dharām śva-vishthāyām kṛimi-
- 21 r=bhūtvā pitribhis=saha majjati I(II) Samba(mva)tsara-ga(śa)tē chatuḥ-
saptatē Āshāḍha-māsa-
- 22 sya chaturdāsamē divasē asyām divasa-purvāyām² likhitam³ mayā
bhōgika-Rājyi-
- 23 l-āmātya-naptri-bhōgika-Dhruvadatta-puttra-bhōgika-Guñjakirttinā [I*] Dūtak-
ōparika-⁴
- 24 dīkshita-grihapati-sthapatīsamrāt-**Chchha(chha)rvvadatta**, iti || Samba(mva)t
100 70 4 Āshā-
- 25 dha di 10 4 I(II)

TRANSLATION.

Om! Hail! From (the city or hill of) **Uchchakalpa**,¹—(There was) the **Mahārāja Ōghadēva**. His son, who meditated on his feet, (was) the **Mahārāja Kumārādēva**, begotten on the **Mahādēvī Kumārādēvī**. His son, who meditated on his feet, (was) the **Mahārāja Jayasvāmin**, begotten on the **Mahādēvī Jayasvāminī**. His son, who meditated on his feet, (was) the **Mahārāja Vyāghra**, begotten on the **Mahādēvī Rāmadēvī**.

(Line 4.)—His son, who meditates on his feet, the **Mahārāja Jayanātha**,—begotten on the **Mahādēvī Ajjhitadēvī**,²—being in good health,³ issues a command to the

¹ Metre, Ślōka (Anushṭubh); and in the following five verses

² Supply *tithau*.

³ Supply *śśsanam*.

⁴ Read *dūtaka uparika*.—*Dūtaka* should be a word by itself, in the nominative singular; not in composition with *uparika*.

⁵ The context is in line 5 f.,—“the **Mahārāja Jayanātha** issues a command.” The genealogy that intervenes, is by way of a parenthesis.

⁶ See page 16 above, note 2.

⁷ The first part of this name, *ajjhitā*, must be a Prākṛit word. There might be some temptation to correct it into the Sanskrit *ujjhita*; but there is not the slightest approach to the vowel *u* below the final *m* of the preceding word *dēvyām*, in any of the passages in which it occurs.—Gen Cunningham read the name as *Majjhitadēvī*; but this is incorrect, as there is no trace whatever of an *anusvāra* over the *v* of *dēvyām*, in any of the passages.—We have another Prākṛit name in *ljjādēvī* in line 5 of the *Dēvī-Baraṇṣī* inscription of Jīvatigupta II., No. 46 below, Plate xxix B.

⁸ *hūsalin*; a technical expression of constant use in charters.

cultivators, beginning with the Brāhmapas, and to the artisans, at (the village of) **Chhandāpallikā** in the **Nāgādēya santaka** :—

(L. 6.)—“ Be it known to you that, for the purpose of increasing my own religious merit, this village is granted by me,—with the *udranga* and the *uparikara*, (*and with the privilege that it is*) not to be entered by the irregular or the regular troops, (*but*) with the exception of (*the right to fines imposed on*) thieves,—to the Brāhman Mitrasvāmin, of the *Kānva gōtra* and the *Vājasaneyā-Mādhyāmdina (śākhā)*.

(L. 9.)—“ You yourselves shall render to him the offering of the tribute of the customary royalties¹ and taxes, and shall be obedient to (*his*) commands.

(L. 10.)—“ And those kings who shall be born in Our lineage,—by them this grant should not be confiscated, (*but*) should be assented to ; (*and*) the tribute of the taxes which by custom should not belong to the king, should not be taken.

(L. 12.)—“ And whosoever may confiscate this grant,—he shall become investea with (*the guilt of*) the five great sins and the minor sins ”

(L. 13.)—And it has been said in the *Mahābhārata* by the venerable *Vyāsa*,—‘ O *Yudhishtira*, best of kings, carefully preserve land that has been given, whether by thyself or by another ; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant ! The earth has been enjoyed by many kings, commencing with *Sagara*, whosoever at any time possesses the earth, to him belongs at that time, the reward (*of this grant that is now made, if he continue it*) ! As a rule, indeed, no inauspicious condition is experienced by kings, but they at once purified for ever, when they bestow land ! The giver of land enjoys happiness in heaven for sixty thousand years ; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell ! Fathers (*in the world of the dead*) clap their hands upon their arms, (*and*) grandfathers leap (*from joy*), (*saying*)—‘ A giver of land has been born in our family, he shall become our deliverer ’ ! He who confiscates land, rich in all (*kinds of*) grains, (*that has been granted*),—he becomes a worm in the ordure of a dog, and sinks (*into hell*), together with (*his*) ancestors ”

(L. 21.)—In a century of years, together with the seventy-fourth (*year*), on the fourteenth day of the month *Āshādha*,—on this (*lunar day*), (*specified*) as above by the day (*&c.*)²—(*this charter*) has been written by me, the *Bhōgika Guṇjakiritti*, the grandson of the *Bhōgika*, the *Amḍtya Rājyila*, and the son of the *Bhōgika Dhruvadatta*. The *Dūtaka* (*is*) the *Uparika*, *Dikshita*,³ householder,⁴ and chief of architects,⁵ **Śarvadatta**.

(L. 24.)—The year 100 (*and*) 70 (*and*) 4, (the month) *Āshādha*, the day 10 (*and*) 4.

¹ *bhāgabhōga* ; *lit.* ‘ enjoyment or snares. My rendering is on the authority of Monier Williams’ explanation of *bhāga-bhu*, in his Sanskrit Dictionary, by ‘ enjoying taxes, a king, sovereign ’

² See page 97 above, note 1.

³ *Dikshita* ; ‘ one who has received initiation, or by whom the preparatory ceremonies have been observed.’

⁴ *grīhapati* ; ‘ the master of a house, a householder ; a man of the second class, who, having finished his studies, is married and settled.’

⁵ *sthapati-samrāj* ; the meaning, however, is not quite certain. Perhaps it may mean ‘ superintendent of the attendants or the women’s apartments.’

No. 27; PLATE XVII.

KHOH COPPER-PLATE INSCRIPTION OF THE
MAHARAJA JAYANATHA.

THE YEAR 177.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archaeol. Surv. Ind.* Vol. IX. p. 13, No. 4, where he published a partial translation of it, with a lithograph of the passage containing the date (*id.* Pl. iv. No. 6),—is from another set of copper-plates that appear to have been found somewhere in the valley near the village of **Khôh**,¹ in the Nâgaudh State in the Baghêlkhând division of Central India. I obtained the original plates, for examination, from the possession of the Râjâ of Nâgaudh, through the kindness of Major D. W. K. Barr.

The **plates**, which are inscribed on one side only, are two in number, the first measuring about 9½" by 6½", and the second 9½" by 6½". They are quite smooth, the edges having been neither fashioned thicker, nor raised into rims; the inscription, however, is in a state of very good preservation throughout. The plates are fairly thick; but the letters here and there shew through faintly on the backs of them. The engraving is good, but shews, as usual, marks of the working of the engraver's tool throughout.—In the upper part of each plate, there is a hole for a ring to connect them. But the ring and seal are not forthcoming.—The **weight** of the two plates is 3 lbs. 11 oz.—The average **size** of the letters is about ½". The **characters** belong to the northern class of alphabets, and are of the same type with those of the preceding inscription of the same *Mahârâja* of the year 174, No. 26 above, Plate xvi. In *rdjânas*, line 12, the vowel *d* is attached, in a very unusual way, to the top stroke of the *j*, instead of to the centre of it, as in *rôjâ* (for *rdja*), line 13; this occurs occasionally in other inscriptions also; and it is difficult to say whether it is an authorized variety of practice, or only a mistake on the part of the engraver. The letter *r*, in combination with a following consonant, is formed uniformly above the top line of writing. The characters include the rather rare *jh*, in *ajjhita*, line 5.—The **language** is Sanskrit; and the entire inscription is in prose, except for the benedictive and imprecatory verses in lines 16 to 20. From a linguistic point of view, we have to notice (1) the use of the Prâkrit word *phusta*, in line 10; and (2) in *pratishthâpitaka*, line 9, and *uspadyamânaka*, line 12, the affix *ka*, which I have commented on at page 69 above.—In respect of **orthography**, we have to notice (1) the doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *kkramâna*, *puttra*, and *prapautro* line 9; and (2) the use of *v* for *b*, in *vahî*, line 10.

The **inscription** is one of the *Mahârâja Jayanâtha*; and the charter recorded in it is issued from the city or hill called **Uchchakalpa**. The date of the writing of the charter is given, in words, as the year one hundred and seventy-seven (A.D. 496-97), and the twenty-second day, without any specification of the fortnight, of the month Chaitra (March-April). It is a Vaishnavâ inscription. And the object of it is to record the grant, by the *Mahârâja Jayanâtha*, to some Brâhmanç, of the village of **Dhava-shandikâ**, for the purposes of a temple of the god Vishnu, under the name of Bhagavat or the Divine One. established by them there.

¹ See page 93 above, and note 3.

TEXT.¹

First Plate.

- 1 Svasty-Uchchakalpān-mahārāj-Aughadēvas-tasya puttras-tat-pād-ānudhyātō mahā-
 2 dēvyām Kumārād[é°]vyām-utpannō mahārāja-Kumārādēvas-tasya puttras-
 tat-p[ā°]d-ānudhyātō
 3 mahādēvyām Jayasvāminyām-utpannō mahārāja-Jayasvāmi(mi) tasya
 puttras-tat-pād-ānudhyātō
 4 mahādēvyām Rāmadēvyām-utpannō mahārāja-Vyāghras-tasya puttras-
 tat-p[ā°]d-ānudhyātō mahā-
 5 dēvy[ā°]m-Ajjhitadēvyām-utpannō mahārāja-Jayanāthaḥ kuśali(II)
 Dhavashaṇḍikāyā[m°] vrā(brā)hma-
 6 ṇ-ādīn-kuṭumvi(mbi)naḥ kārūkāmś-cha samājñāpayati [I°] Viditam vō-ṣtu
 yath-aisha grāmō may-ā-
 7 chandr-ārka-samakālikah Śāsātānēya-Sarvvavāḍha-divira-tatputtra-bhāgavata-
 Gaṅga-ta[t°]puttra-
 8 Rankabḍṭa-Aja°garadās[ā°]nām sva-puṇy-ābhividdhayē bhagavat-pād[é°]bhyaḥ
 dēv-[ā°]grāhārō-tisṛiṣṭa[h°] [I°]
 9 ēbhiś-cha-ātra pratishṭhāpitaka-bhagavat-pādānām puttra-[pautra°]-prapauttra-
 tatputtr-āti(di)-kkramēṇa khaṇḍa-
 10 phuṭṭa°-pratisamśk[ā°]r[ēpa°] va(ba)li-charu-sattra-pravarttan-ādy-anuṣṭhānēna
 cha sva-puṇy-ābhividdhiḥ
 11 kartavyā [II°] Tē yūyam-ēśhām samuchita-śu[I°]ka-bhāgabhogā-kara-hiraṇy-
 ādi-pratyāy-ōpanayam°
 12 karishyath-ājñā-śravaṇa-vidhēyās-cha bhavishyatha [I°] Yē ch-āsmad-
 vams-ōtpadyamānaka-rājānas-tair-iyam
 13 datti[r°]-nna vilōpyā anumōdan[t°]yā samuchita-rō(rā)j-ābhāvya-kara-
 pratyāyā na grāhyā[h°]

Second Plate.

- 14 chōra-daṇḍa-varjyam I kāl-ānukālām cha pratipālantiya [I°] Yaś-cha-
 aimām dattim lōpayēt-sa pa[rh°]cha-
 15 bhir-mmahāpātakair-upapātakais-cha samyuktaḥ sy[ād°] [II°] Uktam cha
 Mahābhāratē bhagavatā vēda-vyāsēna
 16 Vyāsēna [I°] Sva°-dattām para-dattām-vā yatnād-raksha Yudhisṭhira
 mah[rh°] mahīmātām śrēṣṭha dānāch-chhreyō-nupāla-
 17 nam [II°] Prāyēna hi narēndrāpām vidyatē n-ā-śubhā gatiḥ
 pōyattē(ntē) tē tu satata[rh°] prayachchhantō vasundha-
 18 rā[rh°] II Shashṭim varsha-sahamsrāpi° svarggē mōdati bhūmi-daḥ I
 āchchhētā ch-ānumantā cha tāny-[é°]va narak[é°] vasēt [II°]

¹ From the original plates.² Read *bhī-śya*.³ Read *spañjita*. — *Phuṭṭa* is a regular Prakṛit formation; but is not admissible in a Sanskrit passage.⁴ This *anurodra* is so high above the *ya*, that it seems to have been omitted at first, and inserted subsequently, somewhat at random.

Metre. Ślōka (Anuṣṭubh); and in the following four verses.

⁵ Read *sahasraṇi*.

- 19 Bahubhir-vvasudhā bhuktā rājabhis-Sagar-ādibhiḥ | rya(ya)sya yasya
yadā bhūmis-tasya tasya tadā phalam [11*]
20 Sarvva-sasya-samjiddhān-[t*]u yō harēta vasundharā[rh*] | sa vishṭhāyām
krimi[r*]-bhūtvā pitṛibhiḥ saha majya(jja)tē [11*]
21 Samvatsara-śatē sapta-saptaty-u[ttā*]rē Chaittra-māsa-divasē dvā-
viṃśatimē likhitam¹ bhōgika-Varāhadinna-puttra-sāndhivigrahika-Gallunā | dūtaka-
22 mātya-naptrā bhōgika-Varāhadinna-puttra-sāndhivigrahika-Gallunā | dūtaka-
ōparika²-dikshita-griha-
23 pati-sthapatīsamraṭ-Chharvadvattāḥ || Yattr-āghātāḥ Dhānyavāhika-
pratyuddēśē garttā pāll cha |
24 Durggamaṇḍala-pradēśē pāll [1*] Suvarṇpakakshaka-pradēśē gōpatha-
śaraḥ ardhēna cha pāll [1*]
25 Āmuka-pradēśē garttā [1*] Dāramaṇḍala-pradēśrē(śē) pāll [1*] Vakra-
vaṇṣa-prāvēśya-maṇḍala-pradēśē pāll [1*]
26 grāmē yavat-kūpaṭṭ pravishṭā iti [11*]

TRANSLATION.

Hail! From Uchchakalpa;—(There was) the *Mahārāja Ūghadēva*. His son, who meditated on his feet, (was) the *Mahārāja Kumārādēva*, begotten on the *Mahādēvī Kumārādēvī*. His son, who meditated on his feet, (was) the *Mahārāja Jayasvāmīn*, begotten on the *Mahādēvī Jayasvāmīnī*. His son, who meditated on his feet, (was) the *Mahārāja Vyāghra*, begotten on the *Mahādēvī Rāmādēvī*.

(Line 4.)—His son, who meditates on his feet, the *Mahārāja Jayanātha*,—begotten on the *Mahādēvī Ajjhitādēvī*,—being in good health, issues a command to the cultivators, beginning with the Brāhmins, and to the artisans, at (the village of) *Dhavashapdikā* :—

(L. 6.)—“ Be it known to you that, for the purpose of increasing my own religious merit, (and) for the benefit of the feet of the Divine One,³ this village is granted by me, as an *agrakāra* of the god, to continue for the same time with the moon and the sun, to the *Divira*⁴ Sarvavāḍha, of the Śāsātānēya (*gōtra*) (?), and his son the *Bhḍgavata* Ganga, and his sons Raṅkabōṭa and Ajagarādāsa. And the increase of their own religious merit should be effected by the succession of (their) sons, [sons' sons*], sons of sons' sons, sons of the latter, &c., by repairing whatever may become broken or torn, and by attending to the

¹ Supply *ślokanam*.

² Read *phalgu*.—The name occurs again with the long vowel *ā* in the first syllable, in line 30 of No. 28 below, and line 11 of No. 30 below. But the correct form, with the short vowel *a*, occurs in line 28 of No. 31 below, page 137.

³ Read *āmtya-naptrā*. The syllables *mātya* are repeated by mistake.

⁴ Read *dātaka uparika*; see page 119 above, note 4.

⁵ i. e. “ for the benefit of the Divine One.”—Here, and in line 9 below, the words “ the feet ” are only used in accordance with the customary method of respectful mention. No reference is intended to any shrine containing ‘ foot-prints ’ of Vishnu, which would be denoted by the use of *padā*, not *śalā*.

⁶ *Divira* is a technical official title, explained by Dr. Bühler (*Ind. Ant.* Vol. VI. p. 10) as meaning ‘ a clerk, writer, or accountant,’ on the authority of a passage in the *Lōkaprahāra* of Kshēmēndra, which explains the details of written documents for the benefit of the *Diviras*.

maintenance of the *bas*, *charu*, *sattrā*, and other (*such rites*), of the feet of the Divine One, established here by these persons.

(L. 11.)—"You yourselves shall render to these persons the offering of the tribute of the customary duties, royalties, taxes, gold, &c., and shall be obedient to (*their*) commands.

(L. 12.)—"And those kings who shall be born in Our lineage,—by them this grant should not be confiscated, (*but*) should be assented to; (*and*), with the exception of fines imposed on thieves, the tribute of the taxes which by custom should not belong to the king, should not be taken; and (*this grant*) should be preserved from time to time.

(L. 14.)—"And whosoever may confiscate this grant,—he shall become invested with (*the guilt of*) the five great sins and the minor sins."

(L. 15.)—And it has been said in the *Mahābhārata* by the venerable Vyāsa, the arranger of the *Vēdas*,—"O Yudhishtīra, best of kings, carefully preserve land that has been given, whether by thyself or by another; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant! As a rule, indeed, no inauspicious condition is experienced by kings; but they are purified for ever, when they bestow land! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he ntinue it*)! He who confiscates land, rich in all (*kinds of*) grains, (*that has been granted*),—he becomes a worm in ordure, and sinks (*into hell*), together with his ancestors!"

(L. 21.)—In a century of years, increased by seventy-seven, on the twenty-second day of the month Chaitra, (*this charter*) has been written by the *Sādhivigrahika* Gallu, the grandson of the *Bhōgika*, the *Amātya* Phalgudatta,¹ (*and*) the son of the *Bhōgika* Varāhadinna.² The *Dūtaka* (*is*) the *Uparika*, *Dīkshita*, householder, and chief of architects,³ *Sārvadatta*.

(L. 23.)—The boundaries in this matter (*are*),—in the direction of *Dhānyavāhika*,⁴ a boundary-trench and a bridge;⁵—in the direction of *Durgamaṇḍala*, a

¹ See page 123 above, note 2.

² *dinna* is rather a rare word. But it occurs again (1) as the second part of a proper name, in Indradinna, a Jain teacher (*Ind. Ant.* Vol. XI. pp. 247, 251), and perhaps in Vkriddina, in line 25 of the *Māliya* grant of Dharasēna II., No. 38 below (where, however, it may be a name by itself); (2) as a proper name by itself, in line 9 of the *Nirmaṇḍ* grant of the *Mahāsāmanta* and *Mahārāja* Samudrasēna, No. 80 below, Plate xlv., and in the case of a Jain teacher (*Ind. Ant.* Vol. XI. pp. 247, 252); and (3) as the first component of the name of a village in Dinnāgrāma (*Monier Williams' Sanskrit Dictionary*, s. n.). Also, we have a village or town named Dinnāputra, either a mistake or a local variation for Dinnaputra, or more probably a mistake for Dinnāputra, in line 54 of one of the *Dhānik* grants of Śīlāditya V. (*Journ. Bo. Br. R. Ar. Soc.* Vol. XI. p. 345; and *Indian Inscriptions*, No. 15.)

³ *sthapati-samraj*; see page 120 above, note 5.

⁴ *Dhānyavāhika* must have been a very common village-name in those parts, as the maps give 'Danwai,' 'Dhanwahi' (three times), 'Dhunwahee,' and 'Dhunwai,' all within a distance of thirty-two miles from Uchaharā, on the south-east, south, and south-west.

⁵ *paṭṭ*; or 'a raised bank, dike, or causeway.'—This, also, if it did not occur five times in this passage, and in five different directions, might be taken as a village-name; since the maps give 'Pali,' thirty-seven miles north-west, and again seventy miles south by east, from Uchaharā.

Khob Plates of the Maharaja Jayanatha.—The Year 177.

1
 2
 4
 6
 8
 10
 12

14
 16
 18
 20
 22
 24
 26

bridge;—in the direction of **Suvarṇakakṣhaka**, (partly) the place where the reeds grow by the cattle-path,¹ and partly a bridge:—in the direction of **Āmuka**, a boundary-trench;—in the direction of **Dāramanḍala**, a bridge;—(and) in the direction of the district at the entrance of **Vakravana**, a bridge;—(then the boundaries) enter the village (again) at the well.

No. 28; PLATE XVIII.

KHOH COPPER-PLATE INSCRIPTION OF THE MAHARAJA SARVANATHA.

THE YEAR 193.

THIS inscription, which has not been previously brought to notice, is from another set of copper-plates that appear to have been found somewhere in the valley near the village of **Khôh**,² in the Nāgaudh State in the Baghêlkhand division of Central India. I obtained the original plates, for examination, in the possession of the Rājā of Nāgaudh, through the kindness of Major D. W. K. Barr.

The plates, which, so far as the inscription now published is concerned, are inscribed on one side only, are two in number, the first measuring about $7\frac{1}{2}$ " by $6\frac{1}{2}$ ", and the second, $7\frac{1}{4}$ " by $6\frac{1}{2}$ ". The edges of them are fashioned slightly thicker than the inscribed surfaces, with corresponding depressions inside them, so as to serve as rims to protect the writing; and the inscription is in a state of excellent preservation almost throughout. The plates are rather thick, and the letters, though fairly deep, do not shew through on the backs of them at all. The engraving is good; but, as usual, the interiors of the letters shew marks of the working of the engraver's tool throughout.—In the upper part of each plate, there is a hole for a ring to connect them. The ring is about $\frac{1}{8}$ " thick and $1\frac{1}{2}$ " in diameter. It had not been cut when the grant came under my notice; but one end of it had been forced out of the socket of the seal, so that it could be detached from the plates. It appears, however, to be the ring properly belonging to these plates. The seal, in which the ends of the ring are secured, is rectangular, about $1\frac{1}{8}$ " by $1\frac{1}{4}$ ". With the plates, it has been subjected to the action of fire, and has received considerably more injury than the plates. It can be seen, however, that it contains, in relief on a countersunk surface, at the top, Garuḍa, the bird-vehicle of Viṣṇu, with outstretched wings, just as on the copper-coins of Chandragupta II.; and below this, in two lines, the legend, very much damaged, *Mahārāja-Śa[ṛ]va[nā]tha*.—The weight of the two plates is 2 lbs. 4 oz., and of the ring and seal, 2½ oz.; total, 2 lbs. 6½ oz.—The average size of the letters is about $\frac{1}{4}$ ". The characters belong to the northern class of alphabets, and are of the same type with those of the Kāritalāl grant of the *Mahārāja Jayanātha* of the year 174, No. 26 above, page 117 ff., and Plate xvi. They include the rather rare *jh*, in *ajjhita*, line 5.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 22 to 28, the inscription is in prose throughout. From a linguistic point of view, we have to notice (1) the use of the Prakrit word *phullā*, in line 15; and (2) in *anumōditaka*, line 13 f.; *uparīkṣhita*, line 14; *pratisṣhāpitaku*, line 14 f.; and

¹ *śôpātha-sara*, line 24; the meaning, however, is not quite certain.—*sara*, in one of its meanings, denotes the reed or grass called *Saccharum Sara*.

² See page 93 above, and note 3.

utpadyamdnaka, line 18 f., the affix *ka*, which I have commented on at page 69 above.— In respect of orthography, we have to notice (1) the use of the *upadhmnīya*, in *sah-pañchabhir*, line 21; (2) the use of the dental nasal, instead of the *anusvāra*, before *ś*, in *kdrānsi-cha*, line 8; *ansa*, in various forms, in lines 10 to 12; and *vansa*, line 18; (3) the constant doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *anakkrama*, line 13; *kkrama*, line 14; *puttra*, line 1; *sattra*, line 16; and *kshattriya*, line 31; (4) the doubling of *g*, under the same circumstances, in *viggrahika*, line 31; (5) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, lines 1, 2, 4, 5, and 6; (6) the occasional use of *b* for *v*, in *bā* (for *vā*), line 8; *bā* (for *vā*) line 23; and *sambatsara*, line 29; and (7) the use of *v* for *b*, in *vali*, line 16; and *valadhikṛita*, line 31.

The first plate of this grant is a quasi-palimpsest. On the outer side of it there are traces of sixteen lines of writing, containing an inscription of the same *Mahārāja Śarvanātha*, in the same characters as those of the extant inscription. They have been so carefully beaten in that no impression of them is possible; and only detached words can be read here and there. But I could distinguish the names of *Rāmadēvi*, in line 4; *Ajjhitadēvi*, in line 5; *Jayanātha*, in line 6; and *Śarvanātha* in line 7. And this inscription seems to have been cancelled because of the omission of the words *Tamasā-nadyā uttara-pārv*, between *mahārāja-Śarvanāthah kusāl* and *brāhmaṇ-ādān-kuṭumbinah*, in line 7.

The extant inscription is one of the *Mahārāja Śarvanātha*; and the charter recorded in it is issued from the city or hill called *Uchchakalpa*. The date of the writing of the charter is given, in words, as the year one hundred and ninety-three (A. D. 512-13), and the tenth day, without any specification of the fortnight, of the month *Chaitra* (March-April). It is partly *Vaiṣṇava*, and partly of solar worship; the object of it being to record the grant, by the *Mahārāja Śarvanātha*, of the village of *Āśramaka* on the north bank of the river *Tamasā*, on the agreement between him and the grantees that it was to be applied to, amongst other things, the purposes of a shrine of *Vishṇu* under the title of *Bhagavat* or the *Divine One*, and of a shrine of a god the name of which, as written, must be a mistake for *Āditya*, the *Sun*.

I have not been able to identify the village of *Āśramaka*. But the river *Tamasā* is, of course, the modern '*Tamas*' and '*Tons*' of maps, &c., which rises in the *Mahiyar* State, on the south of *Nāgaudh*, and, running through the north part of *Rewah* (properly *Rtṛwān*, or sometimes *Rtmām*) flows into the *Ganges* about eighteen miles to the south-east of *Allahābād*. And the mention of it, under circumstances which shew that *Śarvanātha* had territorial ownership over at any rate a certain village on its northern bank, is of importance, as giving evidence that the *Mahārājas* of *Uchchakalpa* did belong to the part of the country in which their grants are found. The only other definite proof of this is, as noted above, page 111, the existence of the inscription mentioning both *Hastin* and *Śarvanātha* on the stone-pillar at *Bhumarā*.

TEXT.¹

First Plate.

1 Om Svasty-Uchchakalpāt(n)-mahārāj-Aughadēvas-tasya puttras-tat-pād-
ānuddhyātō mahādēvyā[m*]

¹ From the original plates.

- 2 Kumāradēvyām-utpannō mahārāja-Kumāradēvas-tasya puttras-tat-pād-
ānu-
- 3 ddhyātō mahādēvyām Jayasvāmīnyām-utpannō mahārāja-Jayasvāmī tasya
4 puttras-tat-pād-ānuddhyātō mahādēvyām Rāmadēvyām=utpannō mahārāja-
Vyāghras-tasya
- 5 putras-tat-pād-ānuddhyātō mahādēvyām-Ajjhitadēvyām-utpannō mahārāja-
Jaya-
- 6 nāthas-tasya putras-tat-pād-ānuddhyātō mahādēvyām Muruṇḍadēvyām-
utpannō mahārāja-
- 7 Śarvanāthah kusall Tamasā-nadyā uttara-pāre Āśramakē brāhmaṇ-ā-
8 dīn-kuṭumbinas-sarvva-kārūś-cha samājñāpayati [1*] Vīditam-bā(vō)-stu
yath-aisha
- 9 grāmō may-ā-chandr-ārka-samakālikas-s-[ō*]drangas-s-ōparikarāḥ a-chāta-
10 bhāṭa-prāvēśyaś-chōra-daṇḍa-varjjitah chatu[r*]bhīr-anśē¹ pratipāditaḥ [1*]
atō-
- 11 nśa-dvayam Vishṇunandinah aparō-py-anśah Svāmīnāga-puttra-vaṇija-
12 Śaktināgasya aparō-py-anśah Kumāranāga-Skandanāgayōḥ [1*] ētat-pu-
13 ttra-[pautra*]-prapauttra-tatputtr-ādy-anukkramēṇa² tāmra-śāsanēn-āti-
śriṣṭa[h*] [1*] ēbhīr-sp[1*] may-[ā*]-
- 14 numōditakam yath-ōparilikhitaka-kkramēṇ-aiva sva-puṇy-ābhivṛiddhayē sva
prati-
- 15 śhṭhāpitaka-bhagavat-pādānām-āditsā³-bhāṭṭāraka-pādānāfi-cha khaṇḍa-phuṭṭa⁴
pratisam-
- 16 skāra-karāṇāya va(ba)li-charu-sattra-gandha-dhūpa-mālya-dīpa-pravarttanāya ch-
[ā*]tisriṣṭah⁵ [1*]

Second Plate.

- 17 Tai(tē) yūyam-ēśhām samuchita-bhāgabhōga-kara-hirany-ādi-pratyāy-ōpa
18 naya[m*] karishyath-ājñā-śravaṇa-vidhēyās-cha bhavishyatha [1*] Yē ch-
āsmad-vanś-ōtpadya-
- 19 mānaka-rājānas-tair-iyān-dattir-na vilōpy-ānumōdanīyā yathō(thā)-kālafi-cha
20 pratipēlanīyā samuchita-rāj-ābhāvya-kara-pratyāyās-cha na grāhyah [1*] Yāḥ
21 imān-dattin-iōpayēt-sah-pañchabhīr⁶-mahāpātakair-upapātakais-cha sarhyukta[h*]
22 syād-Uktaś-cha Mahābhāratē bhagavatā vēda-vyāsēna Vyāsēna [1*]
Sva⁷-dattām-para-dattā-

¹ Read *anśāś*.² We have to supply *upabhōgyah*, or some similar word, here.³ Read *āditya*. — *āditsā* is a regular formation, in the sense of 'a desire to seize or take,' from the desiderative of *ād*, 'give,' in composition with the prefix *ā*. But it is not known as a proper name; and there can be no doubt that the engraver has written it by mistake for *āditya*, 'the sun.'⁴ Read *spṛṣṭita*. See page 122 above, note 3.⁵ This *śhṭh* is inserted below the *ch*=[ō*], from want of space at the end of the line.⁶ Read *ya imān-dattin iōpayēt-as pañchabhīr*.⁷ *Mētra*, *Ślōka* (Anuśṭubh); and in the following four verses.

- 23 m-bá(vá) yatnád-raksha Yudhishthira mahlm-mahlmatañ-chhréshtha'
dānāch-chhréyō-nupālanam [11*]
- 24 Prāyēna(ṇa) hi narēndrāpām vidyatē n-[ā*]-subhā gatīḥ pūyantē
tē tu satatam pra-
- 25 yachchhantō vasundharā[m*] [11*] Bahubhir-vasudhā bhuktā rājabis-
Sagar-ādibhiḥ yasya
- 26 yasya yadā bhū(bhū)mis-tasya tasya tadā phalam [11*] Shashṭim
varsha-sahasrāpi svarggē mōda-
- 27 ti bhūmi-dah āchchhētā ch-ānumantā cha tāny-ēva narakē vasēt-
Sarvva¹-sasya-samri-
- 28 ddhān-tu yō harēta vasundharām śva-vishthāyām kṛimir-bhūtvā pitṛibhis-
saha majjatē [11*]
- 29 Likhitam² samba(mva)tsara-śatē tri(tri)-navaty-uttarē Chaittra-māsa-divasē
daśamē
- 30 bhōgika-Phālgū³datt-āmātya-naptrā bhōgika.Varānadinna-puttrēṇa mahā-
- 31 sādhiviggrahika-Manōrathēna [1*] Dūtak[ō*] rma(ma)hāva(ba)lādihkṛita-
kshattriya-
- 32 Śivagūptaḥ [11*]

TRANSLATION.

Om! Hail! From Uchchakalpa;—(There was) the *Mahārāja Ūghadēva*. His son, who meditated on his feet, (was) the *Mahārāja Kumāradēva*, begotten on the *Mahādēvi Kumāradēvi*. His son, who meditated on his feet, (was) the *Mahārāja Jayasvāmin*, begotten on the *Mahādēvi Jayasvāmini*. His son, who meditated on his feet, (was) the *Mahārāja Vyāghra*, begotten on the *Mahādēvi Rāmadēvi*. His son, who meditated on his feet, (was) the *Mahārāja Jayanātha*, begotten on the *Mahādēvi Ajjhitadēvi*.

(Line 6.)—His son, who meditates on his feet, the *Mahārāja Śarvanātha*,—begotten on the *Mahādēvi Murundadēvi*,⁴—being in good health, issues a command to the cultivators, beginning with the Brāhmins, and to all the artisans, at (the village of) *Aśramaka* on the north bank of the river *Tamasā*:—

(L. 8.)—"Be it known to you that this village is allotted by me, in four shares, to endure for the same time with the moon and the sun; with the *udranga* and the *aparikara*; (and with the privilege that it is) not to be entered by the irregular or the regular troops. Out of them, two shares belong to Vishṇunandin; and another share belongs to the merchant Śaktināga, the son of Svāmināga; and another share belongs to Kumārānāga and Skandanāga. It is given by (this) copper-plate charter, [to be enjoyed⁵] by the succession of them and (their) sons, [sons' sons⁶], sons of sons' sons, sons of the latter, &c. Moreover, it is agreed by them (and) by me that it is given for the repairs, by the above-mentioned succession (of them and their descendants), in order to increase their own religious merit, of whatever may become broken or torn (in the shrines) o' the feet⁷ of the

¹ Read *mahlmatañ tréshtha*.

² Read *vasēt* [11*] *Sarvva*.

³ Supply *śāsanam*.

⁴ Read *phalgū*. See page 123 above, note 2.

⁵ This *gu* is very much blurred in the original, but is quite legible.

⁶ In No. 29, line 6, and No. 31, line 6, *abe* is called *Murundasvāmin*.

⁷ See page 123 above, note 3

Khoh Plates of the Maharaja Sarvanatha—The Year 193

i

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16

Handwritten text in an ancient script, likely Grantha or Tamil, arranged in approximately 16 horizontal lines. The characters are densely packed and appear to be in a dark ink on a lighter background.

ii

17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32

Handwritten text in an ancient script, likely Grantha or Tamil, arranged in approximately 16 horizontal lines. The characters are densely packed and appear to be in a dark ink on a lighter background.



Divine One, established by them, and of the feet of the sacred Sun,¹ and for the maintenance of the *bali*, *charu*, *sattra*, perfumes, incense, garlands, and lamps.

(L. 17.)—"You yourselves shall render to them the offering of the tribute of the customary royalties, taxes, gold, &c., and shall be obedient to (*their*) commands.

(L. 18.)—"And those kings who shall be born in Our lineage,—by them this grant should not be confiscated, (*but*) should be assented to, and should be preserved according to opportunity. (*And*) the tribute of the taxes which by custom should not belong to the king, should not be taken.

(L. 20.)—"Whosoever may confiscate this grant,—he shall become invested with (*the guilt of*) the five great sins and the minor sins."

(L. 22.)—And it has been said in the Mahābhārata by the venerable Vyāsa, the arranger of the Vēdas,—“O Yudhishthira, best of kings, carefully preserve land that has been given, whether by thyself, or by another; (*verily*) the preservation (*of a grant*) (*is*) better than making a grant! As a rule, indeed, no inauspicious condition is experienced by kings; but they are purified for ever, when they bestow land! The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continues it*)! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! He who confiscates land, rich in all (*kinds of*) grains, (*that has been granted*),—he becomes a worm in the ordure of a dog, and sinks (*into hell*) together with (*his*) ancestors!”

(L. 29.)—(*This charter*) has been written, in a century of years, increased by ninety-three, on the tenth day of the month Chaitra, by the Mahādāndhivīgrahika Manōratha, the grandson of the Bhōgika, the Amātya Phalgudatta,² (*and*) the son of the Bhōgika Varāhadinna. The Dātaka (*is*) the Mahābaldhikrīta, the Kshatriya Śivagupta.

No. 29; PLATE XIX A.

KHOH COPPER-PLATE INSCRIPTION OF THE MAHARAJA SARVANATHA.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. p. 15, No. 8, where he published a translation of it,³—is on another copper-plate, the only one now forthcoming of an original set of two,⁴ that appears to have been found somewhere in the valley near the village of Khōh,⁵ in the Nāgaudh State in the Baghelkhand division of Central India. I obtained the original plate, for examination, from the possession of the Rājā of Nāgaudh, through the kindness of Major D. W. K. Barr.

¹ See page 123 above, note 5; and page 127, note 3.

² See page 123 above, note 2.

³ But he wrongly took, as the continuation of it, the second plate of the grant of the same Maharāja Sarvanatha of the year 214, No. 31 below, Plate xx.

⁴ See page 128 below, note 3.

⁵ See page 93 above, and note 3.

The plate, which is inscribed on one side only, measures about $7\frac{1}{2}''$ by $6''$. The edges of it were fashioned slightly thicker than the inscribed surface, with corresponding depressions inside them, so as to serve as rims to protect the writing; and the inscription is in a state of very fair preservation almost throughout. The plate is rather thin; but the letters are shallower than usual, and shew through only indistinctly on the back of it. The engraving is good, but shews, as usual, marks of the working of the engraver's tool throughout.—In the upper part of the plate, there is a hole for a ring to connect it with the other that belonged to it. But the ring and its seal are not forthcoming.—The weight of the plate is $10\frac{1}{2}$ oz.—The average size of the letters is about $\frac{1}{8}''$. The characters belong to the northern class of alphabets, and are of the same type with those of the Kārtalāl grant of the *Mahārāja Jayanātha* of the year 174, No. 26 above, page 117, and Plate xvi. They include the rather rare *jh*, in *ajjhita*, line 5.—The language is Sanskrit; and, the first plate only being extant, this portion of the inscription is in prose throughout. It has not been engrossed as carefully as was usual in inscriptions of this early date. From a linguistic point of view, we have to notice (1) the use of the Prakrit word *phutta* in line 12; and (2) in *uparikkhitaka*, line 10, and *utpadyamānaka*, line 15, the affix *ka*, that I have commented on at page 69 above.—In respect of orthography, we have to notice (1) the use of the dental nasal, instead of the *anusvāra*, before *ś*, in *kārāntśa*, line 7, and *vanśa*, line 15; (2) the doubling of *k*, *g*, and *t*, in conjunction with a following *r*, e.g. in *anukrama*, line 10; *ggrāma*, line 8; and *puttra*, line 1, and *sattra*, line 13; (3) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, lines 1 to 5; and (4) the use of *v* for *b*, in *vālī*, line 13.

The inscription is one of the *Mahārāja Śarvanātha*; and the charter recorded in it is issued from the city or hill called *Uchchakalpa*. The date is lost, in the second plate. The inscription is apparently Vaishṇava; the object of it being to record the grant, by the *Mahārāja Śarvanātha*, of half of the village of *Dhavashandikā*, on the agreement between him and the grantees that it should be applied to, amongst other things, the purposes of a temple of the goddess *Pishta-purikādēvi*.

This village of *Dhavashandikā* seems to be the same one that was granted by the *Mahārāja Javanātha*, in the year 177, as recorded in No. 27 above, page 121, for the purposes of a temple of the god *Vishṇu*, under the name of *Bhagavat* or the *Divine One*. And the present assignment of half of it specially for the purposes of a temple of *Pishta-purikādēvi*, furnishes one item of proof that this goddess was a form of *Lakshmi*, the wife of *Vishnu*.¹

TEXT.²

First Plate.

- 1 Om Svasty-Uchchakalpāt(n)-mahārāj-Aughadēvas-tasya puttras-tat-pād-
ānuddhyātō mahādēvyāt.
- 2 Kumārādēvyām-utpannō mahārāja-Kumārādēvas-tasya puttras-tat-pād-
ānuddhyātō
- 3 mahādēvyā[m*] Jayasvāminyām-utpannō mahārāja-Jayasvāmi tasya
puttr s-tat-pād-ānu-
- 4 ddyātō mahādēvyā[m*] Rāmādēvyā[ā*]m-utpann[ō*] mahārāja-Vyāghras-
tasya puttras-tat-p[ā*]d-ānuddhyātō

¹ See also page 113 above, note 2.

² From the original plate.

- 5 mah[ā°]dēvyām-Ajjhitadēvyām-[u°]tpannō mahārāja-Jayanāthas-tasya
puttras-tat-p[ā°]d-ānuddhyā-
- 6 tō mahādā(dē)vyā[m°]¹ Murū(ru)ṇḍasvāmīnyām-utpannō manārāja-
Śarvanāthah kuśall Vōṭa-
- 7 santika-Dhavaśhapdik-ārdhē brāhmaṇ-ādīn-kuṭumbinas-sarvva-kārṇs-cha
samājñāpayati [1]
- 8 Viditam vō-stu yath-aisha ggrām-ārdhbō may-ā-chandr-ārka-sama-
kālikā(ka)s-s-[ō°]draṅgaḥ
- 9 s-ōparikarāḥ a-cha[ā°]ṭa-bhaṭa-prāvēśya[h°] sarvva-kar²-tyagah³ dr(s)-ōtpadya-
mānaka-pui(pra)tyāya-
- 10 samētaḥ Chhōḍugōmika⁴ ētat-putra-[pautra°]-prapauttra-tatputtr-ādy-anu-
kkramēṇa⁴ tāmbra⁴
- 11 śāsanēn-ātisriṣṭah [1°] Anēn-āpi may-ānumōditam yath-ōpari-
likhitaka-
- 12 kkrāmēṇ-aiva bhagavatyāḥ Piṣṭapurik[ā°]⁵-dēvyāḥ khaṇḍa-phuṭṭa⁷-
pratisaṃkāra-
- 13 karapāya va(ba)li-charu-sattra-prādharttanāya⁸ ch-ātisriṣṭas-Tē yūyam-
ēśhām
- 14 samuchita-bhāgabhogā-kara-hiraṇy-ādi-pratyāy-ōpanaya[m°] karishyath-ājñā-
śrava-
- 15 ṇa-vidhēyāś-cha bhaviṣyatha [1°] Yē cn-āsmad-vanś-ōtpadyamānaka-
rājānas-tair-iyā[m°]
- 16 datṭir-na vilōky(py)-ānumōdanīyā

(The second plate of this grant is not forthcoming.)

TRANSLATION.

Om! Hail! From Uchchakalpa;—(There was) the Mahārāja Ōghadēva. His son, who meditated on his feet, (was) the Mahārāja Kumārādēva, begotten on the Mahādēvī Kumārādēvī. His son, who meditated on his feet, (was) the Mahārāja Jayasvāmīn, begotten on the Mahādēvī Jayasvāmīnī. His son, who meditated on his feet, (was) the Mahārāja Vyāghra, begotten on the Mahādēvī Rāmādēvī. His son, who meditated on his feet, was the Mahārāja Jayanātha, begotten on the Mahādēvī Ajjhitadēvī.

¹This *anusotra* is omitted also in line 6 of No. 31 below, Plate xx.; and thus, as Monier Williams, in his Sanskrit Dictionary, gives *Urūḍa* as a proper name of a demon and of a man, as well as *Muruḍa*, we might have read *mahādēvyām-U. ṇḍasvāmīnyām*. In line 6, however, of the newly-discovered grant, No. 28 above, page 127, the reading is very distinctly *mahādēvyām Muruḍadēvyām*.

²Read *sarvva-kara-tyagah*.

³Read *gōmīkya*.

⁴We have to supply *upabhōgyah*, or some similar word, here.

⁵Read *tāmbra*.

⁶See line 11 of No. 31 below, page 137, and Plate xx., in which the long vowel *ē* was duly engraved, and is quite distinct.

⁷Read *spṛuṣṭa*. See page 122 above, note 3.

⁸Read *pravarittanāya*.

(Line 5).—His son, who meditates on his feet, the *Mahārāja Śarvanātha*,—begotten on the *Mahādēvī Murupādāsvāmini*,¹—being in good health, issues a command to the cultivators, beginning with the *Brahmans*, and to the artisans, in half of (the village of) *Dhavaśhaṇḍikā* in the *Vōṭa santika*—

(L. 8).—“Be it known to you that this half village is, by (*this*) copper-plate charter, given to *Chhōḍgōmika*, [to be enjoyed²] by the succession of him and (*his*) sons, sons' sons, sons of the latter, &c.,—to endure for the same time with the moon and the sun; with the *udraṅga* and the *uparikāra*; (*with the privilege that it is*) not to be entered by the irregular of the regular troops; with remission of all the taxes; (*and*) with such tribute as may accrue. And it is agreed by him (*and*) by me, that it is granted for the purpose of the repairs, by the above-mentioned succession (*of him and his descendants*), of whatever may become broken or torn, belonging to the divine goddess *Piśṭapunkādēvī*, and for the maintenance of the *bali*, *charu*, and *sattra*.

(L. 13).—“You yourselves shall render to these persons the offering of the tribute of the customary royalties, taxes, gold, &c., and shall be obedient to (*their*) commands.

(L. 15).—“And those kings who shall be born in Our lineage,—by them this grant should not be confiscated, (*but*) should be assented to.”

(*The rest of this inscription, on the second plate, is not forthcoming.*)

No. 30; PLATE XIX B.

KHOH COPPER-PLATE INSCRIPTION OF THE MAHARAJA SARVANATHA.

THE YEAR 197.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archaeol. Surv. Ind.* Vol. IX. p. 14, No. 6, where he published a partial translation of it,³ with a lithograph of the passage containing the date (*id.* Pl. iv. No. 7),—is on another copper-plate, the only one forthcoming of an original set of two,⁴ that appears to have been found somewhere in the valley near the village of *Khōh*,⁵ in the *Nāgaudh* State in the *Baghēlkhaṇḍ* division of Central India. I obtained the original plate, for examin-


¹In No. 28 above, line 6, page 127, she is called *Murupādēvī*. In No. 31 below, line 6, page 136, the termination of her name is *svāmini* as here.

²But he wrongly treated it as the continuation of the first plate of the grant of the year 214. No. 31 below, Plate xx.

³The grant of the year 214, No. 31 below, Plate xx., furnishes another instance, similar to that of the grant, the date of which is lost, No. 29 above, page 129, in which the last line of the first plate is left half blank. And, so far as the context goes, this inscription might be taken as the continuation of No. 29. But the edges of this plate are rounded off more; the copper is of a totally different quality, thickness, and weight; and the characters, though of just the same period, differ very much in details of execution,—notably in the *visarga*, e.g. in *grākydh*, line 2, *guptah*, line 13, and *dātah*, line 14, as contrasted with *nāthah* in line 6, *r[ṣṇ]drāṅgaḥ* in line 8, and *sumdāh* in line 10, of No. 29, Plate xixA. And there can, on the whole, be no doubt that in Plate xixA. and B. we have the first and second plates of two separate grants; not one entire grant.


⁴See page 93 above, and note 3.

A.—Khoh Plate of the Maharaja Sarvanatha.



SCALE 7/8

B.—Khoh Plate of the Maharaja Sarvanatha —The Year 197



ation, from the possession of the Rājā of Nāgaudh, through the kindness of Major D. W. K. Barr,

The plate, which is inscribed on one side only, measures about $7\frac{1}{16}''$ by $5\frac{1}{8}''$. The edges of it were fashioned slightly thicker than the inscribed surface, with corresponding depressions inside them, so as to serve as rims to protect the writing; and the inscription is in a state of perfect preservation almost throughout. The plate is fairly thick; but the letters are rather deep, and shew through clearly on the back of it. The engraving is good; but, as usual, the interiors of the letters shew marks of the working of the engraver's tool throughout.—In the upper part of the plate, there is a hole for a ring to connect it with the other that belonged to it. But the ring and its seal are not forthcoming.—The weight of the plate is 13 oz.—The average size of the letters is between $\frac{1}{8}''$ and $\frac{1}{4}''$. The characters belong to the northern class of alphabets, and are of the same type with those of the Kārtalāl grant of the Mahārāja Jayanātha of the year 174, No. 26 above, page 117, and Plate xvi.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 4 to 10, the inscription is in prose throughout.—In respect of orthography, we have to notice (1) the use of the *upadhāniya*, in *saḥ-pañchabhir*, line 2; (2) the use of the dental nasal, instead of the *anuvāra*, before *ś*, in *vinśati*, line 11; (3) the doubling of *g* and *t*, in conjunction with a following *r*, e.g. in *vigrahika* and *putrēna*, line 12; (4) the use of *b* for *v*, in *bā*, line 4, and *sambatsara*, line 10; and (5) the use of *v* for *b*, in *valadhikrīta*, line 13.

The first plate, containing the name of the Mahārāja and the place whence the charter was issued, is lost; but the date, and other details at the end, shew that the inscription is one of the Mahārāja Śarvanātha of Uchchakalpa. The date of the writing of the charter is given, in words, as the year one hundred and ninety-seven (A.D. 516-17), and the twentieth day, without any specification of the fortnight, of the month Aśvayuja (September-October.) The details of the grant are lost, in the first plate.

TEXT.¹

(The first plate of this grant is not forthcoming.)

Second Plate.

- 1 Yathā-kālaṅ-cha pratipālanīyā [1^o] samuchita-rāj-ābhāvya-kara-pratyāyāś-
chah²
- 2 na grāhyāḥ [1^o] Ya imān-dattin-lōpayēt-saḥ-pañchabhir³-mahāpātakair-
upapāta-
- 3 kaiś-cha samyuktas-syād-Uktaṅ-cha Mahābhāratē bhagavatā vēda-vyāsēna
Vyāsēna [1^o]
- 4 Sva⁴-dattām-para-dattām-bā(vā) yatnād-raksha Yudhishṭhira mahīm-
mahīmatāṅ-chhrēshṭha⁵ dānā-
- 5 ch-chhrēyō-nupālana[m^o] [11^o] Prāyēna(ṇa) hi narēndrāṅām vidyatē
n-[ā^o]-śubhā gatīḥ pāya-

¹ From the original plate.

² Read *cha*.

³ Read *dattin lōpayēt=sa pañchabhir*.

⁴ Metre, Ślōka (Anuṣṭubh); and in the following four verses.

⁵ Read *mahīmatāṅ hrēshṭha*.

- 6 nt[é*] tē tu satatam prayachchhantō vasundharām [11*] Bahubhir-
vvasudhā bhuktā rājabhis-Sagar-ādi-
7 bhīḥ yasya yasya yadā bhūmis-tasya tasya tadā phalā[m*] [11*]
Shashṭi-va[r*]sha-sahasrā-
8 pi svarggē mōdati bhūmi-daḥ āchchhētā ch-ānumantā cha tāny-ēva
narakē vasē-
9 [t*] [11*] Sarvva-sasya-samriddhān-tu yō harēta yasundharām śva-
vishṭhāyām kṛimir-bhūtvā
10 pitṛibhis-saha majjatē [11*] Likhitam¹ sambamva)tsara-śatē sapta-navaty-
uttarē Aśva-
11 yuja-māsa-divasē vinśatim² bhōgika-Phalgu³datt-āmātya-naptrā bhō-
12 gika-Varāhadinna-puttrēṇa mahāsāndhiviggrahika-Manōrathēna [1*]
13 Dūtakah mahāva(ba)lādihikṛita-Śivaguptah [1*] Halir-ākara-kumbha-daṇḍa-
14 pratimē(mō)chan-ātīlēkhinē=pi dūtakah uparika-Mākṛi(tri)śiva[h*] [11*]

TRANSLATION.

(The opening part of this inscription, on the first plate,
is not forthcoming.)

"And, according to opportunity, it should be preserved. And the tribute of the taxes which by custom should not belong to the king, should not be taken.

(Line 2).—"Whosoever may confiscate this grant,—he shall become invested with (the guilt of) the five great sins and the minor sins."

(L. 3).—And it has been said in the Mahābhārata, by the venerable Vyāsa, the ranger of the Vēdas,—“O Yudhishtira, best of kings, carefully preserve land that has been given, whether by thyself, or by another, (verily) the preservation (of a grant) is more meritorious than making a grant! As a rule, indeed, no inauspicious condition is experienced by kings; but they are purified for ever, when they bestow land! The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (of this grant that is now made, if he continue it)! The giver of land enjoys happiness in heaven for sixty thousand years (but) the confiscator (of a grant), and he who assents (to an act of confiscation), shall dwell for the same number of years in hell! He who confiscates land, rich in all (kinds of) grains, (that has been granted),—he becomes a worm in the ordure of a dog, and sinks (into hell) together with (his) ancestors!"

(L. 10).—(This charter) has been written, in a century of years, increased by ninety-seven, on the twentieth day of the month Aśvayuja, by the Mahāsāndhivigrahika Manōratha, the grandson of the Bhōgika, the Amātya Phalgudatta,⁴ (and) the son of the Bhōgika Varāhadinna. The Dūtaka (is) the Mahābalādihikṛita Śivagupta. Moreover, the Dūtaka to an additional writer⁵ for the remission of the fines on⁶ and water-pots, (is) the Uparika Mātrīśiva.

¹ Supply *śāsanam*.

² We should perhaps correct this into *vinśatitam*, as the base *vinśatima* seems to be properly used only when in composition with another numeral, e.g. *dvā-vinśatima*, in No. 27 above, line 21 page 123. But *vinśatima*, by itself, occurs again in line 18 of the Goa grant of Satyāśraya-Dhruvardja Indravarma (*Jour. Bo. Br. R. As. Soc.* Vol. X, p. 365.)

³ Read *phalgu*; see page 123 above, note 2.

⁴ See page 123 above, note 2.

⁵ See page 100 above, note 3.

⁶ The meaning of *halir-ākara* is not apparent.

No. 31; PLATE XX.

KHÖH COPPER-PLATE INSCRIPTION OF THE
MAHARAJA SARVANATHA.

THE YEAR 214.

THIS inscription,—which was first brought to notice by General Cunningham, in 1879, in the *Archæol. Surv. Ind.* Vol. IX. pp. 14 and 16, Nos 6 and 8, where he published a translation of it,¹ with a lithograph of the passage containing the date (*id.* Pl. iv. No. 8),—is on another set of copper-plates that appear to have been found somewhere in the valley near the village of Khöh,² in the N'gaudh State in the Baghelkhand division of Central India. I obtained the original plates, for examination, from the possession of General Cunningham.

The plates, which are inscribed on one side only, are two in number, the first measuring about 8½" by 6", and the second 8½" by 5½". The edges of them are fashioned slightly thicker than the inscribed surfaces, with corresponding depressions inside them, so as to serve as rims to protect the writing; and, though the plates are here and there worn quite through by rust, the inscription is in a state of very good preservation almost throughout. The plates are rather thin; and the letters shew through on the backs of them so clearly that in many places they can be read there. The engraving is good; but, as usual, the interiors of the letters shew marks of the working of the engraver's tool throughout.—In the upper part of each plate, there is a hole for a ring to connect them. But the ring, with the seal attached to it, is not now forthcoming; having been abstracted by slitting the plates from the ring-holes to the edges.—The weight of the two plates is 1 lb. 2 oz.—The average size of the letters is about 1½". The characters belong to the northern class of alphabets, and are of the same type with those of the Kārtalāl grant of the Mahārāja Javanātha of the year 174, No. 26 above, page 117, and Plate xvi. They include the rather rare *jh ajjhita*, line 5.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 20 to 27, the inscription is in prose throughout. From a linguistic point of view, we have to notice, in *utpannaka*, line 9; *utpadyamānaka*, lines 9 and 16; and *kāritaka*, line 11, the affix *ka*, which I have commented on at page 69 above.—In respect of orthography, we have to notice (1) the use of the *upadhmaniya*, in *saḥ-pañchabhir*, line 18; (2) the use of the guttural nasal, instead of the *anusvāra*, before *ś* and *h*, in *vanśa*, line 16, and *sahhitā*, line 19; and (3) the doubling of *g* and *t*, in conjunction with a following *r*, in *viggrahika*, line 29, and *puttra*, lines 1 to 5; but not in *putra-pautra*, line 12.

The inscription is one of the Mahārāja Sarvanātha; and the charter recorded in it is issued from the city or hill called Uchchakalpa. The date of the writing of the charter is given, in words, as the year two hundred and fourteen (A.D. 533-34), and the sixth day, without any specification of the fortnight, of the month Pausha (December-January). It is apparently a Vaishnava inscription; the object of it being to record the sanction of the

¹ But he wrongly attached No. 30 above, with the date of 197, to the first plate of this grant, and took the second plate of this grant as the continuation of No. 29 above.

² See page 93 above, and note 3.

Mahārāja Śarvanātha to the transfer, among private grantees, of two villages named **Vyāghrapallika** and **Kācharpallika** in the **Maṇināga pāṭha**, for the purposes of a temple of the goddess **Piṣṭapurikādevī** at the town of **Mānapura**.

This town of **Mānapura** is possibly the modern **Mānpur**,¹ near the river **Śōṅ**, about forty-seven miles in a south-easterly direction from **Uchaharā**, and thirty-two miles south-east of **Kārtalāt**. And, if this identification is accepted, we have here another item of evidence tending to connect the *Mahārājas* of **Uchchakalpa** with the part of the country in which their grants are found. But it is obviously not of as much force as the two points to which I have previously drawn attention; *viz.* the existence of the inscription of **Hastin** and **Śarvanātha** on the pillar at **Bhumarā**, No. 24 above, page 110; and the mention of the river **Tamasā**, in **Śarvanātha**'s grant of the year 193, No. 28 above, page 125, in such a way as to shew that he had actual territorial ownership over at any rate a certain village on the northern bank of that river. As regards the present passage, it is not so conclusive, because a *Mahārāja* might very well make a grant of land within his territory to a temple outside it. At the same time, that temple would not be far distant from his own domains.

TEXT.²

First Plate.

- 1 Ōm Svasty-Uchchakalp[ā*]n-mahārāj-Aughadēvas-tasya puttras-tat-pād-ānudhyātō mahādēvyā[m*]
- 2 Kumāradēvyām-utpannō mahārāja-Kumāradēvas-tasya putt[r*]as-tat-pād-ānudhyātō
- 3 mahādēvyā[m*] Jayasvāmīnyām-utpannō mahārāja-Jayasvāmī tasya puttras-tat-pād-ā-
- 4 nudhyātō mahādēvyām Rāmadēvyām-utpannō mahārāja-Vyāghras-tasya putt[r*]as-tat-pād-ānudhyā-
- 5 tō mahādēvyām-Ajjhitadēvyām-utpan[n*]ō mahārāja-Jayanāthas-tasya puttras-tat-pād-ānu-
- 6 dhyātō mahādēvyā[m*]³ Muruṇḍasvāmīnyām-utpannō mahārāja-Śarvanāthas kusalī Maṇi-
- 7 nāga-pēṭhē Vyāghrapallika-Kācharpallika-grāmayō[r*]-brāhmap-ādīt(n)-prativāsinaḥ⁴
- 8 samājñāpayatī [i*] Viditā[m*] vō-stu yath-aisha(ṭau) grāmau mayā s-ōdraṅgau s-ōparikarau
- 9 a-chāṭa-bhāṭa-prāvēśyō(śyau) rāj-ābhāvyā-sarva-kara-pratyāy-ē(ō)tpannak-ōtpadya-mānaka-samō(mē)-
- 10 tau ā-chandr-ārkka-samakālikau chōr-ṭa(da)ṇḍa-varjīṭau Pulinda⁵bhāṭasya pras[ā*]dīkṛitau

¹ The 'Manpoor, Manpora, and Mānpur,' of maps, &c. Indian Atlas, Sheet No. 89. Lat. 23° 46' N.; Long. 81° 11' E.

² From the original plates.

³ See page 131 above, note 1.

⁴ This *visarga* is imperfect, only the upper part of it having been engraved.

⁵ The stroke at the bottom of this *śa*, which gives it somewhat of the appearance of *śra*, seems to be due to a slip of the engraver's tool.

- 11 tén=āpi **Mānapurē** kārītaka-dēvakul[é*] bhagavatyaḥ Paśtha'purikā-
dēvyāḥ pūjā-ni-
12 mittarḥ khaṇḍa-sphuṭita-pratisaṃskāraṇāya cha Kumārasvāminē putra-
pautr-ānvay-ōpa-
13 bhōjyō(jyau) pratipādītau [1*] may-āpi bhūmichchhidrā(dra)-nyāyēna tāmra-
śāsan[é*]n-ānumōdītau [1*]
14 Tē yūyam=ēv-ōpalabhy=ājñā-śravana-vidhēyā bhūtva samuchita-bhāgabhoḡa-
kara-hiraṇy-ā-
15 vāt-āy-[ā*]di-pratyāyān=upanēshyatha [1*]

Second Plate.

- 16 Y[é*] ch=āsmad-vanś-ōtpadyamānaka-rājānas=tair=iyam datt[r*]-nna vilōpyā
yathā-kāla[m*] sa[m*]varddha-
17 nly=ānumōdanlyā paripālānyā cha [*] rāj-Abhāvya-kara-pratyāyā[h*]
sarvvē na grāhyā[h*] [1*]
18 Yaś-ch=aitām dattīm lōpayēt=saḥ=pañchabhir^a-mahāpātākair=upapātakaiś=cha
sarhyuktō bhūyā-
19 d-Uktañ=cha Mahābhāratē śatasāhasry[ā*]m sanhitāyām param-arshiṇā
Parāśara-sutēna
20 vēda-vyāsēna Vyāsēna [1*] Pūrvva^a-dattām dvīatībhyō yatnād=raksha
Yudhishṭhira mahi[m*] mahi-
21 vatā^a śrēshṭha dānāch=chhrēyō=nupālanam [11*] Prāyēna hi narēndrānām
ridyatē n=[ā*]-śubhā
22 gatib pūyattē(ntē) tē tta(tu) satatām prayachchhantō vasu[ndharām*] [11*]
[Bahubhir=vvasu*]dhā bhuktā rājabis=Sagar-ādībhi[h*]
23 yasya yasya yadā bhūmis=tasya tasya tadā phalam [11*] Śbāshṭi-
varsha-sahasrāṇi
24 svarggē mōdati bhūmi-daḥ ākshēptā ch=ānumantā cha tāny=ēva narakē
vaset [11*] Sva-da-
25 ttām para-dattām vā yō harēta vasundharā[m*] śva-vishṭhāyām
kṛimir-bhūtva pitṛibhis=saha
26 majjati [11*] A-pānyēshv=aranyēshu sushka-kōta[rā*]-vāsinah kṛishṇ-āhayō
hi jā-
27 yantē pūrvva-dāyam haranti yē [11*] Likhītam^c sa[m*]vatsara-śata-
īvayē chaturdaś-ōttarē
28 Pausha-māsa-divasē shapṭhē(shṭhē) Phalgudatt-āmatyā-pranapt[r*]ā Varāha-
din[n*]a-napt[r*]ā
29 Manōratha-sutēna sāndhiviggrahika-Nāthēna [1*] Dūtakō Dhṛiti-
svāmikah [11*]

*Read pishṭa**^aRead sa pañchabhir**^bMetro, Ślōka (Anushṭubh); and in the following five verses**^cRead mahimatām.**^dSupply śāsanam*

TRANSLATION.

Om! Hail! From **Uchchakalpa**;— (*There was*) the **Mahārāja Ūghadēva**. His son, who meditated on his feet, (*was*) the **Mahārāja Kumāradēva**, begotten on the **Mahādēvi Kumāradēvi**. His son, who meditated on his feet, (*was*) the **Mahārāja Jayasvāmin**, begotten on the **Mahādēvi Jayasvāmini**. His son, who meditated on his feet, (*was*) the **Mahārāja Vyāghra**, begotten on the **Mahādēvi Rāmadēvi**. His son, who meditated on his feet, (*was*) the **Mahārāja Jayanātha**, begotten on the **Mahādēvi Ajjhitadēvi**.

(Line 6).—His son, who meditates on his feet, the **Mahārāja Śarvanātha**,—begotten on the **Mahādēvi Muruṇḍasvāmini**,—being in good health, issues a command to the residents, beginning with the Brāhmins, at the villages of **Vyāghrapallika** and **Kāchrapallika** in the **Maṇināga pāṭha**:—

(L. 8).—“Be it known to you that these two villages were bestowed, as a mark of favour, upon Pulindabhaṭa,—with the *udranga* and the *uparikara*; (*with the privilege that they were not to be*) entered by the irregular or the regular troops; with whatever had (*by custom*) accrued or might accrue in connection with the tribute of all the taxes which should not belong to the king; to endure for the same time with the moon and the sun; (*but*) with the exception of (*the right to*) fines imposed on thieves. And now they are granted by him to Kumārasvāmin, to be enjoyed by the succession of (*his*) sons and sons' sons, for the purpose of the worship of the divine goddess Pishtapurikādēvi at the temple which he has caused to be built at (the town of) **Mānapura**, and for the purpose of repairing whatever may become broken or torn. And, by (*this*) copper-plate charter, they have been assented to by me, according to the rule of *bhūmicchhidra*.³

(L. 14).—“You yourselves, understanding (*this*), (*and*) being obedient to (*their*) commands, shall render the tribute of the customary royalties, taxes, gold, *śudā*,⁴ revenue,⁵ &c

(L. 16).—“And those kings who shall be born in Our lineage,—by them this grant should not be confiscated, (*but*) according to opportunity should be increased (*and*) assented to and preserved. And none of the tribute of the taxes which should not belong to the king, should be taken.

(L. 18).—“And whosoever may confiscate this grant, he shall become invested with (*the guilt of*) the five great sins and the minor sins.

¹ In No. 28 above, line 6, page 127, she is called Muruṇḍadēvi. In No. 29 above, line 6, page 131, the termination of her name is *svāmini*, as here.

² *bhūmicchhidra*, *lit.* ‘a fissure (furrow) of the soil,’ is a technical fiscal expression of constant occurrence in inscriptions. Dr. Bühler has recently discovered the meaning of it, in Yādavaprakāśa's *Vajrayanti*, in the *Vaiyādhya*, verse 18, where it is explained by *krishya-yōgyā bhūḥ*, ‘land fit to be ploughed or cultivated.’

³ *śudā* is a technical fiscal term, the meaning of which is not apparent. It is derived either from *śū*, ‘to blow, or *was*, to become dried or withered,’ in composition with the prefix *ś-*.—The more usual expression is simply *vāta*; e.g. *sa-vāta-bhūta-dhanya-hiranyadāya* in line 26 of the *Māliya* grant of Dharasēna II, No. 38 below, Plate xxv.



⁴ *śya*, *lit.* ‘that which comes in; income,’ is now a technical fiscal term for ‘the customary dues of the hereditary village-officers and servants.’ It is, however, not quite certain that it had this special meaning in the early inscriptions.

Khoh Plate of the Maharaja Sarvanatha:—The Year 214

AN INDIGO PHOTO-LITH.

SCALE 7/8

J. P. B. P. L. E. R. O. C. S.



(L. 19.)—And it has been said in the Mahābhārata, in the *Śatasāhasrī-Samhitā*, by Vyāsa, the arranger of the Vēdas, the supreme sage, the son of Parāśara,—“O Yudhiṣṭhira, best of kings, carefully preserve land that has previously been given to the twice-born; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant! As a rule, indeed, no inauspicious condition is experienced by kings; but they are purified for ever, when they bestow land! The earth has been enjoyed by [many*] kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! He who confiscates land that has been given, whether by himself, or by another,—he becomes a worm in the ordure of a dog, and sinks (*into hell*) together with his ancestors! Those who confiscate a previous grant, are born (*again*) as black serpents, inhabiting the dried-up hollows of trees, in desert places destitute of water!”

(L. 27.)—(*This charter*) has been written in two centuries of years, increased by fourteen, on the sixth day of the month Pausha, by the *Sāmdhivigrahika* Nātha, the great-grandson of the *Amdīya* Phalgudatta; the grandson of Varāhadinna; (*and*) the son of Manōratha. The *Dātaka* (*is*) Dhṛitisvāmika.

No. 32; PLATE XXI A.

MEHARULI POSTHUMOUS IRON PILLAR INSCRIPTION OF CHANDRA.

THIS inscription was first brought to notice in 1834, in the *Four. Beng. As. Soc. Vol. III.* p. 494, where Mr. James Prinsep published a lithograph of it (*id.* Plate xxx.), reduced from a facsimile made in 1831 by Lieutenant William Elliot, 27th Regiment N. I. This lithograph was not accompanied by any details of the contents of the inscription; and it does not represent a single letter of the original correctly, and is quite unintelligible from beginning to end.—In 1838, in the same Journal, Vol. VII. p. 629 ff., Mr. James Prinsep published a much improved lithograph (*id.* Plate xxxiii.), reduced from an ink-impression made in the same year by Captain T. S. Burt, of the Engineers; and, with it, his own reading of the text and a translation of it.¹—And finally, in 1875, in the *Four. Be. Br. R. As. Soc. Vol. X.* p. 63 ff., Dr. Bhau Daji published a revised version of the text and translation, including the correct reading of the king's name as Chandra, with a lithograph which appears to have been reduced from a copy on cloth made by Dr. Bnagwanlal Indrajī.²

Mēharaulī, or Mēhharaulī,³—an evident corruption of Mihirapurī,—is a village

¹ The translation is reprinted in Thomas' edition of Prinsep's *Essays*, Vol. I p. 320.

² This paper was published in 1875; but it was read before the Society four years earlier, on the 13th April 1871.

³ The 'Maharoli, Manroli, and Muhroulee, of maps. Indian Atlas, Sheet No. 49. Lat. 28° 31' N.; Long. 77° 14' E.—The pillar has always been known as the "Dehli Pillar;" and I think the name of the village in which it really stands, so important because of its obvious derivation, *vis.* Mihirapurī, 'the city of the sun. or of the Mihiras,' was not put on record, in connection with the inscription, until I noticed it (*Ind. Ant.* Vol. XV. p. 362.)

nine miles almost due south of Dehli, the chief town of the Dehli District in the Pañjāb. The inscription is on the west side of a tapering iron column, sixteen inches in diameter at the base and twelve at the top, and twenty-three feet eight inches high, standing near the well-known Kutb Minār in the ancient fort of Rāy Pithorā within the limits of this village.

The writing, which covers a space of about 2' 9½" broad by 10½" high, is in a state of excellent preservation throughout, owing, of course, to the nature of the substance on which it is engraved. The bottom line of the inscription is about 7' 2" above the stone platform round the lower part of the column. The engraving is good; but, in the process of it, the metal closed up over some of the strokes, which gives a few of the letters a rather imperfect appearance in the lithograph; this is especially noticeable in the *sy* of the opening word *yasyō*, and in the *r* of *wasā* in the same line.—The size of the letters varies from ⅙" to ⅓". The characters belong to the northern class of alphabets; and, allowing for the stiffness resulting from engraving in so hard a substance as the iron of this column, they approximate in many respects very closely to those of the Allahābād posthumous pillar inscription of Samudragupta, No. 1 above, Plate i. But, as a distinguishing feature, we have to notice the very marked *mātrās*, or horizontal top-strokes of the letters, which we have already observed in the Bilsad pillar inscription of Kumāragupta, No. 10 above, page 43, and Plate v.—The language is Sanskrit; and the inscription is in verse throughout.—In respect of orthography, we have to notice (1) the use of the dental nasal, instead of the *anusvāra*, before *ś*, in *prāṅsu*, line 6; (2) the doubling of *t*, in conjunction with a following *r*, in *śatru*, line 1; and (3) the very unusual omission of the second *t*, which is formative and not due to the preceding *r*, in *māryā* for *mārttyā*, and *kīrtiyā* for *kīrttyā*, line 3.

The inscription is a posthumous eulogy of the conquests of a powerful king named **Chandra**, as to whose lineage no information is given. It is not dated.¹ It is a Vaishṇava inscription, and the object of it is to record the erection of the pillar, which is called a *dhvaja*, or 'standard,'² of the god Viṣṇu, on a hill called **Viṣṇupada**, i. e. "the hill that is marked with) footprints of Viṣṇu."

As regards this hill named **Viṣṇupada**, and the question whether it should be identified with that part of the **Dehli Ridge** on which the column stands,—the actual position of the column is in a slight depression, with rising ground on both sides; a position

¹ Mr. Prinsep allotted this inscription to the third or fourth century A. D., and Dr. Bhau Daji, to a period later than the time of the Guptas. Mr. Ferguson (*Indian Architecture*, p. 508), drawing special attention to the Persian form of the capital, expressed a conviction that the inscription is of one of the Chandraguptas of the Early Gupta dynasty, and consequently belongs to A. D. 363 or 400.—My own impression at first, on independent grounds, was to allot it to Chandragupta I., the first *Mahārājādhrāja* of the family, of whose time we have as yet no inscriptions; and I should not be surprised to find at any time that it is proved to belong to him. The only objection that I can see, is that it contains no reference to the Indo-Scythians, by overthrowing whom the Early Guptas must have established themselves. But, having regard to the name of the village at which the pillar is, it is also possible that the inscription is one of the younger brother of Mihirakula, whose name is not mentioned by Huen Tsiang.

² Compare *dhvaja-stambha*, 'flag-staff,' as applied to the Ēran column in line 9 of No. 19 above. There is another iron column, at Dhār, the ancient Dhārā, now the chief town of the Dhār State in Central India. But there is no ancient inscription on it; unless it is completely hidden under, and destroyed by, a Persian inscription that was engraved on it when the Musalmāns conquered that part of the country.

which hardly answers to the description of its being on a *giri* or 'hill.' And this, coupled with the tradition that the column was erected, in the early part of the eighth century A.D., by Anaṅgapāla, the founder of the Tōmara dynasty,¹ lays it quite open to argument whether this is the real original position of the column, or whether, like the Aśōka columns at Dehli, and possibly the Aśōka (and Gupta) column at Allahābād, it was brought to where it now stands from some other place. But the fact that the underground supports of the column include several small pieces of metal "like bits of bar-iron,"² is in favour of its being now in its original position; as they would probably have been overlooked, and left behind, in the process of a transfer.

TEXT.³

- 1 Yasy⁴=ōdvarttayataḥ pratpam=urasā satrūn=samēty=āgatān=Vañgēshv=āhava-varttinō=bhlikhitā khaḍgēna kīrttir=bhujē
- 2 tīrtvā sapta mukhāni yēna samarē Sindhōr=jjitā Vāhlikā⁵ yasy-ādyāpy=adhivāsyatē jalañidhir=vvtryy=āñilair=ddakṣiṇāḥ [11*]
- 3 Khinnasy=ēva visrijya gām narapatēr=ggām=āśritasy=ētarām mūr[t*]yā karmma-jit=āvanīr gatavataḥ kīrt[t*]yā sthitasya kshitau
- 4 sāntasy=ēva mahā=vanē hutabhujō yasya pratāpō mahān=n=ādyāpy=utsrijati prañāśita=ripōr=yyatnasya śēśhaḥ kshitim [11*]
- 5 Prāptāna swa=bhuj=ārjjitāñ=cha suchirañ=ch=aikādhirājam kshitau Chandr-āhvēna samagra=chandra=sadriśīm vaktra=śriyam bibhratā
- 6 tēn=āyam prañidhāya bhūmipatinā dhāvēna⁶ Viṣṇō(shṇau) matiṁ prānsur=Vviṣṇupadē girau bhagavatō Viṣṇōr=dhvajaḥ sthāpitaḥ [11*]

TRANSLATION.

He, on whose arm fame was inscribed by the sword, when, in battle in the **Vaṅga** countries, he kneaded (and turned) back with (his) breast the enemies who, uniting together, came against (him),—he, by whom, having crossed in warfare the seven mouths of the (river) **Sindhu**, the **Vāhlikas**⁷ were conquered;—he, by the breezes of whose prowess the southern ocean is even still perfumed;—

(Line 3.)—He, the remnant of the great zeal of whose energy, which utterly destroyed (his) enemies, like (the remnant of the great glowing heat) of a burned-out fire in a great forest, even now leaves not the earth; though he, the king, as if wearied, has quitted this earth, and has gone to the other world, moving in (bodily) form to the land (of paradise) won by (the merit of his) actions, (but) remaining on (this) earth by (the memory of his) fame;—

¹ *Archæol. Surv. Ind.* Vol. I. p. 171² *Id.* Vol. IV. p. 28, and Plate v.³ From the original pillar.⁴ Metre, Śārdūlavikrīḍita, throughout.

⁵ Prinsep also read *vāhlikā*, but Bhau Daji, varying in also the first syllable, read *bāhlikā*.—In the first *akshara*, the *v* is imperfect on the right side, through the closing up of the metal. In the second *akshara*, the *h* is turned in the opposite direction to that in which it is turned in *dhava*, line 1 and *mahāvān*⁶ and *mahān*, line 4. But, that the *akshara* is *hī*, not *hi*, is certain; because *l* can only be formed to the left; whereas, at this period, *h* was formed sometimes to the left and sometimes to the right; and, in the present inscription, it is turned to the right, as here, again in *hutabhujō*, line 4, and *dhāvēna*, line 5.

⁶ See page 142 below, note 2.⁷ See note 5 above.

The column with the present inscription lies, partially buried, north and south, with the top to the north. The base of it is rectangular, about 3' 4" square by 4' 5" high; and, as there is no socket at the bottom to indicate that it was fitted into any masonry foundation, this part must have been buried when the column stood upright. From this base there rises a sixteen-sided shaft, each face of which is about 8½" broad where it starts from the base; part of the shaft, about 17' 0" in length, is still connected with the base, making the length of this fragment about 21' 5"; and the present inscription, occupying five of the sixteen faces, is on this fragment, the bottom line being about 2' 2" above the top of the base. Immediately in continuation of this, there lies the remainder of the shaft, about 17' 10" long; at the upper end of this, the faces are each about 7" broad, shewing that the column tapers slightly from bottom to top. The upper end of this fragment is flat, with a round socket projecting from it; which shews these two fragments make up the entire shaft, the total length of which was thus about 39' 3", or 34' 10" above the base. This column appears to have broken naturally in falling, and not to have been deliberately divided, as the other was, in the manner described below. The next part of this column, the lower part of the capital, lies about forty yards away to the north, close up to the hedge of the hamlet, and is a fluted bell, about 2' 6" high and 3' 2" in diameter, almost identical in design with the corresponding part of a small pillar from an old Gupta temple at Sāñchi, drawn by General Cunningham in the *Archæol. Surv. Ind.* Vol. X. Plate xxii. No. 1. In the bottom of it there is a socket-hole, about 11" in diameter, answering in size to the socket on the top of the shaft; and on the top there is a projecting socket. About twenty-five yards south of this, and fifteen yards north of the column, I found a flat stone buried in the ground, just level with the surface; and, on excavating it, it proved to be the next portion, the square upper part of the capital. It measures about 2' 8" high by 3' 10" square; the vertical corner edges are trimmed off. I could not get at the bottom of it; but there must be there a socket-hole, answering to the projecting socket on the top of the bell-shaped part that came below it. I only exposed one side of it; but this was sufficient to shew that it is a lion-capital, exactly like the capital of the other column, noticed more fully below. On the top surface of it, there is in the centre a circular socket-hole about 11½" in diameter and 4" deep, with eight other rectangular socket-holes round it, one in the centre of each side, and one opposite each corner. The total length of this column, up to the top of the lion-capital, is about 44' 5"; or forty feet above the ground, if it stood with the entire base buried. The square lion-capital must have been surmounted by a statue or statues, of the same kind as that which stands on the summit of the column at Éran¹ which has on it Budhagupta's inscription, No. 19 above, page 88; but I cannot feel sure of having found it. I found, indeed, in the same field, towards the west side, in three pieces, a very well executed sandstone bas-relief slab, 9' 0" high, with a rectangular pedestal 3' 2" broad by 1' 8" deep and 8" high, of a male figure, standing, somewhat larger than life-size, wearing a *kirita* or high head-dress, with necklace and armlets, and draped from the waist downwards, with a small figure standing by the right leg. And close by this there were, in two pieces, the *kirita* and the head and shoulders of another figure of the same size, evidently a duplicate of the above. Unless, however, there were some intervening parts that

¹ See *Archæol. Surv. Ind.* Vol. X. p. 81, and Plate xxvi.

have been altogether lost, these slabs cannot belong to the columns, since their pedestals have no sockets to fit into the socket-holes on the tops of the lion-capitals.¹

The other column, with the fragmentary duplicate copy of this inscription, No. 34 below, Plate xxiC., stood, as is shewn by the present position of its base, about twenty yards north of the column that I have just described. When overthrown, it fell east and west, with the top towards the west. The base is rectangular, about 3' 3" square by 3' 11" high. Differing from the first column, the base here is followed by a concave circular part, about 1' 0" high. From this there rises a sixteen-sided shaft, each face of which is about 8" broad where it starts from the base. But the portion of the shaft that remains attached to the base is only about 1' 1" long; and a row of chisel-marks all round the column here, shews that it was deliberately broken by the insertion of wedges. The next piece of the column,—or rather a remnant of it, as it is broken vertically, and part of it has been lost,—lies about three yards to the north of the base, and parallel with it, but in an inverted position, with the upper end to the east. This piece is about 9' 0" long; and the remnant of the duplicate inscription is here, on two of the faces; the bottom line of it being about 2' 9½" above the square base. The next piece of the shaft is missing altogether, and is supposed to be entirely buried somewhere in this field. The remainder of the shaft, about 6' 9" in length, lies, almost entirely buried, a few yards to the west of the portion including the base and the commencement of the shaft. Each face here is about 7" broad at the top; shewing that this column also tapers slightly from bottom to top. The top of this fragment is flat, with a round socket projecting from it; which shews that we have here the end of the shaft. Immediately west of this fragment, there lies the fluted bell part of the capital, about 3' 0" high and 3' 3" in diameter, similar in design to the same part of the capital of the other pillar. In the bottom of it there is a socket-hole, about 11" in diameter, answering in size to the socket on the top of the shaft; and on the top there is a projecting socket. Just to the west of this there lies, upside down and partially buried, the next portion of the capital, the square upper part, measuring about 3' 0" high and 3' 10" square; the vertical corner edges are trimmed off. The bottom, and one entire side and parts of two others, are exposed; and enough is visible to shew that each side consists of a bas-relief sculpture of two lions, each sitting on its haunches and facing to the corner, where it merges into the corresponding corner lion on the next side;² with the head of a conventional *simha* or mythological lion in the centre, over the backs of the lions. In the bottom of this stone there is a socket-hole, about 10½" in diameter, answering to the projecting socket on the top of the bell-shaped part that came just below it. And I dug under one of the corners of the top enough to find there a rectangular socket-hole, which justifies us in assuming that the top has one circular and eight rectangular socket-holes, just as in the top of the lion-capital of the first column. As in the case of the first column, I cannot feel sure of having found the statue or statues which must have stood on the top of it.

The two inscribed columns were evidently intended as a pair, though the full measure of the second cannot be taken. From the distance between them; from the difference in the detailed measures; and from the analogous instance of the Êraṅ column, as shewing

¹ There are some similar bas-relief slabs set up in a group under some palm-trees in another field, about fifty yards away to the east from where the inscribed columns lie; but these, again, do not appear to belong to the columns.

² Compare the lions on the upper part of the square portion of the capital of the Êraṅ column

the way in which they must have been finished off at the top,—they can hardly have been connected by a beam, after the fashion of a *śraṇa* or arched gateway; and there are no traces of any temple to which they can have belonged. They are evidently an actual instance of two *raṣṭastambhas* or “columns of victory in war,” such as the Kauṭhēn¹ grant of Vikramāditya V., dated Śaka-Saṃvat 930 (A.D. 1008-9) expired, speaks of as having been set up by the Rāshṭrakūṭa king Karkara or Kakka III., and as having then been cut asunder in battle by the Western Chālukya king Taila II.

To return to the inscription on the first column,—the **writing**, which covers a space of about 3' 2½" broad by 1' 2½" high, has suffered a good deal from the weather; and, owing to the difficulty of obtaining lights and shades, partly in consequence of the letters being rather shallow, and partly because of the natural light colour of the stone, it is rather difficult to read on the original column; but, in the ink-impression and the lithograph, it can easily be read with certainty throughout.—The **size** of the letters varies from ½" to ¾". Differing from the Mandasor inscription of Kumāragupta and Bandhuvarman, No. 18 above, page 79, Plate xi., the **characters** here belong to the northern class of alphabets, and are a development, in some respects, of the type of the Allahābād posthumous pillar inscription of Samudragupta, No. 1 above, Plate i., and, in others, of that of the Mathurā inscription of Chandragupta II., No. 4 above, Plate iiiB. They include the rather rare lingual *dh*, in *upagādāha*, line 4. In *vīrya*, line 4, and *sāmantair-yasya*, line 5, the *r* is formed on the line of writing, with only a single *y* below it; in combination with other consonants, e.g. in *sumbrōr-ovighaṭita*, line 1, and *dharmaṣya*, line 8, the *r* is formed above the top line of writing, and the consonant is doubled, in the usual way.—The **language** is Sanskrit; and, except for the two words at the end, recording the engraver's name, the inscription is in verse throughout.—In respect of **orthography**, we have to notice (1) the use of the *upadhmdāṣya* in *sikharīṇaḥ-pāschimda*, line 5; (2) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *ānsu*, line 5, and *vanśa*, line 8; and before *s*, in *tśjānsu*, line 1, and *pānsu*, line 3; (3) the doubling of *k* and *t*, in conjunction with a following *r*, in *dhkrānti*, line 4; *chakra*, line 7; *mātra* and *yatra*, line 3; *anyatra*, line 6; and *nyāyittra*, line 7; but not in *kriyanti*, line 5, and *satru*, line 1; and (4) the doubling of *dh*, in conjunction with a following *y*, in *addhyasint*, line 4.

The **inscription** is one of a king named **Yaśōdharman**,² whose dominions are described as including the whole of the northern part of India, from the river **Lauhitya**, or the **Brahmaputra**, to the **Western Ocean**, and from the **Himālayas** to the mountain

¹ *Ind. Ant.* Vol. XVI. p. 18.

² Having regard to the frequency with which, in the period of this inscription, *varman* occurs as the termination of proper names, and to the rarity of *dharman*,—there might be some temptation to suggest that Yaśōdharman should be corrected into Yaśōvarman. But the *dh* is very distinct in line 7 here, and in the corresponding place in line 7 of the remnant of the original duplicate copy of this inscription, No. 34 below, Plate xxiC.; and again in line 8 below; and again in the same name in line 4 of the inscription of Yaśōdharman and Vishṇuvardhana, No. 35 below, Plate xxii.—The form *dharman* is not of frequent occurrence. But we do meet with it in other proper names; e.g. Kṛitadharman, Kaṭatradharman, Kaṭemadharman, Jayadharman, and Sudharman. And it also occurs in ordinary composition; e.g. in *Manu-śi-pravīta-vidhi-vidhāna-dharmma*, in line 5 of the Māliya grant of the Mahārāja Dharasēna II. of the year 252, No. 38 below, Plate xxiv.; and in *tśjōbhīr-āditya-samāna-dharmma*, in line 29 of the Kauṭhēn grant of Vikramāditya V. of Śaka-Saṃvat 930 expired (*Ind. Ant.* Vol. XVI. p. 22).

Mahendra.¹ We have an important allusion in the statement that he possessed countries which not even the **Guptas** and the **Hūnas** could subdue; and a still more important record, in connection with the general history of the period, to the effect that homage was done to him by even the famous king **Mihirakula**. It is not dated. But **Yaśódharman's** date is now known from the Mandasor inscription of Málava-Śamvat 589 (A.D. 532-33) expired, No. 35 below, which mentions him and Vishṇuvardhana; and the present inscription, having been engraved by the same person, Góvinda, must fall within a few years on either side of that date. Also, the use of the present tense almost throughout, coupled with the record that **Yaśódharman** himself erected the column, shews that the inscription is one of his own time, not posthumous. The opening verse contains a Śaiva invocation; which is in accordance with the boast, in line 6, that Yaśódharman never bowed his head to any save the god Śiva. But the record itself is non-sectarian; the object of it being only to narrate the erection of the column, for the purpose of reciting the king's glory and power.

TEXT.²

- 1 Vépantē³ yasya bhīma-stanita-bhaya-samudbhṛanta-daiṭyā digantāḥ śrīng-
āghātāiḥ Sumērōr-vvighaṭita-dṛishadaḥ kandarā yaḥ karōti |
ukshāpām tam dadhānaḥ kshithidharatanayā-datta-pañch-āngul-
ānkam drāghishṭhāḥ Śūlapāṇēḥ kshapayatu bhavatām śatru-tējāsi
kētuḥ ||
- 2 Avirbhūt-avalépair-avinaya - paṭubhir - llanghit-āchāra - mārggair - mmōhād - aidam-
yugñair-apa-śubha-ratibhiḥ pdyamānā narēndraḥ | yasya kshma
Śārngapāṇēr-iva kaṭhna-dhanur-iyā-kiṅ-ānka-prakōshṭham bāhum lōk-
ōpakāra-vrata-saphala-parispanda-dhīram prapannā ||
- 3 Nindy-āchārēshu yō-smin-vinaya-mushi yugē kalpanā-mātra-vrit[*]yā
rājasv-anyēshu pānsushv-iva kusuma-balir-nn-ābhāhāsē prayuktāḥ | sa
śrēyō-dhāmi samrād-iti Manu-Bharat-Ālarka-Māndhātṛi-kalpē kalyāṇē
hēmi bhāsvān-mapir-iva sutarām bhṛajāte yatra śabdaḥ ||
- 4 Yē bhuktā Gupta-nāthair-nna sakala-vasudh-ākkrānti-driṣṭa-pratāpair-nn-
ājñā Hūn-ādhipānām kshitipati-mukū-āddhyāsini yān-pravishṭā |
dēsāms-tān-dhanva-śaila-druma-śa(ga)hana-sarid-vīrabh-ōpagōḍhān-vīry - āva-
skanna-rājñāḥ sva-griha-parisar-āvajñayā yō bhunakti ||
- 5 Ā Lauhity-ōpakaṇṭhāt-tala-vana-gahan-ōpatyākād-ā Mahēndrād-ā Gang-
āśliṣhta-sānōs-tuhinaśikharipaḥ-paśchimād-ā payōdhēḥ | sāmantair-
yasya bāhu-draviṇa-hṛita-madaih pādāyōr-ānamadbbhiś-chūdāratn-āṅsu-rāji-
vyatikara-śabalā bhāmi-bhāgāḥ kriyantē ||
- 6 Sthānōr-anyattra yēna prapāti-kripanātām prāpitām n-ōttamāngam yasy-
āśliṣṭō bhujābhyām vahati himagirir-durgga-śabd-ābhimanam |

¹ It is doubtful whether this denotes here the famous Mahēndragiri or Mahēndrāchala in the Gañjām District, among the Eastern Ghats; or another mountain of the same name, not so well known, which appears to be mentioned also in line 2 of an earlier Nāik inscription of the nineteenth year of Siri-Pulmāyi (*Archæol. Surv. West. Ind.* Vol. IV, No. 14, pp. 108, 109), and in the *Brihat-Saṁhitā*, xiv. vv. 11-16 (Kern's Translation, *Jour. R. As. Soc. N. S.* Vol. V. p. 83), and must be located somewhere in the Western Ghats.

² From the ink-impression.

³ Metre, Sragdhārā; and in the next seven verses

- nichais-tên-âpi yasya prapâti-bhuja-bal-âvarjjana-klišta-mûrddhna
 chûdâ-pustp-ôpahârair-Mimihirakula-nripêṅ-ârchchitam pâda-yugmam ||
- 7 [Ga]m-êv-ônmatum-ûrddhvam viganayitum-iva jyôṭishâm chakkravâlam
 nirdêshṭum mârggam-uchchair-ddiva iva sukrit-ôparjjitayâḥ sva-
 krttêḥ | tên-â-kalpânta-kâl-âvadhîr-âvanibhujâ śri-Yaśôdharmman-
 âyam stambhaḥ stambh-âbhîrâma-sthîra-bhuja-parighêṅ-ôchchhritim
 nâyitô-ttra ||
- 8 Ś[1]âghyê janm-âsya vanê charitam-âgha-haram drîsyatê kântam-
 asmin-dharmmasy-âyam nikêṭas-chalati niyamitam n-âmunâ lôka-
 vrittam [1*] ity-utkarsham guṇânâm likhitum-iva Yaśôdharmmanas-
 chandra-bimbê râgâd-utkshipta uchchair-bhuja iva ruchimân-yâḥ
 prithivyâ vibhâti ||
- 9 Iti¹ tushṭîshaya² tasya nripatêḥ punya-karmmanâḥ | Vâsulên-ôparachitâḥ
 ślokaḥ Kakkasya stânunâ || Utkrâṇa³ Gôvîndenâ ||

TRANSLATION.

May that very long banner of (the god) Śûlapâni destroy the glory of your enemies ;— (that banner) which bears (a representation of) the bull (Nandi), marked by the five fingers (dipped in some dye and then) placed on him by (Pârvatî) the daughter of the mountain (Himâlâya), who causes the distant regions, in which the demons are driven wild with fear by (his) terrible bellowings, to shake; (and) who makes the glens of (the mountain) Sumêru to have their rocks split open by the blows of his horns!

(Line 2).—He, to whose arm, as if (to the arm) of (the god) Śârngapâni,—the fore-arm of which is marked with callous parts caused by the hard string of (his) bow, (and) which is steadfast in the successful carrying out of vows for the benefit of mankind,—the earth betook itself (for succour), when it was afflicted by kings of the present age, who manifested pride; who were cruel through want of proper training; who, from delusion, transgressed the path of good conduct; (and) who were destitute of virtuous delights :—

(L. 3).—He who, in this age which is the ravisher of good behaviour, through the action simply of (his good) intentions shone gloriously, not associating with other kings who adopted a reprehensible course of conduct,—just as an offering of flowers (is beautiful when it is not laid down) in the dust;—he in whom, possessed of a wealth of virtue, (and so) falling but little short of Manu and Bharata and Alarka and Mândhâtri, the title of "universal sovereign"² shines more (than in any other), like a resplendent jewel (set) in good gold :—

(L. 4).—He who, spurning (the confinement of) the boundaries of his own house, enjoys those countries,—thickly covered over with deserts and mountains and trees and thickets and rivers and strong-armed heroes, (and) having (their) kings assaulted by (his)

¹ Metre, Śloka (Anushtubh).² Supply *prastâṭh*.³ *anârj*; 'a sovereign who rules over kings and has performed the *râjasya*-sacrifice.'—For a description of the *râjasya*, which is a great sacrifice or religious ceremony performed, at the coronation of a supreme sovereign or universal monarch, by the king himself and his tributary princes, see the *Râjasya-Parva* in the *Sâhâ-Parva* of the *Mahâbhârata*; Protap Chandra Roy's Translation, page 95 ff.

prohess,—which were not enjoyed (*even*) by the lords of the **Guptas**, whose prowess was displayed by invading the whole (*remainder of the*) earth, (*and*) which the command of the chiefs of the **Hānas**, that established itself on the tiaras of (*many*) kings, failed to penetrate :—

(L. 5).—He before whose feet chieftains,¹ having (*their*) arrogance removed by the strength of (*his*) arm, bow down, from the neighbourhood of the (river) **Lauhitya** up to (the mountain) **Mahendra**,² the lands at the foot of which are impenetrable through the groves of palmyra-trees, (*and*) from (**Himālaya**) the mountain of snow, the table-lands of which are embraced by the (river) **Gaṅgā**, up to the **Western Ocean**,—by which (*all*) the divisions of the earth are made of various hues through the intermingling of the rays of the jewels in the locks of hair on the tops of (*their*) heads :³—

(L. 6).—He by whom (*his*) head has never been brought into the humility of obeisance to any other save (the god) **Sthāpu**;—he, through the embraces of whose arms (**Himālaya**) the mountain of snow carries no longer⁴ the pride of the title of being a place that is difficult of access;—he to whose two feet respect was paid, with complimentary presents of the flowers from the lock of hair on the top of (*his*) head, by even that (*famous*) king **Mihirakula**, whose forehead was pained through being bent low down by the strength of (*his*) arm in (*the act of compelling*) obeisance :—

(L. 7).—By him, the king, the glorious **Yaśodharman**,⁵ the firm beams of whose arms are as charming as pillars, this column, which shall endure to the time of the destruction of the world, has been erected here,—as if to measure out the earth; as if to enumerate on high the multitude of the heavenly lights; (*and*) as if to point out the path of his own fame to the skies above, acquired by good actions;—(this column) which shines refulgent, as if it were a lofty arm of the earth, raised up in joy to write upon the surface of the moon the excellence of the virtues of **Yaśodharman**, to the effect that—“ His birth (*is*) in a lineage that is worthy to be eulogised; there is seen in him a charming behaviour that is destructive of sin; he is the abode of religion; (*and*) the (*good*) customs of mankind continue current, unimpeded (*in any way*) by him.”

(L. 9).—From a desire thus to praise this king, of meritorious actions, (*these*) verses have been composed by **Vāsula**, the son of **Kakka**. (*This eulogy*) has been engraved by **Gōvinda**.

¹ *Sāmanta*, lit. ‘bordering, neighbouring; a neighbour, a feudatory prince, the chief of a tributary district,’ is a technical official title, denoting a rank next below that of the *Mahāsāmanta*, which title occurs, for instance, in several places in the Nirmaṇḍ grant of the *Mahāsāmanta* and *Mahārāja Samudrasēna*, No. 80 below, Plate xlii.—*Sāmanta* is of constant occurrence, in other inscriptions, in its technical sense; but it is here used only in a general way, and is translated accordingly.

² See page 146 above, note 1.

³ *chūḍā* is a single lock or tuft of hair left on the crown of the head after the ceremony of tonsure, which is performed in early childhood.

⁴ To complete the sense, we must apparently supply, in connection with *vahati*, the negative particle *na* from the first *pada* of the verse.

⁵ See page 145 above, note 2.

No. 34; PLATE XXIC.

MANDASOR DUPLICATE STONE PILLAR INSCRIPTION
OF YASODHARMAN.

THIS inscription, which I published, for the first time, in 1886, in the *Ind. Ant.* Vol. XV. p. 257 f., is the remnant, mentioned above, of the original duplicate copy of the inscription of Yaśódharman on the second inscribed column, described at page 144 above, at Mandasór,¹ or more properly Dasór, the chief town of the Mandasór District of Scindia's Dominions, in the Western Málwa division of Central India. It was discovered by Mr. Arthur Sullivan, who forwarded his hand-copy of it to General Cunningham in 1879. And it was this that led to the search which was made under my direction in 1884, and which resulted in the discovery of the entire copy of this inscription No. 33 above, page 142, and Plate xxiB., and of the inscription of Kumáragupta and Bandhuvarman of the Málava years 493 and 529, No. 18 above, page 79, and Plate xi.

The writing, which covers a space of about 1' 1" broad by 1' 2" high, is in some respects in a state of rather better preservation than the entire copy; but nearly three-quarters of the full inscription is lost here, through the column having cracked vertically and part of it being now not forthcoming.—The size of the letters varies from $\frac{1}{2}$ " to $\frac{3}{4}$ ". The characters belong, as before, to the northern class of alphabets, and were engraved by the same person, Góvinda, who engraved the entire copy, No. 33 above; and this record appears to have been in all essential details an exact reproduction of the copy that has been preserved entire. We have the lingual *dh* in *upagádha*, line 4. And the two methods of forming *r* in combination with a following consonant, are very well illustrated by *vrya*, line 4, and *ópahdráir-mmihirakula*, line 6.—In respect of orthography, we have to notice (1), as before, the use of the guttural nasal, instead of the *anusvára*, before *ś*, in *śśśś*, line 5; and before *s*, in *tśśśśś*, line 1; and (2) the doubling of *ś*, in conjunction with a following *r*, in *yattrá*; line 3, and *śśyitś-ttra*, line 7; and also in *śattru*, line 1, where it is not doubled in the entire copy.

This fragmentary inscription preserves the names of Yaśódharman and Míhiraakula. But the passage mentioning the Guptas and the Hūnas has been lost; and also that which gives the boundaries of Yaśódharman's dominions.

TEXT.*

1 [da]tta ¹ -pañc-āṅgul-āṅkam	drāghishṭhaḥ	Śūlapāṇēḥ	kshapayatu
	bhavatām śatru-tējānai kētuḥ			
2 jy[ś]-kiṅ-āṅka-prakōśhṭham	bāhum	lōk-ōpakāra-vrata-saphala-	
	parispanda-dhīr ² am prapannā			
3 [Ā]rarka-Māndhātri-kalpē	kalyāṇē	hēmni	bhāsvān-manir-iva
	śarāśm bhrājatē yattrā śabdāḥ			
4 [v]ra-bāh-ōpagādhan-vry-āvaskanna-rājśhā		sva-griha-parisar-āvajñāyā	
	yō bhunakti			

¹ See page 79 above, and note 1.² Metre, Sragdhārā; and in the next seven verses.

* From the ink-impression.

- 5 pādāyōr-ānamadbhīś-*chōḍāratn-āṅsu-rāji-vyatikara-śabalā bhūmi-bhāgāh*
 kriyantē ||
- 6 [Avar]jjana-kliṣṭa-mārddhna *chōḍā-puṣhp-ōpahārair-Mmihirakula-*
 nripēn-ārchchitam pāda-yugmaṁ ||
- 7 [śrī]-*Yaśōdharman-āyaṁ stambhah stambh-ābhirāma-sthira-bhuja-*
 pariḥēp-ōchchhritim nāyitō-ttra ||
- 8 [*Yaśōdha*]rmanas-*chandra-bimbē rāgād-utkshipta uchchair-bhuja*
 iva ruchimān-vaḥ prithivyā vibhāti ||
- 9 [Ka]kkasya¹ sununā || Utkrṣṭa² Gōvindēna ||

TRANSLATION.

[It is unnecessary to offer a translation of this fragment, as the contents of it are fully explained by the translation of the entire copy, at page 147 above. It is sufficient to note that we have the name of *Yaśōdharman*,¹ complete in line 7, and partially preserved in line 8; the name of *Mihirakula*, very clearly legible, in line 6; and, in line 9, the name of *Gōvinda*, the engraver of the record.]

No. 35; PLATE XXII.

MANDASOR STONE INSCRIPTION OF YASODHARMAN AND
VISHNUVARDHANA.

THE MALAVA YEAR 589.

THIS inscription, which I published, for the first time, in 1886, in the *Ind. Ant.* Vol. XV. p. 222 ff., is from a stone-tablet, which, when shewn to me in 1885, was in the possession of Sir Michael Filose, K.C.S.I., at Ujjain, but which had come originally from an old well, somewhere in the lands of *Mandasōr*,³ or more properly *Dasōr*, the chief town of the *Mandasōr* District of Scindia's Dominions in the Western *Mālwa* division of Central India, where it was found, in the course of repairs, built up with the inscribed surface inside. I could obtain no accurate information on the point; but possibly this is a large and ancient well, which immediately attracts attention, just inside the eastern entrance of the Fort.

The stone is a smooth and beautifully engraved tablet, apparently of slate-stone, measuring about 1' 11" broad by 1' 6½" high and 2½" thick. There are no sculptures on it, connected with the inscription. But, on the back, which is divided into two compartments by what seems to be either a spear with a curved handle, or a shepherd's crook, there are engraved in outline, very roughly,—at the upper corners, the sun on the proper right, and the moon on the proper left; and, lower down, on each side, a man on horse-back, facing towards the central dividing sculpture; the horseman on the proper right side carries in his left hand either a *chaurs* or fly-flap made from the bushy tail of the *Bos Grunniens*, or a *śankha* or conch-shell; the other horseman carries something in his right hand, but I could not distinguish the object. These sculptures were engraved, of course, when the tablet was fixed in the position in which it was discovered, with the inscribed


¹ Metre, Śībka (*Anushubbh*).² See page 145 above, note 2³ Supply *prastitāh*.⁴ See page 79 above, and note 1.

CORPUS INSCRIPTIONUM INDICARUM.

Vol. III

Plate xxic

C.—Mandasor Duplicate Pillar Inscription of Yasodharman



surface inwards; and it is owing to this position, that the inscription has remained in so perfect a state of preservation.—The writing covers the entire surface of the stone, with a margin of from 1" to 1½"; and is in a state of excellent preservation almost throughout, though there are just a few letters from which it was impossible to clear out the hard incrustation of lime, with which the writing was blocked up from beginning to end, sufficiently for them to come out quite perfectly in the ink-impression, and so in the lithograph. At the ends of lines 1, 2, and 3, a few letters have been lost by the edges of the stone being chipped here; and at some other places a few letters have been damaged in the same way. But the only place where the missing letters cannot be supplied, is at the commencement of line 16.—The average size of the letters is about ¼". The characters belong to the northern class of alphabets, and are of precisely the same type, being in fact engraved by the same hand, with those of the Mandasor duplicate pillar inscriptions of Yaśodharman, No. 33 above, page 142, and Plate xxii, and No. 34, page 149, and Plate xxiC. They include the very rare initial *au*, in *aulikara*, line 5; and the lingual *dh*, in *udāḍha* and *gāḍha*, line 7; *rāḍha*, line 11; and *ādha*, line 18.—The language is Sanskrit; and, except for the opening word *siddham*, and the two words at the end recording the name of the engraver, the entire inscription is in verse.—In respect of orthography, we have to notice (1) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *vanśa*, lines 6 and 9; *anśu*, line 9; *anśa*, line 11; and *abhvanśin*, line 12; (2) the use of the dental nasal, before *s*, in *bhūyānsi*, line 2, and *yaśānsi*, line 4; though we have the more usual *anusvāra* in *manāmsi*, line 22; (3) the doubling of *t*, in conjunction with a following *r*, e.g. in *kattra*, line 4; *kalattra*, line 11; and *pāriyātra*, line 16; and (4), the doubling of *dh*, in conjunction with a following *y* and *v*, in *addhyānsita*, line 16-17, and *addhvāni*, line 18, though not in other places.

The inscription refers itself, in the first instance, to the time of Yaśodharman,¹ here called a tribal ruler,² whose name is already on record from his duplicate pillar inscriptions at Mandasor, No. 33 above, page 142, and No. 34, page 149. It then mentions a king³ named Vishnupardhana, who, though he had the titles of *Rājādhirāja* and *Paramēśvara*, would appear to have acknowledged a certain amount of supremacy on the part of Yaśodharman. Vishnupardhana's family is mentioned as the lineage that had the *aulikara*-crest.⁴ The inscription is dated, in words, when the year five hundred and

¹ See page 145 above, note 2.

² *janendra*; *lit.* 'a lord of a people or tribe.'

³ *narādhipati*; *lit.* 'a chief ruler of men.'

⁴ *aulikara-lāchhana*.—I have not been able to obtain any explanation of the word *aulikara*; but it seems to denote either 'the hot-rayed (sun),' or 'the cool-rayed (moon).—As regards *lāchhana*, 'a mark, sign, token, spot,' which I render by 'crest,' it is the technical term for the principal emblem impressed by king³ on the copper-seals attached to their charters, and is quite distinct from the emblem on their *dhvajās* or banners. Thus, the Rāṭṭas of Saundatti and Belgaum had the *svarṇa-garuḍa-dhvaja* or 'banner of a golden Garuda,' but the *śindhura-lāchhana* or 'elephant-crest' (e.g. line 43 of the Tērdāi inscription of Śāka-Samvat 1045, &c.; *Ind. Ant.* Vol. XIV. p. 18, and p. 24, note 24). So also the Kādambas of Banawāsi, and also those of Goa, had the *śikhā-charāndra-dhvaja* or *vānara-mahādhwaja*, 'the banner of a monkey, or of (Hanumat) the king of monkeys,' but the *śikhā-lāchhana*, or 'lion-crest,' which latter appears on the seals of their grants and on their coins (e.g. line 28-29 of the Kargudari inscription of Śāka-Samvat 1030, *Ind. Ant.* Vol. X. p. 252; and line 9 of the Golihāḷi inscription, *Jour. Bo. Br. R. As. Soc.* Vol. IX. p. 296; see also, for the seals of their grants, *ib.* p. 230, No. 8, and *Ind. Ant.* Vol. XIV. p. 288; and, for their coins, *Jour. Bo. Br. R. As. Soc.* Vol. X. p. xxiv.) The Chalukyas, in all their branches, had the *śikhā-lāchhana*

eighty-nine had expired from the tribal constitution of the **Mālavas**, and, therefore, when the year five hundred and ninety (A.D. 533-34) was current; but no further details of the date are given. The opening invocations are addressed to the god Śiva. But the record itself is non-sectarian; the object of it being only to record the construction of a large well by a person named **Dakṣha**, the younger brother of Dharmadōsha, who was a minister of Viṣṇuvardhana, in memory of their deceased uncle Abhayadatta, who had formerly held the same office for the tract of country bounded by the **Vindhya**s and the **Pāriyātra** mountain, and the (**Western**) **Ocean**.

The genealogy of this family of ministers is given; and it includes a somewhat noticeable name in that of **Bhānuguptā**, the wife of Dakṣha's grandfather, Ravikīrtti. Her date would be just about one generation before that of the king **Bhānugupta**, for whom we have the date of Gupta-Sarṅvat 191 (A.D. 510-11) from the Ēraṇ posthumous pillar inscription of Gōparāja, No. 20 above, page 91, and Plate xiiB.; and the coincidence of name and time is such, that it is almost impossible not to imagine some family connection between him and her. Bhānugupta, of course, must have been a Kshatriya; and Bhānugupta's husband, Ravikīrtti, was evidently a Brāhmaṇ. But the ancient Hindu law authorised the marrying of Kshatriya wives by Brāhmaṇs. And we have an epigraphical instance of this practice in the Ghaṭōtkacha cave inscription of Hastibhōja, a minister of the **Vākāṭaka Mahārāja** **Dēvasēna**; it tells us that Hastibhōja's ancestor, the Brāhmaṇ **Sōma**, "in accordance with the precepts of revelation and of tradition" married a Kshatriya wife, through whom Hastibhōja was descended, in addition to some other wives of the Brāhmaṇ caste, whose sons, and their descendants, applied themselves to the study of the **Vēdas**.¹

TEXT.²

- 1 Siddham [11*] Sa³ jayati jagatām patih Pinākl smita-rava-gtishu
yasya danta-kāntih | dyutir-iva taditām niṣi sphurantī tirayati
cha sphuṭayaty-adaś=cha viśvam || Svayambhūr⁴=bhūtānām sthiti-
laya-[samu]-
- 2 tpatti-vidhishu prayuktō yēn-ājñām vahati bhuvanānām vidhṛitayē |
pitṛitvam ch=āntō jagati garimāṇam gamayatā sa Śambhur=bhūyānsi
pratidīśatu bhadraṇi bhava[tām] || Phaṇa⁵=maṇi-guru-bhār-[ākk]r[ā].
- 3 nti-dūr-āvanamram sthagayati rucham-indōr=mmaṇḍalam yasya mūrdhnām [1*]
sa śirasi vinibadhnan-randhriṇm=asthi-mālām srijatu bhava-srijō vaḥ
klēśa-bhaṅgam bhujāṅgaḥ || Shashṭya⁶ sahasraiḥ Sagar-ātmanām
khāta[h]

¹ 'boar-crest,' which appears on the seals of all their charters, and on their coins; and the special connection of the *idākhana* with the *śāsana* or 'charter,' is shewn by a passage in lines 73 ff. of the Korumelli grant of Rājārāja II., "on whose charter the mighty form, that of the first boar, of (the god) Viṣṇu, which lifted up the entire circle of the earth on the tip of (its right-hand) tusk, became in a pleasing way the crest" (*id.* Vol. XIV. p. 85)

² *Archaeol. Surv. West. Ind.* Vol. IV. p. 140 and note.

³ From the original stone.

⁴ Metre, Pushpitāgrā.

⁵ Metre, Śikhariṇ.

⁶ Metre, Māliṇ.

⁷ Metre, Upajāti of Indravajrā and Upēndravajrā.

- 4 kha-tulyām rucham-ādadhānaḥ | asy-ōdapan-ādhipatēs-chirāya yaśānsi pāyāt-
payaśām vidhātā || Atha¹ jayati janēndrah śrī-Yaśōdharmma-
nāmā pramada-vanam-iv-āntaḥ śatru-sainyam vigāhya vrapa-
- 5 kisalaya-bhaṅgair-yyō-ṅga-bhūshām vidhattē taruṇa-taru-latā-vad-vīra-kirttr-
vvināmya || Ajau² jitt vijayatē jagatm-punaś-cha śrī-Vishṇuvarddhana-
narādhipatiḥ sa ēva | prakhyāta zulikara-lācchhana ātma-
- 6 vaśō yēn-ōdit-ōdita-padam gamitō garlyāḥ || Prāchō nripān=su-brihataś-
cha bahūn-udcchah sāmna yudhā cha vaśa-gān-pravidhāya yena [1*]
nām-āparam jagati kāntam-adō durāpam rājādhirāja-paramē-
- 7 svāra ity-udōḍham || Snigdha³-śyām-āmbud-ābhāih sthagita-dinakritō
yajvanām-āya-dhūmair-ambhō-mēghyam Maghōn-āvadhishu vidadhātā
gāḍha-sampanna-sasyāḥ | sarṇharshād-vāpinīnām kara-rabhāsa-hṛit-ō-
- 8 dyāna-chūt-ānkur-āgrā rājanvantō ramantē bhujā-vijitā-bhuvā bhūrayō yēna
dētāḥ || Yasy⁴-ōtkētubhir-unmada-dvipa-kara-vyāviddha-lōdhra-drumair-
uddhūtēna van-ādhvani dhvani-nadad-Vindhyādri-randhrāir-bbalaiḥ balē-
- 9 ya-chchhavi-dhūmarēṇa rajasā mand-āṅsu samlakshyatē paryāvritta-
śikhṇḍi-chandraka iva dhyāman ravēr-mmaḍdalam || Tasya⁵
prabhōr-vvaśa-kritān nripānām pād-āśrayād-vīruta-puṇya-kirttiḥ |
bhṛityāḥ sva-naibhṛitya-jit-ā-
- 10 ri-shatka āst-d-vastyan-kila Shashthidattaḥ || Himavata⁶ iva Gāngas-
tuṅga-namrah pravāhaḥ śasabhṛita iva Rēvā-vāri-rāsīḥ prathlyān [1*]
param-abhigamanlyāḥ suddhimān-anvavāyō yata udita-gari-
- 11 mnaś-tāyatē Naigamānām || Tasy⁷-ānukūlah kulajāt-kalattrāt-sutah
prasūtō yaśasām prasūtīḥ | Harēr-iv-āṅśam vaśinām var-ārham
Varāhadāsam yam-udāharanti || Sukṛiti⁸-vishayi-tuṅgam rūḍha-mūlam
- 12 dharāyām sthitim-apagata-bhaṅgām sthēyasim-ādadhānam [1*] guru-śikharam
iv-ādrēs-tat-kulam sv-ātma-bhūtyā ravir-iva Ravikrttiḥ su-prakāśam
vyadhata || Bibhrat⁹ subhram-a-bhraṅśi smārttam vartm-ōchitam
satām [1*] na visambvā(va)-
- 13 ditā yēna Kalāv-āpi kullnatā || Dhuta-dhī-didhiti-dhvāntān-havirbhujā
iv-ādharān [1*] Bhānuguptā tataḥ sādhrvī tanayāms-trīn-ājjanat ||
Bhagavaddōsha ity-āst-prathamah kāryya-vartmasu | āḷa-
- 14 mbanam bāndhavanām-Andhakānām-iv-ōddhavaḥ || Bahu¹⁰-naya-vidhi-Vēdhā
gahvarē-py-ārtha-mārggē Vidura iva vidūram prēkshayā prēkshamāṇah |
vachana-rachana-bandhē samskrita-prākṛitē yaḥ kavibhir-udi-
- 15 ca-rāgam glyatē gīr-abhijñāḥ || Prapīdhi-dṛig-anugantrā yasya bauddhēna
ch-ākshṇā na niśi tanu davyō v-āsty-a-driṣṭam dhantryām [1*]
padam-udayi dadhānō-nantaram tasya ch-ābhūt-sa bhayam-Abhayadattō
nāma

¹ Metre, Mālinī.² Metre, Vasantatilaka; and in the next verse.³ Metre, Sragdharā.⁴ Metre, Śārdūlavikṛḍita.⁵ Metre, Indravajrā.⁶ Metre, Mālinī.⁷ Metre, Upajāti of Indravajrā and Upēndravajrā.⁸ Metre, Mālinī.⁹ Metre, Ślōka (Anashṭubh); and in the next two verses.¹⁰ Metre, Mālinī; and in the next verse.

- 16 *chi[nva?]*n-prajānām || **Vindhyasy**¹-āvandhya-karmmā śikhara-taṭa-patāt-
pāṇḍu-Rēv-āmbu-rāsēr-ggōlangūlaiḥ sa-hēlam pluti-namita-tarōḥ
Pāriyāttasya ch=ādrēḥ | ā **sindhōr**=antarālam nija-śuchi-sachiv-
āddhya-
- 17 *sit-ānēka-dēsām* rājasthāniya-vṛit[*t**]yā suragurur=iva yō varṇinām
bhūtayē=pāt || **Vihita**²-sakala-varṇ-āsankaram śānta-ḍlmbam Kṛita iva
kṛitam=ētad-yēna rājyam nirādhi | sa dhuram=ayam=idānlm
- 18 **Dōsbakumbhasya** sūnur-guru vahati tad-ūḍhām dharmmatō Dharmmadō
shah || **Sva-sukham**=an-ativāchchha(fichha)n-durggamē=ddhvany-a-saṅgām
dhuram=ati-guru-bhārām yō dadhad=bhartur=arthē | vahati nripati-vēsham
kēvalam lakshma-māttram
- 19 *valinam=iva vilambam* kambalam bāhulēyah || **Upahita-hita-rakṣā**-maṇḍanō
jāti-ratnair=bhuja iva pṛithul-āmsas-tasya **Dakṣah** kanlyān [*1**]
mahad-idam=udapānam khātayām-āsa bibhra-
- 20 *ch=chhṛiti-hṛidayā*-nitānt-ānandi nirdōsha-nāma || **Sukh**³-āsṛēya-chchhāyam
paripati-hita-svādu-phala-dam gajēndrēṅ=āruggam drumam=iva Kṛitāntēna
balinā | pitṛivyaḥ prōddīśya priyam=Abhayadattam pṛi-
- 21 *thu-dhiyā* prathlyas=tēn-ēdam kuśalam=iha karmm-ōparachitam || **Pañchasa**⁴
śatēshu śaradām yātēshv-ēkām-na-navati-sahitēshu | **Mālava-gaṇa**-sthiti-
vaśāt=kāla-jñānāya likhitēshu || Ya-
- 22 *smn*⁵-kālē kala-mṛidu-girām kōkilānām pralāpā bhindant=iva Smara-
śara-nibbāḥ prōshitānām manāmsi | bhṛing-āllnām dhvanir=anu-vanam
bhāra-mandraś=cha yasminn-ādhūta-jyam dhanur=iva nadach=chhṛyātē
pushpa-
- 23 *kētōḥ* || **Priyatama**⁶-kupitānām rāmayau=baddha-rāgam kisalayam=iva
mugdham mānasam maninām [*1**] upanayati nabhasvān=māna-bhaṅgāya
yasmn=kusuma-samaya-māsē tatra nirmāpitō=yam ||
- 24 *Yavat*⁷-tungair=udanvān-kirāṇa-samudayam sānga-kāntam taraṅgair=ālingann-
indu-bimbam gurubhir=iva bhujaiḥ saṁvidhattē suhṛittām [*1**] bibhrat-
saudh-ānta-lēkhā-valaya-parigatim muṇḍa-mālām=iv-āyam sat-kūpas-
tāvad=ā-
- 25 *stām*=amrita-sama-rasa-svāchchha-vishyandit-āmbuḥ || **Dhlmām**(n)⁸ **Dakṣhō**
dakṣiṇāḥ satya-sandhō hṛtmāmch=chhūrō vṛiddha-sēvī kṛitajñāḥ |
baddh-ōtsāhaḥ svāmi-kāryyēshv-a-khēdī nirdōshō-yam pātu dharmmam
chirāya || Utklṛṇṇā⁹ Gōvindēna ||

TRANSLATION.

Perfection has been attained! Victorious is he, (the god) Pinākin, the lord of (all) the worlds,—in whose songs, hummed with smiles, the splendour of (his) teeth, like the lustre of lightning sparkling in the night, envelops and brings into full view all this

¹ Metre, Sragdharā.² Metre, Sīkharīṅ.³ Metre, Mandākṛāntā.⁴ Metre, Sragdharā.⁵ Supply *pṛaiasth*.⁶ Metre, Mālinī; and in the next two verses.⁷ Metre, Āryā.⁸ Metre, Mālinī.⁹ Metre, Śālinī.

universe! May he, (the god) Śambhu, confer many auspicious gifts upon you,—employed by whom in the rites of (*effecting the*) continuance and the destruction and the production of (*all*) things that exist, (the god) Svayambhū, is obedient to (*his*) commands, for the sake of the maintenance of (*all*) the worlds; and by whom, leading (*him*) to dignity in the world, he has been brought to the condition of being the father (*of the universe*)! May the serpent of the creator of existence¹ accomplish the allayment of your distress,—(that serpent) the multitude of whose foreheads, bowed down afar by the pressure of the heavy weight of the jewels in (*their*) hoods, obscures the radiance of the moon (*on his master's forehead*); (*and*) who (*with the folds of his body*) binds securely on (*his master's*) head the chaplet of bones which is full of holes (*for stringing them*)! May the creator of waters,² which was dug out by the sixty thousand sons of Sagara, (*and*) which possesses a lustre equal to (*that of*) the sky, preserve for a long time the glories of this best of wells!

(Line 4.)—Now, victorious is that tribal ruler,³ having the name of the glorious Yaśōdharman,⁴ who, having plunged into the army of (*his*) enemies, as if into a grove of thornapple-trees, (*and*) having bent down the reputations of heroes like the tender creepers of trees, effects the adornment of (*his*) body with the fragments of young sprouts which are the wounds (*inflicted on him*).

(L. 5.)—And, again, victorious over the earth is this same⁵ king of men,⁶ the glorious Viṣṇuvarḍhana, the conqueror in war; by whom his own famous lineage, which has the *aulikara*-crest,⁷ has been brought to a state of dignity that is ever higher and

¹ *bhava-sṛj*.—Originally, Brahman was the creator; Viṣṇu, the preserver; and Śiva, the destroyer. But of course the Vaiṣṇavas and the Śaivas invested their own special gods with all three attributes. As regards Śiva, we may also refer to line 51 of the Aṅgā grant of Śāliditya VII. of the year 447, No. 39 below, Plate xxv., where, under the name of Paramēvara, he is again clearly referred to as the creator. While, as regards Viṣṇu, in the *Viṣṇu-Purāna*, book I, chap. ii. (Hall's edition of Wilson's Translation, Vol. I, p. 41), he is described as himself becoming Brahman, and so engaging in the creation of the universe.—That *bhava-sṛj* here denotes Śiva, is shown by the general purport of the preceding two verses, and especially by the mention of the chaplet of bones in this verse. He is always represented with a necklace of skulls, a serpent hanging round his neck, and the crescent moon on his forehead.

² The ocean. The allusion in this verse is to the legend that the bed of the ocean was excavated by the sons of Sagara in their search for their father's *asvatthā*-horse, which was stolen from their custody by the sage Kapila, and was only found by them when they had dug down through the earth into the lower regions. Kapila, in his anger, reduced them to ashes, but subsequently restored the horse on the intercession of Aṅgumat, the grandson of Sagara. The obsequies, however, of the sons of Sagara remained unperformed, and their transfer to heaven was barred, until Bhagratna, the grandson of Aṅgumat, brought the river Ganges down from heaven, and led it over the earth to the chasm made by the sons of Sagara. Flowing down through this, it washed their bones and ashes; by which they were raised to heaven. And, as such of its waters as remained in the chasm constituted the ocean, the latter was called *sagara* in commemoration of Sagara and his descendants.

³ *janendra*; see page 151 above, note 2.

⁴ See page 145 above, note 2.

⁵ This expression looks at first sight as if Yaśōdharman and Viṣṇuvarḍhana were one and the same person. But the general structure of this verse, as well as the use of the two distinct titles *janendra* and *narādhipati* and of the expression *śma-saśī*, shows that this is not the case. "This same" simply means "this reigning king," in whose time and territory the inscription is written.

⁶ *narādhipati*; see page 151 above, note 3.

⁷ *aulikara-lāchhana*; see page 151 above, note 4.

higher. By him, having brought into subjection, with peaceful overtures and by war, the very mighty kings of the east and many (*kings*) of the north, this second name of "supreme king of kings¹ and supreme lord,"² pleasing in the world (*but*) difficult of attainment, is carried on high. Through him, having conquered the earth with (*his own*) arm, many countries,—in which the sun is obscured by the smoke, resembling dense dark-blue clouds, of the oblations of the sacrifices; (*and*) which abound with thick and thriving crops through (the god) Maghavan pouring cloudfuls of rain upon (*their*) boundaries; (*and*) in which the ends of the fresh sprouts of the mango-trees in the parks are eagerly plucked in joy by the hands of wanton women,—enjoy the happiness of being possessed of a good king. Through the dust, grey like the hide of an ass,—stirred up by his armies, which have (*their*) banners lifted on high; (*and*) which have the *lôdhra*-trees³ tossed about in all directions by the tusks of (*their*) infuriated elephants; (*and*) which have the crevices of the *Vindhya* mountains made resonant with the noise of (*their*) journeying through the forests,—the orb of the sun appears dark (*and*) dull-rayed, as if it were an eye in a peacock's tail reversed.⁴

(L. 9).—The servant of the kings who founded the family of that lord, was Shash-tidatta,—the fame of whose religious merit was known far and wide through the protection of (*their*) feet; who by his resoluteness conquered the six enemies (*of religion*);⁵ (*and*) who was indeed very excellent. As the torrent, flowing high and low, of (the river) *Gāngā* (*spreads abroad*) from (the mountain) *Himavat*, (*and*) the extensive mass of the waters of (the river) *Rēvā* from the moon,—(*so*) from him, whose dignity was manifested, there spreads a pure race of *Naigamas*, most worthy to be sought in fellowship.

(L. 11).—Of him, from a wife of good family, there was born a son, resembling him (*in good qualities*), the source of fame,—whom, (*being named*) *Varāhadāsa*, (*and*) being full of self-control (*and*) of great worth, people speak of as if he were an (*incarnate*) portion of (the god) *Hari*.

(L. 11).—As if it were the sun (*illuminating*) the mighty summit of a mountain, *Ravikṛtti* with the wealth of his character illumined that family, which was made eminent by men who combined good actions with worldly occupations; which had its foundations well established in the earth; (*and*) which maintained a very firm position of endurance that was free from (*any risk of*) being broken;—(*Ravikṛtti*), by whom, sustaining the pure (*and*) undeviating path of traditional law that is acceptable to good people, nobility of birth was not made a thing of false assertion (*even*) in the *Kali* age. From him, (*his*) chaste wife *Bhānuguptā* gave birth to three sons, who dispelled the darkness (*of ignorance*) with the rays of (*their*) intellects,—as if (*she had produced three*) sacrifices from a fire.

(L. 13).—The first was *Bhagavaddōsha*, the prop of his relatives in the paths of religious actions, just as *Uddhava* (*was*) of the *Andhakas*,—who was a very *Vēdhas* in displaying much prudence in the hard-to-be-traversed path of the meaning (*of words*); who, like *Vidura*,⁶ always looked far ahead with deliberation; (*and*) who is with great

¹ *Rājādhirāja*; see page 35 above, note 7.

² *Paramitvara*, see page 10 above, note 3.

³ *lôdhra*, also *rôdhra*; the tree *Symplocos Racemosa*.

⁴ *i.e.* "looked at from the wrong side of the feathers."

⁵ The *ari-shatka* or *ari-shad-varga*, 'the aggregate of six hostile things,' *vis.* desire, wrath, covetousness, bewilderment, pride, and envy, which impede the practice of religion.

⁶ An epic hero, the younger brother of *Dhritarāshṭra* and *Pāṇḍu*, described as the wisest of all prudent and sagacious people.

pleasure sung of by poets, in Sanskrit and Prākṛit construction of the arrangement of sentences, as being well versed in speech.

(L. 15).—And after him there came that (*well-known*) Abhayadatta, maintaining a high position on the earth, (*and*) collecting (*in order to dispel it*) the fear of (*his*) subjects (?);—by whose eye of intellect, which served him like the eyes of a spy, no trifle, however remote, remained undetected, (*even*) at night;—(Abhayadatta), of fruitful actions, who like (Bṛihaspati) the preceptor of the gods, to the advantage of those who belonged to the (*four recognised*) castes, with the functions of a *Rājasthānīya*¹ protected the region, containing many countries presided over by his own upright counsellors, which lies between the *Vindhya* (mountains), from the slopes of the summits of which there flows the pale mass of the waters of (the river) *Rēvā*, and the mountain *Pāriyātra*, on which the trees are bent down in (*their*) frolicsome leaps by the long-tailed monkeys, (*and stretches*) up to the (*western*) Ocean.

(L. 17).—Now he, Dharmadōsha, the son of Dōshakumbha,—by whom this kingdom has been made, as if (*it were still*) in the Kṛita-age, free from any intermixture of all the castes, (*and peaceable through*) having hostilities allayed, (*and*) undisturbed by care,—in accordance with justice proudly supports the burden (*of government*) that had (*previously*) been borne by him;²—(Dharmadōsha), who,—not being too eager about his own comfort, (*and*) bearing, for the sake of his lord, in the difficult path (*of administration*), the burden (*of government*), very heavily weighted and not shared by another,—wears royal apparel only as mark of distinction (*and not for his own pleasure*), just as a bull³ carries a wrinkled pendulous dew-lap.

(L. 19).—His younger brother, *Dakṣha*,—invested with the decoration of the protection of friends, as if he were (*his*) broad-shouldered (*right*) arm (*decorated*) with choice jewels; (*and*) bearing the name of “the faultless one,” which causes great joy to the ear and heart,—caused to be excavated this great well. This great (*and*) skilful work was achieved here by him, who is of great intellect, for the sake of his paternal uncle, the beloved Abhayadatta, who was cut off (*before his time*) by the mighty (god) Kṛitānta, just as if he were a tree, the shade of which is pleasant to resort to (*and*) which yields fruits that are salutary and sweet through ripeness, (*wantonly*) destroyed by a lordly elephant

¹ *Rājasthānīya*, lit. ‘one who belongs to a *Rājasthāna* or king’s abode;’ or perhaps ‘one who occupies the position of a *Rāja*,’ is a technical official title, the exact grade of which remains to be determined. The explanation of the word in Kāśhēmendra’s *Lāṅkāra*, iv., as given by Dr. Bühler (*Ind. Ant.* Vol. V. p. 207) is *prajā-pālan-ārtham-udvāhātī rakshayati cha sa rājasthānīyah*, “he who carries out the object of protecting subjects, and shelters them, is called a *Rājasthānīya*, i. e. ‘a viceroy.’” But, though ‘viceroy’ is a fair enough rendering of the word on etymological grounds, it seems to be in reality too exalted a title to be a suitable equivalent. In line 21 of the Māliya grant of the *Mahārāja* Dharmasēna II. of the year 552, No. 38 below, Plate xxiv., and in line 9 of the *Dōṣa* Baraṅg inscription of Jivitagupta II., No. 46 below, Plate xxix.B. (where Dr. Bhagwanlal Indraji proposed to render it by ‘political agent, or regent’), the *Rājasthānīya* is mentioned rather low down in the list of officials; so also in line 33 of the Bhagalpur grant of Nārāyaṇapāla (*Ind. Ant.* Vol. XV. p. 306), and in the passage in connection with which it was explained by Dr. Bühler.

² *sa*. Abhayadatta.—Dōshakumbha, the father of Dharmadōsha, must be the younger brother of Abhayadatta, and the third and youngest of the sons of Ravikṛiti and Bhānugupta.

³ *śūbhīya*; this meaning is not given in Monier Williams’ Sanskrit Dictionary; and I owe it, and the explanation of one or two other passages in this inscription, to Pandit Durga Prasad, of Jaipur.

(L. 21.)—Five hundred autumns, together with ninety less by one, having elapsed from (*the establishment of*) the supremacy¹ of the tribal constitution of the *Mâlavas*, (*and*) being written down in order to determine the (*present*) time ;—in the season² in which the songs, resembling the arrows of (the god) Smara, of the cuckoos, whose utterances are low and tender, cleave open, as it were, the minds of those who are far away from home ; and in which the humming of the flights of bees, sounding low on account of the burden (*that they carry*), is heard through the woods, like the resounding bow of (the god *Kâmadêva*) who has the banner of flowers, when its string is caused to vibrate ;—in the season in which there is the month of the coming on of flowers, when the wind, soothing the affectionate (*but*) perverted thoughts of disdainful women who are angry with their lovers, as if they were charming fresh sprouts arrayed in colours, devotes itself to breaking down (*their*) pride,—in that season this (*well*) was caused to be constructed.

(L. 24.)—As long as the ocean, embracing with (*its*) lofty waves, as if with long arms, the orb of the moon, which has its full assemblage of rays (*and is more*) lovely (*than ever*) from contact (*with the waters*), maintains friendship (*with it*),—so long let this excellent well endure, possessing a surrounding enclosure of lines at the edge of the masonry-work, as if it were a garland worn round a shaven head, (*and*) discharging pure waters the flavour of which is equal to nectar !

(L. 25.)—May this intelligent *Dakṣha* for a long time protect this act of piety,—(*he who is*) skilful, true to (*his*) promises, modest, brave, attentive to old people, grateful, full of energy, unwearied in the business-matters of (*his*) lord, (*and*) faultless. ! (*This eulogy*) has been engraved by *Gôvinda*.

No. 36; PLATE XXIII A.

ERAN STONE BOAR INSCRIPTION OF TORAMANA.

THIS inscription was discovered in 1838 by Captain T. S. Burt, of the Engineers, and was first brought to notice in the same year, in the *Four. Beng. As. Soc.* Vol. VII. p. 631 ff., where Mr. James Prinsep published his reading of the text, and a translation of it,³ accompanied by a lithograph (*id.* Plate xxx.), reduced from an ink-impression made by Captain Burt.—And in 1861, in the same Journal, Vol. XXX. p. 20 ff., Dr. FitzEdward Hall published his revised reading of the text, from the original pillar, and a translation of it.

This is another inscription from *Ēraṇ*⁴ in the Khurât Sub-Division of the *Sâgar* District in the Central Provinces. It is on the chest of a colossal red-sandstone statue of a Boar, about eleven feet high, representing the god *Vishṇu* in his incarnation as such, that stands, facing east, in the portico of a ruined temple at the south end of the well-known group of temples about half a mile to the west of the village.⁵

The Boar is covered all over with elaborate sculptures, chiefly of *Ṛishis* or saints

¹ *vasât* ; but it is very difficult to find a really satisfactory meaning for this word in this passage.

² *i.e.* the spring.

³ The translation is reprinted in Thomas' edition of Prinsep's *Essays*, Vol I. p. 249 f.

⁴ See page 18 above, and note 1.

⁵ *Archæol. Surv. Ind.* Vol. X. page 82 ff., and Plates xxv. and xxvi.

clinging to its mane and bristles.¹ It has the earth, represented as a woman, hanging on, in accordance with the legend, to its right-hand tusk; and over its shoulders there is a small four-sided shrine, with a sitting figure in each face of it. There are several very serious cracks in the Boar; one of which, right through the centre of it from front to back, shews in the lithograph published herewith. The surface on which the inscription is, is slightly concave.—The writing, which covers a space of about 2' 9" broad by 10½" high, has in one or two places suffered a good deal from the weather; but, except where a few letters have been entirely destroyed through the stone breaking away at the edges of the crack mentioned above, it can be read with certainty throughout. The bottom line is about 6' 0" above the level of the ground.—The average size of the letters is about ¾". The characters belong to the northern class of alphabets, and are very similar in type to those of the Érap pillar inscription of Budhagupta, No. 19 above, Plate xiiiA. The two methods of forming the letter *r*, in combination with a following consonant, are illustrated, on the one hand, by *paryanta*, line 5 and, on the other, by *ghârṇṇita*, line 1, *pûrvvâyam*, line 3, and *artha*, line 7.—The language is Sanskrit; and the inscription is in verse as far as the end of the date in line 3, and the rest in prose.—In respect of orthography, the only point that calls for notice is the doubling of *k*, *t*, and *dh*, in conjunction with a following *r*; e.g. in *krivîṣṇa*, line 6; *maitrîyânîya*, line 3; *pauptrasya*, line 4; (but not in *bkrâtrâ*, line 6); and *mahâddhrah*, line 1.

The inscription refers itself to the reign of Tôramâna. It is dated, in words, in the first year of his reign, without any reference to an era; and on the tenth day, without any specification of the fortnight, of the month Phâlguna (February-March). It is a Vaishṇava inscription. And the object of it is to record the building of the temple, in which the Boar stands, by Dhanyavishṇu, the younger brother of the deceased Mahârâja Mâtrivishṇu.

The mention of Mâtrivishṇu in this inscription as deceased, is of importance, as shewing that Tôramâna comes, so far as his possession of Eastern Mâlwa is concerned, shortly after Budhagupta, in whose time Mâtrivishṇu, then alive, in conjunction with Dhanyavishṇu set up the column that bears Budhagupta's inscription of the year 165, No. 19 above, page 88.

TEXT.*

- 1 Ô.n [11^o] Jayati² dharany-uddharanê ghana-ghôn-âghâta-ghûrṇṇita-mahâddhrah
dêvô varâha-mûrttis-traulôkya-mahâ-griha-stambhah [11^o] Varshê³ prathamê
prithivîm
- 2 prithu-krîttau prithu-dyutau mahârâjâdhirâja-îrî-Tôramânê praśâsati 1(11)
Phâlguna-divasê⁴ dasamê | ity-êvam râjyavarsha-mâsa-dinai⁵ [11^o] êtasyâṃ
- 3 pûrvvâyam | sva-lakshânair-yukta-pûrvvâyam⁶ 1(11) Sva-karm-âbhiratasya
kratu-yâjinô-dhîta-svâdhyâyasya vipr-arshêr-Mmaitrîyanîya-vrîshabhasya-
Êndravishṇôḥ prapaupttrasya |

¹ I noticed a similar boar, almost entirely buried, by the roadside, about half way between Sâschi and Udayagiri; but I had no means of raising it to ascertain whether there is any inscription on it.

² From the original stone.

³ Metre, Âryâ.

⁴ This sentence is in prose, though it commences like a verse in the Âryâ metre.

⁵ Metre, Âryâ.

⁶ Supply *tithau*

- 4 pitur-gup-ānukāripō Varuṇavishṇōḥ pauttrasya pitaram-anu-jātasya
sva-vamśa-vridhī-hētōr-Harivishṇōḥ puttrasy-ātyanta-bhagavad-bhaktasya
Vidhātur-ichchhaya¹ !¹
- 5 svayamvaray-ēva rāja-lakshmy-ādhitgatasya chatuh-samudra-paryanta-prathita-
yaśasaḥ akshīṇa-māna-dhanasy-ānēka-śatru-samara-jishṇōḥ mahār[ā²]ja-
Mātrivishṇōḥ
- 6 svar-ggatasya bhrātr-ānujēna | tad-anuvīdhāyina tat-prasāda-parigrihītēna³
Dhanyavishṇunā tēn-aiva [sa]h-āvibhakta-puṇya-kkriyēṇa mātāpitrōḥ
- 7 puṇy-āpyāyan-ārtham-ēsha bhagavatō varāha-mūrttēr-jagat-parāyanasya
Nārāyaṇasya śilā⁴-prās[ādah] sva-vishay[ē]-smīn-Airikiṇē kārītaḥ I(II)
- 8 Svasty-astu gō-brāhmaṇa-purōgābhyaḥ sarvva-prajābhya [i]ti ||

TRANSLATION.

Om! Victorious is the god (Vishṇu), who has the form of a Boar,⁴—who, in the act of lifting up the earth (*out of the waters*), caused the mountains to tremble with the blows of (*his*) hard snout; (*and*) who is the pillar (*for the support*) of the great house which is the three worlds!⁵

(Line 1.)—In the first year; while the *Mahārājadhirdja*, the glorious *Tōramāna*, of great fame (*and*) of great lustre, is governing the earth;—

(L. 2.)—On the tenth day of (the month) Phālguna;—on this (*lunar day*), (*specified*) as above by the regnal year and month and day, (*and*) invested as above with its own characteristics;—

(L. 3.)—By *Dhanyavishṇu*,—the younger brother, obedient to him (*and*) accepted with favour by him, of the *Mahārāja Mātrivishṇu*, who has gone to heaven, who was excessively devoted to the Divine One; who, by the will of (the god) Vidhātṛ, was approached (*in marriage-choice*) by the goddess of sovereignty, as if by a maiden choosing (*him*) of her own accord (*to be her husband*); whose fame extended up to the borders of the four oceans; who was possessed of unimpaired honour and wealth; (*and*) who was victorious in battle against many enemies;—who was the son of the son's son of Indravishṇu, who was attentive to his duties, who celebrated sacrifices; who practised private study (*of the scriptures*); who was a Brāhmaṇa saint; (*and*) who was the most excellent (*of the followers*) of the Maitrāyaṇya (*śākhā*);—who was the son's son of Varuṇavishṇu, who imitated the virtuous qualities of (*his*) father;—(*and*) who was the son of Harivishṇu, who was the counterpart of (*his*) father in meritorious qualities,⁶ (*and*) was the cause of the advancement of his race;—

¹ This mark of punctuation is unnecessary.

² This word is followed by a cross-mark, which indicates that *tēn-aiva [sa]h-āvibhakta-puṇya-kkriyēṇa* should have stood here, before *dhanyavishṇunā*.


³ Prinsep read *nārāyaṇasy-ādirna*; and Hall, *nārāyaṇasy-ādirnak*. They were led into this by the engraver having run the right stroke of the *l* in *śilā* too high up, probably through his tool slipping.

⁴ The allusion is to his incarnation as a boar, when he plunged into the great ocean and rescued the earth, which had been carried off and hidden there by the demon Hiranyāksha.

⁵ Compare the similar invocation of Śiva, in Śaiva inscriptions, as "the foundation-pillar for the erection of the city which is the three worlds;" *eg.* in line 1 f. of the Aihole inscription of Śaka-Samvat 1091 (*Ind. Ant.* Vol. IX. p. 97)

⁶ *pitaram-anu-jātasya*; see page 90 above, note 3.


A.—Eran Boar Inscription of Toramana.



2
4
6
8

SCALE .80

B.—Gwalior Inscription of Mihirakula.



2
4
6

(L. 6.)—(By this **Dhanyavishṇu**), accomplishing, in unison with (*the previously expressed wishes of*) him,¹ a joint deed of religious merit, for the sake of increasing the religious merit of (*his*) parents, this stone temple of the divine (*god*) Nārāyaṇa, who has the form of a Boar (*and*) who is entirely devoted to (*the welfare of*) the universe, has been caused to be made in this his own *viśaya* of **Airikīṇa**.

(L. 8.)—Let prosperity attend all the subjects, headed by the cows and the Brāhmaṇs!

No. 37; PLATE XXIII B.

GWALIOR STONE INSCRIPTION OF MIHIRAKULA.

THIS inscription appears to have been discovered by General Cunningham, and was first brought to notice in 1861, in the *Four. Beng. As. Soc.* Vol. XXX. p. 267 ff., where Dr. Rajendralala Mitra published his reading of the text, and a translation of it, from an ink-impression taken by General Cunningham, of which, in the following year,—as an accompaniment to Dr. Rajendralala Mitra's paper on "Vestiges of the kings of Gwālior," in the *Four. Beng. As. Soc.* Vol. XXXI. p. 391 ff.,—a reduced lithograph was published (*id.* Plate i. No. 1).

The inscription is on a broken red-sandstone slab, now measuring about 2' 8½" broad by 5½" high, that was found built into the wall in the porch of a temple of the sun in the fortress at Gwālior² (properly Gwālhêr), the capital of the dominions of Scindia in Central India; it is now in the Imperial Museum at Calcutta. When the stone was first found, two or three letters had already been broken away and lost at the beginning of each line; and, since then, it has suffered a still more serious injury, in part of line 7, and the whole of lines 8 and 9, being cut away and destroyed in trimming the stone and fixing it, I suppose, in some other building, after the time when it was first found and before its rescue and transfer to the Museum.

The writing, which covers the entire face of the stone, except for a margin of about an inch at the top and on the right side, is in a state of excellent preservation almost throughout.—The average size of the letters is about ⅜". The characters belong to the northern class of alphabets; and, though differing a little in actual execution, are of the same type with those of the preceding inscription of Tōramāṇa. The two methods of forming *r*, in combination with a following consonant, are illustrated, on the one hand, by *śauryaḍḍ*, line 3, and, on the other, by *chakrō-rīti-hartīḍḍ*, line 2, and *abhiṣuddha-māna*, line 4.—The language is Sanskrit; and the inscription is in verse throughout.—In respect of orthography, all that calls for special notice is the use of the *upadhāntya* once, in *amsubhiḥ-pamkajānām*, line 2.

The inscription refers itself to the reign of **Mihirakula**. It is dated, in words, in the fifteenth year of his reign, without any reference to an era; and in the bright fortnight of the month Kārttika (October-November), but without any specification of the day of the fortnight or month. It is an inscription of solar worship. And the object of it is to

¹ *i.e.* the deceased Mātrivishṇu.

² The 'Gwalior' of maps, &c. Indian Atlas, Sheet No. 51. Lat. 26° 13' N.; Long. 78° 12' E.—For the ancient names of the place, see the next note.

record the building of a temple of the Sun, by a person named **Mâtrichêta**, on the mountain called **Gôpa**, i.e. the hill on which the fortress of Gwâlîor stands.¹

TEXT.²

- 1 [Ôm] [II*] [Ja]yati³ jalada-vâla-dhvântam=utsârayan=svaiḥ kiraṇa-nivaha-jâlair-
vyôma vidyôtayadbhiḥ u[daya-gi]r[i]-tat-âgra[m] maṇḍayan⁴ yas-
tura[m*]gaiḥ chakita-gamana-khêda-bhrânta-chamchat-saṭ-ântaiḥ I(II) Udaya-
g[i]r[i]-
- 2 [— —]grasta-chakrô=rtti-harittâ bhuvana-bhavana-dîpaḥ sarvvari-nâsa-hêtuh
tapita-kanaka-varṇair=amśubhiḥ=pamkajân[â*]m=abhmava-ramaniyam yô
vidhattê sa vô-vyât I(II) Śrî⁵.Tôram[âṇa] i]ti yah prathitô
- 3 [bhûcha]kra(?)-paḥ prabhûta-guṇaḥ satya-pradâ(dhâ)na-śauryâd=yêna maḥi
nyâyata[h*] śâstâ [II*] Tasy-ôdita-kula-kirttêḥ putrô=tula-vikramaḥ patih
prithvyâḥ Mihirakul-êti-khyâtô-bhangô yah Paśupati[m] [— —] [II*]
- 4 [Tasmin=râ]jani śâsati prithvim prithu-vimala-lôchanê=rtti-harê abhi-
varddhamâna-râjyê paṁchadaś-âbdê nripa-vrīshashya I(II) Śâsi-raśmi-
hâsa-vikasita-kumud-ôtpala-gandha-śital-âmôdê Kârttika-mâsê prâp[ê*]
gagana-
- 5 [patau(?) ni]rmmalê bhâti I(II) Dvija-gaṇa-mukhyair=abhisamstutê cha
puṇy-âha-nâda-ghôshêṇa tithi-nakshatra-muhûrttê samprâptê suprasasta-
dinê I(II) Mâtritulasya tu pautrah putraś=cha tath=aiva Mâtridâsasya
nâmnâ cha Mâtrichêtaḥ parvva-
- 6 [ta] vastavyaḥ [II*] Nâna-dhātu-vichitrê Gôp-âhvaya-nâmi
bhûdharê ramyê kâritavân=śailumayam bhânôḥ prâśâda-vara-
mukhyam I(II) Puṇy-abhivridhi-hêtôr=mmâtâpitrôs=tath=âtmanaś=ch=aiva
vasatâ[m*] cha giri-varê=smi[n*] râjñah
- 7 pâ(?)dêna [II*] Yê kârayanti bhânôs=chandr-âmsu-sama-prabham
griha-pravararṇ têshâm vâsaḥ svarggê yâvat=kalpa-kshayô bhavati II
Bhaktiyâ ravêr=vrachitam sad-dharma-khyâpanam su-kirttimayaḥ
nâmnâ cha Kêśav-êti-prathitêna cha I⁷

¹ Dr R. Mitra read the name here (line 6) as Giripa; but quite wrongly.—Other forms of the ancient Sanskrit name of the hill, and of the fortress on it, are (1) Gôpagiri; e.g. in line 1 of the Gwâlîor inscription of Bhôjadêva of Vikrama-Samvat 933 (*Four. Beng. As. Soc. Vol. XXXI. p. 407*); (2) Gôpâchaladurga, e.g. in an inscription of Vikrama-Samvat 1497 on the pedestal of a colossal figure of Âdinâtha at Gwâlîor (*id. p. 422*); (3) Gôpâdri, and Gopâdrîdurga, e.g. in lines 4 and 14 of the Gwâlîor inscription of Mahîpâla of Vikrama-Samvat 1150 (*Ind. Ant. Vol. XV. pp. 36, 37*); and (4) Gôpâlikêra; in line 2 of a Gwâlîor inscription of Vikrama-Samvat 1161 (*id. p. 202*).—Dr. Hultzsch (*id. p. 202, note 5*) has pointed out that the last form, Gôpâlikêra, seems to be the one that is the immediate source of the modern name Gwâlîor.

² Lines 1 to 6, and the last part of line 7, from the original stone; and, the lower part of the stone being now broken off and lost, the rest from Gen. Cunningham's lithograph published with Dr. Rajendralala Mitra's paper in the *Four. Beng. As. Soc. Vol. XXXI. p. 391 ff.*

³ Metre, Mâlinî; and in the next verse.

⁴ This π was omitted in its proper place, and was then inserted below the line.

⁵ Metre, Âryâ; and in the next nine verses.

⁶ We require here a verb, supplying the antithesis to (a)bhângô, 'without breaking; unbroken.' But the *aksharas* are much damaged by a crack in the stone; and I am unable to supply them.

⁷ This mark of punctuation appears to have been inserted unnecessarily, to fill up the space at the end of the line.

- 8 ... di(?)tyēna || Yāvach'-Chharvva-jatā-kalāpa-gahanē vidyōtatē chandramā
divya-strī-charapair-vvibhūshita-taṭṭō yāvach-cha Mēru-nagaḥ yāvach-
ch-ōraśi nīla-nrada-nibhē Vishṇur-vvi(bbi)bharty-u[j]*]valām Śrīms-
tāvad'-giri-mūrdhni tishṭhati
9 [śilā(?) -prā]śāda-mukhyō ramē ||

TRANSLATION.

[Ōm !] May he (the Sun) protect you, who is victorious,—dispelling the darkness of the banks of clouds with the masses of the multitude of his rays that light up the sky ; (and) decorating the top of the side of the mountain of dawn with (his) horses, which have the tossing ends of (their) manes dishevelled through the fatigue (induced) by (their) startled gait ;—(and) who,—having (his) chariot-wheels (?) swallowed (?) the mountain of dawn ; dispelling distress ; (being) the light of the house which is the world ; (and) effecting the destruction of night,—creates the fresh beauty of the water-lilies by (his) rays which are of the colour of molten gold !

(Line 2.)—(There was) a ruler of [the earth], of great merit, who was renowned by the name of the glorious **Tōramāna** ; by whom, through (his) heroism that was specially characterised by truthfulness, the earth was governed with justice.

(L. 3.)—Of him, the fame of whose family has risen high, the son (is) he, of unequalled prowess, the lord of the earth, who is renowned under the name of **Mihirakula**, (and) who, (himself) unbroken, [broke the power of] **Paśupati**.

(L. 4.)—While [he], the king, the remover of distress, possessed of large and pellucid eyes, is governing the earth ; in the augmenting reign, (and) in the fifteenth year, of (him) the best of kings ; the month **Kārttika**, cool and fragrant with the perfume of the red and blue waterlilies that are caused to blossom by the smiles of the rays of the moon, having come ; while the spotless moon is shining ;* and a very auspicious day,—heralded by the chiefs of the classes of the twice-born† with the noise of the proclamation of a holy day, (and) possessed of the (proper) *tithi* and *nakshatra* and *mukūrta*,—having arrived ;—

(L. 5.)—The son's son of **Matritula**, and the son of **Mātridāsa**, by name **Mātrichēta**, an inhabitant of on the hill, has caused to be made, on the delightful mountain which is speckled with various metals and has the appellation of **Gōpa**,‡ a stone-temple, the chief among the best of temples, of the Sun, for the purpose of increasing the religious merit of (his) parents and of himself, and of those who, by the of the king, dwell on this best of mountains.

(L. 7.)—Those who cause to be made an excellent house of the Sun, like in lustre to the rays of the moon,—their abode is in heaven, until the destruction of all things !

(L. 7.)—(This) very famous proclamation of the true religion† has been composed through devotion to the Sun, by him who is renowned by the name of **Kēśava** and by ... ditya.

(L. 8.)—As long as the moon shines on the thicket that is the knot of the braided hair of (the god) **Śarva** ; and as long as the mountain **Mēru** continues to have (its) slopes

* Metre, Śārdūlavikrīḍita.

† Read *śrīm tāvad*.

‡ See page 162 above, note 6.

§ i.e. in the bright fortnight of the month.

¶ i.e. by the *Brāhmaṇa*.

‡ See page 162 above, note 1.

† i.e. this inscription.

adorned by the feet of the nymphs of heaven; and as long as (the god) Vishṇu bears the radiant (goddess) Śrī upon (his) breast which is like a dark-blue cloud;—so long (this) chief of [stone]-temples shall stand upon the delightful summit of the hill!

No. 38; PLATE XXIV.

MALIYA COPPER-PLATE INSCRIPTION OF THE MAHARAJA DHARASENA II.

THE YEAR 252.

THIS inscription,¹ which was originally brought to notice by me in 1884, in the *Ind. Ant.* Vol. XIII. p. 160 ff., is from some copper-plates that were found at Māliyā,² the chief town of the Māliyā Mahāl or Sub-Division of the Junāgadh State in the Kāthiāwāḍ Peninsula in the Bombay Presidency. The original plates are, I understand, in the possession of the Junāgadh Darbār. I obtained them, for examination, through the kindness of the Diwān, Mr. Haridas Viharidas.

The plates, which are inscribed on one side only, are two in number, each measuring about $11\frac{1}{2}$ " by $7\frac{1}{2}$ ". The edges of them were raised into rims, to protect the writing; and the inscription is in a state of almost perfect preservation throughout. The plates are of fair thickness; but the letters are deep, and shew through very distinctly on the backs of them. The engraving is well executed; but, as usual, the interiors of the letters shew marks of the working of the engraver's tool throughout.—The plates are connected by two rings, passing through holes in the lower part of the first plate, and the upper part of the second. Both of the rings had already been cut, when the grant came under my notice. One of them is a plain copper ring, roughly circular in shape, about $\frac{1}{8}$ " thick and $1\frac{1}{4}$ " in diameter. The other is of the same thickness, but of an irregular oval shape, as is customary with the rings of the Valabhi seals. The ends of it are secured in a seal, the front of which is roughly oval, about $1\frac{1}{2}$ " by $2\frac{1}{8}$ ", and which has, in relief on a countersunk surface, at the top, a bull, recumbent to the proper right, the usual emblem on the Valabhi seals; and below it, separated by two horizontal lines, the legend *Śrī-Bhājarkkaḥ*, for *Śrī-Bhājarkkaḥ*, *i.e.* "the illustrious Bhaṭārka."—The weight of the two plates is 3 lbs. 1 oz., and of the two rings and the seal, $12\frac{1}{2}$ oz.; total, 3 lbs. $13\frac{1}{2}$ oz.—The size of the letters varies from $\frac{1}{8}$ " to $\frac{1}{16}$ ". The characters belong to the southern class of alphabets; but they include, *e.g.* in *chādd*, line 3, *khaḍga*, line 10, and *ḍombhi*, line 24, a separate form of the lingual *ḍ*, as distinct from the dental *d*, borrowed from the northern alphabet. They furnish a very good specimen of

¹ The inscriptions of this family that have already been discovered, are too numerous to be all included in the present volume; and they will, it is hoped, be some day disposed of by themselves in a separate collection. Meanwhile, the family is concerned so closely in the history of the period with which the present volume deals, that my book would be incomplete without a specimen or two of the Valabhi grants, as an accompaniment to the necessary historical chapter. I therefore give two of the inscriptions of this family; the present one, to illustrate the standard form according to which most of the earlier charters were drafted; and the next, partly as an illustration of the form of the later charters, and partly because it is the latest inscription of the family at present known of, and introduces the well-known and important name of Dhṛvabhāta or Dhruvabhāta, as a title of Śhāditya VII.

² The 'Māliya and Mallia' of maps, &c.; about twenty-three miles south by west of Junāgadh. It is also called 'Māliyā-Hāttī,' to distinguish it from another Māliyā, called 'Māliyā-Miāna,' in the north of Kāthiāwāḍ.

what may be called the Saurāshtra or Kāthiawāḍ alphabet of the sixth century A.D. They include, in line 36, forms of the numerical symbols for 2, 5, 10, 50, and 200.—The language is Sanskrit; and, except for the benedictive and imprecatory verses in lines 33 to 35, the inscription is in prose throughout.—In respect of orthography, the only points that call for notice are (1) the use of the *upadhmanīya*, once, in *pāddavarttāḥ-pañchadaśa*, line 23; and (2) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, once, in *ashdvintati*, line 25.

The inscription is one of the *Mahārāja Dharasēna II.*, of the family of the **Kings of Valabhi**; and the charter recorded in it is issued from the city of **Valabhi**, the modern **Walā**,¹ the chief town of the Walā State in the Gōhīlwad Prānt or Division of Kāthiawāḍ. Its date, in numerical symbols, is the year two hundred and fifty-two (A.D. 571-72); and the fifteenth lunar day of the dark fortnight of the month Vaiśākha (April-May). It is a non-sectarian inscription; the object of it being simply to record the grant, by the *Mahārāja Dharasēna II.*, to a Brāhmaṇ, for the maintenance of the five great sacrificial rites, of some lands at the villages of **Antaratrā**, **Ḍombhigrāma**, and **Vajragrāma**.

TEXT.²

First Plate.

- 1 Om Svasti **Valabbhitāḥ** prasabha-praṇat-āmītrāṇām **Maitrakāṇām**-atula-bala-sa[ṁ]³]panna-maṇḍalābhōga-saṁsakta-saṁprahāra-śata-labdha-pratāpaḥ
- 2 pratāp-ōpanata-dāna-mān-ārjav-ōparjīit-ānurāg-ānurakta-maulabhṛita-mitra-śrēṇī-bal-āvāpta-rājya-śrīḥ paramamahēśvaraḥ śrī-sēnāpati-
- 3 **Bhātārkakāḥ** [11⁴] Tasya sutas=tat-pāda-rajō-ruṇ-āvanata-pavitṛkṛita-śīrāḥ śīrōvanata-śatru-chūḍamaṇi-prabhā-vichchurita-pāda-nakha-pankti-dīdhītir-ddī-
- 4 n-anātha-kṛipāṇa-jan-ōpajlvyamāna-vibhavaḥ paramamahēśvaraḥ śrī-sēnāpati-**Dharasēnas**-Tasy-ānujas=tat-pāda-praṇāma-prasāstatara-vimala-
- 5 maṇir⁵-Mmanv-ādi-praṇīta-vidhi-vidhāna-dharmmā Dharmmarāja iva vihita-vinaya - vyavasthā - paddhatir - akhila - bhuvana - maṇḍal - ābhōg - aika - svāminā para-svāminā
- 6 svayam-upahita-rājya-ābhishēkaḥ mahā-vīśrāṇan-āvapūta-rājya-śrīḥ paramamahēśvarō mahārāja-**Drōṇasimhaḥ** simha iva [11⁶] Tasy-ānujaḥ sva-bhujā-
- 7 bala-parākramēṇa para-gaja-ghaṭ-āṅkīnām-ēka-vijayī śaraṇ-aishīṇām śaraṇam-avavōbdhā⁶ śāstrī-ārtha-tatvānām kalpatarur-iva suhṛit-pra-
- 8 ṇayinām yathābhilāshita-kāma-phal-ōpabhōga-daḥ paramabhāgavataḥ śrī-mahārāja-**Dhruvasēnas**-Tasy-ānujas-tach-charaṇaravinda-praṇāti-pra-
- 9 vidhaut-āśēsha-kalmashaḥ suvīśuddha-bhya(sva)-charit-ōḍaka-prakṣhālita-sakala-Kali-kalāṅkaḥ prasabha-nirjīit-ārāti-paksha-prathita-mahima
- 10 paramādityabhaktāḥ śrī-mahārāja-**Dharapattas**-Tasy-ātmapas-tat-pāda-saparyy-āvāpta-puṇy-ōdaya[ḥ]⁷ śaiśavāt-prabhṛiti khadga-dvītīya-bāhur-ē-

¹The 'Vala, Wala, Waleh, and Wulleh,' of maps, &c.; eighteen miles west by north from Bhāwnagar. Lat. 21° 52' N.; Long. 71° 57' E.

²From the original plates.

³The Jhar grant of the same *Mahārāja* (*Ind. Ant.* Vol. XV. p. 187 f.), drawn up from the same standard draft, gives here the fuller and better reading of *prastatara-vimala-mauli-maṇir*.

⁴Read *śatśatśat*.

- 11 va samada-para-gaja-ghaṭ-āspḥōṭana-prakāsita-sat[t*]va-nikashaḥ tat'-prabhāva-
prapat-ārāti-*chūḍāratna-prabhā-saṁsakta-sakhya(vya)-pā-*
- 12 da-nakha-raśmi-samhati[h*] sakala-smṛiti-praṅṭa-mārgga-samyak-paripālana-prajā-
hṛidaya-rañjanād-anvartha-rāja-śabdō rūpa-kānti-sthairyya-
- 13 gāmbhṛyya-buddhi-sampadbhiḥ Smara-śaśānk-ārdri(dri)rāj-ōdadhi-tridaśaguru-
Dhanē[śā*]n-atīśayānā(nō)-bhaya-pradāna¹-paratayā triṇa-va-
- 14 vad-apāst-[ā*]śēsha-sva-kāryya-phalaḥ pādachār-iva sakala-bhuvanamaṇḍal-
ābhōga-pramōdaḥ paramamāhēśvaraḥ śrī-mahārā-
- 15 ja-Guhasēnaḥ [11*] Tasya sutas-tat-pāda-nakha-mayūkha-saṁtāna-nirvitta-
Jāhnavi-jal-ō(au)gha-vikshālit-āśēsha-kalmashaḥ praṇayī-śata-
- 16 sahasr-ōpajītya-bhōga-sampat rūpa-lōbhād-iv-āśrī(śrī)tas-sa-rasam-ābhigāmikair-
guṇai[h*] sahaja-śakti-śikshā-viśēsha-vismā-
- 17 pit-ākhila-dhanurdharaḥ prathama-narapati-samatisriṣṭānām-anupālayitā
dharmmya(rmma)-dāyānam-apākartā
- 18 praj-ōpaghāta-kāriṇam-upaplavānām darsayitā śrī-sarasvatyōr-ēk-ādhipāsasya
samhat-ārāti-

Second Plate.

- 19 paksha-lakshmi-parikshōbha²-daksha-vikramaḥ kram-ōpasamprāpta-vimāla-
pārthiva-śrīḥ paramamāhēśvaraḥ mahārāja-
- 20 śrī(śrī)-Dharasēnaḥ kuśali sarvān-ēv-āyuktaka-viniyuktaka-drāṅgika-
mahattara-ohāṭa-bhaṭa-dhruvādihikaraṇika-dāṇḍapāsika-
- 21 rājasthānlya-kumārāmty-ādīn-anyāśis-cha yathā-sambadhyanānakān samā-
jñāpayaty-Astu vaḥ samviditam yathā mayā mātā-
- 22 pitrōh³ puny-āpyāyanāy-ātmanas=ch-aihiḥ-āmushmika-yathābhilashita-phal-āvāptayē
Antaratrayām Śivaka-padrakē Vīrasēna-
- 23 dantika-pratyaya-pādāvartta-śatam étasmād-aparataḥ pādāvarttāḥ-pañchadaśa
tathā apara-sīmni Skambhasēna-pratyaya-pādāvartta-śatam vimś-ādihikam⁴
- 24 pūrvva-sīmni pādāvarttā daśa Dombhigrāmē pūrvva-sīmni Varddhaki-
pratyaya-pādāvarttā navati[h*] Vajragrāmē-para-sīmni grāma-śikhara-
pādāvartta-śatam
- 25 Vi(?)ki(?)⁵dinna-mahattara-pratyayā ashtāviṁśati-pādāvartta-parisará vāpl I
Bhumbhusa-padrakē kuṭumvi(mbi)-Bōṭaka-pratyayā(ya)-pādāvartta-śatam
- 26 vāpl cha I état=s-ōdrāṅgam s-ōparikaram sa-vāta-bhūta-dhānya-hirany-
ādēyam s-ōtpadyamāna-vishtī(śhī)kam samasta-rājakyānām=a-
- 27 hasta-prakshēpaṅlyam bhūmichchhidra-nyāyēna Unnatānivāstī(si)-Vāja-
sanēty(yi)Kapva-Vatsasagōtra-brāhmaṇa-Rudrabhūtayē bali-charu-vaiśva-

¹ This t was at first omitted, and was then inserted rather above its proper position.

² The Jhar grant, mentioned above, gives here the better reading of *atīśayānāḥ sarvaṅgat-abhasy-pradāna*; so also in No. 39 below, Plate xxv. line 5.

³ The Jhar grant gives here the better reading of *paribhōga*; so also in No. 39 below, line 10.

⁴ This *visarga* was forced rather low down by the size of the *śhā* above it.

⁵ These ten *aksharas* are engraved over something else that had been previously engraved.

⁶ The vowels of these two *aksharas* are quite distinct; but the consonants are very doubtful. There seems to be some fault in the copper here, which prevented the engraver from forming these two *aksharas* properly, and induced him then to leave a blank space before *vāpl*, at the beginning of the next line.

- 28 dēv-āgnihōtr-ātrīhi-pamchamanāyājñikānām kriyānām samutsarppaṇ-ārttham-
ā-cnandr-ārkk-ārppava-sarit-kshiti-sthiti-samakāllnam putra-pau-
- 29 tr-ānvaya-bhōgyam udaka-sarggēṇa nisrīṣṭam [i*] Yatō=sy-ōchitayā
brahmadēya-sthityā bhujjataḥ kṛishataḥ karshayataḥ pradīfataḥ vā
- 30 na kaiśchit-pratishēdhē varttitavyam [i*] [Ā*]gāmi-bhadra-nṛipatibhiḥ=ch-
āsmad-vamśa-jair-a-nityāny-aīśvaryaṇy-a-sthiram mānushyaṇ sāmānyam
cha bhūmi-
- 31 dāna-phalam-avagachchhadbhir-ayam=asmad-dāyō-numantavyaḥ paripālayitavyaś-
cha [i*] Yaś=ch-aīnam=āchchhimdyād-āchchhidyamānam v-ānu-
- 32 modēta sa pamchabbhir-mmahāpātakai[h*] II¹ s-ōpāpātakai[h*] II² sa[r*]-
yuktas=syād=ity=Uktaṁ cha bhagavatā vēda-vyāsēna Vyāsēna II(I)
- 33 Shashtīm³ varsha-sahasrāṇi svarggē tishṭhati bhūmi-daḥ āchchhētā
ch-ānumantā cha I⁴ tāny-ēva narakē vaśē II Pūrvva-dattām
- 34 dvijātibhyō yatnād-raksha Yudhishṭhira II(I) mahi[r*] mahimatām
srēshṭha II⁵ dānāch-chhrēyō=nupālanam II Bahubhir-vvasudhā bhuktā
- 35 rājabbhis-Sagar-ādibhiḥ II(I) yasya yasya yadā bhūmiḥ tasya tasya tada
phalam-itih⁶ I(II) Likhitaṁ⁷ s[Ā*]ndhivigrahika-Skandabhatēna II
- 36 Sva-hastō mama mahārāja-srī-Dharasēnasya II Dū⁸ Chirbbira[h*] II Sam
200 50 2 Vaiśākha ba 10 5 [II*]

TRANSLATION.

Om! Hail! From (the city of) **Valabhi**:⁹—(There was) the illustrious *Sēndapati*:¹⁰ **Bhatārka**, a most devout worshipper of (the god) Mahēśvara,—who was possessed of glory acquired in a hundred battles fought with the large armies, possessed of unequalled strength, of the **Maitrakas**, who had by force bowed down (*their*) enemies;¹¹ (and) who

* and ² In each case, the engraver seems to have formed the mark of punctuation by mistake for a *visarga*.

¹ Metre, Ślōka (Anuṣṭubh); and in the following two verses

² and ³ In each case, the mark of punctuation is unnecessary.

⁴ Read *it*. ⁵ Supply *śāsanam*.

⁶ i.e. *dātakaḥ*.

⁷ The proper context is "the *Mahārāja*, the illustrious Dharasēna, being in good health, issues a command," &c., in line 19 ff. The intervening genealogy is by way of a parenthesis.

⁸ *Sēndapati*, *i.e.*, 'lord or chief of the army; a general,' is a technical military title.—The next grade above this was that of the *Mahāsēndapati*, whose title occurs, for instance, in line 1 of the Bijayagadh inscription of the Yaudhēyas, No. 58 below, Plate xxxviiB.

⁹ The correct interpretation of this important passage was first conclusively pointed out by Professor Kielhorn, in re-editing the Walā grant of Ślīāditya I. of the year 286 (*Ind. Ant. Vol. XIV. p. 328 f.*) Dr. Bhau Daji, however, evidently had an idea as to the proper meaning; since he wrote (*Jour. Bo. Br. R. As. Soc. Vol. VIII. p. 244 f.*)—"A sentence in the copper-plate, which has hitherto not been translated correctly, shows that they" (the rulers of Valabhi) "triumphed over a sun-worshipping people (Maitrakas)." Dr. R. G. Bhandarkar's translation (*Ind. Ant. Vol. I. p. 14*) was—"(**Bhatārka**), who obtained greatness by a hundred wounds received in the midst of a circle of friends of matchless might, who with main force had subjugated their enemies." Dr. Bühler's (*id. Vol. IV. p. 106*) was—"Bhatārka, who obtained an empire through the matchless power of his friends that humbled his enemies by main force;—who gained glory in a hundred battles fought at close quarters," Mr. V. N. Mandlik, following Dr. Bhau Daji, translated (*Jour. Bo. Br. R. As. Soc. Vol. XI. p. 346*)—"(**Bhatārka**), who had achieved success in hundreds of battles occurring in the

acquired the goddess of royalty through the strength of the array of (*his*) hereditary servants and friends, who had been brought under subjection by (*his*) splendour, and had been acquired by gifts and honourable treatment and straightforwardness, and were attached (*to him*) by affection.

(Line 3).—His son, whose head was purified by being bowed down in the red dust of his feet, (*was*) the illustrious *Śaṅḍapati Dharasēna* (I.), a most devout worshipper of (the god) *Mahēśvara*,—the rays of the lines of the nails of whose feet diffused themselves among the lustre of the jewels in the locks of hair on the tops of the heads of (*his*) enemies when they bowed down with (*their*) heads (*before him*); (*and*) whose wealth was the sustenance of the poor, the helpless, and the feeble.

(L. 4).—His younger brother, whose spotless jewel [in the lock of hair on the top of (*his*) head*] was made more lustrous (*than before*) by the performance of obeisance to (*his*) feet, (*was*) the *Mahārāja Drōṇasimha*, like unto a lion, a most devout worshipper of (the god) *Mahēśvara*,—who had as (*his*) law the rules and ordinances instituted by *Manu* and other (*sages*); who, like (*Yudhisṭhira*) the king of justice, adhered to the path of the maintenance of good behaviour; whose installation in the royalty by besprinkling was performed by the paramount master in person, the sole lord of the circumference of the territory of the whole earth; (*and*) the glory of whose royalty was purified by (*his*) great liberality.

(L. 6).—His younger brother (*was*) the illustrious *Mahārāja Dhruvasēna* (I.), a most devout worshipper of the Divine One,—who was victorious, by himself alone, through the prowess of his own arm, over the troops of the array of the elephants of (*his*) enemies; who was the asylum of those who sought for protection; who was the teacher of the real meaning of the sacred writings; (*and*) who, like the *kalpa*-tree,¹ granted the enjoyment of fruits which were the desires, in accordance with (*their*) wishes, of (*his*) friends and favourites.

(L. 8).—His younger brother, whose sins were all washed away by doing obeisance to the waterlilies that were his feet, (*was*) the illustrious *Mahārāja Dharapatta*, a most devout worshipper of the Sun,—by the water of whose very pure actions all the stains of the *Kali* age were washed away, (*and*) who forcibly conquered the renowned greatness of the ranks of (*his*) enemies.

(L. 10).—His son, who acquired an increase of religious merit by doing service to his feet, was the illustrious *Mahārāja Guhasēna*, a most devout worshipper of (the god) *Mahēśvara*,—whose sword was verily a second arm (*to him*) from childhood;² the test of whose strength was manifested by clapping (*his*) hands on the temples of the rutting elephants of (*his*) foes; who had the collection of the rays of the nails of (*his*) left foot interspersed with the lustre of the jewels in the locks of hair on the tops of the heads of (*his*) enemies who were made to bow down by his prowess; whose title of 'king' was obvious and suit-

wide extent of territories of *Maitrakas*, who were endowed with incomparable courage, and who had forcibly reduced their enemies to submission." My own original translation (*Ind. Ant.* Vol. VIII. p. 303) was—" (In the lineage) of the *Maitrakas*, who by force compelled their enemies to bow down before them, there was *Bhaṭṭārka*, who was possessed of glory acquired in a hundred battles fought within the circuit of the territories that he had obtained by means of his unequalled strength."

¹ *kalpa*-tree; one of the trees in *Indra's* paradise, which granted all desires.

² Or, perhaps, "who even from childhood carried a sword with his second arm;" *i.e.* "who could wield a sword with both arms at the same time."

Māyīya Grant of the Mēśa Dharasena II — The Year 252

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18

The image shows a fragment of an ancient inscription on a dark, rectangular stone or metal plate. The text is written in a highly stylized, cursive script, likely an Indic script such as Brahmi or Kharosthi. The characters are densely packed and run horizontally across the plate. There are two circular holes on the right side of the fragment, which were likely used for binding or mounting the inscription. The overall appearance is that of a well-preserved but somewhat weathered archaeological find.

W. GREGG, PHOTO-LITH

SCALE 80

7 F. FLEET, LQ 59

18

20

22

24

26


28

30

32

34

36



18
 20
 22
 24
 26
 28
 30
 32
 34
 36

The main body of the image contains a dense block of handwritten text in an ancient script, likely Tamil. The text is arranged in approximately 19 horizontal lines, corresponding to the numbered markers on the left. The script is highly stylized and compact, with many characters appearing to be variations of a few basic forms. The overall appearance is that of a manuscript page or a collection of inscriptions.

able, because he pleased the hearts of (*his*) subjects by properly preserving the path prescribed by all the traditional laws; who in beauty, lustre, stability, profundity, wisdom, and wealth, surpassed (*respectively*) (the god) Smara, the moon, (Himālaya) the king of mountains, the ocean, (Bṛihaspati) the preceptor of the gods, and (the god) Dhanēśa; who, through being intent upon giving freedom from fear [to those who came for protection³], was indifferent to all the (*other*) results of his actions, as if they were (*of as little value as*) straw; (*and*) who was, as it were, the personified¹ happiness of the circumference of the whole earth.

(L. 15).—His son, whose sins have been all washed away by the torrent of the waters of (the river) Jāhnavī that was constituted by the diffusion of the rays of the nails of his feet,—whose wealth and riches are the sustenance of a hundred thousand favourites; who is with appreciation, as if from a desire for (*his*) beauty, resorted to by (*all*) the virtuous qualities of an inviting kind;² who astonishes all archers by the speciality of (*his*) innate strength and (*skill acquired by*) practice; who is the preserver of religious grants bestowed by former kings; who averts calamities that would afflict (*his*) subjects; who is the exponent of (*the condition of being*) the one (*joint*) habitation of wealth and learning; whose prowess is skilful in causing annoyance to³ the goddess of the fortunes of the compact ranks of (*his*) enemies; (*and*) who possesses a spotless princely glory, acquired by inheritance,—(*is*) the *Mahārāja*, the illustrious *Dharaśēna* (II.), a most devout worshipper of (the god) Mahēśvara, who, being in good health, issues a command to all the *Āyuktakas*,⁴ *Viniyuktakas*,⁵ *Drāṅgikas*,⁶ *Mahattaras*,⁷ irregular and regular troops, *Dhruvādihika*.

¹ *pāda-chārin*, *lit.* 'moving on feet or legs'; see Dr. R. G. Bhandarkar's translation of line 7 of the grant of Dharaśēna IV. of the year 326 (*Ind. Ant.* Vol. I. p. 14.)

² The *śhigāmiḥ gṛhā* are explained by Kāmandaka in the *Nīsidra*, iv. vv. 6 to 8 (Calcutta edition, p. 78), as quoted by V. N. Mandlik in the *Your. Bo. Br. R. As. Soc.* Vol. XI. p. 348, note; they are—good birth, steadfastness in misfortune and prosperity, youth, a good disposition, civility, absence of dilatoriness, speech that is not contradictory, truthfulness, reverence for the aged, gratitude, the state of being favoured by destiny, wisdom, being independent of trifles, capability of subduing hostile neighbouring chiefs, firmness in attachment, far-sightedness, energy, purity, having great aims, modesty, and firm devotion to religion and justice.

³ *paribhāga*; other grants, drafted from the same form, and also No. 39 below, line 10, give *paribhāga*, '(skilful in) enjoyment (of)'; which is a better reading.

⁴ This, and the following, are technical official terms, for which suitable translations have not yet been fixed.—With the present term, *Āyuktaka*, we may compare the expression *dyukta-purusha* in line 26 of the Allahābād pillar inscription, No. 1, page 8 above.

⁵ *Viniyuktaka*; compare the use of *niyuj*, 'to appoint; to commission,' in line 9 of the Junāgaḥ rock inscription, No. 14 above, page 59; also compare *tan-niyukta* in line 76 of No. 39 below, Plate xxv.

⁶ *Drāṅgika*; other forms are *drāṅgika* (*Ind. Ant.* Vol. V. p. 205, line 14; where, however, it may be a mistake for *drāṅgika*), and *drāṅgin* (*id.* Vol. IV. p. 105, line 15). The present form, *drāṅgika*, occurs again in *id.* Vol. IV. p. 175, line 6; and, in line 10 of the same grant, we have *drāṅga*, which is the origin of these terms, in Maṅḍallādrāṅga. Dr. Bühler, in the places quoted, proposed to render *drāṅga* by 'township,' and *drāṅgika*, &c., by 'heads of towns;' and Monier Williams, in his Sanskrit Dictionary, gives *drāṅga* as meaning 'a town, a city.'

⁷ *Mahattara* is the comparative formation of *mahat*, 'great,' and is given by Monier Williams in the special sense of 'the head or oldest man of a village.'—In other inscriptions we have the superlative formation, *Mahattama*, used in the same technical way.

raṇikas,¹ *Dāndapātikas*,² *Rājasthāntyas*, *Kumārāmtyas*, and others, according as they are concerned —

(L. 21).—“ Be it known to you, that, for the purpose of increasing the religious merit of (my) parents, and in order that I myself may obtain the reward that is wished for both in this world and in the next, there is given by me, with libations of water, in accordance with the rule of *bhāmichchhidra*, to the Brāhman Rudrabhūti, an inhabitant of *Uṇnata*, (a student) of the Vājasaneyi-Kaṇva (*śākhā*), and a member of the Vatsa *gōtra*,—for the maintenance of the five great sacrificial rites of the *bali*, *charu*, *vaitvadēva*, *agnihōtra*, and *atithi*; to endure for the same time with the moon, the sun, the ocean, the rivers, and the earth; (and) to be enjoyed by the succession of (his) sons and sons' sons,—at (the village of) *Antaratrā*, in the common-land³ called *Śivakapadraka*, one hundred *pāddvartas*⁴ (of land), (known as) the holding⁵ of *Virasēnadantika*; (and) fifteen *pāddvartas* on the west of this; also, in the western boundary, one hundred *pāddvartas*, increased by the twentieth,⁶ (known as) the holding of *Skambhasēna*, (and) ten *pāddvartas* in the eastern boundary,—in the village of *Ḍombhigrāma*, in the eastern boundary, ninety *pāddvartas*, (known as) the holding of *Vardhaki*;—in the village of *Vajragrāma*, in the western boundary, one hundred *pāddvartas* in the highest part⁷ of the village, (and) an irrigation-well with an area of twenty-eight *pāddvartas*, (known as) the holding of the *Mahattara* *Vikidinna*;⁸ (and) in the common-land called *Bhumbhusapadraka*, one hundred *pāddvartas*, (known as) the holding of the cultivator *Bōtaka*, and an irrigation-well;—(the whole of) this (being given) together with the *udraṅga* and the *uparikara*; with the *vāta*,⁹ *bhūta*, grain, gold, and *śalya*; with (the right to) forced labour as the occasion for

¹ *Dhruvādhikaraṇika*; ‘one who has the superintendence of the *Dhruvas*.’—*Dhruva* has been explained by Dr. Bühler (*Ind. Ant.* Vol. V. p. 205) as being still used in *Kāthiawāḍ* and *Kachh* to denote “a person who, on the part of a *Rāja*, superintends the collection of the royal share of the produce in grain which is made by the farmers of revenue.”

² *Dāndapātika*, or *dandapātika*, is explained by Monier Williams in his Sanskrit Dictionary as meaning ‘one who holds the fetters or noose of punishment; a policeman.’

³ *padraka* seems to be a fuller form of *padra*, which is given in Monier Williams' Sanskrit Dictionary as meaning ‘a village; the entrance into a village; the earth; a particular district.’ Dr. Bühler (*Ind. Ant.* Vol. XV. p. 337) has explained it as being the modern *pādr*, ‘a grazing-place.’ I do not know what authority he has for this meaning. But, in H. H. Wilson's *Glossary of Indian Terms*, *pādar* (i.e. *pādr*) is explained by ‘common-land, land adjacent to a village left uncultivated.’ And this seems more likely to be the correct meaning.

⁴ *pāddvarta*, *lit.* ‘the turning round of a foot,’ is given by Monier Williams in his Sanskrit Dictionary as meaning ‘a square foot.’ But it seems more likely that such an expression as ‘a hundred *pāddvartas*’ means ‘a plot of ground measuring a hundred feet square each way, i.e. ten thousand square feet,’ rather than only ‘one hundred square feet,’ which would measure only ten feet each way, and would be rather a small area for a grant; to say nothing of the still smaller areas mentioned further on.

⁵ *pratyaya*; in other passages, the form *pratyāya* occurs.

⁶ i.e. “one hundred and twenty *pāddvartas*.”

⁷ *śikhara*; *lit.* ‘peak, top, summit.’

⁸ See page 166 above, note 6.

⁹ The meaning of *vāta*, *bhūta*, and *śalya*, is not apparent.—*vāta* is derived either from *vā*, ‘to blow,’ or from *vai*, ‘to become dried or withered,’ compare *śvāta* in line 14 f. of No. 31 above, page 137.—*bhūta* is the past participle of *bhū*, ‘to be, to become,’ but no suitable meaning suggests itself.—*śalya* seems to mean either ‘that which is to be given,’ from *ś* in composition with *śā*, ‘to give,’ or ‘that which is to be cut, reaped, or mown,’ from *ś* with *śā*. But it is possible that, instead of the prefix *ś*, we have the negative particle *a*, and that the word means ‘that which is not to be given.’

it occurs; (and with the privilege that it is) not to be (even) pointed at with the hand (of undue appropriation) by any of the king's people.¹

(L. 29).—"Wherefore, no one should behave so as to cause obstruction to this person in enjoying (it) in accordance with the proper conditions of a grant to a Brâhman, (and) cultivating (it), (or) causing (it) to be cultivated, or assigning (it to another).

(L. 30).—"And this Our gift should be assented to and preserved by future pious kings, born of Our lineage, bearing in mind that riches do not endure for ever, that the life of man is uncertain, and that the reward of a gift of land belongs in common (both to him who makes it and to him who continues it). And he shall become invested with (the guilt of) the five great sins, together with the minor sins, who may confiscate this (grant), or assent to its confiscation."

(L. 32).—"And it has been said by the venerable Vyâsa, the arranger of the Vêdas:—The giver of land abides in heaven for sixty thousand years; (but) the confiscator (of a grant), and he who assents (to an act of confiscation), shall dwell for the same number of years in hell! O Yudhishthira, best of kings, carefully preserve land that has previously been given to the twice-born; (verily) the preservation (of a grant) is more meritorious than making a grant! The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (of this grant that is now made, if he continue it)!

(L. 35).—(This charter) has been written by the *Sâmdhivigrahika* Skandabhata. (This is) the sign-manual² of me, the Mahârâja, the illustrious Dharmasena. The Dâtaka (is) Chirbira. The year 200 (and) 50 (and) 2; (the month) Vaisâkha; the dark tortnight; (the lunar day) 10 (and) 5.

No. 39; PLATE XXV.

ALINA COPPER-PLATE INSCRIPTION OF SILADITYA VII.

THE YEAR 447.

THIS inscription was discovered by Mr. Harivallabh, Assistant Deputy Educational Inspector, Kaira and Broach; and was first brought to notice in 1878, in the *Ind. Ant.* Vol. VII. p. 79 ff., where Dr. Bühler published his reading of the text, with remarks. It is on some copper-plates that were found either at, or in the neighbourhood of, Alina or Alina, a village about fourteen miles north-east of Nadiâd,³ the chief town of the Nadiâd Talukâ or Sub-Division of the Kaira (Khêdâ) District in Gujarat in the Bombay Presidency.

cut, reaped, or mowed.—Instead of *vâta-bhûta*, we sometimes have *bhûta-vâta*, in reversed order; e.g. in line 67 of No. 39 below, Plate xxv.

¹ *samasta-râjakyâdâm-a-hasta-prakshâpanya*. This is the customary expression in the Valabhi grants. From the south, we have (1) the almost identical expression *râjakyâdâm-an-anguli-prâkshâpanya*, e.g. in line 45 of the Goa grant of Shashhadêva II. of Kaliyuga-Samvat 4348, (*Ind. Ant.* Vol. XIV. p. 291); and (2) the variant *râja-râjapurushair-apy-an-anguli-nirdâya*, in line 61 of the Paithan grant of Râmachandra of Sâka-Samvat 1193 (*id.* Vol. XIV. p. 317).

² *sva-hasta*; *lit.* 'the own hand.'—Occasionally an actual representation of a sign-manual is given; e.g. at the end of the grant of Silâditya VII., No. 39 below, Plate xxv., and at the end of the Barâda grant of Dhruva II. of Sâka-Samvat 757 (*Ind. Ant.* Vol. XIV. p. 198 f. and Plate).

³ The 'Nadiâd, Nariad, and Neriad' of maps, &c.

When they first came to light, they had been lying for some time in a merchant's shop at Allnā. They are now in the possession of the Royal Asiatic Society in London, to which they were presented by Dr. Bühler.

The plates, which are inscribed on one side only, are two in number. The first measuring about 1' 2½" by 1' 1½", and the second, which is rather irregular in shape, about 1' 3½" by 1' 0½". The edges of them were fashioned somewhat thicker than the inscribed surfaces, with corresponding depressions inside them, so as to serve as rims to protect the writing. The surfaces of the plates, however, have suffered very much from corrosion; and in some places the letters, though not destroyed, are so choked up with a hard deposit of rust, which I found it impossible to remove, that they fail to appear in the lithograph. But the inscription is for the most part legible enough on the original plates; the only part that has really suffered being at the top, especially towards the right corner, of the second plate. The plates are thick, and very substantial; and the letters, though fairly deep, do not shew through on the backs of them. The engraving, as displayed where the plates have not suffered much injury, is fairly well executed; but the interiors of the letters shew, as usual, marks of the working of the engraver's tool throughout.—There are holes for two rings, in the bottom of the first plate and the top of the second; but the rings, with the seal on one of them, are not forthcoming.—The weight of the two plates is 17 lbs. 3½ oz.—The size of the letters varies from ⅜" to ¼". The characters belong to the southern class of alphabets; they are a later development of the type of those of the preceding grant of the *Mahārāja* Dharasēna II. of the year 252, No. 38 above, page 164, and Plate xxiv., and illustrate what may be called the Saurashṭra or Kāthiāwāḍ alphabet of the eighth century A.D. They include, from northern sources, a separate form of the lingual *ś*, as distinct from the dental *ṣ*, e.g. in *chādd*, line 4; also the rather rare lingual *ḡh* in *uāḡḡha*, line 11, and *samupōḡha*, line 56. They also include, in line 78, forms of the numerical symbols for 5, 7, 40, and 400.—The language is Sanskrit; and, except for four stanzas in lines 58 to 63, and for some of the usual benedictive and imprecatory verses in lines 72 to 75, the inscription is in prose throughout. As is the case with all the later grants of this family, the inscription was engrossed with great carelessness and inaccuracy; and there are a few passages, the proper reading of which can hardly yet be determined with certainty.—In respect of orthography, we have to notice (1) the occasional use of the guttural nasal, instead of the *anusvāra*, before *s*, in *vāṅsa*, lines 45 and 62, and *nistrīṅsa*, line 51; (2) the use of *siṅgha* for *siṃha*, in line 56; (3) the use, once, of the dental nasal, instead of the *anusvāra*, before *s*, in *ansa*, line 11; (4) the doubling of *k*, in conjunction with a following *r*, once, in *vikkrama*, line 11; and once in conjunction with a following *ri*, a very exceptional occurrence, in *prakhṛiti*, line 26-27; and (5) the doubling of *dh*, in conjunction with a following *y*, in *anudḡḡyāta*, lines 10, 14, 19, 23, 50, 53, 54-55, and 58.

The inscription is one of Śīlāditya VII., who also had the title of *Dhrūbhāṭa*, i.e. *Dhruvabhāṭa*,¹ of the family of the Kings of Valabhi; and the charter recorded

¹ As pointed out by Dr. Bühler (*Ind. Ant.* Vol. VII. p. 80), *Dhruvabhāṭa* is the full and correct form of the name; and the first two syllables have been contracted in this inscription, partly because the metre required one long syllable, not two short ones, and partly because *Dhrū* was no doubt at that time, just as now, the vernacular Gujarātī form of *Dhruva*, especially in its meaning, in Kāthiāwāḍ and Kachh (*id.* Vol. V. p. 205), as a technical official title denoting "persons who, on the part of the *Rājā*, superintend the collection of the royal share of the produce in grain which is made by the farmers of revenue; their duty is to see that he" (? the *Rājā*, or a farmer) "does not collect more than his proper share."

in it is issued from his camp at the town of **Anandapura**. It is dated, both in words and in numerical symbols, in the year four hundred and forty-seven (A.D. 766-67), on the fifth lunar day of the bright fortnight of the month Jyēshtha (May-June). It is a non-sectarian inscription; the object of it being simply to record the grant, by **Silāditya VII.** himself, to a **Brāhmap**, for the maintenance of the five great sacrifices and other rites, of the village of **Mahilabali** or **Mahilābali** in the **Uppalahēta pathaka**¹ in the **Khētaka dhra**.²

Of the places mentioned in this grant, **Khētaka** is of course the modern **Khēḍā** or **Kaira**³ itself. **Uppalahēta** is evidently the modern **Uplēt** or **Uplētā**, in the **Thāsrā Tāluka**, about thirty-five miles almost due east of Kaira. And **Anandapura** must be the modern **Ānand**, the chief town of the **Ānand Tāluka**, about twenty-one miles south-east of Kaira.

TEXT.*

First Plate.

- 1 Om Svasti Śrīmad-**Ānandapura**-sam[ā^o]vāsita-jayaskandhāvare⁴ prasabha-
prapat-āmitrāpām **Maitrakāpām**-atula-bala-sampanna-maṇḍalābhō[ga-
samśa]kta-samprahāra-śata-labdha-pratāpā.
- 2 t-pratāp-ōpanāta-dāna-mān-ārjjav-ōpārjjit-ānurāgād - anuraktā⁵-maulabhritāḥ⁶-śrēṇī-
bal-āvāpta-rājya-śriyaḥ paramamahēśvaraḥ⁷-śrī-**Bhaṭārkrād**-ā(a)vyava-
chchhinna-varṣān-mā-
- 3 tāpitri-charaṇāravinda-prapāti-pravivikt-śēśha-kalmashaḥ śaiśavāt-prabhṛiti
khaḍga-dvityaḥ⁸-bāhur-ēva samada-para-gaja-ghaṭ-āsp[ō]ḥ[āna-prakāsitā-
[sattva-ni]kashaḥ tat-p[r^o]ja-
- 4 [bhā]va-prapat-ārāti-chūḍāra[t^o]na-prabhā-sa[m^o]sakta-pāda-nakha - raśmi - samhatih
sakala - smṛiti - prapṛiti(ta) - mārggaḥ⁹-samyak - kriyā - pālanāḥ¹⁰-prajā - hridaya-
ramjanā[d-a^o]nvartha-rāja-śab[d]ō rūpa-kā-
- 5 nti-sthai[r^o]jya-gāmbhṛitya-buddhi-sampadbhiḥ Smara-śas[ā]h[ā]k-ādirāj-
ōdā(da)dhi-triā(tri)daśagusa(ru)-Dhanēśān-atisāyānaḥ śaraṇāgat-ābhaya-
pradānaḥ¹¹-paratayā tripa-vad-vapast¹²-ā[śēśha-sva]-viryya-
- 6 phalaḥ prārthan-ādihik-ārttha-prad[ān-ā]nandita-vidvat-suhrit-prapayi-hridaya[h^o]
pādachār-iva sakala-bhuvanamaṇḍal-ābhōga-pram[ō^o]da[h] parama-

¹ *pathaka* is a technical territorial term, a suitable translation for which has not yet been determined. It is evidently connected with *pathin*, *patha*, 'a path, a road.'

² *dhra* is another technical territorial term, a suitable rendering of which has not yet been determined.—In line 25 f. of the Althā grant of Dharasēna II. of the year 270 (*Ind. Ant.* Vol. VII p. 72), we have the expression *Khētak-dhra-vishay*; which seems to shew that the term *dhra* is synonymous with *vishaya*.—There is another term, *dharaṇ*, which is evidently a synonym of *dhra*, since the Hastavapra *dharaṇ* is mentioned in line 21 of the Wallā grant of Dharasēna II. of the year 269 (*Ind. Ant.* Vol. VI. p. 12); while the Hastavapra *dhra* is spoken of in a grant of Dharasēna IV. of the year 326 (*id.* Vol. I. p. 43).

³ Lat. 23° 44' N.; Long. 72° 44' E.

⁴ From the original plates.

⁵ Read *skandhāvare*.—In *ndh*, the engraver first formed *dh*, and then corrected it into *ndh*.

⁶ Read *aurdy-aurakts*.

⁷ Read *bhṛite*.

⁸ Read *mādivara*.

⁹ Read *dvitya*.

¹⁰ Read *mārgga*

¹¹ Read *pāna*.

¹² Read *pradāna*.

¹³ Read *spati*.

- 7 m^hésvarah¹ śrī-Guhasēnah² [11*] Tasya sutah tat-pāda-nakha-[mayūkha*]-
samtāna-visrija(ta)-[āhnavi-jal-augha-praksālit-āsēsha-kalmashah prapayī-
śata-sa-
- 8 has-ōpajīvyamāna-sampad-rūpa-lōbhād-[v-ā]śrī(śrī)taḥ sarabhā(bha)sam-ābhi-
gāmkaiḥ guṇaiḥ sahaja-śaktiḥ³-śikshā-viśēsha-vismāpita-labdha⁴-dhanur-
ddharah⁵ prathama-[na]-
- 9 rapati-samatisriṣṭānām-anupālayitā⁶ dharmma[dāyā]n⁷m-api(pā)karttā praj-
ōpaghāta-kāriṇām upaplavanām śamayitā⁸ śrī-sarasvatyōr-ēk-ādhipāsasya
sahōpapati⁹-pa-
- 10 ksha-lakshmi-paribhōga-daksha-vikkramah vikram-ōpama-samp[r]āpta¹⁰-vimala-
pārthiva-śrīḥ paramam^hésvarah¹¹ śrī-Dharasēnah¹² [11*] Tasya sutah
tat-pād-ānuddhyātaḥ sakala-jagad-ānandan-ātyā(tya)dbhu-
- 11 ta-guṇa-samudra¹³-sthagita-samagra-digmaṇḍalāḥ samara-śata-vijaya-śōbhā-
sanātha-maṇḍalāgra-dy[u*]ti-bhāsura-ānsa-pīṭh-ōvyū(dū)ḍha-guru-manōratha-
mahābhava(ra)ḥ sarvva-vidyā-pāra-parama-
- 12 bhāg-ādhipāma-vimala-matir-api sarvataḥ subhāshita-lavēn-āpi sv¹⁴-
ōpapādanīya-par[ī*]tōshah¹⁵ samagra-lōk-āgādha-gāmbhīryya-hridayō=pi
savya(chcha)rit-ātīśaya-suvyakta-parama-
- 13 kalyāṇa-svabhāvaḥ kh[ī*]lībhūta-Kṛitayuga-nṛipati-patha-viśōdhan-ādhipat-ōdagra-
kṛtīḥ dharm-ānugā(rō)dh-ā(ō)j[ī]v¹⁶]alatar[kṛit-ārtha-sukha-sa[m]pad-u[pa*]-
sēva-nirahāḍha¹⁷.Varjmāditya¹⁸-tvi(dvi)tīya-nāma
- 14 pā(pa)ramam[ā*]h[ē*]śvarah¹⁹ grī(śrī)-Gī(śi)lādityah²⁰ [11*] Tasya sutah²¹ tat-
pād-ānuddhyātaḥ svayav(m)-Upendra-gurur-ēpa(va) guruh²² gurur-
ātyādaravatā samabhilashāṣṭyām²³=api rāja-lakshmi[m*]
- 15 skandh-āsakt[ām] parama-bhadranām²⁴ dhur[re*]yyas-tad-āj[n*]śa-sa[m*]pādan-
ē(ai)ka-rasatay-ōdvāhana²⁵ khēda-sukharatibhyām anāyāsita-[sattva*]-
sarpatti[b*] prabhāva-sā(sa)mānad-vā(va)śikṛita-nṛipati-śata-śirō
- 16 ratnā(tna)-vnā(chchhā)y-ōpagūha(dha)-pādapīthō=pi parām-āvajñ²⁶-ābhimāna-
sahas²⁷-ānālī[ng*]jita-manōvrittīḥ prapatīrōkā²⁸ parityajya prakhyāta-
paurush-ābhimānair-ā(a)py-ā(a)rātibhir-anāsā[di]
- 17 ta-prakṛitay²⁹-ōpāyah³⁰ kṛita-nikh[ī*]la-bhuvan-āmā(mō)da-vimala-guṇa-sa[m]hatīḥ
prasabha-vighaṭita-sakala-Kali-vilas[ī*]ta-gatir-mattra³¹-jan-ābhidrō(rō)hibhir-
āsashaiḥ³² dōshair-anāmṛi

¹ Read *śakti*.² Read *vismāpita-sarvas*, or *vismāpiti-ākhila*.³ Here, and after *śamayitā* in this line, and in other places, there follows a mark which may perhaps be intended for a mark of punctuation. It is the same as the *anusvāra* (except that it is not in the proper place for the *anusvāra*), or half a *visarga*.⁴ Read *darīlayitā*.⁵ Read *sahhat-ārśi*.⁶ Read *ōpasamprāpta*, or *ōpakrama-samprāpta*.⁷ Read *samudaya*.⁸ Read *sukh*.⁹ Read *nirvāho*.¹⁰ Read *dharmmāditya*.¹¹ This *visarga* is imperfect, only the lower part being engraved.¹² Read *śasy-ānujāḥ*; on the authority of line 15:16 of the next grant of certain date after this generation; that of Dhruvasēna II. of the year 310 (*Ind. Ant.* Vol. VI. p. 14); and of later grants also (e. g. *Ind. Ant.* Vol. XII. p. 149, line 17, and Vol. VII. p. 74, line 18).¹³ Omit this word.¹⁴ Read *samabhilashāṣṭyām*.¹⁵ Read *paramabhādra īpa*.¹⁶ Read *śubhan*.¹⁷ Read *par-āvajñ*.¹⁸ Read *ras*.¹⁹ Read *prapatim-ābhā*.²⁰ Read *pratibiy*.²¹ Read *utcha*.²² Read *śaktiḥ*.

- 18 [shṭ-ā*]tyunnata-hridaya[h*] prakhyāta-paurushah śāstra-kōṭal¹-ātiśay[ō*]
guṇa² - gapatiha - vipaksha - kshitipati - lakshmi - svayamsvayam³grāhē(ha) -
prakāśita-praviā(vī)ra-purusha-prathamah⁴-[samkhy-ā]-
- 19 dhigamah⁵ ya(pa)ramam[ā*]hēśvarah śrī-Kharagrahaḥ [ī*] Tasya sutaḥ
tat-pād-ā[ā*]muddhyātaḥ sa[r*]vva-v[ī*]dy-ād dhigamah-pahita⁶-nikhila-vidvaj-
jana-manah-paritōshit⁷-ātisha(śa)ya[h*] sat[ī*]va-
- 20 sa[r*]pat-tyāgaiḥ śauryyēṇa cha vigat-ānusa[r*]dhāna-samāhit-ārāti-
paksha-manōratha-rathāksha-bhaṅgaḥ samyag-upalakshit-ānēka-śāstra-kalā-
lōkacharita-gahvara-vi-
- 21 bhāgō-pi parama-bhadra-prā(pra)kṛitir-akṛitri(tri)ma-praśrayō-pi vibha(na)ya-
śōbhā-vibhūsanāḥ⁸ samara-śata-jayapatāk-āharaṇa-pratyay-ōdagra-bāhu-daṇḍa-
vidhvamsita-pra[tipa]ksha-
- 22 darpp-ōdayaḥ sva-dhanu[h*]-prā(pra)bhāva-[pari*]bhūt-āstrakausal-ābhimāna-
sakala-nṛpati-maṇḍa[l-ā*]bhinandita-śāsanā(na)ḥ para[mamā]hēśvarah
grī(śrī)-Dharasā(śē)naḥ [ī*] Tasy-ānujaḥ ta[ī]-p[ād-ānu]-
- 23 ddhyātaḥ sachcharit-ā[ā*]tiru(śa)yita-sakala-pū[r*]vva-narapatih dus-
sādhanā[nā*]m-api prasādhayitā vishay[ā*]nām mū[r]tt[ī]m[ā*]n-iva
purushakārah parivridha-gu[ṇ-ā]nūrāga-[nirbbha]-
- 24 ra-chitta-vṛitti[bhī*]ḥ Manur-iva svā(śva)yam-abhyupapannaḥ prakṛitibhir-
avi(dhi)gata-kalā-kalāpa[h*] kanti-tiraskṛita-salāchhanah⁹-kumudā(da)-
nātha[h*] prājya-pratāpa-sthagita-diga[n]tarāla[h]
- 25 pradhvamsita-dhvānta-rāśih satat-ōdita-savitā prakṛitibhya[h*] para[m*] pu-
tyayam - artthavantam - atipa(ba)hutit ha - prayōjan-ānubandhamam¹⁰ = [ā*]gama-
paribhū(pū)ṇṇa[m*] vidadhāma(na)ḥ sandhi-vigraha-
- 26 samāsa-niśchaya-nipupa[h*] sthānam-anupadēśam dadantam¹¹ guṇa-vṛiddhi-
rājadinita¹²-sa[r*]sk[ā*]ra-sādhūnām rājya-Śālātu[r]jya-tantrayōr-ubhayōr-api
nishpātaḥ prakkrī-
- 27 ti-vikramō-pi karupā-mṛidu-hṛidayah śrutavān-apy-i(a)-garvv[ī*]taḥ kāntō-pi
praśami(mī) śi(sthi)ra-sauh[ā*]rddō-pi nirasitā dōshadōsha¹³vātām-
udaya-samupajan[ī]-
- 28 ta-jan-ānūrāga-parivṛi[m*]hita-bhuvana-samarthhita-prathita-Bālādityi(tya)-dvitlya-
nām[ā*] paramamāhagvana¹⁴ grī(śrī)-Dharasanaḥ¹⁵ [ī*] Tasya sutaḥ
tat-pādaradēla¹⁶-praṇā-
- 29 ma-dharani-kashana-di(ja)nita-kiṇa-lānchhana-lalāta-chandra-sa(śa)kala[h*] śiśu-
bhāva ēva śravaṇa-nihita-mauktik-ālanākāra-vibhram-āmala-śruta-viśō(śē)-
sha[h*] pradāna-sa-

¹ Read *kaṭal*.⁵ Omit this word.² Omit this second *svaya*.⁴ Read *prathama*.³ This *visarga* is imperfect, only the upper part being engraved.⁶ Read *ād dhigama-vihita*.⁷ Read *paritōsh*.⁸ Read *vibhūshanaḥ*.⁹ Read *salāchhana*.¹⁰ Read *ānubandham*.¹¹ Read *sthān-ānūrāgam-ādīnam dadantām*.¹² Read *vidhāna-janita*.¹³ Omit this second *dōsha*.¹⁴ Read *māhātmya*.¹⁵ Read *āhrasanaḥ*, on the authority of line 9-10 of his own grant of the year 310 (*Ind. Ant.* Vol. VI. p. 15), and of subsequent inscriptions.¹⁶ Read *pādaradēla*.

- 30 lila-kshālit-āgrahastāravindah Vyāsa¹ iva mṛidu-kara-grahaṇād-amandīkrit-
ānanda-vidhīh vasu[m^o]dharayāh rā(kā)rmmurā(ka)-dhanurvv[é^o]da iva
sabhāvināsapra²-lakshya-kalāpa[h^o] pra-
- 31 nāta - samasta - sāmanta - maṇḍal - āpamōnirbhṛita - chūḍāmanīyamana³ - śāsanaḥ
parama[māhē^o]śvaraḥ paramabhāṭṭāraka-mahār[ā^o]jādhirāja-param[é^o]śvara-
chakravartī-śrī⁴-Dha-
- 32 rasēnaḥ [II^o] Tat-pitāmaha-bhrāṭri-śrī-Silādityasya Vā(śā)ṅgapāpēr-iv-
āgrājanmanō⁵ bhakti-bandhur-āvayava-[kalpita-prapatē]r-ati-dhavalayā tat-
pādāravinda-prapri(vri)ttayā charaṇa-nakha-maṇi-
- 33 [ru]chā Mandākiny-ēva nityā(tya)m-amalit-ōttamāṁva(ga)desasy-Ava(ga)-
styasy-[é^o]va rājakchō(rshē)h d[ā^o]kshīyam-ānatanvānasya⁶ prabala-
dhavalivnō(mnā) yaga(śa)sām valay[é^o]na ma-
- 34 [ṇḍita]-kakubhā navayātharalitāśēpiḥkhaḍgaparivama⁷-maṇḍalasya payē(yō)da-
śyāma-śikhara-chūchura-kachi-sama-vinyasta-stana⁸-yugayāh kshit[é]h
paty[u]h śrī-[Dērabha]ta-
- 35 ay-āgrajāḥ⁹ kshiti[pa^o]-sa[m]hatēḥ charu vibhāgasya¹⁰ gu(śu)chir-yyagō-
ṅuka¹¹-bhṛitaḥ svayamvar-ābhilāshīṅm-iva rāj[y]a-śriyam-arppayantayāḥ
krita-par[i^o]graha[h] śaurīyam-apratiha]-
- 36 ta-pratāp-ānamita¹²-prachanḍa-ripu-maṇḍalam maṇḍalāgram-apālampadhūanāḥ¹³
śaradi prasabham-[ā^o]kṛiṣṭa-śiltmukha-pā(bā)ṇāsan-āpādita-prasādha[nānām]
37 para-bhuvāṁ vidhivad-ācharita-kara-grahaṇaḥ pūrvam-[é^o]va vividha-varṁ(rṇ)-
ōj[ī^o]valēna gru(śru)t-ātiśay[é^o]n-ō[dbhā]sita-śravaṇa-yugalāḥ puna[h]-punar-
uktēn-ēva ratn-ā]-
- 38 [la]h[k]ārēn-ālaṅkṛita-grōtrā¹⁴ parisphurat-kā(ka)ṭaka-vikaṭa-klṭa-paksha-ratna-
kīraṇam-īpachchhinna¹⁵-pradāna-salīla-nivahānavasē[ka¹⁶-vilasan-nava-śaival-ām]-
- 39 kuram-ap¹⁷-āgrapāṇim-udvaha[n^o] dhṛita-viś[ā^o]la-ratna-pa(va)laya-jaladhī-vēl[ā^o]-
tatāyam[ā^o]na-bhujā-pariṣhvakta-viśvam[bha]raḥ, paramam[ā^o]hēśvaraḥ śrī-
Dhruvasēnaḥ-Tasy-āgra-

¹ Read *hanydyā*.² Read *sambhāvit-dīśha*.³ Read *maṇḍal-ōttamāṅga-dhṛita-chūḍāmanīyamāna*.⁴ In line 39 of the grant of Dharaśēna IV. himself, of the year 326, Āshādha śukla 10, the reading is *chakravartī śrī-ājyaka-pāḍ-ānudhyatāh śrī* (*Jour. Bo. Br. R. As. Soc. Vol. X. p. 79*, and *Ind. Ant. Vol. I. p. 16*); also in his grant of the same year, Māgha bahula 5, of which we have only the translation of the second plate (*Ind. Ant. Vol. I. p. 45*).—In all the subsequent grants, the epithet *śrī-ājyaka-pāḍ-ānudhyatāh* was, for some reason or other, omitted, as here; even in his own grants of the year 330 (*Ind. Ant. Vol. VII. p. 75*, line 41, and Vol. XV. p. 340, line 40).⁵ Read *āngājanmanō*, in accordance with line 29 of the next available grant of the generation after this, that of Kharagraha II. of the year 337 (*Ind. Ant. Vol. VII. p. 78*).⁶ Read *ānavānasya*.⁷ Read *nabhāsi yāminīpatēr-vvirachil-ākhanda-parivōśha*.⁸ Read *chūchuka-ruchira-sakya-vindhya-stana*.⁹ Read *āgrajāḥ*, on the authority of line 32 of the grant of Kharagraha II., quoted above, note 3 and of most of the subsequent grants.¹⁰ Read *samhatēr-anurōgīnyāḥ*.¹¹ Read *yatō-ānuka*.¹² Read *apratihata-vyāpāram-ānamita*.¹³ Read *iv-ślambamānaḥ*.¹⁴ Read *trōtrāḥ*.¹⁵ Read *avichchhinna*.¹⁶ Read *nivah-śvasṭha*.¹⁷ Read *iv*.

Second Plate.

- 40 [j]ó'-para]-ma[h]pa[ti-sparddha(rśa)-dōsha-nāga(śa)na-dh[ī]y-(ē)va lakshmyā
svayam-atispashṭa-chēṣṭam-aśliṣṭ-āṅgayash [t̄ir-atiruchiratara-charita-garima-
parikalita-sakala-na]rapa[t̄]ir-ati-
- 41 prakriṣṭ - ānurāga - [sa*]rabhasa - vaśkṛita - prapata - samasta - sāmanta - chakra -
chōḍāmaṇi-mayūkha-[khachita-charapakamala-yugalāḥ] prōddām-[ōḍāra]-
dō[r]ddanḍa]-dalita-dvishad-va-
- 42 rrga-darppaḥ prasarpāt-patlyah-pratāpa-plōshīt-aśēsha-śatru-va[m*]śaḥ praṇayi-
paksha-ni[kshipta-lakshmlkaḥ] prērita-gad-ōtkshi]pta-su[darśana-chakra]h
parihṛita-
- 43 [bāla-kṛ]dō-anadhahkṛita-dvijātir-ēka - vikrama - prasādhitā - dharitritalō - namgtkṛita-
jalaśayy[ō-pūrvva-purushōtta]mah [śakshād-dharmma iva samyag-
vya]yasthā-
- 44 pita-varṇ-āśram-āchārah pūrvvair-apy-urvvi(rvvi)patibhiḥ trishṇā-lava-lubdhaiḥ
yāny-apahṛitā[ni] dēva-brahma]-d[ē]yā[ni] tē]śhām-apy-[atisarala]-manah-
pra-
- 45 [sa]ra-mut-sa[nika]la[n-ānu]mōdanābhyām parimudita-tri(tri)bhuvan-ābhinandit-
ōchchhrit-ōtkriṣṭa-dhavalā-dha[rmma]-dh[vaja]ḥ [prakāśita-ni]ja-vaṇśaḥ
d[ē]va-dvija-gurō[n-pratipū]ya yathārtha]m-anavarata-
- 46 pravartita - mah - ōdraṅ - [ā]di - dāna - vyavasana - ānupajāta³ - samtōsh - ōpāt - ōḍāra-
kṛtiḥ⁴-[param]parā-[danturita-ni]kh[i]la-dikchakravālah [spashtam-ēva
ya]th-ārtha[m] Dharmmādityi(tya)-
- 47 [dvi]tīya-nāmā para[ma*]mahēsvarah śrī-Kharagrahah [II*] Tasy-āgra-
janmanah⁴ kumuda-shanḍa-śrī-[vikāsinyā kalāvataś-chandrikay-ēva kirtya
dhavalita-sa]kala-digmanḍa-
- 48 lasya khamdit-āguru-[vi]lēpana-vidā⁴-śyāmala-Vindhya-[śai]la-vipula-payōdharāyāḥ
kshi[tēḥ] patyu]ḥ śrī-Śilādityasya sūnu[r-nava-prāleyakira]ṇa i]va
- 49 pratidina-samvardhamāna-hṛidaya⁴-kalā-chandra(kra)vālah [kēsar]indra-[ś]iśur-iva
rāja-lakshmiḥ sakala⁴-vana[sthalim-i]v-ālamkurvānah [śikha]ṇḍikētana
iva ruchi[mach-chōḍā]-ma[ṇḍanaḥ]
- 50 prachanḍa-śakti-prabhāvaś-cha śarad-āgama iva⁴ dvishatām parama-

¹ It is rather peculiar that the elder brother should be mentioned after the younger. The reading, *agrajā*, however, is the same in line 37 of Kharagraha's own grant of the year 337 (*Ind. Ant.* Vol. VII. p. 78), which seems to put the correctness of it beyond doubt; and the same reading is repeated in all the later grants without exception.—See also note 4 below.

² Read *vyavasthān-ōpajāta*, or *vyavasy-ōpajāta*.

³ Read *kṛti*.

⁴ Here we have another instance of the elder brother being mentioned after the younger (see note 1 above). But, except that *agrajā* is written by mistake for *agrajanmanah*, the reading is the same in line 47 of the next grant after this generation, that of Śilāditya III. of the year 352, the son of Śilāditya II. who is now under notice (*Ind. Ant.* Vol. XI. p. 308); and this seems to put the correctness of it beyond doubt. Also, the same reading that we have here, *agrajanmanah*, is repeated in all the later grants.

⁵ Read *piṇḍa*.

⁶ Omit this word *hṛidaya*.

⁷ Read *lakshmlm=achala*.

⁸ A considerable amount of matter is omitted here. The full passage should run — *śarad-āgama iva pratīpavān=ullasat-padmaḥ samyugḍ vidalayan=ambhōdharān=iva para-gojān=udaya-tapanā-bāddāpa iva samgrāmbiḥku mushyann=abhikukhāndm=dyūmṣti dvishatām*.

- mâhêsvarah paramabhaṭṭâraka-mahârajâdhirâja-paramêsvara-śrî-bappa'-pâd-
ânudhyâtaḥ paramabhaṭṭ[ṭ]âraka-[mahâra]-
- 51 jâdhirâja-paramêsvarah śrî-Śilâdityadêvas-Tasya sutah pâramaisvaryya[h*]¹
kôp-âkrishja-nistri[nstri]nâsa-pâta-vidalit-ârâti-kari-kumbhasthal - ôllasat - pra[srita-
ma]hâ-pratâp-ânalah prâ[kâra]-
- 52 [parigata*]-jaganmaṇḍala-labdha-sthitiḥ vikâṭa-nija-dôrdandâ-âvalambinâ sakala-
bhuvan-âbhôga-bhâjâ manth-âsphâlana-vidhu[ta-dugdhasi]ndhu-phê[na-piṇḍa-
pâ]ṇḍura-yaśô-vitâ[nêna]
- 53 vihita-âtapatrah parama[mâhê*]svarah paramabhaṭṭâraka-mahârajâdhirâja-
paramêsvara-śrî-bappa-pâd-ânudhyâtaḥ paramabhaṭṭâraka-mahâra[jâdhi]râja-
pa[ramêsva]ra-[śrî]-Śilâditya[dêvah] [II*] [Tat-putrah]
- 54 pratâp - ânurâga - prapâta - samasta - sâmanta - chûḍâmâri - nakha - mayûkha² - nichita-
rañ[jita-pâdâravindah] parama[mâ*]hêsvarah paramabhaṭṭâraka-mahârajâ-
dhirâja-paramêsvara-śrî-[bappa]-pâd-â-
- 55 nudhyataḥ paramabhaṭṭâraka-mahârajâdhirâja-paramêsvara-śrî-Śilâditya-
dêva[h] [II*] Tasya-âtmajah prasamita-ri(?)pu(?)-bala-darppah vipula-jaya-
mârgal-âsrayah śrî-samâlim[ga-na-lâli]ta-
- 56 vakshâ[h*] sam[u*]pôḍha-nârasingha-vigrah-ôrjjet-ô[d*]dhura-saktiḥ samuddhâ-
(dḍha)ta-vipaksha-bhûbhrit-kṛita-nikhila-gômaṇḍala-rakshah purush-ôttama[h*]
prapâtanâbhûta³-pârthivâ-kirta-
- 57 [mâ]ñikya - [ma]sṛipita - charaṇa - nakha - mayûkha - ramjit - âgêjâ⁴ - digvadhû - mukhah
paramamâhêsvarah paramabhaṭṭâraka-mahârajâdhirâja-paramêsvara-śrî-bappa-
pâ-
- 58 [d-â]nudhyataḥ paramabhaṭṭâraka-mahâraladhirâja⁵-paramêsvara-śrî-Śilâditya-
dêvah paramamâhêsvarah⁶ [II*] Tasya-âtmajah prathita-dussaha-vitryya-
chakrô lakshmy-âlay[ô]
- 59 [nara]ka-nâsa-kṛita-prayatnah prithvi-samuddharâna-kârîya-kṛita-aika-nishṭhah
sampûrṇa-chandra-kara-ni[r*]mmala-jâta-klrttiḥ [II*] Jâta-[tra]j[ti]-[g]juṇa-
mayô jita-vai[r]i-pakshah sampa[nna]-
- 60 [—]ma(?) - sukhaḥ sukha-dah sad-aiva jñân-âlaya[h*] sakala-vandita-lôkapâlô
vidyâdharair-anug taḥ prathitah prî(pri)thivyâm [II*] Ratn-ôj[ti]valô
vara-tanu-

¹ Read *bôva*, in accordance with line 46 of the grant of the next generation after this, that of Śilâditya IV. of the year 372 (*Ind. Ant.* Vol. V. p. 212; and *Archæol. Surv. West. Ind.* Vol. III. p. 99); with lines 45 and 46 of the two grants of Śilâditya V. of the year 403 (*Jour. Bo. Br. R. As. Soc.* Vol. XI. p. 343; and *Indian Inscriptions*, Nos. 15 and 16); and with the explanation that I give below, on the translation of this passage.—In line 51 of the grant of Śilâditya VI. of the year 441 (*Ind. Ant.* Vol. VI. p. 20), the reading is *bappa*, as here, wrongly.—In line 51 of the grant of Śilâditya III. himself of the year 352 (*Id.* Vol. XI. p. 309), the whole passage between *paramamâhêsvarah* and *śrî-Śilâdityadêvah*, including both the reference to *bôva* and his own regal titles, is omitted.

² Several words are omitted before this. The full reading is *tasya sutô-para-pruthôv-nirmâna-vyavashy-âśidita-pâramaisvaryyaḥ*.

³ Read *chûḍâmâri-mayûkha*.

⁴ Read *prapâta-prabhûta*.

⁵ Read *âśvha*.

⁶ Read *paramabhaṭṭâraka-mahârajâdhirâja*.

⁷ This epithet is repeated unnecessarily, as we have already had it in the preceding line.

⁸ Metre, *Vasantalaka*; and in the following three verses.

- 61 [r-ggu]na-ratna-rāṣiḥ aiśvarya-vikrama-guṇaiḥ paramaiḥ-upētaḥ sat[t*]v-
ōpakāra-karaṇē satatam pravrittah s[ā*]kshāḥ-[j*]janārdana(na) iv-
Arddita-dushta-darppah [11*]
- 62 Yuddhā¹ sakriḍ-gā(ja)g-ghatā-ghātan-aika-dakshah puṇy-ālayō jagati gīta-
mahā-pratāpah rājādhirāja-param[e*]śvara-vaṅśa-janmā śrī-Dhūrūbhātō
jayati jā-
- 63 ta-mahā-pramōdām¹ [11*] [Sa cha*] paramēśvarah² paramabhāṭṭāraka-mahārājā-
dhirāja-paramēśvara³-śrī-pa(ba)ppa-pāp(d)-ānuddhyātah para(rā)mabhāṭṭāra-
na(ka)-mahārājā-
- 64 dhirāja-paramēśvara-śrī-Śilādityadēvaḥ sarvān-ēva samājhāpayaty-Astu
vaḥ sarividita[m*] yathā mayā m[ā*]tāpitrōr-ātmanāś-cha puṇya-yaśō-
bhivri-
- 65 ddhayē aihik-āmushmika-phal-āvāpty-artnam śrīmadĀnandapuravāstavya-
tachchāturvvidyāsāmānya-Ś[ā*]rkkarākshisagōśtra(tra)-bahvricḥasabrahmachāri-
- 66 bhāṭṭ-Ākhaṇḍalamitrāyē(ya) bhāṭṭa-Viṣṇu-putrāya bali-charṇ-vaiśva-dēv-
āgnihōtra-kratu-kri(kri)y-ādy-utsarppaṇ-ātthē⁴ grī(śrī)-Khetak-anāre
Uppalahēta-
- 67 pathakē Mahila(Plā)bali-n[ā*]ma-grāmah s-ōdraṅga[h*] s-[ō*]parikā(ka)rah
s-ōtpadyā(dya)māna-viśṭīkaḥ sa-bhūta-pā(vā)ta-pratyādōyah⁵ s-daś-
āparādhaḥ sa-
- 68 bhōga-bhāgaḥ sa-dhānya-hirany-ād[ē*]yah - sarvva-rājakyānaḥ a-hasta-
prakshōpaślyah⁶ pūrva-pradatta-dōpadāya-piśmadāya-varjā⁷ bhūā(bhū)mi-
chchhidra-nyāy[ē*]n-a-cha[n[dr]-ā[r*]kk-ā-
- 69 rṇava-kshiti-parvata-samakālnah putra-pautr-ānvaya-bhōgya uday(k)-
ātisarggēpa brahmadāyatvēna pratipācitah [i*] yatō=bhy(sy)=ōchitayā
brahmadā[ya-sthi]-
- 70 tyā bhurjataḥ krishataḥ karshāpayataḥ pratidīśatō vā na kaiśchid-
vyāsēdhē vartitavya[m*] ॥ Āgāmi-bhadra-nrū(nri)patibhiḥ a-
- 71 smad-vaṅśa-jair-anyair-vv-ā-nityānityāny⁸-aiśvaryaṇy-a-sthira[m*] mānujya-
(shya)kaṁ sāmānyam cha bhūmi-dānaḥ⁹.phalam avagachchhadbhiḥ
ayam-a-
- 72 smad-dāyō-numantavyah pālayitavyaś=cha [11*] Uktañ=cha pē(ve)da-
vyāśō(se)na Vyā¹⁰sēna [1*] Bahubhi[r*]¹¹=vvāsuraadhā¹² bhuktā rajabhiḥ
Sagar-ādibhiḥ

¹ Read *yuddhē*.² Read *pramōdāḥ*.³ Read *paramamōdēśvarah*⁴ Read *paramēśvara*.⁵ Read *dr̥ttham*.⁶ Read *pratydyah*.⁷ Read *rājakyānām=a-hasta-prakshōpaślyah*⁸ Read *dēvadāya-brahmadāya-varjām*.⁹ Read *vv-ā-nityāny*.¹⁰ Read *dāna*.¹¹ The engraver first formed apparently *gyā*, and then corrected it into *vyā*.¹² Metre, Ślōka (Anuśtubh).¹³ Read *vasurdhā*.

- 73 *yasya yasya yadā bhūmis-tasya tasya tadā phala[rh*] I(II) Yān'-lha*
dattāni purā nna(na)rēndraiḥ dhanāni dharmmāyatanākriātāni¹
nirmmālya-vāntaḥ².
- 74 *prati[mā]ni tāni kē(kō) nāma [sā*]dhu[b*] pratir-ādaditah³ [II*]*
Shashī⁴-varva(rsha)-sahasrāpi sva[r]gg[ē*] tishṭhāti bhu(bhū)mi-daḥ*
a(ā)chchhētā ch-ānumant[ā] chcha(cha) tāny-ēva nara-*
- 75 [kē va]sēt II *Bhushv-ātavishv⁵-a-tē(tō)yāsu sushu⁶-kōṭara-vāsinah krishṇ-*
[ā]hay) hi jāyantō(ntē) bhūmi-d[ā*]yām haranti y[ē*] II Dutakē⁷-tra*
mahāpratihā-
- 76 [ra] . . . h[ā*]kshapaṭalika-tra-rājakula¹⁰-śrī-Siddhasēna[h*] grī(śrī)-Śarvata-
sutaḥ [I] tava(thā) tanniyukta-pratinartaka-kulaputr-āsā(mā)-*
- 77 *tya-G[u]hēna Hemaṭa-putrēna likhitam¹¹=iti II Samva[t]sara-śata-*
chatusṭayē sapta-chatvāriṅśad-adhikē Dyētha¹²-śuddha-pañchamāyām
aṅka-
- 78 *ta[h*] sava¹³ 400 40 7 Śrē(jyē)shṭha gu(śu) 5 [II*] Sva-hastō*
mama¹⁴ [II]*

TRANSLATION.

Om! Hail! From the victorious camp located at the famous town of **Ānanda-pura**:¹⁵—In unbroken descent from the most devout worshipper of (the god) Mahēśvara, the illustrious **Bhatārka**,—who was possessed of glory acquired in a hundred battles fought with the large armies, possessed of unequalled strength, of the **Maitrakas**, who had by force bowed down (*their*) enemies; (*and*) who acquired the goddess of royalty through the strength of the array of (*his*) hereditary servants, who had been brought under subjection by (*his*) splendour, and had been acquired by gifts and honourable treatment and straightforwardness, and were attached (*to him*) by affection,—(*there was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Guhasēna**,—whose sins were all removed by doing obeisance to the waterlilies that were the feet of (*his*) parents; whose sword was verily a second arm (*to him*) from childhood;¹⁶ the test

¹ Metre, Upajāti of Indravajrā and Upēndravajrā.

² Read *āyatanakriātāni*.

³ Read *vānta*.

⁴ Read *punar-ādadīta*.

⁵ Metre, Ślōka (Anusṭubh); and in the following verse.

⁶ Read *vindhy-ātavishv*.

⁷ Read *śushka*.

⁸ Read *dūtakō*.

⁹ Two very doubtful *aksharas*, or perhaps three, are engraved here. Dr. Bühler read them as *śrī-īēta*, giving the proper name of Dēṭaha. But we ought to have simply the *ma* of *mahākshapaṭalika*.

¹⁰ Read *paṭalika-rājakula*. The *tra* is meaningless, and it is not easy to see how it came to be introduced.

¹¹ Supply *śāsanam*.

¹² Read *jyēshṭha*.

¹³ Read *samvat*.


¹⁴ In the original, these two words, with a representation of the sign-manual underneath them, stand in an enclosure at the end of lines 70-78.

¹⁵ The proper context is in line 64,—“The glorious Śīlādityadēva (VII.) issues a command to all people.”

¹⁶ See page 168 above, note 2.

CORPUS INSCRIPTIONUM INDICARUM.


Alina Plates of Siladitya VII — The Year 447



2
4
6
8
10
12
14
16
18
20
22
24
26
28
30
32
34
36
38

SCALE 1/67

PLATE NO. 25



40
42
44
46
48
50
52
54
56
58
60
62
64
66
68
70
72
74
76
78

of whose strength was manifested by clapping (*his*) hands on the temples of the rutting elephants of (*his*) foes; who had the collection of the rays of the nails of (*his*) feet interspersed with the lustre of the jewels in the locks of hair on the tops of the heads of (*his*) enemies who were made to bow down by his prowess; whose title of 'king' was obvious and suitable, because he pleased the hearts of (*his*) subjects by preserving the proper rites of the path prescribed by all the traditional laws; who in beauty, lustre, stability, profundity, wisdom, and wealth, surpassed (*respectively*) (the god) Smara, the moon, (Himālaya) the king of mountains, the ocean, (Brihaspati) the preceptor of the gods, and (the god) Dhanēśa; who, through being intent upon giving freedom from fear to those who came for protection, was indifferent to all the (*other*) results of his vigour, as if they were (*of as little value as*) straw; who delighted the hearts of learned people and (*his*) friends and favourites, by giving (*them*) wealth greater (*even*) than their requests; (*and*) who was, as it were, the personified happiness of the circumference of the whole earth.

(Line 7.)—His son, whose sins were all washed away by the torrent of the waters of (the river) Jāhnavī spread out by the diffusion [of the rays*] of the nails of his feet, (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Dharasēna (II.)**,—whose riches were the sustenance of a hundred thousand favourites; who was with eagerness, as if from a desire for (*his*) beauty, resorted to by (*all*) the virtuous qualities of an inviting kind; who astonished all archers by the speciality of (*his*) innate strength and (*skill acquired by*) practice; who was the preserver of religious grants bestowed by former kings; who averted calamities that would have afflicted (*his*) subjects; who was the exponent of (*the condition of being*) the one (*joint*) habitation of wealth and learning; whose prowess was skilful in enjoying¹ the goddess of the fortunes of the compact ranks of (*his*) enemies; (*and*) who possessed a spotless princely glory, acquired by (*his*) prowess.

(L. 10.)—His son, who meditated on his feet, (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Śilāditya (I.)**, who acquired the second name of **Dharmāditya** by the pursuit of wealth, happiness, and riches, illumined by conformity with religion,—who pervaded all the regions with the excess of (*his*) wonderful good qualities that gladdened all mankind; who supported the great burden of weighty desires on a cushion that was (*his*) shoulder, radiant with the lustre of (*his*) scimeter that was possessed of the brilliance of victory in a hundred battles; who, though (*his*) intellect was pure through mastering the endmost divisions of the limits of all the sciences, was easily to be gratified with even a small amount of good conversation; who, though (*his*) heart possessed a profundity that could be fathomed by no people, yet had a most agreeable disposition that was displayed by the excess of (*his*) good actions; (*and*) who acquired an eminent reputation by clearing out the blocked-up path (*of the good behaviour*) of the kings of the Kṛita age.

(L. 14.)—His younger brother,² who meditated on his feet, (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Kharagraha (I.)**,—who possessed a wealth [of vigour*] that was not worn out, either with fatigue or with pleasurable enjoyment, when, bearing the yoke as if he were a most choice bullock, he was carrying on (*his*) shoulders, with the sole object of fulfilling his commands,³ the goddess of sovereignty, even while she was still an object to be longed for by (*his*) elder (*brother*) who, excessively full

¹ See page 169 above, note 3.

² See page 177 above, note 1.

³ *i.e.*, the commands of Śilāditya I.

of respect (*for him*), (*behaved*) as if he were (the god Indra) the elder (*brother*) of Upendra;¹ who, though (*his*) footstool was covered over with the lustre of the jewels on the heads of a hundred kings subdued by (*his*) wealth of power, had a disposition that was not embued with the sentiment of haughtiness (*induced*) by contempt for other people; by (*whose*) enemies, even though renowned for manliness and pride, no remedy, except the performance of obeisance alone, could be successfully employed; the collection of whose pure virtues effected the happiness of the whole world; who forcibly destroyed all the specious procedure of (*this wicked*) Kali age; whose very noble heart was not tainted by any of the faults that assert an ascendancy over inferior people; who was renowned for manliness; who excelled in knowledge of the sacred writings; (*and*) who manifested (*his*) attainment of being accounted the first among heroes, by being spontaneously chosen (*as her lord and husband*) by the goddess of the fortunes of the assembled hostile kings.

(L. 19).—His son, who meditated on his feet, (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Dharasēna** (III.),—who, by mastering all the sciences, produced an excess of joy in the minds of all learned people; who, with (*his*) goodness and wealth and liberality, and with (*his*) heroism, broke the chariot-axes that were the thoughts of (*his*) enemies who, occupied in intense reflection (*upon his might*), lost the power of acting in concert (*against him*); who, though thoroughly well conversant with the devious divisions of the many sacred writings and the arts and sciences and the proceedings of mankind, still had a nature that was of the most gracious kind; who, though possessed of innate affability, was (*still further*) decorated with the grace of modesty; who destroyed the display of pride of (*his*) opponents by the staff of (*his*) arm that was uplifted in the act of capturing banners of victory in a hundred battles; (*and*) whose commands were hailed with joy by the whole array of kings whose pride, induced by (*their*) skill in the use of weapons, was subdued by the power of his own bow.

(L. 22).—His younger brother, who meditated on his feet, (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Dhruvasēna** (II.),² whose famous second name of **Bālāditya** was established as one of appropriate meaning, through the (*whole*) world being pervaded by the affection of mankind that was produced by (*his*) rising;³—who surpassed all previous kings in excellent achievements; who was the accomplisher of objects, even such as were hard to be attained;⁴ who was, as it were, the very personification of manhood; who, as if he were Manu, was spontaneously resorted to by (*his*) subjects, the action of whose thoughts excelled in affection for (*his*) great good qualities; who mastered all the arts and sciences; who, in beauty, put to shame the moon, which (*lustrous as it is, still*) is marked with spots; who pervaded with (*his*) great brilliance all the intermediate spaces between the points of the compass; who destroyed

¹ Upendra, the younger brother of Indra, is Vishnu. The allusion seems to be to the contest between Vishnu (in his incarnation as Kṛishṇa) and Indra concerning the tree of Indra's paradise, in which Vishnu was victorious and had homage done to him by Indra (see the *Vishnu-Purāna*, book V, chap. xxx.; Hall's edition of Wilson's Translation, Vol. V, p. 97 ff.).—On this analogy, it would seem that the two brothers, Śītāditya I. and Kharagraha I., had some dispute about the leadership of their family; and that eventually Śītāditya I. conceded the question to his younger brother.

² See page 175 above, note 15.

³ The play on words is on the meaning of *bālāditya*, 'the young sun, the rising sun.'

⁴ Or "who was the conqueror of territories, even such as were hard to be subdued."

the mass of darkness; who, being a sun that was always risen, was (*ever*) conferring upon (*his*) subjects confidence of the highest kind, that was fully justified, (*and*) was the result of the very various objects with which he busied himself (*for their welfare*), (*and*) was filled out with (*constant*) augmentation; who, being clever (*on the one side*) in determining peace and war and reconciliation (*and on the other*) in settling the euphonic joining of letters and the analysis of words and composition, was thoroughly well versed even in both the rituals of sovereignty and of Śālāturiya,¹ (*the text-books on the one side*) of those who give commands suitable to the rank (*of their subordinates*) (*and on the other side*) of those who apply substituted grammatical forms suitable to the places (*that they are to fill*), (*and on the one side*) of those who are eminent in refinement effected by the employment of an increase of virtue, (*and on the other side*) of those who excel in the perfection of language effected by the employment of the *guna*² and *vridhhi*³ changes of vowels; who, though naturally valorous, possessed a heart that was tender through compassion; who, though well acquainted with sacred learning, was free from pride; who, though beautiful, was full of tranquillity; (*and*) who, though firm in friendship, repudiated people pervaded with faults.

(L. 28).—His son, whose forehead, resembling a portion of the moon, had on it a spot that was the mark caused by rubbing against the earth in performing obeisance to the waterlilies that were his feet, (*was*) the most devout worshipper of (the god) Mahēśvara, the *Paramabhāṭīdraka*, *Mahārājādhirāja*, *Paramēśvara*, and *Chakravartin*,⁴ the glorious **Dharasēna (IV.)**,—who, in very childhood, had a speciality of sacred learning that was as pure as the beauty of the pearl-ornaments worn in (*his*) ears; who had the waterlilies that were (*his*) fingers besprinkled with the stream of (*constant*) liberality; who intensified the happiness of the earth by the lenient levying of taxes, as if he were intensifying the happiness of a maiden by tenderly taking (*her*) hand (*in marriage*); who, as if he were (*the very personification of*) the science of archery of bowmen, perceived at once all objects that should be aimed at; (*and*) whose commands were like the jewels in the locks of hair worn on the heads of all the chieftains who bowed down before (*him*).

(L. 32).—Of the son⁵ of the illustrious Śilāditya (I.),⁶ who was the (*elder*) brother of his father's father⁷ (**Kharagraha I.**), (*and*) who was, as it were, (the god) Śāringa-

¹ The grammarian Pāṇini, as having been born in the town of Śālātura. The play on words here rests on the ordinary and grammatical meanings of *saṁdhi*, *vigraha*, and the other terms employed.

² The formative change of *i*, and *ī*, *u* and *ū*, *ri* and *rī*, and *lri*, into *ḥ*, *ḍ*, *ar* or *ra* and *al*.

³ The formative change of *a*, *i* and *ī*, *u* and *ū*, *ri* and *rī*, into *ḥ*, *ai*, *au*, *ār* or *rā*, and *āl*.

⁴ *Chakravartin* is explained by Monier Williams, in his Sanskrit Dictionary, as meaning "a ruler, the wheels (*chakra*) of whose chariot roll everywhere without obstruction;" or "the ruler of a *chakra* or country described as extending from sea to sea." Another explanation is given in the *Vishnu-Purāna*, book I. chap. xiii. verse 46 (see Hall's edition of H. H. Wilson's Translation, Vol. I. p. 183, and note 1), *vis.* "a discus (*chakra*), the sign of (the god) Vishnu, (is to be found among the marks) on the hands of all *Chakravartins*; (and such a ruler is one) whose prowess cannot be withstood even by the gods."—The word *Chakravartin* denotes 'an universal ruler,' and is one of the technical titles of paramount sovereignty, though it is not of such frequent occurrence as the others are (see page 10 above, note 3).—This Dharasēna's own grant of the year 326, inserts, after *Chakravartin*, the epithet "who meditated on the feet of (his) illustrious grandfather" (see page 176 above, note 4).

⁵ See page 176 above, note 5.

⁶ Mentioned in line 14 above.

⁷ *i.e.* of the father's father of the last-mentioned king, Dharasēna IV.

pāṇi,—(*vis.*) of the illustrious **Dērabhaṭa**, who performed obeisance with (*his*) limbs bowed down through attachment; whose head was always rendered pure, as if by (the river) Mandākinī, by the very dazzling lustre, proceeding from the waterlilies that were his feet,¹ of the jewels that were the nails of (*his*) feet; who, as if he were Agastya, was a royal saint, displaying courtesy on all sides; who with the exceedingly white circle of (*his*) fame, that adorned the points of the compass, formed an entire halo round the moon in the sky; (*and*) who was the lord of the earth which has (the mountains) Sahya and Vindhya for (*its*) lovely breasts,² the nipples of which are (*their*) summits that are made of a dark-blue colour by the clouds (*resting upon them*),—the son³ (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Dhruvasēna** (III.),—who accepted in marriage the goddess of royalty, just as if she were longing to choose (*him*) of her own accord, from the assemblage of kings, full of affection (*for him*) (*and*) wearing fine garments that were (*their*) resplendent reputations, which offered (*her to him*); who relied upon (*his*) heroism, which was never exerted in vain, as if upon a scimitar which bowed down the array of (*his*) fierce enemies; who, in the autumn season,⁴ according to proper custom levied taxes from (*his*) enemies' lands, the quiet state of which was upset by (*his*) bow, the arrows of which were forcibly drawn out to the full; who, having (*his*) ears already decorated with an excess of sacred learnings, radiant with a variety of topics, had them (*still further*) adorned with the embellishment of jewels, as if it were (*with that sacred learning*) repeated again and again; (*and*) who,—holding up a fore-arm which, (*covered*) with gleaming bracelets and wings of beautiful insects and rays of jewels, was as it were a fresh sprout of a *śaivala*-plant⁵ looking charming in the waters that were (*his*) ceaseless gifts,—embraced the (*whole*) earth with (*his*) arms which, wearing great jewelled bands, behaved as if they were the banks of the shores of the ocean.

(L. 39.)—His elder⁶ brother (*was*) the most devout worshipper of (the god) Mahēśvara, the illustrious **Kharagraha** (II.), who, in a very clear and suitable manner, had the second name of **Dharmāditya**—whose slender body was embraced in a very public fashion by the goddess of fortune herself, who was minded, as it were, to destroy the pollution of the touches of other kings; who surpassed all (*other*) kings by the greatness of (*his*) exceedingly brilliant achievements; who had the waterlilies that were (*his*) feet studded with the rays of the jewels in the locks of hair on the tops of (*their*) heads of the whole assemblage of chieftains who bowed down when they had been subdued by the violence of (*their*) excessive affection (*for him*); who broke the pride of the multitude of (*his*) enemies with the large and lofty staff of (*his*) arm; who scorched the whole race of (*his*) foes with (*his*) very hot brilliance that spread itself abroad; who delivered over (*all his*) wealth to the ranks of (*his*) favourites;⁷ who had a mace that he hurled, and a nice-looking discus that he threw; who discarded childish sports; who never treated the twice-born with contempt; who ac-

¹ *i.e.* the feet of Dharaśēna IV.

² See page 86 above, note 2.

³ See page 176 above, note 9.

⁴ As being suitable for campaigns, and also for marriages, as indicated by the secondary meaning of this sentence, in which *para-bhuvām* means "his enemies' daughters."

⁵ The aquatic plant, Vallisneria Octandra.

⁶ See page 177 above, note 1.

⁷ In this and some of the following sentences, he is, through their secondary meanings, compared and contrasted with the god Vishṇu.

quired the (*whole*) surface of the earth by (*his*) prowess alone; who approved not of making his couch among stupid people; who was one of the best of men of a kind that was unprecedented; who, as if he were the personification of religion, properly regulated the practices of the different castes and stages of life; whose lofty and excellent white banner of religion was hailed by the three worlds that were gladdened by (*his*) collecting together, in the joy of (*his*) very upright disposition, and then assenting to (*the continuance of the enjoyment of*), even those grants to gods and Brāhmanas that had been confiscated by previous kings, who were made avaricious by a little greed; who glorified his own lineage; (*and*) who, having done worship to the gods and Brāhmanas and spiritual preceptors, filled all the circuit of the regions with the continuity of (*his*) excellent reputation acquired by (*their*) satisfaction produced by (*his*) settlement of liberal grants of the *udraṅga*¹ and other (*rights*) which were ceaselessly made (*by him*) according to the merits (*of the recipients*).

(L. 47.)—Of his elder brother,² the illustrious Śīlāditya (II.),³—who made all the regions white with (*his*) fame, as if with the light of the full-moon that makes the beauty of the waterlilies to develop itself; (*and*) who was the lord of the earth, the bulky breasts of which are the Vindhya mountains of a dark-blue colour like cakes of ointment made of pounded aloe-bark,—the son (*was*) the *Paramabhaṭṭāraka*, *Mahārājādhirāja*, and *Paramēśvara*, the glorious Śīlādityadēva (III.),—who day by day increased (*his*) circle of accomplishments, like the new cold-rayed (moon) day by day increasing (*its*) digits; who adorned the goddess of sovereignty, like a young lordly lion adorning a forest on a mountain; who, like (the god Kārttikēya) who has the banner of a peacock, was adorned with a beautiful lock of hair on the top of the head, and was possessed of excessively great energy and majesty; who was [full of glory (*and*) possessed ample treasures*],⁴ like the approach of autumn, [which is full of warmth (*and*) causes the waterlilies to bloom*], [who used to part asunder in battle the elephants of (*his*) enemies, just as the young sun, hot (*even*) in (*its*) rising, parts asunder the clouds*]; [who used to steal in war the lives*] of (*his*) enemies, who was a most devout worshipper of (the god) Mahēśvara; (*and*) who meditated on the feet of the *Paramabhaṭṭāraka*, *Mahārājādhirāja*, and *Paramēśvara*, (*his*) glorious uncle.⁵

(L. 51.)—His son (*was*) the *Paramabhaṭṭāraka*, *Mahārājādhirāja*, and *Paramēśvara*, the glorious Śīlādityadēva (IV.),—[who achieved*] supreme lordship⁶ [by engaging in the creation of another world]; the diffused fire of whose great prowess played about on the temples of (*his*) enemies' elephants, which were split open by the blows of (*his*) sword that was drawn in anger; who acquired a firm position on the earth by encircling it about

¹ See page 97 above, note 6.

² See page 177 above, note 4.

³ In Dr. Bühler's genealogical table (*Ind. Ant.* Vol. V. p. 208; and *Archæol. Surv. West Ind.* Vol. III. p. 26), this Śīlāditya, because he did not actually reign, is passed over without being numbered; with the result that the last of the family, the maker of the present grant, is called Śīlāditya VI., instead of Śīlāditya VII. But this arrangement, if endorsed, would place us under the inconvenience of having to refer to him in a very roundabout way, by specifying his father, son, or brother, in any discussion of the history of the family. He belongs to the direct line of descent; and all considerations of expediency require that he should be duly numbered, quite as much as his grandfather and descendants of the same name.

⁴ See page 177 above, note 8.

⁵ *Ibid.*—See page 178 above, note 1, and page 186 below, note 1.

⁶ See page 178 above, note 2.—In this passage, Śīlāditya IV. is likened to the god Śiva, under the name of *Paramēśvara* or 'the supreme lord,' and as the creator (see page 155 above, note 1.)

with a rampart; whose umbrella was constituted by the canopy of (*his*) fame, white as the clusters of foam of the ocean of milk when it was stirred about by the shaking of the churning-stick, which hung out from a mighty staff that was his own arm, (*and*) which enveloped the whole circumference of the earth; who was a most devout worshipper of (*the god*) Mahéśvara; (*and*) who meditated on the feet of the *Paramabhāṭṭāraka*, *Mahārājādhirāja*, and *Paraméśvara*, (*his*) glorious father.¹

¹ *bappa*.—This word has already occurred in line 50 above, where, however, it is a mistake for *bāva*, 'uncle.'—The word *bāva*, qualified by the paramount titles, in the epithet *paramabhāṭṭāraka-mahārājādhirāja-paraméśvara-īrī-bāva-pād-ānudyāta*, actually occurs (1) only in respect of the *Paramabhāṭṭāraka*, *Mahārājādhirāja*, and *Paraméśvara* Śīlāditya III., a most devout worshipper of the god Mahéśvara (Śiva), in line 46 of the grant of his son Śīlāditya IV. of the year 372 (*Ind. Ant.* Vol. V. p. 212; and *Archæol. Surv. West. Ind.* Vol. III. p. 99), and in lines 45 and 46 respectively of the two grants of Śīlāditya V. of the year 403 (*Four. Bo. Br. R. As. Soc.* Vol. XI. p. 343). No other instance of the use of *bāva* is known to me.—The word *bappa* is of far more frequent use. In the Valabhi grants it occurs, qualified by the same paramount titles, in *paramabhāṭṭāraka-mahārājādhirāja-paraméśvara-īrī-bappa-pād-ānudyāta*, an epithet that is applied (2) here and in lines 54-55, 57-58, and 63 below, and in other grants as far as they go, to Śīlāditya IV. V. VI and VII, each of whom came in direct succession after his father, and each of whom had the paramount titles of *Paramabhāṭṭāraka*, *Mahārājādhirāja*, and *Paraméśvara*, and was also a most devout worshipper of the god Mahéśvara. Among the inscriptions of other families, the same expression, *bappa-pād-ānudyāta*, without any qualifying titles of *bappa*, is used as an epithet (3) of the *Bhāṭṭāraka* and *Mahārāja* Śivadēva I. of Nēpāl (*Ind. Ant.* Vol. XIV. p. 98, line 1-2); (4) of the *Mahāsāmanta* Amsuvarman of Nēpāl, who was also favoured by the feet of the god Paśupati, *s.e.* Śiva (*id.* Vol. IX. p. 169, No. 6, line 2, and p. 170, No. 7, line 4-5); (5) of Jishnugupta of Nēpāl, who again was also favoured by the feet of the god Paśupati (*id.* Vol. IX. p. 171, No. 9, line 4, and p. 173, No. 10, line 6-7); and (6) of the *Paramabhāṭṭāraka* and *Mahārājādhirāja* Śivadēva II. of Nēpāl, who again was also favoured by the feet of the god Paśupati, and was a most devout worshipper of the god Mahéśvara (*id.* Vol. IX. p. 174, No. 12, line 2, and p. 176, No. 13, line 2).—The same expression *bappa-pād-ānudyāta*, with the feudatory titles of *Mahārāja* and *Bhāṭṭāraka* qualifying *bappa*, occurs in *paramadaivata-bappa-bhāṭṭāraka-mahārāja-īrī-pād-ānudyāta*, an epithet (7) of the *Bhāṭṭāraka* and *Mahārāja* Vasantasēna of Nēpāl (*id.* Vol. IX. p. 167, No. 3, line 1-2).—And finally, a compound of almost identical import, *viz. bappa-pāda-bhaktā*, "devoted to the feet of *bappa*," occurs, with the title *Bhāṭṭāraka* qualifying *bappa*, in the epithet *bappa-bhāṭṭāraka-pāda-bhaktā*, which is applied (8) to the Pallava *Mahārāja* Simhavarman II., who was a most devout worshipper of Bhagavat, *s.e.* the Divine One, or Vishnu (*id.* Vol. V. p. 155, line 13), (9) to the Vengi *Mahārāja* Vijayanandivarman, also a most devout worshipper of Bhagavat (*id.* Vol. V. p. 176, line 1), and (10) to the Pallava *Mahārāja* Nandivarman, again a most devout worshipper of Bhagavat (*id.* Vol. VIII. p. 168, line 14-15); and, with the further qualifying title of *Mahārāja*, in the epithet *bappa-bhāṭṭāraka-mahārāja-pāda-bhaktā*, which is applied (11) to the Pallava *Yuvamahārāja* Vishnugopavarman, again a most devout worshipper of Bhagavat (*id.* Vol. V. p. 51, line 14).—In publishing the two grants of Śīlāditya V. of the year 403, Mr. V. N. Mandlik (*Four. Bo. Br. R. As. Soc.* Vol. XI. p. 355, note) treated the words *bappa* and *bāva*, quite unnecessarily, as identical, and considered that they denoted "some great teacher of the Śaiva faith, or some remarkable great king of that name; but more probably the former, from the adjectives used;" or, again, some "sage, venerated equally in all parts of Hindustān." So, also, Dr. Bhagwanlal Indraj (*Ind. Ant.* Vol. IX. p. 167, note 17) has recorded his opinion that *bappa* is "a general title used by chief priests." And I myself (*id.* Vol. X. p. 57 f., note 4), have suggested that the name is that of "some king or pontiff of very early times, whose authority was recognised universally in his own day, and was afterwards preserved in the tradition of several distinct regal families."—These suggested explanations, however, cannot be upheld.—In the first place, the epithet in which *bappa* occurs belongs undoubtedly to persons of the Śaiva faith in instances 1 to 6 above. But Nos. 8 to 11 show that it was applicable just as much to followers of the Vaishnava faith.—In the second place, as pointed out by Dr. Bühler (*id.* Vol. V. p. 208 f.) the feudatory title *Mahārāja* which qualifies *bappa* in Nos. 7 and 11 above, and, still more, the paramount sovereign titles of *Paramabhāṭṭāraka*, *Mahārājādhirāja*, and *Paraméśvara*, which qualify it in the instances grouped under No. 2, show that the word must refer to some one of noble or regal birth, and cannot denote a priest, no matter how high

(L. 53).—[His son] (was) the *Paramabhattaraka, Mahārājādhirāja*, and *Paramēsvara*, the glorious *Śīlādityadēva* (V.),—the waterlilies of whose feet were tinted by being covered over with the rays of the jewels in the locks of hair on the tops of the heads of all the chieftains, who did obeisance through the affection (produced) by (his)

his rank in the hierarchy might be.—As regards the question of *bappa* being a proper name, the word does occur in this way, as the name of an official, the *Baldhikrita* and *Bhōgika* Bappa (*id.* Vol. V p. 212, and *Archæol. Surv. West. Ind.* Vol. III. p. 99, line 59), as the name of someone after whom was named the *Bappa-pādīya-vihāra*, or "Buddhist monastery of the feet of Bappa," at Valabhi (*Ind. Ant.* Vol. VI. p. 12, line 19); in Bappasvāmin, one of the grantees in the Khōh grant of the Parvārājaka *Mahārāja* Hastin, of the year 163 (No. 22 above, p. 103, line 11); in Bappārya, one of the grantees in line 53 of the Chammak grant of the Vākātaka *Mahārāja* Pravarasēna II. (No. 55 below, Plate xxxiv. line 53); and in Bappabhatti, a Jain teacher, allotted to Vikrama-Samvat 800 to 895 (*Ind. Ant.* Vol. XI. p. 253). The same word is probably a component of Bappāra, the name of the family to which, as recorded in an unpublished inscription of Maṅgallāa (*Dynasties of the Kanarese Districts*, pp. 19, 22), Durlabhādēvi, the wife of the Early Chalukya king Pulikēsin I., belonged. A similar word *bāppa*, probably derived from it, occurs in Bāppadēva, the name of a *Sēnāpati* in the Siwāni grant of Pravarasēna II. (No. 56 below, Plate xxxv. line 35). And, finally, Bappa has been preserved by tradition, in 'Mewar,' as the more familiar appellation of an early Gōhila chief, who is said to have established the power of that tribe on the overthrow of the Bhīllas or Bhīlis (see *Tod's Annals of Rājasthān*, chapter II., Calcutta Reprint, Vol. I. p. 238 ff., also pp. 121, 253, 258 f.; see also *Ind. Ant.* Vol. XV. p. 275, note 26).—But the idea that, in the technical expression under discussion, *bappa* denotes some particular priest, whether of the Śaiva or Vaiṣṇava faith, whose memory had been preserved in different parts of India from very early times, has been disposed of above. And, this being so, it remains difficult, on the supposition that the word is a proper name, to imagine how it should have cropped up again from time to time, under precisely similar circumstances, in such different parts of the country, and such varying periods, as are indicated by instances 2 to 11 above.—The true explanation of the word first occurred to me from noticing the way in which the titles that qualify *bappa* vary in accordance with the titles of the persons to whom the epithet *bappa-pād-śrudhyāta* is applied, and it is fully borne out by the epithet *śīl-ajjaka-pād-śrudhyāta*, which is applied only to Dharasēna IV. in his complete grant of the year 326 (*Four. Bo. Br. R. As. Soc.* Vol. X. p. 79, line 38, and *Ind. Ant.* Vol. I. p. 16), and in his grant of the same year of which only the translation of the second plate has been published (*Ind. Ant.* Vol. I. p. 45). This expression, which, if it had not been so completely overlooked, would probably have made the matter clear long ago, dropped out in all the subsequent Valabhi grants, even in those of Dharasēna IV. himself of the year 330; probably on account of something in the official relations between Śīlāditya I. and Kharagraha I. which remains to be cleared up. But it occurs in these two instances; and, in accordance with Dr. R. G. Bhandarkar's rendering (*Id.* Vol. I. p. 16), it undoubtedly means "meditating on the feet of (his) illustrious grandfather" *Ajja* in Kanarese, and *ajjā* and *ajjā* in Marāṭhī, are the ordinary words for 'a grandfather' in the present day. And it is evident that *ajjaka* is the older Prākṛit word, from which these have been derived. On this analogy, *bappa* suggests itself at once as the old Prākṛit form of the modern *bāp*, 'a father. And now it becomes clear why the word is qualified by the paramount titles in its connection with the paramount sovereign Śīlāditya IV. and his successors, the reason being that the father of each of them was himself a paramount sovereign; and, on the other hand, why, in its connection with feudatories, it has either no qualificatory title at all, or only the feudatory titles *Mahārāja* and *Bhattāraka*, as in the case of Vasantaśēna, Siṃhavarman, Vijayanandivarman, Nandivarman, and Viṣṇugōpavarman. The rule thus disclosed also shews why, in the case of Śivadēva II., himself a paramount sovereign, *bappa* has no qualifying term; for, the way in which he is introduced in lines 11-12 of the Nēpā inscription No. 15 (*id.* Vol. IX. p. 178; see also Vol. XIV. p. 348) shews that he brought in a new branch of the Thākuri family, and that his father Narēndradēva, even if he held the rank of *Mahārāja*, was at least not a paramount sovereign. And the same rule explains why, in connection with the paramount sovereign Dharasēna IV., *ajjaka* is qualified by nothing more than the ordinary title *śīl*, for, he himself was the first paramount sovereign in the family; and his grandfather, Kharagraha I., was at the best only a *Mahārāja*.—The analogy of *ajjaka* and *bappa* now suffices fully to clear up the meaning of the word *bāp*. It suggests at once that it is nothing but the older Prākṛit word from which have been derived, with somewhat differing significations in Marāṭhī, *bābā*, 'a term of respect-

splendour; who was a most devout worshipper of (the god) Mahēśvara; (and) who meditated on the feet of the *Paramabhaṭṭāraka*, *Mahārājādhirāja*, and *Paramēśvara*, (his) glorious [father].

(L. 55.)—His son (was) the *Paramabhaṭṭāraka*, *Mahārājādhirāja*, and *Paramēśvara*, the glorious *Śīlādityadēva* (VI.),—who allayed the pride of the strength of (his) enemies; who was the auspicious asylum of great victory; whose breast dallied with the embraces of the goddess of fortune; whose unrestrained energy exceeded (even) that of (the god Vishṇu) who assumed the form of the man-lion;¹ who effected the protection of the whole earth by eradicating the hostile kings; who was the best of men; who tinted the faces of all the women that are the distant regions with the rays of the nails of (his) feet shining with the rubies in the tiaras of the powerful princes who bowed down before (him); who was a most devout worshipper of (the god) Mahēśvara; (and) who meditated on the feet of the *Paramabhaṭṭāraka*, *Mahārājādhirāja*, and *Paramēśvara*, (his) glorious father.

ful mention for a father or an elderly person; *bāwā*, 'a term of respectful mention for a Gōśaī, Guru, father, or elderly person,' and *bhāwā*, 'a husband's brother, especially an elder brother; and in Kanarese, *bāva*, 'the son of a mother's brother, or father's sister, a man or woman's brother-in-law (in every case, if older than one's self),' and *bhāva*, 'a husband or wife's elder brother, a maternal uncle's son (similarly, in every case, if older than one's self)' Looking for its application in connection with Śīlāditya III, we note, in the first place, that the grants shew very clearly that his father Śīlāditya II. did not reign at all, which explains why the epithet *bappa-pād-ānuahyāta* is not used in respect of him; and, in the second place, that the only paramount sovereign before him was his father's distant cousin Dharasēna IV., who, so far as paramount sovereignty is concerned, was his immediate predecessor. This shews us that *bāva* was used, here at least, to denote 'a male relative, of the same generation with a father,' or roughly 'an uncle;' and explains why *bāva* is qualified here with the paramount titles. And the fact that, after the first adoption of this technical expression, the Valabhi succession was in each instance direct from father to son, explains why the expression *bāva-pād-ānuahyāta* does not occur again.—In Kanarese, *bappa* appears in the form of *boppa* (marked in Sanderson's edition of Reeve's Kanarese Dictionary as a word common to most Hindu languages), in *boppana-siṅga*, 'the lion of (his) father,' an epithet applied to the Raṭṭa chieftain Lakshmidēva II., the son and successor of Kārtavīrya IV. (*Archæol. Surv. West. Ind.* Vol. III. p. 113, line 63-64). In confirmation of this I may quote, with the analogous introduction of terms of relationship, *ayyana-siṅga*, 'the lion of (his) father,' a title of the Śīlāhāra chieftain Gaṇḍarāditya of Kōlāpur (*Jour. Bo. Br. R. As. Soc.* Vol. XIII p. 3, line 21), and also of his son Vijayāditya (*Dynasties of the Kanarese Districts*, p. 105); *māvana-siṅga*, 'the lion of (his) father-in-law,' applied to the *Dandānyaka* Kēśavādityadēva (*Archæol. Surv. West. Ind.* Vol. III. p. 106, line 17-18), *annana-gandhadrāya*, 'the choice elephant of (his) elder brother,' applied to the *Dandānyaka* Sōmēśvarabhāta in the same inscription (*id.* line 11-12); *annan-ankakāra* 'the warrior or champion of (his) elder brother,' applied to the Sinda chieftain Āchugi II. (*Jour. Bo. Br. R. As. Soc.* Vol. XI. p. 247, line 9); and *bhāvan-ankakāra*, 'the warrior or champion of (his) uncle or other relation of the same generation with his father,' applied to a Śīlāhāra chieftain named Gonkidēva (*Ind. Ant.* Vol. XIV. p. 16, line 46). Other similar titles, which help to explain the preceding, through the introduction of proper names instead of words of relationship, are *Sēnana-siṅga*, 'the lion of Sēna,' applied to the Raṭṭa chieftain Kārtavīrya II., the son and successor of Sēna I. (*Jour. Bo. Br. R. As. Soc.* Vol. X. p. 213, line 7); *Tailana-siṅga*, 'the lion of Taila,' applied to the Kādamba chieftain Kīrtivarman II. of Banawāsī, the son and successor of Taila I. (*Dynasties of the Kanarese Districts*, p. 85); *Tailaman-ankakāra*, 'the warrior or champion of Tailama,' applied to Kāmadēva of the same family, the son and successor of Tailama (*id.* p. 86), and *Gonkan-ankakāra*, 'the warrior or champion of Gonka,' and *Gūhēyana-siṅga*, 'the lion of Gūhēya,' applied to the Śīlāhāra chieftain Mārasimha, the son and successor of Gonka, and the nephew of Gūhala or Gūvala I. (No. 10 of the separate publications of the Archaeological Survey of Western India, p. 103, line 28.)

¹ When he became incarnate, in a form that was half that of a man, and half that of a lion, in order to destroy the demon Hiranyakāśipu, who had obtained a boon from Brahman that he should not be destroyed by either god or man or animal.

(L. 58.)—Victorious is his son, the glorious **Dhrūbhata**,¹ born in a lineage of supreme kings of kings and supreme lords, (*and*) possessed of great happiness,—who is renowned for an abundance of heroism that is hard to be resisted; who is the abode of the goddess of fortune; who has striven to destroy hell; who has made it (*his*) sole resolve to save the earth; whose fame is as pure as the rays of the full-moon;—who is full of virtue through his knowledge of the three (Vēdas); who has conquered the ranks of (*his*) enemies; who is possessed of happiness; who always confers happiness; who is the abode of knowledge; who is a protector of the world whom all people applaud; who is attended by learned men; who is praised far and wide on the earth;—who is resplendent with jewels; who has a beautiful person; who is a very pile of jewels that are virtuous qualities; who is endowed with the choicest virtues of lordship and prowess; who is always employed in conferring benefits on living creatures; who, as if he were (the god) Janārdana incarnate, humbles the pride of wicked people;—who is always most skillful in disposing the array of elephants in war; who is the abode of religious merit; (*and*) whose great prowess is sung over the (*whole*) earth.

(L. 63.)—[And he²], the most devout worshipper of (the god) Mahēsvara, the *Paramabhaiṣṭraka*, *Mahārājādhirāja*, and *Paramēsvara*, the glorious **Śīlādityadēva** (VII.), who meditates on the feet of the *Paramabhaiṣṭraka*, *Mahārājādhirāja*, and *Paramēsvara*, (*his*) glorious father, issues a command to all people:—

(L. 64.)—"Be it known to you that, for the purpose of increasing the religious merit of (*my*) parents and of myself, (*and*) in order to obtain a reward both in this world and in the next, the village named **Mahilabali**,³ in the **Uppalahēta** *pathaka* in the famous **Khēṭaka dhāra**,—with the *udraṅga* (*and*) the *uparikara*; with (*the right to*) forced labour as the occasion arises; with the revenue of the *bhūta* and *vāta*,⁴ with (*the fines for*) the ten offences;⁴ with (*its*) enjoyments and shares; with the grain, and gold, and *ādya*;

¹ See page 172 above, note 1.

² Or perhaps Mahilābali, with the long vowel *ā* in the third syllable.

³ See page 170 above, note 9.

⁴ *sa-datāparādhaḥ*.—This is a technical fiscal expression, of constant use in charters, for which I have not been able to obtain any absolutely certain explanation. But Mr. S. Ch. Chitnis has brought to my notice that, in the *Dharmasindhusāra* of Kāśnāthpādhyāya, chapter ii. verse 19 ff., we have—*Adattānām=upādānam himsā ch=aiṅ-ā-vidhanataḥ* || *Para-dār-śpaśvā cha kāyikāṃ tri-vidhāṃ smṛitā* | *pārushyam=anṛitā ch=aiṅ paṣunyam ch=āpi sarvasāḥ* || *Asambaddha-pralāpa=cha vānmayāṃ syāch=chatur-vidhā* | *para-dravyeṣṭu=abhidyānam manas=āniṣṭa-chintanam* || *Vitath-ābhiniṣṭai=cha mānasam tri-vidhāṃ smṛitā* | *stāni daṭa pāpāni hara tvam mama Jāhnavī* || *Datāpā-harā yasmāt=tasmād=Datāharā smṛitā*,—"the appropriation (theft) of things that are not given, and killing in a manner that is not in accordance with precept, and the pursuit of the wives of other men, are laid down to be the three (sins) of the body; harshness of language, and untruthfulness, and slandering in all directions, and incoherent conversation, are the four (sins) of speech; coveting the property of others, (and) thinking with the mind about things which are wrong, and tenacity of that which is not true, are laid down to be the three (sins) of the mind; do thou, O Jāhnavī (Gangā), take away these my ten sins; because thou takest away (these) ten sins, therefore art thou called "Daśaharā."—These verses occur in connection with the Daśaharā (popularly *Dasarā* or *Dusrāb*) a festival in honour of the river Ganges, held on the tenth day of the bright fortnight of the month Jyēṣṭha.—So, also, in the *Aṣṭāṅgahridaya* of Vāgbhata, *Sū-trasthāna*, chapter i. verse 21 f. (Bombay edition of 1880, p. 38) we have, in only slightly different language,—*Himsā-sib-ānyathādmān paṣunyam pārush-anṛitā* | *sambhinndlāpa-vyāpādān=abhidyāḥ ṛigviparyāyam* || *Pāpāni harm=bi datādhā kāya-vān-mānasais=tyajit*; which shews that the classification was a well-established and well-known one.—These ten sins are probably the

(with the privilege that it is) not to be (even) pointed at with the hand (of undue appropriation) by any of the king's people; (and) with the exception of previously-given grants to gods and Brāhman, —is given by me, with copious libations of water, on the terms of a grant to a Brāhman, in accordance with the rule of *bhūmichchhidra*, —to endure for the same time with the moon, the sun, the ocean, the earth, and the mountains; (and) to be enjoyed by the succession of sons and sons' sons, —to the *Bhatta* Ākhaṇḍalamitra, the son of the *Bhatta* Viṣṇu, an inhabitant of the famous town of Ānandapura, belonging to the community of *Chaturvēdins* of that (place), a member of the Śārkarākṣhi *gōtra*, and a student of the *Bahvṛicha* (*śākhā*), —for the maintenance of the rites of the *bali*, *charu*, *vaiśvadeva*, *agnihōtra*, and *atithi* sacrifices, and other (ceremonies).

(L. 69.)—“Wherefore, no one should behave so as to cause obstruction to this person in enjoying (it) in accordance with the proper conditions of a grant to a Brāhman (and) cultivating (it), (or) causing it to be cultivated, or assigning (it to another).

(L. 70.)—“ (And) this Our gift should be assented to and preserved by future pious kings, whether born of Our lineage or others, bearing in mind that riches do not endure for ever, that the life of man is uncertain, and that the reward of a gift of land belongs in common (both to him who makes it and to him who continues it).”

(L. 72.)—And it has been said by Vyāsa, the arranger of the Vēdas:—The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (of this grant that is now made, if he continue it) ! These chattels, made into altars of religion, which have been formerly given here (on earth) by (previous) kings, (are) like the remains of offerings to gods, and like food that is vomited up; verily, what good man would take them back again? The giver of land abides in heaven for sixty thousand years; (but) the confiscator (of a grant), and he who assents (to an act of confiscation), shall dwell for the same number of years in hell! Those who confiscate a grant of land, are born as black serpents, dwelling in the hollows of dried-up trees in the Vindhya mountains, destitute of water!

(L. 75.)—The *Dātaka* in this matter (is) the *Mahāpratihāra*,¹ the *Mahākṣhapatalika*,² a member of the king's household, the illustrious *Siddhasēna*, the son of the illustrious Śarvata; and (this charter) has been written by his deputy, the *Pratinartaka*,³ the high-born *Anātya Guha*, the son of *Hembaṭa*, who was deputed by him (to write it).

dasa aparādhaḥ, or 'ten offences,' referred to in the text. And the full technical expression evidently conveyed, to the grantee of a village, the right to the proceeds of fines imposed for the commission of these, or similar, wrongful actions in the limits of his village.

¹ *Mahāpratihāra*, lit. 'the great *Pratihāra*,' is a technical official title denoting the superior officer of the *Pratihāras* or 'door-keepers.'

² *Mahākṣhapatalika*, lit. 'the great *Ākṣhapatalika*,' is a technical official title denoting the superior officer of the *Ākṣhapatalikas* or 'keepers of the records.'—The title *Ākṣhapatalika* occurs for instance, in an abbreviated form, in line 34 of the Kaṭī grant of *Bhīmadēva* II. of *Vikrama-Samvat* 1283 (*Ind. Ant.* Vol. VI. p. 200). It is derived from *akṣhapāṭala*, which *Monier Williams* gives in his Sanskrit Dictionary as meaning 'a court of law; a depository of legal documents,' and which occurs in the title *Akṣhapāṭalādāhnikṛita*, synonymous with *Ākṣhapāṭalika*, in line 15 of No. 60 below, Plate xxxvii.—Another title, *Ākṣhaśālika*, which is perhaps synonymous with *Ākṣhapāṭalika*, occurs in line 25 of the 'Chitacole' grant of *Indravarman* of the year 146 (*Ind. Ant.* Vol. XIII. p. 123).

³ *Pratinartaka* appears to be an official or family title. *Westergaard*, in his *Radices*, does not give *nīti* in composition with *prati*. *Monier Williams*, in his Sanskrit Dictionary, gives it in the sense of 'to dance before, in token of contempt.' But it more probably has some connection with *nartaka* in the sense of 'a bard, a herald.'

(L. 77.)—In four centuries of years, increased by forty-seven; on the fifth lunar day of the bright fortnight of (the month) Jyēshṭha; (or) in figures, the year 400 (and) 40 (and) 7; (the month) Jyēshṭha; the bright fortnight; (the lunar day) 5. (This is) my sign-manual.¹

No. 40; PLATE XXVI.

ARANG COPPER-PLATE INSCRIPTION OF THE RAJA MAHA-JAYAKAJA.

THIS inscription,—which was first brought to notice by General Cunningham, in 1884, in the *Archæol. Surv. Ind.* Vol. XVII. p. 55 ff. and Plates xxiv. and xxv.; and is now published in full for the first time,—is on some copper-plates that were obtained by Colonel Bloomfield, and were found at **Āraṅg**,² a village about twenty miles almost due east of Rāypur,³ the chief town of the Rāypur District in the Central Provinces. The original plates are now in the Provincial Museum at Nāgpur.

The **plates**, of which the first is inscribed on one side only, are three in number, each measuring about $5\frac{3}{8}$ " by $2\frac{1}{2}$ " at the ends and a little less in the middle. They are quite smooth, the edges of them being neither fashioned thicker nor raised into rims. A few of the letters have been damaged by rust; but the inscription is for the most part in a state of perfect preservation throughout. The plates are of fair thickness; and the letters, though fairly deep, do not shew through on the backs of them at all. The engraving is very good, but shews here and there, as usual, in the interiors of the letters, marks of the working of the engraver's tool.—Towards the proper right end of each plate, there is a hole for a **ring** to connect them. The ring is circular, about $\frac{3}{8}$ " thick, and 3" in diameter; it had already been cut, for the purpose of taking impressions of the plates, when the grant came into my hands; but there is no reason to suppose that it is not the ring properly belonging to the plates. The **seal**, in which the ends of the ring are secured, is circular, about $3\frac{1}{2}$ " in diameter; and, like the seal of the Rāypur grant of Mahā-Sudēvarāja, No. 41, below, Plate xxvii., it has a strong yellow glint in it, which gives it the appearance of being made of a kind of brass, rather than of copper. It has, in relief, on a countersunk and slightly concave surface,—across the centre, a **legend**, in two lines, of which the text and translation are given below;—in the upper part, a standing figure of the goddess Lakshmi, facing full-front; on each side of her, an elephant standing on a waterlily, with its trunk lifted up to pour water over her head; in the proper right corner, an expanded waterlily, on its stalk; and in the proper left corner, a *śankha* or conch-shell;—and in the lower part, there seems to have been a floral device. The seal has, at some time or other, been subjected to the action of fire, but not enough to do any very serious damage to the legend and devices on it.—The **weight** of the three plates is about 1 lb. 3 oz., and of the ring and seal, 1 lb. 1 oz.; total 2 lbs. 4 oz.—The average **size** of the letters is about $\frac{7}{8}$ "

¹ *sva-hasta*.—In the original these words have some wavy lines under them, which are intended for an actual representation of the sign-manual. See also page 171 above, note 2.

² The 'Airing and Arang' of maps. Indian Atlas, Sheet No. 91. Lat. $21^{\circ} 12' N.$; Long. $82^{\circ} 1' E.$ —Gen. Cunningham was first informed (*Archæol. Surv. Ind.* Vol. XVII. p. 55) that the plates were found at Ārvi (see page 192 below, and note 4); then (*id.* p. 59), that they were actually obtained at Rāypur, but were most probably found at Āraṅg; and finally (*id.* Preface, p. iii.), that they were found at Āraṅg.

³ The 'Raepoor, Raipur, and Ryepoor,' of maps.

The characters belong to the southern class of alphabets, and give another very good specimen of the 'box-headed' variety of the Central India alphabet, on which I have commented at page 19 above. They include, however, in *chādd*, line 1, the separate form of the lingual *d*, as distinct from the dental *d*. The superscript long vowel *ī* is denoted in rather a peculiar way, by a mark just like an *anusvāra* inside the circle which, by itself, represents the superscript short *i*; see, for instance, *śmāmītī*, line 2, and *vaśhtrīya*, line 4; the burr of the copper, raised in the process of engraving, gives in a few places, in the ink-impression and consequently in the lithograph, a faint mark, very similar to this, inside the short *i* proper, e.g. in *bhāmipān*, line 13; but the difference can, of course, be detected at once in the original plates. The characters also include, in line 24, forms of the numerical symbols for 5 and 20.—The language is Sanskrit. The legend on the seal is in verse; but the inscription itself, except for the benedictive and imprecatory verses in lines 13 to 23, is in prose throughout.—In respect of orthography, we have to notice (1) the use of the *jihvāmūliya* and *upadhānīya*, in *yañ-kāśīchanam*, line 18; and *pradah h-parama*, line 3, and *dhiyañ-pravadānti*, line 14; (2) a constant use of the *anusvāra*, instead of the dental *n*, and the doubling of *t* after it, e.g. in *śmāmītī*, line 1; *uddharamītī*, line 17; and *bhavamītī*, line 18; (3) the doubling of *v* after the *anusvāra*, in *samvatsara*, line 24; (4) the insertion of a superfluous *anusvāra*, in *prasanna*, line *a* of the seal; *śmūmbubhir*, line 1-2; *kutūmbināḥ*, line 5; and *pravadānti*, line 14; (5) the doubling of *k*, in conjunction with a following *r*, in *vikkram-ākkrāmīta*, line *a* of the seal, and *vikkrama*, line 1; (6) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, line 4; (7) the introduction of a superfluous sibilant, in *pradah h-parama*, line 3; *anuddhyātaḥ s-srī*, line 4; and *kutūmbināḥ s-samajñāpayaḥ*, line 5; and (8) the use of *śingha* for *śimha*, line 24, and of *tāmra* for *tāmra*, line 11.

The inscription is one of the *Rāja Jayarāja* or *Mahā-Jayarāja*; and the charter recorded in it is issued from the town of *Śarabhapura*. The date of the engraving of it is recorded, in numerical symbols, as the year five of increasing victory, and the twenty-fifth day, without any specification of the fortnight, of the month *Mārgaśira* (November-December). No era is referred to; and, as we have a similar small date of the year ten in the next inscription of *Mahā-Sudēvarāja*, the fifth year must be simply that of the power or government of *Jayarāja*. It is a non-sectarian inscription; the object of it being only to record the grant, by *Jayarāja* himself, to a *Brāhmaṇa*, of the village of *Pamvā* in the *Pūrvarāshṭra* or *Eastern Country*.¹

As regards the town of *Śarabhapura*, whence the charter was issued General Cunningham² has suggested—in the first place, that, by elision of the initial *ś*, it may, through the forms of 'Arabhpura' and 'Arbhi,' be represented by the modern *Ārvi*,³ the chief town of the *Ārvi Tahsil* or Sub-Division of the *Wardhā District* in the Central Provinces;—and in the second place, that it may be represented by the modern 'Sambal-

¹ So called, perhaps, from its lying on the east of the range of mountains, identified by Gen. Cunningham with the *Mēkala* mountains, which commences near 'Amarkantak,' runs to the south, passing about half-way between *Nāgpur* and *Rāypur*, and then, near 'Wairagarh,' takes a sharp turn to the east, and comes to an end about sixty miles south-east of *Rājim*.

² *Archaeol. Surv. Ind.* Vol. XVII, p. 57 f.

³ The *Arooe*, *Arvi*, and *Arwee*, of maps, &c. Indian Atlas, Sheet No. 72. Lat. 20° 59' N Long. 78° 16' E.—It is thirty miles north-west of *Wardhā*, and about two hundred and thirty miles west by south from *Rāypur*.

pur' or 'Sambhalpur,¹ the chief town of the 'Sambalpur' District in the Central Provinces, where, or in which neighbourhood, another copper-plate inscription of Mahā-Sudēvarāja was obtained.² But neither of these proposed derivations can be upheld. And, if Śarabhapura is represented by any place now existing, we have to look in the maps for some such name as Sarbhōr or Sābhōr.

TEXT.

The Seal.

- a Prasamna^a-h[rida]jasya-aiva vikram-ākrā[m]tta-
vidviṣa[h]
b śrīmatō **Jayarājasya** śāsa[nam] ripu-śāsanam [I*]

First Plate.

- 1 Svasti **Sarabhapurāt** d-vikram³-ōpanata-sāmanṭa-chōḍamaṅ[ī]-prabhā-prasēk-
āt-
2 mbubhir⁴-dhō(dhau)ta-pāda-yugalō ripu-vilāsīn⁵-śīmanṭ-ōddharana-hētu-
3 r-vasu-vasudhā-gō-pradaḥ ḥ-parama⁶bhāgavatō mātāpitri-pā-
4 d-anuddhyātaḥ ś-śrī⁷-**Mahā-Jayarājah** **Pūrvvarāshtrīya-Pamvām⁸**-prati-
5 vāsi-kuṭurmbi⁹naḥ s-sam¹⁰ājñāpayati | Vīditam-astu vō yathā-

Second Plate; First Side.

- 6 smābhir-ayam grama- | s¹¹-tridaśapati-sadana-sukha-pratiśth-ākārō yāva-
7 d-ravi-śaśi-tārā-kiraṇa-pratuhata-ghōr-āndhakāram jaga[d-a*]vatiśṭhatē
8 tāvad = upabhōgyas = sa - nidhis = s - ōpanidhir = a - chāṭa - bhāṭa - prāvēśyas = sa -
9 rva-kara-visarjitaḥ Vāji(ja)sanēya-Kauṇḍinyasagōtraḥ Brahma¹²dēva-
10 svāmīnē II(I)¹³ mātāpitrōr-ātmanaś-cha puṇy-ē(ā)bhivri[d*]dhayē II(I) udaka-
pūrvva[m*]

¹ Indian Atlas, Sheet No. 106. Lat. 21° 27' N.; Long. 84° 1' E.—It is about one hundred and forty-five miles almost due east of Rāypur.

² It has been published by Dr. Rajendralala Mitra, in 1866, in the *Jour. Beng. As. Soc.* Vol. XXXV. p. 195 ff. But the original plates, which were presented to the Society by the finder of them, Col G. Bowie, are not now forthcoming; and the published version is not sufficiently reliable to be reproduced. I have, therefore, not been able to include this inscription in the present volume.

³ From the original plates.—Read *prasanna*.

⁴ Metre, Ślōka (Anuṣṭubh).

⁵ Read *purd*-vikram.—The *t* of *purd* is so small and shallow, that it plainly was only inserted as an afterthought. It is quite superfluous; since its representative by *sam*hi, viz. *d*, had already been duly engraved in conjunction with the following *vi*.

⁶ Read *ambubhir*, or *ambubhir*.

⁷ Read *pradaḥ*-parama, or *pradaḥ parama*.

⁸ Read *anuddhyāt*-śrī, or *anuddhyāt* śrī.

⁹ From a comparison of the corresponding passage in line 4-5 of No. 41, page 198 below, the reading that was intended is probably *pamvōyām* *prativōsi*.

¹⁰ Read *kuṭumbi*, or *kuṭumbi*.

¹¹ Read *nas*-sam, or *nah* sam.

¹² Read *brāmas*, expunging the mark of punctuation.

¹³ Read *sagōtra*-brahma.

¹⁴ This mark of punctuation is exactly like the *visarga*, as the latter is written in this inscription. But, that the sign may be interpreted as either a mark of punctuation or the *visarga*, is shewn by the regularity with which it occurs where a mark of punctuation is appropriate, and a *visarga* is not; and also by the occurrence of the half mark of punctuation, formed in the same way, and impossible to be mistaken for anything else, in lines 5 and 6 above, and 22 below, and in lines 5, 15, 16, and 17, of No 41, page 198 below

Second Plate; Second Side.

- 11 tām̄bra(mra)-śāsanēn-ātisra(sri)sh̄taḥ [11*] Tē yōyam-ēvam-upalabhy-āsy-ājñā-
śravana-
12 vl(vi)dhēyā bhūtva yath-ōchitam bhōga-bhāgam-upanayamttā(ttah) sukham
prativa[t*]sya-
13 tha || Bhavishyataś-cha bhūmipān-anudarśayati ||(1) Dānād¹-viśiṣṭam-a-
14 nupālana-jam purāṇē(nā) ||(1) dharmmēshu niśchita-dhiyaḥ-pravadamnti²
dharmmam ||(1)
15 tasmād=[d*]vijāya suvisuddha-kula-śrutāya ||(1) dattā[m*] bhuvan bhavatu
vō ma[ti*]r-ē-

Third Plate; First Side.

- 16 va gōpt[u*]m || Tad-bhavadbhir-apy-ēshā dattir-anupālayitavyā || Vyāsa-
gltāmś-ch-ātra
17 ślōkān-udāharamti ||(1) Agnē³-apatyam prathamam suvarṇṇa[m*] bhūr-
Vvaishnavi sū-
18 ryya-sut[ā*]ś-cha gāvaḥ [1*] dattās-trayas-tēna bhavamti lōkāḥ yaḥ-
kāñchanam gā[m*]
19 cha mahi[m*] cha dadyā[t*] || Shashṭhim⁴ varsha-sahasrāni svarggē
vasati bhūmi-dah [1*]
20 āchchhētā ch-ānuma[m*]ttā cha tāny-ēva narakē vasē[t*] || Sva-
dattā[m*] para-dattā[m*] vā ya-

Third Plate; Second Side.

- 21 tnā[d-ra]ksha Yudhishṭhira ||(1) mahit(m)-mahimatām chchhrēṣṭhā⁵ dānāch-
chhrēyō-nupālana[m] [11*]
22 Bahubhir-vvasudhā dattā rājabbis-Sagar-ādibhi[h*] | yasya [yasya*] yadā
bhūmis-ta-
23 sya tasya tadā phalam⁶-iti [11*] Sva-mukh-ājñayā uktt(ktk)ṛṇṇam⁷
Acha-
24 lasiṅghēna pravarddhamāna-vijaya-samvatsara 5 Mārgasira 20 5 [11*]

TRANSLATION.

The Seal.

A charter of the illustrious **Jayarāja**,—who verily has a gracious heart; (and) who has overcome (*his*) enemies by (*his*) prowess,—(is) a charter for (*the observance of even his*) enemies!

The Plates.

Hail! From the town of **Śarabhapura**, the illustrious **Mahā-Jayarāja**,—whose two feet are purified by the waters which are the flowing forth of the radiance of the jewels in the locks of hair on the tops of the heads of the chieftains, (*bowing down before*

¹ Metre, Vasantatilaka.² Read *pravadanti*, or *pravadamti*.³ Metre, Indravajrā.⁴ Metre, Ślōka (Anushtubh); and in the following two verses.⁵ Read *irishjha*.⁶ Read *phalam*.⁷ Supply *śāsanam*.


Arang Plates of the R.aja Maha-Jaya-raja
iii

1
 2
 3
 4

16
 18
 20

iii
 6
 8
 10

iii
 22
 24



iii
 12
 14

him), who have been subjugated by (*his*) prowess; who is the cause of the tearing out of the parted hair of the women of (*his*) enemies; who is the giver of treasure and land and cows; who is a most devout worshipper of the Divine One; (*and*) who meditates on the feet of (*his*) parents,—issues a command to the cultivators residing at (the village of) **Pamvā** in the **Eastern Country** :—

(Line 5.)—"Be it known to you, that this village, the source (*by this grant of it*) of (*Our*) ensuring the happiness of (*attaining*) the abode of (Indra) the lord of the gods, is by (*this*) copper-charter conveyed by Us, with libations of water, for the increase of the religious merit of (*Our*) parents and of Ourselves, to Brahmadvāsvāmin, of the Vājasaneyā (*śākhā*) and the Kauṇḍinya *gōtra*,—to be enjoyed as long as the world endures, having the terrible darkness dispelled by the rays of the sun and the moon and the stars; together with (*its*) hidden treasures and deposits; not to be entered by the irregular or the regular troops; (*and*) exempted from all taxes.

(L. 11.)—"Being aware of this, you should be obedient to his commands, and should dwell in happiness, rendering in proper manner (*his*) share of the enjoyment."

(L. 13.)—And he enjoins upon future kings,—“The ancients, whose minds are fixed upon religion, say that the virtue that arises from the preservation (*of a grant*) is greater than (*that which arises from*) making a grant; therefore your mind should verily incline to preserve land that has been given to a Brāhman of very pure family and holy learning. Therefore this gift should be preserved by you also.”

(L. 16.)—And they cite on this point the verses that were sung by Vyāsa :—Gold (*is*) the first offspring of fire;¹ the earth² belongs to (the god) Vishṇu;³ and cows (*are*) the daughters of the sun;⁴ therefore the three worlds⁵ are given by him who gives gold, and a cow, and land! The giver of land dwells in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! O Yudhishtīra, best of kings, carefully preserve land that has been given, whether by thyself, or by another; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant! Land has been given by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)!

(L. 23.)—At the command of (Mahā-Jayarāja's) own mouth, (*this charter*) has been engraved by **Achalasiṅgha**, (*in*) the year 5 of increasing victory, (*in*) (the month) **Mārgaśira**, (*on the day*) 20 (*and*) 5.

¹ Dr. Hultsch (*Ind. Ant.* Vol. XIV. p. 203, note 46) has explained this, by saying that, “according to the Naiyāyikas” or followers of the Nyāya philosophy, “gold consists of fire (*śūdra*).”

² This is the customary reading—In line 39 of the Khārēpāṭaṅ grant of the Śīlāhāra chieftain Rattarāja of Śaka-Samvat 930 (*Jour. Bo. Br. R. As. Soc.* Vol. I. p. 218) the reading is *dyauh*, ‘the sky,’ instead of *bhūh*, ‘the earth’; but I know of no other instance of this variation.

³ Or, perhaps, “the earth (is) Vaishṇavī (the personification of the *śakti* or female energy of Vishṇu).”

⁴ This seems to be explained by the *Rig-Veda*, vii. 101, 6, in which the sun is described as “the bull that impregnates all the cows” (Muir's *Sanskrit Texts*, Vol. IV. p. 112 f.)

⁵ The three worlds are sometimes reckoned as heaven, earth, and the lower region; sometimes as the sky, the atmosphere, and the earth. The latter arrangement seems to be the one referred to in this verse, the sky being represented by cows, as the daughters of the Sun or the god Sūrya, the lord of the sky, and the atmosphere by gold, as the offspring of fire or the god Agni, who is the lord of the Pīṭhis or spirits of deceased ancestors, whose abode is in the region of the air.

No. 41; PLATE XXVII.

RAYPUR COPPER-PLATE INSCRIPTION OF THE RAJA
MAHA-SUDEVARAJA.

THIS inscription,—which was first brought to notice by General Cunningham, in 1884, in the *Archaeol. Surv. Ind.* Vol. XVII. p. 55 ff., and Plates xxvi. and xxvii.; and is now published in full for the first time,—is from some copper-plates that were obtained by Colonel Bloomfield at Rāypur,¹ the chief town of the Rāypur District in the Central Provinces. The original plates are now in the Provincial Museum at Nāgpur.

The plates, of which the first is inscribed on one side only, are three in number, each measuring about 6" by 3½" at the ends and a little less in the middle. They are quite smooth, the edges of them being neither fashioned thicker nor raised into rims. The inscription is in a state of perfect preservation throughout. The plates are of fair thickness; and the letters, though fairly deep, do not shew through on the backs of them at all. The engraving is very good; but, as usual, the interiors of some of the letters shew marks of the working of the engraver's tool.—Towards the proper right end of each plate, there is a hole for a ring to connect them. The ring is circular, about ½" thick and 3½" in diameter; it had already been cut, for the purpose of taking impressions of the plates, when the grant came into my hands; but there is no reason to suppose that it is not the ring properly belonging to the plates. The seal, in which the ends of the ring are secured, is circular, about 3½" in diameter; and, like the seal of the Āraṅg grant of Mahā-Jayarāja, No. 40 above, page 191, and Plate xxvi., it has the appearance of being made of a kind of brass, rather than of copper. It has plainly, at some time or other, been subjected to the action of fire, which, with the effects of wear and tear, has almost completely destroyed the upper surface of it. But there are visible, in relief on a slightly countersunk and concave surface, faint traces of—across the centre, a legend, in two lines, of which, as restored, the text and translation are given below;—in the upper part, a standing figure of the goddess Lakshmi facing full-front; on each side of her, an elephant, standing on a waterlily, with its trunk lifted up over her head, to pour water over her; in the proper right corner, an expanded waterlily, on its stalk; and, in the proper left corner, a *śankha* or conch-shell;—and, in the lower part, there seems to have been a floral device.—The weight of the three plates is about 1 lb. 5¼ oz., and of the ring and seal, 1 lb. 7¼ oz.; total, 2 lbs. 13 oz.—The average size of the letters is about ¼". The characters belong to the southern class of alphabets; and give another specimen of the 'box-headed' variety of the Central India alphabet, on which I have commented at page 19 above. They are of almost exactly the same type as those of the preceding inscription of Mahā-Jayarāja, No. 40 above, page 191, and Plate xxvi. The most noticeable difference is in the formation of the superscript long vowel *ī*; the stroke, similar to an *anusvāra*, which distinguishes it from the short *ī*, being placed, not in the centre of the circle, but on the right side of it, as part of the down stroke of the circle; see, for instance, *vīdsinī*, line 2, and *rdshīrīya*, line 4. The separate sign for the lingual *ḍ*, as distinct from the dental *ḍ*, occurs in *chāḍḍa*, line 1.

¹The 'Raepoor Raipur, and Ryepoor,' of maps, &c. Indian Atlas, Sheet No. 91. Lat. 21° 15' N.; Long. 81° 41' E

We have the very rare initial *au*, in *aupamanyava*, line 10. And forms of the numerical symbols¹ for 9 and 10 occur in line 27.—The language is Sanskrit. The legend on the seal is in verse; but the inscription itself, except for the benedictive and imprecatory verses in lines 15 to 24, is in prose throughout. From a linguistic point of view, we have to notice, in *atishyishṭaka*, line 11-12, the affix that I have commented on at page 69 above.—In respect of orthography, we have to notice (1) the use of the *jihvāmūlīya* and *upadhmanīya*, in *yah-kādāchanam*, line 20; *visarjītaḥ-kūṇḍīnya*, line 9; *pradaḥ-parama*, line 3; and *dhiyaḥ-pravadamnti*, line 16; (2) the doubling of *v*, after the *anusvāra*, in *samvatsara*, line 24; (3) the insertion of a superfluous *anusvāra*, once only, in *pravadamnti*, line 16; (4) the doubling of *k*, in conjunction with a following *r*, in *vikkrama*, line 1; (5) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, line 4; and (6) the use of *siṅha* for *śiṅha*, line 28, and of *tāmra* for *tāmra*, line 11.

The inscription is one of the *Rāja Sudēvarāja* or *Mahā-Sudēvarāja*; and the charter recorded in it is issued, as in the case of the preceding inscription of *Mahā-Jayarāja*, from the town of *Śarabhapura*. The occasion of its issue was the *uttarayāna*, or the sun's commencement of his progress to the north. The date of the engraving of it is recorded, in numerical symbols, as the year ten of increasing victory, and the ninth day, without any specification of the fortnight, of the month *Māgha* (January-February). No era is referred to; and the tenth year must be simply that of the power or government of *Sudēvarāja*. It is a non-sectarian inscription; the object of it being only to record the assent of *Sudēvarāja* to the grant, to two *Brāhmaṇas*, of the village of *Śrīśāhikā*, in the *Pūrvarāshtra* or *Eastern Country*.

TEXT.²*The Seal.³*

a Prasanna⁴-hridayasy-aiva vikram-akkrānta-vidvishah
 b śrīmat-Sudeva⁵rājasya śāsanam ripu-śāsanam [11*]

First Plate.

1 Om Svasti Śarabhapurād-vikram-ōpanata-sānanta-makuta-chōḍā-manḥ-
 2 prabhā-prasēk-āmbu-dhō(dhau)ta-pāda-yugalō ripu-vilāsini-simant-ōddha-
 3 rapa-hētur-vvasu-vasudhā-gō-pradaḥ⁶=paramabhāgavatō .nātāpitri-

¹ The symbol for the day might perhaps be interpreted as 30. But it seems, on the whole, to be a transitional form of the symbol for 9, from which the modern *Dēvanāgarī* decimal figure 9 was developed.—Gen. Cunningham read the symbol for the year as 80, not 10; but I do not think this can be upheld. It is evidently a square and upright variety of the second form of 10 given in col. 5 of Dr. Bhagwanlal Indrajī's Table in the *Ind. Ant.* Vol. VI. p. 44 f.

² From the original plates.

³ With the exception of the word *prasanna* at the beginning of the first line, the legend is almost entirely obliterated. But there are faint indications here and there, which, with the help of the legend on the seal of No. 40, page 193 above, and Plate xxvii., enable us to restore it as above.

⁴ Metre, *Ślōka* (Anusṭubh).

⁵ The lithograph in the *Archæol. Surv. Ind.* Vol. XVII. Plate xxvi. shews *śrī-Mahā-Sudēva*. But this reading is not legible on the seal; and, as it does not suit the metre, it cannot have been so engraved.

⁶ Here, and in line 16 below, the *jihvāmūlīya*, instead of being clearly formed as in lines 3 and 14 of No. 40, Plate xxvi., is indicated, hardly perceptibly, by little more than a vertical division of the square top of the *pa*.

- 4 pād-anuddhyātās-śrī-Mahā-Sudēvarājaḥ Pūrvvarāshṭriya-Srisāhi-
5 kāyām prativāsi-kuṭumbīnas-samājñāpayati | Vīditam-astu vō
6 yath-āsmābhir-ayam grāmas-tri(tri)daśapati-sadana-sukha-pratishṭh-āka-

Second Plate; First Side.

- 7 rō yāvad-ravi-śāsi-tārā-kirāṇa-pratihata-ghōr-āndhakāram jagad-ava-
8 tishṭhatē tāvad-upabhōgyas-sa-nidhis-s-ōpanidhir-a-chāta-bhaṭa-prāvēśya[h*]
9 sarvva - kara - visarjitaḥ = Kō(kau)ṇḍinyasagōtra - Vājasanēya - Savit[rī*] -
10 svāmīna [A*]tmīya-kanyā-prāḍānē[na*] Aupamanyava-[Va*]tsasagōtra yā'mā-
11 trō[h*] Nāgavatsasvārī-Bandhuvatsasvāmīnōs-tāmbra(mra)-śāsanēn-āti-
12 stri(sri)shtakō bhūtv-āsmābhir-apy-uttarāyaṇō mātāpitrōr-ātmanaś=cha

Second Plate; Second Side.

- 13 puny-ē(ā)bhivriddhayē-numōditaḥ [II*] Tē yūyam-ēvam-upalabhy-āsy-ājñā-śra-
14 vaṇa-vidhēyā bhūtvā yath-ōchitaḥ bhōga-bhāgam-upamupanayantas*-su-
15 kham prativatsyatha [II*] Bhavishyatas=cha bhūmipā[n-a*]nudarśayati |
Dānād-viśiṣṭa-
16 m-anupālana-jam purāṇē(nā) ddha(dha)rmēshu nīschita-dhiyaḥ-pravadamntī'
dharmam | tasmā-
17 d=[d*]vijāya su⁶-viśuddha-kula-śrutāya dattam bhuvam bhavatu vō matir-
ēva gōptum [II*] Ta-
18 d-bhavadbhir-apy-ēśhā dattir-anupālayitavyā [II*] Vyāsa-gītā[m*]ś-ch-ātra
ślōkān-udāharanti [I*]

Third Plate; First Side.

- 19 Agnē⁹-apatyam prathamam suvarṇa[m*] bhūr-vvaishṇavi sūryya-
sutās=cha gāvā[h*] dattā-
20 s-trayas-tēna bhavanu lōkā yah-kāñchanam gan-cha mahīn=cha
dadyāt [II*] Shashṭi¹⁰-va-
21 rsha-sahasrāni svarggē mōdati bhūmi-daḥ āchchhētā ch-ānumantā
cha tāny-ē-
22 va na[ra*]kē vasēt [II*] Bahubhir-vvasudhā dattā rājabhi[h*] Sagar-
ādibhih yasya
23 yasya yadā bhūmis-tasya tasya tadā phalam [II*] Sva-dattā[m*] para-
dattā[m] [vā*] ya
24 tñād-raksha Yudhishṭhira mahī¹¹ mahimatā[m*] śrēshṭha dānāch=chhrēyō-
nupāla¹².

¹ Before | this word, *yāmātrō*, there is a cross, to indicate that this is not the place to which it properly belongs. It is plain that the reading intended in lines 9 to 11 was *Savitrisvāmīna ātmīya-kanyā-prāḍānēna yāmātrōr=Aupamanyava-Vatsasagōtra-Nāgavatsasvāmī* &c.

² Before this *trō*, *mi* was engraved, and then cancelled; and *ba* seems to have been engraved and cancelled in the place where the *trō* stands.

³ Over this *visarga*, there is a cross, to indicate that something has to be inserted here; *vis.* the passage commencing with *asmīn=ēva grāmē*, in lines 25 and 26 below.

⁴ Read *upalabhy=astayōr-ājñā*.

⁵ Read *bhāgam=upanayantas*.

⁶ Metre, Vasantatīlaka.

⁷ Read *pravadanti*, or *pravadamti*

⁸ First *si* was engraved, and then *u* was added, without the ; being sufficiently cancelled.

⁹ Metre, Indravajrā.

¹⁰ Metre, Ślōka (Anushṭubh); and in the following two verses.

¹¹ Read *mahīm*.

¹² The proper context is *lanam=iti*, in line 27.

Third Plate; Second Side.

- 25 Asmin[n*]-ēva grāmē pūrvva-taṭākasya paryyatta(ṅta)-bhūmi-vapra-baddhā Śrī-
 26 vā'pikā panthānam yāvaj-jā(jyē)shṭha iti kṛtvā Nāga[va*]tsasvāminē grām-
 arddhasy-ādhi¹kā dattā
 27 lanam²-iti || Sva-mukh-ājñayā pravarddhamāna-vijaya-sarhvvatsara 10
 Māgha 9
 28 ukti(tkl)ṛṇṇa[m*]³ Drōnasinghā(ṅghē)na [11*]

TRANSLATION.

The Seal.⁴

A charter of the illustrious **Sudēvarāja**,
 —who verily has a gracious heart; (and)
 who has overcome (his) enemies by (his)
 prowess,—(is) a charter for (the observance
 of even his) enemies!

The Plates.

Om! Hail! From the town of **Śarabhapura**, the illustrious **Mahā-Sudēvarāja**,—
 whose two feet are purified by the waters which are the flowing forth of the radiance
 of the jewels in the locks of hair (*wound*) in the tiaras of the chieftains, (*bowing down
 before him*), who have been subjugated by (his) prowess; who is the cause of the tearing
 out of the parted hair of the women of (his) enemies; who is the giver of treasure and
 land and cows; who is a most devout worshipper of the Divine One, (and) who meditates
 on the feet of (his) parents,—issues a command to the cultivators residing at (the village
 of) **Śrīsāhikā** in the **Eastern Country** :—

(Line 5.)—“Be it known to you, that this village, the source (*by this grant of it*) of
 (Ours) ensuring the happiness of (*attaining*) the abode of (Indra) the lord of the gods,—
 which has been conveyed by a copper-charter to Nāgavatsasvāmin and Bandhuvatsa-
 svāmin, of the Aupamanyava (*śākhā*) and the Vatsa *gōtra*, who, by the gift in marriage of
 his daughters, are the sons-in-law of Savitṛisvāmin of the Kauṇḍinya *gōtra* and the Vājasa-
 nēya (*śākhā*); to be enjoyed as long as the world endures, having the terrible darkness dis-
 pelled by the rays of the sun and the moon and the stars; together with (*its*) hidden treasures
 and deposits; not to be entered by the irregular or the regular troops; (and) exempted
 from all taxes,—has, at the time of the sun's commencement of his progress to the north,

¹ Before this *vā*, there is a cross, to indicate that something has to be inserted here, or, more properly, before the *śrī*; viz. *grām-arddhasy-ādhi¹kā*, from the end of the line—
 The reading intended in these two lines was—*Asminn-ēva grāmē pūrvva-taṭākasya paryyanta-
 bhūmi-vapra-baddhā grām-arddhasy-ādhi¹kā Śrīvāpikā panthānam yāvaj-jyēshṭha iti kṛtvā Nāga-
 vatsasvāminē dattā*. And this passage should properly have been inserted after *anumōditāḥ*, in line
 13 (see page 198 above, note 3.)

² Over this *āhi* there is a cross, to indicate that something has to be inserted here; viz the
 syllables *kā dattā*, which are placed between the lines, below *minē*

³ This is the proper context of *nupā*, at the end of line 24.

⁴ Supply *śāsanam*.

⁵ As restored, with the help of the few letters that remain, on the analogy of the legend on the
 seal of the **Āraṅg** grant of Mahā-Jayarāja, No. 40 above, page 194

been assented to by Us indeed, for the increase of the religious merit of (*Our*) parents and of Ourselves.

(L. 13.)—"Being aware of this, you should be obedient to their commands, and should dwell in happiness, rendering in proper manner (*their*) share of the enjoyment."

(L. 15.)—And he enjoins upon future kings,—“The ancients, whose minds are fixed upon religion, say that the virtue that arises from the preservation (*of a grant*) is greater than (*that which arises from*) making a grant; therefore your mind should verily incline to preserve land that has been given to a Brâhman of very pure family and holy learning. Therefore this gift should be preserved by you also.”

(L. 18.)—And they cite on this point the verses that were sung by Vyâsa—Gold is the first offspring of fire; the earth belongs to (the god) Vishnu; and cows are the daughters of the sun: therefore the three worlds are given by him who gives gold, and a cow, and land! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! Land has been given by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)! O Yudhishthira, best of kings, carefully preserve land that has been given, whether by thyself, or by another; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant!

(L. 25.)—In this same village, the irrigation-well called Śrīvāpikā, constructed within the mound on the land that skirts the eastern tank, (*and*) extending up to the road, is given to Nâgavatsasvâmin, in excess of (*his exact*) half of the village, because he is the elder.

(L. 27.)—At the command of (Mahâ-Sudêvârâja's) own mouth, (*in*) the year 10 of increasing victory, (*in*) (the month) Mâgha, (*on the day*) 9, (*this charter*) has been engraved by Drôṇasingha.

No. 42; PLATE XXVIII.

APH SAD STONE INSCRIPTION OF ADITYASENA.

THIS inscription was discovered by Major Markham Kittoe, some time anterior to 1850; but the first notice of it, that I have been able to trace, is General Cunningham's mention of it in 1863, in his report for the year 1861-62, which was issued as a supplement to the *Journal* of the Bengal Asiatic Society, Vol. XXXII. p. iii ff., and was in 1871 reprinted in the *Archæol. Surv. Ind.* Vol. I., where this inscription is referred to on page 40.—In 1866, in the *Four. Beng. As. Soc.* Vol. XXXV. p. 267 ff., Dr. Rajendralala Mitra published his reading of the text, and a translation of it, from a transcript of the original, in modern Dêvanâgarî characters, which Major Kittoe had given to General Cunningham in 1850.—In 1882, in the *Archæol. Surv. Ind.* Vol. XV. p. 11, General Cunningham supplemented this translation, by notifying, from his own examination of a rubbing of the original inscription made by Major Kittoe, which had meanwhile been discovered by Mr. J. D. M. Beglar in a box of inscriptions in the Bengal Asiatic Society's Library, that the name of the second king was Harshagupta; not Hashkagupta, as read by Major Kittoe.—And in 1883, in the *Archæol. Surv. Ind.* Vol. XVI. p. 79, he further notified that Dr. Bhagwanlal Indrajî, apparently in a letter to him, had indicated that

the name of *Īśanavarman* should be substituted, in line 7, for the *Śāntavarman* of Major Kittoe's transcript.

Aphsad or **Aphsād**,¹ also called **Jāfarpur**, is a village near the right bank of the *Sakarī* river, about fifteen miles towards the north-east of *Nawāda*,² the chief town of the *Nawādā* Sub-Division of the *Gayā* District in the *Bengal Presidency*. The inscription is on a stone-slab, that was found here, and was afterwards removed by Major Kittoe, in order "to re-examine it, and to restore it as much as possible, before having it fixed in a pedestal near the *Varāha*" in *Aphsad*. According to the local statement, Major Kittoe removed the stone to *Nawādā*; but General *Cunningham* failed to find it, or to hear anything more of it, either there, or at *Gayā* and *Benares*. The loss of the original stone, however, is as well compensated for as is possible by the existence, in the Library of the *Bengal Asiatic Society* at *Calcutta*, of an exceptionally good red-chalk rubbing, made by Major Kittoe himself, from which I now edit the inscription, and from which my lithograph has been prepared.

The writing, with its margin, covers the entire front of the stone; and is apparently on a slightly countersunk surface about 2' 9" broad by 1' 5½" high, with a corresponding rim from ¾" to 1" broad. It has suffered a great deal from the effects of the weather, about the centre of the stone; but, even here, nothing of a historical nature seems to be lost, except perhaps, in line 15, a completion of the hint as to the relations between *Mādhavagupta* and *Harshadēva*, i.e. *Harshavardhana* of *Kanauj*. The rest of the inscription is very legible. The impression indicates that the stone has been broken at the lower proper right corner; but, as shewn in the note to line 25 of the Text, the stone seems to have been originally imperfect here; and not so much of the writing has been lost, as would be expected at first sight.—The size of the letters varies from about ⅙" to ⅙". The characters belong to the northern class of alphabets, and present a very marked development as contrasted with the preceding plates of this volume. They belong to a particular type, to which the special name of *Kuṭila* has come to be attached, in consequence of the upright strokes having at the bottom a small tail which is 'crooked, curved, or bent' (*kuṭila*) to the right. The term *Kuṭila* actually occurs in the 'Dewal' inscription³ of (*Vikrama*)-*Samvat* 1049; in the last line of which it is recorded that "this (eulogy) has been written by the scribe *Takshāditya*,—(a native of) the (country of) *Gauḍa*; and the son of *Vishnuhari*,—who is well acquainted with the curved letters." The term used here for "curved letters" is *kuṭil-āksharāṇi*. It does not seem to be employed with the specific object of recording a standing name of this style of writing; any more than the expression *vīkat-āksharā*, " (an eulogy) in beautiful letters," is used in that way in line 27 of the present inscription; and *ruchir-ākshara-panttibhīḥ*, " (this eulogy has been engraved) in lines of pleasing letters," in line 27 of an inscription in the Provincial Museum at *Nāgpur*; and *sad-varṇā*, " (an eulogy) in excellent letters," in line 41 of the *Sāsabāhū* temple inscription of *Mahīpāla*.⁴ But the term *Kuṭila* fits this type of letters so well, that, as the name has been

¹ The 'Aphsar, Ufsund, and Ufsund-Jafurpoor,' of maps, &c. *Indian Atlas*, Sheet No. 112. Lat 25° 4' N.; Long. 85° 44' E.

² The 'Nawāda, Newadeeh, Nowada, and Nowāda,' of maps, &c.

³ *Archaeol. Surv. Ind.* Vol. I. p. 355, Pl. li.

⁴ *Ind. Ant.* Vol. XV. p. 41.

applied to the alphabet for so long a time, there seems no objection to continuing it. The alphabet of the present inscription might be called the Kuṭiḷa variety of the Magadha alphabet of the seventh century A.D. It really differs but little from the modern Dēvanāgarī. The form of the lingual *dh*, which occurs in *gādhā*, line 1, and *āridha*, line 2, is almost quite identical with the modern Dēvanāgarī form. The form of the lingual *d*, which occurs in *chūddā*, lines 3 and 16, in *khadga*, line 18, and *jadō*, line 21, is still rather transitional, differing but little from the form of the dental *d*. And the most antique remnant in the whole inscription is the form of *r*, in conjunction with a following consonant, e.g. in *harsha*, lines 2 and 15, *ghanur-bhīma*, line 2, *sindhur-lakshmi*, line 7, and *artha*, line 12; following the custom noted at several places above, but practised in the earlier inscriptions in respect only of *r* in combination with a following *y*, it is formed throughout on the line of writing, instead of above it, and in the *rya* of *śaurya*, in line 7, we have an exact reproduction of the same letter as it was written nearly two centuries before, e.g. in *kuryāt* in line 12 of the Majhgawām plates of the Mahārāja Hastin, of the year 191, No. 23 above, Plate xiv.—The language is Sanskrit; and the inscription is in verse throughout. It offers about the earliest instance of the hyperbolic expressions and mythological allusions with which the later inscriptions abound, distinguishing them so completely from the artistic, concise, dignified, and frequently really poetical, style of the more ancient records.—In respect of orthography, the only points that call for notice are (1) the doubling of *l*, in conjunction with a following *r*, once, in *lāpatra*, line 21; where, however, it may possibly be due to a mistaken idea as to the etymology of the word; and (2) the use throughout of *v* for *b*, e.g. in *vivuddha*, lines 9 and 11; *valinō*, line 14-15; *vahśūva*, line 15; and *vibhratī*, line 17.

The inscription is one of **Ādityasēna**, of the family of the **Guptas of Magadha**. It is not dated. It is a Vaishnava inscription; the principal object of it being to record the building, by **Ādityasēna**, of a temple of the god Vishnu. But it also records the building of a religious college or monastery by his mother **Śrīmatī**, and the excavation of a tank by his wife **Kōṇadēvi**.

TEXT.¹

- 1 Ōm [H²] Āsid³=danti-sahasra-gādha-katakō vidyādhar-ādhyāsitaḥ sad-
vaśīḥ sthira unnatō girir-iva śrī-Krishnaguptō nripaḥ | dṛipt-
ārātī-madāndha-vāraṇa-ghatā-kumbhasthalīḥ kshundatā yasy-āsamkhyā-
ripu-pratāpa-jayinā dōshnā mṛigēndrāyitaḥ || Sakalāḥ⁴ kalāṅka-rahitaḥ
- 2 kshata-timiras-tōyadhēḥ śaśāṅka iva | tasmād-udapādi sūtō dēvaḥ śrī-
Harshagupta iti || Yō⁵ yōgy-ākāla-bēl-āvanata-dṛiḍha-dhanur-bhīma-
vān-augha-pātī mūr[t⁶]jaiḥ sva-svāmi-lakshmi-vasatī-vimukhitair-lkshitaḥ
s-āsrupātāḥ | ghōrānām-ā
- 3 havānam likhitam-iva jayam ślāghyam-āvirdadānō vakshasy-uddāma-
sastra-vraṇa-kāthina-kina-granthi-lēkhā-chchhalāna || Śrī⁷. Jivitaguptō-bhūt-
kshitiśa-chōḍāmanīḥ sutas-tasya | yō dṛipta-vairi-nārī-mukhaalina-van-
aika-śésēra⁸karah ||

¹ From Major Kitter's impression; so, also, the lithograph.

² Metre, Śārdūlavikrīḍita.

³ Metre, Āryā

⁴ Metre, Sragdharā.

⁵ Metre, Āryā.

⁶ Read *tīra*.

- 4 Mukta¹mukta²-payah-pravāha-sīśirās-ōttuṅga-tālvana-bhrāmyad-danti-kar-āvalūna-kadali-kāṇḍāsu vēlās-vapi | śchyōtat-sphāra-tushāra-nirjhara-payah-sītē-pi-sailē sthitān=yasy-ōchchair-dvishatō mumōcha
- 5 na mahā-ghōrah pratāpa-jvarah || Yasy³=ātimānusham karma drīsyatē vismayaj=jan-aughēna | adyāpi Kōsavardhana-tatāt-plutam Pavana⁴jasy-ēva || Prakhryāta-śaktim-ājishu purāhsaram śrī-Kumā-
- 6 raguptam=iti | ajanayad=ēkam sa nripō Hara iva śikhivāhanam tanayam || Utsarppad⁵-vāta-hēlā-chalita-kadalika-vichi-mālā-vitānah prōdyad-dhūli-jalaugna-bhramita-guru-mahā-matta-
- 7 mātamga-sailah | bhimah śr-Ī⁶śānavarmma-kshītipatīśasīnah sainya-dugdhdōda-sindhur-llakshmi-samprāpti-hētuh sapadi vimathtō Mandarī-bhūya yēna || Śāurya⁷-satyavrata-dharō yah Prayāga-gatō dha-
- 8 nē | ambhas-iva karīsh-āgnau magnah sa pushpa-pūjītah || Śrī-Dāmōdaraguptō=bhūt=tanayas=tasya bhūpatēh | yēna Dāmōdarēn-ēva Daityā iva hatā dvishah || Yō⁸ Maukharēh samitish-ōddha-
- 9 ta-Hūna-sainyā valgad-ghatā vighatayann=uru-vāraṇānām | sammūrchchīlūtah sura-vadhū(dhū)r=varayam(n) mam-ēti tat-pāp[ī]pankaja-sukha-sparśād-vīvu(bu)ddhah || Guṇavad⁹-[d¹⁰]vijja-kanyānā[m¹¹] nān-ālamkāra-yauvana-
- 10 vatnām | pariṇāyitavan=sa nripah śatam nisrisht-āgrahārānām || Ś[ri]¹² Mahāsēnaguptō=bhūt=tasmād=vr-āgran[ī]¹³ sutah | sarva-vīra-samājēshu lēbhē yō dhuri vīratā[m¹⁴] || Śr[ī]mat¹⁵.Susthitavarmma-yuddha-vijaya-
- 11 slāghā-pad-ānkam muhur=yasy-ādyāpi vīvu(bu)ddha-kunda-kumuda-kshunn(?)-āchchha-hāra[]ta[m¹⁶] | Lōhityasya tat[ē]shu ś[ī]tala-tal[ē]sh-ōtp[h]u[]jā-nāgadri[]jma-chchhāyā-supte-vīvu(bu)ddha-s[ī]ddha-m[ī]thun[ai]h sph[ī]tam yaśō giyatē || Vasudēva-
- 12 d¹¹=iva tasmāch=Chhrī-s(ē)vana-[śō(?)]bh-[ō]dita-charana-yugah | śrī-Mādhva-guptō=bhūn-Mādhava iva vikram-aika-rasa[h¹⁷] || [— — — — —] a)num[n]r[ī]tō dhuri ran[ē] slāghāvatām=āgran[ī]h sō(sau)janyasya nidhānam=artha-nidha(cha)-
- 13 ya-tyāg-ō[d¹⁸]dharānām dha(?va)ra[h] | lakshmi[ī]-sa[tya-sa]rasvatī-kulagriha[m] dharmasya sētur-driḍhah pū(?)yyō(?) n=ās[ī]t[ī] sa bh[ū]tal[ē] [— — — — —] [—] sadgun[āih] || Chakra[m] pāni-talēna sō=py=udavahat=tasy=āpi śārngā[m] dhanu-
- 14 r-nāśāy-āsuhrīdā[m] sukhāya suhrīdām tasy-āpy=asir=nandakah | prāptē vidvishatām vadhē pratihat[—] tēn-āpa[— — — — —] — — — — — dha(?)ri(?)ma(?)[— —]nyāh prapēmur=jjanāh || Ajau¹⁹ mayā vīnihatā va(ba)-

¹ Metre, Śārdūlavikrīḍita. ² Metre, Āryā; and in the following verse. ³ Metre, Sragdhārā

⁴ The lower part of the *f*, and all except the extreme end of the *r*, either were left unfinished or have been broken away. But enough remains to shew clearly what the *akshara* really is.

⁵ Metre, Ślōka (Anushṭubh); and in the next verse.

⁶ Metre, Vasantatilaka.

⁷ The metre is faulty here; instead of two long syllables, we ought to have two short and one long.

⁸ Metre, Āryā.

⁹ Metre, Ślōka (Anushṭubh).

¹⁰ Metre, Śārdūlavikrīḍita.

¹¹ Metre, Āryā.

¹² Metre, Śārdūlavikrīḍita; and in the next verse.

¹³ Metre, Vasantatilaka; and in the next verse.

- 15 linó dvishan[taḥ] kritya[m] na m[é*]-sty-aparam-ity-avadhārya vīraḥ [I]
 śrī-Harshadēva-nija-sa[m]gama-vāñchaya cha(?) [— — — — — — — — — —]
 — — — — — [II] Ś[r]īmān=va(ba)bhōva dalit-āri-karīndra-kumbha-muktā-
 rajah-
- 16 paṭala-pāmsula-maṇḍalāgrah I Ādityasēna iti tat-tanayaḥ kshītīśa-
 chūdāmaṇ[i]r-dda[— — — — — — — — — —] [II] [— — — — — — — — — —]m-
 āgatam=ari-dhvamsa-ōttham=āptam yaśaḥ ślāghyaṃ
- 17 sarvva-dhanushmatām pura iti ślāghaṃ parāṃ vi(bi)bhrati I aśīrvvāda-
 paramparā chi(?)ta-sak.i(?)d[— — — — — — — — — —]
 — — — — — yāmāsama(?) II Ājau³ svēda-chchhalēna dhva-
- 18 ja-pata-śikhayā mārjyatō dāna-paṅkam khaḍgaṃ kshunnēna muktā-śakala-
 sikatī[i(?)kri(?)tya(?) [— — — — — — — — — —]
 —]matī[?]a-mātā[m]ga-ghātam tad-gauḍh-ākñishta-sarppad-va(ba)-
- 19 hala-paṇmala-bhrāta(ṅta)-matt-āli-jālaṃ II Āva(ba)ddha³-bhima-vikata-bhrukuṭi-
 kathōra-sa[m]g[r]āma[— — — — — — — — — —] I — — — — — [— — — — —]va-
 vallabha-bhritya-vargga-gōsthīshu pēśa-
- 20 latayā parihāsa-śilāḥ II Satya⁴-bharttri-vratā yasya mukh-ōpadh[ā]na-
 tāpasi I par[i]hās[— — — — — — — — — —] [II] [— — — — — — — — — —]
 —]ñāh sakala-ripu-va(ba)la-dhvamsa-hētur-ggari-
- 21 yān=nistriś-ōtkhāta-ghāta-śrama-janita-jadō=py=ūrjita-sva-pratāpah I yuddhē
 matt-ēbha-kumbhastha[la — — — — — — — — — —] — — — — —]śv[ē]t-
 ātapattra-sthagita-vasumati-mandalō lō-
- 22 kapālah II Ājau³ matta-gajēndra-kumbha-dalana-sphīta-sphurad-dōr-yugu
 dhvast-Anē(?)ka(?)-ripu-prabhāva-v[— — — — — — — — — —] yaśō-maṇḍalah I nyast-
 aśēsha-narēndra-mauli-charaṇa-sphāra-pratāp-āna-
- 23 lō lakshmivan-samar-ābhimāna-vimala-prakhyāta-kīrttir-riṇipah II Yēn=ēyaṃ
 śarad-indu-vimva-dhavalā prakhyāta-bhūmandalā lakshmi-saṃgama-
 kāmshayā su-mahatī kirttiś-chiram kōpitā I yātā sā-
- 24 gara-pāram-adbhutatamā sāpatnya-vaiśād-āhō tēn=ēdam bhavan-ōttamam
 kshutibhujā Vishṇōh krite kāritam II Taj²-jananyā mahādēvyā
 Śrīmatyā kārītō mathah I dhārmikēbhya svayam-dattah sura-lō-
- 25 ka³-grīh-ōpanah II Śamki³-ēndu-sphatika-prabhā-pratisama-sphāra-sphurach-
 chhikaram nakra-krañtī-chalat-taranga-vilasat-pakshu-pranṛityat-timī I rājīyā
 khānitam=adbhutam su-tapasā pēpiyamānam
- 26 janais=tasya-siva priya-bhāryayā narapatēh śrī-Kōnadēvyā saraḥ II
 Yāvach-chandra-kalā Harasya śirasi Śrīḥ Śārnginō vakshasi
 Vra(bra)hm-asyē cha Sarasvatī krita-

¹ Metre, Śārdūlavikrīḍita² Metre, Sragdharā³ Metre, Vasantatilaka.⁴ Metre, Ślōka (Anushtubh)⁵ Metre, Sragdharā.⁶ Metre, Śārdūlavikrīḍita; and in the next verse.⁷ Metre, Ślōka (Anushtubh).

⁸ The stone appears to be broken away at this corner. But there seems also to have been some fault here when the inscription was engraved, since,—though nine *aksharas* are entirely lost, and two more are partly destroyed, at the beginning of line 27, which commenced at the edge of the stone,—the metres shew that nothing is lost at the beginning of line 26, which was commenced at the distance of about nine *aksharas* from the edge of the stone, and that only four *aksharas* are lost at the beginning of line 28, which was commenced at the distance of about sixteen *aksharas* from the edge of the stone.

⁹ Metre, Śārdūlavikrīḍita; and in the next verse.

- 27 [— — — — —] | [bhôgē] bhûr-bhujag-ādhipasya cha tadid-
yāvad-ghanasy-ōdarē tāvat-kirtim-ih-ātanōti dhavalām-Ādityasēnō
nripāḥ || Sūkshmaśivēna¹ Gaudēna praśastir-*vvikāt-āksharā* ||(1)
- 28 [— — —]mā(?)mitā samyag-dhārmikēṇa su dhimatā¹ |

TRANSLATION.

Om! There was a king, the illustrious **Krishnagupta**, who was like a mountain, in that (*his*) cities, like the slopes of a mountain, were crowded with thousands of elephants; in that he was attended by men of learning, as a mountain is inhabited by Vidyādhara; in that he was of good descent, as a mountain is possessed of excellent bamboos; (*and*) in that he was firm (*and*) lofty; (*and*) whose arm played the part of a lion, in bruising the foreheads of the array of the rutting elephants of (*his*) haughty enemies, (*and*) in being victorious by (*its*) prowess over countless foes.

(Line 1.)—Just as the full-moon, destitute of spots, the destroyer of the darkness, was produced from the ocean, so from him there was born a son, the majestic one, named the illustrious **Harshagupta**, who,—raining down a terrible flight of arrows from (*his*) firm bow that was bent with ease at the befitting proper time, (*and*) being gazed upon with copious tears by (*his enemies*) who, averse to the abode of the goddess of fortune being with (*her*) own lord, were stupefied (*at being unable to prevent it*),—was (*always*) displaying a glorious triumph, the written record as it were of terrible contests, in the guise of the rows of the knots of hard callous places, caused by wounds from many weapons, on (*his*) chest.

(L. 3.)—His son was the illustrious **Jivitagupta (I.)**, the best among kings, who was a very cold-rayed (moon) to (*with her*) the waterlilies that were the countenances of the women of (*his*) proud enemies. The very terrible scorching fever (*of fear*) left not (*his*) haughty foes, even though they stood on seaside shores that were cool with the flowing and ebbing currents of water, (*and*) were covered with the branches of plantain-trees severed by the trunks of elephants roaming through the lofty groves of palmyrapalms; (*or*) even though they stood on (*that*) mountain (Himālaya) which is cold with the water of the rushing and waving torrents full of snow. Even still his superhuman deeds are regarded with astonishment by all mankind, like the leap of (the monkey Hanumat) the son of the Wind² from the side of (the mountain) Kōśavardhana.³

¹ Metre, Ślōka (Anushtubh).

² Hanumat was one of the most celebrated of a host of semi-divine apes, who were created to become the allies of Rāmachandra in his war with Rāvaṇa. The leaders of this army of monkeys were supposed to be the offspring of various gods; and Hanumat was the son of Pavana or Māruta, the Wind. One famous leap taken by Hanumat was from the mainland, over the sea, onto Ceylon, in order to discover the whereabouts of Śītā. Another was his leap back from Ceylon to the mainland, after setting Rāvaṇa's city on fire, on which occasion he sprang from a mountain which sank into the ground under the shock. A third leap, or flight through the air, was when he went to the mountain Gandhamādana, to procure a medicinal herb to cure the wounded Lakshmaṇa. Which of these leaps is alluded to here, is difficult to say, as Kōśavardhana does not seem to be given in the epic as the name of a mountain at all; and I cannot find the names of the mountains from which his leaps were taken.

³ The only other mention that we have of a mountain Kōśavardhana, is in line 17 of the Shērgadh (Kōśā) Buddhist inscription (*Ind. Ant.* Vol. XIV. p. 46), where it seems to denote the hill on which the Fort of Shērgadh now stands. This may, or may not, be one of the mountains from which Hanumat took one of his flights through the air.

(L. 5.)—That king begat one son, by name the illustrious **Kumāragupta**, of renowned strength, a leader in battle; just as (the god) Hara begat a son, (Kārttikēya) who rides upon the peacock;—by whom, playing the part of (the mountain) 'Iandara,¹ there was quickly churned that formidable milk-ocean, the cause of the attainment of fortune, which was the army of the glorious **Īśānavarman**, a very moon among kings, (and) which had for (its) spreading rows of waves the plantain-trees that were wantonly shaken to and fro by the roaring wind (caused by the marching of the troops), (and) had (its) rocks, that were the ponderous and mighty rutting elephants (of the forces), whirled round and round by the masses of water that were the rising dust (stirred up by the soldiers). Cherishing heroism and adherence to the truth, (even) in (the possession of) wealth, he went to **Prayāga**; (and there), honourably decorated with flowers, plunged into a fire (kindled) with dry cow-dung cakes, as if (simply plunging to bathe) in water.²

(L. 8.)—The son of that king was the illustrious **Dāmōdaragupta**, by whom (his) enemies were slain, just like the demons by (the god) Dāmōdara. Breaking up the proudly stepping array of mighty elephants, belonging to the **Maukhari**, which had thrown aloft in battle the troops of the **Hūnas** (in order to trample them to death), he became unconscious (and expired in the fight); (and then, waking again in heaven, and) making a choice among the women of the gods, saying " (this one or that) belongs to me," he was revived by the pleasing touch of the waterlilies that were their hands. He, (while he was) king, gave away in marriage a hundred daughters of virtuous Brāhmins endowed with many ornaments and with youth, (and) dowered with *agrahāra*-grants.

(L. 10.)—From him there was a son, the illustrious **Mahāsēnagupta**, the leader, among brave men; who in all the assemblages of heroes acquired a (reputation for) valour (that stood) in the foremost rank;—whose mighty fame, marked with the honour of victory in war over the illustrious **Susthitavarman**, (and) [white] as a full-blown jasmine-flower or waterlily, or as a pure necklace of pearls pounded into little bits (?), is still constantly sung on the banks of (the river) *Lōhitya*, the surfaces of which are (so) cool, by the Siddhas in pairs, when they wake up after sleeping in the shade of the betel-plants that are in full bloom.

(L. 11.)—As (the god) Mādhava, whose feet are graced by the attentions of (the goddess) Śrī, (was born) from Vasudēva, so from him there was (a son), the illustrious **Mādhavagupta**, finding pleasure only in prowess, whose feet were graced by the attentions of the goddess of fortune. He being remembered in the foremost rank ; being the leader of those who acquire renown in war; (and) being a very store-house of goodness, the best of those who excel in the collection and bestowal of riches, the natural home of wealth, truth, and learning, (and) a firm bridge of religion, —there is no one on the earth who is (as) worthy to be praised by vir-

¹ One of the names of Kārttikēya was Kumāra; hence the comparison between him and Kumāragupta.

² The allusion in this verse is to the churning of the ocean by the gods and demons, for the recovery of the nectar and other precious things that had been lost. The mountain Mandara was utilised as the churning stick. And, during the process, Lakshmi, the goddess of fortune and wealth, sprang from the froth of the sea.

³ This verse seems to indicate that Kumāragupta's funeral rites took place at Allahābad; but not necessarily that he placed himself on the funeral pyre while still alive.

tuous people, (as he was). He also (*like the god*), carried a discus in the palm of (*his*) hand;¹ to him also belonged a bow made of horn, and a pleasing sword (*which was employed*) for the destruction of (*his*) enemies (*and*) the happiness of his friends;² (*and*), when the slaughter of (*his*) foes had been achieved, was averted by him; people did obeisance "*(My)* mighty enemies have been slain by me in battle; there remains nothing more for me to do,"—thus he, the hero, determined in his mind; (*and then*) with the desire to associate himself with the glorious **Harshadêva**.....

(L. 15).—His son was the illustrious one, named **Âdityasêna**, the best among kings, whose scimitar was sullied with a thick coating of dust in the shape of the pearls from the temples of the lordly elephants⁴ of (*his*) enemies that were split open (*by it*), Maintaining the supreme renown, that (*his*) perfect praise, coming from (*and*) rising from the destruction of (*his*) enemies, is worthy to be lauded in the presence of all wielders of the bow,—a continuous line of blessings Cleaning with the edge of the silken cloth of a banner, (*used*) under the excuse of (*wiping away*) sweat in battle, (*his*) sword that was stained with the rut (*of the elephants slain by him*), and was covered with sand in the shape of the minute fragments of the pearls (*from their foreheads*) through that was broken to pieces, the destruction of rutting elephants, in the course of which many swarms of bees, led into a mistake by the copious fragrant juice that trickled forth, were attracted by their perfume. in battle which is full of terrible and repulsive frownings (*he*) is accustomed to laugh in a charming manner in the gatherings of (*his*) favourites and servants. His [*wife*], truthfully constant to (*her*) lord; performing penance with the excellent qualities of (*her*) mouth (?); laughter Being (*and*) being the greatest cause of the destruction of the power of all (*his*) enemies, (*and*) being possessed of his own mighty prowess, even when he is full of weariness produced by the fatigue of drawing (*his*) sword forth *from its scabbard* and (*dealing*) blows (*with it*),— the foreheads of rutting elephants in battle, [*he is verily*] a guardian of the world, by whose white umbrella the whole circuit of the earth is covered. He, the king, has had both (*his*) gleaming arms increased in bulk by splitting open the temples of rutting elephants in war; he

¹ The god carries an actual discus; the king had the mark of a discus (see page 183 above, note 4).

² The allusions here are to the discus of Vishnu (Mâdhava), to his bow of horn named Sârnga, and to his sword called Nandaka.

³ Harshavardhana of Kanauj.—The present form of his name occurs also in the *Harshacharita* (Kâsmîr edition), p. 119, line 5.—I notice that he is often called Sîrharsha, and Sîrharshavardhana; as if *sîr* were a component part of his name, instead of being only the honorific prefix. But I cannot find any authority whatever for this. I cannot trace a single instance in which the reading of any inscription or book is *sîr-Sîrharsha* (see page 8 above, note 3); while, in line 26 of the Kauthêhî grant of Vikramâditya V. (*Jnd. Ant.* Vol. XVI. p. 22), he is distinctly called *Harsha-mahânripa*, "the great king Harsha." So, also, Bâqa's book about him and his history is always called simply *Harshacharita*, not *Sîrharshacharita*, in the colophon of each division of it; and the *sîr*, which is prefixed on the title-page of the Kâsmîr edition, only qualifies *Harshacharita*, as the name of the book, in the sense of "the famous history of Harsha."

⁴ The belief, to which there are constant allusions in Sanskrit poetry, was, that there are pearls to be found inside the foreheads of elephants.

has a halo of fame, [acquired] by destroying the power of many enemies; the darting fire of the prowess of (*his*) feet has had thrown into it (*to feed it*) the locks of hair on the tops of the heads of all (*other*) kings; he is possessed of fortune; (*and*) he has a pure and celebrated reputation (*acquired*) by honourable behaviour in war.

(L. 23.)—This best of temples has been caused to be made, on account of (the god) Vishnu, by him, the king, whose very great fame, (*of*) this (*kind that has been described*), white as the orb of the autumn moon (*and*) conferring renown on the (*whole*) circle of the world, was for a long time made angry by him through (*his*) desire for (*her*) association with (*his*) wealth, and then, becoming more wonderful than ever, went, forsooth, through the enmity natural to the condition of rival wives, to the other side of the ocean (*in order to dwell there far away*).¹

(L. 24.)—By his mother, the *Mahādēvi Śrīmati*, a religious college has been caused to be built, resembling a house in the world of the gods, (*and*) has been given by herself in person to religious people.

(L. 25.)—By the queen, the illustrious *Kōnadēvi*, the dear wife of that same king, in the performance of an excellent penance, there has been caused to be excavated a wonderful tank, the waters of which are eagerly drunk by people; which is full of drifting and glistening spray, resembling in lustre a *sankha*-shell, or the moon, or crystal; (*and*) in the waves of which, driven to and fro by the motion of the alligators, the birds disport themselves and the large fishes play about.

(L. 26.)—As long as a digit of the moon [remains] on the head of (the god) Hara, (*and*) (the goddess) Śrī on the breast of Vishnu, (*and*) (the goddess) Sarasvatī in the mouth of Brahman; as long as the earth [remains] on a hood of (*Śēsha*) the king of serpents; and as long as there is lightning in the interior of a cloud,—so long shall the king *Adityasēna* display here (*in these works*) (*his*) dazzling fame!

(L. 27.)—(*This*) eulogy, (*written in*) beautiful letters, [has been composed, or engraved] by *Sōkshmasīva*, (*a native of*) the *Gauḍa* (*country*), who is thoroughly religious (*and*) very intelligent.

No. 43; PLATE XXIXA.

SHAHPUR STONE IMAGE INSCRIPTION OF ADITYASENA.

THIS inscription was discovered, apparently in 1879-80, by Mr. J. D. M. Beglar, Assistant to the Director General of Archæological Surveys; and was first brought to notice, in 1882, in the *Archæol. Surv. Ind.* Vol. XV. p. 12, where General Cunningham published his reading of the text, and a translation of it, accompanied by a lithograph (*id.* Plate xi. No. 1).

Shāhpur,² also known as *Shāhpur-Tētarāwān*, is a village on the right bank of

¹ *Kīrtti*, 'fame,' and *Lakshmi*, 'fortune or wealth,' are here regarded as the two co-wives of the king. The idea is that his fame became at length so great as to extend to the uttermost ends of the world, beyond even the oceans; and this is indicated by *Kīrtti* becoming at length jealous of *Lakshmi*, and leaving her husband's house in order to dwell far away from her rival wife.

² The 'Shāhpur, Shāhpur, Shāhpur, Shāhpur-Tētarāwān, and Shāhpur-Titarāwān' of maps, &c. *Indian Atlas*, Sheet No. 112. Lat. 25° 6' N.; Long. 85° 43' E.

the Sakari river, about nine miles to the south-east of Bihâr, the chief town of the Bihâr Sub-Division of the Patna District in the Bengal Presidency. The inscription is on the pedestal of a standing image of the sun,—represented as a man, 2' 10" high, holding a waterlily in each hand; and with, on each side, a small standing figure, that on the right being armed with a club,—which was found on a mound in the lands of this village. When I sent my copyists to Shâhpur in 1884, they could not find the image, and could obtain no information as to what had become of it; my lithograph, therefore, has been prepared from Mr. Beglar's pencil-rubbing, which suffices for practical purposes, though perhaps the date is not quite as clear as it might be.

The writing, which covers a space of about 1' 4½" broad by 4" high, has suffered a good deal of injury towards the proper right side of the stone; the rest, however, is very well preserved.—The average size of the letters is about ⅙". The characters belong to the northern class of alphabets, and are of almost precisely the same Kutila type as those of the preceding Apsaḥ inscription of Âdityasēna, No. 42, Plate xxviii. They include, in line 2, forms of the numerical symbols¹ for 6, 7 (?), and 60.—The language is Sanskrit, and the inscription is in prose throughout.—In respect of orthography, the only point that calls for notice is the use of *v* for *b* in *valâdhikrîta*, line 3.

The inscription refers itself to the time of Âdityasēna, of the family of the Guptas of Magadha. Its date, in numerical symbols, is the year sixty-six, on the

¹ The symbol for the day is a little doubtful, but it seems to be 7.—Gen. Cunningham interpreted these symbols as decimal figures, and read the year as 55, and the day as 1. At the same time he notified that Dr. Bhagwanlal Indrajî, interpreting them in the same way, read the year as 88. And the date certainly has the appearance, in Gen. Cunningham's published lithograph, of either 55 or 88.—But this is too early a period for the occurrence of decimal figures, and, though the symbols are rather damaged, I think quite enough of them remains to shew very clearly a 60, followed by a 6.—So far as definite dates are available, the system of numerical symbols was preserved in this part of the country as late as Harsha-Samvat 188 (A.D. 794-95) as shewn by the Bengal Asiatic Society's grant of the *Mahârâja* Vinâyakapâla (*Ind. Ant.* Vol. XV. p. 138 ff.), and in the neighbouring country of Nêpâl, as late as Harsha-Samvat 153 (A.D. 659-60), as shewn by the inscription of Jayadêva II. (*Ind. Ant.* Vol. IX. p. 178 ff., and Vol. XIV. p. 345), and Gupta-Samvat 535 (A.D. 854-55), as shewn by another Nêpâl inscription (*id.* Vol. IX. p. 168 ff., and Vol. XIV. p. 345). In the west of India, it continued, in Gujarât, as late as Śâka-Samvat 679 (A.D. 757-58), as shewn by the Kârêlî grant of Kakka of Gujarât (*Four. So. Br. R. As. Soc.* Vol. XVI. p. 105 ff). In Central India, as late as Vikrama-Samvat 879 (A.D. 822-23), as shewn by the Shêrgadh (Kôta) inscription of the *Sâmantâ* Dêvadatta (*Ind. Ant.* Vol. XIV. pp. 45 ff., 351). And in the South, as late as about Śâka-Samvat 549 (A.D. 627-28), as shewn by the Vizagapatam grant of the Eastern Chalukya *Mahârâja* Vishuvardhana I. (Burnell's *South-Indian Palæography*, p. 137 f. and Pl. xxvii; see also *Ind. Ant.* Vol. VII. p. 186, where I gave the date as the sixteenth year, instead of the eighteenth, which it really appears to be.)—As regards the introduction of decimal figures (setting aside the question of the first invention of them, which was probably by the astronomers of Ujjain in the fifth or sixth century A.D.), the earliest epigraphical instances of the use of them that I can quote, are, in the north, the Gwâlhor inscription of Bhôjadêva dated Vikrama-Samvat 933 or A.D. 876-77 (*Four. Beng. As. Soc.* Vol. XXXI. p. 407 f.; see also *Ind. Ant.* Vol. XV. p. 108, note 25); and the 'Pehewa' inscription of the same king, dated Harsha-Samvat 276 or A.D. 882-83 (*Four. Beng. As. Soc.* Vol. XXII. p. 673 ff., and Vol. XXXIII. p. 223 ff.; see also *Ind. Ant.* Vol. XV. p. 109, note 27); in Central India, the 'Deogarh' inscription of the same king, dated Vikrama-Samvat 919 and Śâka-Samvat 784 or A.D. 862-63 (*Archæol. Surv. Ind.* Vol. X. p. 100 ff.; see also *Ind. Ant.* Vol. XV. p. 110, note 32); in Gujarât, the 'Bagumra' grant of the Râshtrakûta chieftain Dhruva III., dated Śâka-Samvat 789 or A.D. 732-33 (*Ind. Ant.* Vol. XII. p. 185); in Kâthîawâd the Môrbi grant of Jâinka, dated (irrespective of the actual reading in line 17) Gupta-Samvat 585 (A.D. 804-5); and in the Dekkan, the Sâmaḡadh grant of Dantidurgâ, dated Śâka-Samvat 675 or A.D. 753-54 (*Ind. Ant.* Vol. X. p. 108 ff.).

seventh (?) day of the bright fortnight of the month Mārga, *i.e.* Mārgaśira or Mārgaśirsha (November-December). The era is not specified; but, from the known facts of Ādityasēna's history, it is that of Harshavarḍhana of Kanauj, commencing¹ A.D. 606 or 607; and the result for this date, therefore, is A.D. 672-73. The inscription is one of solar worship; and the object of it is to record, in the first place, some grant, the details of which are illegible in line 1; and, in the second place, the installation of the image by the *Balādhikṛta*² **Sālapaksha**, in, apparently, the *agrahāra* of **Nālanda**.

The name of **Nālanda** is rather doubtful in this inscription; but there is no special objection to reading it, since Nālanda was a famous place, originally Buddhist, in the neighbourhood of Shāhpur, being in fact identified by General Cunningham³ with the modern 'Baragaon,'⁴ seven miles due north of Rājgir, and about fifteen miles nearly due west of Shāhpur. The image, being fairly small and portable, may easily have been originally set up at Nālanda, and then removed at some time or other to Shāhpur.

TEXT.⁵

- 1 kh . l . dh g . chandra-kshiti-kālam yāvat-p[r]jatipāditam [11*]
 2 Ōm Samvat 60 6 Mārgga śu di 7(?) asyān-divasa-māsa-
 samvatsar-Anupūrvyām⁶ śrī-Āditya'sēna-
 3 [dēva]-rāj[y]ē **Nā(?)landa(?)**-mah-āgrahāre sād[h]un]ā va(ba)lādhikṛta-
Sālapakshēna dē[ya*]-dharmmō-yam pratishthitam(h)
 4 [mātāpitṛrō=ā]tmanaś=cha puny-ābhivṛddhayē [11*]

TRANSLATION.

. has been granted, to endure for the same time with
 and the moon and the earth.

(Line 2.)—Ōm! The year 60 (*and*) 6; (the month) Mārga; the bright fortnight,⁷ the day 7 (?),—on this (*lunar day*), (*specified*) as above by the day and month and year,⁸—in the reign of the illustrious **Ādityasēnadēva**, this appropriate religious gift has been installed by the virtuous **Sālapaksha**, the *Balādhikṛta*, in the *great agraḥāra* of **Nālanda** (?), for the purpose of increasing the religious merit of (*his*) parents and of himself.

¹ See *Ind. Ant.* Vol. XIII. p. 420, note 37.

² *Balādhikṛta* is a technical military title, meaning literally 'one who is appointed to (a command of) the troops.' The superior of the *Balādhikṛtas* was the *Mahābalādhikṛta*; see page 109 above, note 2.

³ *Anc. Geog. Ind.* Vol. I. p. 468 ff.

⁴ Indian Atlas, Sheet No. 103. Lat. 25° 8' N., Long 85° 29' E.—In the map, the name is written 'Burgaon.' The correct form of the name would therefore seem to be Badgaum.

⁵ From Mr. Beglar's pencil-rubbing; so also the lithograph.

⁶ Supply *titha*.

⁷ Read *śry-śditya*.

⁸ The text here has the abbreviation *śu*, which represents *śuddha*, or *śukla*, in composition with *paksha* or *pakshā* see page 92 above, note 1.

⁹ See page 97 above, note 1.

A.—Shakpur Lingo Inscription of Adityasena.



SCALE 400

B.—Deo-Baranark Inscription of Jivakagupta II.



2
4
6
8
10
12
14
16
18
20

Nos. 44 and 45; (No PLATE)

MANDAR HILL ROCK INSCRIPTIONS OF ADITYASENA.

THESE two inscriptions were discovered by Dr. Francis Buchanan (Hamilton), and were first brought to notice in his reports, from which Mr. Montgomery Martin compiled, and in 1838 published, the book entitled *Eastern India*, where the inscriptions are mentioned in Vol. II. p. 58, with reduced lithographs (*id.* Plate iv. Nos. 3 and 4).—I cannot find that any fuller notice of them has ever been published.

Mandâr or **Mandâragiri**¹ is a famous hill about seven miles south-east of Bânkâ,² the chief town of the Bânkâ Sub-Division of the Bhâgalpur³ District in the Bengal Presidency. When I was on tour in the north of India, I could not succeed in acquiring any accurate information as to the position of the inscriptions, and was thus unable to obtain impressions and publish lithographs of them. But Dr. Buchanan's facsimiles, though not good enough to reproduce, are intelligible throughout, with the exception of the three letters immediately following the name of Âdityasênadêva. And quite recently Mr. Beglar has sent me a rubbing and a hand-copy of No. 44, which, though not suitable for lithography, fully endorse Dr. Buchanan's rendering of this record, and enable me also to read with certainty some of the letters that are doubtful in his lithograph. From Mr. Beglar's remarks, I learn that this inscription, No. 44, is on the rock to the right of the steps rising from a corner of the lower tank, now called Pâpahannî, and at the base of a flight leading to the upper tank. The position of the other inscription, No. 45, seems to be not now known at all.

The two inscriptions are identical in substance; but are arranged, one in two lines, and the other in four. The **writing** of No. 44 covers a space of about 6' 2" broad by 2' 11" high; and is in a state of fairly good preservation; but the surface of the rock seems to be so rough that it is doubtful whether an ink-impression could be obtained, sufficiently good for lithography.—The average **size** of the letters is about 5". The **characters** belong to the northern class of alphabets, and are of almost precisely the same Kuṭila type as those of the Apsad inscription of Âdityasêna, No. 42 above, Plate xxviii. page 200.—The **language** is Sanskrit, and the inscriptions are in prose.—The **orthography** presents nothing calling for remark.

The inscriptions refer themselves to the time of **Adityasêna**, of the family of the **Guptas** or **Magadha**. They are not dated. But the paramount titles of *Paramabhaktâraka* and *Mahârâjâdhirâja* applied here to Âdityasêna, shew that they belong to the period of confusion and anarchy that attended the death of Harshavardhana of Kanauj, when Âdityasêna established the independence of his family in Magadha; and that they are slightly later than his Apsad and Shâhpur inscriptions, in the latter of which,—as it is in prose,—the paramount titles would certainly have been introduced, if he had assumed them by that date. They are non-sectarian; and the record being simply that Âdityasêna's *ifr*, **Kôṇudêvi**, caused a tank to be made.

¹ The 'Mandar, Mandargiri, Mundar Hill, and Mundar H. Temple,' of maps, &c. Indian Atlas, Sheet No. 112. Lat. 24° 50' N. Long. 87° 4' E.

² The 'Banka' of maps.

The 'Bhagalpur and Bhaugulpur' of maps, &c.

TEXT.¹

No. 44.

- 1 Ōm Paramabhāṭṭāraka-mah[ā]r[ā]j[ā]d[ī]dh[ī]r[ī]t[ā]jja-
 2 śrī-Aditya'sēnadēva-davī[ś] parama-
 3 bhāṭṭārik[ā]-r[ā]j[ā]rāj[ā]-mān[ā]rāj[ā]-śrī-**[Kō]nad[ē]v[ī]**
 4 puškariṇī-kīrtim-im[ā]n-k[ā]r[ī]t[ā]va[ṭ] [II*]

No. 45

- 1 Ōm Paramabhāṭṭāraka-mah[ā]r[ā]j[ā]d[ī]dh[ī]r[ī]t[ā] śrī-Ad[ī]tya'sēnadēva-
 day[ī]tā
 2 paramabhāṭṭārik[ā]-r[ā]j[ā]rāj[ā]-mah[ā]d[ī]vi-śrī-K[ō]nad[ē]v[ī] pu[ś]kariṇ-
 kīrt[ī]t[ī]m-im[ā]n-kāritavāṭ [II*]

TRANSLATION.

Ōm! The *Paramabhāṭṭārikā*,² the queen,³ the *Mahādēvī*,⁴ the glorious **Kōnadēvī**,—the dear wife of the *Paramabhāṭṭāraka* and *Mahārājādhirāja* the glorious **Aditya-sēnadēva**,—caused to be made this famous work.⁵ [II*]

¹ From Mr. Beglar's rubbing of No. 44 and Dr. Bhandarkar's unpublished lithograph of No. 45.

² Read *īry-āditya*. The name of the deity is *Aditya*.

³ *Paramabhāṭṭārikā*, lit. 'she who is appointed to be the guardian or venerator' of the *devī*, nine of *paramabhāṭṭāraka* (see page 17 above). The title is a Sanskrit technical title of the wives of paramount sovereigns.

⁴ *rājā*; also in line 2 ff. of the following inscription. The word is *rājā* in the present day; only the feminine form of *rājān*; but it does not seem to be so used elsewhere, and technically used as a subordinate feudatory title, in the way in which it is used in the present day also. *Rājā*, which is the Prākṛit form of *rājān*, is the proper title of a king of a *Rājya*, but is also used, equally with *Mahārājā*, as a title of the Queen-Empress of a kingdom and India.

⁵ *kīrtti*.—Mr. K. T. Telang (*Ind. Art.* Vol. IX, p. 39, note 13) first brought to notice, on the authority of Dr. Bhagwanlal Indraji, that a certain copper-plate *śrīṭana* has the meaning of 'a temple'; e.g. in line 18 of the Khārēpātan grant of Avantadevi, dated Śaka-Samvat 1016 (*id.* p. 34), which he was then editing.—This was supported by Dr. B. N. Chaudharker (*id.* Vol. XII, p. 228 f.); who, in pointing out the error into which, from not being aware of this meaning of the word, I had fallen in translating the passage in lines 14 f. of the Garuda grant of Kaska II, dated Śaka-Samvat 734 (*id.* Vol. XII, p. 159), was able to quote three passages from the *Agni-Purāna* (in the *Bibliotheca Indica*, Vol. I, p. 111), Bāṇa's *Kadambā*, and Śaṅkara's *Kīrttikāumudī*, in which the word evidently has the same meaning.—And in these instances I have since been able to add the 'Dudahi' inscriptions of Dēvalabdhū (*id.* Vol. XII, p. 233), and the Udayagiri inscription, dated Vikrama-Samvat 1093 (*id.* Vol. XIII, p. 185).—On the analogy of these authorities, there is every reason for allotting the same meaning, when required, to *kīrtti*, which is a derivative from the same root. Dr. Bhandarkar has, however, recently suggested to me that *kīrtti* and *kīrtana* are hardly to be actually translated by the word 'temple,' or by any other specific term, but denote generally 'any work, of public utility, calculated to render famous the name of the constructor of it.' This is in accordance with the etymology of the words, from the root *kīrt*, 'to mention, commemorate, praise.' And the particular work referred to may be a temple, as in the instances quoted above; or a tank, as in the present inscriptions; or anything else of a suitable nature.

Another passage in which *kīrtti* has the same meaning, though we have no information now as to the specific nature of the work referred to, is in line 4 f. of an inscription on the right-hand side pier in the porch of the temple of Vaidyanātha at 'Deoghar' in the 'Santāl' Parganas in the Bengal Presidency, edited by Dr. Rajendralala Mitra in the *Four Beng. As. Soc.* Vol. LII, Part I

No. 46; PLATE XXIX B.

DEO-BARANARK INSCRIPTION OF JIVITAGUPTA II.

THIS inscription was discovered in 1880-81 by General Cunningham; and was first brought to notice by him, in 1883, in the *Archæol. Surv. Ind.* Vol. XVI pp. 68 and 73 fl., where he published a reading of the text, and a partial translation of it, supplied to him by Dr. Bhagwanlal Indraji, with a lithograph (*id.* Plates xxv. and xxvi.) from a photograph by his Assistant, Mr. H. B. W. Garrick.

p. 190 f., No. 3. It is a Vaishnava inscription, and, therefore, as pointed out by Dr. R. Mitra, it does not belong properly to the temple of Vaidyanātha, which is a Śaiva shrine, and, from the concluding words, it seems to have been brought away from some building on the Mandār Hill. I had no opportunity of obtaining a proper impression of the inscription. But the one in the Society's library suffices to show that Dr. R. Mitra's version of the text, which I now give, with my own translation of it, is correct:—

TEXT.

- 1 Śāstā samudrānta-vasundharāyāḥ yasht=śvamedh-ādyā-mahā-
kratūṅm | Ādityasēnah prathita-prabhā-
- 2 vō babbhūva rāj=āmara-tulya-tējāḥ || Māghyām Visākhā-pada-
samyutāvām Kritē yugē Chōla-purād=a-
- 3 pētya mahā-manīnām ayuta-trayēna trilaksha-chāmīkara-tankakēna ||
Ishtv=śvamedhā-trita-
- 4 yēna dattvā mahābhūyuktam | śrī-Kōshadēvyā
sahitō mahāyājābhīkarāḥ ||
- 5 ritum=imāṁ sa sauvām || dvijēndraḥ svayam vattō narēndrah |
brāhṁānābh-
- 6 tōr=bhuvana-trayasya chakāra samsthām Nriharēḥ sa ēva ||
Sthāpitō Balabhadrēna varāhō bhukti-mukti-
- 7 dah | svarg-ārthē pitri-mātrīnām jagataḥ sukha-hētavē || Iu
Mandāragri-prakaranam ||

TRANSLATION.

There was a king, Ādityasēna, of renowned prowess, equal in glory to the gods, the ruler of the (whole) earth up to the shores of the oceans, the performer of the *śvamedha* and other great sacrifices. On the full-moon day of (the month) Māgha, coupled with the sign of (the lunar asterism) Visākhā, in the Kṛita age,—having arrived from the Chōla city,—having sacrificed with three *śvamedha*-sacrifices, (and) having given away his own weight a thousand times over, together with a crore of horses,—he, with (his) consort, the glorious Kōshadēvi, caused to be made the whole of this famous work (Mīrī), with three myriads of large jewels (and) three lakhs of gold (coins of the kind called) *tankakas*. Having consecrated (it) according to due rite (through the ceremonies performed) by Brāhmins, just as if he, the king, himself (was laying out) the path of the Vēdas, he made an establishment of (the god) Nrihari, who is the cause of the prosperity of the three worlds. A boar (i.e. the god Vishnu in that form), the giver of enjoyment and final emancipation, has been set up by Balabhadra, in order that (his) parents may attain heaven, (and) for the happiness of the (whole) world. Thus runs the chapter on the Mandāragiri.

DĒḌ-*Baranārk*,¹ or **Dēva-*Baranārk***, the ancient **Vārunikā** of this inscription, is a village about twenty-five miles south-west of Arrah (properly *Ārā*), the chief town of the *Shahābād* District in the Bengal Presidency. The inscription is on two contiguous faces of a pillar in the entrance-hall of a temple on the west side of the village,² which has apparently been adapted in modern times as a temple of the god *Vishṇu*.³

The writing, which covers a space of about 2' 3½" broad by 1' 4" high, has suffered a great deal of injury from the weather, especially down the proper right side, where many passages are hopelessly illegible; but fortunately the whole of the genealogy of the *Guptas* of *Magadha* given in this inscription is intact, with the exception of the first three syllables of the name of *Mādhavagupta*, in line 2, which can easily be supplied. In lines 7 ff., however, there was a good deal of historical information that is not now quite perfect.—The average size of the letters is about ⅞". The characters belong to the northern class of alphabets, and are of almost the same *Kutila* type as those of the *Aphsāḍ* inscription of *Ādityasēna*, No. 43 above, Plate xxviii.; but they do not shew the bent tails of the letters quite so markedly.—The language is *Sanskrit*; and the inscription is in prose throughout. In style, it follows the customary form of a copper-plate charter; not of a stone-inscription.—In respect of orthography, we have to notice (1) the use of *śā*, instead of the *jīhvāmūlīya* or the *visarga*, in *antashpāti*, line 7; (2) the use of the dental *n*, instead of the *anusvāra*, before *s*, in *hansa*, line 14; (3) the doubling throughout of *t*, in conjunction with a following *r*; e.g. in *ttraya*, line 1; *puttra*, line 5; and *mitra*, line 16; and (4) the use of *v* for *b*, in *vāldīdīya*, line 13.

The inscription is one of *Jīvitagupta II.*, of the family of the *Guptas* of *Magadha*; and the charter recorded in it is issued from the fort of *Gōmatikottaka*. It is not dated.⁴ It is an inscription of solar worship;⁵ its object being to record the continuance of the grant of a village, either *Vārunikā* or *Kisōravātaka*, to the Sun, under the title of *Varuṇavāsini*, a name which is of some interest, as apparently preserving the ancient belief, in accordance with which *varuna*, *lit.* 'that which envelopes,' meant 'the all-encompassing sky, before it became the name of the ocean-god *Varuṇa*, who himself was ori-

The characters, called *Maithila* by Dr R. Mitra, shew that this inscription is quite modern, —certainly not earlier than the sixteenth century A.D., and it must have been engraved when the boar-statue of *Vishṇu*, spoken of in line 6, was set up by *Balabhadra*. I have thought it worth while, however, to give the record in full, because, in my opinion, it so plainly contains a memorial of the great *Ādityasēna* of *Magadha*. The antiquity of the allusion is indicated by its being referred to the *Kṛita* age. And though the name of *Ādityasēna's* wife is here given as *Kōśhadēvi*, instead of *Kōnadēvi*, this is to be explained by the usual inability of the people, then as now, to read correctly the ancient characters of the inscription or other record from which the composer of these verses obtained his information, and it is a mistake of the kind that corroborates, not invalidates, the identification of *Ādityasēna*.

¹ The 'Deo-Barnārak, Deo-Barnārāk, Deo-Barunārak, and Deonar Narooḥ,' of maps, &c. Indian Atlas, Sheet No. 103. Lat 25° 15' N; Long. 84° 31' E.

² See *Archæol. Surv. Ind.* Vol. XVI. Plates xxii. xxiii. and xxiv.

³ *id.* p. 69.

⁴ Gen. Cunningham read in it the date of 152, which he referred to the era of *Harshavardhana* of *Kanauj*. But this arose only from a misunderstanding of the words *sa-dasāparādha-paṅcha*, in line 19.

⁵ It appears that two special festivals in honour of the sun still take place at *Dēḍ-*Baranārk**, on the sixth day of the bright fortnight of the months *Chaitra* and *Kārttika* (see *Archæol. Surv. Ind.* Vol. XVI. p. 72).

ginally looked upon as one of the twelve Ādityas, or forms of the sun, the offspring of Aditi.¹

The importance of this inscription consists, first, in its continuation, for three more generations, of the genealogy of the **Guptas of Magadha**, including the name of **Dēvagupta**, which, as will be seen hereafter, gives the clue to the date of the **Vākātaka Mahārājas**; and secondly, in its recording the names of certain previous kings, who each in succession had confirmed the grant. The names that are now legible are those of **Bālāditya**, who, as is known from the writings of the Chinese pilgrim Hiuen Tsiang, played so important a part in connection with Mihirakula; **Śarvavarman**, who is evidently the Maukhari king Śarvavarman, whose copper-seal we have in No. 47 below, Plate xxxA.; and **Avantivarman**, who is probably the Maukhari Avantivarman, mentioned in Bāṇa's *Harshacharita* as the father of Grahavarman who became the husband of Rājyaśrī, the sister of Harshavardhana of Kanauj.²

Of the places mentioned in the inscription, **Gōmatikoṭṭaka**, the fort whence the charter was issued, must evidently be looked for somewhere along the river Gōmati, the modern Gōmtī or Gumti, which, rising in the Shāhjahānpur District of the North-West Provinces, passes Lucknow and Jaunpur, and flows into the Ganges about half-way between Benares and Ghāzipur, and about eighty-five miles to the west of Dêô-Baranārka. And **Vāruṇikā** is plainly the modern **Dêô-Baranārka** itself. In the modern name, the first component is *dēva*, 'a god,' and the second, a corruption of Varuṇārka, evidently gives the name of a later conception of the original god, embodying the attributes of the Sun (*arka*) with those of Varuṇa.

TEXT.³

- 1 ' [na]mah [I*] Svasti Śakti-ttray-ōpātta-jayaśabdān=mahā-nau-
hā(ha)sty-aśva-patti-sambhāra-durnivārā=jaya-skandhāvārāt **Gōmatikoṭṭaka**-
samīpa-vāsa-
- 2 [kāt]⁴ [śrī-Mādhava]guptas=tasya putras=tat-pād-ānudhyātah
paramabhāṭṭārikāyām rājñyām mahādēvyām śrī-Śrīmatyām-utpannah
paramabhāgavatah śrī-Āditya[sē]-
- 3 [nadēvas=tasya] pu[ttra]s=tat-pād-ānudhyātah paramabhāṭṭārikāyām rājñyām
mahādēvyām śrī-Kōṇad[ē*]jvyām=utpannah paramamāhēśvara-
paramabhāṭṭāraka-mahār[ā][ā]-
- 4 [dhirāja-paramēśvara]-śrī-D[ē]vaguptad[ē]vas⁷=tasya putras=tat-pād-ānu-

¹ See, for instance, Monier Williams' *Indian Wisdom*, pp. 12 f. and 68, and Muir's *Sanskrit Texts*, Vol. I. p. 27, note 42.

² See FitzEdward Hall's preface to the *Vāsavadattā*, p. 52, and the *Harshacharita*, Kāśmir edition, p. 311 ff.

³ From the ink-impression.

⁴ Bhagwanlal Indraji supplied *varunavāsi-bhāṭṭārakāya* here. But only about five aksharas, or at the most six, appear to have been destroyed.

⁵ Some sectarian title of Mādhavagupta must have been destroyed here, but there seems hardly room enough for *paramabhāgavata* or *paramamāhēśvara*.

⁶ Read *śry-āditya*.

⁷ This name of Dēvaguptadēva,—which is of considerable importance, from its bearing on the date of the **Vākātaka Mahārājas**,—is very indistinct, but I agree with Bhagwanlal Indraji that it can be read with sufficient certainty.

- dhyātaḥ paramabhāṭṭārikārikāyā[m*] rājñyā[m*] mahādēvyā[m*] śrī-
Kamala'dēvyām-utpannaḥ paramamāhē-
- 5 [śvara-paramabhāṭṭāraka-ma]hārājā[dhi]rāja-paramēśvara-śrī-**Vishnuguptadēva**-
 tasya puttras-cat-pād-ānudhyātaḥ paramabhāṭṭārikāyā[m*] rājñyā[m*]
 mahādēvyā[m*] śrī-Ijjā'dē[vyā]:
- 6 [m-utpannaḥ parama³-parama]bhāṭṭāraka-mahārājādhīrāja-paramēśvara-
 śrī-**Jivita'guptadēva[h*]** kuśall **Nagara**-bh[u*]ktau **Vālavī**-vaiśhayika-
 śrī-**Vā(ṽb)** ..
- 7 padra(?)lik(?ksh)-āntashpāti-**V[ā*]runikā**-grama-
 gōshṭh[ā]na(?)kula-talāvātaka-dūta-slmakarmakara-madyā(?)-
- 8 taka-rājaputtra-rājāmattrā⁴-maha
 ksharika-mahādāṇḍānyaka-mahāpratthāta-mah[ā]śā-
- 9 pra(?)mātasā k[ū]m[ā]rāmātya-rājasthānīy
 ōparika- dhika-chaurōddharaṇika-dāṇḍika-da(?)ḍā-
- 10 [pāsika(?)] ka rshn(?)vala-vyāyata-
Kiśō(?)ravā(?)ta(?)ka(?)g[r]āma-h d . t yanikaga pati-
 karma(?)-
- 11 rasaka t-āsmat-[p]āda-prasād-ōpajlvinaś=cha
 prativ[ā]sinaś=cha vrā(bra)hmaṇ-ōttarā[n*] mahattara-ka(?ku)kshi(?)pura-
- 12vijñāpita-śrī-Varuṇavāsī-
 bhāṭṭāraka-prativa(ba)ddha-bhōjaka-Sūryamittreṇa upan-likhi-
- 13 [ta] grām-ādi-samyutam paramēśvara-
 śrī-**Vā(bā)lādityadēvēna** sva-śāsanaēna bhagava-śrī⁵-Varuṇavāsī-
 bhāṭṭāraka ..
- 14 ka va-parivā(?)haka bhōjaka-Hansa-
 mittresya samāpat[t*]yā yathākāl-ādhyāsibhiś=cha ēvaṃ paramēśvara-
- 15 śrī-**Sarvvavarmma** bhōjaka-Rishi'mittra yatakam
 ēvaṃ paramēśvara-śrī[ma*]d-**Avantivarmmanā** pūrva-dattakam avaia-
- 16 [mbya] ēvaṃ mah[ā*]rājādhīrā⁶]ja-paramēśvara-
 śāsana-dānēna bhōjaka-Durdha(?)ra(?)mittresy=
 ānumō-
- 17 [dita] tē(?)na(?) bhu(?)jyatē(?) [I*] tad=aham
 kimapi(?) ēvaṃ matimān ānupā(inō)ditam=iti
 sa(?)rvva(?)-samājñāpa(?)nā(?) [I*] ēta ..
- 18 payu
 Varuṇavāsy-āvatanaṃ tad=anu dattam

¹ Bhagwanlal Indrajī read *kumdra*; but the three *aksharas* are distinctly *kamala*.

² Read *sr-ijjā*. ³ Either *bhāgavata* or *māhēśvara* is illegible here

⁴ Bhagwanlal Indrajī read *savitri*; but the three *aksharas* are distinctly *jivita*, as, in fact, was recognised by Gen. Cunningham (*Archaeol. Surv. Ind.* Vol. XVI. pp. viii., 68)

⁵ Read *rājāmātya*.

⁶ Read *bhagavach-chhrī*.

⁷ Read *bhōjaka-rishi*; or, according to the more usual custom, *bhōjaka-arshi*.—In the case of a final *a*, followed by an initial *ri*, it is usual to join the vowels in regular *samāhi*. But Dr. Hultsch has drawn my attention to the fact that the commentary on Pāṇini, vi. 1, 128, *riṭy=akha*, states that the *samāhi* here is in accordance with the opinion of Śākalya, and thus seems to intimate that, according to other grammarians, the *samāhi* is optional, and a hiatus is equally permissible.

19 tyaksha
 s-ōdraṅgaṃ s-ōpanikaraṃ sa-daśāparādha-pañcha ..
 20 [H*]

TRANSLATION.

Reverence to! Hail! From the victorious camp, possessed of shouts of victory acquired by the three constituents of power,¹ (and) invincible through (its) equipment of great ships and elephants and horses and foot-soldiers, (and) situated near the fort of Gōmatikoṭṭaka :—

(Line 2).—(There was) the illustrious Mādhavagupta. His son, who meditated on his feet, (was) the most devout worshipper of the Divine One, the glorious Adityasēnadēva,² begotten on the Paramabhaṭṭarika, the queen,³ the Mahādēvī, the glorious Śrīmatidēvī.

(L. 3).—His son, who meditated on his feet, (was) the most devout worshipper of (the god) Mahēsvara, the Paramabhaṭṭaraka, Mahārājādhirāja, and [Paramēsvara], the glorious Dēvaguptadēva,⁴ begotten on the Paramabhaṭṭarika, the queen, the Mahādēvī, the glorious Kōnadēvī.

(L. 4).—His son, who meditated on his feet, was the most devout worshipper of (the god) Mahēsvara, the [Paramabhaṭṭaraka], Mahārājādhirāja, and Paramēsvara, the glorious Viṣṇuguptadēva, begotten on the Paramabhaṭṭarika, the queen, the Mahādēvī, the glorious Kamaladēvī.⁵

(L. 5).—His son, who meditates on his feet, the most devout worshipper of the Paramabhaṭṭaraka, Mahārājādhirāja, and Paramēsvara, the glorious Jivita-guptadēva⁶ (II),—[begotten] on the Paramabhaṭṭarika, the queen, the Mahādēvī, the glorious Ijjādēvī,⁷—being in good health, [issues a command] to the herdsmen, Talavōṭṭakas,⁸ messengers,⁹ makers of boundaries,¹⁰

¹ *takti-traya*.—The three *taktis*, or 'constituents of regal power,' are *prabhutva*, 'majesty'; *mantra*, 'good counsel'; and *utsāha*, 'energy.'

² The omission, in the case of Ādityasēna, of the paramount titles,—which are duly attached to his name in the Mandār Hill inscriptions, Nos. 44 and 45 above, page 211, and to the names of his mother and wife, and all his successors, in the present inscription,—is rather peculiar.

³ *rājī*; see page 212 above, note 5.

⁴ See page 215 above, note 7.

⁵ See page 216 above, note 1.

⁶ See page 216 above, note 4.

⁷ This is a Prākṛit name, in which *ijjī* represents the Sanskrit *ijyā*, 'a sacrifice.'—We have had another Prākṛit name of a female, in Ajjjitadēvī; e.g. in line 5 of the Kārtalāl grant of the Mahārāja Jayanātha of the year 174, No. 26 above, page 117.

⁸ *Talavōṭṭaka* is an official title, the etymology and meaning of which are not apparent.—Dr. Bhagwanlal Indraji, in his treatment of this inscription, read the word with the short vowel *a* in the second syllable, and explained it as meaning the modern *Talāṭṭ* or *Talāṭṭh*, 'the village accountant; but of course some authority requires to be cited, before this explanation can be accepted.

⁹ *Dūtas*; the word seems to denote here simply ordinary message-carriers or postmen, not the special officers called *Dūtakas*, employed in connection with copper-plate charters (see page 100 above, note 3).

¹⁰ *Sīmakarmatara*.

..... *Rājaputras*,¹ *Rājāmdtyas*, *Mahādandanāyakas*, *Mahāpratthāras*,²
 *Kumārāmdtyas*, *Rājashānīyas*, *Uparikas*,
 *Chaurōddharanikas*,³ *Dāndikas*,⁴ *Dandapāsikas*,
 of the village of *Vārunikā*, which lies in the
 in the *Nagara bhukti*,⁵ (and) belonging to the
Vālavī vishaya, (and) to the village of *Kiśoravātaka* (?), which
 was laid out by
 and to those who subsist on the favour of Our feet, and to the neighbours, headed by the
 Brāhmanas, (and) to the *Mahattaras*,

(L. 12).—By the *Bhōjaka* ⁶ *Sūryamitra*, belonging to (the establishment of) the divine
 (god) the holy and sacred *Varuṇavāsin*, who was requested the
 above-mentioned [village] together with and the
 village, &c., was formerly bestowed by the *Paramēśvara*, the glorious *Bālādityadēva*, by
 (his) own charter, the divine (god) the holy and sacred *Varuṇavāsin*,
 by restoration to the *Bhōjaka* *Hamsamitra*, and by those who presided at
 different times, *vis. the Paramēśvara*, the glorious *Śarvavarman*
 [to] the *Bhōjaka* *Ṛishimitra* by the *Paramēśvara* *Avantivarman*. In accord-
 ance with this practice⁷ assent to its enjoyment by the
Bhōjaka *Durdharamitra* was given, by the grant of a charter, by the *Mahārājādhirāja* and
Paramēśvara; and it is now enjoyed by him.

(L. 17).—"Therefore I [now announce] that it is assented to
; such is (my) command to all people.
 the altar of (the god) *Varuṇavāsin*; after that, there is given
 with the *udranga* and the *uparikara*, with (the proceeds of
 fines for) the ten offences, the five

¹ *Rājaputra* means literally 'a king's son, a prince;' but, as used in such passages as the present, it evidently has some technical official meaning, differing from this. In the modern Prakrits we have, in Marāṭhī, *rāut* or *rādā*, and in Gujarāṭī, *rāvat*, in the sense of 'a horse-soldier, a trooper.' And these words would seem to be derived from *rājaputra*, and so to indicate its technical meaning; rather than, as given by Molesworth and Candy in their Marāṭhī Dictionary, from *rāva-dāta*, 'a king's messenger.'

² *Mahāpratthāra*, *lit.* 'a great door-keeper,' was the technical title of the officer next in grade above the *Pratthāras* (see page 190 above, note 1).

³ *Chaurōddharanika*, *lit.* 'one who is entrusted with the extermination of thieves,' is evidently the technical title of a certain class of police officers.

⁴ *Dāndika*, *lit.* 'a chastiser, a punisher,' may denote either a judicial functionary, from *danda* in the sense of 'a fine;' or a police officer, from the same word in the sense of 'a rod (of punishment).'

⁵ *Bhukti*, *lit.* 'enjoyment,' is a technical territorial term.—From the arrangement of the text here, as also from the mention of "the village of *Pānyaka*, in the *Śrāvastī bhukti*, and belonging to the *Vālavī vishaya* which lay in the *Śrāvastī maṇḍala*," in the *Dighvā-Dubaulf* grant of the *Mahārāja* *Mahēndrapāla* (*Ind. Ant.* Vol. XV. p. 112, line 7 f.), and the mention of "the village of *Tikkarikā*, in the *Pratishthāna bhukti*, and attached to the *Kāśpāra pathaka* which belonged to the *Vārāṇasī vishaya*," in the *Bengal Asiatic Society's* grant of the *Mahārāja* *Vinayakapāla* (*id.* Vol. XV. p. 141, line 9 f.), the term *bhukti* seems to have denoted a larger extent of territory than a *vishaya*.

⁶ *Bhōjaka* is explained by *Monier Williams*, in his *Sanskrit Dictionary*, as denoting 'a class of priests, or sun-worshippers, supposed to be descended from the *Magas* by intermarriage with women of the *Bhōja* race.'—*Childers*, in his *Pāli Dictionary*, gives the same word as meaning 'a village-headman.'

⁷ The construction of the original is *Bālādityadēva* *pārva-dattakam-avalambya*, "having relied on (i.e. having adapted himself to) the former grant that was made by *Bālādityadēva* (and the others mentioned)."⁷ I have broken up the construction for convenience of translation.

No. 47; PLATE XXX A.

ASIRGADH COPPER SEAL INSCRIPTION OF SARVAVARMAN.

THIS inscription was first brought to notice, through two independent channels, in 1836. In the *Your. Beng. As. Soc.* Vol. V. p. 482 ff., Mr. James Prinsep published the Rev. W. H. Mill's reading of the text, and translation of it, accompanied by a lithograph (*id.* Plate xxvi.) reduced from a drawing, forwarded to him by Dr. J. Swiney, which had been made in 1805 from a wax-impression of the original seal, and had been in the possession of Dr. Mellish from then; the lithograph is a fairly good one; but the rendering of the inscription was erroneous almost throughout. And in the *Your. R. As. Soc. F. S.* Vol. III. p. 377 ff., Professor H. H. Wilson published Sir Charles Wilkins' reading of the text and translation of it, accompanied by a lithograph, apparently full-size, prepared from an impression which was found in 1805 or 1806 by Captain Colebrooke at Asirgadh, in a box containing property of the Mahārājā Scindia, and was forwarded by him to Sir Charles Wilkins.

Asirgadh¹ is a hill-fort, which formerly belonged to Scindia, about eleven miles to the north-east of Burhānpur,² the chief town of the Burhānpur Tahsil or Sub-Division of the Nimād³ District in the Central Provinces. As is shewn by the Sōmpat seal of Harshavardhana, No. 52 below, Plate xxxiiB., and the seal attached to the spurious Gayā plate of Samudragupta, No. 60 below, Plate xxxvii., the original of the inscription is evidently the seal, presumably of copper, of a copper-plate grant. The grant itself appears never to have been found. As regards the seal, it is not quite clear from the published accounts whether the original was ever found, or only impressions of it. But, at any rate, I have not been able to find out what became either of the seal, or of the impressions of it. My lithograph is a full-size reproduction of the lithograph published with Professor H. H. Wilson's paper.

In the absence of the original seal and impressions, I am unable to give any details as to its measurements, weight, state of preservation, &c. But, if the original lithograph is full-size, it represents a seal, roughly oval in shape, measuring about $4\frac{1}{4}$ " by $5\frac{1}{4}$ ". The upper part is occupied by emblems, which are—in the centre, a bull, walking to the proper right, decorated with a garland; beyond it, or perhaps attached to its off-side, there is an umbrella, the staff of which is decorated with two streamers; on the proper right side, in front of the bull, there is a man, walking, who carries in his right hand a curved double axe on a short transverse handle, and in his left hand, either a standard, with a wheel or sun-emblem on the top of it, or perhaps an *abddgtr* or 'sunshade'; and on the proper left, behind the bull, there follows another man, who carries in his left hand an ordinary long-handled double axe, and in his right either a *chauri*-brush or a stick, with which he is driving the bullock.—The characters belong to the northern class of alphabets; and, though rather florid, especially in respect of the representation of the superscript vowels, they are of a perceptibly older type than those of the inscriptions of the Guptas of

¹The 'Asirgadh and Assec Gurh' of maps, &c. Indian Atlas, Sheet No. 54. Lat. $21^{\circ} 28' N.$; Long. $76^{\circ} 20' E.$

²The 'Burhanpur and Boorhanpoor' of maps, &c.

³The 'Nimār' of maps, &c.

Magadha, Nos. 42, 43, and 46, Plates xxviii. and xxixA. and B.—The language is Sanskrit; and the inscription is in prose throughout.—In respect of orthography, we have to notice (1) the use of the *upadhmanya*, in *utpannaḥ-parama*, line 7; (2) the doubling throughout of *k* and *t*, in conjunction with a following *r*; e.g. in *atikkrānta*, line 1, and *putra*, line 3; and (3) the doubling of *dh*, in conjunction with a following *y*, in *anuddhyāta*, lines 3, 4, 5, and 6.

The seal is one of the Maukhari king Śarvavarman, whose approximate date is fixed very closely by the mention of his father Īśānavarman, as the contemporary of Kumāragupta of Magadha, in line 7 of the Aphaś inscription of Ādityasēna, No. 42 above, page 200. The mere finding of the inscription at Aśirgadh of course does not suffice in any way to connect the members of this family of Maukharis with that locality. Their territory probably lay some hundreds of miles more to the east. Its real position, however, is a point that, with the definite date of Śarvavarman, can only be cleared up by the discovery, if it is still in existence, of the plate itself, to which the seal belongs.

TEXT.¹

- 1 Chatus-samudr-ātikkrānta-kīrttiḥ pratāp-ānurāg-ōpanat-ānya-rājā(jō)^a varṇ-
āśrama-vyavasthā-
- 2 pana-pravṛitta-chakkras=Chakkradhara iva prajānām-artti-hara[h^o] śrī(śrī)-
mahārāja-Harivarmmā [11^o] Tasya
- 3 puttras=tat-pād-ānuddhy[ā^o]tō Jayasvāmini-bhaṭṭārikā-dēvy[ā^o]m-utpannaḥ
śrī-mahārāj-Ādityava-
- 4 rmmā [11^o] Tasya puttras=tat-pād-ānuddhyātō Harshaguptā-bhaṭṭārikā-
dēvyām-utpannaḥ śrī-mah[ā^o]rā-
- 5 j-Ēśvaravarmmā [11^o] Tasya puttras=tat-pād-ānuddhyāta Upaguptā^b-
bhaṭṭārikā-dēvyām-utpannō
- 6 mah[ā^o]rājādhirāja-śrī(śrī)-Īśāna^cvarmmā [11^o] Tasya puttras=tat-pād-
ānuddhyātō La(?)ksh[m]īva-
- 7 [tṣ^h]^d-bhaṭṭārikā-mah[ā^o]dēvyām-utpannaḥ-paramamāhēśvarā(rō) ma-
- 8 hārājādhirāja-śrī-Śarvavarmmā Maukharīḥ [11^o]

¹ From the lithograph published with Sir Charles Wilkins and Prof. Wilson's paper; so also the present lithograph.


² In the absence of the original seal, which possibly was not properly cleaned before it was copied, I can only treat this, and a few other instances, as mistakes of the original, though they may be only defects in the lithograph.

³ Sir Charles Wilkins read *umdguptā*. As regards the second syllable, *m* and *p* are very much alike in the lithograph. But the letter here seems to be *p*, rather than *m*; and there is certainly no *d* over it.—In support of my reading, the name Upaguptā occurs in the masculine form, Upagupta, as the name of the fourth or fifth Buddhist Patriarch (e.g. *Ind. Ant.* Vol. IX. pp. 149, 315; *Buddh Rec. West. World*, Vol. I. p. 182, and Vol. II. pp. 88, 93, 273).

⁴ Read *īśāna*.

⁵ Sir Charles Wilkins read *harshinī*; but there are four *aksharas* to be accounted for, not three. The first *akshara* is very doubtful; the second is certainly not *rshī*, but seems to be *ksh[m]ī*, rather imperfectly copied; the third is *va*; in the fourth, the superscript *f* is distinctly visible, and the consonant, which is almost entirely illegible, naturally suggests itself as *t*.

A.—Asirgadh Seal of Sarvavarman.



FULL SIZE

B.—Barabar Hill Cave Inscription of Anantavarman.

ॐ नमो भगवते वासुदेवाय ॥ १ ॥
 ॐ नमो भगवते वासुदेवाय ॥ २ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ३ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ४ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ५ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ६ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ७ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ८ ॥
 ॐ नमो भगवते वासुदेवाय ॥ ९ ॥
 ॐ नमो भगवते वासुदेवाय ॥ १० ॥

SCALE 1/2

TRANSLATION.

(*There was*) the illustrious *Mahārāja Harivarman*, whose fame stretched out beyond the four oceans; who had other kings brought into subjection by (*his*) prowess and by affection (*for him*); who was like (the god) Chakradhara, in employing (*his*) sovereignty¹ for regulating the different castes and stages of religious life; (*and*) who was the remover of the afflictions of (*his*) subjects. His son, who meditated on his feet, (*was*) the illustrious *Mahārāja Ādityavarman*, begotten on the *Bhaṭṭārikā* and *Dēvī Jayasvāmini*. His son, who meditated on his feet, (*was*) the illustrious *Mahārāja Śīsvavarman*, begotten on the *Bhaṭṭārikā* and *Dēvī Harshaguptā*. His son, who meditated on his feet, (*was*) the *Mahārājādhirāja*, the glorious *Śīśavarman*, begotten on the *Bhaṭṭārikā* and *Dēvī Upaguptā*.² His son, who meditates on his feet, (*is*) the most devout worshipper of (the god) Mahēśvara, the *Mahārājādhirāja Śarvavarman*, the *Maukhari*, begotten on the *Bhaṭṭārikā* and *Mahādēvī Lakshmiṇvatī*.³

No. 48; PLATE XXX B.

BARABAR HILL CAVE INSCRIPTION OF ANANTAVARMAN.

THIS inscription appears to have been discovered, about 1785, by Mr. J. H. Harington, and was first brought to notice, in 1790, in the *Asiatic Researches*, Vol. II. p. 167 *l.*, where Sir Charles Wilkins published his translation of it, apparently from a copy made under the direction of Mr. Harington.⁴—In 1837, in the *Four. Beng. As. Soc.* Vol. VI. p. 674 *ff.*, Mr. James Prinsep published his reading of the text, and a translation of it, accompanied by a lithograph (*id.* Plate xxxvi. Nos. 15, 16, and 17) reduced from an ink-impression taken under the direction of Mr. Hathorne.—And in 1884, in the *Ind. Ant.* Vol. XIII. p. 428, note 55, Dr. Bhagwanlal Indraji has incidentally published his own reading of the text.

The *Barābar Hill*, the ancient *Pravaragiri* of this inscription, stands about a mile and a half away on the north side of the village of *Panāri*,⁵ which is about fourteen miles to the north by east of *Gayā*,⁶ the chief town of the *Gayā District* in the *Bengal Presidency*. In the south part of the hill there is a cave-temple, which it has become the custom to call the "*Lōmaśa Rishi Cave*,"⁷ and the original construction of which is allotted by

¹Typified by the *chakra*, or 'wheel (of his chariot).'*—chakra* means also the diacus of *Vishnu*, and hence the point of the comparison.

²*Bhaṭṭārikā*, *lit.* 'she who is entitled to reverence or homage,' is the feminine form of *bhaṭṭārika* (see page 17 above, note 1). It is used here as a technical title of a wife of a *Mahārāja*; but, in line 7 below, it occurs also as the title of a wife of a *Mahārājādhirāja*.

³*Dēvī*, *lit.* 'goddess,' is another technical title of a wife of a *Mahārāja*.

⁴See page 220 above, note 3.

⁵See page 220 above, note 5.

⁶See also the Calcutta reprint of the *Asiatic Researches*, Vol. II. p. 128.

⁷The '*Punaree-Ferozpoor*' of the *Indian Atlas*, Sheet No. 103. Lat. 24° 59' N.; Long. 85° 7' E. The hill itself is entered under the name of '*Baraber Hill*,' and is a *Trigonometrical Survey Station*.

⁸The '*Gya*' of maps, &c.

⁹Marked C. in Gen. Cunningham's sketch given in the *Archæol. Surv. Ind.* Vol. I. p. 40, Plate xviii.

General Cunningham to the Aśoka period, though the entrance-porch was enlarged and decorated with a sculptured façade at a later time, probably when the present inscription was engraved. The inscription is on a smooth polished surface of the granite rock, over the entrance to the cave.¹

The writing, which covers a space of about 3' 9½" broad by 1' 3½" high, is in a state of excellent preservation throughout.—The size of the letters varies from ⅜" to 1½". The characters belong to the northern class of alphabets, and exhibit very markedly the fully developed *mātrās*, or horizontal top-strokes of the letters, that have already been noticed at pages 43 and 140 above.—The language is Sanskrit; and, except for the opening symbol representing the word *śm*, the inscription is in verse throughout.—In respect of orthography, the only points that call for notice are (1) the doubling throughout of *t*, in conjunction with a following *r*; e.g. in *puttra*, line 1, and *yattra*, line 5; and (2) the use of *v* for *b*, in *vabhāva*, line 4.

The inscription is one of a Maukhari chieftain named Anantavarman; but, from the way in which his father Śārdūla or Śārdūlavarman is mentioned in line 5, it seems to have been engraved while the latter was still alive. It is not dated. It is a Vaishṇava inscription; the object of it being to record the installation in the cave, by Anantavarman, of an image of the god Viṣṇu, in his incarnation as Kṛiṣṇa.

The hill itself is mentioned in line 2, under the name of Pravaragiri. The word, of course, is capable of being taken simply as an epithet, to be rendered by "(this) excellent hill." But, on the analogy of the town of Pravarapura, which is mentioned in the first line of the Chammak grant of the Mahārāja Pravarasēna II., No. 55 below, Plate xxxiv., it seems to me to be clearly intended as the actual name of the hill. And we have possibly a reminiscence of it in the modern name Barābar, for which, at any rate, General Cunningham's proposed etymology of *barā dvāra*, 'the great enclosure,' does not suffice to account.

TEXT:

- 1 Om⁴ [11^o] Bhūpānā[ṛṇ^o] Maukharipāṇāḥ kulam-atanu-guṇḍ-lam-chakār-ātma-jātyā⁵ १^o śrī-Śārdūlasya yō-bhūj-jana-hṛdaya-harō-Nantavarmmā su-puttraḥ [1^o]
- 2 Kṛiṣṇasy-ākṛiṣṇa-klṛtīḥ Pravaragiri-guhā-samśritāḥ vīrtvam-ētat mūrta'm lōkē yaśa[h^o] svam rachitam-iva mud-āchkarat-kāntimat-saḥ ॥

¹ Gen. Cunningham (*Archæol. Surv. Ind.* Vol. I. p. 47) speaks of it as "two distinct inscriptions, the upper one, of two lines, being somewhat later in date than the lower one, of four lines, in rather larger characters." But the six lines are all one and the same inscription; and the rather smaller size of the letters in the first two lines is simply due to the lateral space available being less, in consequence of the turning over of the upper part of the façade, within the limits of which the inscription is engraved.

² *id.* p. 43.

³ From the original stone.

⁴ In the original, the symbol for this word, *śm*, stands in the margin, opposite the commencement of line 3.

⁵ Metre, Sragdhara.

⁶ This mark of punctuation is unnecessary.

⁷ The engraver first formed *rīti*, and then partially cancelled the *i*.

- 3 KĀlah' sattru-mahābhujān prapayinān ichchhā-phalaḥ pādapō¹ dīpah
kshattra-kulasya naika-samara-vyāpāra-śōbhāvataḥ [1*]
4 kĀntā-chitta-harāḥ Smara-pratisamaḥ pātā va(ba)bhūva kshiteḥ śrī-Śārdūla
iti pratishṭhita-yaśā[h*] sāmanta-chūdāmanih ||
5 Utpaksh-māntavilōhit-ōru-tarala-spasht-ēshta-tārān rushā¹ śrī-Śārdūla-nripah
karōti vishamān yattra sva-dṛishṭim ripō(pau) |
6 tattr-ākārṇa-vikṛishṭa-śārngā-śaradhi-vyastāś-śarō-tt(nt)-āvahah tat-puttrasya
pataty-ananta-sukha-dasy-Ānantavarmma-śrutēḥ ||

TRANSLATION.

Om! He, **Anantavarman**, who was the excellent son, captivating the hearts of mankind, of the illustrious **Sardūla**,⁴ (*and*) who, possessed of very great virtues, adorned by his own (*high*) birth the family of the **Maukhari** kings,—he, of unsullied fame, with joy caused to be made, as if it were his own fame represented in bodily form in the world, this beautiful image, placed in (*this*) cave of the mountain **Pravaragiri**, of (the god) **Krishna**.

(Line 3.)—The illustrious **Sardūla**, of firmly established fame, the best among chieftains,⁵ became the ruler of the earth;—he who was a very Death to hostile kings; who was a tree, the fruits of which were the (*fulfilled*) wishes of (*his*) favourites; who was the torch of the family of the warrior caste, that is glorious through waging many battles; (*and*) who, charming the thoughts of lovely women, resembled (the god) **Smara**.

(L. 5.)—On whatsoever enemy the illustrious king **Sardūla** casts in anger his scowling eye, the expanded and tremulous and clear and beloved pupil of which is red at the corners between the up-lifted brows,—on him there falls the death-dealing arrow, discharged from the bowstring⁶ drawn up to (*his*) ear, of his son, the giver of endless pleasure, who has the name⁷ of **Anantavarman**.

No. 49; PLATE XXXI A.

NAGARJUNI HILL CAVE INSCRIPTION OF ANANTAVARMAN.

THIS inscription, again, appears to have been discovered, about 1785, by Mr. J. H. Harington, and was first brought to notice, in 1790, in the *Asiatic Researches*, Vol. II. p. 168 f., where Sir Charles Wilkins published his translation of it, apparently from a copy made under the direction of Mr. Harington.⁸—In 1847, in the *Four. Beng. As. Soc.* Vol. XVI. p. 401 ff., Major Markham Kittoe published a lithograph of it

¹ Metre, Śārdūlavikṛīḍita; and in the following verse.

² and ³ These marks of punctuation are unnecessary.

⁴ As regards this abbreviated form of his name, see page 8 above, note 3.

⁵ *Sāmanta*; see page 148 above, note 1. The use of the word here perhaps indicates the exact status of these Maukhari chiefs.

⁶ *śaradhi*, lit. 'the arrow-holder,' is usually explained by 'quiver.' But here it plainly denotes the string of the bow.

⁷ *lit.* 'the hearing, the sound.'

⁸ See also the Calcutta reprint of the *Asiatic Researches*, Vol. II. p. 129.

- 3 Śrī-Śārdūla-nṛip-ātmapajāḥ para-hitāḥ śrī-pauruṣhaḥ śrūyatē 1^a lōkē chandra-
marīchi-nirmala-guṇō yō-Nantavarman-ābhidhā(dha)ḥ [1^a]
- 4 dṛiṣṭ-ādṛiṣṭa-vibhūti karṭri-varadaṁ tēn-ādbhutaṁ kāritaṁ 1^a vimvaṁ
Bhūtapatēr-guh-āsritaṁ-idaṁ Dēvyāś=cha pāyāj-jagat ||
- 5 An^a-ānt-ākriṣṭa-śāṅga-pravitata-saśara-jyā-sphuran-maṅḍal-ānta- | -vyakta-
bhrūbhāṅga-lakṣma-vyatikara-śaval-ākhaṇḍa-vaktṛēndu-vimva[h^a] |
- 6 antāy-Ānantavarmanā Smara-sadriśa-vapur-jjivitē ni[h^a]sprihābhīḥ dṛiṣṭa[h^a]
sthitvā mṛigibhīḥ suchiram-animiśa-snigdha-mugdh-ēkṣaṇābhīḥ ||
- 7 Atyākriṣṭāt^a=kurara-viruta-sparddhinaḥ śāṅga-yantrā- | -d^a=vēg-āviddhaḥ
pravitata-guṇād-īritāḥ saushṭhavēna |
- 8 dō'ra-prāpī vimathita-gaj-ōdbhrānta-vājī pravīṭō 1^a vāṇō-ri-strī-vyasana-padavi-
dēsikō=Nanta-nāmnā(mna)ḥ^a ||

TRANSLATION.

Om! There was a glorious king, the illustrious **Yajñavarman**,—who, as if he were Anu,²⁰ instructed all rulers of the earth in the duty of those who belong to the warrior caste;—whose gait was like the play of a rutting elephant;—(and) through whose sacrifices (the goddess) Paulōmi, always emaciated by separation from (the god Indra) who has a thousand eyes, invoked (by this king so constantly as to be perpetually absent from her), has had the beauty of (her) cheeks for a long time sullied by the falling of tears.

(Line 3.)—He, the son of the illustrious king **Śārdūla**, who has the name of **Anantavarman**; who is reputed in the world to be benevolent to others, (and) to be possessed of fortune and manliness, (and) to be full of virtues that are as spotless as the rays of the moon,—by him was caused to be made this wondrous image, placed in (this) cave, of (the god) Bhūtapati and (the goddess) Dēvi, which is possessed of excellencies (of workmanship) some of them (previously) beheld (in other images) but others not so; (and) which confers boons upon the maker (of it). May it protect the world!

(L. 5.)—Having the surface of the full-moon that is (his) face made grey through being scattered over with spots that are (his) frowns displayed at the ends of the bent arc, glistening with (its) string pulled tight and fitted with an arrow, of the bow drawn up to the extremities of (his) shoulders, **Anantavarman**, whose body is like (that of) (the god) Smara,—having stood, gazed upon for a very long time by the does, indifferent to life, whose moist and tender eyes omit to blink (through the intentness with

¹ and ² These marks of punctuation are unnecessary.

³ Metre, Sragdharā.

⁴ Read *anta-vyakta*, omitting the mark of punctuation.

⁵ Metre, Mandākrāntā.

⁶ Read *yantrā*, omitting the mark of punctuation.

⁷ This *akshara* is partly mixed up with the *ś* of *dś* in *vidhivasu*, which was subsequently engraved below this inscription, but has no connection with it.

⁸ This mark of punctuation is unnecessary.

⁹ This *visarga* was at first omitted, and then was inserted partially on the first stroke of the following mark of punctuation, when the text was altered from *nāmnā* to *nāmnāḥ*.

²⁰ See page 224 above, note 6.—Anu, one of the sons of Yayāti, was the progenitor of the Ānavas who are identified by Gen. Cunningham (*Archaeol. Surv. Ind. Vol. II. p. 14 ff.*) with the 'Janjāhas,' who now occupy 'Makhylā' and other places in the Salt Range, in the Panjāb.

which they regard him),—(lives only) for (the purpose of dealing out) death. The far-reaching (and) powerful arrow, scattering the elephants and driving horses wild with fear, of him who has the name of **Ananta**,¹—impelled with speed (and) skilfully discharged from the machine of (his) bow, fitted with a well-stretched string, that is drawn very tight (and) rivals the screams of an osprey (with the noise of its twanging),—teaches to the wives of (his) enemies the condition of the sorrows (of widowhood).

No. 50; PLATE XXXIB.

NAGARJUNI HILL CAVE INSCRIPTION OF ANANTAVARMAN.

THIS inscription, again, appears to have been discovered, about 1785, by Mr. J. H. Harington, and was first brought to notice in 1788, in the *Asiatic Researches* Vol. I. p. 276 ff., where Sir Charles Wilkins published his translation of it, from a copy made under the direction of Mr. Harington, and, with it, a lithograph from the same materials.²—And in 1837, in the *Four. Beng. As. Soc.* Vol. VI. p. 672 ff., Mr. James Prinsep published another reading of the text, and a translation of it, accompanied by a lithograph (*id.* Plate xxxiv.), reduced from an ink-impression taken under the direction of Mr. Hathorne.

This is another inscription from the **Nâgârjuni Hill**³ in the lands of **Jâphra**, in the **Gayâ District** of the Bengal Presidency. On the south side of the hill, there is another cave-temple, which also is shewn to belong to the **Aśôka** period by another inscription, in four lines, of **Dasalatha-Dêvânâmpiya** on the rock over the entrance, and which, from the first two words of that inscription, has come to be called the "**Gôpl Cave**."⁴ The inscription now published is on the smooth and polished surface of the granite rock, on the left hand in the entrance to the cave

The writing, which covers a space of about 4' 11" broad by 1 11½" high, is in a state of excellent preservation throughout; except that, in the last line, the name of the village that was granted has been intentionally obliterated.—The average size of the letters is about 1". The characters belong to the northern class of alphabets, and are of precisely the same type as those of the preceding two inscriptions of the same chieftain, Nos. 48 and 49 above, Plates xxxB. and xxxiA., exhibiting, in the same way, the fully developed *mâtrās*.—The language is Sanskrit; and, except for the opening symbol representing the word *ôm*, the inscription is in verse throughout.—In respect of orthography, we have to notice (1) the use of the guttural nasal, instead of the *anusvâra*, before *ś*, in *anśu*, line 2, and before *h*, in *anśas*, line 9; (2) the customary doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *viktrama*, line 4, and *puttrêna*, line 7; and (3) the use throughout of *v* for *h*, in *lavdham*, line 5; *vandhu*, line 6; and *amvubhih*, line 9.

The inscription is another record of the **Maukhari** chieftain **Anantavarman**. It is not dated. It is either a **Śaiva**, or a **Śākta**, inscription; the object of it being to record the installation in the cave, by **Anantavarman**, of an image of the goddess **Pārvatī**, the wife of **Śiva**, under the name of **Kātyāyanī**, and also the grant to the same goddess, under the name of **Bhavānī**, of a village, the name of which has been destroyed.

¹ As regards this abbreviated form of his name, see page 8 above, note

² See also the Calcutta reprint of the *Asiatic Researches*, Vol. I. p. 276 ff.

³ See page 224 above, and note 1.

⁴ Marked E. in Gen. Cunningham's sketch in the *Archæol. Surv. Ind.* Vol. I. p. 40, Pl. xviii.

A.—Nagarjuni Hill Cave Inscription of Anantavarman

1. ॐ नमो भगवते वासुदेवाय ॥
 2. ॐ नमो भगवते वासुदेवाय ॥
 3. ॐ नमो भगवते वासुदेवाय ॥
 4. ॐ नमो भगवते वासुदेवाय ॥
 5. ॐ नमो भगवते वासुदेवाय ॥
 6. ॐ नमो भगवते वासुदेवाय ॥
 7. ॐ नमो भगवते वासुदेवाय ॥
 8. ॐ नमो भगवते वासुदेवाय ॥

scale. 17

B.—Nagarjuni Hill Cave Inscription of Anantavarman

1. ॐ नमो भगवते वासुदेवाय ॥
 2. ॐ नमो भगवते वासुदेवाय ॥
 3. ॐ नमो भगवते वासुदेवाय ॥
 4. ॐ नमो भगवते वासुदेवाय ॥
 5. ॐ नमो भगवते वासुदेवाय ॥
 6. ॐ नमो भगवते वासुदेवाय ॥
 7. ॐ नमो भगवते वासुदेवाय ॥
 8. ॐ नमो भगवते वासुदेवाय ॥
 9. ॐ नमो भगवते वासुदेवाय ॥
 10. ॐ नमो भगवते वासुदेवाय ॥

In line 8 of this inscription, the **Nâgarjuni Hill** is spoken of as (a part of) the **Vindhya range**. This is in accordance with facts; since the Vindhya mountains, though most conspicuous in Western and Central India, do extend right across the peninsula, until, passing through the neighbourhood of Gayâ, their easternmost spurs reach and disappear in the valley of the Ganges at Râjmahâl.

TEXT.¹

- 1 Om [11^{*}] Unnidrasya² sarôruhasya sakalâm-âkshipya sôbhâm ruchâ³ !
s-âvajñam Mahish-âsurasya śirasi nyastah kvaṇan-nôpurah |
- 2 Dēvyā vah sthira-bhakti-vāda-sadrīśm yufjan-phalēn-ārthitām | diśyād-
achchha-nakh-āṅśu-jāla-jatilah pādah padam sampadam ||
- 3 Āstid-iṣhta-samridha-yajña-mahimā śrī-Yajñavarmmā nripah | prakhyātā(tō)
vimal-ēndu-nirmalāya-yaśā[h^{*}] kshātrasya dhāmnah padam |
- 4 prajñān-ānvaya-dāna-vikkrama-guṇair-yō rājakasy-āgraj[h^{*}] | bhōtv-āpi
prakṛiti-stha ēva vinayād-akshôbhya-sat[t^{*}]v-ôdadhi[h^{*}] ||
- 5 Tasy-ôdīrṇa-mah-ārnav-ôpama-raṇa-vyāpāra-lavdha(bdha)m yaśah [1^{*}] tanvānah
kakudam mukhēshu kakubhām kṛt[t^{*}]yā jit-ēdamyugah [1^{*}]
- 6 śrīmān=va(ba)ndhu-suhrij-jana-prapayinām-āśāh phalaih pūraya[n^{*}] | puttrah
kalpa-tarōr-iv-āpta-mahimā⁴ Śārdūlavarmmā nripah ||
- 7 Tasy-anantam-ananta-kīrtti-yaśasō-Nant-ādi-varmm-ākhyayā | khyātēn-āhita-
bhakti-bhāvita-dhiyā puttrēna pūt-ātmanā [1^{*}]
- 8 ā-sūrya-kshiti-chandra-tārakam-iyam puny-āspadam vāñchchha(ñchha)tā |
vinyast-ādbhuta-Vindhya-bhōdhara-guhām-āśritya Kātyāyan! ||
- 9 Dhaut-ānhō-mala-pāṅka-dōsham-amalair-māhānadair-amvu(mbu)bhīh | vyād hūt-
ôpavana-priyangu-vākulair-āmōditam vāyubhi[h^{*}] |
- 10 kalpant-āvadhī-bhōgyam-uchcha-śikhari-chchhāy-āvrit-ārka-dyutim | [— —]
grāmam-analpa-bhōga-vibhavam ramyam Bhavānyai dadau ||

TRANSLATION.

Om | May the foot of (the goddess) *Dēvī*, fringed with the rays of (*śrī*) pure nails point out the way to fortune, endowing with a (*suitable*) reward your state of supplicator which is such as befits the expression of firm devotion;—(that foot) which, surpassing in radiance all the beauty of a full-blown waterlily, was disdainfully placed, with its tinkling anklet, on the head of the demon Mahishāsura !⁵

(Line 3.)—There was a king, the illustrious **Yajñavarma**n, possessed of greatness by celebrating copious sacrifices; renowned; possessed of fame as pure as the spotless moon; the abode of (*all*) the dignity of one of the warrior caste;—who, though he was the foremost of all kings in respect of wisdom, (*high*) descent, liberality, and prowess, yet, through modesty, was (*like*) an ocean which adheres to the natural state (*of tranquillity*), (*and*) the calmness of which is never to be disturbed.

¹ From the original stone.² Metre, Śārdūlavikrīḍita, throughout.³ It is not customary to punctuate the first and third *pādas* of a verse; but it was done almost uniformly throughout this inscription.⁴ Read *mahimā*.⁵ A demon who assumed various forms, but principally that of a buffalo, and was slain by *Pārvaṭī*, who, in the form of *Dēvī* or *Durgā*, attacked him, on a lion, and cut off his head.

(L. 5.)—His son (*was*) the king **Sârdûlavarman**, who stretched out over the faces of the points of the compass, (*as*) an emblem of sovereignty, the renown that he had acquired in the occupation of war resembling (*in its extensiveness*) the great swollen ocean; who conquered (*the stains of*) this present age with (*his*) fame; who was illustrious; (*and*) who acquired, as it were, the glory of the *kalpa*-tree, by satisfying with rewards the wishes of (*his*) relatives and friends.

(L. 7.)—Of him, who was always possessed of infinite fame and renown, the son (*is*) he, pure of soul, (*and*) possessed of intellect animated with innate piety, who is known by the appellation of **Varman** commencing with **Ananta**;¹—by whom, desiring a shrine of religious merit that should endure as long as the sun, the earth, the moon, and the stars, this (*image of*) (the goddess) Kâtyâyani has been placed in (*this*) wonderful cave of the **Vindhya** mountains.

(L. 9.)—He has given to (the goddess) Bhavâni, to be enjoyed up to the time of the destruction of all things, the charming village of, possessed of a great wealth of enjoyment,—the sin, impurity, mud, and blemishes of which are washed away by the pure waters of a great river;²—which is filled with perfume by the breezes that agitate the *priyangu*³ and *vakula*-trees⁴ in (*its*) groves;—(*and*) from which the radiance of the sun is screened off by (*this*) lofty mountain.

No. 51; PLATE XXXIIA.

JAUNPUR STONE INSCRIPTION OF ISVARAVARMAN.

THIS inscription,—which was discovered by General Cunningham in 1875-76 or 1877-78, and was first brought to notice by him in 1880, in the *Archæol. Surv. Ind.* Vol. XI. p. 124 f., where he published his reading of the text, accompanied by a lithograph (*id.* Plate xxxvii. No. 1),—is from a stone built in as one of the lower voussours of the outer arch of the south gate of the Jâmi Masjid at **Jaunpur**,⁵ the chief town of the Jaunpur District in the North-West Provinces.

The **writing**, which covers a space of about 1' 3½" broad by 1' 1½" high, is, so far as it goes, in a state of very good preservation, except for the marks by which it has been disfigured a little above the centre of the stone. But it is only a fragment of a very much larger inscription. Nothing has been lost at the top, and at the ends of the lines. But from thirty-eight to seventy-two *aksharas*,—probably the larger number,—are lost at the beginning of each line; and also an indefinite number of lines below the last line that is extant.—The average size of the letters is about ½". The **characters** belong to the

¹ *i. e.* Anantavarman.

² We might find in this verse a reference to "the pure waters of (the river) Mahânadî." But the Mahânadî, which rises in the Râjpur District, flows into the Bay of Bengal, without coming anywhere within two hundred and fifty miles of the Nâgârjunî hill. The small river that runs past this hill, is named the Phalgu; and it flows into the Ganges, not into the Malânadî. Under the name of Phalgu, it is mentioned in an inscription, belonging to about the twelfth century A. D., of a prince named Yakshapâla, at the Satî Ghât at Gayâ (*Ind. Ant.* Vol. XVI. p. 64, line 2).

³ *priyangu*; the Panicum Italicum; a medicinal plant, and perfume.

⁴ *vakula*; the Mimosa Elengi.

⁵ The 'Jounpoor' of maps. Indian Atlas, Sheet No. 88. Lat. 25° 41' N.; Long. 82° 43' E.

northern class of alphabets, and are radically of much the same type as those of the Asirgadh seal of Śarvarman, No. 47 above, Plate xxxA.; but the execution is, in some details, still more florid. In *dōrbhyām*, line 1, *kirttēr*, line 4, *karair-gunair-gunavatām*, line 5, and other places, we have to note that the superscript *r* is formed on the top line of the writing, instead of above it.—The language is Sanskrit; and the extant portion of the inscription is in verse throughout.—In respect of **orthography**, the only points that call for notice are (1) the doubling of *k*, *t*, and *d*, in conjunction with a following *r*, e.g. in *kkrūra*, line 5; *kshatrēna*, line 1, and *upaddravair*, line 5; and (2) the use of *v* for *b*, in *lavdha*, line 1.

The inscription mentions, in line 4, a 'king' named **Īsavarman**, of the **Maukhari**, or as it is here called the **Mukhara** family, who is evidently the *Makārdja* **Īsavarman**, the grandfather of Śarvarman, who is mentioned in line 5 of the Asirgadh seal, No. 47 above, page 219. But the lacunæ in the following lines are so extensive, that it is impossible to say whether the historical information given in them refers to Īsavarman, or to one of his descendants. It is much to be wished that the first half of the stone could be recovered; since, in addition to clearing up this point, it would probably give the name of a king in connection with the city of **Dhārā** that is mentioned in line 6, and also the name of a king in connection with the **Andhras** who are spoken of in lines 7 and 8; and the latter information might afford the much-wanted starting-point for settling the chronology of the Andhra family. It would probably give us also the name of a king of **Saurāshtra** or **Kāthiāwād**, in connection with the mountain **Raivataka** that is mentioned in line 7. The extant portion of the inscription contains no date, and nothing to indicate a sectarian character.

TEXT.¹

- 1 r(?) . ksh(?) . l(?) . gam² || Dōrbhyām³=[Ā]tmabhuvō dhanuh
saha-bhuvā kshatrēna lavdh(bdh)-ātmanā vistār⁴
- 2 [u]dayini⁵ **Mukharāṇām** bhūbhujām-anvavāyē | sakala-
purusha-śakti-vyakta-śārnga-pratāpō
- 3 karnimanā⁶ yājñām dh[ū]ma-vitāna-mēgha-nivahaḥ pūpyam
vitēnē divi ||⁷
- 4 laka⁸-srast-ālakāgram kulaih || Tasya⁹ dikshu [v]itat-
āmala-kirttēr-ātmajō nripatir-**Īsavarammā**

¹ From the ink-impression.

² If (since we have a half-mark of punctuation after *anvavāyē* in line 2) we accept the double mark of punctuation after the fourth extant *akshara* of this line as marking properly the end of a verse, seventy-two *aksharas* have been cut away and lost here. If, however, it marks only the end of the second *pāda* of a verse, then only thirty-eight *aksharas* are lost.—I have tried several ways of arranging the verses, in order to determine exactly how many *aksharas* are lost at the commencement of each line, but without being able to satisfy myself. The probability is, however, that the larger number (seventy-two) has been lost at the beginning of this line, and in proportion all the way down.

³ Metre, doubtful.

⁴ Metre, Śārdūlavikrjīta.

⁵ Metre, Mālinī.

⁶ Metre, Śārdūlavikrjīta.

⁷ This mark of punctuation is followed by some scroll-work, to fill up the line.

⁸ Metre, Śārdūlavikrjīta.

Metre, Svāgatā.

- 5 [kri]p¹ -ānurāga-samita-kkrūr-āgam(?) -ōpaddravair-lōk -ānanda -karair-
gupair-gupavatām kō nāma
- 6 [a]dhishtitam kshatibhujām simhēna simhāsanam || Dhārā-
mārgga-vinirgat-āgni-kanika
- 7 dam || Vindhya-ādreḥ prati-randhram-**Andhra**-patinā samkā-
parēṇ-āsitam yātō Raivata-kāchalam
- 8 sām² vāraṇānām ghaṭāsu vyāptēsh-ōtkhāta-khadga-dyuti-
khachita-bhujēshv-**Andhra**-sēnā-bhaṭēshu
- 9 ra³-prapāta-salilaiḥ snātām silā-gandhibhiḥ prāley-āddri-
bhuvāś-cha śīta-payasaḥ prakshā-
- 10 rēpubhir-giri-sarit-pūr-ōrmmi-bhaṅg-ākulair-utsarpadbhir-anupragē-
pi divasō yasy-āp.
- 11 ḥ ya
.....

TRANSLATION.

..... [Wielding]
with (*his*) arms the bow of (the god) Ātmabhū,⁴ by means of (*his*) innate warriors' skill that pervaded (*his very*) soul in the flourishing lineage of the **Mukhara** kings; whose prowess with the bow was displayed with all the energy of a man; by the rite; (*and his*) religious merit, arising from sacrifices, spread out over the sky (*in the form of*) the mass of the clouds of the canopy of the smoke (*of his oblations*) having the ends of (*their*) curls fallen down by the families

(Line 4).—Of him, whose spotless fame spread far and wide over the regions, the son (*was*) king **Iśvaravarman**, with virtues which by means of compassion and affection allayed the troubles (*caused*) by the approach of cruel people, and which effected the happiness of mankind; who, indeed, of virtuous people; by him, a very lion to (*hostile*) kings, the throne was occupied. A spark of fire that had come by the road from (the city of) **Dhārā** the lord of the **Andhras**, wholly given over to fear, took up (*his*) abode in the crevices of the **Vindhya** mountains; went to the **Raivataka** mountain among the warriors of the **Andhra** army, who were spread out among the troops of elephants (*and*) whose arms were studded with the lustre of (*their*) swords drawn out (*from the scabbards*), bathed with the waters, fragrant with benzoin, of the torrents of and cleansing the lands, full of cool waters, of (Himālaya) the mountain of snow with the pollen disordered by the breaking of the waves of the swollen mountain-streams, (*and*) flowing onwards, whose day, even in the hours that come next after daybreak


¹ Metre, Śārdūlavikrīḍita, and in the next three lines.

² Metre, Sragdhara.

³ Metre, Śārdūlavikrīḍita, and in the next line.

⁴ *Iti*. 'the self-existent one;' an epithet of Brahman, Vishṇu, and Śiva. From the mention of a bow, it must here denote Vishṇu, who carries the bow of horn named Śārngā.

A.—Jaunpur Inscription of Isvaravarman



SCALE .25

B.—Sonpat Seal of Harshavardhana



FULL SIZE

No. 52; PLATE XXXII B.

SONPAT COPPER SEAL INSCRIPTION OF HARSHAVARDHANA.

THIS inscription, which is now brought to notice for the first time, is from a copper seal in the possession of Moharsingh Ramratan Mahajan, a merchant at **Sônpat**¹ or **Sônipat**,² the chief town of the Sônpat Tahsil or Sub-Division of the Dehli District in the Panjâb. I obtained the seal for examination through the kindness of Mr. J. D. Tremlett, B.C.S., who, in fact, had the first information of it, and brought it to my notice.

The seal is oval, measuring about $5\frac{3}{4}$ " by $6\frac{1}{4}$ ". All round it there runs a rim, about $\frac{1}{4}$ " broad; and inside this there are, in rather shallow relief on a slightly countersunk surface,—at the top, a bull, recumbent to the proper right; and below this, the inscription that is given below. That it is only a seal, belonging to a copper-plate from which it has been detached, is shewn by plain indications of soldering on the back of it, and also by the spurious Gayâ plate of Samudragupta, No. 60 below, Plate xxxvii., which has a similar seal attached to it. The letters of the inscription are worn down so much, that in many places they can only be read by getting the light to fall on the surface at different angles; and in some places they are entirely illegible. The only historical information, however, that seems to be lost, is the completion of the name of Prabhâkaravardhana's father, in line 4. I have to acknowledge some assistance from Dr. Bhagwanlal Indraji in reading this inscription; but, of course, without binding him to any of the details of it, as here published.—The weight of the seal is 3 lbs. 6 oz.—The average size of the letters is about $\frac{1}{16}$ ". The characters belong to the northern class of alphabets, and are of much the same type as those of the Aśirgadh seal of Śarvavarman, No. 47 above, Plate xxxA.; but the forms are rather more conservative in details.—The language is Sanskrit; and the inscription is in prose throughout.—In respect of orthography, the only point that calls for notice is the doubling of *t*, in conjunction with a following *r*, in *putra*, lines 2 and 7.

The seal is one of Harshavardhana, king of Kanauj, who began to reign³ A.D. 606 or 607; and it is of peculiar interest, as being the first of his own epigraphical records that has ever come to light. I have made every effort to discover the plate to which it belongs; as the inscription on the plate would make the genealogy perfect, and also, if belonging to the early years of Harshavardhana's reign, would probably shew what era was used by him prior to the establishment of his own. But I have not succeeded in obtaining any information about it; and it seems to have been hopelessly lost sight of. The present owner of the seal states that there is no record of the plate itself having ever been in the possession of his family; so it is very doubtful whether it is now in existence.

¹ The 'Sonipat, Soonput, and Sunput,' of maps, &c. Indian Atlas, Sheet No. 49. Lat $28^{\circ} 59' N$ Long. $77^{\circ} 3' E$.

² Other forms of the name are Sônêpat, and Sunpat

³ See *Ind. Ant.* Vol. XIII. p. 420, note 37.

TEXT.¹

1 y ...	śrīma(?)há(ṛdā) ..
2	paramādityabha[ktō	mahārā]ja-śrī-Rājyavarddhanah [11*]
	Tasya	puttras=tat-p[ā]-	
3	[d-ānudhyātaḥ]	śrī(?)-Ma(?)há(?)dēvyām-[utpannah	paramā]dityabhaktō
	mahārāja-śrīmad-Āditya-		
4	{varddhanah ² [11*]	[Ta]sya [puttras=tat-pād-ānudhyātaḥ	śrī]-Mahā- sēnaguptā-dēvyām=utpanna
5	y . sarv[v]a-varṇ-āśrama-vyavasthāpana-	
	pravri-		
6	[ttaḥ]	y...va(?) prava[r]ddh.....	paramādityabhaktah
	paramabhaṭṭāraka-		
7	mahārājādhirāja-śrī-Prabhākaravarddhanah [11*]	Tasya	puttras=tat-pād- ānudhyā[ta]
8 i.....	śr[ī]matyā[m]	Yaś[ō]maty[ām]-utpannah]
	paramasō(sau)gata		
9	[paramabhaṭṭāraka]-mahārājādhi[rāja]-śrī-Rājyava[rddhanah] [11*]	
10	[Tasy-ānujas=tat-pād-ānu]dhyātō	mahādēvyā[m]	Yaśōmatyā-
11	[m-utpannah]		[pa]-
12	[ramabhaṭṭāraka-ma]hārājā[dhi]rāja-śrī-Harsha-		
13		varddhanah ⁴ [11*]	

TRANSLATION.

(There was) the most devout worshipper of the Sun, the *Mahārāja*, the illustrious *Rājyavardhana* (I.) His son, [who meditated on] his feet, (was) the [most devout] worshipper of the Sun, the *Mahārāja*, the illustrious *Ādityavardhana*,² [begotten] on the illustrious *Mahādēvi*(?). His [son, who meditated on his feet], (was) the most devout worshipper of the Sun, the *Paramabhaṭṭāraka* and *Mahārājādhirāja*, the glorious *Prabhākaravardhana*, begotten on the *Dēvi*, [the illustrious] *Mahāsēnaguptā*, (and) who was employed in regulating all the castes and stages of religious life. His son, who meditated on his feet, (was) the most devout follower of *Sugata*,³ the *Paramabhaṭṭāraka* and *Mahārājādhirāja*, the glorious *Rājyavardhana* (II.), begotten on the glorious *Yaśōmati*. [His younger brother], who meditated on [his feet], (is) the [*Paramabhaṭṭāraka* and] *Mahārājādhirāja*, the glorious *Harshavardhana*, [begotten] on the *Mahādēvi*, *Yaśōmati*.

¹ From the original seal.

² This part of the name is quite illegible; but the analogy of the other names seems to indicate that the termination here was the same, viz. *vardhana*.

³ These two *aksharas*, *mahā*, are very indistinct; but I think they may be accepted as certain.

⁴ These three *aksharas*, *varddhanah*, are rather small and cramped, in the centre of the bottom of the seal.

⁵ See note 2 above.

⁶ *paramasugata* is a Buddhist sectarian title. *Sugata*, lit. 'well-gone; well-bestowed; one who has attained a good state,' was one of the names or titles of Buddha.

Nos. 53 & 54; PLATE XXXIII A & B.

NACHNE-KI-TALAI STONE INSCRIPTIONS OF THE
MAHARAJA PRITHIVISHENA.

THESE two inscriptions were discovered by General Cunningham in 1883-84, and were brought to notice by him in 1885, in the *Archæol. Surv. Ind.* Vol. XXI. p. 97 f., where he published his reading of the text of the complete one, No. 54, accompanied by lithographs of both of them (*id.* Plate xxvii.)

Nachnê-ki-talâi, meaning literally the "tank of Nachna," is a small village or collection of huts, about seven miles south-west of Jasô,¹ the chief town of the Jasô State in the Bundêlkhand division of Central India. When I drafted the title of the Plate, I understood that the inscriptions were on a boulder lying in the jungle; whereas it now appears, from General Cunningham's published account, that they are on a loose slab which was found lying at 'Lakhura, Lakhuria, or Lakhâwara,' which is the name of the ground outside the fort of 'Kûthara or Kûtharagarh,' which again is given as an older name of the site on part of which the village of Nachna or Nachnê-ki-talâi now stands. The inscription of four lines, No. 54, is on the face of the slab; and the incomplete inscription, No. 53, on the side or edge of it. The explanation of No. 53 probably is, that this side was intended to be the front of the stone; but that the stone was then found to be too rough, and this face was made the side of it, and the inscription was commenced again and finished on what is now the front of it. And I am extremely doubtful whether the inscription on the side, No. 53, really consists of more than one line. Some signs resembling the syllables *vyâghra* are pencilled-in on the impressions that were sent to me; but I was unable to depute my own copyists to Nachnê-ki-talâi for the purpose of taking fresh impressions to settle this point, or to go there myself.

The **writing** of No. 53 covers a space of about 1' 9 $\frac{1}{2}$ " broad by 7 $\frac{1}{2}$ " high; and of No. 54, about 1' 9" broad by 1' 1" high. The imperfections of some of the letters appear to be due to incomplete engraving, owing to irregularities of the stone, rather than to subsequent injury. In the centre of No. 54 there is a **sculpture** which may be either a Buddhist wheel, or the sun-symbol.—The **size** of the letters varies from $\frac{1}{4}$ " to 1 $\frac{1}{4}$ ". The **characters** belong to the southern class of alphabets, and give another specimen of the 'box-headed' variety of the Central India alphabet, which I have noticed at page 18 f. above.—The **language** is Sanskrit; and both the inscriptions are in prose.—In respect of **orthography**, the only point calling for remark is the doubling of *dh*, before *y*, in *anuddhyâia*, in line 2 of No. 54.

As regards the contents of the **inscriptions**, No. 53 gives simply the name of the *Mahârâja Prithivishêna* of the *Vâkrâta*ka tribe or dynasty. No. 54 repeats this, and adds the name of a feudatory of his, *Vyâghradêva*. No date is given; and nothing to shew any sectarian purpose. And the record simply refers to *Vyâghradêva* having made something or other, which must have been either a temple, or a well or tank, of which this slab evidently formed a part.

¹ The 'Nachna, Nâchna, and Nârhua,' of maps, &c. It should be in the Indian Atlas, Sheet No. 70, but is not entered there. Lat. 24° 24' N., Long. 80° 30' E.

² The 'Jasso, Jusso, and Jussoo,' of maps, &c.

As regards the name of this family, **Vākātaka**, General Cunningham¹ has proposed its identification with the modern **Bhāndak**,² a place evidently of considerable antiquity, the chief town of the Bhāndak Parganā in the Chāndā District in the Central Provinces, fifteen miles north-west of Chāndā,³ and eleven miles south-east of Warōdā.⁴ It is possible that Bhāndak may have been the Vākāśaka capital. But the identity of the two names cannot be upheld. In the first place, there is the difficulty of accounting for the disappearance of the *k* in the second syllable of Vākātaka, and for the change of the lingual *t* into the dental *d*, with a nasal before it. In the second place, as pointed out by Dr. Bühler,⁵ there is an insuperable obstacle, in the suggested change of *v* into *bh*. And, in the third place, I have to point out that the name Vākātaka must be derived from an original *vakāta*; like, for instance, Māhākāntāraka from Māhākāntāra, Kausalaka from Kōsala, Kairājaka from Kēraja, and Paishtapuraka from Pishtapura, in line 19 of the Allahābād posthumous pillar inscription of Samudragupta, No. 1 above, and like Traikūtaka from Trikūta, in line 1 of the 'Pard' grant⁶ of the Traikūtaka *Mahārāja* Dahrasēna of the year 207. If any trace of the name is to be found in the maps of the present day, we must look for some such place as Wakāt, Bakāt, Bakat, Baktōr, or Baktauli; and it might possibly be found in 'Waktapur,' in the Rēwā-Kanṭhā Agency.

TEXT.⁷

No. 53.

- 1 Vākātakānām mahārāja-śri(śrī)-Prithivishēna . . .
2 Vyā(?)ghra(?)⁸

No. 54

- 1 Vākātakāna[m*] mahārāja-śri(śrī)-
2 Prithivishēna - pād a⁹nuddhyātō
3 Vyāghradēvō mātāpitṛō[h*] puny-
[a*]rttham
4 kṛitam¹⁰=iti [11*]

¹ *Archæol. Surv. Ind.*, Vol. IX, p. 121 f.² The 'Bhanduk' of the Indian Atlas, Sheet No. 73. Lat. 20° 6' N; Long. 79° 9' E.³ The 'Chandah' of maps.⁴ The 'Warodā and Wurrodā' of maps, &c.


⁵ *Archæol. Surv. West. Ind.* Vol. IV, p. 117 f., and *Ind. Ant.* Vol. XII, p. 239 f.—Dr. Bühler speaks of Vākātaka as being the name of a country, as well as of the tribe governing it. It probably did, in the usual way, denote the country, as well as the tribe or dynasty. But it does not occur in the compound quoted by him, 'Pavarāja-Vākātaka,' which exists only in the original misreading, for Pavarājāvātaka, in line 22 of the Siwanī grant, No. 56 below, page 246.—Vākātaka has also been supposed to occur as the name of a place or country in line 163 of the Anamkond inscription of the Kākatya chieftain Rudradēva, but this, again, is only due to the original misreading (*Jour. Beng. As. Soc.* Vol. VII, pp. 903, 908), the place that is really mentioned is Kātaka, as is shewn by the lithograph published with my own reading of this inscription (*Ind. Ant.* Vol. XI, pp. 11, 16, 20).

⁶ *Jour. Bo. Br. R. As. Soc.* Vol. XVI, p. 341.⁷ From Gen. Cunningham's ink-impressions; so also the lithographs.⁸ This *śr* was at first omitted and then inserted below the line.⁹ These two *akṣaras* are very doubtful; they are pencilled-in on the ink-impression, and there may be some traces of them; but the impression is not deep enough for them to shew in relief on the back of it.¹⁰ This *śr* was at first omitted and then inserted below the line.¹¹ Read *kṛitam*.


A.—Nachne-ki-talai Rock inscription of the Maharaja Prthivishena.




B.—Nachne-ki-talai Rock inscription of the Maharaja Prthivishena.



C.—Seal of the
Chammak Plates of
the Maharaja Pravarasena II.



D.—Seal of the
Siwani Plates of
the Maharaja Pravarasena II.



TRANSLATION.

Vyâghradêva, who meditates on the feet of the *Mahârdja* of the **Vâkâtakas**, the illustrious **Prithivishêna**, has made (*this*) for the sake of the religious merit of (*his*) *parents*.

No. 55; PLATE XXXIV.

CHAMMAK COPPER-PLATE INSCRIPTION OF THE
MAHARAJA PRAVARASENA II.

THIS inscription was discovered about 1868, and,—the original plates having been obtained by Major H. Szczepanski, and forwarded by him to Dr. John Wilson, of Bombay,—was first brought to notice in 1879, by Dr. Bhagwanlal Indrajî's reading of the text, published in *Notes on the Bauddha Rock-Temples of Ajanta*,¹ p. 54 ff.—And in 1883, Dr. G. Bühler, C.I.E., published his own reading of the text, and a translation of it, in the *Archæol. Surv. West. Ind.* Vol. IV. p. 116 ff., and also, accompanied by a lithograph of the plates, but not of the seal, in the *Ind. Ant.* Vol. XII. p. 239 ff.

The inscription is on some copper-plates that were found in ploughing a field at **Chammak**,² the ancient **Charmânka** of the inscription, a village about four miles south-west of Ilichpur,³ the chief town of the Ilichpur District in the Commissioner-ship of East Berar, in the Haidarâbâd Assigned Districts. The original plates, which I obtained for examination from Dr. Burgess, are now, I understand, again in the possession of Major Szczepanski.

The **plates**, of which the first and last are inscribed on one side only, are seven in number, each measuring from $7\frac{3}{8}$ " to $7\frac{1}{2}$ " by from $3\frac{1}{2}$ " to $3\frac{3}{8}$ ". They are quite smooth, the edges of them having been neither fashioned thicker, nor raised into rims. A few of the letters on the first and last plates have been damaged by rust; but the rest of the inscription is in a state of excellent preservation. The plates are fairly thick and substantial; and the letters, which are not very deep, do not shew through on the reverse sides at all. The engraving is good, but, as usual, the interiors of the letters shew here and there marks of the working of the engraver's tool.—Towards the top of each plate, there is a hole for a **ring** to connect them. The ring is circular, about $\frac{1}{4}$ " thick and $3\frac{3}{8}$ " in diameter. It was not soldered into the socket of a seal; but the ends of it were flattened off, as if to overlap and fasten with a pin or bolt; there is, however, no hole in them to shew that they were ever actually secured in this way. The **seal**⁴ is a flat disc of copper, rising slightly towards the centre, about $\frac{1}{4}$ " thick and $2\frac{3}{8}$ " in diameter. To the centre of the back of it, there is soldered a small ring, by which it slides on the larger ring mentioned above. Across the surface of the seal, there is the **legend**, in four lines, of

¹ No. 9 of the separate pamphlets of the Archæological Survey of Western India

² The 'Chamuck' of the Indian Atlas, Sheet No. 54. Lat. $21^{\circ} 12' N.$; Long $77^{\circ} 31' E.$ —In *Notes on the Bauddha Rock-Temples of Ajanta*, p. 54, the plates are said to have been obtained from Sâgar in the Central Provinces. And in *Ind. Ant.* Vol. XII. p. 234, they are called the Ilichpur grant. But in *Archæol. Surv. Ind.* Vol. IV. p. 116, it is stated explicitly that they were found in a ploughed field at Chammak.

³ The 'Ellichpur' of maps, &c.

⁴ See Plate xxxiiiC.

which the text and translation are given below.—The **weight** of the seven plates is about 6 lbs. 14 oz., and of the two rings and the seal, about 14½ oz.; total 7 lbs. 12½ oz.—The **average size** of the letters is about 1½". The **characters** belong to the southern class of alphabets, and are of the 'box-headed' variety of the Central India alphabet, on which I have commented at page 18 f. above. But, whether intentionally or accidentally, the heads of the letters were scooped out hollow through nearly the whole of this inscription; and the true box-shaped tops are discernible in only a few places; e.g. in lines 58 and 59. The characters include forms of the **numerical symbols** for 8 and 10, in line 60, and for 8,000, in line 19.—The **language** is Sanskrit. The legend on the seal is in verse; but the inscription itself, except for the benedictive and imprecatory verses in lines 36 to 39, is in prose throughout.—In respect of **orthography**, we have to notice (1) the use of the *upadhānīya*, in *rājñah-pravara*, line c; *pāñh-prasāda*, line 13; *sambhōh-prasāda*, line 16; and *rakshitavyah-pari*, line 32; but not in *kāliyah putra*, line 30; (2) the occasional doubling of *k* and *d*, in conjunction with a following *r*, e.g. in *kkrama*, line b; *kkriyābhīs*, line 31; and *ddrōha*, line 4; (3) the doubling of *th* and *dh*, in conjunction with a following *y*, in *bhāgīratthy-amala*, line 6, and *sarvoddhyaksha*, line 21; and (4) the doubling of *v* after the *anusvāra*, in *samvatsarē*, line 60.

The inscription is one of the **Mahārāja Pravarasēna II.**, of the **Vākātaka** tribe or dynasty; and the charter recorded in it, is issued from the town of **Pravarapura**. It is dated, both in words and in numerical symbols, in the eighteenth year (of his government), on the thirteenth lunar day of the bright fortnight of the month Jyēsthā (May-June). It is a non-sectarian inscription; the object of it being simply to record the grant, by **Pravarasēna II.**, to a thousand Brāhman, of the village of **Charmānika**, i.e. the modern **Chammak** itself, in the **Bhōjakata** kingdom.

TEXT.¹

The Seal.

- a Vākātaka²-lalāmasya
b kkrama-prāpta-nripa-śriyah
c rājñah-Pravarasēnasya
d śāsanañ ripu-śāsanaṃ [11*]

First Plate.

- 1 Driṣṭarñ³ [11*] Svasti Pravarapurād-agnishōm-āptōryām-ōkthya-
shōḍaśy-ātīrātra.⁴
2 vājapēya - bṛihaspatīsa - sādyaskra - chaturaśvamēdha - yājinaḥ
3 Rvi(wi)shñ[u]v[ri]ddha-sagōtrasya samrād Vākātakanāñ⁵
mahārāja-śri(sri)-Pravarasēnasya
4 sūnōh sūnōh atyanta-[S]vāmi-Mahābhairava-bhaktasya a[m*]sa-
bhāra-santi(nni)vēśi-
5 ta-Śiva-ling-[ō]dvahana-Śiva-suparītushta-samutpādi[ta]-rājava[m*]śā-

¹ From the original plates.

² Metre, Ślōka (Anuṣṭubh).

³ See page 140 below, note 2.

⁴ See page 241 below, note 6.

⁵ Read *samrād-Vākājakudmī*, in composition.—The final *d* of *samrād* (or possibly *f* of *samrād*), rather small and faint, stands below the line, and just above the *mi* of *sūmi* in the next line.

Second Plate; First Side.

- 6 nām-parākram-ādhigata-Bhāgratthy-ā(a)mala-jala-mūrdh(n) - ābhi-
shiktānān-daś-ā-
- 7 śvamedh-āvabhṛitha-snānānām-Bhārasivānāri mahārāja-śrī-Bhava-
nāga-dau-
- 8 hitrasya Gautami'putrasya putrasya Vākātakanām mahā-
rāja-śrī-Rudrasē-
- 9 nasya sūnōr-atyatna(nta)māhēśvarasya saty-ārjjava-kārunya-
śauryya-vikrama-na-
- 10 ya - vinaya - mahātmy - ādhima(ka)tva - hā³(pā)tr - āgata - bhakti(kti)tva-
dharmmav(i)jayt(yi)tva-

Second Plate; Second Side.

- 11 manōnairmmā(rmma)ly-ādi-guṇais=samupētasya varsha-śatam-abhi-
varddhamāna-kōśa-
- 12 daṇḍasādhana-sannā(ntā)na-putra-pautriṇaḥ Yudhishṭhira-vṛitnē(tē)r-
Vākātakā-
- 13 nām mahārāja-śrī-Prithivishēnasya sūnōr-bbhagavataś=Chakra
pāṇēḥ-prasā-
- 14 d-ōpārjji²ta-śrī-samudayasya Vākātakanām mahārāja-śrī-Rudra-
sēna-
- 15 [sya¹] sūnōr-mmahārājādhirāja-śrī-Dēvagupta-sutāyām Prabhāva-

Third Plate; First Side.

- 16 tiguptāyām=utpaunasya Śambhōḥ-prasāda-dhṛiti-kārttayagasya
- 17 Vākātakanām - para-namāhēśvara - mahārāja - śrī - Pravarasēnasya
vachanā[t¹]
- 18 Bhōjakata-rājyē Madhunadi(dī)-tatē Charmmānka⁴-nāma-
gr[ā¹]maḥ rājamānika-bhu(bhū)mi-
- 19 sahasrair=ashtābhiḥ⁵ 8000 Śatr[u¹]ghnarāja-putra-Koṇḍarāja-
vijñāptyā nānā-gō-
- 20 tra-charaṇēbhyō brāhmaṇēbhyaḥ sahasrāya dattaḥ [II¹]

Third Plate; Second Side.

- 21 Yatō-smat-santakā[h¹] sarvāddhyaksh-ādhīyōga-niyuktā ājñā-
sañch[ā¹]ri-kulaputr-ādhikṛitā

¹ The form of superscript *f* that we have here, is somewhat different from that which occurs throughout the rest of this inscription.—In line 7 of the next inscription, page 245 below, this syllable has the short vowel *i*, as is optionally allowable.

² The engraver first formed *hi*, and then partially cancelled the *i*. Probably the man who wrote the copy from which he engraved, had hesitated between *hit-āgata* and *pōtr-āgata*.—The form of superscript *i* used here, was not of general use till somewhat later times. But, in the present inscription, it occurs again distinctly twice in *ti*, in line 16, in *si*, line 21, and twice in *vi*, line 23; and in other places; and, in many other instances throughout the inscription, there is a tendency to form it in the same way.

³ The engraver first formed *ji*, and then corrected it into *rjji*.

⁴ The engraver first formed *śak*, and then partially cancelled the *ś*.

⁵ We have to supply *parimitāḥ*, or some similar word, after this instrumental case.

- 22 bhatach(s)-chhatrás-cha viśruta-pūrvvay=ājñay-ājñāpayitavyā Viditam-
astu vō yath=é-
- 23 h-āsmākam=manō¹ dharmm-āyur-bva(bba)la-vijay-aivaryya-vividdhayē
ih-āmutra-hit-ā-
- 24 rtham=ātm-ānugrahāya vaijaikē² dharmmasthānē apūrvva-dat[t*]yā
udaka-purvva-
- 25 m=atisrishtah [I] ath=āsy-ōchitām pūrvva-rāj-ānumatām chātur-
vvaidya-grāma-ma-
- 26 ryyādān(m)=vitarāmas=tad=yathā a-karādāy³ a-bhata-chhchha-
(chchhā)tra-prāvēśya[h*]

Fourth Plate, First Side.

- 27 a-pārapara-gō-balivardda[h*] a-pushpa-kshira-satdō(ndō)ha[h*] a-
ch[ā*]rā-
- 28 sana-charmm-āngāra[h*] a-lavana-kinna-kkrēṇi-khēnaka[h*] sarvva-
vē(vi)shti-pari-
- 29 hāra-parhrītah⁴ sa-nidhis-s-ōpanidhi sa-klī(klī)pt-ōpaklī(klī)ptah
- 30 ā-chandr-āditya-kālyāh putra-pautr-[ā*]nugamakah [I*] bhū[m*]jatām
na kē-
- 31 nachī[d*]=vyāghātam(h) karttavayas=sarvva-kkriyābhīs-sa[m*]rakshi-
tavyah=par[t*]varddhayi-
- 32 tav[y*]aś=cha [I*] yaś=ch=āyam⁵ śāsanam=a-ganayamānō(nah)
svalp[ā*]m=api [pa*]rībhāhām⁶

Fourth Plate, Second Side

- 33 n(n)=kuryyāt=kārayitā vā tasya brāhmanair=vvēditasya sa-
va(da)nda-nigrahām kuryyā-
- 34 ma II Asmi[m*]ś=cha dharmm-āvara-karapē atī(tī)t-ānēka-rāja-
datna(tta)-sañchitna(nta)na-
- 35 paripālanam krita-puny-ānukirttana-parihār-ārttham na
kirttayāmah [II*]
- 36 Vyāsa-gītau ch=ātra ślōkau pra'māni(nī)karttavayau [I*] Svā⁷-
datnā(ttā)m=para-datnā(ttā)m
- 37 vvā(vā) yō harēta vasundharām gavām śata-sahasrasya
hantu-

Fifth Plate; First Side

- 38 r-harati dushkritam [II*] Shashtim varsha-sahasrāni(nī) svarggē
mōdati bhū-

¹ Read *yath=aiśha āsmānō*.

² Read *vaijayikē*.

³ The engraver first formed *yai*, and then corrected it into *yī*

⁴ Read *parhrītah*.

⁵ Read *yai=ch=ādam* The *cha* of *scha* closed up again, almost entirely, after the engraving

⁶ After this word, *kuryyē* was engraved and then cancelled.—The *anusvāra* is not required, since, in the next line, we have *m*, by mistake for *ś*, connecting *parībhāhām* in *samāhi* with *kuryyē*.

⁷ The engraver first formed *ā=pra*, and then cancelled the *ā*.

⁸ Metre, Ślōka (Anuśtubh); and in the following verse.

- 39 mi-dah áchchhétta ch-anumantá cha' tány-éva naraké vaséd-
iti [11*] Śśa(śá)sana-
40 sthitiś=ch-éyah bráhmañair-Íśvaraiś=ch-ánupálaniyá tad-yathá
rájñáti sa-
41 ptángé rájyé a-ddróha-pravrintá(ttá)nám [a*]-brahmaghna-chaura²-
páradárika-rájá-
42 pathyakári-prabhñiti(tl)nám [a*]-sañgr[á*]ma-kurvvatám anya-
gráméshv=an-a- II

Fifth Plate; Second Side.

- 43 par[á*]ddhánám³ á-chandr-áditya-kályah [1*] ató-nyathá kurvvatám-
anumódatám vá⁴
44 rájñah bhu(bhū)mi-chchhédám kurvvatáh a-stéyam-iti [11*]
Prá(pra)tigrá'ñipás=ch-átra
45 vára-niyuktáh [1*] Śátyáyanah Gañáryyah Vátsya-Dévaryyah
Bháradvája-
46 Kumárasarmmáryya[h*] Páráśaryya-Guhasarmmá Káśyapa-
Dév[á*]ryyah Mahéśva-áryya[ḥ*]
47 Mátráryya[h*] Kauñḍinya-Rudráryya[h*] Sómáryya[h*]
Harísarmmáryya[h*]

Sixth Plate; First Side.

- 48 Bháradvája-Kumárasa[r]mm[á]ryya[h*] Kauñḍinya(nya)-Mátri(tri)-
sarmmá Varásarmm[á*]
49 Góṇḍasarmmá Nágaśarmmá Bháradvája[*]-Śantísarmmá Rudra-
sarmmá Vátsyah
50 Bhójakad[é*]váryya[h*] Maghasarmmá Dévasarmmá Bháradvája-
Mókshaśarmm[á*]
51 [Ná]gaśarmmá Révatiśarmmá Dharmmáryya[h*] Bháradvája-
Sarmmáryya[h*]
52 Nandanáryya[h*] Múlaśarmmá † Íśvaraśarmmá † Varásarmmá

Sixth Plate; Second Side

- 53 Chánsya²-Skandáryya[h*] Bháradvája-Bappáryya[h*] Dharm-
máryya[h*] Átréya-Skandáryya[h*]
54 Gautama-Sómásarmmáryya[h*] Bha[r*]tríśarimá Rudrasa[rmmá*]-
ryya[h*] Magháryya[h*] Mátri-
55 śarmmáryya[h*] Íśvaraśarmmáryya[h*] Gautama-sagótra-Mátri-
śarmmá-
56 ryya[h*] Kauñḍinya(nya)-Dévasarmmáryya[h*] Varásarmmáryya[h*]
Róháryya[h*]

¹ The engraver first formed *chcha* or *chchha*, and then cancelled the lower *ch*, or the *chha*.

² The engraver first formed *rd*, and then cancelled the *d*.

³ Read *an-apar[á*]ddhánám*, omitting the mark of punctuation.

⁴ The engraver first formed *vrd*, and then cancelled the lower *v*.

⁵ The engraver first formed *gvá*, and then corrected it into *grá*.

⁶ This *ryya* stands at the end of the line, below the *rd* of *mahéśvaré*; but this is evidently the place to which it properly belongs.

⁷ Read *vátsya*.

Seventh Plate

- 57 Gautama-sagôtra-Svâmidê[vâ*]ryya[h*] Rêvatîsarmmâryya[h*]
 58 Jyêshthasarmmâryya[h*] Śândilya-Kumârasarmmâryya[h*] Svâtî-
 sarmmâ-
 59 ryya[h*] Ś[â*]tyâyaṇa(na)-Kāṇḍ[â*]ryya-prabhritayah [H*] Sênâpatau
 60 Chitravarmmani samvatsarê=shtëadaśa[mê*] 10 8 Jyêshtha-
 mâsa-śukla-
 61 paksha-trayôdaśyâ[m*] śâsanam likhitam=itih' [H*]

TRANSLATION.

The Seal.

A charter of king **Pravarasêna**, the ornament of the **Vâkâtakas**, who has attained royal dignity by inheritance, (25) a charter for (the observance of even his) enemies!

The Plates.

Sight has been attained! Hail! From the town of **Pravarapura**;—(Line 17.)—At the command of the most devout worshipper of (the god) Mahêśvara, the **Mahârāja** of the **Vâkâtakas**, the illustrious **Pravarasêna** (II.),¹ who was begotten on **Prabhâvatiguptâ**, the daughter of the **Mahârâjadhîrāja**, the glorious **Dêvagupta**; who, through possessing the favour of (the god) Śarîbhu, is (as virtuous as) one belonging to the **Krita** age;—

(Line 13.)—(And) who is the son of the **Mahârāja** of the **Vâkâtakas**, the illustrious **Rudrasêna** (II.), who acquired an abundance of good fortune through the favour of the divine (god) **Chakrapâni**;—






(L. 9.)—Who² was the son of the **Mahârāja** of the **Vâkâtakas**, the illustrious **Prithivishêna**, who was an excessively devout worshipper of (the god) Mahêśvara; who was endowed with an excess of truthfulness, straightforwardness, tenderness, heroism, prowess, political wisdom, modesty, and high-mindedness, and with devotion to worthy people and guests, and with the condition of being victorious through religion, and with

¹ Read *iti*.—Two forms of the double mark of punctuation are used in this inscription; the upright form, after *anyagrâmêshv-ana* in line 42^a and the horizontal form, after *kuryyama* in line 33-34. The latter rather resembles the *visarga*. And thus the engraver came to form a *visarga*, instead of a double mark of punctuation, after the word *iti*.

² As regards the Text and my Translation here, Dr. Bühler, while admitting that the opening *aksharas* looked like *drishtam* or *driptom*, interpreted them as *ôṃ ôṃ*.—Dr. Bhagwanlal Indraji read them as *drishtam*.—The mark over the *drî* is not an *anusvâra*, but only a rust-mark. And the reading is as indisputably *drishtam* here, as it is *drishtam* at the commencement of the next inscription.—The same word occurs, if possible still more clearly, in the margin of the first plate of the Goa grant of Satyâśraya-Dhruvarâjya-Indravarma (Four. Bo. Br. R. As. Soc. Vol. X. p. 348 ff.), where Mr. K. T. Telang (*id.* p. 360, note) suggested that it might mean 'sanctioned.' But it is of course the remnant of some such expression as *drishtam bhagavatâ*, 'sight (*i.e.* clearness of perception in religious matters; a thorough insight into the nature of the universe and everything connected with it) has been attained by the Divine One,' see my remarks on *siddham*, page 25 above, note 4.

³ The context is "the village named Charnâka" &c., in line 18 ff. below.

⁴ *i.e.* Rudrasêna II.



W. BRIGGS, PHOTO-LITH.

— 22 —

PLATE XXVII

purity of mind, and with other meritorious qualities; who belonged to an uninterrupted succession of sons and sons' sons, whose treasure and means of government had been accumulating for a hundred years; who behaved like Yudhishtira;—

(L. 4.)—Who¹ was the son of the *Mahārāja* of the *Vākātakas*, the illustrious *Rudrasēna* (I.), who was an excessively devout devotee of (the god) Svāmi-Mahābhairava; who was the daughter's son of the illustrious *Bhavanāga*, the *Mahārāja* of the *Bhārasīvas*, whose royal line owed its origin to the great satisfaction of (the god) Śiva, (caused) by (their) carrying a *śūga* of Śiva placed as a load upon (their) shoulders, (and) who were besprinkled on the forehead with the pure water of (the river) Bhāgrathī that had been obtained by (their) valour, (and) who performed ablutions after the celebration of ten *atvamēdha*-sacrifices;—who² was the son of *Gautamiputra*;³—

(L. 1.)—(And) who⁴ was the son of the son of the *Mahārāja* of the sovereign *Vākātakas*, the illustrious *Pravarasēna* (I.), who celebrated the *agnishōma*,⁵ *aptōryama*, *ukthya*, *śhōdāsin*, *atirātra*,⁶ *vājapya*, *brihaspatisava*,⁷ and *sādayaskra*⁸ sacrifices and four *atvamēdha*-sacrifices, (and) was of the *Vishṇuviddha gōtra*:—

(L. 18.)—The village named *Charmāka*, on the bank of the river *Madhunadi*, in the *Bhōjakata* kingdom, (measured) by eight thousand *bhūmīs*,⁹ (or in figures) 8000, according to the royal measure, is, at the request of *Koṇḍarāja*, the son of *Śatrughnarāja*, given to one thousand Brāhmins of various *gōtras* and *charaṇas*.

(L. 21.)—Wherefore Our¹⁰ obedient and high-born¹¹ officers, employed in the office of general superintendents,¹² (and *Our*) regular soldiers and umbrella-bearers, should be (thus) directed with a command preceded by (the words) 'O illustrious one':—“Be it known to you, that, in order to increase *Our* religion and life and strength and victory and dominion, (and) for the sake of (*Our*) welfare in this world and in the next, (and

¹ i.e. Prithivishēpa.

² i.e. Rudrasēna I.

³ See page 237 above, note 1.

⁴ i.e. Rudrasēna I.

⁵ The *agnishōma*, lit. 'praise of the god Agni, or fire,' was a protracted sacrifice, extending over five days in spring, and forming one of the parts of the *Jyōtishōma*, which was one of the principal sacrifices connected with the sacred *Sōma* plant and juice. Other parts of the *Jyōtishōma* sacrifice were the *aptōryama*, *ukthya*, *śhōdāsin*, *atirātra*, and *vājapya* ceremonies, which are mentioned in the text here; and the seventh, and last, part being the *atyagnishōma*, which is not here mentioned.

⁶ Monier Williams, in his Sanskrit Dictionary, gives only the form *atirātra*, with the short vowel *a* in the first syllable; so also Max Müller in his *Sanskrit Literature*, p. 177, note. But the Text here distinctly gives the long vowel *ā*. And, though in line 1 of the next inscription, page 245 below, the vowel is rather imperfectly formed, yet a comparison with *bhāgrathy-śmala*, in line 5 of the same, shews that there also the vowel *ā* is intended.

⁷ The *brihaspatisava* was another sacrifice, lasting a day, apparently connected with *Brihaspati*, the priest and preceptor of the gods.

⁸ The *sādayasra* was another sacrifice, of which I have not been able to find any explanation in the books of reference available.

⁹ *bhūmī*, lit. 'land, the earth,' is evidently used here as some technical land-measure, the value of which is not known.

¹⁰ *asmat-santaha*, lit. 'belonging to Us,' see Childers' Pāli Dictionary, a. v. *santaha*.

¹¹ *kulaputra*.

¹² *Sarvādhyaksha*.

generally) for Our benefit, this (*village*) is granted, in (*Our*) victorious office of justice, as a grant not previously made, with libations of water.

(L. 25.)—“Now We grant the fixed usage, such as befits this (*village*), (*and*) such as has been approved of by former kings, of a village which belongs to a community of *Chaturvādin*; namely, it is not to pay taxes; it is not to be entered by the regular troops or by the umbrella-bearers; it does not carry with it (*the right to*) cows and bulls in succession of production,¹ or to the abundance of flowers and milk, or to the pasturage, hides, and charcoal, or to the mines for the purchase of salt in a moist state; it is entirely free from (*all obligation of*) forced labour; it carries with it the hidden treasures and deposits, and the *klīpta* and *upaklīpta*;² it is (*to be enjoyed*) for the same time with the moon and the sun; (*and*) it is to follow (*the succession of*) sons and sons' sons. No hindrance should be caused by any one to those who enjoy it. It should be protected and increased by all (*possible*) means. And whosoever, disregarding this charter, shall give, or cause to be given, even slight vexation, We will inflict on him punishment, together with a fine, when he is denounced by the Brāhman̄s.”

(L. 34.)—And in this document, which has at least (*the merit of*) religion,³—in order to avoid boasting of (*other*) meritorious actions performed (*by Us*),—We do not recite (*Our*) care and protection of grants made by various kings who are dead and gone.

(L. 36.)—And two verses, sung by Vyāsa, are to be cited as an authority on this point:—Whosoever confiscates land that has been given, whether by himself, or by another, he incurs the guilt of the slayer of a hundred thousand cows! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell!

(L. 39.)—And this condition of the charter should be maintained by the Brāhman̄s and by (*future*) lords; namely (*the enjoyment of this grant is to belong to the Brāhman̄s*) for the same time with the moon and the sun, provided that they commit no treason against the kingdom, consisting of seven constituent parts,⁴ of (*successive*) kings; that they are not slayers of Brāhman̄s, and are not thieves, adulterers, poisoners of kings, &c.; that they do not wage war; (*and*) that they do no wrong to other villages. But, if they act otherwise, or assent (*to such acts*), the king will commit no theft in taking the land away.

(L. 44.)—And the recipients, appointed for the occasion in this matter, (*are*):—Gaṇārya, of the Śātyāyana (*gōtra*). Dēvārya, of the Vātsya (*gōtra*). Kumāraśarmārya, of the Bhāradvāja (*gōtra*). Guhaśarman, of the Pārāśarya (*gōtra*). Dēvārya, of the

¹ The interpretation here is not quite certain. But this and the next three expressions seem to reserve certain rights for the villagers against the grantees.

² These are technical fiscal expressions, the meaning of which is not known.

³ This is in accordance with Dr. Bühler's rendering (*Archzol. Surv. Ind.* Vol. IV. p. 123, note 8).—As regards *karana* in the sense of 'a document,' it is borne out by *Karanika*, which is of constant occurrence in evidently the meaning of 'one who has to do with documents, a writer, a scribe,' e.g. in the passage from the 'Dewal' inscription of Vikrama-Samvat 1049, referred to at page 201 above.—Dr. Bhagwanlal Indraji proposed to correct the text into *dharman-dara*, probably meaning "in this act of respect for religion."

⁴ The *saptāṅga*, or 'aggregate of the seven constituent elements (of a kingdom),' consists of the king, and his ministers, ally, territory, fortress, army, and treasury.

Kāśyapa (*gōtra*); Mahēśvarārya, (*and*) Mātrārya. Rudrārya, of the Kauṇḍinya (*gōtra*); (*and*) Sōmārya, (*and*) Hariśarmārya. Kumāraśarmārya, of the Bhāradvāja (*gōtra*). Mātrīśarman, of the Kauṇḍinya (*gōtra*); (*and*) Varaśarman, Gōṇḍaśarman, (*and*) Nāgaśarman. Śāntīśarman, of the Bhāradvāja (*gōtra*); (*and*) Rudraśarman. Bhōjakadēvārya, of the Vātsya (*gōtra*); (*and*) Maghaśarman, (*and*) Dēvaśarman. Mōkshaśarman, of the Bhāradvāja (*gōtra*); (*and*) Nāgaśarman, Rēvatīśarman, (*and*) Dharmārya. Śarmārya, of the Bhāradvāja (*gōtra*); (*and*) Nandanārya, Mōlaśarman, Īśvaraśarman, (*and*) Varaśarman. Skandārya, of the Vātsya (*gōtra*). Bappārya, of the Bhāradvāja (*gōtra*); (*and*) Dharmārya. Skandārya, of the Ātrēya (*gōtra*). Sōmaśarmārya, of the Gautama (*gōtra*); (*and*) Bhartrīśarman, Rudraśarmārya, Maghārya, Mātrīśarmārya, (*and*) Īśvaraśarmārya. Mātrīśarmārya, of the Gautama *gōtra*. Dēvaśarmārya, of the Kauṇḍinya (*gōtra*); (*and*) Varaśarmārya, (*and*) Rōhārya. Svāmīdēvārya, of the Gautama *gōtra*; (*and*) Rēvatīśarmārya, (*and*) Jyēshṭhaśarmārya. Kumāraśarmārya, of the Śāṇḍilya (*gōtra*); (*and*) Svātīśarmārya. (*And*) Kāṇḍārya, of the Śātyāyana (*gōtra*); and so forth.

(L. 59).—(This) charter has been written, while **Chitravarman** is the *Sēndapati*, in the eighteenth year, (or in figures) 10 (*and*) 8, on the thirteenth lunar day of the bright fortnight of the month Jyēshṭha.

No. 56; PLATE XXXV.

SIWANI COPPER-PLATE INSCRIPTION OF THE MAHARAJA PRAVARASENA II.

THIS inscription was first brought to notice in 1836, in the *Four. Beng. As. Soc.* Vol. V. p. 726 ff., where, the original plates having been forwarded by Mr. D. M. McLeod, Mr. James Prinsep published his reading of the text, and a translation of it, accompanied by a lithograph (*id.* Plate xxxiii. Nos. 1 and 2).

The inscription is on some copper-plates which were obtained by me for examination from the possession of a Zamīndār or land-holder named Hazari Gond Malguzar, living at the village of Pipḍarāl, in the Siwan Tahsil or Sub-Division of the Siwan-Chhapārā District¹ in the Central Provinces. I have no information as to where the plates were originally found; and, as they have always been known as the **Siwani** grant, it seems desirable to continue that name; though, of course, in the absence of any local identification of the places mentioned in the inscription, this name indicates only in a general way the part of the country to which the grant belongs.

The **plates**, of which the first and last are inscribed on one side only, are five in number, each measuring about $8\frac{3}{8}$ " by $4\frac{1}{8}$ " at the ends and somewhat less in the middle. They are quite smooth, the edges of them having been neither fashioned thicker, nor raised into rims. The inscription is in a state of perfect preservation throughout. The plates are rather thin, and the letters shew through on the reverse sides, so clearly that many of them can be read there; in a very exceptional manner, this is noticeable even on the intermediate plates; though, of course, not to such an extent as to make the letters of one side of a plate legible on the other in the lithograph. The engraving is very

¹ The chief town is Siwan; the 'Seoni and Seonce' of maps, &c. Indian Atlas, Sheet No. 79. Lat. 23° 5' N.; Long. 79° 35' E.

good; but, as usual, the interiors of the letters shew in a few places marks of the working of the engraver's tool.—Towards the proper right end of each plate, there is a hole for a ring to connect them. The ring is circular, about $\frac{1}{2}$ " thick and $3\frac{1}{2}$ " in diameter. The ends of it were flattened off, so as to overlap, and were fastened with a pin or bolt; they were still secured in this manner, when the grant came into my hands. The seal¹ is a thin flat disc of copper, about $3\frac{1}{8}$ " in diameter. A bolt in the centre of it secures it to a thin band of copper, about $\frac{1}{8}$ " broad and $3\frac{1}{2}$ " in circumference, by which it slides on the ring mentioned above. Across the surface of the seal, there is the legend, in four lines, of which the text and translation are given below.—The weight of the five plates is about 3 lbs. $4\frac{1}{2}$ oz., and of the ring and seal, $5\frac{1}{2}$ oz.; total 3 lbs. $9\frac{1}{2}$ oz.—The average size of the letters is about $\frac{1}{4}$ "; except on the seal and on the last plate, where they are rather larger. The characters belong to the southern class of alphabets, and give a very perfect and beautiful illustration of the 'box-headed' variety of the Central India alphabet, on which I have commented at page 18 f. above. They include two forms of *b*; one, the customary form of this alphabet, occurs in *brikaspati*, line 1, and in other places in this and the preceding inscription; the other, a square and more antique form, occurs only in *bennd*, line 17; in the lower *b* in *Ayur-bbala*, line 26; and in *bāppa*, line 36.—The language is Sanskrit. The legend on the seal is in verse; but the inscription itself except for the benedictive and imprecatory verses in lines 39 to 42, is in prose throughout.—In respect of orthography, we have to notice (1) the use of the *upa-dhmāntya*, once, in *rājñah-pravara*, line c; (2) the use of the dental *n*, instead of the *anusvāra*, before *ś* and *s*, in *vansa*, lines 5 and 17, and *ansa*, line 4; (3) the doubling of *th* and *dh*, in conjunction with a following *y*, in *uttthya*, line 1, and *bhdgratthy-amala*, line 5, and in *sarvuddhyaksha*, line 24; (4) the doubling of *dh*, in conjunction with a following *v*, in *addhvaryavē*, line 19-20; and (5) the doubling of *v* after the *anusvāra* (which, however, was omitted in the actual engraving), in *samvvatsarē*, line 18.

The inscription is another record of the *Mahārāja Pravarasēna II.*, of the *Vākātaka* tribe or dynasty. The place whence the charter was issued, is not recorded. It is dated, in words, in the eighteenth year of his government, on the twelfth lunar day of the bright fortnight of the month Phālguna (February-March). It is a non-sectarian inscription; the object of it being simply to record the grant to a Brāhman, by *Pravarasēna II.*, of the village of *Brahmapūraka*, in the *Bennākārpara bhāga*.²

Of the villages mentioned in defining the position and boundaries of the village that was granted, *Kollapūraka* is possibly the modern 'Kolapoor' of the map,³ twenty-one miles south of Ilchpur.

¹ See Plate xxxiiiD.

² *bhāga*, *lit.* 'a part, share, division, allotment,' is a technical territorial term, of rare occurrence, the exact purport of which is not apparent.

³ Indian Atlas, Sheet No. 54. Lat. $20^{\circ} 56'$ N.; Long. $77^{\circ} 34'$ E.—The same name, in a slightly different form, occurs in the Kollāpura of the southern inscriptions (e.g. line 48 of the Tērdāli inscription; *Ind. Ant.* Vol. XIV. p. 18; see also *id.* p. 23, note 22), as the ancient name of the modern Kōllāpur, the chief town of the Kōllāpur State in the Bombay Presidency.

TEXT.¹*The Seal.*

- a **Vākātaka**²-lalāmasya
 b krama-prāpta-nṛpa-śriyah
 c rājñah-Pravarasēnasya
 d śāsana[rh³] ripu-śāsanam [ll⁴]

First Plate.

- 1 Drishtam Siddham⁵ || Agniṣṭōm-āptōryām-ōktthya-shōdaśy-
 ātirātra⁶-vājayē(pē)ya-brihaspatisava-
 2 sādyaaskra-va(cha)turaśvamēdha-yājinaḥ **Vishṇuvriddha**-sagōtrasya
 sashraṭ **Vākātakānā-**
 3 **m⁷**-mahārāja-śri-Pravarasēnasya sūnōḥ sūnōḥ atyanta-
 Svāmi-Mahā-
 4 bhairava-bhaktasya ansa-bhāra-sanniv[ē⁸]śita-Śiva-līng-ōdvahana-Śiva-
 suparitusṣṭa-
 5 samutpādita-rājavanśānām parākram-ādhighata-Bhāgratthy-ā(a)mala-
 jala-mūrdh-ābhi-

Second Plate; First Side.

- 6 shiktānām daś-āśvamēdh-āvabhṛitha-snānānam-**Bhārasivānām**-mahā-
 rāja-śri-**Bhavanā-**
 7 ga-dauhitrasya l⁹ **Gautami¹⁰putrasya** putrasya | **Vākātakānām-**
 mahārāja-śri-
 8 **Rudrasēnasya** sūnōḥ atyantamāhēsvarasya | satv-ārjjava-
 kārunya-śau-
 9 ryya - vikrama - naya - vinaya - mātmy¹¹-[ā¹²]dhima(ka)tva-pātr-[ā¹³]gata-
 bhaktitva-dharmmavijayi-
 10 tva-manōnairmmaly-ādi-guṇa-samuditasya | varsha-śatam-abhivarddha-
 māna-kōśa-
 11 daṇḍasādhana-santāna-putra-pautripaḥ Yudhishṭhira-vṛittēr-**Vvākāta-**
kānām-mahārāja-

Second Plate; Second Side.

- 12 śri-Prithivishēnasya sūnō[h¹⁴] bhagavataś-Chakrapānēḥ prasād-
 ōpārjita-
 13 śri-samudayasya | **Vākātakānām**-mahārāja-śri(śri)-**Rudrasēnasya**
 sūnōḥ

¹ From the original plates.² Metre, Ślōka (Anuṣṭubh)³ In the original, this word, *siddham*, stands between the lines, below *drishtam*.—As regards *drishtam*, see page 240 above, note 2.⁴ See page 241 above, note 6.⁵ Read *samrūd-vākātakānām*.⁶ This and the following marks of punctuation, down to line 23 are unnecessary.⁷ See page 237 above, note 1.⁸ In this compound, the *t* is formed very anomalously; but the character cannot stand for anything else.

- 14 pūrvva-rāj-ānuvṛitta-mārgg-ānusaṛiṇaḥ sunaya-bala-parākkram-ō-
 15 chchhinna-sarvva-dvishah mahārājādhirāja-śrī-Dēvagupta-sutāyām-
Prabhāvati-
 16 guptāyām-utpannasya Śambhō[h*] prasāda-dhṛiti-kārttayugasya¹
Vākātaka-

Third Plate; First Side.

- 17 vanā-ālankāra-bhūtasya | mahārāja-śrī-Pravarasēnasya vachanāt
Bennā-
 18 kārppara-bhāgē pravarddhamāna-rājya-sa[m*]jvatsarē | ashtā-
 daśamē | Phālgū-
 19 na(na)-śukla-dvādaśyām Maudgalya-sagōtrāya | Taittiri(ri)yāy-
 āddhvaryya-
 20 vē Dēvaśarm-āchāryyāy-ōdaka-pūrvvam sa-koraṭaḥ sa-
 pañchāśatkaḥ
 21 **Brahmapūrakān-**nāma grāmō-tisṛishṭaḥ **Vaṭapūrakasy-**
 ōttarēna | Kīṇihikhē-
 22 **ṭakasy-**āparēna | **Pavarajjavāṭakasya** dakṣhiṇēta(na) |
Kollapūrakasya

Third Plate; Second Side.

- 23 purvveṇa | sva-simā-par[i*]chchh[ē*]dēna **Karāñjavi(Pchi)raka-**
 taṭē I(II) Atr-āsmat-santakāḥ
 24 sarvāddhyakṣa-n[i*]yōga-n[i*]yuktāḥ **ājñāsañchāri-**kulaputr-ādhi-
 kṛitāḥ bhaṭāḥ-
 25 ś²-chhātrās=cha viśruta-pūrvvayā **ājñayā** **ājñāpayitavyāḥ** [I*]
 Vidita-
 26 m=astu ta(va)ḥ yath-aishō-smābhiḥ **ātmanō** dharmm-āyur-
 bbala-vijay-aśvarya-vi³vri[d*]dhayē
 27 ih-[ā*]mutra-hit-ārttham-ātva(tm)-ānugrahāya I⁴ vaijayikē dharmma-
 sthānē⁵ | a-bhaṭa-

Fourth Plate; First Side.

- 28 chchh[ā*]tra-prāvēśyaḥ a-pārampara-gō-balivarddaḥ a-pushpa-
 kshīra-sandōha[h*] a-chā-
 29 rāsana-charmm-āṅgarāḥ a-la⁶vāṇa-tlinva⁷-krēṇi-khanakaḥ I⁸ sarvva-
 viṣṭi-parihāra-
 30 pariḥṛitaḥ sa-nidhiḥ s-ōpanidhiḥ sa-klī(klṛi)pt-ōpakli(klṛi)ptaḥ
 ā-chandr-āditya-

¹ Read *kārttayugasya*.

² Read *bhaṭāḥ*.

³ First *vri* was engraved here, and then, it was corrected into *m*, by adding the *i* and partially erasing the *vri*.

⁴ This mark of punctuation is unnecessary.

⁵ After this word, we require *atisṛishṭaḥ*, or some similar word, as in line 24 f., of the preceding inscription, page 238 above.

⁶ First *li* was engraved, and then it was corrected into *la* by partial erasure of the *i*.

⁷ Read *klīnna*.

⁸ This mark of punctuation is unnecessary.

- 31 káli(II)yaḥ putra-pautr-ānugāmi | bhujyamāno na kēnachid-
vyāghātayi-
32 tavyaḥ sarvva-kriyābhiḥ samrakshitavyaḥ parivarddhayitavyā(vya)ś-
cha [1*] yaś=ch=āsma-
33 cn-chhāsanam=a-gaṇayamānaḥ svalpām=api paribādhān(h)-k[u*]ryyāt-
kārayita¹ vā 1²

Fourth Plate; Second Side.

- 34 tasya brāhmaṇair-āvēditasya | sadaṇḍa-nigrahaṁ kuryyāma
kārayēma v=ēti [II*]
35 Sēnāpatau Bāppadēvē likhitaṁ āchāryyēna || Asmi[m*]ś=cha
dharm-ādhipara-
36 ṇē 1³ ati(II)t-ānēka-rāja-dattā⁴-samchintana-paripālana[m*] kṛita-
pu-
37 ny-ānukirttayāmaḥ⁵ [1*] śhyantakāla-prabhaviṣṇūnam⁶ gauravād-
bhaviṣyān-vi-
38 jñāpayāmaḥ || Vyāsa-gītau ch=ātra ślōkau pramāṇi(nī)-
karttayau ||(I)

Fifth Plate.

- 39 Shashtī⁷-varsha-sahasrāṇi svarggē mōdati bhūmi-daḥ āchchhētā
ch=ānumattā(ntā)
40 cha tāny-ēva narakē vasēta(t) || Sva-dattām-paradattāv(m)-
vā yō harē-
41 ta vasundharāma(m) gavāṁ śata-sahasrasya hantur=harati
dushkrītam=iti ||

TRANSLATION.

The Seal.

A charter of king **Pravarasēna**, the ornament of the **Vākātakas**, who has attained royal dignity by inheritance, (is) a charter for (the observance of even his) enemies!

The Plates.

Sight has been attained! Perfection has been attained!—(Line 17.)—At the command of the *Mahārāja*, the illustrious **Pravarasēna (II.)**, who follows the path of imitating the behaviour of previous kings; who has extirpated all enemies by (his) excellent policy and strength and prowess; who was begotten on **Prabhāvatiguptā**, the daughter of the *Mahārājādhirāja*, the glorious **Dēvagupta**; who, through possessing the favour of (the

¹ Read *kārayitā*, as in line 33 of No. 55 above, page 238; or *kārayēma*

² This mark of punctuation is unnecessary, also that in the next line

³ This mark of punctuation is unnecessary

⁴ Read *datta*.

⁵ Read *kṛita-puny-ānukīrtana-parikhāra-ārtham* na *kṛitayāmaḥ*, as in line 35 of the preceding inscription, page 238 above.

⁶ Read *śhyantakāla-prabhaviṣṇūnam*.

⁷ Metre, Ślōka (Anuṣṭubh); and in the following verse.

god) Śambhu, is (as virtuous as) one belonging to the Kṛita age; who is the ornament of the lineage of the Vākātakas;—

(Line 12).—(And) who is the son of the Mahārāja of the Vākātakas, the illustrious Rudrasēna (II.), who acquired an abundance of good fortune through the favour of the divine (god) Chakrapāṇi;—

(L. 8).—Who was the son of the Mahārāja of the Vākātakas, the illustrious Prithivishēṇa, who was an excessively devout worshipper of (the god) Mahēśvara; who was possessed of an excess of truthfulness, straightforwardness, tenderness, heroism, prowess, political wisdom, modesty, and high-mindedness, and with devotion to worthy people and guests, and with the condition of being victorious through religion, and with purity of mind, and with other meritorious qualities; who belonged to an uninterrupted succession of sons and sons' sons, whose treasure and means of government had been accumulating for a hundred years; who behaved like Yudhishtira;—

(L. 3).—Who was the son of the Mahārāja of the Vākātakas, the illustrious Rudrasēna (I.), who was an excessively devout devotee of (the god) Svāmi-Mahābhairava, who was the daughter's son of the illustrious Bhavanāga, the Mahārāja of the Bhārasīvas, whose royal line owed its origin to the great satisfaction of (the god) Śiva. (caused) by (their) carrying a *linga* of Śiva placed as a load upon (their) shoulders, (and) who were besprinkled on the forehead with the pure water of (the river) Bhāgīrathī that had been obtained by (their) valour, (and) who performed ablutions after the celebration of ten *atvamēdha*-sacrifices;—who was the son of Gautamiputra;—

(L. 1).—(And) who was the son of the son of the Mahārāja of the sovereign Vākātakas, the illustrious Pravarasēna (I.), who celebrated the *agnishtōma*, *apṭōryāma*, *ukthya*, *śhōdasin*, *ātīrātra*, *vājapēya*, *bṛihaspatisava*, and *sādyaska* sacrifices, and four *atvamēdha*-sacrifices, (and) was of the Vishṇuvṛiddha *gōtra*;—

(L. 17).—In the Bennākārpara *bhāga*,—in the eighteenth year of the augmenting reign; on the twelfth lunar day of the bright fortnight of (the month) Phālguna,—the village named Brahmapūraka,—(which), according to the specification of its boundaries (is) on the bank of (the river) Karāñjaviraka,⁶ on the north of (the village of) Vāṭapuraka, on the west of (the village of) Kiṇihikhētaka, on the south of (the village of) Pavarajjavātaka, (and) on the east of (the village of) Kollapūraka,—is given, with libations of water, together with the *korata*⁷ and the fifty (hamlets?), to the *Adhvaryu*, the *Āchārya* Dēvaśarman, of the Maudgalya *gōtra*, (and) of the Taittirya (*śikhā*).

(L. 23).—In this matter, Our obedient and high-born officers, employed in the office of general superintendents, and (Our) regular soldiers and umbrella-bearers, should be

¹ i.e. Rudrasēna II.

² i.e. Prithivishēṇa.

³ i.e. Rudrasēna I.

⁴ See page 237 above, note 1.

⁵ i.e. Rudrasēna I.

⁶ Or, perhaps, Karāñjachiraka.

⁷ *sa-korata* is a technical fiscal term, the meaning of which is not known. But *korata* has a Drāviḍian appearance and sound, and is perhaps an old form of the Kanarese *koradu*, *koradu*, *koradu*, 'a pollard, the trunk of a lopped tree; a log, stump, short stick.'—In Marāṭhī we have, *kōrat*, 'spun silk, while still raw or unboiled;' *kōraṇṇā*, *kōraṇṇā*, *Barleria* or *Amaranth*; and *kōraḍā*, 'dry, empty, yielding no returns or profit.'

24
 26
 28

34
 36
 38

30
 32

40

(*thus*) directed with a command preceded by (*the words*) 'O illustrious one:—' Be it known to you, that, in order to increase Our own religion and life and strength and victory and dominion, (*and*) for the sake of (*Our*) welfare in this world and in the next, (*and generally*) for Our benefit, this (*village*) [is granted¹] in (*Our*) victorious office of justice.

(L. 27).—' It is not to be entered by the regular troops or by the umbrella-bearers ; it does not carry with it (*the right to*) cows and bulls in succession (*of production*), or to the abundance of flowers and milk, or to the pasturage, hides, and charcoal, or to the mmes for the purchase of salt in a moist state ; it is entirely free from all (*obligation of*) forced labour ; it carries with it the hidden treasures and deposits, and the *kripta* and *upakripta* ; it is (*to be enjoyed*) for the same time with the moon and the sun ; (*and*) it is to follow (*the succession of*) sons and sons' sons. The enjoyment of it should not be obstructed by any one. It should be protected and increased by all (*possible*) means. And whosoever, disregarding Our charter, shall give, or cause to be given, even slight vexation, We will inflict on him, or will cause to be inflicted, punishment, together with a fine, when he is denounced by the Brāhman.' "

(L. 35).—(*This charter*) has been written by the *Āchārya*, while *Bāppadēva* is the *Sādpati*.

(L. 35).—And in this subject-matter of religion,—in order to avoid boasting of (*other*) meritorious actions performed (*by Us*),—We do not recite the religious merit acquired by (*Our*) care and protection of grants made by various kings who are dead and gone. (*But*), out of respect for those who shall be pre-eminent in times to come, We make a request (*for protection of the grant*) to future (*kings*).

(L. 38).—And two verses, sung by Vyāsa, are to be taken as an authority on this point :—The giver of land enjoys happiness in heaven for sixty thousand years ; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell ! Whosoever confiscates land that has been given, whether by himself, or by another, he incurs the guilt of the slayer of a hundred thousand cows !

No. 57; PLATE XXXVIA.

PAHLADPUR STONE PILLAR INSCRIPTION.

THIS inscription was discovered by Captain T. S. Burt, of the Engineers, and was first brought to notice in 1838, in the *Four. Beng. As. Soc.* Vol. VII. p. 1055, where Mr. James Prinsep published the text of it, as read by Pandit Kamalakanta from Captain Burt's facsimile, and, with the text, his own translation.

Pahlādpur¹ is a village near the right bank of the Ganges, six miles east by south of Dhānapur, the chiet town of the Mahāch Parganā in the Zamānyā² Tahsil or Sub-Division of the Ghāzlpur District in the North-West Provinces. The inscription is on a sandstone monolith column,—about three feet in diameter ; polished and rounded for a

¹ The 'Palladpur and Puhladpoor' of maps, &c. Lat. 25° 26' N.; Long. 83° 31' E.—It should be in the Indian Atlas, Sheet No. 103, almost opposite the village of 'Puharpoor' on the other side of the river; but it is not entered there.

² The 'Zamania, Zamiana, Zamanaoa, and Zumeniah,' of maps, &c.

length of twenty-seven feet; with a rough base of nine feet; the total length being thirty-six feet,—which was found lying here, more than half buried in the ground, and was afterwards, in or about 1853, removed to Benares and set up in the grounds of the Sanskrit College there, on the north side, where it still stands. At the village of 'Lathiya,' one and a half miles east of Zamānyā, there stands another sandstone column, rather smaller in its dimensions, which is supposed to be the sister-column of the Pahlādupur pillar; but it is not inscribed.

The writing, which covers a space of about 4' 11" broad by 4" high, is about ten feet above the place where the column starts from its present pedestal; and, commencing on the north-west, it runs a little more than half-way round the column. The greater part of it is in a state of very good preservation; but a few letters in the third *pāda* of the verse, containing the name of the king, if it was recorded, have unfortunately quite peeled off, and are entirely illegible. There are several inscriptions in the so-called "shell-characters" on this column; but, apparently, no sculptures connected with the inscription now published.—The size of the letters varies from $\frac{1}{4}$ " to $\frac{3}{4}$ ". The characters belong to the northern class of alphabets. They include the so-called Indo-Scythic form of *m*, which disappeared in Northern India very soon after the commencement of the Early Gupta period; and its appearance here is sufficient to stamp this record as being at least as early as any other inscription in this volume.—The language is Sanskrit; and the inscription consists only of one verse, preceded by the word *iha*, 'here.'—The orthography presents nothing calling for remark.

The inscription is not dated, and is non-sectarian. It only commemorates the fame of a king whose name, if it was recorded, is unfortunately peeled away and lost. Mr. Prinsep suggested, from the comparison in the last *pāda* of the verse, that his name was Lōkapāla. From the rhyming ends of the four *pādas*, it seems that his name must have ended in *pāla*. But, in the third *pāda* of the verse, we have certainly the well-known name of Śīsupāla; and,—whether the name as it stands here is that of the king himself, or is that of the Purānic king Śīsupāla of Chēdi, with whom he is compared,—the inference seems to be that the name of the king, whose inscription is on the pillar, was Śīsupāla. The chief interest of the inscription, however, is in the early date of it, as shewn by the characters; and in there being the possibility that it is a record of the Pallavas in Northern India. The king is called *pārthiv-anika-pālah*. This might be rendered by simply "the protector of the armies of kings." But *pārthiva* has so much the appearance of standing as a proper name here,¹ that I think the correct translation is "the protector of the army of the Pārthivas." And, if Dr. Oldhausen's derivation of the name Pallava, through the form Pahlava, from Parthava, *i.e.* Parthian,² can be upheld, there will be no objection to considering that we have in this record a fuller and more completely Sanskritised form of the early name of this tribe.

TEXT.³

- 1 Iha [i^h] Vipula^h-vijaya-klrt[^t]ih kshatra-saddharma-pālah satata-dda(da)yita-
p[ā^o]rtthah P[ā^o]rthiv-āni(ni)ka-pālah diśi-diś[i] Śīsupāla[—]timā
[—]pau(?)lah vihita iva Vidhātrā pañchamō lō[kapā]lah [i^h]

¹ As a Hindu name, it denotes one of the families of the Kauśikas, descended through Viśvāmitra from Kauśika who was brought up among the Pahlavas (see Muir's *Sanskrit Texts*, Vol. I. p. 351 ff.).

² See Weber's *History of Indian Literature*, p. 188, note 201.

³ From the original pillar.

⁴ Metre, MĀlinī.

CORPUS INSCRIPTIONUM INDICARUM.

A.—Panidpur Pillar Inscription




SCALE 17

B.—Bijayagadh Inscription of the Yaudheyas



SCALE 24

C.—Bijayagadh Pillar Inscription of Vishnuvardhana — The Year 438



SCALE 60

1/8 FLEET, 90 C.B.

W. GRIGGS, PHOTO-LITH.

TRANSLATION.

Here, he,—who is possessed of extensive victory and fame; who is the protector of the true religion of the warrior caste; who always cherishes princes; who is the protector of the army of the Pārthivas;¹ who day after day Śisūpāla
—was created, as if he were a fifth *Lakṣmāna*,² by (the god) Vidhātṛi.

No. 58; PLATE XXXVI B.

BIJAYAGADH STONE INSCRIPTION OF THE YAUDHEYAS.

THIS inscription was first brought to notice by myself in 1885, in the *Ind. Ant.* Vol. XIV. p. 8, and is now edited for the first time. It is from a stone that was found by my copyists, built into the inside of the Fort wall, near the pillar which has on it the following inscription of the Varika Vishṇuvaradhana, of the year 428, No. 59, Plate xxxviC., in the hill-fort of Bijayagadh or Bējēgadh, about two miles to the south-west of Byāna,³ the chief town of the Byāna Tahsil or Sub-Division of the Bharatpur⁴ State in Rājputāna.

The writing, which covers the whole front of the stone, about 1' 5½" broad by 2½" high, except for a margin of about an inch at the beginning of each line, is in a state of fairly good preservation, as far as it goes. But it is only a fragment of the original inscription. An indefinite amount is lost at the end of each line; and also an indefinite number of lines below line 2. Every effort was made to discover the rest of the inscription, but without success.—The average size of the letters is about ½". The characters must be considered as belonging to the northern class of alphabets; and the so-called Indo-Scythic form of the *m* stamps them at once as of decidedly early date. But they are of such a peculiarly ornate type, that, having no inscription of known date with which to compare them, it is not possible at present to suggest any definite period for them.—The language is Sanskrit; and the extant portion of the inscription is entirely in prose.—The orthography presents nothing calling for remark.

All the historical contents of the inscription, including the name, except perhaps the first syllable and part of the second, of the *Mahārāja* and *Mahāsēnāpati* whose titles occur in line 1, are lost. The interest of the inscription lies in its being a record of the tribe of the Yaudhēyas, who are mentioned elsewhere in this volume only in line 22 of the Allahābād pillar inscription, No. 1 above, where they are included among the tribes subjugated by the Early Gupta king Samudragupta.

¹ See the introductory remarks.

² The four *Lakṣmānas*, or regents of the quarters of the world, are—Indra, of the east; Yama, of the south; Varuṇa, of the west; and Kuvēra, of the north.—The number is sometimes increased to eight, by the addition of Agni at the south-east, Sūrya at the south-west, Vāyu at the north-west, and Chandra at the north-east.

³ The 'Byana' of the Indian Atlas, Sheet No. 50. Lat. 26° 57' N.; Long. 77° 20' E.—Other writers give the name as 'Baianā', Bayāna, Biāna, and Biānah; but this is wrong; the name, of which the mediæval form is said to have been Bēhayāna, is dissyllabic.—As regards Mr. A. C. L. Carlisle's utterly untenable derivation of Byāna from the name of the demon Bāḥāsura, see my remarks in *Ind. Ant.* Vol. XIV. p. 9.—The ancient Sanskrit name of the place was Śrīpatthā; see *id.* pp. 8 f., and 10; and Vol. XV, p. 239.

⁴ The 'Bharatpur' of maps, &c.

TEXT:¹

- 1 Siddham [11*] **Yaudh[ĕ]ya-gaṇa-puraskritasya** mahārāja-mahāsēnāpatēh
 pu
- 2 brāhmaṇa-purōgam ch-ādhishtānam śarir-ādi-kuśalam prishṭvā likhaty-
 Asti Rasmā
- 3 '.....

TRANSLATION.

Perfection has been attained! Of the *Mahārāja* and *Mahāsēnāpati*, who has been made the leader of the *Yaudhēya* tribe, and having asked the settlement, headed by the Brāhmaṇs, as to the health of (*their*) bodies &c., writes—
 "There is

No 59, PLATE XXXVIC.

BIJAYAGADH STONE PILLAR INSCRIPTION OF
VISHNUVARDHANA.

THE YEAR 428.

THIS inscription was discovered in 1871-72 by Mr. A. C. L. Carlleyle, and was first brought to notice by him in 1878, in the *Archæol. Surv. Ind.* Vol. VI. p. 59 ff., where he published Dr. G. Bühler's reading of the text and translation,¹ from an ink-impression supplied by himself, with a lithograph (*id.* Plate viii). It is on a monolith red-sandstone pillar that stands in a conspicuous position, near the south wall of the Fort, inside the hill-fort of *Bijayagadh* or *Bējēgadh* near Byānā,² the chief town of the Byānā Sub-Division of the Bharatpur State in Rājputānā. The pillar stands on a rubble masonry platform, which is about 13' 6" high and 9' 2" square at the top. The height of the pillar above the plinth is 26' 3". The base is square, to the height of 3' 8"; each face measuring 1' 6". Above this, the pillar is octagonal, for a length of 22' 7"; and it then tapers off to a point. The extreme top, however, is broken; and a metal spike, which projects from it, indicates that it was originally surmounted by a capital. The inscription is towards the south side of the pillar; it runs vertically down the pillar, and is read from the top downwards;³ and the lowest letter of line 3, the longest line, is about 7' 0" above the level of the plinth. The platform, on which the pillar stands, is plainly of much more recent construc-

¹ From the ink-impression.

² Several superscript vowels are legible along this line; but the consonants are all broken away and lost.

³ Both more or less mutilated in publication.

⁴ See page 251 above, and note 3.

⁵ On this point, Mr. Carlleyle's account is exactly the opposite; but he is wrong; as is, in fact, shewn by his further statement that line 2 is on the left of line 1, and so on; this could not be the case, if the inscription ran from the bottom upwards.

tion than the pillar itself; and this suggests that possibly the present position of the pillar is not its original one. On the south side of the pillar, towards the top of the square base, there is engraved, in two lines of rather rough Dēvanāgarī characters of about the tenth to the twelfth century A.D., *Śrī-yōgi Vra(bra)hmasāgara*, "the holy ascetic, Brahmasāgara;" with perhaps an imperfect date below, of (Vikrama-Samvat) 1008 (A.D. 951-52). And this may possibly indicate the period when the pillar was placed in its present position.

The writing, which covers a space of about 9' 4" broad by 2' 6½" high, is in a state of almost perfect preservation throughout.—The size of the letters varies from 1½" to 2". The characters must be regarded as belonging to the northern class of alphabets. They include the so-called Indo-Scythic form of *m*, quite in accordance with the date of the record. They also include, in line 1, forms of the numerical symbols for 8, 20, and 400.—The language is Sanskrit; and the entire inscription is in prose.—In respect of orthography, we have to notice (1) the use of the *jihvāmāliya* in *yaśāk-kula*, line 4; (2) the use of the guttural nasal, instead of the *anusvāra*, in *vinśēshu*, line 1, and *vanśa*, line 4; (3) the doubling throughout of *t*, in conjunction with a following *r*, e.g. in *puttrēna*, line 2; (4) the doubling of *p*, once, under the same circumstances, in *suppratishthita*, line 2; (5) the very exceptional doubling of *ś*, in conjunction with a following *r* and *y*, in *śśrēyś*, line 4, and *pañchadaśyām*, line 2; (6) the doubling of *bh* in conjunction with a following *y*, in *abbhyudaya*, line 4; and (7) the doubling of *t*, in conjunction with a following *v*, in *puttratva*, line 4.

The inscription is one of a *Rāja* named **Vishṇuwardhana**, of the **Varika** tribe. It is dated, both in words and in numerical symbols, when the year four hundred and twenty-eight had expired; on the fifteenth lunar day of the dark fortnight of the month *Phālguna* (February-March). The era is not stated; but the type of the characters indicates with the locality of the inscription, that we must refer the date to the *Mālava* or *Vikrama* era, with the result of A.D. 371-72 expired, and A.D. 372-73 current. And this shews that the **Varika Vishṇuwardhana** was in all probability a feudatory of the **Early Gupta** king **Samudragupta**.¹ The inscription is non-sectarian; the object of it only being to record the erection, by **Vishṇuwardhana**, of this pillar, which is called a *yāpa* or 'sacrificial post,' on the completion of a *puṇḍarīka*-sacrifice.

TEXT.²

- 1 Siddham [1⁰] Kṛitēshu chaturshu varsha-śatēshv-ashṭāvinśēshu 400 20 8
- 2 Phālguna(na)-bahulasya pañchadaśyām-ētasyām-pūrvvāyām³ [1⁰]
- 3 Kṛitau puṇḍarikē yūpō=yam=pratishtāpitas-suppratishthita-rājya-nāmadhēyēna
 śrī-Vishṇuwardhanēna Varikēna Yaśōvardhana-sat-puttrēna
 Yaśōrāta-sat-pauttrēna Vyāghrarāta-sat-prapauttrēna⁴

¹ If we refer the date to the Śaka era, the result, A.D. 506-7, might perhaps be used to identify this Vishṇuwardhana with the king of the same name mentioned in the Mandasor inscription of Mālava-Samvat 589 (A.D. 532-33). But there is nothing to justify us in assuming that the Śaka era was ever used in early times in this part of the country. Also, the form of *m*, as a northern letter, is too early for that period. And, as is shewn by his titles of *Rājādhirāja* and *Paramāvara*, as well as by the general tenor of his inscription, the Vishṇuwardhana of the Mandasor record was a far greater person than this Vishṇuwardhana, the *Varika*.

² From the original stone.

³ Supply *tithau*.

⁴ The form of *pa* that occurs here differs from the form used in the other instances throughout this inscription, in the distinct loop on the right hand of the bottom of the letter.

4 śrīyajña - dharmma - śśrēyō - bbhuyudaya - yaśah - kula - vaṅśa - bhāga - bhōg - ābhivri-
ddhayē [11*] Siddhir=astu puṣṭir=astu śāntir=astu jīvaṣṭuttrattvam=
astv=ichṭa-kām-āvāptir=astu śrā(śra)ddhā-vittē syātām=iti¹ [11*]

TRANSLATION.

Perfection has been attained ! Four centuries of years, together with the twenty-eighth (year), (or in figures) 400 (ana) 20 (ana) 8, having been accomplished ;² on the fifteenth lunar day of the dark fortnight of (the month) Phālguna ;—on this (lunar day), (specified) as aforesaid :—

(Line 3.)—On the ceremony of the *puṇḍarīka*-sacrifice (having been performed), this sacrificial post has been caused to be set up by the **Varika**, the illustrious **Vishṇu-wardhana**, whose royalty³ and name are well established,—who is the excellent son of **Yaśōvardhana** ; (and) the excellent son's son of **Yaśōrāta** ; (and) the excellent son of the son's son of **Vyāghrarāta**,—for the purpose of increasing (his) splendour, sacrifices, religion, welfare (in the other world), prosperity, fame, family, lineage, good fortune, and enjoyment.⁴

(L. 4.)—Let there be success ! Let there be increase ! Let there be tranquillity ! Let there be the condition of (his) having a son who shall live ! Let there be the attainment of desires that are wished for ! May there be faith and wealth !

No. 60; PLATE XXXVII.

SPURIOUS GAYA COPPER-PLATE INSCRIPTION OF SAMUDRAGUPTA.

THE YEAR 9.

THIS inscription, which is now published for the first time, is from a copper-plate that was obtained a few years ago by General Cunningham at **Gayā**,¹ the chief town of the Gayā District in the Bengal Presidency, and was, I think, first brought to notice by him in 1883, in his *Book of Indian Eras*, page 53, where it is entered as being dated in the year 40. I obtained the original plate, for examination, from General Cunningham.

The plate, which is inscribed on one side only, measures about 8" by 7½". It is quite smooth, the edges having been neither fashioned thicker, nor raised into rims. About half-way down the proper left side, the plate has laminated rather seriously ; and there is also a small crack just below this place, and another in the top of the plate, in the

¹ As is seen in the lithograph, there is no foundation whatever for the additional letter *yō* which, in Mr. Carlleyle's published lithograph, follows this *ti*, or, rather, the *h* into which the *ti* was so gratuitously converted by him. The result was naturally such as to puzzle Dr. Bühler as to the close of the inscription.

² *hrīdīshu* ; see page 73 above, note 1.

³ Or, more technically, 'condition of being a *Rāja*.'

⁴ Or perhaps *bhāgabhāga* should be taken as one word, meaning 'enjoyment of taxes ; lordship, royalty ;' see Monier Williams' Sanskrit Dictionary, s. v. *bhāgabhūj*, which is explained by 'enjoying taxes ; a king, a sovereign.'

⁵ The 'Gya' of maps, &c. Indian Atlas, Sheet No. 104 Lat. 24° 48' N. ; Long. 85° 3' E.

word *vsakdt*; but, except at these places, the inscription is in a state of perfect preservation almost throughout. The plate is fairly thick and substantial; and the letters, which are shallow, do not shew through on the reverse side of it at all. The engraving is fairly good; but, as usual, the interiors of the letters shew marks of the working of the engraver's tool throughout.—Onto the proper right side of the plate, there is fused a seal, oval in shape, about $2\frac{1}{2}''$ by $3\frac{3}{8}''$. It has, in relief on a countersunk surface,—at the top, *Garuḍa*, represented as a bird, standing to the front, with outstretched wings; and, below this, a legend in five lines, which, being also in relief, is so worn, that nothing of it can be read except a few disconnected letters here and there, and *Sam[u]drag[u]p[taḥ]*, very faintly, at the end of line 5. It must have contained a succinct recital of the genealogy, after the fashion of the *Aśīrgaḍh* seal of *Sarvavarman*, No. 47 above, page 219, and the *Sōnpat* seal of *Harshavardhana*, No. 52 above, page 231.—The weight of the plate, with the seal, is 2 lbs. 10 oz.—The average size of the letters is $\frac{3}{8}$ '. The characters belong to the northern class of alphabets. They include, in line 14, forms of the numerical symbols¹ for 9 and 10.—The language is Sanskrit; and the inscription is in prose throughout. In line 3-4, we have, instead of the usual expression *utsanna*, the word *uchchanna*, which, as used here, is, according to Sir Monier Williams' Sanskrit Dictionary, a Prakrit corruption of the Sanskrit *utsanna*.—In respect of orthography, we have to notice (1) the doubling of *t* throughout, in conjunction with a following *r*, e.g. in *prapauttrasya*, line 4; *pītrōr*, line 8; and *sagōtrāya*, line 9; (2) the doubling of *dh*, in conjunction with a following *y*, in *ayōdhyā*, line 1; (3) the occasional use of *b* for *v*, in *bō*, line 8, and *sambat*, line 14; and (4) the use of *v* for *b*, in *vrāhmaṇa*, lines 7 and 10; *vahrīchya*, line 9; and *savrahmachārīṇ*, line 9-10.

The inscription purports to be one of the Early Gupta king *Samudragupta*, and to record a charter issued from his camp at the city of *Ayōdhya*.² It purports to be dated, in numerical symbols,³ in the year nine (A.D. 328-29), on the tenth solar day, without any specification of the fortnight, of the month *Vaiśākha* (April-May). It is a non-sectarian inscription; the object of it simply being to record the grant to a *Brāhmaṇa*, ostensibly by *Samudragupta*, of the village of *Rēvatikā* in the *Gayā viśhaya*.

The legend on the seal of this grant is in characters which present a very different appearance to those of the body of the inscription; as also does the copper of the seal, as compared with the substance of the plate; and the seal is in all probability a genuine one of *Samudragupta*, detached from some other plate. The inscription itself, however, is undoubtedly spurious. This is shewn conclusively, if by nothing else, by the fact that from *uchchhītuḥ*, line 1, to *dauhittrasya*, line 5, the epithets of *Samudragupta* are uniformly in the genitive case; the drafter of the inscription was copying from a grant of *Chandragupta II.* or some other descendant of *Samudragupta*;⁴ he only then recognised

¹ The symbol which I take to be meant for 9, was interpreted by Gen. Cunningham as 40. But it certainly is not 40. It resembles most the decimal figure 2. But the day of the month is distinctly marked by a form of the numerical symbol for 10. This shews that the sign here also is intended for a numerical symbol; and the only symbol to which it approximates, is that for 9.

² The modern *Ajōdhya* or *Ajōdhyā* (the 'Oudh or Ajoodhia' of the Indian Atlas, Sheet No. 87), Lat. $26^{\circ} 48' N.$; Long. $82^{\circ} 14' E.$, on the south bank of the river 'Ghāgra or Ghōgra,' about four miles north-east of *Faizābad*, the chief town of the *Faizābād* Division of *Oudh* in the North-West Provinces.

³ See note 1 above.

⁴ Compare the construction in the *Mathurā* inscription of *Chandragupta II.*, No. 4 above, page 25, and in the *Bhitārī* pillar inscription of *Skandagupta*, No. 13 above, page 52.

that this construction would not suit a supposed inscription of Samudragupta himself, which was required in accordance with the seal that was to be attached; and he promptly then adopted the nominative construction, *utpannah* *Samudraguptah*, without taking the trouble to correct the preceding passages. It is difficult to suggest any definite time for the fabrication of this grant; on the one side, some of the characters are antique, e.g. the forms of *k*, *p*, *m*, and *r*, and particularly *h*; on the other side, others are comparatively modern, especially the *sh* in *valakhauskabhyām*, line 7-8. But it has the general appearance of having been made somewhere about the beginning of the eighth century A.D. Points which may hereafter serve to fix its date more definitely are (1) the use of the Prākṛit corruption *uchchhanna*, in line 3-4; and (2) the opening expression *mahā-nau-hasty-aśva* &c., in line 1; the only other instances of similar expressions being in line 1 of the Déo-Baranārka inscription of Jīvitagupta II., No. 46 above, page 215, and in line 1 of the Dighwā-Dubault grant¹ of the *Mahā-dja* Mahēndrapāla, of A.D. 761-62, and of the Bengal Asiatic Society's grant² of the *Mahārdja* Vināyaka-pāla, of A.D. 794-95.

TEXT.³

- 1 Ōm Svasti Mahā-nau-hasty-aśva-jayaskandhāvārāj(d)-Ā(ajyōddhyā-vāsakāt-sarvva-rāj-ōchchhēttu[*h**) pri-
- 2 thivyām-a-pratirathasya chatur-udadhi-saili-āsvādita-yaśa[sō**] Dhanada-Varuṇ-Ēndr-Ā-
- 3 ntaka-samasya Kṛitānta-paraśōr-nyāy-āgat-ānēka-gō-hiranya-kōṭi-pradasya chir-ōchchha-
- 4 nn¹-āsvamēdh-āharttu[*h**) mahārāja-śrī-Gupta-prapauttrasya⁴ mahārāja-śrī-Ghaṭōtkacha-pauttrasya⁵
- 5 mahārājādhirāja-śrī-Chandragupta-puttrasya⁶ Lichchhivi-dauhitrasya⁷ mahā-dēvyā[*m**) Ku-
- 6 mā¹⁰radēvyām-utpanna[*h**) paramabhāgavatō mahārājādhirāja-śrī-Samudra-gupcaḥ Gayā-vaishayika-Rēvatikā-grāmē vrā(brā)hmana-purōga-grāma-vala-
- 8 tkaushabhyām-āha ! Ēva ch-ārtha[*m**) viditam-bō(vō) bhavaty-ēśa(śha) grāmō mayā mātāpitrōr-ā-
- 9 tmanās-cha punv-ābhivriddhayē Bhāradvāja-sagōttrāya Va(ba)hvṛichāya sav[r]ja(bra)hmacchā-
- 10 riṇē vrā(brā)hmana-Gōpadēvasvaminē s-ōparikar-ōddēśēn-āgrahāratvēn-āti-

¹ *Ind. Ant.* Vol. XV. p. 112.² *id.* p. 140.³ From the original plate.⁴ There is a mark over the *śa*, which may be only a rust-mark, but which renders it a little doubtful whether *yaśō-dhanada* was engraved, or *yaśa dhanada* with an omission of *sō*. The other inscriptions, however, shew that the correct reading is *yaśasō dhanada* &c.⁵ The other inscriptions all read *utsanna*.—Monier Williams, in his Sanskrit Dictionary, suggests that *uchchhanna*,—which, in the sense of 'uncovered,' is a regular derivative from *ud* + *chhad*,—is, in the sense of 'destroyed, fallen into disuse,' a Prākṛit corruption of *utsanna*, from *ud* + *sad*.⁶ In order to render the inscription capable of translation, read *propauttrah*. And, at the same time, correct all the preceding genitives into nominatives.⁷ Read *pauttrah*.⁸ Read *puttrah*.⁹ Read *dauhitrāh*.¹⁰ This *mā* was first engraved closer to the margin of the plate, and then, being indistinct there, was repeated.

Sparticus Gaya Plate of Sarcouragupta — The Year 9



W. GRIGGS PHOTO-LITH.

SCALE 90

J. P. FLEET, BO. 63

- 11 sñshtāh [I*] tad-yushmābhir-asya śrótavyam-ājñā cha karttavāyā sarvā
 cha¹ sa²muchitā grāma-pra-
 12 tyayā mēya-hirany-ādāyō dēyāh [I*] na ch-ē(ai)tat-prabhṛity-ētad-āgrahārikēn-
 [A*]nyad³-grā-
 13 m-ādi-karada-kutumbi-kāruk-ādayah pravēśayita.yā ma(a)nyathā nīyatam=a(a)grā-
 14 hār-ākshēpa[h*] syād=iti [II*] Samba(mva)t⁴ 9 Vaiśākha di 10 [II*]
 15 Anya-grām-ākshapaṭalādhikṛita-Dyūta-Gōpasvāmy-ādēśa-likhitah⁵ [II*]

TRANSLATION.

Om! Hail! From the victorious camp, full of great ships and elephants and horses, situated at (the city of) **Ayōdhyā**,—the most devout worshipper of the Divine One, the *Mahārājādhirāja*, the glorious **Samudragupta**,—who is the exterminator of all kings; who has no antagonist (*of equal power*) in the world; whose fame is tasted by the waters of the four oceans; who is equal to (the gods) Dhanada and Varuṇa and Indra and Antaka; who is the very axe of (the god) Kṛitānta; who is the giver of many millions of lawfully acquired cows and gold; who is the restorer of the *āsvamedha*-sacrifice, that has been long in abeyance; who is the son of the son's son of the *Mahārāja*, the illustrious **Gupta**; who is the son's son of the *Mahārāja*, the illustrious **Ghatōtkacha**; (and) who is the son of the *Mahārājādhirāja*, the glorious **Chandragupta (I.)**, (and) the daughter's son of **Lichchhivi**, begotten on the *Mahādēvī Kumārādēvī*,—says to the two village *Valatkaushans*,⁶ together with the Brāhman, at the village of **Rēvatikā** belonging to the **Gayā vishaya**;—

(Line 8.)—"Be it known to you! For the sake of increasing the religious merit of (my) parents and of myself, this village is granted by me, as an *agrahāra*, with the assignment of the *uparikara*, to the religious student, the Brāhman *Gōpasvāmin*, of the *Bhāradvaja gōtra* (and) the *Bahvricha (śākhā)*.

(L. 11.)—"Therefore attention should be paid to him by you; and (*his*) commands should be obeyed; and all the customary tributes of the village, consisting of that which is to be measured, gold, &c., should be given. And, from this time forth, the tax-paying cultivators, artizans, &c., of other villages, &c., should not be introduced by the *Āgrahārika* of this (village) (*for the purpose of settling in it and carrying on their occupations*), (*for*) otherwise there would certainly be a violation of (*the privileges of*) an *agrahāra*." The year⁷ 9; (the month) *Vaiśākha*; the day 10.

(L. 15.)—(*This deed*) has been written by the order of **Dyūta-Gōpasvāmin**, the *Akshapaṭalādhikṛita*⁸ of another village.

¹ *sa* was engraved here, and then corrected into *cha*.

² *cha* was engraved here, and then corrected into *sa*. ³ Read *anya*.

⁴ As regards the interpretation of the first symbol, see page 255 above, note 1.

⁵ Supply *ullēkhō=yam*, or any similar words.

⁶ *Valatkaushan* is evidently a technical official title; but it occurs nowhere else, and I am not able to suggest an explanation of its meaning.

⁷ As regards the interpretation of the symbol, see page 255 above, note 1.

⁸ *Akshapaṭalādhikṛita*, meaning *lit.* 'he who is appointed to (the duties of) a depository of legal documents,' is an official title that is evidently synonymous with *Akshapaṭalika* (see page 100 above).

No. 61; PLATE XXXVIII A.

UDAYAGIRI CAVE INSCRIPTION.

THE YEAR 106.

THIS inscription was discovered in 1874-75 or 1876-77 by General Cunningham, and was first brought to notice by him in 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 53 f., where he published his reading of the text, and a translation of it by Rājā Siva Prasad, accompanied by a lithograph (*id.* Plate xix).—And in 1882, in the *Ind Ant.* Vol. XI. p. 309 f., Dr. E. Hultzsch, working from General Cunningham's facsimile, published his own revised reading of the text, and translation of it.

This is another inscription from **Udayagiri**,¹ in the Bhēlsā Sub-Division of the Īsāgadh District of Scindia's Dominions in Central India. It is inside a cave-temple, which General Cunningham has named "No. 10, the Jain Cave." The cave, which is about a hundred yards beyond "No. 9, the Amṛita Cave," is readily discernible from the plain, by means of the rough stone wall which forms the front of the main part of it, it is high up in the north-western end of the hill, and is not very easy of access, in consequence of its having to be entered by a narrow and steep flight of steps on the very edge of the cliff. The inscription is on the smoothed face of the rock, on a partly natural and partly artificial low arch, leading from the principal room of the cave to the next room towards the east.

The **writing**, which covers an irregular space of about 1' 3¼" broad by 7¼" high, has suffered a little damage at the beginning and end of some of the lines, owing to the chipping of the angular edges of the rock; but the readings here can be completed without any doubt; and the rest of the inscription is in a state of perfect preservation. Below the last line, there is a row of five roughly cut modern numerals, reading 31245, the tops of which can be seen in the lithograph; but they have no connection with the inscription.—The average **size** of the letters is about ⅜". The **characters** belong to the northern class of alphabets.—The **language** is Sanskrit; and, except for the opening invocation of the saints or perfect ones, the inscription is in verse throughout.—The **orthography** presents nothing calling for special remark.

The **inscription** refers itself to the period of the **Early Gupta** kings; but not to the reign of any particular sovereign. The recorded date, however, shews that it belongs to the time of **Kumāragupta**. It is dated, in words, in the year one hundred and six (A.D. 425-26), on the fifth solar day of the dark fortnight of the month Kārttika (October-November). It is a Jain inscription; and the object of it is to record the installation of an image of the *Tīrthamkara* Pārśva, or Pārśvanātha, at the mouth of the cave.

TEXT.²

1 Namah siddhēbhyaḥ [11*] Śrī³-samyutānām guṇa-tōyadhīnām Gupt-
ānvayānām nṛipa-sattamānām

¹ See page 23 above, and note 1.² From the original stone.³ Metre Indravajrā.

- 2 rájyē kulasy=abhivivarddhamānē shaḍbhir-yyutē varsha-śatē=tha māsē [11*]
Su¹-Kārttikē bahula-dine=tha pañchamē
- 3 guhā-mukh^A sphāṭa-vikaṭ-ōtkāṭm-imām jita-dvishō Jina-vara-Pārśva-
samjñikām Jin-ākṛitīm śama-damavān=a-
- 4 chikarat [11*] Āchāryya²-Bhadra-ānvaya-bhūṣhaṇasya śiṣhyō hy-asāv-āryya-
kul-ōdgatasya āchāryya-Gōśa-
- 5 rma-munēs=sutas=tu Padmāvāt³-āsvapatēr-bbhaṭasya [11*] Parair⁴-a-
jēyasya Ripughna-māninas=sa Saṅghi-
- 6 lasy-ēty=abhivīśrutō bhuvī sva-samjñayā Śāṅkara-nāma-śabdītō vidhāna-
yuktāṃ yati-mā-
- 7 rggam-āsthitaḥ [11*] Sa⁵ uttarāṇām sadṛiṣē Kurūṇām udag-diśā-dēśa-varē
prasūtaḥ
- 8 kshayāya karm-āri-gaṇasya dhimān yad-ātra puṇyāṃ tad-
apāsasarjja [11*]

TRANSLATION.

Reverence to the Perfect Ones!¹ In the augmenting reign of the family of the best of kings, belonging to the **Gupta lineage**, who are endowed with glory (*and*) are oceans of virtuous qualities;—in a century of years, coupled with six; and in the excellent month of Kārttika; and on the fifth day of the dark fortnight;—

(Line 3.)—He² who has conquered the enemies³ (*of religion*), (*and*) is possessed of tranquillity and self-command, caused to be made (*and set up*) in the mouth of (*this*) cave, this image of a Jina, richly endowed with (*the embellishments of*) the expanded hoods of a snake⁴ and an attendant female divinity, (*and*) having the name of Pārśva, the best of the Jinas.

(L. 4.)—He is, indeed, the disciple of the saint, the *Āchārya* Gōśarman, who was the ornament of the lineage of the *Āchārya* Bhadra (*and*) sprang from a noble family; but he

¹ Metre, Ruchirā.

² Metre, Indravajrā.

³ We have here the locative case of a base *padmāvati*, which, to suit the metre, is substituted for the proper base *padmāvatiḥ*, the locative of which would be *padmāvatyām*.

⁴ Metre, Vamāsatha.

⁵ Metre, Upēndravajrā.

⁶ *siddhēbhyaḥ*. These Siddhas are not to be confused with the mythical semi-divine Siddhas who are mentioned, e.g., in line 1 of No. 18 above, page 81. They are saints, who by austere practices have attained *siddhi* or 'perfection or final beatitude' (see the remarks on *siddham*, page 25 above, note 4) in the shape of some or all of the five states of *salokitā*, 'residence in the same heaven with any particular deity; ' *sarūpatā*, 'identity of form with the deity, or assimilation to him; ' *sāmīpya*, 'nearness to the deity; ' *sāyujya*, 'absorption into the deity; ' and *sārśritā* or *samānāivaryatva*, 'equality with the supreme being in power and all the divine attributes.'—The Jain term *siddha* corresponds pretty closely to the Buddhist *samyak-sambuddha*, which occurs in line 1 of No. 11 above, page 46.

⁷ i. e. Śāṅkara, whose name occurs in line 6 below.

⁸ The allusion is to the *ari-shatka* or *ari-shad-varga*; see page 156 above, note 5.

⁹ Dr. Hultzsch wrongly read *sphuta*, and thus missed the meaning of this passage.—For *vikaṭā*, which I have translated by 'an attendant female divinity,' see Monier Williams' Sanskrit Dictionary s.v., where he explains it by 'a kind of female divinity, peculiar to Buddhists'—The image referred to in this inscription, is not now in the cave. But, in support of my explanation of the passage, we may refer to a precisely similar image, in the Jain cave at Bādāmi, described in *Archaeol. Surv. West. Ind.* Vol. I. p. 25. It represents the same Jina, Pārśvanātha, with a five-hooded snake over him as a kind of nimbus, and a female on the right side, with a serpent's hood, holding up the rod of the umbrella that shades him

is more widely renowned on the earth (*as being*) the son, (*begotten*) on Padmāvati,¹ of the *Aśvapati*,² the soldier Sanghila, who, unconquerable by (*his*) enemies, took himself to be a very Ripughna;³—by his own appellation, he is spoken of under the name of *Śamkara*;—(*and*) he has adhered to the path of ascetics, conformable to the sacred precepts.

(L. 7.)—Born in the region of the north, the best of countries, which resembles (*ix beatitudo*) the land of the Northern Kurus,⁴—he, the wise one, has set aside whatever religious merit (*there is*) in this (*act*), for the purpose of destroying the band of the enemies⁵ of religious actions.

No. 62; PLATE XXXVIII B.

SANCHI STONE INSCRIPTION.

THE YEAR 131.

THIS inscription was first brought to notice in 1837, in the *Four. Beng. As. Soc.* Vol. VI p. 451 ff., where Mr. James Prinsep published a very fair lithograph of it (*id.* Plate xxvi.), reduced from copies on cloth and paper made by Captain Edward Smuh, of the Engineers, and, with it, his own reading of the text, and a translation of it.

This is another inscription from *Sāñchi*,⁶ in the Dīwāngāñi Sub-Division of the Bhōpāl State in Central India. It is on the outer side of the centre rail in the fourth row outside and on the south side of the eastern gateway, and in a re-entering angle of the railing, of the Great *Stūpa*.

The *writing*, which covers a space of about 2 5" broad by 2' 0" high, is in a very fair state of preservation, every letter being, with care, legible from beginning to end; but, owing to the discolouration of the stone from lapse of time, it is much easier to read in the ink-impression and lithograph, than on the original stone.—The *size* of the letters varies from $\frac{1}{2}$ " to 1". As in the case of the *Sāñchi* inscription of Chāndragupta II. of the year 93, No. 5 above, page 29, Plate iiiB, the *characters* belong to the southern class of alphabets; they are not so carefully formed as the characters of that inscription · but,

¹ See page 259 above, note 3.

² *Aśvapati*, *lit.* 'lord of horses,' appears to be a technical official title—See Prof. F. Kielhorn's note on the analogous term *Gajapati*, in the *Ind. Ant.* Vol. XV. p. 9, note 52.


³ Or we may translate "took himself to be the slayer of (*all his*) foes"—But Ripughna seems to be intended as a proper name, and as a synonym for Ripumjaya, which was the name of three or four Purāṇic kings and heroes; or for Śatrugna, which was the name of one of the brothers of Rāma. We may also compare the name of Śatrugnarāja, in No. 55 above, *lin.* 19, page 237.

⁴ The Kurus, one of the tribes of India, were divided into two branches, the northern and the southern Uttarakuru, or the country of the Northern Kurus, is supposed to be a region beyond the most northern range of the Himālaya mountains, and is described as a country of everlasting happiness.

⁵ Here, again, the allusion is to the *ari-shad-varga*, see page 156 above, note 5.


⁶ See page 29 above, and note 2.—In connection with what I have said there, regarding the origin of the name of *Sāñchi*, I would add that we should compare, with *Sāñchi* or *Sāchi* and *Kāchi*, such instances as *Tōṅdal* and *Bōṅdal*, two villages next to each other, separated only by a stream, in the *Mālsiras Tāluka* or Sub-Division of the *Shōlāpur District*; and *Hīsrā* and *Phīsrā*, two contiguous villages in the *Karmājēm Tāluka* of the same District. Similar rhyming names may be found all over the country.

A—Udayagiri Cave Inscription—The Year 106



SCALE 40

B—Sanelu Inscription—The Year 131



allowing for this, the details shew no particular development. In line 11, they include forms of the numerical symbols for 1, 5, 30, and 100.—The language is Sanskrit; and the inscription is in prose throughout. In *pravishṭaka*, line 4, we have to notice the affix *ka* which I have commented on at page 69 above.—In respect of orthography, the only point that calls for remark, is the doubling of *v*, after the *anusvāra*, in *samvāt*, line 11.

The inscription does not refer itself to the reign of any king; but the date recorded in it, allots it to the time of either **Kumāragupta**, of the Early Gupta dynasty, or his son and successor **Skandagupta**. It is dated, in numerical symbols,¹ in the year one hundred and thirty-one (A.D. 450-51), on the fifth solar day, without any specification of the fortnight, of the month *Aśvayuj* (September-October). It is a Buddhist inscription. And the object of it is to record the grant, by the *Upāsikā* or lay-worshipper **Harisvāminī**, the wife of the *Upāsaka* *Sanasiddha*, of certain sums of money to the *Ārya-Saṅgha*, or community of the faithful, at the great *vihāra* or Buddhist convent of **Kākanādabōṭa**,—i.e. the great *Stūpa* at *Sāñchi*,²—for the purpose of feeding one *Bhikṣhu* day by day, and of maintaining lamps in the shrines of Buddha.

TEXT.

- 1 S[iddha]m* [11*] Upāsaka-Sanasiddha-bhāryayā upāsik[ā*]-Harisvāminyā
mātā-
- 2 pitarām* = uddiśya **Kākanādabōṭa**-śrī-mahā-vihāre cāturddiśāy = āryya-saṅ-
3 ghāya akshaya*-nivi dattā dīnāra dvādasa [1*] ēśhām dīnāraṇām
yā vṛiddhi-
- 4 r = upajāyatē tayā divasē-divasē saṅgha-madhya-praviṣṭaka-bhikṣur = ēkah
bhōja-
- 5 yitavyah [11*] Ratna-grīhē-pi dīnāra-trayaṁ dattam [1*] [ta]d-dīnāra-
trayasya vṛi[d*]dhyā ratna-grīhē
- 6 bhagavatō Buddhasya divasē-divasē dīpa-trayam prajvālayitavyam [11*]
Chatur-Buddh-āsa-
- 7 nē = pi dattam dīnāra ēkah [1*] tasya vṛiddhyā chatur-Buddh-āsanē
bhagavatō Buddhasya
- 8 divasē-divasē dīpaḥ prajvālayitavyah [11*] Ēvam = ēsh-akshaya-nivi
9 ā-chandir-ārka-silā-lēkhyā svāminī-Sanasiddha-bhāryayā
- 10 upāsik[ā*]-Harisvāminyā pravartitā iti [11*]
- 11 Samvāt 100 30 . Aśvayug-di 5 11

¹ Gen. Cunningham (*Bhilai Topes*, p. 193) read the first symbol as 300. But the two marks on the right side, required to convert 100 into 300, are entirely wanting; and he must have been misled by the natural marks of the stone becoming exaggerated in an imperfect ink-impression.

² See page 31 above.

³ From the original stone.

⁴ This word is in the margin, before *upāsaka*. The traces that remain of it are very faint.

⁵ Read *mātāpitarāv*.

⁶ The initial *a* of this word is badly formed, and is partly run into the *ya* of *saṅghāya*. Perhaps *saṅghāy = akshaya* was being engraved, as required by *samāhi*, and then the initial *a* was inserted.

⁷ As regards the reading of the first symbol, see note 1 above.

TRANSLATION.

Perfection has been attained! By the *Upāsikā Harisvāminī*, the wife of the *Upāsaka Sanasiddha*, for the sake of (*her*) parents, twelve *dīnāras* are given, (*as*) a permanent endowment, to the community of the faithful, collected from the four quarters of the world, at the holy great *vihāra* of *Kākanādabōta*. With the interest that accrues of these *dīnāras*, day by day one *Bhikshu*, who has been introduced into the community, should be fed.

(Line 5.)—Also three *dīnāras* are given in the jewel-house.¹ With the interest of these three *dīnāras*, day by day three lamps of the divine Buddha should be lit in the jewel-house.

(L. 6.)—Also, one *dīndra* is given in the place where (*the images of*) the four Buddhas are seated.² With the interest of this, day by day a lamp of the divine Buddha should be lit in the place where (*the images of*) the four Buddhas are seated.

(L. 8.)—Thus this permanent endowment,—written upon stone (*so as to endure*) for the same time with the moon and the sun,—has been accomplished by the *Upāsikā Harisvāminī*, the noble lady,³ the wife of Sanasiddha.

(L. 11.)—The year⁴ 100 (*and*) 30 (*and*) 1 ; (the month) *Aśvayuj* ; the day 5.

No. 63; PLATE XXXIX A.

MATHURA STONE IMAGE INSCRIPTION.

THE YEAR 136.

THIS inscription was discovered by General Cunningham, and was first brought to notice in 1871, in the *Four. R. As. Soc. N. S. Vol. V. p. 184 f.*, where Professor J. Dowson published his reading of the text, and a translation of it, accompanied by a lithograph (*id.* Plate ii. No. 8) reduced from General Cunningham's ink-impression.—And this rendering of the inscription was reprinted, with a few corrections, in 1873, in the *Archæol. Surv. Ind. Vol. III. p. 36 f.*, accompanied by a fresh lithograph (*id.* Plate xvi. No. 22).

The inscription is on the pedestal of a broken standing statue that was found in the Jail Mound at *Mathurā*,⁵ the chief town of the *Mathurā* District in the North-West Pro-

¹ *ratna-grīha* ; see page 33 above, note 5.

² *chatur-Buddh-āsana*.—As pointed out by Gen. Cunningham in his *Bhilsa Topes*, p. 191 f., this is explained by four statues of Buddha, seated, one opposite each entrance, which are in the circular enclosure that runs round the *Stūpa*, inside the railing. Owing, I suppose, to alterations made in the course of the restorations that have been carried out at *Sāñchi*, the statue at the south entrance is now a seated statue, similar in general design to the statues at the north, east, and west entrances, it is evidently the original statue, which had somehow been shifted, now restored to its proper place ; and the standing statue, which was opposite the southern entrance when Gen. Cunningham wrote his description, now stands a little to the west of it.

³ *svāminī* —Or perhaps the word stands here for the fuller title, *Vihārasvāminī*, which occurs in the next inscription ; see page 263 below, note 7.

⁴ As regards the reading of the first symbol, see page 261 above, note 1.

⁵ See page 26 above, and note 2.

vinces. When I examined it, it was in the Government Museum at Allahâbâd; but it has now, I understand, been transferred to the Provincial Museum at Lucknow. Of the statue itself, all that remains is the feet, with part of a small kneeling figure at each side, and there is thus nothing to shew its nature; but, from the tenour of the inscription, it must have been a standing image of Buddha.

At the commencement of the inscription, in the margin, there is engraved a Buddhist *dharmachakra*, or 'wheel of religion,' an emblem the object of which appears to be to denote the way in which religion encompasses and envelops everything.—The writing covers a space of about 1' 6 $\frac{3}{4}$ " broad by 2 $\frac{3}{4}$ " high; and is in a state of very good preservation, except in the last line, of which almost the whole of the last part is broken away and lost.—The average size of the letters is about $\frac{1}{2}$ ". The characters belong to the northern class of alphabets. They include, in line 1, forms of the numerical symbols for 5, 20, 30, and 100.—The language is Sanskrit. The first two lines are in prose, and the rest in verse.—In respect of orthography, the only point that calls for notice is the doubling of *v*, after the *anusvâra*, in *samvatsara*, line 1.

The inscription does not refer itself to the reign of any king; but, from its date, it appears to belong to the time of the Early Gupta king Skandagupta; since his father, Kumâragupta, having commenced to reign in at least the year 96, can hardly have continued on the throne up to the present date. It is dated, both in words and in numerical symbols, in the year one hundred and thirty-five (A.D. 454-55), and on the twentieth solar day, without any specification of the fortnight, of the month Pushya (December-January). From the expressions used, as well as from the emblem on the margin of the stone, it is evidently a Buddhist inscription; and the object of it is to record the gift of the statue, on the pedestal of which it is engraved.

TEXT.¹

- 1 Samvatsara-satê pamcha-stris²-ôttaratamê 100 30 5 Pushya-mâsê

divasê vi[m]s[ê] di 20 [1*] Dêya-dharm[ô]=yam vihârasvâminy[â]
- 2 Dêvtâyâ³ [11*] Yad=atra punyam tad=bhavatu matâpitroh sarvva-

sat[t*]vânâni=cha anuttara-jñân⁴-âptayê⁵ ||
- 3 Saubhâgyam⁶ pratiru(rô)patâ guṇavatî kirttis=sapatna-kshayah śrîman[t]ô

vibhavâ bhavâ[h*] sukha-phalâ nirvânânam=amê śivam
- 4 a-stabdhâ(?)ni bhavanti dâna-niratau chittam niyôjy=aikadâ [-] i [- - ∪]

vichâ(ṭâ)raṇa[∪ ∪]dhiyam [- - ∪ - -] i [∪] yam [11*]

TRANSLATION.

In a century of years, increased by the thirty-fifth (*year*), (*or in figures*) 100 (*and*) 30 (*and*) 5; in the month Pushya; on the twentieth day, (*or in figures*) the day 20;—this is the appropriate religious gift of the *Vihârasvâminî*⁷ Dêvatâ. Whatever religious

¹ From the original stone.

² Read *trims*

³ Read *dvatâyâh*.

⁴ This π is rather an anomalous one; but the character cannot stand for anything else.

⁵ There is no objection to the present reading, but we usually have *avâptayê*.

⁶ Metre, Śârdûlavikrjita.

⁷ *Vihârasvâminî*, *lit.* 'mistress (lady-superintendent) of a *vihâra*,' seems, not to be a technical religious title denoting an office held by females, but to mean simply 'the wife of a *Vihârasvâmin*;' see page 279 below, note 5.—We may compare *Dandanîyaktî*, in line 40-41 of the Kargudari in-

merit (*there is*) in this (*act*),—let it be for the acquisition of supreme knowledge by (*her*) parents and by all sentient beings!

(Line 3.)—Good fortune; the condition of being a model (*worthy of imitation*), abounding in virtuous qualities; fame; the destruction of the enemies (*of religion*);¹ riches abounding in prosperity, births that result in happiness; (*and*) finally, an auspicious *nirvāna*;—(*all these*) are not permanent (?);² having once fixed the thoughts upon the happiness of making gifts,

No. 64: PLATE XXXIX B.

GADHWA INSCRIPTION.

THIS inscription was discovered by General Cunningham in 1874-75 or 1876-77, and was first brought to notice by him in 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 10 f., where he published his reading of the text, accompanied by a lithograph (*id.* Plate v. Nos. 2 and 3).

It is another inscription from **Gadhwa**,³ in the Karchhanā Sub-Division of the Allahābād District in the North-West Provinces. It was found on pulling down a ruined wall; and is on two faces of a fragment of a square sandstone pillar which had been cut into four beams by splitting it down the middle of each face, in order to adapt it to some later building purposes. The other pieces were not found. The original stone is now in the Imperial Museum at Calcutta.

The **writing** includes the remains of two separate records, which, however, seem to refer to one and the same object of donation. On that face of the stone which is represented in the left part of the lithograph, we have the remains of fourteen lines, covering a space of about 3½" broad by 1' 2¼" high; and, on the other side, the remains of eight lines, covering a space of about 6½" broad by 11¼" high. Such of the writing as remains, is fairly well preserved; but of course some of the letters are doubtful from want of the context to explain them.—The **size** of the letters varies from ⅜" to ¼". The **characters** belong to the northern class of alphabets, and are of precisely the same type as those of Nos. 7, 8, and 9 above, Plate ivB. C. and D. They include, in lines 18 and 19, forms of the numerical symbols for 1 and 2.—The **language** is Sanskrit; and the inscription is in prose throughout.—In respect of **orthography**, the only point that calls for notice is the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *vinśati*, line 16.

From the letters visible at the end of line 1, the **inscription** may belong to the time of the **Early Gupta** king **Kumāragupta**. The details of the date, however, have been

scription of Śaka-Saṁvat 1030 (*Ind. Ant.* Vol. X. p. 252, and note 20), it means, not 'a female Leader of the Forces,' but 'the wife of a *Dandandiyaka*.' Modern instances of finding appellations for women in the official titles of their husbands, are afforded by the Kanarese *Gaudarāni*, and the Marāṭhī *Pāṭhīn*, as used to designate the wife of the *Gauda* or *Pāṭhī*, the village-headman.

¹ The allusion is to the *ari-shad-varga* or *ari-shaṭka*; see page 156 above, note

² According to the Buddhist doctrine, it would appear that even *nirvāna*, or the extinction of existence, is not a permanent state, and does not free the individual who attains it from the liability of future births unless it is followed by *parinirvāna*, or absolute destruction of identity by complete absorption into the divine essence.

³ See page 36 above, and note 1.

A — Mathura Image Inscription — The Year 135



SCALE .80

C — Kosam Image Inscription of the Maharsja Bhimavarman — The Year 139.



SCALE .35

B — Gadwa Inscription



SCALE .55

D — Gadwa Inscription — The Year 148



SCALE .35

W. GEORGE, PHOTO-LITH.

J. F. FLEET, SO. C.S.

entirely destroyed. The remnant of the inscription does not display any sectarian character. The object of it was to record certain grants to a *sattra*, or charitable hall or almshouse.

TEXT.¹

First Part.

1	sr . ku- ²
2	r.....	sattra yû(?) 9(?)
3	[di]vasa-pûrvvâyam ma-	
4	guptasy-aiva da . y .	
5	[A.]nantaguptâya(?)â)	
6	puṇy-âpyâyan-â-	
7	[rttham]	sattra-sâ[mâ ²]nya-bhōja-
8	[na]	[di]nâraiḥ
9	vâsô-yugâ-
10	parô di-
11	[nâra]	dinâraiḥ dē(?)va-
12	[Yas̄-ch-ainam]	dharma-skandham vyu-
13	[chchhindyât-sa	pañchabhir-mahâpâta]kaiḥ	sa[m̄]yu-
14	ktah syâd-iti [11]		

Second Part.

15	sat[t ²]ra-sâmânya-bhōjanê	
16	prati suva	upair-ékân-na-viñsatibhi[h]
17	kâritah [1 ²]	Brâhma(?)nô mayika.....	
18	dvayam a	karôta a bra.....	
19	yugam i	koṭṭayba sukun.....	
20	dakshina-kôla-	kañchaḍam paksha.....	[11 ²]
21	Yas̄-ch-ainam	vyuchchhin[dy]â[t-sa	pañchabhir-mahâ]-
22	[pâ]takais-sa[m̄ ²]yuktah	[s]y[âd-iti 11]	

TRANSLATION.

It is impossible to give any connected rendering of the contents of this inscription. We can only note that, in the First Part, we may perhaps have remnants of the name of **Kumâragupta** in line 1-2; that there is the name of Anantagupta or Anantaguptâ in line 5, evidently belonging to some private person; and that lines 7 to 12 appear to have recorded certain grants, fixed in *dindras*, for the purpose of providing food in a *sattra* or 'almshouse,' and also to provide pairs of upper and lower garments. It ends with the usual imprecation against interfering with the continuance of the grant.

The Second Part, again, refers to food in an almshouse, recording something in connection with it at a cost of nineteen gold coins of the kind called *suvarna*. Other details follow, including two *karôtas* or 'basins or cups,' and one pair [of upper and lower garments]. Then follows apparently a grant of some land, on the south bank of a river. And the inscription winds up, as before, with the usual imprecation against interfering with the grants.

¹ From the original stone.² Possibly the original had *iri-Kumâraguptasya*.

No. 65; PLATE XXXIX C.

KOSAM STONE IMAGE INSCRIPTION OF THE
MAHARAJA BHIMAVARMAN.

THE YEAR 139.

THIS inscription was discovered in 1874-75 or 1876-77 by General Cunningham, and was first brought to notice by him in 1880, in the *Archæol. Surv. Ind.* Vol. X. p. 3, where he published his reading of the text, accompanied by a lithograph (*id.* Plate ii. No. 3).

Kōsam,¹ the ancient **Kausāmbī**, is a small village near the left bank of the Jamnā, about eight miles to the south of Karārī,² the chief town of the Karārī Parganā in the Manjhanpur or Manjhandpur Tahsil or Sub-Division of the Allahābād District in the North-West Provinces. The inscription is on the broken base of a sculptured standing group of Siva and Pārvatī that was found buried in a field near the large monolith pillar inside the fort, which is described in the *Archæol. Surv. Ind.* Vol. I. p. 309 ff.

The writing, which covers the whole face of the stone, measuring about 10½' broad by 4" high, is in a state of very fair preservation, as far as it goes. But it is only a fragment, as at least one line is almost entirely destroyed below line 2; and it is also impossible to say how much has been lost at each side of the stone.—The average size of the letters is about ⅙". The characters belong to the northern class of alphabets. They include forms of the numerical symbols for 7, 9, 30, and 100, and perhaps³ for 2.—The language is Sanskrit; and the extant portion of the inscription is all in prose.—The orthography presents nothing calling for remark.

The inscription is one of a *Mahārāja* named **Bhimavarman**, who, judging by the date, must have been a feudatory of the **Early Gupta** king **Skandagupta**. Its date, in numerical symbols, is the year one hundred and thirty-nine (A.D. 458-59), and the seventh solar day, perhaps of the second fortnight of a month, or perhaps of the second month of a season;⁴ but the details here are broken away and lost. It is evidently a Śaiva inscription; and the object of it must have been to record the gift or installation of the sculpture on the base of which it is engraved.

¹ The 'Kosam and Kosim Kheraj' of maps, &c. Indian Atlas, Sheet No. 88. Lat. 25° 20' N., Long. 81° 27' E.—*Kheraj* is a mistake for *khirāj*; the village consisting of two parts, of which one is *śām* or 'rent-free, and the other is *khirāj* or 'rent-paying.'

² The 'Kuratee' of maps

³ See note 4 below.

⁴ Before the word *diva* there are two marks which seem to be the numerical symbol 2; and the passage might be completed either in accordance with the method of, for instance, the date of the Nāsik inscription of Pujumāyī, "in the year nineteen, 19; in the second fortnight, 2, of the hot season, on the thirteenth day, 13" (*Archæol. Surv. West. Ind.*, Vol. IV. p. 108, No. 18); or the date of the Mathurā inscription of Vāsudēva, "in the 44 (?74); in the first month of the rainy season; on the thirtieth day, 30" (*Archæol. Surv. Ind.* Vol. III. p. 32, No. 8). But I know of no other instance of these ancient methods being continued as late as the period of the present inscription; and this makes it doubtful whether the signs in question really are the numerical symbol 2.

TEXT.¹

- 1 Mah[ā²]r[ā]jasya śrī-Bhimavarmmaṇḥ sarmva[³] 100 30 9

 2 2(?)⁴ diva³ 7 [1³] śtad-[d³]ivasa kumaramē

 3 pa

TRANSLATION.

..... (In the government) of the *Mahārāja*, the illustrious **Bhimavarman** ;
 —the year 100 (and) 30 (and) 9; 2 (?)⁴; the day 7;—(on)
 this day

No. 66; PLATE XXXIX D.

GADHWA STONE INSCRIPTION.

THE YEAR 148.

THIS inscription was discovered in 1874-75, or 1876-77 by General Cunningham, and was first brought to notice by him in 1881, in the *Archæol. Surv. Ind.* Vol. X. p. 11, where he published his reading of the text, accompanied by a lithograph (*id.* Plate v. No. 4).—This rendering of the inscription has remained the only published version of it up to the present time. But in 1882, in the *Ind. Ant.* Vol. XI. page 311, note 3, Dr. E. Hultzsch pointed out that the correct interpretation of the date gave the year 148; not 140, as read by General Cunningham.

This is another inscription from **Gadhwa**,² in the Karchhanā Sub-Division of the Allahābād District in the North-West Provinces. It is on a sandstone fragment that was found in the pavement of the Daśavatāra temple of Viṣṇu, and is now in the Imperial Museum at Calcutta.

With the exception of a margin of about 1½" at the top and bottom, and at the end of the lines, the inscription covers the entire front of the stone, measuring about 2' 4" broad by 7½" high. The **writing** is a good deal damaged, but can be made out satisfactorily with a little trouble. It is, however, only a fragment; since the first part of each line, containing nearly as much as is now extant, has been cut away in adapting the stone to some later building purpose, and this part of the stone has not been found.—The average size of the letters is about ⅙". The **characters** belong to the northern class of alphabets.—The **language** is Sanskrit; and the entire inscription is in prose.—In respect of **orthography**, we have to notice (1) the use of the guttural nasal, instead of the *anusvāra*, before *ś*, in *śatvārinśad* and *vinśati*, line 1; (2) the doubling of *ś*, in conjunction with a following *r*, in *chittra*, line 3; and (3) the doubling of *v*, after the *anusvāra*, in *samvatsara*, line 1.

¹ From Gen. Cunningham's ink-impression; so also the lithograph.

² See page 266 above, note 4.

³ i.e. *divasa*, or *divasī*.

⁴ See page 266 above, note 4.

⁵ See page 36 above, and note 1.

The inscription refers itself to the reign of some particular king; but his name has been entirely broken away and lost in the first half of line 1. The recorded date, however, shews that it was either of the time of the Early Gupta king Skandagupta, or immediately after his reign. It is dated, in words, in the year one hundred and forty-eight (A.D. 467-68), on the twenty-first solar day, without any specification of the fortnight, of the month Māgha (January-February). It is a Vaishṇava inscription. And the object of it is to record the installation of an image of the god Vishṇu, under the name of Anantasvāmin; and,—for the purpose of providing perfumes, incense, garlands, &c., and of executing repairs,—a grant, the details of which are lost, but which would seem to have consisted of some land at a village belonging to the same god under the name of Chitrakūtasvāmin, or 'the lord of Chitrakūta.'

TEXT.¹

- 1 **sya** pravarddhamāna-vijaya-rājya-sambhvvatsara²-śatē-śtā-
chatvāriṅśad-uttarē Māgha-māsa-divasē ēka-viṅśatimē [1³]
2 puny-ābhivṛddhy-artham vaḍabhīm-kārayayitvā⁴ Ananta-
svāmi-pādārh⁵ pratishthāpya gandha-dhūpa-srag
3 s[phu]ṭa-pratisamkāra-karaṅ-ārtham bhaga[va]ch-Chitra-
[k]ūtasvāmi-pādīya-kōshthē(?)ta-prāvēśya-mati .
4 lā dattā dvādaśa [11⁶] Yainar⁷
vyuchchh[ī]ndy[ā]t-sah⁸ paṃchabhiḥ mahāpātakaiḥ sa[rhy]uktah⁹
śyād-iti [11¹⁰]

TRANSLATION.

..... In the augmenting victorious reign¹ of
in a century of years, increased by forty-eight, on the twenty-first day of the month
Māgha;—

(Line 2.)—Having caused (*a temple having*) a flat roof² to be made, for the sake of
increasing the religious merit of (*and*) having installed the feet³ of
(the god) Anantasvāmin perfumes, incense, garlands
..... for the purpose of repairing whatever may become torn, there have
been given twelve belonging to the entrance of ...
..... which belongs to the feet of the divine (god) Chitrakūtasvāmin.

¹ The Chitrakūta referred to here is the modern 'Chatarkot,' 'Chitarkot,' and 'Chitrakote Hill of maps, &c., in the 'Bānda' District of the North-West Provinces, forty-two miles south-east of Bānda, and seventy-one miles south-west of Allahābād; Lat. 25° 12' N.; Long. 80° 47' E. It is a great place of pilgrimage, and is specially sacred to Vishṇu in his incarnation as Rāma.

² From the original stone.

³ Read *rājyē sambhvvatsara*; see page 38 above, note 5.

⁴ Read *vaḍabhim kārayitvā*, or *vaḍabhīn-kārayitvā*.

⁵ Read *pādān* or *pādau*.

⁶ Read *ya śnam*, or *yaś-cā-śnam*.

⁷ Read *sa*.

⁸ See page 38 above, note 5.

⁹ *vaḍabhī* (also *valabhī*, which occurs in line 6 of No. 18 above, page 81) is explained as meaning 'the wooden frame of a roof; a flat roof, house-top, top-room, turret, top-floor, balcony; any temporary erection on the top of a palace; an awning, a tent;' but it seems to refer to a building here, and to denote 'a flat-roofed temple.'

¹⁰ *i.e.* "having installed an image;" see page 123 above, note 5. The use of the word *pāda*, not *pada*, shews that the inscription does not refer to the foot-prints or impressions of the feet, which are so frequently objects of worship. So, also, just below this passage, "the feet of the divine (god) Chitrakūtasvāmin" means simply "the divine (god) Chitrakūtasvāmin."

(L. 4.)—Whosoever may interrupt this (*grant*), he shall become invested with (*the guilt of*) the five great sins!

No. 67; PLATE XL A.

TUSAM ROCK INSCRIPTION.

THIS inscription appears to have been discovered by Mr. Bird, and was first brought to notice by General Cunningham in 1875, in the *Archæol. Surv. Ind.* Vol. V. p. 138 ff., where he published a translation of it by Babu Pratap Chandra Ghosh, accompanied by a lithograph (*id.* Plate xl. No. 5).

Tusām¹ or **Tusām** is a village about fourteen miles to the north-west of Bhiwān,² the chief town of the Bhiwān Tahsil or Sub-Division of the Hisār or Hissār District in the Pañjāb. Immediately on the west of the village there is a steep isolated hill, that rises abruptly out of the plain to a height of some eight hundred feet. And the present inscription is on the surface of a rock, about half-way up the east side of this hill.

About a foot below the centre of the last line of the inscription, there is engraved on the rock an **emblem**, of which a complete restoration is given by General Cunningham in his published lithograph, and which may be either a Buddhist *dharmachakra* or 'wheel of religion,' or a sun-symbol. But there is nothing to connect it of necessity with the inscription now published; and it may belong to one of the shorter records, e.g. the *Ītish bhagavatā bhagavat-pāda-dhā*, "victory has been achieved by the Divine One, in (*this*) region belonging to the feet³ of the Divine One," which is engraved just above the present inscription, in large and somewhat irregular characters of about the same period.⁴—The **writing** covers an extreme space of about 4' 2" broad by 2' 2½" high; the lines being of unequal length to suit the irregularities of the rock. The engraving was rather shallow, and some of the letters are a good deal weather-worn; but, on the original rock, the inscription is quite legible throughout.—The **size** of the letters varies from ⅜" to 1¼". The **characters** belong to the northern class of alphabets: but in the word *āli*, 'a bee,' in line 1, they include the southern *l*, which I have commented on at page 4 above.—The **language** is Sanskrit; and the inscription is in prose throughout.—In respect of **orthography**, the only points that call for notice are (1) the doubling of *dh*, in conjunction with a following *y*, in *upādādhya*, line 5; and (2), as noted above, the use of the southern *l* in *āli*, line 1, which is probably due to Sômatrāta, whose record this inscription is, being a Sāvata from Central or Southern India.⁵

¹ The 'Toosham and Tosham' of maps. Indian Atlas, Sheet No. 49. Lat. 28° 51' N.; Long. 76° 0' E.—The name is written sometimes with the palatal sibilant, and sometimes with the dental; but with a preference for the former.—Gen. Cunningham wrote the name 'Tushām,' and suggested that it is derived from *Tushār-Arāma*, 'the Tushār monastery.' But the sibilant is not the lingual *sh*; and the proposed etymology, due in the first instance to the supposition that the inscription mentioned a Tushār king named Vishṇu, cannot be upheld.

² The 'Bhewani and Bhewannee' of maps.

³ See page 123 above, note 5.

⁴ See *Archæol. Surv. Ind.* Vol. V. Pl. xl. No. 1; which, however, is not quite an accurate representation of the original.

⁵ See page 271 below, note 1.

The inscription does not refer itself to the reign of any king, and is not dated; but, on palæographical grounds, it may be allotted to the end of the fourth, or the beginning of the fifth century A.D. It is a Vaishṇava inscription; and the object of it is to record the making, by an *Āchārya* named *Sōmatrāta*, of two reservoirs and a house, for the use of the god *Vishṇu* under the name of *Bhagavat* or the *Divine One*.

The manipulation of General Cunningham's ink-impresion, as shewn by the published lithograph, led to the introduction of the name of the *Early Gupta Mahārāja Ghaṭōtkacha* in line 2; and to the supposition that the name *Vishṇu*, in the same line, was that of a *Tushāra* king who conquered *Ghaṭōtkacha*, and who might be identified with the third *Kaṇva* or *Kaṇvāyana* prince *Nārāyaṇa*.¹ As is to be seen, however, in my lithograph now published, there is no foundation whatever for this; the *aksharas* were supposed to give the name of *Ghaṭōtkacha*, being, in reality, nothing but *dānav-āṅganā*, "(the women) of the demons;"² and *tushāra* here has no meaning but that of 'frost.'

TEXT.³

- | | | |
|---|--|--------------------------------------|
| 1 | Jitam ⁴ -abhtkshṇam=ēva | Jāmbavati-vadanāravind-ōrjijit-āḷinā |
| 2 | dānav-āṅganā-mukhāmbhōja-lakshmi-tushāreṇa | Vishṇunā (11) |
| 3 | Anēkapurushābhyāgat . āryyaSātvata . y ⁴ ōgachāryya . | |
| 4 | bhagavadbhakta-Yaśastrāta-prapautrasy-āchāryya-Vishṇutrāta- | |
| | pautrasy-āchāryya- | |
| 5 | Vasudatta-p[<i>u</i>]trasya Rāvanyām-utpannasya Gōtama- | |
| | sagōtrasy-āchāryy-ōpāddhyāya- | |
| 6 | Yaśastrāt-[ān]ujasy-āchāryya-Sōmatrātas-y-ēdam bhagavat- | |
| | pād-ōpayō- | |
| 7 | | iyam kuṇḍam-uparyy-āvasathaḥ ku- |
| 8 | | ṇḍam ch-āparam [11 ⁵] |

TRANSLATION.

Verily victory has been achieved again and again by (the god) *Vishṇu*, who is a mighty bee on the waterlily which is the face of *Jāmbavati*, (and) a very frost to (cause the withering of) the beauty of the waterlilies which are the faces of the women of the demons!

(Line 3.)—This reservoir, intended for the use of the feet⁶ of the *Divine One*, (and) the house above (it), and the second reservoir, (are the work) of the *Āchārya Sōmatrāta*,—the son of the son's son of *Yaśastrāta*, who was the successor of many men (of

¹ Mentioned, for instance, in the *Vishṇu-Purāṇa*, book IV. chap. xxiv.; F. E. Hall's edition of H. H. Wilson's Translation, Vol. IV. p. 192.—The *Tushāra*, *Tukhāra* or *Tushkhara* (? *Turushka*) kings are mentioned in the same volume, p. 203.

² From the original stone.

³ Over this *m*, there are the vowel-marks for *ē*. But they are not connected in any way with the *m*; and it is not apparent why they were made, as they cannot possibly stand for the syllable *ēm*, and they are altogether superfluous and unmeaning.

⁴ This *y* is rather an anomalous one; but the character cannot stand for anything else.


⁵ See page 123 above, note 3.

A—Tusam Rock Inscription.



SCALE 15

B—Deorisa Image Inscription




SCALE 50

C—Kasia Image Inscription



SCALE 50

D—Mathura Image Inscription - The Year 230



preceding generations); who was a highly esteemed Sātvata;¹ who was an Āchārya of the Yōga philosophy; and who was a devotee of the Divine One;—the son's son of the Āchārya Vishnubrāta;—the son, begotten on Rāvaṇ, of the Āchārya Vasudatta;—a member of the Gōtama gōtra;—(and) the younger brother of the Āchārya and Upādhyāya Yaśāstrāta.

No. 68; PLATE XL B.

DEORIYA STONE IMAGE INSCRIPTION.

THIS inscription was discovered in 1871-72 by General Cunningham, and was first brought to notice by him in 1873, in the *Archæol. Surv. Ind.* Vol. III. p. 48 f., where he published his reading of the text and a translation of it, accompanied by a lithograph (*id.* Plate xviii D).

Dēoriyā or Dēwariyā² is a small village on the right bank of the Jamnā, about eight miles towards the south-west of Arail or Arayal, the chief town of the Arail Parganā in the Karchhanā Sub-Division of the Allahābād District in the North-West Provinces. The inscription is on the pedestal of a stone standing image of Buddha,—draped, and with small attendant figures kneeling at his feet, one on the right side, and two on the left,—that was found at this village. When I examined the image, it was in the Government Museum at Allahābād; but it is now, I understand, in the Provincial Museum at Lucknow.

The writing, which covers the whole front of the pedestal, about 1' 1" broad by 2½" high, is in a state of good preservation throughout.—The size of the letters varies from ⅙" to ⅙". The characters belong to the northern class of alphabets.—The language is Sanskrit; and the whole inscription is in prose.—The orthography presents nothing calling for remark.

The inscription does not refer itself to the reign of any king, and is not dated; it may be allotted, however, on palæographical grounds, to about the fifth century A.D. It is a Buddhist inscription; and the object of it is to record the gift, by a Śākya mendicant named Bōdhivarman, of the statue, on the pedestal of which it is engraved.

TEXT.

- 1 Dēya-dharmnō-yarṇ Śākya-bhikshō[r*]-Bōdhivarmmanāḥ [1*] Yad-atra
 puṇya[m*]
 2 tad'-bhava[tu*] mātāpitrō[h*] sarvva-sat[t*]vānāṃ ch-ānut[t*]ara-jñān-
 āvāptayē [11*]

¹ Sātvata is explained in Monier Williams' Sanskrit Dictionary as being a name of Vishnu or Kṛishṇa, and also of a people, inhabiting a district in Central India, said to be the descendants of outcaste Vaiśyas.—It seems to be, as used here, the name of some special sect of Vaiśnavas or Bhāgavatas, probably from Central or Southern India.

² The 'Deoriya and Deorya' of maps. Indian Atlas, Sheet No. 88. Lat. 25° 19' N.; Long. 81 51' E.—Dr. Bhagwanlal Indrajī writes the name 'Dēvaliā' (*Jour. Bo. Br. R. As. Soc.* Vol. XVI. p. 354).

³ From the original stone.

⁴ This *ś* was at first omitted, and was then inserted above the line.

TRANSLATION.

This (*is*) the appropriate religious gift of the Śākya *Bhikṣu* *Bôdhivarman*. Whatever religious merit (*there is*) in this (*act*), let it be for the acquisition of supreme knowledge by (*his*) parents and by all sentient beings.

No. 69; PLATE XLC.

KASIA STONE IMAGE INSCRIPTION.

THIS inscription was discovered in 1875-76 or 1876-77 by Mr. A. C. L. Carlleyle, and was first brought to notice by him in 1883, in the *Archæol. Surv. Ind.* Vol. XVIII. p. 59, where he published his reading of the text and proposed interpretation of it, followed (*id.* p. 60, note 1) by my own reading of the text (of course mutilated in publication), and my translation as it then suggested itself to me.

*Kasiâ*¹ or *Kasyâ* is a village thirty-four miles due east of Gôrâkhpur, in the Padraunâ² Tahsil or Sub-Division of the Gôrâkhpur District in the North-West Provinces; and is the head-quarters of a Joint-Magistrate in charge of a Sub-Division of the District. The inscription is below the figure of a man, sitting in a squatting position, on the lower part of the western side of the pedestal of a colossal stone statue of Buddha, recumbent in the act of attaining *nirvâna*, which was found by Mr. Carlleyle in the course of excavations in a large mound of ruins at this village.

The writing, which covers a space of about 1' 3½" broad by 2½" high, is in a state of very good preservation, except that the name of the sculptor is partially illegible in line 2.—The average size of the letters is about ⅞". The characters belong to the northern class of alphabets.—The language is Sanskrit; and the whole inscription is in prose.—The orthography presents nothing calling for remark.

The inscription does not refer itself to the reign of any king, and is not dated; on palæographical grounds, however, it may be allotted to about the end of the fifth century A.D. It is a Buddhist inscription; and the object of it is to record the gift, by a *Mahāvihārasvamin*³ named *Haribala*, of the figure below which it is engraved.

TEXT.⁴

1	Dēya-dharmmô-yaṃ	mahāvihārasvaminô	Haribalasya	1
2	Pratimâ	ch-ēyaṃ	ghaṭitâ	Dinē .. mā(?)śvarēṇa 1(11)

¹ The 'Kasia, Kassia, Kasya, Kesiya, and Kusya,' of maps, &c. Indian Atlas, Sheet No. 102. Lat. 26° 45' N.; Long. 83° 58' E.

² The 'Paraona, Paruna, and Pudrownan,' of maps, &c.

³ *Mahāvihārasvamin*, *lit.* 'a great master (superintendent) of a *vihāra*,' is evidently a technical religious title of office, denoting the officer who came, in the management of a *vihāra*, next above the *Vihārasvamin* or 'masters (superintendents) of the *vihāra*.' The latter title occurs in the Sābhi pillar inscription No. 73 below, Plate xlii A.

⁴ From Mr. Carlleyle's ink-impression; so also the lithograph.

TRANSLATION.

This (is) the appropriate religious gift of the *Mahāvihārasvāmin* Haribala. And this image has been fashioned by Dinē .. māsvara (?)

No. 70; PLATE XLD.

MATHURA STONE IMAGE INSCRIPTION.

THE YEAR 230.

THIS inscription was discovered by General Cunningham, and was first brought to notice in 1871, in the *Four. R. As. Soc. N. S. Vol. V. p. 185*, where Professor J. Dowson published his reading of the text, and a translation of it, accompanied by a lithograph (*id. Plate ii. No. 9*) reduced from General Cunningham's ink-impression.—And this rendering of the inscription was reprinted, with a few corrections, in 1873, in the *Archaeol. Surv. Ind. Vol. III. p. 37*, accompanied by a fresh lithograph (*id. Plate xvi. No. 23*).

This is another inscription from **Mathurā**,¹ the chief town of the Mathurā District in the North-West Provinces; and is on the pedestal of a stone standing statue of Buddha, draped, and with a nimbus behind his head and shoulders, that was found in the Katrā² mound. When I examined it, it was in the Government Museum at Allahābād; but it is now, I understand, in the Provincial Museum at Lucknow.

The writing, which covers a space about 1' 4½" broad by 2" high on the upper part of the face of the pedestal, is in a state of fairly good preservation.—The average size of the letters is about ⅜". The characters belong to the northern class of alphabets. They include, in line 2, forms of the numerical symbols for 30 and 200. In the *rya* of *bhaḥḥāyār-yad*, line 1, we have to notice that the *r* is formed on the line of writing, with a single *y* below it. And the same method of forming the *r* is followed in *dharmā* and *rjaya*, though not in *sarvva*, in the same line.—The language is Sanskrit; and the whole inscription is in prose.—The orthography presents nothing calling for remark.

The inscription does not refer itself to the reign of any king. But its date, in numerical symbols, is the year two hundred and thirty (A.D. 549-50), without any further details. It is a Buddhist inscription; and the object of it is to record the gift, by a Śākya female mendicant named **Jayabhaddā**, to a monastery called the **Yasāvihāra**, of the image on the pedestal of which it is engraved.

TEXT.³

- 1 Dēya-dharmo-yam **Yasā(śō)vihārē** Śākya-bhikṣuṇyār-Jayabhaddāyār-
Yad'-atra puṇyam tad-bhāvatu sarvva-sa-
2 tvanam⁴-anuttara-jñān āvāptayē 1(11) Samvatsarāḥ 200 30 1(11),

¹ See page 26 above, and note 2.

² See page 26 above, note 1.

³ From the original stone.

⁴ Read *bhikṣuṇyā Jayabhaddāyāḥ* || *Yad*.

⁵ Read *sattvadam*.

TRANSLATION.

This (*is*) the appropriate religious gift, at the (monastery called) **Yasôvihâra**, of the Śākya *Bhikṣuṅ* **Jayabhaddâ**. Whatever religious merit (*there is*) in this (*act*), let it be for the acquisition of supreme knowledge by all sentient beings! The year 200 (*and*) 30.

No. 71; PLATE XLIA.

BODH-GAYA INSCRIPTION OF MAHANAMAN.

THE YEAR 269.

THIS inscription, which was published by me, for the first time, quite recently, in the *Ind. Ant.* Vol. XV. p. 356 ff., is from a stone-tablet that was discovered in the course of the excavations made by General Cunningham and Mr. J. D. M. Beglar at **Bôdh-Gayâ**,¹ the famous Buddhist site about five miles due south of Gayâ, the chief town of the Gayâ District, in the Bengal Presidency. The original stone is now in the Imperial Museum at Calcutta.

The stone has the appearance of having been originally set in a socket about three inches deep, and morticed at the sides into a building. The front surface measures about 1' 7½" broad by 1' 6" high. Below the inscription, towards the proper right side of the stone, there are engraved in outline a cow and a calf, standing towards, and nibbling at, a small tree or bush; the tips of the ears of the cow are discernible in the lithograph, below the commencement of line 14.—The writing, which is in the upper part of the stone, and covers a space of about 1' 7½" broad by 1' 0" high, including a margin of about an inch all round, is in a state of perfect preservation almost throughout.—The average size of the letters is about ¼". The characters belong to the northern class of alphabets. The form of *y*, throughout this inscription, is a slightly older variety of the fully developed *Devanâgarî* form exhibited throughout the Aphaṣṭ inscription of *Ādityasēna*, No. 42 above, page 200. In the conjunct letter *ry*, in *yatir-yatah*, line 7, we have to note that the *r* is formed on the line, with a single *y* below it. The characters include, in the last line, forms of the numerical symbols for 7, 9, 60, and 200.—The language is Sanskrit; and, except for the opening symbol representing *ōm*, and for the date at the end, the inscription is in verse throughout.—In respect of orthography, the only points calling for notice are (1) the occasional doubling of *k* and *t*, in conjunction with a following *r*, e.g. in *chakkraṣ*, line 13; *tantra*, line 2; and *chaitra*, line 14; and (2) the use of *v* for *b* throughout, e.g. in *vandhu*, lines 2 and 8; *vabhāva*, line 6; and *vôdhi*, lines 10 and 12.

The inscription does not refer itself to the reign of any king. Its date, in numerical symbols,² is the year two hundred and sixty-nine (A.D. 588-89), on the seventh

¹ The 'Bodh-Gya and Buddh-Gaya' of maps, &c. Indian Atlas, Sheet No. 104. Lat. 24° 41' N., Long 85° 2' E.

² As regards the third symbol in the years, 9, it occurs as the second symbol, in the record of the day, in line 9 of the *Bhumarkî* pillar inscription of the *Mahârâj*as Hastin and Śarvanâtha, No. 24 above; in connection with which instance, I remarked (page 110, note 2) that, though it resembles most a rather straight and upright form of the symbol for 9, yet it might possibly be 7 or 8. I also

solar day of the bright fortnight of the month Chaitra (March-April). It is a Buddhist inscription. And the object of it is to record the erection, by a certain **Mahānāman**,—the second of that name mentioned in this inscription,—of a mansion of Buddha, *i.e.* a Buddhist temple or monastery, at the **Bōdhimaṇḍa**, or, rather, within the precincts of it; *i.e.* at the modern **Bōdh-Gayā**.

With regard to the places mentioned in this inscription, **Lankā** is, of course, one of the most well-known names of **Ceylon**. And General Cunningham tells me that **Āmrāvīpa**, 'the mango-island,' is another of its names, derived from its resemblance in shape to a mango. **Bōdhimaṇḍa** is the name of the miraculous throne under the *bōdhi*-tree at **Bōdh-Gayā**, also called the *vajrasana* or 'diamond-throne,' on which Buddha and his predecessors sat, when attaining *bōdhi* or perfect wisdom.¹ And Professor Childers, in his Pāli Dictionary, added that he inferred that the term was also applied to the raised terrace built under the *bōdhi*-tree within the precincts of any Buddhist temple, in imitation, presumably, of Buddha's throne. This, rather than the throne itself, seems to be its meaning in the present inscription.

The chief interest of this inscription, lies in the probability that the second **Mahānāman** mentioned in it, is the person of that name who composed the more ancient part of the Pāli *Mahāvamsa*, or history of Ceylon. If this identification is accepted, it opens up a point of importance in the question of dates. On the one hand, there can be no doubt that the date of the present inscription has to be referred to the Gupta era, with the result of A.D. 588-89. On the other hand, from the Ceylonese records, Mr. Turnour arrived at A.D. 459 to 477 as the period of the reign of Mahānāman's nephew (sister's son) **Dhātusēna**,² and it was during his reign that **Mahānāman** compiled the history.

then considered that the same symbol occurs, in the record of the day, in the Khōh grant of the *Mahārāja Saṅkshōbha*, No. 25, above; in line 24 of which (page 115) I accordingly read the solar day as 29. Mr. Sh. B. Dikshit, however, has found, by actual calculation, that the thirteenth lunar day of the bright fortnight of Chaitra, which is mentioned in line 2 f. of that record (page 114), was the twenty-seventh solar day in the month. Accordingly, the symbol which we have there, in line 24, must be interpreted as 7; not 9.—On fuller consideration of the whole matter, with the help of Mr. Sh. B. Dikshit's calculation, I find that, in the three passages, we are concerned with two separate symbols; not one and the same.—One is the symbol which is the third in the years of the present inscription of Mahānāman, and the second in the record of the day in the Bhumarā pillar inscription; and I see no reason to alter my original opinion, that it is a rather straight and upright form of the symbol for 9. A sign extremely like it occurs, it is true, in the date of the Mōrbī grant (*Ind. Ant.* Vol. II. p. 258, and Plate, line 19), where the record in words compels us to interpret it as 8; but it is there a decimal figure, not a numerical symbol; and that record also comes from a far distant part of the country; so that we are not bound to adopt the same interpretation in the present instance.—The other symbol is the second in the record of the day in the grant of Saṅkshōbha. And an examination of the lithograph (Plate xv B.) will shew, that it really differs from the symbol which I interpret as 7 through a slight mark below it, which, being a little detached from it, I took originally to be a rust-mark, and not part of the symbol itself. Taking it now as part of the symbol itself, it makes the symbol identical with, though in execution somewhat inferior to, the symbol for the day in the present inscription of Mahānāman; and, accordingly, the symbol for the day here must now be interpreted as 7; not as 8, which I took it to be in my original version of this inscription.—The same symbol occurs also in lines 19 and 21 of the Nēpāl inscription of Jishugupta (*Ind. Ant.* Vol. IX. p. 172, and Plate); and it was Dr. Bhagwanlal Indraji's interpretation of it there as 8, which led me to read it originally as 8 in the present instance.

¹ See, amongst other authorities, Beal's *Buddhist Records of the Western World*, Vol. II. p. 116.

² See Turnour's *Mahavamsa*, pp. ii. liv. lxii. 254 ff.; and *Four. Beng. As. Soc.* Vol. VII. p. 92

The recorded date of the present inscription, therefore, shews,—if the identification suggested above is accepted,—either that the details of the Ceylonese chronology are not as reliable as they have been supposed to be; or else that a wrong starting-point has been selected in working them out, and that they now require considerable rectification.

TEXT.¹

- 1 Om [11²] Vyāpt³ yēn-ā-pramēyah sakala-śāsi-ruchā sarvvataḥ sat[⁴]va-
dhātuḥ kahunnāḥ pāshaṇḍa-yōdhās-sugati-patha-rudhas-tarkka-śastr-
ābhīyuktāḥ sampūrnō
- 2 dharmma-kōshah prakṛiti-ripu-hṛitah sādhitō lōka-bhūtyai⁵ śāstuh Śāky-aika-
va(ba)ndhōr-jjayati chiratarah tad-yaśas-sāra-tantram || Nairōdhit⁶
śubha-bhāvānā-
- 3 m-anusritah samsāra-samklēsa-jin-Maitrēyasya karē vimukti-vaśitā yasy-
ādbhutā vyākṛitā | nirvān-āvasarē cha yēna charanau dṛiṣṭau munēḥ
- 4 pāvanau⁷ pāyād-vaḥ sa munīndra-śāsana-dharah stutyō⁸ Mahā-Kāsyapaḥ ||
Samyukt-āgaminō viśuddha-rajasaḥ sat[⁴]v-ānukamp-ōdyatāḥ śiṣhyā
- 5 yasya sakṛid-vichēsur-amalām Laṅk-āchal-ōpatyakām tēbhyaḥ śīla-gun-
ānvitās-cha śataśah śiṣhya-prāśiṣhyāḥ kramāj-jātās-tunga-narēndra-
- 6 varṣa-tilakāḥ prōtsriyya rājya-īriyam || Dhyān-ōday-āhita-hitaḥ śubh-
āsubha-vivēkakṛid-vihata-mōhaḥ sad-dharm-ātula-vibhavō Bhavō
va(ba)bhūva
- 7 śramapas-tataḥ || Rāhul⁹-ākhyās-cha tach-chhishya U¹⁰pasēnō yatir-yataḥ
Mahānāmā kramād-ēvam-U¹⁰pasēnas-tatō-parah || Vātsalyam¹¹ śaraṇ-ā-
- 8 gatasya satatam dīnasya vaiśēhikam vyāpat-śāyaka-santati-kshata-dhṛitēr-
ārttasya ch-āpatyakam | krūrasy-āhita-kāripaḥ pravītatam va(ba)ndhōr-
yathā-
- 9 bhāvataḥ ēvam sach-charit-ōdbhavēna yaśasā yasy-āchitam bhūtarah ||
Āmradvip¹²-ādhipasī prithu-kula-jaladhīst-tasya śiṣhyō mahīyān
- 10 Laṅkā-dvīpa-prasūtaḥ para-hita-nirataḥ ssn-Mahānāma-nāmā | tēn-ōchchair-
Vvō(bō)dhimaṇḍē śāsi-kara-dhavalah sarvvatō maṇḍapēna¹³
- 11 kāntah prāsāda ēsha Smara-va(ba)la-jayinah kārītō lōka-śāstuh ||
Vyapagata¹⁴-vishaya-snēhō hata-timira-daśah pradīpa-vad-a-saṅgaḥ
- 12 kuśalēn-ānēna janō vō(bō)dhi-sukham-anuttaram bhajatām || Yāvad¹⁵-
dhvānt-āpahārī pravītata-kiraṇah sarvvatō bhāti bhāsvān-yāvat-pārṇṇō-
mvu(mbu)-

¹ From the original stone.² Metre, Sragdhara.³ This mark of punctuation is unnecessary.⁴ Metre, Śārdūlavikṛīḍita; and in the following verse.⁵ This mark of punctuation is unnecessary.⁶ My original reading was *stutyai*. I owe the correction, as also that of *amaldm*, for *atuldān*, in line 5, to the kind suggestion of Dr. Kielhorn.⁷ Metre, Āryā.⁸ Metre, Śīlōka (Anushtubh).⁹ From the vowel *ś* being partially engraved over this *n*, the engraver seems to have begun to form the *ś* here.¹⁰ Metre, Śārdūlavikṛīḍita.¹¹ Metre, Sragdhara.¹² This mark of punctuation is unnecessary.¹³ Metre Āryā¹⁴ Metre, Sragdhara.

- 13 rāṣīḥ phaṇi-phaṇa-kuṭilair-ūrmī-chakkrais-samantāt yāvach-ch-Ēndr-ādhivāso
 vividha-maṇi-śilā-charu-sringaḥ Sumeruḥ śōbh-āḍhyam
 14 tāvad-étad-bhavanam-uru-munēḥ śāśvatatvam-prayātu ॥ Samvat 200 60 9
 Chaitra śu dī¹ 7 ॥

TRANSLATION.

Om ! Victorious for a very long time is that doctrine, replete with fame, of the Teacher, the chief kinsman of the Śākya, by which, lustrous as the full-moon, the inscrutable primary substance of existence has been pervaded in all directions ; by which the warriors, who are heretics, obstructive of the path of beatitude, have been broken to pieces, being assailed with the weapon of logic ; (*and*) by which the whole treasure of religion, that had been stolen by the enemy which is original nature, has been recovered for the welfare of mankind !

(Line 2).—May he, **Mahā-Kāśyapa**, who is worthy of praise, protect you,—he who observed the precepts of (Buddha) the chief of saints ; who practised that auspicious habit of abstract meditation which is of the nature of a trance ; who overcame the anguish of successive states of existence ; whose wonderful subjugation of the passions in final emancipation (*is to be*) displayed in the hand of Maitrēya,² and by whom the two pure feet of (Buddha) the saint were beheld at the time of attaining *nirvāṇa* !³

(L. 4).—His disciples, endowed with a connected tradition of doctrine, purified as to (*their*) emotions, (*and*) active in compassion for existing beings, roamed at one time over the stainless country at the feet of the mountains of **Laṅkā** ; and in succession from them there were born, in hundreds, disciples and disciples' disciples, possessed of the virtue of (*good*) character, who, without the glory of (*actual*) sovereignty, were the ornaments of a lofty race of kings.

(L. 6).—Then there was the **Śramaṇa Bhava**, whose welfare was effected by the development of abstract meditation ; who discriminated between good and evil ; who destroyed error ; (*and*) who possessed an unequalled wealth of true religion.

(L. 7).—And his disciple (*was*) he who had the name of **Rāhula** ; after whom (*there came*) the ascetic **Upasēna (I.)** ; then in succession (*there was*) **Mahānāman (I.)** ; (*and*) after him another **Upasēna (II.)**, whose special characteristic of affection, of the kind that is felt towards offspring,—for any distressed man who came to him for protection, and for any afflicted person whose fortitude had been destroyed by the continuous flight of the arrows of adversity,—extended, in conformity with the disposition of a kinsman, (*even*) to any cruel man who might seek to do (*him*) harm ; (*and*) by whose fame, arising from good actions, the whole world was thus completely filled.

¹ As regards the interpretation of the symbol for the day, see page 274 above, note 2.

² Maitrēya is a Bōdhisattva, at present in the Tushita heaven, who is to be the next Buddha. And the present passage, which is rather obscure, is perhaps explained by the injunction which Buddha, when on the point of attaining *nirvāṇa*, gave to Mahā-Kāśyapa, to deliver over his *kāśīya* or yellow robe (and with it the transmission of the Buddhist doctrine) to Maitrēya, when he should attain the condition of a Buddha (see Beal's *Buddh. Rec. West. World*, Vol. II. p. 142 ff.)

³ Mahā-Kāśyapa was seated in meditation, when suddenly a bright light burst forth, and he perceived the earth shaking. And then, exerting his divine sight in order to ascertain what wonderful event was indicated by this portent, he saw Buddha in the act of entering on *nirvāṇa* (see *id.* Vol. II. p. 161).

(L. 9.)—His disciple, greater (*even than himself*), (*is*) he who has the excellent name of **Mahānāman** (II.); an inhabitant of **Āmradvīpa**; a very ocean of a mighty family; born in the island of **Lankā**; delighting in the welfare of others;—by him this beautiful mansion of the Teacher of mankind, who overcame the power of (the god) Smara,¹—dazzling white as the rays of the moon, with an open pavilion on all sides,—has been caused to be made at the exalted **Bōdhimaṇḍa**.

(L. 11.)—By means of this appropriate (*action*), let mankind,—freed from attachment to worldly things; having the condition of (*mental*) darkness dispelled; (*and*), like (*the flame of*) a torch, having no adhesion (*to material objects*),—enjoy the supreme happiness of perfect wisdom!

(L. 12.)—As long as the sun, the dispeller of darkness, shines in all directions with diffused rays; as long as the ocean (*is*) full on all sides with its circles of waves that are curved like the hoods of hooded snakes; and as long as (the mountain) Sumēru, the abode of (the god) Indra, has its summits made beautiful by various jewelled slabs, in such a way as to be full of lustre,—so long let this temple of the great saint attain the condition of being everlasting!

(L. 14.)—The year 200 (*and*) 60 (*and*) 9; (the month) Chaitra; the bright fortnight; the day² 7.

No. 72; PLATE XLI B.

BODH-GAYA IMAGE INSCRIPTION OF MAHANAMAN.

THIS inscription, which, also, was published by me quite recently, for the first time, in the *Ind. Ant.* Vol. XV. p. 359, is from the pedestal of a Buddhist image that was discovered in the excavations made by General Cunningham and Mr. Beglar at **Bōdh-Gayā**,³ in the Gayā District in the Bengal Presidency.

The **writing**, which covers a space of about 1' 8½" broad by 1¼" high, is in a state of almost perfect preservation.—The average **size** of the letters is about ¼". The **characters** belong to the northern class of alphabets, and are of precisely the same type with those of the preceding inscription of Mahānāman.—The **language** is Sanskrit; and the inscription is in prose.—The **orthography** presents nothing calling for remark.

The **inscription** does not refer itself to the reign of any king, and is not dated; but the characters allot it to precisely the same time with the preceding Bōdh-Gayā inscription of Mahānāman, of A. D. 588-89. It is a Buddhist inscription. And the object of it is to record the presentation of the statue, on the pedestal of which it is engraved, by a *Sthavira* named **Mahānāman**, who is obviously the second Mahānāman mentioned in the preceding inscription.

As pointed out to me by General Cunningham, this inscription shews that **Mahānāman** must have been at least thirty years old when he visited Bōdh-Gayā; by the Buddhist rules, he could not receive the *upasampadda*-ordination, before attaining the age

¹ This refers generally to the subjugation of the passions; but also specially to the temptation by Māra, or Love as the Destroyer, which is referred to in *Buddh. Rec. West. World*, Vol. II. p. 69 ff.

² As regards the interpretation of the symbol for the day, see page 274 above, note 2.

³ See page 274 above, and note 1.

of twenty years; and, after that, he would have to wait at least ten or twelve years, before he could be invested with the title of *Sthavira* or *Thēra*. A further point to be noted, is, that Mahānāman's visit to Bôdh-Gayā probably occurred before the time when Dhātusēna became king of Ceylon,—during the flight of the uncle and nephew to avoid the persecution of the usurper Pāpdu; according to Mr. Turnour's deductions, this was between A.D. 434 and 439.

TEXT:

1 Ōm Dēya-dharmmō-yam Śākya-bhikshōh Amradvīpa-vāsi-sthavira-
Mahānāmasya¹ [11^o] Yad-atra punyam tad-bhavatu sarvva-
sat[²]vānām-anuttara-jñān-āvāptayē-stu³ [11^o]

TRANSLATION.

Ōm! This (is) the appropriate religious gift of the Śākya *Bhikshu*, the *Sthavira* *Mahānāman*, a resident of *Āmradvīpa*. Whatever religious merit (*there is*) in this (*act*), let it be for the acquisition of supreme knowledge by all sentient beings!

No. 73; PLATE XLII A.

SANCHI STONE PILLAR INSCRIPTION.

THIS inscription was discovered by General Cunningham, and was first brought to notice by him in 1854, in his *Bhilsa Topes*, p. 199, where he published his reading of it, accompanied by a lithograph (*id.* Plate xxi. No. 199).

This is another inscription from *Sāñchi*,¹ in the Diwān, Sub-Division of the Bhōpāl State in Central India. It is on the north side of part of a small monolith round pillar, broken, that stands a few yards to the north-east of the eastern gateway of the great *Stūpa*.

The writing covers a space of about 10" broad by 2½" high. Except for the first three letters, which are very much damaged, it is in a state of fairly good preservation, as far as it goes. But it is only a fragment; the concluding part of it being broken away and lost.—The average size of the letters is about ⅜". The characters belong to the southern class of alphabets.—The language is Sanskrit; and the inscription is in prose.—In respect of orthography, we have to notice the doubling of *t*, in conjunction with a following *r*, in *putra*.

The inscription does not refer itself to the reign of any king, and is not dated. But, on palæographical grounds, it may be allotted roughly to the fifth century A.D. It is evidently the remnant of a Buddhist inscription; and its object seems to have been to record the gift of the pillar, on which it is inscribed, by a *Vihārasvāmin*,² the son of

¹ From Mr. J. D. M. Beglar's ink-impression; so also the lithograph.

² Read *mahānāmasya*.

³ This *stū* (*astū*) is redundant, as we have already had *bhavatu*. The same redundant *astū* occurs also in line 3 of the Bôdh-Gayā image inscription, No. 76 below, page 282.

⁴ See page 29 above, and note 2.

⁵ *Vihārasvāmin*, *lit.* 'master of a *vihāra*,' is a technical religious title of office, applied to certain functionaries who came next in rank below the *Mahāvihārasvāmin*; see page 272 above, note 3.

Gôôrasimhabala, whose name is partially destroyed, only the first two syllables, **Rudra**, remaining.

TEXT.¹

1 A(?)ka .. vihárasvâmi-Gôôrasimhabala-puttra-**Rudra**

TRANSLATION.

..... the *Vihdrasvâmin Rudra*, the son of Gôôrasimhabala

No. 74; PLATE XLII B.

CALCUTTA MUSEUM STONE IMAGE INSCRIPTION.

THIS inscription, which has not been previously brought to notice, is from the pedestal of a sandstone image that is in the Imperial Museum at Calcutta. The image seems to have been originally a standing statue of Buddha; but the whole of the upper part of it, above the ankles, is broken away and lost. I have no information as to where it was found.

The **writing**, which covers a space of about 9½" broad by 2½" high, is in a state of fairly good preservation, as far as it goes; but it is only a fragment; the conclusion of it, in the third line, having been cut away, apparently in trimming the stone for some building purpose.—The **size** of the letters varies from ¼" to ⅞". The **characters** belong to the northern class of alphabets.—The **language** is Sanskrit; and the inscription is in prose.—In respect of **orthography**, we have to notice the doubling of *t*, in conjunction with a following *r*, in *attra* and *pittrôh*, line 2.

The **inscription** does not refer itself to the reign of any king, and is not dated; but, on palæographical grounds, it may be allotted roughly to the fifth century A.D. It is a Buddhist inscription. And the object of it is to record the gift, by a Śākya mendicant named **Dharmadâsa**, of the image on the pedestal of which it is engraved.

TEXT.¹

1 Dêya-dharmô-yam Śākya-bhikshôr=**Dharmadâsasya** [1^o] ya-
2 d-attra punyam tan²-mâtâpittrô[h^o] sarva-sat[1^o]vânâh ch-â-
3 [nuttara³-jñân-âvâptayê-stu ||]

TRANSLATION.

This (1s) the appropriate religious gift of the Śākya **Bhikshu Dharmadâsa**. Whatever religious merit (*there is*) in this (*act*), [let] it [be for the acquisition of supreme knowledge] by (*his*) parents and by all sentient beings.

¹ From the original pillar

² From the original stone.

³ This *n* was at first omitted, and then inserted above its proper place.

⁴ This last line has been entirely cut away and lost, apparently in trimming the stone for some building purpose

A.—Sanchi Pillar Inscription



SCALE 50

B.—Calcutta Museum Image Inscription



SCALE 50

C.—Sarnath Inscription.



SCALE 50

D.—Bodhi-vaya Image Inscription.



SCALE 1

W. GIBSON, PHOTO-LITH.

J. W. FLEET, SO. C.B.

No. 75; PLATE XLII C.

SARNATH STONE INSCRIPTION.

THIS inscription was discovered by General Cunningham, and was first brought to notice by him in 1871, in the *Archæol. Surv. Ind.* Vol. I. p. 123, and Plate xxxiv. No. 4.

Sárnâth is the modern name of a large collection of Buddhist ruins, about three and a half miles north of Benares (properly Banâras or Baṅâras), the chief town of the Benares District in the North-West Provinces. The inscription is below a sandstone bas-relief representation of three scenes in the life of Buddha, that was found here in the course of excavations. The original stone is now in the Imperial Museum at Calcutta.

The **writing**, which covers a space of about 1' 1 $\frac{3}{8}$ " broad by 2 $\frac{1}{2}$ " high, is in a state of fairly good preservation throughout.—The average **size** of the letters is about $\frac{1}{8}$ ". The **characters** are a peculiarly square variety of the northern alphabet.—The **language** is Sanskrit; and the inscription is in verse.—The **orthography** presents nothing calling for remark.

The **inscription** does not refer itself to the reign of any king, and is not dated. But, on palæographical grounds, it may be allotted roughly to the fifth century A.D. It is a Buddhist inscription; and the object of it is to record that the sculpture, below which it is engraved, was made by the order of a religious mendicant named **Harigupta**.

TEXT.¹

- 1 Guruh² pûrvvaṅgamam kṛtvâ 1³ mâtaram pitaram tathâ 1 kâritâ
2 pratimâ śâstuh 1³ **Hariguptēna** bhikṣuṣâ 11

TRANSLATION.

Having placed first (*in the order of those who are to acquire religious merit from this act*) (*his*) spiritual preceptor and (*his*) mother (*and*) father, this image of the Teacher has been caused to be made by the *Bhikṣu Harigupta*.

No. 76; PLATE XLII D.

BODH-GAYA STONE IMAGE INSCRIPTION.

THIS inscription, which does not appear to have been previously brought to notice, is from the pedestal of a Buddhist stone statue that was found by General Cunningham and Mr. Beglar in their excavations at **Bôdh-Gayâ**,³ in the Gayâ District in the Bengal Presidency. The original statue is now in the Imperial Museum at Calcutta.

The **writing**, which covers a space of about 1' 11" broad by 2" high, towards the top of the pedestal, is in a state of very good preservation throughout.—The average

¹ From the original stone.² Metre, Ślôka (Anuṣṭubh).³ and ⁴ In each case, the mark of punctuation is unnecessary.⁴ See page 274 above, and note 1.

size of the letters is about $\frac{1}{16}$ ". The characters belong to the northern class of alphabets; and are of almost precisely the same type as those of the Bôdh-Gayâ image inscription of Mahânâman, No. 72 above, page 278, Plate xli B. But, as contrasted with the form in Mahânâman's inscription of the year 269, No. 71 above, page 274, Plate xli A., we have to notice that, in conjunction with a following *y*, the *r* is here formed above the line, and the *y* is doubled.—The language is Sanskrit; and the inscription is in prose.—In respect of orthography, the only point that calls for notice is the doubling of *t*, in conjunction with a following *r*, in *attra*, line 1.

The inscription does not refer itself to the reign of any king, and is not dated; but, on palæographical grounds, it may be allotted roughly to the sixth century A.D. It is a Buddhist inscription; and the object of it is to record the grant, by two Śākya mendicants named Dharmagupta and Damaśhṛasēna, natives of Tishyâmrâtirtha, of the statue on the pedestal of which it is engraved.

TEXT.¹

- 1 Om Dēya-dharmô-yam Śākya-bhikshvôs-Tishyâmrâtirtha-vāsika-
Dharmma₂gupta-Damaśhṛasēnayôr-Yyad-attra puṇya[m] tad-bhavatu
mâtâpī[ta*]rāv-âchâryy-ôpâdhyâyau pûrvvaṅgama[m] kṛitvâ
2 sarvva-satvanâm³-anuttara-jñân-âvâptayê-stu⁴ ||

TRANSLATION.

Om! This (is) the appropriate religious gift of the two Śākya *Bhikshus*, *Dharmagupta* and *Damaśhṛasēna*, residents of *Tishyâmrâtirtha*. Whatever religious merit (*there is*) in this (*act*), let it be for the acquisition of supreme knowledge by all sentient beings, after (*their*) parents and (*their*) *Āchârya* and *Upâdhyâya*.

No. 77; PLATE XLIIIA.

LAHOR COPPER SEAL INSCRIPTION OF THE MAHARAJA MAHESVARANAGA.

THIS inscription, which has not been previously brought to notice, is from a copper seal that was obtained by General Cunningham from a native dealer at Lâhôr,¹ the chief town of the Lâhôr District in the Pafjâb. It is not known where it was originally found. I obtained it, for examination, from General Cunningham.

The seal is on an exaggerated signet-ring, in shape closely resembling the ordinary English pattern, of the kind which may still be seen worn loosely on the thumbs of the ministers of Native States. From the flat surface of the seal, to the bottom of the ring, it is about $1\frac{1}{2}$ " high. The flat surface of the seal is about $\frac{1}{16}$ " thick, and slightly oval in shape, about $1\frac{1}{2}$ " by $1\frac{1}{8}$ ". At the top there is a bull, recumbent to the proper left, with a crescent moon in front of its face; below this, a straight line, turned up at each end; below

¹ From the original stone.

² Read *sattvodâm*

³ This *stû* (*astû*) is redundant, as we have *bhavatu* in line 1; see page 279 above, note 3.

⁴ The 'Lahore' of maps, &c. Indian Atlas, Sheet No. 30. Lat. 31° 34' N.; Long. 74° 21' E

this, the legend, in two lines, of which the text and translation are given below; and, at the bottom, a curved line, which is evidently intended for a *nda* or hooded snake. The legend is in reverse in the original, so as to give a direct impression on documents; and it is evidently for some purpose or other of this kind that the seal was used. I give a direct representation of it in the lithograph.—The weight of the seal and ring is about $2\frac{1}{2}$ oz.—The characters belong to the northern class of alphabets.—The language is Sanskrit; and the legend is in prose.—The orthography presents nothing calling for remark.

The inscription simply records the name of the *Mahārāja Mahēśvaranāga*, the son of *Nāgabhatta*, belonging, it may be presumed, to a branch of the well-known *Nāga* family or tribe. On palæographical grounds, it may be referred roughly to about the end of the fourth century A.D.

TEXT.¹

- 1 Mahārāja-Nāgabhatta-
- 2 putra-Mahēśvaranāga

TRANSLATION.

The *Mahārāja Mahēśvaranāga*, the son of *Nāgabhatta*.

No. 78; PLATE XLIII B.

ROHTASGADH STONE SEAL-MATRIX OF THE
MAHASAMANTA SASANKADEVA.

THIS inscription, which has not been previously brought to notice, was discovered by Mr. Beglar cut in the rock at the hill-fort of *Rōhtāsgadh* or *Rōhitāsgadh*,² twenty-four miles south by west of *Sahasrām*,³ the chief town of the *Sahasrām* Sub-Division of the *Shāhābād* (*Ārā*) District in the Bengal Presidency.

In the upper part, there is a somewhat damaged representation of a bull, recumbent to the proper right, and below this, separated by a line about $\frac{1}{8}$ " broad, the legend, in two lines, of which the text and translation are given below; the whole being enclosed in a circle, about $4\frac{1}{2}$ " in diameter, with a breadth of circumference varying from $\frac{1}{4}$ " to $\frac{1}{2}$ ". I give a direct representation in the lithograph. But the original, on the rock, is in reverse; and, with the bull, the circular surrounding line, and the line across the surface, the legend is countersunk, not in relief. It is plain that what we have here, is a mould or matrix, for casting copper-seals in relief, to be attached to copper-plate charters.—The average size of the letters is about $\frac{1}{8}$ ". The characters belong to the northern class of alphabets.—The language is Sanskrit; and the legend is in prose.—The orthography presents nothing calling for remark.

¹ From the original seal.

² The 'Rhotasgarh and Rohitagarh' of maps, &c. Indian Atlas, Sheet No. 104. Lat. $24^{\circ} 37' N.$; Long. $85^{\circ} 55' E.$

³ The 'Sahasrām, Sahseram, and Sasseram' of maps.—The name is understood to be a corruption of the Sanskrit *sahasra-grāma*, 'the (circle of a) thousand villages.'

The inscription simply records the name of the *Mahāsāmanta*¹ *Śaśāṅkadēva*. The age of the characters would justify us in identifying him with the *Śaśāṅka* (*Sho-shang-kiā*), king of *Karṇasuvarṇa* (*Kie-lo-na-su-fa-la-na*) in Eastern India,—the contemporary and murderer of *Rājyavardhana* II. of Kanauj,—who is mentioned by Hiuen Tsiang as a persecutor of the Buddhists.² And, if this identification is accepted, it will refer the inscription to just about the commencement of the seventh century A.D.

TEXT.³

- 1 Śrī-mahāsāmanta-
- 2 Śaśāṅkadēvasya

TRANSLATION.

Of the illustrious *Mahāsāmanta Śaśāṅkadēva*.

No. 79; PLATE XLIIIC.

SARNATH STONE INSCRIPTION OF PRAKATADITYA.

THIS inscription, which has not been previously brought to notice, is from a stone that was discovered by General Cunningham at *Sárnāth*,⁴ close to Benares. It has now, I think, been sent to the Imperial Museum at Calcutta.

The writing, which covers the entire front of the stone, about 2' 0½" broad by 1' 6" high, has suffered a great deal of injury; especially towards the bottom, where the first halves of lines 12 to 16 are now quite illegible; and I have to acknowledge some very appreciable assistance from Dr. Bhagwanlal Indraji, in respect of some of the more pointedly damaged passages. In addition to its being so worn, the extant record is only a remnant of what was originally engraved. Nothing is lost at the top and bottom; but parts of the original stone have been cut away at the sides, evidently in order to adapt it to some building purpose; and the verse commencing in line 3 and ending in line 4, shews that at least eighteen letters have been destroyed in this way, between the last that is legible in line 3 and the first in line 4; the general run of the inscription seems to shew that nearly the whole of what was thus cut away, came at the ends of the lines. Also, as may be seen in the lithograph, two round holes were drilled in the stone for some purpose or other, about half-way down.—The average size of the letters is about ¼". The characters belong to the northern class of alphabets; and, except that the *Kuṭila* characteristic is only discernible in a few places, e.g. in *nitarāṅ nishkampah*, line 7, they are of almost precisely the same type as those of the *Aphaṣṭ* inscription of *Adityasēna*,

¹ *Mahāsāmanta*, lit. 'a great chief of a district,' is a technical official title which, as noted above (page 15, note 4), seems to denote the same rank as *Mahārāja*.—Next below the *Mahāsāmanta* came the *Sāmanta*. This latter title is of equally frequent use, in its technical value, in other inscriptions. In the present series, however, it is only used in a general way, to denote 'feudal chiefs;' e.g. in line 5 of No. 33 (see page 148 above, note 1), and in line 1 of No. 80 below, page 288.

² See Beal's *Buddh. Rec. West. World*, Vol. I. p. 210 ff., and Vol. II. pp. 42, 91, 118, 121.

³ From Mr. Beglar's rubbing; so also the lithograph.

⁴ See page 281 above.

A—Lahor Seal of
the Maharaja Mahesvaranaga




FULL SIZE

B—Rohtasgadh Seal-Matrix of
the Mahasamanta Sasanakadeva.



SCALE 30

C.—Sarnath Inscription of Prakataditya.



No. 42 above, page 200, Plate xxviii.—The language is Sanskrit. The last line seems to be in prose; and the rest of the inscription, in verse throughout; though the metres cannot in every instance be recognised.—In respect of orthography, the only points that call for notice are (1) the doubling of *t*, in conjunction with a following *r*, once, in *putrēna*, line 16; and (2) the use of *v* for *b* throughout; e.g. in *vāldīditya*, and *lavdha*, line 3.

The inscription is one of a king named *Prakāṭāditya*, whose capital appears to have been *Kāśī*, i.e. *Benares*, which is mentioned in the first line. It is not dated; but, on palaeographical grounds it may be referred roughly to about the end of the seventh century A.D. It is a *Vaiṣṇava* inscription; and the object of it is to record the building of a temple of the god *Vishṇu*, under the name of *Muradvish*, and some provision, the details of which are lost, for the repairs of it.

The chief interest attaching to this inscription, consists in its mentioning at least two kings of the name of *Bālāditya*. One of them was the father of *Prakāṭāditya*. The other was an ancestor of the same name; and, as he himself is called "another" *Bālāditya*, the presumption is that the name of the still earlier ancestor, who was mentioned in the passages that have been destroyed in lines 2 and 3, was also *Bālāditya*. And the probability is, that the first *Bālāditya* is the one who is so well known in connection with the history of *Mihirakula*.

TEXT.¹

- 1 dē(?)vō(?) || **Kāśī**-Iti-
vikhyātaṃ puram kā(?)mē(?)na bhūshitaṃ |
2 [ll] [Pu]raṃdara i[va] pataty-ahō(?) ||
T[u]ṅga-ta(?)raṅga(?)va .. śāstra-vidō taṭānām | kari
3 rān²-madhya-da .. mśam-āntah | tad-vaṃśa-sambhavō-nyō **Vā(bā)lā-**
dityō pṛipah pṛityā || Tad-gōtra-lavdha(baha)-janmā **Vā(bā)lādityō**
.....
4 patiḥ || Tasya³ **Dhaval**-ēti jāyā pati-vratā Rōhinī-va
chandrasya | Gaur-iva Śōlapāpēr-L[ī]akshmir-iva Vāsu[dēvasya ||]
.....
5 [pra]tāpa-tapt-āmitra-vadhū-sindhu-śō[sha] | ti-vinayā
dvaya-bhṛi(?)taṃ bhakti-dharmm-aika-śakti-satata-prathita
6 nu(?)ḥ suta-vatsala sutah śauryya-
vinaya-sampannah | śrīmān-**Prakāṭādityō**
7 [dvi]jja⁴-vara-nikar-āśrayah pravṛi(?)ddha(?)-gūṇah | kalpa-druma iva
nitarāṃ nishkampah prakāṭa-mūlō-pi ||
8 [i] dvija⁵-gana-sēvyah sa[tata]ṃ vidvat-samudaya-vihita-ruchih ||
Nir[ī]jita-[du]rjaya-śat[tru]s-tri
9 pō(?)rvvah Kārttikēya iva || Yasya va .. nirgata
ludha(bdha)-hrishṭa-bhramad-bhrama[ra] vi
10 ta⁶-dinaṃ pṛithu-pushkariṇyah || Ye(?)na(?)⁷ ripu-sundarīṇam
malināni kṛitāni v[ī]pu[la]
.....

¹ From the ink-impression.² Metre, Ślōka (Anuṣṭubh)³ Metre, Āryā; and probably in the next verse.⁴ Metre, Āryā.⁵ Metre, Āryā.⁶ Metre, Āryā; and probably in the next verse.⁷ Metre, apparently Vasantatilaka⁸ Metre, probably Āryā.

11naṣa(?)na(?)-dviṣa-guru	karitam-étad-
	bhavanam Muradvishô ra			
12			yabhâ(?)su(?)
	yutâyamikâ prakāṣa			
13		bahu-matô	dharma-
	yaśô-râsi			
14		yab(?)	Khaṇḍa ¹ -
	sphuṭita-sarṣkâra.... dhû			
15		hamṣa-bha	praśastiḥ
	svâ..... ta(?)ḥ 			
16			R[â]machandra-
	[pu]ttr[é]ṣa Dêvakēna 			

TRANSLATION.

This inscription is too fragmentary for a connected translation to be offered. But we have to note the following points. Line 1 mentions the city of **Kâśi**; and line 2 apparently the god **Purandara**, in connection with it. The passage lost between the last legible letter in line 2 and the first in line 3, contained the name of a king, in connection with whom we perhaps have, at the commencement of line 3, a mention of the **Madhyadēsa** or Central Country. In his lineage, there was born "another" king **Bâlâditya** (l. 3). In the family of the latter, there was born yet another **Bâlâditya** (l. 3). His wife was **Dhavalâ** (l. 4), who is compared with **Rôhini**, the wife of the Moon, **Gauri**, the wife of **Śiwapati**, and **Lakshmi**, the wife of **Vāsudēva**. Their son was the glorious **Prakāśaditya** (l. 6), whose virtues and prowess, including a comparison of him with the god **Kârttikēya** (l. 9), are described in lines 7 to 10, apparently without the introduction of any further historical matter. Line 11 mentions the building of a temple of the god **Muradvish**. Line 14 contained some provision for the repairs of this temple. And line 16 gives us the name of **Dêvaka**, the son of **Râmachandra**, apparently as the engraver of the inscription.

No. 80; PLATE XLIV.

NIRMAND COPPER-PLATE INSCRIPTION OF THE MAHASAMANTA AND MAHARAJA SAMUDRASENA.

THIS inscription has been known, to General Cunningham, since 1847 or 1848, but was not brought to notice till 1879, when Major W. R. M. Holroyd, Director of Public Instruction in the **Panjab**, having obtained and forwarded the plate on which it is engraved, Dr. **Rajendralala Mitra** published his reading of the text, and a translation of it, in the *Jour. Beng. As. Soc.* Vol. XLVIII. Proceedings, p. 212 ff.

Nirmand¹ is a village, near the right bank of the **Satlaj**, twenty-one miles north-east of **Plâch**,² the chief town of the **Plâch Tahsil** or Sub-Division of the **Kullû**³ Division of the **Kângra District** in the **Panjab**. The inscription is on a copper-plate, which belongs to a

¹ Metre, probably **Ślôka** (**Anushtubh**).

² The 'Nirmand' of maps. Indian Atlas, Sheet No. 47. Lat. 31° 25' N.; Long. 77° 38' E.

³ The 'Plâch' of maps.

⁴ The 'Kullû and Kulu' of maps.

temple of the god Paraśurāma at this village; and, in accordance with the custom of the country, it is kept nailed up on one of the walls of the temple. I obtained the original plate, for examination, through the kindness of Mr. L. W. Dane, B.C.S.

The **plate**, which is inscribed on one side only, is of rather irregular shape, the extreme measures being about 1' 6 $\frac{3}{8}$ " by 8 $\frac{3}{8}$ ". The edges of it are neither fashioned thicker, nor raised into rims. Three of the four corners are more or less damaged; but nothing has been lost thereby; except in the upper proper right corner, where, unfortunately, the name of the family of the *Mahārāja*, whose grant is recorded, has been broken away at the commencement of line 1. The rest of the inscription is in a state of very good preservation throughout. The plate is rather thin; and the letters, though not very deep, shew through on the reverse side throughout; they were also engraved with such force as to destroy entirely the original smoothness of the plate, and thus to give the majority of them rather a blurred appearance in the lithograph. The engraving is fairly good; but, as usual, the interiors of the majority of the letters shew marks of the working of the engraver's tool.—At the top of the plate, in the centre, there is a hole, which seems to have been made originally for a **ring**, with a seal attached to it; but it has been broken through to the edge, and the ring and seal are not forthcoming. There is another hole in the bottom of the plate; this was probably made later, in order to nail the plate up on to the wall of the temple.—The **weight** of the plate is about 1 lb. 12 oz.—The **size** of the letters varies from $\frac{3}{16}$ " to $\frac{1}{8}$ ". The **characters** belong to the northern class of alphabets. In the combination of *r* with a following *y*, the *r* in this inscription is written on the line, with only a single *y* below it; e.g. in *paryantā*, line 8, and *kuryāt*, line 11. The characters include, in line 14, forms of the **numerical symbols** for 1, 6, and 10.—The **language** is Sanskrit; and, except for the benedictive and imprecatory verses in lines 12 to 14, the inscription is in prose throughout.—In respect of **orthography**, we have to notice (1) the use of the *jihvāmūlyā* and *upadhāntya*, in *yugalah-kratu*, line 2; *dukkha*, line 6; *anūdhyaṭaḥ-parama*, lines 2, 3, and 4; *uṣpannah-pitrā*, line 2; and *daydūḥ-parama*, line 5; (2) the use of the guttural nasal, instead of the *anusvāra*, before *ṣ*, in *vansā*, line 1; (3) the occasional doubling of *k* and *t*, in conjunction with a following *r*, in *samatikkrānta*, line 1; and *attra* and *vddittra*, line 15; and (4) the use of *v* for *b* throughout, in *lavdha*, line 3; *vvali*, line 7; *kuṣumvīnd*, lines 8 and 9; and *kuṣumva*, line 9.

The **inscription** is one of a *Mahāsāmānta* and *Mahārāja* named **Samudrasēna**. Its date, in numerical symbols, is the year six, and the eleventh solar day of the bright fortnight of the month Vaiśākha (April-May). There is nothing to indicate any particular era to which the date should be referred. On palæographical grounds, we might very well refer it to the Harsha era, with the result of A.D. 612-13. But I feel rather doubtful as to the probability of the years of Harshavardhana's reign having been constituted an era, of general acceptance, quite so soon after his accession. And I am inclined to look upon the date of this inscription as referring only to the years of the authority of Samudrasēna himself, as in the *Āraṅ* grant of the *Rāja* Mahā-Jayarāja, No. 40 above, page 191, the *Rāy*pur grant of the *Rāja* Mahā-Sudēvarāja, No. 41 above, page 196, and the *Chammak* and *Siwani* grants of the *Mahārāja* Pravarasēna II., Nos. 55 and 56 above, pp. 235 and 243. And, in that case, all that can be said about the period of the present inscription, is, that it belongs roughly to about the seventh century A.D.¹ The object of

¹ Gen. Cunningham (*Archæol. Surv. Ind.* Vol. XIV. p. 120 ff.) has referred this inscription to Vikrama-Saṁvat 1227 (A.D. 1160-61); but on grounds which will not stand for a moment. It is quite

the inscription is to record the allotment of the village of **Sūlisagrāma** by **Samudrasēna**, to a body of Brāhman̄s who studied the *Atharva-Vēda* at the *agrahāra* of **Nirmaṇḍa**, for the purposes of the god Tripurāntaka or Śiva, who, under the name of Mihirēśvara, had been installed by his mother Mihiralakshmi at a previously established temple of the same god under the name of Kapālēśvara. It is therefore a Śaiva inscription; but the occurrence of the word *mihira*, 'the sun,' as the first component of the god's name, seems to indicate that, in this particular case, some form or other of solar worship was combined with the Śaiva rites.

TEXT.

- 1 ¹ bhikhyāta - narapati - vaṅśa - jas - sama²bhavach - chatur - udadhi-samatikkṛānta-kr̄ttir-anēka-sāmant-ōttamāṅg-āvanata-mukūṭa - maṇi - mayūkha-vichchhurita-charaṇāravinda-⁴
- 2 vugala³h = kratu-yājī mahāsāmanta-mahārāja-śrī-**Varuṇasēnas**-Tasya putras=tat-pād-ānudhyātaḥ - paramadēvyāp(m) - Prava(bā)likā-bhaṭ[ṭ⁴]ārikāyām = utpannaḥ-pitr=aiva tulyō guṇair=mma-
- 3 hāsāmanta-mahārāja-śrī-**Sañjayasēnas**-Tasya putras=tat-pād-ānudhyātaḥ-paramadēvyāṁ Śikharasvāmīni-bhaṭ[ṭ⁴]ārikāyām=utpannas=samara-śata-lavdha(bdha)-jayas=tyāgt ma-
- 4 hāsāmanta-mahārāja-śrī-**Ravishēnas**-tasya putras=tat-p[ā⁴]d-ānudhyātaḥ=paramadēvyāṁ śrī-Mihiralakshmi-bhaṭ[ṭ⁴]ārikāyām=utpannas=śarad-amala-sakalajaranikara iva prāṇi-

true that the alphabetical characters of that part of the country are of an extremely conservative type; but not to anything like such an extent as to enable us to refer the present record to within several centuries of so late a period. The more important point, however, is, that his reading of the date is completely wrong. Overlooking altogether the numerical symbol that stands after the word *samvat*, he has obtained his reading of the date by interpreting, among the words that precede *samvat*, *arka* as 'twelve,' and *gana* as 'twenty-seven.' According to the numerical-word system, *arka* certainly does stand for 'twelve;' and *gana* might possibly be used for 'twenty-seven,' though I can find no authority for it. But, in the present passage, *arka* is simply the second component of the name of the writer of the grant; and, whatever *gana* may mean here, it is most certainly not used as a numerical word. The date is recorded, in the usual way, in the numerical symbol that stands immediately after *samvat*; and that symbol is a 6.—Gen. Cunningham found some corroboration of his interpretation, in the fact that the accepted genealogy of the 'Mandi' and 'Suket' families contains a Samudrasēna, whose date, reckoning backwards at the rate of thirty years to the generation from A.D. 1500, would be about A.D. 1140 to 1166, and who might, therefore, on his interpretation of the date, be identified with the Samudrasēna of this inscription. But this identification cannot be accepted for a moment; it is wholly impossible to accept the names of Virasēna, Savāhanasēna, Kanavāhanasēna, and Naravāhanasēna, which precede him in the genealogy, as being identical with, or even intended to represent, the Ravishēna, Sañjayasēna, and Varuṇasēna, of the inscription.

¹ From the original plate.

² Four letters, or perhaps five, are broken away and lost here. A small part of the last of them, immediately preceding the first legible syllable, *śhi*, is visible; but it is impossible to say what the entire letter may have been.

³ The mark over this *ma* is a fault in the copper, making a hole right through it.

⁴ The mark between the *v* and the *ś* is a fault in the copper, making a hole right through it.

⁵ The upper parts of these three letters are broken away and lost; but enough remains to shew distinctly what they were.

- 5 nāth samāhlādana-karas-samutkhāt-āśēsha-ripur-āśāvātām-aprārthita-phala-pradō
dīn-ānāth-ātura-dayālūḥ-paramamāhēśvarō-ti-vra (bra)hmaṇyaḥ-parārthīy (rtth) -
aika-ratō mahāsāmanta-
- 6 mahārāja-śrī-Samudrasēnō janant-śrī-Mihiralakshmyā dharmm-ārttham
bhagavatas-Tripurāntakasya lōk-ālōka-karasya prapāt-ānukampinas-sarvva-
dukhha-kshaya-karō¹ Kapālē-
- 7 śvarē janant-pratiśthitasya śrī-Mihirēśvarasya Kapālēśvara-vva (ba)li-charu-
sat[^{t*}]ra-srag-dhōpa-dīpi(pa)-dānāya satatam śrīṇa-khaṇḍa-sphuṭita-
sādhanaīya cha Ni-
- 8 rmmaṇḍ-āgrāhār-Ātharvvaṇa-vrā (brā)hmaṇa-stōmāya Sūlisagrāma-navavaidila-
karm-ānta-Vakkhalika-kuṭumvi (mbi)nā dvēsa-bhūmi-paryantā paribhūta-
nāmnā Phakkaś-cha Tālāpura-
- 9 ka-kuṭumvi (mbi)nā dvēsa-bhūmi s-ōdraṅgā sa-sīm-ānta-paryantā
Sulabhaka-kuṭumva (mba)-Dinna-kuṭumva (mba)ś-cha I Kapālēśvara-dēvasya
pūrvva-pratiśthāyām mahārāja-Śarvvavarmmēṇa² bhūmi dattā I
Sūlisagrāmasya śrī-Mihi-
- 10 ralakshmyā dattasya sam-audaka-jangala-bhūmi-samētam-aśēsham sa-prativāsi-
jana-samētam s-ōdranga[^{m*}] sva-sīmā-tṛiṇa-kāsthā-prasravaṇa-yūti (ti)-
paryantam dēvāgrāhārvēn-ā-cha-
- 11 ndr-ārka-tārā-samakālinam pratipādayati sma [II*] Vīditv-aitad-rājabbhis-
tad-āśrī (śrī)tajanēn-ādihkrit-ānadhikritēna hitam-ichchhatā pratipālanīyā [I*]
yō-nyathā kuryāt-paripanthanam-apaha-
- 12 raṇa-plḍ-ōpadravam vā sa pañchabhīr-mmahāpātakair-upapātakaiś-cha
samyuktas-syāt II Uktāñ-cha [I*] Va (ba)hubhīr-vvasudhā bhuktā
rājabbhis-Sagar-ādibhi[^{h*}] yasya yasya yadā bhūmis-tasya tasya
tadā
- 13 pnam [II*] Shashṭīm varsha-sahasrāṇi svarggē mōdati bhūmi-dah
āchchhētā ch-ānumantā cha tāny-ēva narakē vasēt [II*] Sva-
dattām para-dattām-vā yō harēta vasundharām shashṭī-varsha-
- 14 sahasrāṇi viśthāyām jāyatē kṛimīr-iti II Dūtō-tra Nihilapatī-
Kūsalaprakāśāś-cha I lēkhakō-tra Udyōta-arkkaś-cha gaṇa-
srōstha³ [II*] Samvat 6 Khē⁴ śu di 10 I [II*]
- 15 Rāshṭra-samētasy-ā (ē)yam dattī[^{h*}] paripālyā II Ai(?)ṅgi(?)k-ātra
udyā(?)na(?)-sthāvara-vādīttra-ka(?)viśva-sa(?)hadra upalava⁵
- 16 kagalalañcha(?)ṭika dvaīya(?) Mīl(hi)ralakshmi(kshmi)-pratipād[^{i*}]ta iti [II*]

TRANSLATION.

Born in the lineage of the famous kings there was the *Mahā-
sāmanta* and *Mahārāja*, the illustrious *Varupasēna*, whose fame stretched out over the

¹ Read *karasya*.² Read *śarvvavarmmaṇḍ*.³ Metre, Ślōka (Anushtubh); and in the following two verses.⁴ Read *udyōtārkkaś*.⁵ This seems to be intended for *gaṇa-śrēśthāḥ*.⁶ This is what is engraved. But of course it is a mistake for *vai*, i. e. *vaiśākha*; and it is easy to see how the engraver made the mistake in copying from the draft before him.⁷ The mark that follows this *va* is a fault in the copper, making a hole right through it.⁸ The mark before this *dv* is a fault in the copper, making a hole right through it.

four oceans; the waterlilies of whose feet were covered over with the rays of the jewels in the bowed-down tiaras on the heads of many feudal chiefs; (and) who celebrated sacrifices.

(Line 2.)—His son, who meditated on his feet, (and) who was verily equal to (his) father in virtuous qualities, (was) the *Mahāśmanta* and *Mahārāja*, the illustrious **Samjayasēna**, begotten on the *Paramadēvi*,¹ the *Bhaṭṭārikā* Prabhālikā.

(L. 3.)—His son, who meditated on his feet, (and) who attained victory in a hundred battles, (and) who was full of liberality, (was) the *Mahāśmanta* and *Mahārāja*, the illustrious **Ravishēna**, begotten on the *Paramadēvi* Śikharasvāminī.

(L. 4.)—His son, who meditates on his feet, the *Mahāśmanta* and *Mahārāja*, the illustrious **Samudrasēna**,—who was begotten on the *Paramadēvi*, the *Bhaṭṭārikā*, the illustrious Mihiralakshmi; who, like the spotless full-moon of autumn, causes the delight of (all) living creatures; who has uprooted all enemies; who confers upon the expectant rewards that are not (even) sought for (by them); who is tender to the poor, the helpless, and the afflicted; who is a most devout worshipper of (the god) Mahēśvara; who is extremely friendly to Brāhman; (and) who is entirely intent upon the supreme good,—for the sake of the religious purposes of (his) mother, the illustrious Mihiralakshmi, has allotted, as an *agrādāra* of the god, to endure for the same time with the moon and the sun and the stars, to the body of Brāhman who study the *Atharva-Vēda* at the *agrāhāra* of *Nirmaṇḍa*,—for the purpose of giving, at (the temple of the god) Kapālēśvara, the *bali*, *charu*, *sattra*, garlands, incense, and lights, of the holy (god) Mihirēśvara, who is the divine Tripurāntaka, the maker of the visible and invisible world, compassionate to those who worship (him), the destroyer of all sorrows, (and) who was established by (his) mother at (the temple of the god) Kapālēśvara; and for the purpose of always repairing whatever may become worn-out and broken and torn,—the whole of the village of *Sūlisagrāma*, that was granted by the illustrious Mihiralakshmi, together with the level and marsh and forest lands; together with the inhabitants; with the *udraṅga*; (and) including all its boundaries, grass, timber, and springs,—(viz.) (the land) including the *dvēsa*-land² (that had been given) by the cultivator Vakkhalika, (whose holding was) on the edge of the newly-constructed *vaidīla*³ of the village of *Sūlisagrāma*; and the *dvēsa*-land, with the *udraṅga* (and) including the edges of (its) boundaries, (that had been given) by a cultivator of the town of *Tālāpura*,⁴ who under a nick-name (was called) Phakka,⁵ and the holding of Sulabhaka and the holding of Dinna; (and) the land that had been given by the *Mahārāja Śarvavarman* at the former installation of the god Kapālēśvara.

(L. 11.)—(This grant) should be preserved by (future) kings, becoming aware of it; (and) by the people, whether holding office or not holding office, dependent on them, who

¹ *Paramadēvi*, lit. 'supreme goddess,' was a technical title of the wives of *Mahārājas*. The more usual title, however, was *Mahādēvi* (see page 16 above, note 2).


² *dvēsa*.—I have not been able to obtain any explanation of this word, which is probably a local term. Dr. R. Mitra translated it by 'grazing-ground,' but quoted no authority for this.—The purport of the passage from *Sūlisagrāma-nava*, line 8, down to *bhāmi dattā*, line 9, is not quite clear. But it seems to specify certain previous grants which make up the *aiśham* or 'entirety' of *Sūlisagrāma*, as now bestowed by *Samudrasēna*.

³ *vaidīla*.—This is another word of which I have not been able to obtain any explanation.

⁴ Or perhaps *Tālāpura*, with the short vowel *a* in the first syllable.

⁵ lit. 'the cripple.'

Nirmand Plate of the Mahasamanta and Maharaja Samudrasena.



3
4
6
8
10
12
14
16

J. F. FLEET, GO. C. A.

SCALES .89

1

W. BRIGGS, PHOTO-LITH.

are desirous of welfare! Whosoever (*acting*) otherwise, may cause obstruction or the annoyance of the pain caused by confiscation,—he shall become invested with (*the guilt of*) the five great sins and the minor sins!

(L. 12.)—And it has been said:—"The earth has been enjoyed by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs at that time the reward (*of this grant that is now made, if he continue it*)! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! He who confiscates land that has been given, whether by himself or by another, is born as a worm in ordure for the duration of sixty thousand years.

(L. 14.)—And the *Dāta*¹ in this matter (*is*) the *Nihilapati*² *Kuśalaprakāśa*; and the writer in this matter (*is*) Udyōtārka, the leader of the assemblage (?).³ The year 6, (the month) Vaiśākha; the bright fortnight; the day 10 (*and*) 1:

(L. 15.)—This grant, which is one of the whole assembly of (*the people of*) the country, should be preserved! *

No. 81; PLATE XLV.

RAJIM COPPER-PLATE INSCRIPTION OF THE RAJA TIVARADEVA.

THIS inscription was discovered about 1785 by a Marāṭhā chief named Hann-antrao Maharik, and was first brought to notice in 1825, in the *Asiatic Researches*, Vol. XV. p. 499 ff., where, the original plates having been forwarded by Mr. R. Jenkins, a lithograph of it was published (*id.* Plate xiv.), accompanied by a version of the text by a Jain scholar named Srivarmasuri, and a translation by Professor H. H. Wilson.—Subsequently General Cunningham obtained the original plates again, and, in 1884, published a fresh lithograph in the *Archæol. Surv. Ind.* Vol. XVII. p. 17, and Plates vi. vii. and viii.

*Rājim*⁴ is a town on the right bank of the Mahānadi river, about twenty four miles to the south-east of Rāypur,⁵ the chief town of the Rāypur District in the Central

¹ *Dāta*; see page 100 above, note 3.—An Ujjain grant of Vikrama-Samvat 1192 (Colebrooke's *Essays*, Vol. II. p. 273; and *Indian Inscriptions*, No. 51, line 13) gives an instance of more than one original *Dāta* or *Dātaka* being employed for one and the same grant,—*via.* "the *Purōhita*, the *Thakkura*, the illustrious Vāmanasvāmin; the *Thakkura*, the illustrious Purushōttama; the *Maha pradhāna*, the *Rājaputra*, the illustrious Dēvadhara; and others,"—without any such circumstances as those indicated in No. 30 above, page 134, which necessitated the despatch of a second *Dātaka* to authorise the insertion of additional privileges in the charter.

² *Nihilapati*.—I have not been able to obtain any explanation of the first component of this official title.

³ *gaya-śrēṣṭha* (?).—If this is the proper intended reading, the word must have some technical meaning; but its exact purport is not apparent.

⁴ The passage commencing with *ai(?)ngi(?)k=dtra*, in line 15, is too corrupt to be capable of translation. But it appears to record two other grants made by Mihiralakshmi; and it mentions a park, some immovable property, and some musical instruments.

⁵ The 'Rajam and Rajim' of maps. Indian Atlas, Sheet No. 91. Lat. 20° 58' N; Lon. 81° 55' E.

⁶ The 'Raepoor, Raipur, and Ryepoor' of maps &c; see page 196 above, and note 1

Provinces. The plates containing the inscription were discovered in digging for stones to build a house in this town, and are now in the possession of the priests of the temple of the god Rājīvalōchana. I obtained them, for examination, through the District Authorities.

The plates, of which the first and last are engraved on one side only, are three in number, each measuring about $8\frac{1}{8}$ " by $5\frac{3}{8}$ ". They are quite smooth, the edges of them being neither fashioned thicker nor raised into rims. They are rust-eaten in a few places; but the inscription is for the most part in a state of perfect preservation. They are of fair thickness; but the letters shew through on the reverse sides of the first and last plates, so clearly that most of them can be read there. The engraving is good; but, as usual, the interiors of many of the letters shew marks of the working of the engraver's tool.—Towards the proper right side of each plate, about the centre, there is a hole for a ring to connect them. The ring, which had not been cut when the grant came under my notice, is circular, about $\frac{1}{8}$ " thick and $4\frac{1}{4}$ " in diameter. The ends of it are secured, in the usual way, in the lower part of a seal. The top of the seal is circular, about $3\frac{1}{8}$ " in diameter. It has, in relief on a rather deep countersunk surface, across the centre, a legend, in two lines, of which the text and translation are given below; in the upper part, a figure of Garuḍa, facing full-front, depicted with the head of a man and the body of a bird, with his wings expanded, with, apparently, human arms hanging down between the wings and the feet, and with a serpent, with expanded hood, standing up in front of and over each shoulder; on the proper right of this, a *chakra* or discus, the emblem of Vishṇu; and on the proper left, a *śankha* or conch-shell; in the lower part, a floral device.—The weight of the three plates is about 2 lbs. 15 oz., and of the ring and seal, about 2 lbs. $6\frac{1}{2}$ oz.; total, 5 lbs. $5\frac{1}{2}$ oz.—The average size of the letters is about $\frac{1}{16}$ ". The characters belong to the southern class of alphabets; but they include the separate form of the lingual *d*, as distinct from the dental *d*, e.g. in *vaddavdnala*, line 6, and *gūdd*, for *gūddhō*, line 10. They give another specimen of the 'box-headed' variety, peculiar to Central India, on which I have commented at page 18 f. above. They include, in line 36, a form of the numerical symbol¹ for 7, and also of the decimal figure² for 8.—The language is Sanskrit, except for the three vernacular terminations in the record of the date in the last line. The legend on the seal is in verse. The inscription itself, except for one verse at the beginning and the benedictive and imprecatory verses in lines 25 to 35, is in prose throughout.—In respect of orthography, we have to notice (1) the use of the guttural nasal instead of the *anusvāra*, before *ś*, in *nistrinśa*, line 4; *vaṅśa*, line 16;

¹ This sign is, perhaps, rather an intermediate form between the numerical symbol and the decimal figure, as it differs a little from the symbol for 7 which we have in the Bōdh-Gayā inscription of Mahānāman, No. 71 (see page 274 above, note 2); but it approximates much more closely to the symbol, than to the figure.—Gen. Cunningham (*Archaeol. Surv. Ind.* Vol. XVII. p. 17) interpreted it as 6, probably on account of its resemblance to the modern Bengālī form of 6. This will not stand; because of the southern type of the characters of this inscription.—There might possibly be a doubt, whether it represents 7 or 9. But I think, on the whole, that it is intended for a 7.

² Here we have a fully developed decimal figure, and of the southern type, as shown by the slight bend to the left in the vertical stroke; it is also explained by the ordinal adjective *aṣṭamsu*, 'the eighth'.—This mixture of a numerical symbol and a decimal figure, is rather unusual. But a still more marked example occurs in the date of the Shērgaḍh Buddhist inscription of the *Sāmanta* Dhēvadata of Vikrama-Saṁvat 879, where the 800 is expressed by the decimal figure 8 in combination with a form of the numerical symbol for 100 (see *Ind. Ant.* Vol. XIV. p. 351 f.)

and *vrīṣaṅsa*, line 27; (2) the use of *v* for *b*, in *vahala*, line 5; and (3) the use of *b* for *v*, in *bvavasthā*, line 8; *baṃṣhi*, line 9-10; *abhidhdaya*, line 22; *pratibastavyam*, line 25-26; *byāsa*, line 30; and *bā*, line 34.

The inscription is one of the *Rāja Tivaradēva*, of the *Pāṇḍuvarṣa* or lineage of *Pāṇḍu*. In line 18, he has also the name of *Mahāśiva-Tivararāja*; and, according to the legend on the seal, he was the lord of the *Kōśala* country. The charter recorded in it is issued from the town of *Śripura*, which is evidently the modern *Sirpur*, about forty miles east by north from *Rāyṣpur*. It is a non-sectarian inscription; the object of it being simply to record the grant, by *Tivaradēva*, to a *Brāhman*, on the twelfth lunar day, without any specification of the fortnight, of the month *Jyēshṭha* (May-June), of the village of *Pimpripadraka* in the *Peṅthāma bhukti*.¹ The last two lines record, partly with a numerical symbol,² and partly with a decimal figure coupled with the ordinal adjective, a second and fuller date; *vis.* the seventh year of the reign, and the eighth solar day, without any specification of the fortnight, of the month *Kārtika* (October-November). This is evidently the date of the writing or assignment of the charter. And the 'reign' referred to, is probably the government of *Tivaradēva*.

Tivaradēva's paramount sovereign is referred to in line 11. But his name, or lineage, is not mentioned. Nor does the inscription contain any distinct information as to the period to which it is to be referred. This latter point, however, appears capable of determination from other sources. *Tivaradēva* was the adopted son³ of *Nannadēva*, who was the son of *Indrabala*. *Nannadēva* and his father *Indrabala* are mentioned again in an inscription at *Sirpur* itself, discovered by *Mr. Beglar*, and brought to notice by *General Cunningham*, in 1884, in the *Archaeol. Surv. Ind.* Vol. XVII. p. 25 f. and Plate xviii A.; and from this we learn that *Indrabala's* father was *Udayana*, of the *Śavara* lineage. The *Sirpur* inscription contains no date; but, on palæographical grounds, it may be referred roughly to about the eighth or ninth century A.D. And it seems extremely probable that this *Śavara* king or chieftain, *Udayana*, is the one who was conquered, captured, and released again, by the *Later Pallava* king *Pallavamalla-Nandivarman*.⁴ *Mr. Foulkes*⁵ has allotted *Nandivarman* to the century from A.D. 800 to 900; his exact date still remaining to be fixed, in accordance, to a certain extent, with the date of the *Chōla* king *Koppara-Kēsarivarman*, whose name appears in a *Tamil* addition to *Nandivarman's* grant. These points remain for further investigation. But they indicate the period to about which the present inscription of *Tivaradēva* may be referred. And, though the archaic forms of the characters might lead us, at first sight, to allot it to an earlier period, such a conclusion is negated by the vernacular terminations occurring in the last line, and by the use of a decimal figure in the record of the date. *General Cunningham*, indeed,⁶ has arrived at the specific date of A.D. 425 for *Tivaradēva*. But this is based upon his identification of *Nannadēva's* great-grandson *Śivagupta* with a certain *Śivagupta* of the *Sōmavarṣa*, a king of *Katak*, who, according to the *Orissa*

¹ *bhukti*, *lit.* 'enjoyment,' is a technical territorial term, the exact purport of which remains to be determined.

² See page 292 above, notes 1 and 2.

³ *tanaya-prāpta*, line 16; *lit.* 'acquired as a son.'—*Nannadēva's* son by birth was *Chandragupta*, as recorded in line 5 of the *Sirpur* inscription referred to in this paragraph.

⁴ *Ind. Ant.* Vol. VIII. pp. 278, 282 f.; and *Manual of the Salem District*, Vol. II. pp. 360, 364.

⁵ *Four. R. As. Soc. N. S.* Vol. XVII. p. 203.

⁶ *Archaeol. Surv. Ind.* Vol. XVII. p. 17 f.

palm-leaf records, was reigning in the time of Yayāti or Yayātikēsarin; and upon his acceptance of Stirling's date of A.D. 474 to 526 (or 473 to 520) for Yayātikēsarin, as correct. I shall discuss the matter at length hereafter. It is sufficient to say, here, that the date of Yayātikēsarin, derived from the Orissa records, is altogether unreliable, and is too early by at least about four centuries; and that, if the identification of the two Śivaguptas is correct, it leaves no doubt whatever that Tivaradēva cannot be allotted to an earlier date than roughly about A.D. 800.

TEXT.¹

The Seal.

- a Śrīmat²-Tī³varadēvasya Kōsal-
ādhipatē-idaṃ
- b śāsanam dharmma-vriddhy-arttha[m]
sthiram-ā-chandra-tārakam [11⁴]

First Plate.

- 1 Ōm [11⁵] Jayatī⁶ jagat-[t⁷]raya-tilaka[h⁸] kṣhitibhrit-ku⁹la-bhavana-
maṅgala-sūtra[h⁸] śrīi(śrī)mat-Ti(ti)varadēvō dhaurēya[h⁸] sa-
- 2 kala-puṇyakṛitām [11⁵] Sta(sva)stī Śrīi(śrī)purāt=samadhigatapañcha-
mahāśabd-ānēka-nata-nṛipati-kiri(rī)ṭa-
- 3 kōṭi-ghṛipta(ṣṭa)-charaṇa-nakha-darpaṇ-ōdbhāsītō=pi kanthad-unmukha-prakata-
ripu-rāja-lakṣmi(kṣhmī)-
- 4 kēśapās-ākaraṣaṇa-durlalita-pāṇipalla[vō¹⁰] nīśita-nīstrī(stri)nśa-ghana-ghāta-pātīt-
āri-dvirada-ku-
- 5 mbha-maṇḍala-galad-va(ba)hala-śōṇita-sad-āsikta-muktāphala-prakara-maṇḍita-
raṇāṅgana-
- 6 dvi(vi)vidha-ratna-sambhā¹¹ra-lābha-lōbha-vijrimbhamāṇ-āri-kṣhāravāri-vāḍavānalaś=
- chandr-ōdaya iv=ākṛita-
- 7 kar-ōdvēgaḥ kṣhi(kṣh)rōda iv=ādvi(vi)rbhūt-ānēk-ātiśāyi-ratna-sampat
- Garutmān=iva bhujang-ōddhāra-chatūra[h⁸]
- 8 parāmṛiṣṭa-ga(śa)tru-kalatra-nētr-āmjana-kōmala-kapōla-kuṅkumapatra-bhaṅgat
- śiṣṭ-āchāra-bya(vya)vasthā-
- 9 paripālan-aika-datta-chiitta[h⁸] [1¹²] api cha prāktanē tapasi yaśasi
- rahasi chētasi chakshushi ba(va)p[u]-

Second Plate; First Side.

- 10 shi cha pūjītō janēn=āklishtatayā nitāntam=a-vitriptō gūḍō(ḍhō) gāḍa(ḍha)-
svachchha-prasanna-ya(va)da-

¹ From the original plates.

² Metre, Ślōka (Anuṣṭubh).

³ The vowel is somewhat damaged, and it is difficult to say whether *i* was engraved, or *ś*. In lines 1 and 10, the short vowel is used in this name; and, in fact, *i* is used for *ś* throughout the greater part of the inscription; but the metre of line 1 shews that, in this name, the long vowel *ś* is the correct one.

⁴ Metre, Āryā; but one short syllable is wanting in the second *pāda*.

⁵ The vowel *ā* is partly destroyed by the ring-hole of the plate.

- 11 nēna ch-ālan̄kṛita[h*] svāmi-bhavan[é*]-py-a-bahu-lapanō-n-ujjhitaḥ ku-trishṇō-
pi nitānta-tyā-
- 12 ḡi(gt) ripujana-prachan̄dō-pi sō(sau)mya-darśanō bhūti-vibhūshan̄dō=py-a-
parushaḥ svabhāva[taḥ*] ki-
- 13 fch-ā-santushṭō dharm-ārjanēna sampal-lābhē svalpa-krōdhēna prabhava
lubdhō yaśasi na pa-
- 14 ra-vitt-āpahārē sa(sa)k[ī]ḥ subhāsi(shi)tēshu na kāmī(nī)-krīi(krī)dāsu
pratāp-ānala-dagdh-āśēsha-
- 15 ripu-kula-tūlarāśis-tuhinaśilāsāila-dhavala-yaśō-rāśi-prakasuta-diganta[h*] kānta[h*]
prakṛityā
- 16 śrīi(śrī)mad-Indrabala-sūnōr=alaṅkṛita-Pāṇḍuvaśāsya śrīi(śrī)-Nannadēvasya
tanaya-prāptaḥ sva-punya(nya)-
- 17 sambhāra-prasa(sa)mit-āśēsha-jagad-upadravaḥ sva-prajñā-śū(sū)chi-samuddhrit-
ākḥila-kantakāḥ para-
- 18 mayaiśhpavō matāpitri-pād-ānudhyātaḥ śrīi(śrī)-Mahāśiva-Tira'rājāḥ
kuśalī II¹ Peṭṭhāma-bhuktīya-

Second Plate ; Second Side.

- 19 Pimparipadrakē brāhmaṇām(n) sampūjya prativāsinaḥ samājñā-
payati [I*] Vidadam-astu
- 20 bhavatām yath-āsmābhir-ayam grāmō yāvad-ravi-śāsi-tārā-kirana-pratihata-
ghōr-āndhakāram ja-
- 21 gad-avatishtatē tāvad-upabhōgya[h*] sa-nidhiḥ s-ōpanidhiḥ²-a-chāṭa-bhata-
pravēś[ō*] dā-
- 22 radraṅaka-sarva-kar-ādāna-samētō mātā³pitrōr-ātmanaś-cha puṇy-ābhi-
bri(vrī)⁴ddhayē Bhā-
- 23 radvājasagōtra - VājasanēyaMādhyandina bhāṭṭaGauridattaputra - bhāṭṭa-
- 24 Bhavadatta-bhāṭṭaHaradattābhyām Jyēshṭha-dvādaśyām-udaka-pūrvam prati-
pādita i-
- 25 ty-avagamya bhavadbhir-yath-ōchitam-asmai⁵ bhōga-bhāgam-upanayadbhiḥ
sukham-prati-
- 26 vastabya(vya)m=iti II Bhāvinaś-cha bī⁶knipālān-uddiśy-ēdam-abhidhiyatē [I*]
Bhūmī⁷-pra-
- 27 dā divi lalanti patanti hri(ha)nta hṛitvā mahi⁸ nripatayō narakē
nri-śānsāḥ

Third Plate.

- 28 étad-[d*]vaya[m*] parikalayya chalāñ-cha lakshmi(kshmi)m-āyus-tathā
kuruta yad-bhavatām-abhi(bhī)shṭa[m] [II*]

¹ Read *hoars*. The engraver first cut the *rd*, of *rdjāḥ*, omitting both *ra* and *ra*; and then, partially cancelling the *d*, he omitted to insert the *va*.

² This mark of punctuation is unnecessary. ³ Read *s-ōpanidhir*.

⁴ The engraver first formed *va*, and then corrected it into *fa*.

⁵ The engraver first began to form *pitrd*, and then corrected it into *māid*.

⁶ The engraver first formed *brīi*, and then partially cancelled the superscript *i*.

⁷ Read *dhūmī*.

⁸ Metre, Vasantatilaka.

⁹ Read *māhī*.

- 29 Api cha [I*] Raksh'-āpālanayōs=tāvat=phalaṃ su-gati dur-gati kō nāma
svargam=uchchhri(tsrī)jya
- 30 narakam pratipadyatē [II*] Byā(vyā)sa-gi(ḡ)tāmś=ch=ātra ślōkān=udāraharanti [I*]
Agnēr²=a[pa*]tyam prathamam
- 31 sūvarṇam bhūr=vaishnavi(vī) sūryya-sutās=cha gāvah dattā[s*]=trayas=
tēna bhavanti lōkā yah kañchanam gā-
- 32 ā=cha mahi(hi)ā=cha³ dadyā[t*] [II*] Shashti⁴-varsha-sahasrāṇi svargē
mōdati bhūmi-daḥ ākshēptā
- 33 ch=ānumantā cha tāny=ēva narakē vasēt [II*] Bahubhir=vasudhā dattā
rājabbih Sagar-ādibbih
- 34 yasya yasya yadā bhūmi[s*]=tasya tasya tadā phalaṃ [II*] Sva-
dattām para-datlām bā(vā) yatnād=raksha
- 35 Yudhishthirah⁵ mahi⁶ mahimatām śrēshtha dānā śrēyō⁷=nupālanam=
iti || Pravarddhamāna-
- 36 vijaya-rājya-samvatsaru⁸ 7 Kārttika divasu ashtā(shta)mu 8 [II*]

TRANSLATION.

The Seal.

This charter, which is for the sake of the increase of religion, of the illustrious **Tivaradēva**, the supreme lord of (the country of) **Kōsala**, shall endure firmly as long as the moon and the stars!

The Plates.

Ōm¹ Victorious is the illustrious **Tivaradēva**, the ornament of the three worlds; the auspicious thread of the palaces of the race of kings; the most energetic of all those who do works of religion!

(Line 2.)—Hail! From the town of **Śrīpura**;—He who verily is made resplendent by the mirror of the nails of (his) feet, that is polished by a crore of diadems of the many kings, bowing down (*before him in the act of performing obeisance*), who have attained the *pañchamahāsabda*;²—whose fingers are discourteous in pulling the flowing tresses of

¹ Metre, Ślōka (Anushtubh).² Metre, Indravajrā.³ This *ācha* is imperfect in the lower part. It was repeated, and formed completely; but the greater part of the second *ācha* was then destroyed by the ring-hole.⁴ Metre, Ślōka (Anushtubh); and in the following two verses.⁵ Read *yudhishthira*.⁶ Read *mahīm*.⁷ Read *dāndh=chhrōyō*.⁸ Here, and in *divasu* and *ashtamu*, we have evidently a vernacular termination.—As regards the interpretation of the year and the day, see page 292 above, notes 1 and 2.⁹ *pañchamahāsabda*; *lit.* 'five great sounds'—This is a technical expression, the meaning of which remained for a long time in doubt.—In Monier Williams' Sanskrit Dictionary *mahāsabda* is given as meaning 'an official title beginning with the word *maṇḍ* ('great');' and *pañchamahāsabda*, in accordance with this, would denote five titles of rank and honour, such as *Mahārāja*, *Mahāmāyā*, *Itivara*, *Mahāsāmanta*, &c. This explanation was adopted by me (*Jour. Bo. Br. R. As. Soc.* Vol. X. p. 307, note), in preference to a suggestion previously made to me (*id.* Vol. IX. p. 307, note), that the term was identical with the *pañchamahāmantra* of the Jains, and denoted the five titles of *Arhat*, *Siddha*, *Āchārya*, *Upādhyāya*, and *Sarvasādhu*. And, finding the five titles of *Mahāsāmanta*,

Rajim Plates of the Raja Tivara-deva.

1
2
4
6
8

11a

10
12
14
16
18

12b

20
22
24
26

11b

28
30
32
34
36

12c

38
40
42
44
46

12d

48
50
52
54
56

12e

58
60
62
64
66

12f

68
70
72
74
76

12g

78
80
82
84
86

12h

88
90
92
94
96

12i

98
100
102
104
106

12j

108
110
112
114
116

12k

118
120
122
124
126

12l

128
130
132
134
136

12m

138
140
142
144
146

12n

148
150
152
154
156

12o

158
160
162
164
166

12p

168
170
172
174
176

12q

178
180
182
184
186

12r

188
190
192
194
196

12s

198
200
202
204
206

12t

208
210
212
214
216

12u

218
220
222
224
226

12v

228
230
232
234
236

12w

238
240
242
244
246

12x

248
250
252
254
256

12y

258
260
262
264
266

12z

268
270
272
274
276

12aa

278
280
282
284
286

12ab

288
290
292
294
296

12ac

298
300
302
304
306

12ad

308
310
312
314
316

12ae

318
320
322
324
326

12af

328
330
332
334
336

12ag

338
340
342
344
346

12ah

348
350
352
354
356

12ai

358
360
362
364
366

12aj

368
370
372
374
376

12ak

378
380
382
384
386

12al

388
390
392
394
396

12am

398
400
402
404
406

12an

408
410
412
414
416

12ao

418
420
422
424
426

12ap

428
430
432
434
436

12aq

438
440
442
444
446

12ar

448
450
452
454
456

12as

458
460
462
464
466

12at

468
470
472
474
476

12au

478
480
482
484
486

12av

488
490
492
494
496

12aw

498
500
502
504
506

12ax

508
510
512
514
516

12ay

518
520
522
524
526

12az

528
530
532
534
536

12ba

538
540
542
544
546

12bb

548
550
552
554
556

12bc

558
560
562
564
566

12bd

568
570
572
574
576

12be

578
580
582
584
586

12bf

588
590
592
594
596

12bg

598
600
602
604
606

12bh

608
610
612
614
616

12bi

618
620
622
624
626

12bj

628
630
632
634
636

12bk

638
640
642
644
646

12bl

648
650
652
654
656

12bm

658
660
662
664
666

12bn

668
670
672
674
676

12bo

678
680
682
684
686

12bp

688
690
692
694
696

12bq

698
700
702
704
706

12br

708
710
712
714
716

12bs

718
720
722
724
726

12bt

728
730
732
734
736

12bu

738
740
742
744
746

12bv

748
750
752
754
756

12bv

758
760
762
764
766

12bv

768
770
772
774
776

12bv

778
780
782
784
786

12bv

788
790
792
794
796

12bv

798
800
802
804
806

12bv

808
810
812
814
816

12bv

818
820
822
824
826

12bv

828
830
832
834
836

12bv

838
840
842
844
846

12bv

848
850
852
854
856

12bv

858
860
862
864
866

12bv

868
870
872
874
876

12bv

878
880
882
884
886

12bv

888
890
892
894
896

12bv

898
900
902
904
906

12bv

908
910
912
914
916

12bv

918
920
922
924
926

12bv

928
930
932
934
936

12bv

938
940
942
944
946

12bv

948
950
952
954
956

12bv

958
960
962
964
966

12bv

968
970
972
974
976

12bv

978
980
982
984
986

12bv

988
990
992
994
996

12bv

998
1000
1002
1004
1006



W. GREGG PHOTO-LITH.

SCALE 10

A. P. PLEST. 80 C. A.

the goddess of the fortunes of hostile kings, mourning, and looking up in anxious expectation (of even further ill-treatment), and exposed in public;—who is a very submarine

Mahāpratihāra, *Mahādandanayaka*, *Mahākṛtīkṛitika* and *Mahārāja*, twice applied to Dhruvasēna I. of Valabhi, in lines 13 f. and 29 f. of his grant of (Gupta)-Samvat 207 (*Ind. Ant. Vol. IV* p. 105). Dr. Bühler (*id.* p. 106, note) accepted the same explanation. Also, the same rendering has been given by Professor Kielhorn, in his translation of line 3 of the Kanheri inscription of the Rāshtrakūta king Amoghavarsha I. and his Śilāhāra feudatory Kapardin II., dated Śaka-Samvat 775 (*id.* Vol. XIII. p. 135).—Meanwhile, Mr. Sh. P. Pandit (*id.* Vol. I. p. 81, note), while accepting the same explanation, added, though without quoting his authority, that it had been usual to accept the term as referring to the sounds of five musical instruments. Taking up this idea, Sir Walter Elliot (*id.* Vol. V. p. 251 f.) quoted two passages from *Ferishtah*, and one from the nineteenth book of Chand's *Prithirdj-Rasa*, which speak of the *naubat* or 'imperial band' being played at the courts of kings five times daily; and expressed his opinion that this was the custom to which the expression under notice referred. In commenting on this, Mr. Growse (*id.* Vol. V. p. 354 f.) pointed out that the passage in Chand refers to "a noise of the five kinds of music playing every day," rather than to "song and music playing five times a day;" quoted a line from the *Rāmāyana* of Tulsīās, book i., which speaks of "the noise of the five kinds of music, and auspicious songs;" and also gave, from a commentary on the same poem, a Hindi couplet which explains the five kinds of music as being the sounds of the *tantri* or lute, the *ḍāl* or bell-metal instrument played with a stick, the *jhāḍjā* or cymbals, the *naḍra* or kettle-drum, and a wind-instrument. And finally, Mr. K. B. Pathak (*id.* Vol. XII. p. 95 f.) quoting an Old-Kanarese passage from a Jain author, descriptive of a royal procession, which mentions the sounding of the *pañchamahāśābda* and auspicious drums, stated that the *Līngāyat Vivāchachintāmani* enumerates the five musical instruments as being the *śringa* or trumpet, the *tamaṭṭa* or tambour, the *śankha* or conch-shell used as a horn, the *bhēṭ* or kettle-drum, and the *jayaganṭhā* or gong.—The last two contributions to the discussion leave no doubt whatever that the expression *pañchamahāśābda* denotes the sounds of five musical instruments, the use of which was allowed, as a special mark of distinction, to persons of high rank and authority.—Some of the inscriptions mention certain specific musical instruments, which, if they are to be classed among the customary and technical five instruments, remain to be identified with those enumerated in the *Vivāchachintāmani*. Thus, the Bajāgamve inscription of Śaka-Samvat 102 (*Ind. Ant. Vol. V* p. 46, line 4) gives to the Kalachuri king Bijjala the epithet *damaruka-tūrya-nirghōshana*, 'he who has (played before him) the sound of the musical instrument called *damaruka*' (a double drum, shaped like an hour-glass). So, also, the Raṭṭa chieftains of Saundatti and Belgam had the epithet *trivāḍī-tūrya-nirghōshana*; e.g. in the case of Lakshmidēva, in the Saundatti inscription of Śaka-Samvat 1151 (*Four. Bo. Br. R. As. Soc. Vol. X. p. 268*, and *Archæol. Surv. West. Ind. Vol. III* p. 113, line 62). And the Kādambas of Goa had the epithet *permaṭṭi-tūrya-nirghōshana*; e.g. in the case of Śivachitta-Permaḍi, in the Veṅkaṭāpūr inscription of Śaka-Samvat 1080 (*Ind. Ant. Vol. XI* p. 273, line 7 f.).—Occasionally, instead of *pañcha-mahāśābda*, 'the five great sounds,' we have *aśṣha-mahāśābda*, 'all the great sounds;' e.g. in line 41 of the Barōda grant of the Rāshtrakūta chieftain Karka II. of Gujārāt, dated Śaka-Samvat 734 (*Ind. Ant. Vol. XII* p. 160), and in line 24 of the Barōda grant of the chieftain Dhruva II. of the same family, dated Śaka-Samvat 757 (*id.* Vol. XIV. p. 199). But, that this had no wider meaning, is shewn by the double expression *aśṣha-pañcha-mahāśābda*, 'all the five great sounds' which occurs in line 1 of the Ambarānṭh inscription of the Śilāhāra chieftain Māmvaḍi, dated Śaka-Samvat 782 (*Four. Bo. Br. R. As. Soc. Vol. IX* p. 219, and Vol. XII. p. 329), and in line 3 of the Aḷjanēri inscription of the Yādava chieftain Sēunadēva, dated Śaka-Samvat 1063 (*Ind. Ant. Vol. XII* p. 126).—The epithet *samadhigata-pañchamahāśābda*, 'one who has attained the *pañchamahāśābda*,' is of very constant occurrence in inscriptions, in connection with the names of feudatories, and even of *Mahādumras* or heirs-apparent. But the only instances that I can quote, in which it is applied to paramount sovereigns, are the cases of the Rāshtrakūta king Amoghavarsha I., in line 6 f. of his Śīrūr inscription, dated Śaka-Samvat 788 (*Ind. Ant. Vol. XII* p. 218); of another Rāshtrakūta king named Karka, in line 22 of his Chlārōll grant, dated Śaka-Samvat 679 (*Four. Bo. Br. R. As. Soc. Vol. XVI* p. 108); and of Dēvapāla of Dhārā, in line 5 f. of the 'Chārāv' inscription of Vikrama-Samvat 1275 (No. 10 of the separate publications of the Archaeological Survey of Western India, p. 111).—The only instance known to me, in which any reference is made to the source of this mark of distinction, *vis.* to its being bestowed upon a feudatory

fire to the salt water of (*his*) enemies, gaping with the greedy desire to acquire a multitude of various jewels in battle-fields which are decorated with numbers of pearls that are always besprinkled with the thick blood that trickles down from the foreheads of the elephants of (*his*) enemies, struck down with the crushing blows of (*his*) sharp sword;—who has not caused distress by (*his*) taxes, just as the rising moon does not cause distress by (*its*) rays;—who, like the sea of milk, manifests a wealth of many most excellent jewels,—who, like Garutmat, is skilful in eradicating the serpents;¹—who breaks the saffron-leaves on the cheeks, soft with the collyrium (*washed down by the tears*) from (*their*) eyes, of the violated wives of (*his*) enemies;—whose thoughts are solely given to the establishment and protection of virtuous behaviour;—

(L. 9.)—Who, moreover, is not too much puffed up with satisfaction, (*though he is*) unweariedly worshipped by mankind, in (*respect of his*) religious austerity (*and*) fame (*and*) secrecy (*and*) intellect (*and*) faculty of sight and (*beauty of*) form resulting from (*good*) acts done in a former life;—who is reserved, and is decorated with an impene- trable, pure, and complacent countenance;—who, even in the palace of (*his*) lord, is never at a loss (*for words*), though he does not talk too much;—who, though he is thirsty for (*the acquisition of*) land, is yet exceedingly liberal;—who, though he is fierce to (*his*) enemies, is yet mild of aspect;—who, though he is adorned with majesty, is yet not harsh;—who, moreover, is by nature never quite satisfied in accumulating religion in the acquisition of wealth, (*and*) in (*displaying only*) mild anger in (*spite of all his*) power;—who is greedy for fame, (*but*) not for the appropriation of the wealth of others;—who is affable in excellent conversations, (*but*) not in the dallyings of wanton women;—who has burned with the fire of (*his*) prowess all the heap of cotton that is the race of (*his*) enemies;—who has irradiated the ends of the quarters of the world with the mass of (*his*) fame that is as white as the rocky mountain of snow;—(*and*) who is by nature beautiful;—

(L. 16.)—(*He*), the illustrious **Mahâsiva-Tivara-râja**,—who is the adopted son² of the illustrious **Nannadêva**, who was the son of the illustrious **Indrabala**, (*and*) who adorned the **lineage of Pându**; who has allayed all the troubles of the world with the abundance of his religious merit; who has extracted all thorns with the needle of his wisdom; who is a most devout worshipper of (the god) Vishnu; (*and*) who meditates on the feet of (*his*) parents,—being in good health, (*and*) having done worship to the Brâhmanas at (the village of) **Pimparipadraka** belonging to the **Penṭhâma bhukti**, issues a command to the residents:—

(L. 19.)—“Be it known to you, that this village is given by Us, with libations of water, on the twelfth lunar day of (the month) **Jyêshṭha**, for the increase of the religious merit of (*Our*) parents and of Ourselves, to the **Bhatta Bhavadatta** and the **Bhatta Haradatta**, sons of the **Bhatta Gauridatta**, of the **Bhâradvâja gôtra** and the **Vâjasaneyâ-Mâdhyath- dîma (sâkhâ)**,—to be enjoyed as long as the world endures, having the terrible darkness

by the reigning paramount sovereign, is in the Dêgadh inscription of Bhôjadêva of Gwâlior, dated Vikrama-Samvat 919 and Saka-Samvat 784, in which (*Archæol. Surv. Ind. Vol. X. p. 101, and Pl. xxxvii. No. 2, l. 3*) the **Mahâsîmanta** Vishnu (?) has the epithet *tat-pradatto-pañchamahâsîabda*, ‘possessed of the *pañchamahâsîabda* conferred by him, i.e. by Bhôjadêva.’

¹ This possibly contains an allusion to the well-known Nâga family or tribe.

² *tunnya-prâpta*, *lit.* ‘acquired as a son’; see page 293 above, note 3.

dispelled by the rays of the sun and the moon and the stars; together with (*its*) hidden treasures and deposits; not to be entered by the regular or the irregular troops; (*and*) accompanied by (*the right of*) receiving the *dāradranaka*¹ and all the taxes.

(L. 24).—"Being aware of this, you should dwell in happiness, rendering to them, in a proper manner, (*their*) share of the enjoyment."

(L. 26).—And for the guidance of future kings, this is said,—“Those kings who bestow land, enjoy pleasure in heaven; (*but*) alas! those who confiscate land (*that has been given*), and (*thus*) work injury to mankind, fall into hell: bearing in mind these alternatives, and also that fortune (*and*) life are transient, do that which pleases you!” Moreover,—“The reward of protection ensures a fortunate condition, and of omission to protect, a state of misfortune; who, indeed, will (*willingly*) disregard heaven and obtain hell?”

(L. 30).—And they cite on this point the verses that were sung by Vyāsa:—Gold is the first offspring of fire; the earth belongs to (the god) Vishṇu; and cows are the daughters of the sun: therefore the three worlds are given by him, who gives gold, and a cow, and land! The giver of land enjoys happiness in heaven for sixty thousand years; (*but*) the confiscator (*of a grant*), and he who assents (*to an act of confiscation*), shall dwell for the same number of years in hell! Land has been given by many kings, commencing with Sagara; whosoever at any time possesses the earth, to him belongs, at that time, the reward (*of this grant that is now made, if he continue it*)! O Yudhishṭhira, best of kings, carefully preserve land that has been given, whether by thyself, or by another; (*verily*) the preservation (*of a grant*) (*is*) more meritorious than making a grant!

(L. 35).—The year 7 of the increasing victorious reign; (the month) Kārttika; the eighth day, (*or in figures*) 8.

¹ *dāradranaka* is a fiscal term that requires explanation. The dictionaries give *dāra*, in the sense of ‘a cleft, gap, hole; a ploughed field; a wife;’ but they do not give *dranaka*, or any root by means of which it can be explained. The term may refer either to some agricultural cess, or to a marriage-tax of the kind spoken of in line 6 ff. of the Daṇḍapur inscription of Jagattinga II, dated Śaka-Samvat 840 (*Ind. Ant.* Vol. XII. p. 223 f.)

INDEX.

(The figures in thick type refer to the Introduction and Appendices.)

<p><i>abdapa</i>, a conventional term for the <i>Mēsha-Samkrānti</i>, both apparent and mean, 145, 146;— the figures for the <i>abdapa</i>, obtained by Prof. K. L. Chhatre's Tables, are for the apparent <i>Mēsha-Samkrānti</i>, 145, 147;— and they give the week-day and time, on and at which it occurred, 146, 147;— the annual variation in the <i>abdapa</i> is 1 day, 15 <i>ghaṭis</i>, 31'5 <i>palas</i> 147</p> <p><i>a-bhaṭa-chchhātra-prāvīya</i>, a fiscal term 98 n., 242, 249</p> <p>Abhayadatta, a minister of Vishnuvardhana of Mālava 157</p> <p><i>ābhigāmiḥ gundh</i>, certain attractive qualities 169 and n., 187</p> <p>Abhijit, the name of a <i>mukhūrta</i>, 95, 182;— also of an additional <i>nakshatra</i>, in excess of the usual number of twenty-seven, the space of which is taken partly from Uttārā-Aśādhā and partly from Śrāvāna 206, 207</p> <p>Abhira, or Ābhira, a tribe, conquered by Samudragupta 14</p> <p>Achalasingha, engraver of the Āraṅg grant of Jayarāja 195</p> <p>Achalavarman, a proper name 71</p> <p><i>Āchārāṅgikā</i>, a Jain commentary by Śīlāchārya, in the date of which a curious confusion is made between the Gupta and Śaka eras 32 n.</p> <p><i>Āchārya</i>, 'a spiritual guide or teacher' 248, 249, 259, 270, 271, 282</p> <p><i>a-chāṭa-bhaṭa-prāvīya</i>, a fiscal term 293</p> <p><i>a-chāṭa-bhaṭa-prāvīya</i>, a fiscal term 98 and n., 105, 109, 120, 128, 132, 138, 195, 199</p> <p>Achyuta, a king in Northern India, conquered by Samudragupta 12, 13</p> <p><i>ādāya</i>, a fiscal term, requiring explanation 170 and n., 189</p> <p><i>ādhirājya</i>, a derivative from the feudatory title <i>Adhirāja</i>, but not used in a technical sense 142 and n.</p> <p><i>Ādhvaryu</i>, the title of a particular class of priests, whose ceremonial is performed with the <i>Yajur-Vēda</i> 248</p> <p><i>ādikartṛi</i>, 'an originator,' an epithet of the Jain <i>Nirvāṇas</i> 68 and n.</p> <p>Ādityasena, Ādityasēnadēva (Gupta of Magadha), 14, 134 n., 187, 207, 208, 210, 212, 213 n., 214 n., 217;— in the Mandār Hill inscriptions, he has the paramount titles, 211, 212;— but not in</p>	<p>the Shāhpur image inscription, 210;— nor in the Dēś-Baraṅg inscription of Jivitagupta II., 217 and n.;— his wife was Kōṇadēr' 208, 212, 217;— mention of his son-in-law Bhōgavarmaṇ the Maukhari, and his daughter's daughter Vatsadēvī, 187, 15 n.;— his Aṃśad inscription, 200;— his Shāhpur image inscription of the (Harsha) year 66, 208;— his Mandār Hill inscriptions, 211;— a late inscription at 'Deoghar' in the 'Santā' Parganās, mentioning him 212 n.</p> <p>Ādityavardhana, <i>Mahārāja</i>, an ancestor of Harshavardhana of Kanauj, 232;— his wife was Mahāsēnaguptā 232</p> <p>Ādityavarman, <i>Mahārāja</i> (Maukhari), 221;— his wife was Harshaguptā 221</p> <p>Agastya, an ancient sage 184</p> <p><i>agnihōtra</i>, a particular sacrifice, 71 and n.;— mentioned as one of the five great sacrificial rites 170, 190</p> <p><i>agnishōma</i>, a particular sacrifice 241 and n., 248</p> <p>Agnis'āmin, a proper name 105</p> <p><i>agrāhuru</i>, <i>agrāhūra</i>, a village or other allotment of land, granted to gods or Brāhmaṇas, 51, 104, 109, 123, 206, 210, 257, 290;— <i>dēv-āgrāhūra</i>, 'an <i>agrāhūra</i> of the god' 123</p> <p><i>Āgrahūrika</i>, an official title 52 and n., 257</p> <p><i>ahan</i>, 'a day' used to denote the solar, or more properly civil, day 87</p> <p><i>dhāra</i>, a territorial term 95 n., 173 and n., 189</p> <p>Airāvata, the elephant of Indra, alluded to 76</p> <p>Airikīṇa, the ancient name of Ēraṅ in the Sāgar District, 18 and n., 21, 161;— and the chief town of a <i>viśhaya</i> of the same name 161</p> <p>Ajagarādāsa, a grantee 123</p> <p>Ajapura, an ancient town in Bihār 52</p> <p><i>ajjaka</i>, a Prakṛit word meaning 'a grandfather' 187 n.</p> <p>Ajjhitadēvī, wife of Vyāghra of Uchchakalpa 119 and n., 123, 128, 131, 138</p> <p><i>ājñā</i>, 'order, command,' a technical expression connected with giving the order for the drawing up of a charter; standing alone, it indicates the office of <i>Dātaka</i>, and the synonym <i>Ājñādāpaka</i> occurs for <i>Dātaka</i>, 100 n.;— in composition with <i>su-mukha</i>, it implies that a <i>Dātaka</i> is not employed 100 n., 115,</p>
---	---

- Ākhaṇḍalamitra, a grantee 190
Akshapaḍāldhikṛita, an official title
 190 n., 257 and n.
akshaya-nti, 'a perpetual endowment'
 182 n., 33 n., 52, 262
 Alarka, an epic king 147, 149
 Alberūnt, the Arabic historian; his state-
 ments regarding the Gupta and other
 eras, as rendered by M. Reinaud, 23;—
 by Prof. Sachau, 24;—and by Prof.
 Wright, 27;—his statements regarding
 the Lōkakāla of Kāśmīr and other
 parts of the country 26 n.
 Allnā or Allnā, a village in the Kaira
 District, the grant of Śīlāditya VII. of
 the (Gupta-Valabhi) year 447 171
 Allahābād, mentioned under the ancient
 name of Prayāga, 206;—the posthumous
 pillar inscription of Samudragupta 1
 Allahābād District, inscriptions from the
 1, 36, 39, 40, 45, 264, 266, 267, 271
 alphabets used in this series of records:—
 of the northern class 3, 26, 34, 37,
 39, 41, 43, 46, 48, 53, 66, 69, 88, 91,
 94, 101, 106, 110, 112, 117, 121, 125,
 130, 133, 135, 140, 145, 149, 151, 159,
 161, 201, 209, 211, 214, 219, 222,
 224, 226, 228, 231, 250, 251, 253,
 255, 258, 263, 264, 266, 267, 269,
 271, 272, 273, 274, 278, 280, 281,
 282, 283, 284, 287
 of the southern class 18, 22, 30, 57,
 72, 80, 164, 172, 192, 196, 233, 236,
 244, 260, 279, 292
 of the so-called Kuṭila type 201, 209, 211, 214
 of the 'box-headed' type 19, 192,
 196, 233, 236, 244, 292
 of the 'nail-headed' type 19, 22, 106
Amānta, the technical name for the
 scheme of the lunar months in South-
 ern India, according to which arrange-
 ment the months end with the new-
 moon day, and the bright fortnights
 precede the dark, 70;—in astronomical
 works, it is always this arrangement
 that is actually taken for calculations,
 148 n.;—even in Southern India, this
 arrangement was not applied to the
 Śaka years, for the civil reckoning, till
 between A.D. 804 and 866, 79 n.;—on
 the other hand, even in Northern India,
 this arrangement was used in Nēpāl
 with the years of the Nēwār era, 75,
 76;—but it was abandoned there, when
 the Nēwār era was followed by the
 Vikrama era in its northern variety 76
Amātya, an official title 100 and n., 120, 124, 190
 Amblōda, apparently the ancient name of
 Bhumarā 110, 111
 Amōghavarsha I. (Rāshtrakūṭa); exami-
 nation of the date of his Śīrūr inscription
 of the Śaka year 788, which proves
 that the *Amānta* arrangement of the
 lunar fortnights was applied to the Śaka
 years, in Southern India, between A.D.
 804 and 866 79 n.
 Āmrāvḍva, an ancient name of Ceylon
 275, 278, 279
 Amrakārdava, or Āmrakārdava, apparently
 an officer of Chandragupta II 32
 Amrarāta, or Āmrarāta, a proper name 33
 Amśuvarman, (*Mahāsāmanta*), and after-
 wards king (Tihākūrī of Nēpāl), 134 n.,
 177, 178, 179, 180, 188, 190, 191;—men-
 tioned with the feudatory title, 177, 178,
 179;—with the paramount title, 180;—
 as king, by Huen Tsang, 96, 184;—
 and by Ma-twan-lin, 190;—mention of
 his sister Bhōgādēvī, his brother-in-law
 Śūrasēna or Śūrasēna, his nephew
 Bhōgavarman, and his niece Bhāgya-
 dēvī, 180;—his dates, 189;—the value
 of his dates, in the Harsha era, in pro-
 ving the use of the Gupta era in Nēpāl,
 96, 184;—notice of his inscription of
 the (Harsha) year 34 178, —of an-
 other of the same year, 179;—of an-
 other, of the year 39 179, —and of
 another, of the year 44 or 45 180
 Āmuka, apparently an ancient village or
 district in Baghēlkhand 125
 Ānand, a town in the Kaira District;
 mentioned under the ancient name of
 Anandapura 173, 180, 190
 Ānandapura, ancient name of the modern
 Anand 173, 180, 190
 Ananta, an abbreviation of the name of
 Anantavarman 226, 228
 Anantagupta, or Anantaguptā, a proper
 name 265
 Anantasēna, a proper name 51
 Anantasvāmin, the god Vishnu as 'the
 eternal lord,' or as 'the lord of the
 serpent Ananta or Sēvha' 268
 Anantavarman (see also Ananta), a
 Maukhari chief, 223, 225, 226, 228;—
 his inscriptions in the Barābar and
 Nāgarjunī Hill caves 221, 223, 226
 Andhaka, an epic family or tribe 156
 Andhra, a tribe or dynasty, mentioned as
 defeated by a Maukhari king and taking
 refuge in the Vindhya mountains 230
 Animuktakakōnaka, apparently an ancient
 village or district in Baghēlkhand 105
 Antaka, the god Yama, as 'the dealer of
 death' 14, 21, 28, 44, 51, 54, 257
 Antaratrā, an ancient village in
 Kāthāwād 170
 Antarvādi, the country between the
 Ganges and the Jamnā; mentioned as
 part of the dominions of Skandagupta
 69 and n., 71
 Anu, an epic king 224 and n., 225
 Anusad, or Apsand, a village in the Gayā
 District; the inscription of Adityasēna 200
apīṭṛyāma, a particular sacrifice 241 and n., 248
 Arā (Shāhābād) District, an inscription
 from the 283

- Āraṅg, a village in the Rāypur District; the grant of Mahā-Jayarāja . . . 191
 Ardhanārīśvara, the god Śiva, combined with his wife Pārvaī; a probable early instance of an image of this form . . . 224
Arhat, a title in the Jain hierarchy . . . 68
ari-shadvarga, or *ari-shaśka*, 'the collective six enemies of religion' 156 and n., 259, 260, 264
 Arjunadēva (Chaulukya): examination of the date of his Verāwal inscription of the Valabī year 945 . . . 84
 Ārjunāyana, a tribe, conquered by Samudragupta, 14;—the name perhaps denotes early kings of the Kalachuri dynasty . . . 10
 Āryabhata, the first, an astronomer; he was born A.D. 476, . . . 143 and n.; he is the author of the *Aryabhatīya* or *Arya-Siddhānta*, the date of which is A.D. 499-500, . . . 156 n.;—and this is the text-book of the Aryapaksha school of astronomers, 145 n.;—his rule for determining the years of the Twelve-Year Cycle of Jupiter by the mean-sign system . . . 169
 Āryabhata, the second, an astronomer, he is the author of the work which is usually called the *Laghu-Arya-Siddhānta*, and the date of which is between A.D. 628-29 and 1150-51 . . . 156 n.
Āryabhatīya, or *Arya-Siddhānta*, an astronomical work by the first Āryabhata, written A.D. 499-500, . . . 156 n.;—this is the text-book of the Aryapaksha school of Hindu astronomers . . . 145 n.
ārya-saṅgha, 'the community of the faithful,' a Buddhist expression . . . 31, 32, 262
Ārya-Siddhānta, a name applied sometimes to the *Aryabhatīya* of the first Āryabhata, and sometimes to the *Laghu-Arya-Siddhānta* of the second Āryabhata . . . 156 n.
 Āryāvarta, a name of Northern India, 13 and n.;—list of the kings conquered therein by Samudragupta . . . 13
 Aśrīgadh, a hill-fort in the Nimāḍ District; the seal of Sarvavarman (Maukharī) . . . 219
 Āśramaka, an ancient village on the Tamasā . . . 128
 astronomers, Hindu; the starting-point used by them for reckoning the places of heavenly bodies, coincided, in their opinion, with the equinoctial point, about A.D. 522-23, . . . 146;—the three schools are the Aryapaksha, Brāhmapaksha, and Saurapaksha, based on respectively the *Arya-Siddhānta* of the first Āryabhata, the *Brahma-Siddhānta*, and the *Sūrya-Siddhānta* . . . 145 n.
 astronomical terms, explanation of . . . 145 to 153
atvamādha, a sacrificial ceremony which centred in a horse, 28 and n., 241, 248;—after being long in abeyance, it was revived by Samudragupta, 28 and n., 44, 51, 54, 257;—and there is an allusion to this in the epithet *atvamādha-parākrama* on coins which are attributed to him . . . 28 n.
Aivapati, an official title . . . 260 and n.
Atharva-Vēda (see *Vēda*): a mention of the study of it . . . 290
ati-brahmanya, translated by 'extremely friendly to Brāhmins'; but perhaps more properly a sectarian title (compare *parama-brahmanya*, 28 n.) . . . 290
ātirdra, a particular sacrifice . . . 241 and n., 248
atithi (see also *sattra*), one of the five great sacrificial rites . . . 116 n., 170, 190
 Ātmabhū, the god Viṣṇu, as 'the self-existent one' . . . 230 and n.
 Atri, an ancient astronomer, quoted by Rishiputra, and through him by Utpala, for the heliacal-rising system of the Twelve-Year Cycle of Jupiter . . . 170
atyantabhagavadbhakta, a Vaiṣṇava sectarian title . . . 28 n., 90, 160
atyantamāhāvāra, a Śaiva sectarian title . . . 28 n., 240, 248
atyantasvamināhdbharavabhakta, a Śaiva sectarian title . . . 28 n., 241, 248
aulikara-crest, a term requiring explanation . . . 151 and n., 155
 Avareukā, a town or country in Southern India, in the time of Samudragupta, its name was Nīlarāja . . . 13
 Avantivarman, a king, probably of the Maukharī tribe or dynasty . . . 215, 218
duḍḍa, a fiscal term, requiring explanation . . . 138 and n.
āya, 'revenue,' a fiscal term . . . 138 and n.
ayanāmsus, 'the degrees of precession of the equinoxes' . . . 146
 Ayōdhya, the modern Audh or 'Oude' or 'Oudh'; represented, in a spurious grant, to have been a camp of Samudragupta . . . 255, 257
Āyuktaka, an official title . . . 169 and n.
ba, an abbreviation of *bahuln*, 'the dark fortnight'; used in connection with *di* (see under *ba di*), 92 n., 93;—used by itself . . . 171
 Bādāmi, a town in the Kalādgi District; the value of the cave inscription of Māngalīśa, of Śaka-Samvat 500 expiated, in proving that the historical starting-point of the Śaka era is the commencement of the reign of some particular king or kings of the Śaka tribe . . . 142, 143
ba di, or *va di*, and *su di*, are simply abbreviations of separate words (see *ba di*, *su*, and *va*), and not words in themselves (*badi*, *vadi*, *itudi*) meaning 'the

- dark fortnight' and 'the bright fortnight'; they denote the fortnight, and the solar or more properly civil day in the fortnight or in the month . . . 85 n., 92 n.
- Baghêlkhând, inscriptions from . . . 93,
100, 106, 110, 112, 121, 125, 129, 132, 135
- bâhulîya*, 'a bull' 157 and n.
- Baldâhikrita*, an official title . . . 109 n., 210 and n.
- Râladitya, a *biruda* or second name of Dhruvasêna II. of Valabhi 41, 182
- Bâlâditya, a king of Kâśī, and apparently not the first of that name, 285, 286;—another king of Kâśī, of the same name; his wife was Dhavalâ 256
- Bâlâditya, Bâlâdityadêva, an early king of Magadha, who is mentioned by Hiuen Tsiang in connection with Mihirakula, 215, 218;—there is probably an allusion to him in the Sârnamth inscription 286
- Balavarman, a king in Northern India, conquered by Samudragupta 13
- Balavarman *parichchhâda*; an ancient territorial division in Baghêlkhând 105
- bali*, one of the five great sacrificial rites 116 and n., 124, 129, 132, 170, 190, 290
- Bali, a demon, whose power was overthrown by Viṣṇu in his incarnation as a dwarf 62
- Bandhuvrman, a Mâlava feudatory of Kumârâgupta (Early Gupta), 7, 80, 86;—the Mandasâr inscription, which gives for him the date of the Mâlava year 493 79;—the value of this record, in proving that the Gupta era runs from an epoch in or very close to A.D. 319-20 65
- Bandhuvatsavâmin, a grantee 199
- bappa*, a Prâkrit word meaning 'a father' 186 n., 188, 189
- Bâppadêva, a *Sênapati* of Pravarasêna II. 249
- Bappârya, a grantee 243
- Bappasvâmin, a grantee 105
- Barâbar Hill, in the Gayâ District; mentioned under the ancient name of Pravargiri, 222, 223;—the cave inscription of Anantavarman
- bâva*, a Prâkrit word denoting 'a relative of the same generation with a father,' i.e., generally, 'an uncle' 18-186 n
- Bayley, Sir E. Clive; the views expressed by him on the Gupta era and connected matters, with the result that he lectured the epoch of A.D. 190-91 3, 58
- Beal, the Rev. S.; certain points in translation of the Travels of Hiuen Tsiang, which may be made more clear through the Early Gupta chronology 40
- Benares mentioned under the ancient name of Kâśī 286
- Benares District, an inscription from the 284
- Bendall, Mr. C.; the importance of his discovery of the Gôlmâqhiyôl inscription of Śivadêva I. of the (Gupta) year 316, which proves the use of the so-called Gupta era in Nêpâl, and fixes the chronology of the early rulers of that country 96
- Bengal Asiatic Society's Library, an inscription from the 200
- Bengal Presidency, inscriptions from the 47, 200, 208, 211, 212 n., 213, 221, 223, 226, 254, 274, 278, 280, 281, 283
- Bennâkârpara *bhâga*, an ancient division in the territory of the Vâkâtaka *Mahârâjas* 248
- Berars, an inscription from the 235
- Bhadra, a proper name 259
- Bhadrâryâ, a proper name 51, 52
- bhâga*, a territorial term 248
- bhâgabhâga*, 'royalties,' a fiscal expression 120 and n., 124, 129, 132, 138, 254 and n.
- Bhagadatta, the name of a king, or of a family of kings, a Nêpâl inscription allots Harsha of Gauḍa, Kalinga, Kôsala, Ôdra, &c., to the Bhagadatta lineage, 187;—intermarriage of this family with the Thâkurî rulers of Nêpâl 187
- Bhâgalpur District, an inscription from the *bhâgasvâbhaktia*, a Vaishnavâ sectarian title 271
- Bhagavadbôsha, a proper name 156
- Bhâgavat*, in the sense of 'divine,' denotes the god Viṣṇu, if not connected with any other specific name, 28 n.;—thus used (see also some of the sectarian titles quoted under Vaishnavâ inscriptions), 40, 41, 123, 124, 129, 269, 270;—applied to Buddha, 28 n., 47, 262;—to Kârttikêya, 28 n., 44;—to Jinêdra, 28 n.;—to Siva, 28 n., 36, 290;—to the Sun, 28 n., 71, 218;—to Viṣṇu, 28 n., 56, 78, 90, 115, 142, 161;—applied to priests, in the sense of 'venerable,' 28 n.;—and to Vyâsa, the arranger of the Vêdas 28 n., 98, 105, 109, 116, 120, 124, 129, 134, 171
- Bhâgavata*, a Vaishnavâ sect 28 n., 123
- b'âgavati*, feminine of *bhâgavat*; applied to the goddess Pishtapurî or Pishtapurikâ 116, 132, 138
- Bhâgratha, an epic hero 77
- Bhâgrathi, the river Gaṅgâ, as 'belonging to Bhâgratha,' with reference to the legend of his bringing down the river from heaven to earth 241, 248
- Bhagrath, or Bhâgrath; the *Dâtaka* of the grants of Hastin of the (Gupta) years 156 and 163 100 and n., 105
- Bhagwanal Indrajî, Dr.; remarks on, and rectification of, the historical results deduced by him from the Nêpâl inscriptions 95, 96 and n., 177 to 191
- Bhâgyadêvi, daughter of Bhôgadêvi and Sûrasêna or Sûrasêna 180
- Bhairava, see Svâmi-Mahâbhairava 241, 248

- Bhāndak, a village in the Central Provinces; it is not to be identified with Vākātaka as the supposed name of a place 234
- Bhandarkar, Dr. R. G.; views expressed by him on the Gupta era and connected matters 48, 63
- Bhānugupta, a king, perhaps of the Early Gupta stock, 7, 17, 92, 93, 152;—the Eran pillar inscription, which gives for him the date of the (Gupta) year 191, . . . 91;—a note on the details of the date 77 n.
- Bhānuguptā, wife of Ravikṛtī 152, 156
- Bharadvāja *gōtra* included the Parivrājaka *Mahārājās* 115
- Bhāraśiva, a tribe or dynasty, connected by marriage with the Vākātaka *Mahārājās* 241, 248
- Bharata, an epic hero 77 147
- Bharatpur State, inscriptions from the 251, 252
- Bhartṛiśarma, a grantee 243
- Bharukachchha, an intermediate ancient name of the modern Broach 95 n.
- Bhāskarachārya, an astronomer; the author of the *Siddhānta-Sirōmani*, the date of which is A.D. 1150-51, . . . 156 n.;—his rendering of the rule of the *Brahm-Siddhānta*, for one of the unequal-space systems of the *nakṣatras* 166
- Bhāskaradatta, a grantee 97
- bhata*, 'regular troops,' in composition with *chōḍa* and *chhōḍra*, 98 and n., 105, 109, 120, 128, 132, 138, 169, 195, 199, 242, 249, 299;—used alone . . . 98 n., 241, 248
- Bhatārka, *Sāndapati* (of Valabhi), 41, 167, 180;—he overthrew a tribe or dynasty named Maitraka 13, 167, 180
- Bhāṣa*, a title of respect attached to the names of learned Brāhmins 52, 190, 298
- Bhāṣṭraka*, a regal title, properly applied to feudatory *Mahārājās*, 177, 178, 180, 181, 17 n.;—but sometimes applied to paramount sovereigns, 180, 17 n.;—applied to a *Yuvardja*, 181;—used without anything to shew the status of the person whom it qualifies, 182;—in the sense of 'worthy of worship, sacred,' applied to gods, 17 n.;—thus, to the Sun, 129, 218;—in the sense of 'reverend,' applied to priests 17 n.
- Bhāṣṭriki*, feminine of *Bhāṣṭraka*, a title of the wives of *Mahārājās* and *Mahāśmantas* 17 n., 221, 290
- Bhāṣṭisōma, a proper name 67
- Bhau Daji, Dr.; views expressed by him on the Gupta era and connected matters 41, 44
- Bhava, a Buddhist teacher 277
- Bhavadatta, a grantee 298
- Bhavanāga, *Mahārāja*, of the Bhāraśiva tribe or dynasty; his daughter was the wife of Gautamiṣṭra 241, 248
- Bhavanī, the goddess Pārvatī, the wife of Śiva, in her pacific and amiable form . . . 228
- bhava-sṛij*, 'the creator of existence,' an epithet of the god Śiva 155 and n.
- Bhavasvāmin, a grantee 97
- Bhēśā, a town in Scindia's Dominions; inscriptions in its neighbourhood . . . 21, 34
- Bhikṣhu*, 'a Buddhist mendicant,' 33, 34, 47, 262, 281;—mention of Śākya *Bhikṣhus* 272, 279, 280, 282
- Bhikṣhuvī*, feminine of *Bhikṣhu*; mention of a Śākya *Bhikṣhuvī* 274
- Bhīmadēva, a Hindu king of Kābul; remarks on some of his coins, which have been supposed to bear dates in the Gupta era 57 to 60
- Bhīmavarman, *Mahārāja*, 266;—his Kōśam image inscription of the (Gupta) year 139 266
- Bhitari, a village in the Ghāzipur District; the pillar inscription of Skandagupta 52
- bhōga*, a territorial term 112 and n.
- bhōgabhōga*, 'share of the enjoyment, a fiscal term 189, 195, 200, 299
- Bhōgadēvī, sister of Amṣuvarman, and wife of Sūrasēna or Sūrasēna 180
- Bhōgavarman (Maukharī), son-in-law of Adityasēna of Magadha . . . 177 n., 187, 15 n.
- Bhōgavarman, son of Bhōgadēvī and Sūrasēna or Sūrasēna, and nephew of Amṣuvarman 177 n., 180
- Bhōgavarman, *Sāmān*, the *Dātaka* of the inscription of Śivādēva I. of the (Gupta) year 316; perhaps to be identified with the nephew of Amṣuvarman . . . 177 and n.
- Bhōgika*, an official title 100 and n., 105, 109, 120, 124, 129, 134
- bhōgya-tiṭhi*, 'the portion of a *tiṭhi* that is still to run' 152
- Bhōjadēva of Kanauj; examination of the date of his Bhōgadh inscription of Vikrama-Samvat 919 and Śaka-Samvat 784, which proves that one or other, or both, of the unequal systems of the *nakṣatras* continued in use up to A.D. 862 107
- Bhōjaka*, the title of a class of priests 218 and n.
- Bhōjakadēvārya, a grantee 243
- Bhōjakata, a kingdom subject to the Vākātaka *Mahārājās* 241
- Bhōpāl State, inscriptions from the, 29, 260, 279;—remarks on the spelling and derivation of the name of Bhōpāl . . . 29 n.
- Bhrukunthasiha, a proper name 71
- Bhujamgadhā, a proper name 116
- bhukta-tiṭhi*, 'the elapsed portion of a *tiṭhi*' 152
- Bhukti*, a territorial term 100 n., 218 and n., 295 and n., 298
- Bhumarā a village in the Nāgaudi State; the pillar inscription of Hastin and Sarvanātha 110

- Bhumbusapadraka, the name of some land in the village of Vajragrāma . . . 170
- bhūmi*, a particular land-measure . . . 241 and n.
- bhūmichchhidra*, a fiscal term . . . 178 and n., 170, 190
- bhūta*, a fiscal term, requiring explanation . . . 170 and n., 189
- Bhūtapati, the god Śiva, as 'the lord of beings' . . . 225
- Bihār, a town in the Patna District; mentioned under the ancient name of Vi-hāra, and as the city of Yaśodvarman, 47 n.; — the pillar inscription of Skandagupta . . . 47
- Bijayagadh, a hill-fort in Rājputānā, near Byānā, the fragmentary inscription of the Yaudhēyas, 251; — the pillar inscription of the Varika Viśhuvardhana, of the (Mālava) year 428 . . . 252
- Bilsad, or Bilsand, a village in the Etā District, the pillar inscription of Kumāragupta of the (Gupta) year 96 . . . 42
- bird-standard on the Early Gupta coins; there is evidently an allusion to it in the mention of the Garuda-tokens, i.e. coins or banners bearing representations of Garuda, that were given by feudatories to Samudragupta . . . 14 and n.
- Blochmann, Mr.; his proposal for amending the translation of Albrētn's words regarding the origin of the Gupta era . . . 28 n.
- Bōdh-Gayā, a Buddhist site near Gayā; the inscription of Mahānāman of the (Gupta) year 269 (the date of which, however, should perhaps be referred to the Kalachuri era), 274; — the image inscription of Mahānāman, 278; — the image inscription of Dharmagupta and Daṁṣhīrasēna . . . 281
- Bōdhimaṇḍa, the miraculous throne under the *bōdhi*-tree at Bōdh-Gayā, or its site . . . 275, 278
- Bōdhivarman, a proper name . . . 272
- Bombay Presidency, an inscription from the . . . 56
- boppa*, a Prākṛit word meaning 'a father' . . . 188 n.
- bōta*, or *vōta*, a termination of names . . . 31 n.
- Bōtaka, a proper name . . . 170
- 'box-headed' characters . . . 18, 192, 196, 233, 236, 244, 292
- Brahmadēvasvāmin, a grantee . . . 195
- Brahmagupta, an astronomer; he was born A.D. 598, . . . 172; — he is the author of the *Brahma-Siddhānta*, the date of which is A.D. 628-29, . . . 156 n., 165 n.; — and this is the text-book of the Brāhmapaksha school of astronomers, 145 n.; — his rule, as rendered by Bhāskarachārya, for one of the unequal-space systems of the *nakṣatras*, 166; — his rule for determining the years of the Twelve-Year Cycle of Jupiter by the mean-sig system . . . 169
- Brahman, the god, 'the creator' of the Hindu triad (see Svayambhū, Vēdhas, Vidhātṛi; and, for his wife, see Sarasvatī), 155 n., 208; — mentioned as the creator, preserver, and destroyer, subject to the direction of Śiva . . . 155 and n.
- Brahmanya, an epithet of the god Kārttikēya . . . 45
- Brahmapūra, a village in the Beṅgālāpara *bhāga* . . . 248
- Brahmaputra, the river; mentioned under the name of Lauhitya, 145, 148; — and of Lōhitya . . . 206
- Brahma-Siddhānta*, an astronomical work by Brahmagupta; it was written A.D. 628-29, . . . 156 n., 165 n.; — and it is the text-book of the Brāhmapaksha school of astronomers . . . 145 n.
- Brihaspati, the regent of the planet Jupiter, and the preceptor of the gods 170, 76, 86, 90 n., 157
- Brihaspati, an astronomer, quoted by Dādābhāt, in the *Kirāṇavali*, in support of the heliacal-rising system of the Twelve-Year Cycle of Jupiter . . . 170
- brihaspatsava*, a particular sacrifice 241 and n., 248
- Brihat-Samhitā*, an astrological work by Varāhamihira; its statement for the naming of the years of the Twelve-Year Cycle of Jupiter according to his heliacal rising in particular *nakṣatras*, 161; — and for the grouping of the *nakṣatras* for that purpose . . . 162
- Broach (Bharuch, or Bharoeb), the chief town of the Broach District; mentioned under the ancient name of Bharekachcha . . . 95 n.
- Buddha (see also Buddhas, and Sugata), the founder of the Buddhist religion, 262; — mentioned as 'the teacher' or 'the teacher of mankind', 277, 278, 281; — as 'the saint', 'the chief of saints', and 'the great saint', 277, 278; — and as 'the chief kinsman of the Śākya', 277; — inscribed images of Buddha . . . 45, 278, 280, 281
- Buddhagupta, a king of Magadha, mentioned by Hiuen Tsiang; he is not to be confused with the Buddhagupta of the Eraṇ pillar inscription . . . 46 and n.
- Buddhamitra, a proper name . . . 47
- Buddhas, mentioned as four in number, 262 and n.; — invoked in the plural 47 and n.
- Buddhist inscriptions (for another instance of Buddhist worship, see *paramasaugata*) 123, 29, 45, 260, 262, 271, 272, 273, 274, 278, 280, 281
- Buddhists spoken of under the sectarian title of *Paramasaugata* . . . 33 and n.
- Budhagupta, a king, perhaps of the Early Gupta stock, 7, 27, 80, 90; — he is not to be confused with the Buddhagupta, king of Magadha, mentioned by Hiuen Tsiang, 46 n.; — his Eraṇ pillar inscrip-

- tion of the (Gupta) year 165, .. 88;
— examination of the date 80
- Bühler, Dr. G.; quoted as inclined, subject, however, to further consideration, to identify *T'u-lu-h's-po-tu* with Śīlāditya VII. of Valabhi 51
- Bulandshahr District, an inscription from the 68
- bull-emblem on seals 164, 210, 231, 282, 283
- Bundékhagd; mention of this part of the country under the ancient name of Dabhāla or Dahāla, 113, 114 116;— inscriptions from Bundékhand 233
- Calcutta Imperial Museum, inscriptions in the . 18, 36, 39, 40, 264, 267, 274, 280, 281, 284
- castes; mention of the castes and stages of religious life, 185, 221, 232;—castes mentioned in this series of records:— Brāhmaṇ; by the name Brāhmaṇa, 38, 39, 71, 97, 104, 105, 109, 116, 120, 123, 128, 132, 138, 170, 218, 241, 242, 249, 252, 257, 265, 290, 298;—by the word *brahman*, in *brahma-dāya*, *brahma-dāya*, *brahma-gṇa*, *brahma-hatyā* and *brahm-arshi*, 34, 84, 171, 185, 190, 242;—by the words *dvija* and *dvijāti*, 64, 67, 71, 72, 78, 163 and n., 185, 195, 200, 206;—and by the word *vijra*, alone and in *vijra-arshi*, 71, 85, 90, 160;—Kahatriya; by the name Kahatriya, 71, 129;—and by the words *kshattrā* and *kshātrā* 223, 225, 227, 251
- cave-inscriptions . 21, 34, 221, 223, 226, 258
- Central India, inscriptions from . 21, 29, 34, 72, 79, 93, 100, 106, 110, 112, 121, 125, 129, 132, 135, 142, 149, 150, 233, 258, 260, 279
- Central Provinces, inscriptions from the 18, 88, 91, 117, 158, 191, 196, 219, 243, 291
- Ceylon, mentioned under the name of Simhala, and as conquered by Samudragupta, 14;—mentioned under the name of Amradvipa, 278, 279;—and of Lañkā, 277, 278;—its early history and dates require to be rectified in accordance with the Bôdh-Gayā inscription of Mahānāman (or may be adjusted by it, if the date of it should be in the Kalachuri era) 16, 275
- chakra*, 'a discus'; as an emblem on seals 292
- Chakrabharti, the god Vishṇu, as 'the wielder of the discus' 65
- Chakradhara, the god Vishṇu, as 'the holder of the discus' 78 n., 221
- Chakrapālitā, the governor of the town of Girinagara in the time of Skandagupta 63, 64, 65
- Chakrapāṇi, the god Vishṇu, as 'holding the discus in his hand' 240, 248
- Chakravartin*, a title of paramount sovereignty 41, 134 n., 183 and n.
- Chammak, a village in the Illichpur District; mentioned under the ancient name of Charmānka, 236, 241;—the grant of Pravarasēna II. 235
- Chandra, an emperor of Northern India, 12, 142;—he may perhaps be identified with the Early Gupta king Chandragupta I., or he may possibly be the younger brother of Mihirakula, mentioned, but not named, by Hiuen Tsiang, 12, 140 n.;—he may possibly have had also the name of Dhāva; but this is hardly borne out by the construction of the record, 142 n.;—his Mēharaul posthumous pillar inscription 130
- Chandragupta I. (Early Gupta), 17, 18, 16, 28, 44, 51, 54, 257;—he seems to have had the *birudas* or second names of Vikrama and Vikramāditya, 18;—his wife was Kumārādēvi, of the Lichchhavi tribe or clan, 16, 28, 44, 51, 54, 257;—he may perhaps be identified with the Chandra of the Mēharaul pillar inscription 12, 140 n.
- Chandragupta II. (Early Gupta), 17, 28, 25, 28, 32, 33, 35, 38, 44, 51, 54;—spoken of as 'the accepted son' of Samudragupta, 27, 51, 54;—this seems to indicate that he was specially selected by his father to succeed him, 12 n.;—he had the *birudas* or second names of Vikrama, Vikramāditya, and Vikramānka, 28;—he may possibly have had the title of Dēvarāja; but it has not been found on his coins, and it is more probably the name of one of his ministers, 33 n.;—his wife was Dhruvadēvi, 44, 51, 55;—he visited Udayagiri on a tour of conquest, 36;—his Udayagiri inscription of the (Gupta) year 82, . . . 21;—his Mathurā inscription, 25;—his Sāñchi inscription of the year 93, . . . 29;—his undated Udayagiri inscription, 34;—his Gadhwā inscription of the year 88 36
- Chandrāpura, an ancient town 71
- Chandrarvarman, a king in Northern India, conquered by Samudragupta 13
- Chandrarvarman, *Sāmanta*, mentioned in the inscription of Jishnugupta of the (Harsha) year 48 180
- charaṇa*, a sect or school studying any particular *śākhā* of the Vedas 241
- Charmānka, the ancient name of the modern Chammak 236, 241
- charu*, one of the five great sacrificial rites . 116 and n., 124, 12 170, 190, 290
- chhāta*, 'irregular troops,' in position with *dhāta* . . 98 and n., 1 109, 120, 128, 132, 138, 69, 195, 199, 299
- haturdaśa-vidyāsthāna*, 'the fourteen sections of science' 115 and n.
- chatur-śākhī-sāñchi-śrūdhitā-yastā*, an epithet of Samudragupta, 27, 44, 51, 292

54, 257;—applied also to Vijayārjya (Chalukya of Gujārat) 14 n.
Chaturvādin, 'a Brāhmaṇ acquainted with the four Vēdas' 71, 190, 242
chaura-varjam, a fiscal term which is explained by *chōra-danda-varjyam* 109
Chaurōddhāranika, an official title . 218 and n.
 Chēdi era; see Kalachuri or Chēdi era . 8, 9, 10
 Chhagalaga, *Mahārāja* (Sanakānika) 25
 Chhandāpallikā, an ancient village in the Nāgadēya *santaka* 120
chhātra, 'an umbrella bearer,' in composition with *bhāṣa*, 242, 249, — used alone 241, 248
 Chhatre, the late Prof. Kero Lakshman; a method of calculating the week-days, ending-times, and English dates, of Hindu *tithis*, with his Tables, explained by Mr. Sh. B. Dixhit, Appendix II., 145 to 159; — the results thus obtained, may sometimes differ from those obtained from the *Sūrya-Siddhānta* and other Hindu works; but the difference will not amount to more than 5 or 6 *ghaṭis* 155
 Chhōdugōmika, a grantee 132
 Chhōdugōmin, a proper name 116
 Chirbira, the *Dātaka* of the Māliyā grant of Dharasēna II. of the (Gupta-Valabhl) year 252 171
 Chitrakōtasvāmin, the god Vishnu, as 'the lord of Chitrakōta' 268 and n.
 Chitravarman, a *Sēnāpati* of Pravarasēna II. 243
chōra-danda-varjyam, a fiscal term . 98 n., 124
chōra-dvāḍhaka-varjam, a fiscal term which is explained by the preceding 116
chōra-varjam (see also *chaura-varjam*), an elliptical expression for *chōra-danda-varjyam* 98 and n.
chōra-varjita, a fiscal expression which is explained by the same word . 120, 138
 coins; remarks on coins of the Early Guptas, 36 n., 12 ns., 14 ns., 15 n., 25 n., 27 n., 28 ns., 46 n.; —of Samudragupta, 12 ns., 14 ns., 15 n., 27 n., 28 ns.; —of Skandagupta, 25 n., 46 n.; —of the Hindu kings of Kābul, 57 to 60; —of the Kshatrapas or Mahākshatrapas of Saurāshtra, 36 n.; —and of Tōramāna II, 12
 copper-plate charters are usually denoted by the terms *śāsana*, 99 n., 194, 199, 218, 240, 242, 247, 249, 296.—and *tāmra-śāsana*, 99 n., 109, 116, 128, 132, 138, 195, 199, — an exceptional instance, in which such a charter is denoted by the term *prāsāsti*, 87 n.; — an illustration of functions connected with a copper-plate charter, 99 n.; —the edges of copper-plates are sometimes left smooth, 68, 101, 106, 112, 121, 191, 196, 235, 243, 254, 292; — sometimes fashioned thicker, to serve as rims to protect the writing, 68 n., 117, 123, 170,

133, 135, 172; — and sometimes beaten up, to make raised rims for the same purpose 68 n., 164
 cows spoken of as the daughters of the sun, 195 and n., 200, 299;—cow-and-calf-sculpture, with a tree, on an inscription stone 274 and n.
 cremation of widows, an epigraphical instance of 92 and n., 93
 Cunningham, Gen. Sir A.; the views expressed by him on the Gupta era and connected matters, with the result that he finally selected the epoch of A.D. 166-67 32, 33, 38, 45, 48, 51, 53, 61
 current and expired years (see also expired years); the proper method of the interpretation of the years in recorded dates, irrespective of the question of the application of the years for calculation, 22 n.; — current years can come to be ordinarily superseded by expired years, only in the case of eras that are actually applied by astronomers for astronomical purposes, 143; — a distinct instance of the use of a current year, after the quotation of the preceding expired year, 129, 22 n., —instances of the use of regnal years, which are naturally to be interpreted as current years, 24 n., 159, 161, 192, 197, 236, 244, 287, 293, —instances of the use of years, of eras, which, not being specified as expired, are naturally to be interpreted as current, 80, 85, 91, 93, 95, 104, 110, 114, 117, 22, 30, 37, 41, 43, 46, 57, 58, 66, 70, 89, 92, 95, 102, 107, 113, 118, 121, 126, 133, 135, 165, 173, 209, 255, 261, 263, 266, 268, 273, 274; —instances of the use of years, of eras, which apparently are to be interpreted as current, but which have to be applied as expired for calculation, 80 n., 85, 107 n.; —instances of the use of both current and expired years of the Kaliyuga, Vikrama, and Saka eras, in Hindu almanacs 138 to 141

d, lingual; a special and unique form of it, from which the modern *Dēvanāgarī* form is derived 72 and Plate
 Dabhāla, or possibly Dahāla, the name of the hereditary kingdom of Hastin, the modern Bundelkhāṇḍ 113, 114, 116
 Dacca (Dākā), a Division, District, and town in the Bengal Presidency; perhaps mentioned under the ancient name of Davāka 9 n., 14
 Dādābhāt, author of the *Kīrandvālī*, a commentary on the *Sūrya-Siddhānta*; his quotation of Brihaspati in support of the heliacal-rising system of the Twelve-Year Cycle of Jupiter, 170; — his comments on a verse of the *Sūrya-Siddhānta* in the same connection 171 n.

Dabhā, a possible reading instead of Dabhā 113, 114, 116 n.

Daivaputra a dynasty or tribe, conquered by Samudragupta 14

Dakṣha, a proper name 157, 158

dakṣiṇpātha, 'the region of the south,' a technical name for Southern India, 13 and n.;— list of the kings conquered therein by Samudragupta 13

Damaṇa of Eraṇḍapalla, a king in Southern India, conquered by Samudragupta 13

Dāmōdara, the god Viṣṇu, as 'wearing a cord round the belly' 206

Dāmōdaragupta (Gupta of Magadha), 206;— he defeated the Maukharis 206

Dāmōdaragupta, *Mahārāja* (Parivrājaka) 97, 104, 109, 115

Datishṭrasēna, a proper name 282

Dandapāṭika, or *Dāndapāṭika*, an official title 170 and n., 218

Dāndika, an official title 218 and n.

dāradranaka, a fiscal term, requiring explanation 299 and n.

Dāramaṇḍala, apparently an ancient district in Baghelkhand 125

das-āparādha, 'the ten offences' 189 and n., 218

Daśapura, the ancient name of the modern Daśōr or Mandasōr . 79 and n., 84, 86

Daśōr, the popular and more correct name of Mandasōr 79 and n.

dates (see also *eras*) in this series of records, in the other Gupta-Valabhi records quoted for calculation, and in the Nēpāl inscriptions, recorded in— decimal figures 85, 91, 97

decimal figures combined with numerical symbols 292 n., 293

numerical symbols 81, 93, 95, 114, 117, 119, 177 to 184, 22, 30, 37, 41, 46, 89, 92, 107, 110, 118, 165, 173, 192, 197, 209, 236, 255, 261, 263, 266, 273, 274, 287, 293

words 81, 97, 104, 110, 114, 117, 22, 43, 58, 66, 70, 73, 80, 89, 92, 95, 102, 107, 113, 118, 121, 126, 133, 135, 151, 159, 161, 173, 236, 244, 258, 263, 268

Dattadēvi, wife of Samudragupta, 21 n., 27, 44, 51, 54;— a reference to her, without mention of her name 21

Davāka, a country, perhaps the modern Dacca (Dākā); Samudragupta either included it in his empire, or else extended his conquests up to the confines of it 9 n., 14

days of the week, names of the, as used in the only three instances that occur among the Gupta-Valabhi dates—

Ravi, i.e. Ravivāra (Sunday) 85

Sōmā, i.e. Sōmavāra (Monday) 91

Surugurudivasa (Thursday) 61, 90

days, lunar (see also *tithi*); special expressions, of occasional use, connecting them with the solar or more properly

civil days, are, *asyām divasa-pūrodyām*, 38, 40, 41, 44 and n., 97 and n., 104, 120, 265;— *asyām divasa-māsa-samvatsar-ānupūrvyām*, 97 n., 210, — *asyām samvatsara-māsa-divasa-pūrodyām*, 97 n., 108, 115;— and *śasyām pūrodyām*, 160, 254;— and another method, in the Nēpāl inscriptions, is the use of *divd* in composition with the *tithi*, 85 n., 178, 180 to 184;— lunar days mentioned in dates of this series, in the other Gupta-Valabhi dates used for calculation, and in the Nēpāl inscriptions:—

bright fortnight:—

first 95, 182, 183

second 93, 110, 179, 180, 183, 87, 104

third 104, 183, 97

fifth 191

seventh 184

ninth 184

tenth 178, 180, 182

eleventh 25

twelfth 81, 90, 248

thirteenth 117, 183, 115, 243

dark fortnight:—

third 114, 108

seventh 93

fifteenth 254

fortnight not specified:—

twelfth 298

days, solar, or more properly civil, denoted by *ahan*, and by *dina*, or *divasa*, or their abbreviations *di* and *diva*, and mentioned in dates of this series, in the other Gupta-Valabhi dates used for calculation, and in the Nēpāl inscriptions:—

bright fortnight:—

second 91

fifth 97

seventh 210, 278

eleventh 291

thirteenth 77, 87

dark fortnight:—

seventh 93

thirteenth 85

fifteenth 171

fortnight not specified:—

third 114, 109

fourth 34

fifth 259, 262

sixth 64, 139

seventh 267

eighth 299

ninth 200

tenth 40, 129, 160, 237

fourteenth 120

eighteenth 47

nineteenth 119, 112

twentieth 134, 263

twenty-first 268

twenty-second	124	Dēvatā, a proper name	263
twenty-fifth	195	Dēvavishṇu, a proper name	71
twenty-seventh	117, 116, 274 n.	<i>dēvī</i> , a title of wives of <i>Mahārājās</i> (used also as a termination of the names of wives of both paramount sovereigns and feudatories; see under names, proper)	221 and n., 232
decimal figures (see also dates); the earliest epigraphical instances of the use of them, 209 n.;—instances of the use of them in the Verāwal and Mōrbī records, 85, 91, 97;—instances of the mixture of them with numerical symbols, 292 and n.;—forms of decimal figures illustrated in this series of Plates:—			
eight	292	Dēvī, the goddess Pārvatī, the wife of Siva, as 'the (principal) goddess,' 225, 227;—a mention of her defeating the demon Mahishāsura	227
Dehli District, an inscription from the	139	Dēvī, daughter of a supposed Mahādaitya, an imaginary wife of Samudragupta	18, 19
Dēh-Baraṅk, a village in the Shāhābād District; mentioned under the ancient name of Vārunikā, 214, 215, 218;—the modern name is from Dēva-Vārunārka, 215;—the inscription of Jīvitagupta II.	213	<i>dēva-dharma</i> , 'an appropriate religious gift'; a formula used in certain donative inscriptions	25 and n., 210, 263, 272, 273, 274, 279, 280, 282
Dēōgadh, a village in Central India; examination of the date of the inscription of Bhōjadēva of Kanauj, of Vikrama-Sarhvatigandaka-Samvat 784, which proves that one or other, or both, of the unequal systems of the <i>nakshatras</i> continued in use up to A.D. 862	107	Dhanada, —the god Kubēra, as 'the giver of wealth'	14, 21, 28, 44, 51, 54, 257
'Deoghar,' a village in the 'Santal' Parganās; a late inscription at this place, mentioning Ādityasēna of Magadha	212 n.	<i>Dhanada-Varun-Ēndr-Antaka-sama</i> , an epithet of Samudragupta, 14, 21 n., 28, 44, 51, 54, 257;—applied also to Vijayarāja (Chalukya of Gujārat)	14 n.
Dēōriya, a village in the Allahābād District; a Buddhist inscription	271	Dhanashya of Kusthalapura, a king in Southern India, conquered by Samudragupta	13
Dērabhaṭa (of Valabhī)	47, 184	Dhanēsa, the god Kubēra, as 'the lord of wealth'	169, 181
<i>dēśa</i> , a territorial term	32 and n.	Dhānyavāhika, an ancient village in Baghēlkhāṇḍ	124 and n.
Dēva, a proper name	71	Dhanvavishṇu, younger brother of the <i>Mahārāja</i> Mātṛivishṇu	89, 90, 160, 161
Dēvādāngira, a grantee	105	Dhā-tā, a city, the modern Dhār in Central India; reference to the defeat of a king of this city by a Maukhari chief	230
Dēvādhyā, <i>Mahārāja</i> (Pativrājaka)	97 and n., 104, 109, 115	Dharapaṭṭa, <i>Mahārāja</i> (of Valabhī)	41, 168
Dēvagupta, Dēvaguptadēva (Gupta of Magadha), 15, 215 n., 217, 240, 247;—his wife was Kamaladēvī, 217;—his daughter Prabhāvatiguptā was the wife of Rudrasēna II.	15, 240, 247	Dharasēna I., <i>Sōndapati</i> (of Valabhī)	41, 168
Dēvaka, a proper name	286	Dharasēna II., <i>Mahārāja</i> (of Valabhī) 41, 169, 171, 181;—his Māliya grant of the (Gupta-Valabhī) year 252	164
Dēvaki, the mother of Krishna	55	Dharasēna III. (of Valabhī)	41, 182
Dēvamitra, a grantee	105	Dharasēna IV. (of Valabhī), 41, 134 n., 183;—he was the first paramount sovereign in the Valabhī family; and his power was perhaps more extensive than that of his successors, 134 n.;—examination of the date in his Kairiz grant of the (Gupta-Valabhī) year 330	93
Dēvanāga, a grantee	105	<i>dharmachakra</i> , the Buddhist 'wheel of religion,' as an emblem on inscription stones	263, 269
Dēvapattana, an ancient name of the modern Verāwal	91	Dharmadāsa, a proper name	280
Dēvarāja, possibly a title of Chandragupta II.; but it has not been found on his coins, and it is more probably the name of one of his ministers	33 and n.	Dharmadēva (Lichchavi of Nēpāl), 182, 186, 189;—his wife was Rājyavatī	182
Dēvarāshtra, a country in Southern India; in the time of Samudragupta, its king was Kubēra	13	Dharmāditya, a <i>biruda</i> or second name of Śīlāditya I. of Valabhī, 41, 181;—and of Kharagraha II. of Valabhī	41, 184
Dēvārya, a grantee, 242;—another of the same name	242	Dharmadōsha, a minister of Vishnuvardhana of Mālava	157
Dēvāgarman, a grantee, 243;—another of the same name	248	Dharmagupta, a proper name	282
Dēvāsarmārya, a grantee	243	Dharmārya, a grantee, 246;—another of the same name	243
Dēvasvāmin, a grantee, 105;—another of the same name	109		

- Dhāva, possibly another name of the emperor Chandra; but this interpretation is hardly borne out by the construction of the record 142 n.
- Dhavalā, wife of the second Bāladitya mentioned by name in the Sārāsth inscription 286
- Dhavaṣaṅgikā, an ancient village in Baghēlkhaṇḍ, 123; — another of the same name, or perhaps the same village, in the Vōṭa *santisa* 130, 132
- Dhiniki, a village in Kāthiāwāḍ; examination of the date in the grant of Jāika-dēva, purporting to be in the Vikrama year 794, with the result that this grant must be held to be spurious 62 n.
- Dhritivāṃika, the *Dātaka* of the grant of Śarvanātha of the (Gupta) year 214 139
- Dhṛōbhāṭa, a marical abbreviation of the name of Dhruvabhāṭa 42, 172 n., 189
- Dhruvabhāṭa, a *biruda* or second name of Śīlāditya VII. of Valabhh, occurring in the abbreviated form of Dhṛōbhāṭa, 42, 172 n., 189; — it has been supposed to be represented by the Chinese *T'u-lu-h'o-po-tu*; but the Chinese name certainly cannot denote the seventh Śīlāditya 40
- Dhruvabhūti, *Mahādāṇḍadyaka* 16
- Dhruvadatta, *Bhūgika* 120
- Dhruvadēva, *Mahārāja* (Lichchavi of Nēpāl), 180, 181, 189, 190, 191; — he had the epithet of 'the banner or glory of the Lichchavikula' 282
- Dhruvadēvī, wife of Chandragupta II. 44, 51, 55
- Dhruvādāhiraṅgika, an official title 169, 170 n.
- Dhruvaśarman, the person who caused the Bilsāḍ inscribed pillars to be set up 45
- Dhruvasēna I., *Mahārāja* (of Valabhh) . 42, 168
- Dhruvasēna II., *Mahārāja* (of Valabhh), 42, 182; — he had the *biruda* or second name of Bāladitya 41, 182
- Dhruvasēna III. (of Valabhh) 42, 184
- dhruva*, 'a banner or standard,' as distinguished from *idāchhana*, 'a crest,' 151 n.; — used to denote the Mēharaul pillar, 140, 142; — *dhruva-stambha* 'a flag-staff,' used to denote the Eraṅg pillar 89, 90
- di*, an abbreviation of *dina*, *dint*, *divasa*, or *divasā*, 85 n., 92 n.; — used in connection with *su*, 91, 97, 210, 277, 291; — used in connection with *ba* or *va*, 85, 93; — used by itself 124, 127, 34, 47, 109, 116 120, 257, 262, 263
- Dighwā-Dubau' a m the Sāran District; the value of the grant of the *Mahārāja* Mahēndrapāya, of the (Haraha) year 155, towards provin^a the epoch of the liars^b 178 n.
- Dikabit, Mr. Shankar Balkrishna; his calculations of dates, 34, 35, 62, 75, 76, 77, 80 to 124, 127, 128, 129, 141; — his exposition of a method of calculating the week-days, ending-times, and English dates, of Hindu *tithis*, with Prof. K. L. Chhatre's Tables, Appendix II., 145 to 159; — his exposition of the Twelve-Year Cycle of Jupiter, Appendix III. 161 to 176
- Dikshita*, a Brāhmanical title 120 and n., 124
- dina* (see also *dī*, and *divasa*), 'a day;' 146, 92 n.; — used to denote the solar or more properly civil day 64, 77, 87, 259
- dindra*, a particular gold coin, or weight of gold 33, 38, 39, 40, 41, 262, 265
- Dinē . . māsvara, a proper name 273
- Diāna, a proper name 124 n., 290
- dina*, an abbreviation of *divasa* or *divasā*; used to denote the solar or more properly civil day 267
- ciud*, 'by day,' an indeclinable used in some of the Nēpāl inscriptions in composition with words denoting *tithis* or lunar days 85 n., 178, 180 to 184
- Divākaradatta, a grantee 97
- Divākarasvāmin, a grantee 105
- divasa* (see also *dī*, *dina*, and *dina*) a day,' 146, 92 n.; — used for the week-day, instead of the usual term *vāra*, 81, 90; — used to denote the solar or more properly civil day, 119, 32 n., 38, 40, 44, 97, 104, 112, 120, 124, 129, 134, 139, 160, 263, 268, 299; — used in connection with words denoting *tithis* or lunar days 97, 104, 108, 115
- Divira*, an official title 123 and n.
- Ḍombhigrāma, an ancient village, in Kāthiāwāḍ 170
- Dōshakumbha, a proper name 157
- Drūgika*, an official title 169 and n.
- drīṣṭam*, 'sight has been attained'; an invocation used at the commencement of inscriptions, 240 and n., 247; — it is the remnant of some such expression as *drīṣṭam bhagavatē* 25 n., 240 n.
- Drōḡasimha, *Mahārāja* (of Valabhh) . . 42, 168
- Drōḡasingha, the engraver of the Rāypur grant of Sudēvarāja 200
- Ḍuḍika, a proper name 71
- duplicate inscriptions 42, 142, 149
- Durdharamiṭra, a grantee 218
- Durgamaḡḡala, apparently an ancient district in Baghēlkhaṇḍ 124
- Durlabha of Muktā, an astronomer quoted by Al-Bērūnī; his method for converting Lōkākāla dates into Saka dates shows that the Lōkākāla reckoning was introduced, at Muktā, in A.D. 926 26 n.
- Dūta*, an occasional substitute for *Dātaka*, 100 n., 291; — used in the sense of an ordinary message-carrier or postman 217 and n.
- Dūtaka* (see also *dūtā*, *Dūka*, and *sumukh-dūtā*), the technical title of an officer, in connection with charters usually recorded on copper-plates but in a few instances on stone, whose duty it was to carry the king's orders to the local officials by whom the charter was

then drawn up and delivered, 100 and n.;—instances of *Dātakas* for charters recorded on copper-plates, 100, 105, 109, 120, 124, 129, 134, 139, 171, 190, 291;—and for charters which, following more or less the same form, are recorded on stone, 177 to 184;—an instance of a second *Dātaka* for additional orders, 100 n., 134, — an instance of more *Dātakas* than one for the original orders 291 n.

dakṣa-land, a term requiring explanation 290 and n.

Dyūta-Gōpasvāmin, *Ākṣhapāṭaldhikīta*, the official under whose orders the spurious Gayā grant of Samudragupta purports to have been written 257

earth; the earth spoken of as 'belonging to Vishṇu, or as being *Vaiṣṇavi*, the female energy of Vishṇu,' 195 and n., 200, 299;—spoken of as resting on a hood of the serpent *Śeṣha*, 208;—its marriage-string is the verge of the four oceans, 86;—its breasts are the mountains *Kailāsa* and *Sumēru*, 86 and n.;—the *Vindhya* mountains, 185;—the *Vindhya* and *Sahya* mountains, 184;—and the mountains *Vindhya* and *Himālaya* 86 n.

Eastern Country, or *Pūrvarāshtra*, an ancient name for part of the Central Provinces; the territory of *Jayarāja* and *Sudēvarāja* 192 and n., 195, 199

eclipse of the sun, mentioned in the *Mōrbi* grant of *Jāinka* 97

elephants, in connection with the goddess *Lakṣmi*, on the seals of grants 191, 196

emblems on the seals of grants and at the top or bottom of stone inscriptions 72, 123, 164, 191, 196, 219, 231, 235, 263, 269, 274, 282, 283, 292

English dates; a method of calculating the English dates of *Hindu tithis*, with Prof. K. L. Chhatre's Tables, Appendix II. 158, 159

epoch; this word is used as the most convenient term for the year 0 of an era, as required for comparison and calculation, and as contrasted with its commencement or first current year *passim*

Ēraṅg, a village in the *Sāgar* District; mentioned under the ancient name of *Aurikīya*, 18 n., 21, 161;—the inscription of *Samudragupta*, 18;—the pillar inscription of *Budhagupta*, of the (*Gupta*) year 165, . . . 88;—the posthumous pillar inscription of (*Bhānugupta* and) *Gōparāja* of the (*Gupta*) year 191, . . . 91;—the boar inscription of *Tōra-māna* 158

*Ēraṅg*palla, a town in Southern India; in the time of *Samudragupta*, its king was *Damana* 13

eras used in this series of records, in the other *Gupta-Valabhi* records quoted for calculation, and in the *Nēpāl* inscriptions:—

Gupta 81, 95, 97, 104, 110, 114, 117, 119, 178, 182, 183, 184, 23, 30, 37, 41, 43, 46, 57, 58, 66, 70, 88, 92, 95, 102, 107, 113, 254, 258, 260, 262, 266, 267, 273

Gupta; hitherto treated as such, but perhaps *Kaichuri* or *Chēdi* 118, 121, 126, 133, 135, 274

Gupta-Valabhi; i.e. belonging to the period when the *Gupta* era may have begun to be called the *Valabhi* era 93, 165, 173

Harsha 178 to 184, 209, and perhaps 287

Hijra 85

Mālava, i.e. *Vikrama* 66 n., 73, 80, 151, 253

Simha 85

Valabhi; i.e. belonging to the period when the *Gupta* era had come to be called the *Valabhi* era 85, 92

Vikrama 85

Ērā District, an inscription from the 42

expired years (see also current and expired years); they can come to be ordinarily used, instead of current years, only in the case of eras that are actually applied by astronomers for astronomical processes, 143;—instances of the use of expired years distinctly specified as such, 79 n., 97, 129, 22 n., 73, 80, 151, 253;—instances of the use of years, which are not distinctly specified as expired, but which have to be applied as such 80 n., 85, 107 n.

feet of a person or god, used for respectful mention of that person or god himself 16, 71, 123 and n., 124, 128, 268, 269, 270

Fergusson, Mr. J.; the views expressed by him on the *Gupta* era and connected matters, with the result that he selected the epoch of A.D. 318-19, . . . 32, 46, 54;—this result is correct within one year; the error being due to certain special considerations connected with the Sixty-year Cycle of *Jupiter*, which do not really apply 33

fire; gold spoken of as 'the first offspring of fire' 190 and n., 200, 299

forest countries, all the kings of the, were subdued by *Samudragupta* 13 and n.

forest kingdoms, the eighteen, mentioned as part of the territory of the *Mahārāja* *Hastin* 13 n., 113, 116

- fortnights, lunar (see *Amānta*, *Pārnimānta*, days, lunar, and intercalary months); an instance of a lunar fortnight of only thirteen solar or civil days 89 n.
- Gaddhara, the god Vishṇu, as 'the bearer of the club or mace' 78 n.
- Gadhwa, a village in the Allahābād District; the inscription of Chandragupta II. of the (Gupta) year 88, . . . 36;—an inscription of Kumāragupta, 39;—the inscription of Kumāragupta of the year 98 . . . 40;—a fragmentary inscription, sps of the time of Kumāragupta, 264;—a miscellaneous inscription of the (Gupta) year 148 267
- Gallu, *Sāmadhvivrahika*, writer of the grant of Jayanātha the (Gupta or Kalachuri) year 177 124
- Gaṇapatiāga, a king in Northern India, conquered by Samudragupta 13
- Gaṇārya, a grantee 242
- gaṇa-srāshtha*, 'a leader of an assemblage' (?) 291 and n.
- Gandharva, a class of celestial beings; the musicians of heaven 84, 85
- Gaṇeśa Daivajña, an astronomical writer; his *Graha-Lāghava* was written A.D. 1520-21 146 n.
- Ganga, a grantee 123
- Gaṅgā, the river Ganges (see also Bhāgīrathī, Jāhnavī, and Mandākinī), 16, 56, 148, 156;—mentioned as flowing through the matted hair of the god Siva 16
- Gaṅgdhār, a village in the Jhāiāwād State, the inscription of Viśvavarmān of the (Mālava) year 480 72
- Garga, an ancient astronomer, quoted by Utpala for the heliacal-rising system of the Twelve-Year Cycle of Jupiter, 170;—and for a variation from the usually accepted grouping of the *nakṣatras*, 163 n.;—Utpala's quotation of his rule in the *Garga-Samhitā*, for one of the unequal-space systems of the *nakṣatras*, 164;—and of a verse by him, which seems to refer to the mean-sign system of the cycle 172
- Gargārā, the ancient name of the river on which the village of Gaṅgdhār stands 72 n., 77
- Garga-Samhitā*, an astronomical work by Garga; Utpala's quotation of its rule for one of the unequal-space systems of the *nakṣatras* 164
- garṭa*, or *garṭā*, 'a boundary-trench,' 97 and n., 124, 125;—*garṭa* as the termination of names of villages, in Kōrparagarta, 107;—and in Vālugarta 109
- Garuḍa (see also Garutmat), a supernatural being, half a man, half a bird, the vehicle of Vishṇu, and the enemy of the serpent race, 62 and n.;—mentioned as the ensign on the banner of Vishṇu, 90;—Garuḍa-tokens, *i.e.* coins or banners bearing representations of Garuḍa, were given by feudatories to Samudragupta, 14;—Garuḍa as an emblem on seals of grants 255, 292
- Garutmat, another name of Garuḍa 14 n., 298
- Gauḍa, a country, and an inhabitant of it 208
- Gaulmika*, an official title 52 and n.
- Gaupta*, 'of or belonging to the Guptas,' an adjective which may possibly be used in the date of the Mōrbi grant of Jainika; but it does not seem probable 21, 08, 58 n
- Gaurī, a name of the goddess Pārvatī 286
- Gauridatta, a proper name 293
- Gautamiputra, or Gautamīputra (Vākātaka); his wife was the daughter of Bhavanāga 237 n., 241, 248
- Gaya District, inscriptions from the 201, 221, 223, 226, 254, 274, 278, 281
- Gaya *vishaya*, an ancient territorial division in Bihār 257
- ghaṭī*, *ghaṭī*, *ghaṭikā*, 'the sixtieth division of a mean solar, or more properly civil, day and night,' equal to twenty-four English minutes 147
- Ghaṭōtkacha, *Mahārāja* (Early Gupta), 17, 16, 28, 44, 51, 54, 257;—the coins that bear the name of Kācha cannot belong to him, 27 n.;—he is not mentioned in the Tuśām inscription 270
- Ghāzīpur District, inscriptions from the 52, 249
- gold spoken of as 'the first offspring of fire' 195 and n., 200, 209
- Gōlmādhītāl, a village or hamlet near Khātānḍu in Nēpāl; notice of the inscription of Śivādēva I. of the (Gupta) year 316, . . . 177;—the value of this record in proving the use of the so-called Gupta era in Nēpāl, and in fixing the chronology of the early rulers of that country 96, 177, 184
- Gōmatikōttaka, a camp of Jīvitagupta II. 215, 217
- Gōmikasvāmin, a grantee 109
- Gōḍaśarman, a grantee 243
- Gōp, a village in Kāthiāwād, perhaps mentioned under the ancient name of Gōpta 98 n., 58 n.
- Gōpa, the ancient name of the hill on which stands the fortress at Gwālīor 162, 163
- Gōparāja, a chieftain, 93;—his posthumous pillar inscription of the (Gupta) year 191, . . . 91;—a note on the details of the date 77 n.
- Gōpasvāmin, a grantee, 97;—another of the same name 257
- Gōpasvāmin, or Dyūta-Gōpasvāmin, the *Akshapatalāśāhikrīta* under whose orders the surigious Gayā grant of Samudragupta purports to have been written 257

<i>gopathasara</i> , perhaps meaning 'a cattle-path'	195 and n.
Gōpta, apparently an ancient name of a village, and perhaps represented by the modern Gōp	98 and n., 58 n.
Gōrakhpur District, an inscription from the	65
Gōrisvāmin, a grantee	105
Gōsārman, a proper name	250
Gōśūrasindhābala, a proper name	280
<i>gōtra</i> , 'a family or clan' (see also Bharadvāja and Vishṇuvṛiddha); names of <i>gōtras</i> mentioned in this series of records:—	
Ātrēya	243
Aupamanyava	109
Bharadvāja	105, 115
Bhāradvāja	242, 243, 257, 298
Bhārgava	105
Gautama	243
Gōtama	271
Kāṇva	120
Kāśyapa	243
Kauṇḍinya	195, 199, 243
Kautsa	36, 97, 105
Maudgalya	248
Pārśasārya	242
Śāṅḍilya	243
Śārkarakshi	190
Śāśātanēya (?)	123
Śātyāyana	242, 243
Varshagana	71
Vāsula	105
Vatsa	170, 199
Vātsya	242, 243
Vishṇuvṛiddha	241, 248
Gōvardhana, or more fully Gōvardhanadhara, the god Kṛishṇa, as 'holding up the mountain Gōvardhana'	91
Gōvinda, the god Vishṇu	65
Gōvinda, the engraver of the Mandasor pillar inscriptions of Yaśōdharman, and of the Mandasor inscription of Yaśōdharman and Vishṇuvardhana of the Mālava year 589	148, 150, 158
Gōvinda III. (Rāshṭrakūṭa); examination of the date in his grant of the Śaka year 726, which proves that, up to A.D. 804, the <i>Pūrṇimānta</i> arrangement of the lunar fortnights was used with the Śaka years, even in Southern India, and also the mean-sign system of the Twelve-Year Cycle of Jupiter	79 n.
Gōvindasvāmin, a grantee	109
Gōyindā, a proper name	40
<i>Graha-Lāghava</i> , an astronomical work, written A.D. 1520-21, by Gaṇeśa Daivajña, from which, with the <i>Tiṅgi-Chintāmaṇi</i> , Hindu almanacs are now prepared in the Dekkan and some other parts	146 and n.
<i>Grāmika</i> , an official title	112 and n.

<i>grihapati</i> , 'a householder'	120 and n., 124
Guba, <i>Pratinarīkata</i> and <i>Amātya</i> , the writer of the Allnā grant of Śilāditya VII. of the (Gupta-Valabhi) year 447	190
Guhāsārman, a grantee	242
Guhāsena, <i>Mahārāja</i> (of Valabhi) 41, 168, 180	
Guhilasvāmin, a proper name	52
Guṇjākṛtti, <i>Bhōgika</i> , the writer of the grant of Jayanātha of the (Gupta or Kalachuri) year 174	120
Guṇthaka, a grantee	105
Gupta, <i>Mahārāja</i> (Early Gupta), 17, 15, 28, 44, 51, 54, 257, — indications that his name really was simply Gupta, and not Śrīgupta, 8 n.; — he is not to be identified with the <i>Mahārāja Śrīgupta</i> who is mentioned by I-tsing	8 n.
Gupta era, a convenient name for the era, commencing in A.D. 320, used by the Early Gupta kings and their successors; the nomenclature of the era, 19 to 23; — there is no ancient authority for connecting the name of the Guptas with the era, as the establishers of it, or for accepting the early existence of any such appellations for it as <i>Guptakāla</i> , <i>Gupta-samvat</i> , and <i>Gupta-sam</i> , 19, 22; — in the date of the Junāgaḍh inscription of Skandagupta, the mention of the Guptas only shews that the date was being recorded in an era new to that part of the country, 19, 20, 57 n.; — in the date of the Mōrbi grant of Jāiṅka, the adjective <i>Gaṇpta</i> , 'of or belonging to the Guptas,' may possibly exist, but it does not seem probable, 21, 98, 58 n.; — the reasons for which the era would come to be popularly known as the Gupta era, 19, 33 n., 125; — and as the Valabhi era, 33 n., 126; — instances of its being mentioned by the expressions <i>Valabhi-sam</i> and <i>Valabhi-samvat</i> , 84, 91; — it is convenient to speak of it as the Gupta era, the Valabhi era, and the Gupta-Valabhi era, 23; — Alberūnī's statements regarding the Gupta and other eras, 23, 24, 27; — he speaks of both the Gupta era and the Valabhi era, 25; — but he distinctly shews that he is referring to one and the same era under these two names, 31; — his illustration of the method of converting <i>Lōkākāla</i> dates into Śaka dates through the Gupta reckoning, 26 n.; — his statements do not really include the assertion of the existence of an era dating from the extinction of the Gupta sovereignty, 28; — this idea is due only to Prinsep's rendering of the date in the Kahāṭh pillar inscription of Skandagupta, and its endorsement by Reinaud in his translation of Alberūnī, 25, 26; — Alberūnī's words only shew that the Gupta era continued in use after the extinction of the	

Gupta sovereignty, 31;—a curious instance of confusion, by the Jain writer Śīlāchārya, between the Gupta and the Śaka eras, 32 n.;—the epochs of the Gupta era, based, by previous writers, on Reinaud's translation of *Alberŭnī*; *vis.* by Mr. Thomas, the Śaka epoch, A.D. 77-78; by Gen. Sir A. Cunningham, A.D. 166-67; by Sir E. Clive Bayley, A.D. 190-91; and by Mr. Fergusson, A.D. 318-19, . . . 31 to 33;—examination of these theories, 33 to 65;—remarks on the Mandasŕ inscription of the Mālava year 520, . . . 65 to 68;—it proves that any statement that the Early Gupta sovereignty was extinguished in or about A.D. 319, is wrong; and that the era used by the Early Gupta kings runs from an epoch in or very close to that year, 68;—the determination of the exact epoch of the era, with the result of A.D. 319-20, equivalent to Śaka-Samvat 241 expired, 69;—the scheme of the years of the era, 69, 71;—it included the *Pāruṣimānī* arrangement of the lunar fortnights, 77, 85;—proof that the Gupta year did not commence with the months Kārttika or Mārgaśīrṣa, 86, 87, 90, 108, 111, 115, 118;—the treatment of it as a northern Śaka year, gives satisfactory results for every recorded date, except two which are capable of explanation, 84, 90, 97, 99, 104 n.;—and it is almost certain that it soon became identical in all respects with the northern Śaka year, having Chaitra śukla 1 as its initial day, 79;—the calculation of recorded dates, the results of which answer to the above conditions, 80, 84, 95, 97, 104, 110, 114, 117, 119;—the *Ēraṅ* pillar inscription of Budhagupta of the (Gupta) year 165, proves that the running difference between current Gupta-Valabhi and current Śaka years is two hundred and forty-two years; and that, in following *Alberŭnī* and adding two hundred and forty-one, what we obtain is the last Śaka year expired before the commencement of the current Śaka year corresponding to a given current Gupta-Valabhi year, 84;—the *Verāwal* inscription of Arjunadēva of the Valabhi year 945, proves that the original *Pāruṣimānī* arrangement was preserved with the Gupta year, in *Kāthīwādī*, up to A.D. 1264, . . . 90;—the two exceptional dates are those in the *Verāwal* inscription of the Valabhi year 927, and in the Kaira grant of Dharaṣena IV. of the (Gupta-Valabhi) year 330, the results for which answer to a year commencing with the month Kārttika preceding the true commencement of the Gupta year, 90, 93;—the explana-

tion of this difference, 78, 73, 92, 93, 95;—proof as to the epoch afforded by the use of the Twelve-Year Cycle of Jupiter in records of the Early Gupta period, 101 to 124;—summary of the results, which prove A.D. 319-20 as the epoch of the era and A.D. 320-21 as its first current year, 124 to 127;—proof that the years in Gupta-Valabhi dates are to be interpreted as current years, unless the contrary is distinctly specified, 127 to 130;—inquiry as to the origin of the era, 130 to 137;—its epoch, or its commencement, was not determined by the expiration, from the epoch or the commencement of the Śaka era, of an even number of Cycles of Jupiter, either of the Twelve-Year or of the Sixty-Year system, or by any other astronomical considerations, 33, 130;—but its origin must be found in some historical event, which occurred actually in A.D. 320, . . . 130;—it was not established by any member of the Valabhi family, 130;—nor by the *Mahārāja* Gupta, the founder of the Early Gupta family, 130;—it cannot run from the accession of Chandragupta I., the first paramount sovereign in the family, 131, 132;—it was adopted by the Early Guptas from some extraneous source, 132;—the reasons for which they would not adopt any era then in use in India itself, 132 to 134;—the so-called Gupta era was in use, outside India, in Nēpal, by the Lichchhavi rulers of that country, 95, 96, 134, 184;—further instances of this, 178, 182, 183, 184;—the antiquity and power of the Lichchhavis, and the friendly relations, including intermarriage, between them and the Early Guptas, would dispose the latter to adopt any Lichchhavi era, 135;—and in all probability the so-called Gupta era is a Lichchhavi era, dating either from the general establishment of monarchy among the Lichchhavis, or from the commencement of the reign of the Lichchhavi king Jayadēva I. in Nēpal 136

Gupta-Adia, an expression used by *Alberŭnī* for the Gupta era; it is a perfectly justifiable term, but there is no authority for the early existence of it 19, 22, 24, 25, 30

Gupta-nripa-rājya-bhuktan, a technical expression in the grants of the *Parivrajaka Mahārājas*, shewing that at certain dates the Gupta sovereignty was still continuing 42, 43, 50, 101, 104, 110, 114, 117, 95 and n., 96, 104, 108, 115

Gupta-Valabhi era; a convenient name for the Gupta era during the period when, through its use by the Kings of Valabhi, it may have begun to be called the Valabhi era 83

Guptas, the Early, 7 n.;— the actual dates of their records extend from A.D. 401 to 466, . . . 7;— but the records of the Parivrajaka *Mahārājas* prove that the Gupta dominion continued to A.D. 528, . . . 8;— their final overthrow was accomplished by Mihirakula, 10;— their genealogical tree, 17;— there is nothing to support the supposition that they belonged to the Solar Race, 19, 1;— their family mentioned as the *Guptavatsā*, 20, 55, 67;— and as the *Guptāvaya*, 259;— mention of them in the plural, as a family or dynasty, 19, 20, 63, 65, 67;— mention of them as the Gupta kings, 104, 110, 114, 117, 96, 104, 108, 115;— mention of them, in the Junāgadh rock inscription, in connection with the reckoning of an era, 19, 20, 21, 22, 57 n., 63, 65;— but there is no ancient authority for connecting their name with the Gupta era, as the establishers of it, 19;— remarks on some of their coins for the legends on their silver coins, see *Ind. Ant.* XIV. 65), 36 n., 12 na., 14 na., 15 n., 25 n., 27 n., 28 na., 46 n.;— allusions to a temporary obscuration of their power between the reigns of Kumāragupta and Skandagupta, 55;— a further indication of this is perhaps given by Kumāragupta having only the title of *Mahārāja* in the Mankuār inscription, 46;— mention of them in Yasōdharman's pillar inscription, 146, 148

Guptas of Magadha, 7 n., 14, 205, 206, 207, 208, 210, 212, 213 n., 217;— the family was an offshoot of the Early Gupta stock; and the founder of it, Krishna-gupta, came very shortly after Skandagupta, 14;— intermarriages of this family, with the Maukharis, 24, 187;— with the Kings of Kanauj, or more properly of Thāpēsar, 15, 232;— and more of the Vākātaka *Mahārājas* . . . 15, 240, 247

Guptasya kālā, 'the time or era of Gupta,' an expression supposed, but quite wrongly, to exist in the Junāgadh rock inscription of Skandagupta, 19, 44, 57 n.;— and in abbreviated forms on certain Kābul coins . . . 19, 57 to 60

Gwāllior (Gwālher), the capital of Scindia's Dominions; the hill on which the fortress stands, mentioned under the ancient Sanskrit name of Gōpa, 162 and n., 163;— the modern name of Gwālher is derived directly from Gōpālikhēra, 162 n.;— the inscription of Mihirakula . . . 161

Haidarābd in the Dekkan; examination of the date of the grant, of the Śaka year 534 expired, of Pulikēsin II.,

which proves that up to A.D. 612, the *Pārimānā* arrangement of the lunar fortnights was used with the Śaka years, even in Southern India . . . 79 n.

HĀĀrt year; a year with Āshādha fulla 1 as its initial day, used in the western part of Kāthiāwād . . . 79 n.

halisrakara, a fiscal term requiring explanation . . . 134 n.

Hall, Dr. F. E.; views expressed by him on the Gupta era and connected matters . . . 42

Hāmsamitra, a grantee . . . 218

Hanumat, the chief of the monkeys, mentioned as 'the son of the Wind,' and with a reference to his leap through the air from the mountain Kōśavardhana . . . 205

Hara, the god Śiva, as 'the seizer or despoiler' . . . 87, 206, 208

Haradatta, a grantee . . . 298

Hari, the god Vishṇu . . . 156

Haribala, a proper name . . . 372

Haribhāṣa, a proper name . . . 78

Harigupta, a proper name . . . 281

Hariśarmārya, a grantee . . . 243

Harishēṣa, *Sāmahivagrāhika*, *Kumārā-mātya*, and *Mahādāndānyaka*, the composer of the Allāhābd posthumous pillar inscription of Samudragupta . . . 16

Hariśvāminī, a proper name . . . 262

Haritrāta, a proper name . . . 71

Harivarman, *Mahārāja* (Maukharī), 221;— his wife was Jayasvāminī . . . 221

Harivishṇu, a proper name . . . 90, 160

Harsha, also called Vikramāditya, a king of Ujjain, mentioned in the *Rājataranginī*, allotted by Mr. Fergusson to the sixth century A.D., and held by him to be the real person in commemoration of whom the Vikrama era was invented and named . . . 47, 55, 56

Harsha of Gauḍa, Kalinga, Kōśala, Ōjra, &c.; in a Nēpāl inscription, he is mentioned as belonging to the Bhagadatta family, 187;— his daughter, Rājyamati, was the wife of Jayadēva II of Nēpāl . . . 187

Harsha, or Harshavardhana, of Kanauj, or more properly of Thāpēsar, 15, 232;— mentioned under the name of Harshadēva, 207;— his name was simply Harsha or Harshavardhana, and not Śrīharsha or Śrīharshavardhana, 207 n.;— Hiuen Tsiang gives him the *biruda* or second name of Śrīāditya, 39, 40;— his accession, as determined by the commencement of the Harsha era, is to be placed in A.D. 606, . . . 178 n.;— his Sōnpat seal . . . 231

Harsha era; an early era of this name, commencing in or about B.C. 457, is mentioned by Aliberūnī, 23, 24, 30;— but there is no other evidence of its existence, 23 n.;— the only proved era of this name, is that which runs from

- the accession of Harshavardhana of Kanauj, or more properly of Thāṇṣar, 23 n.; — as far as it can be determined by means of the Dighwā-Dubaulf grant of the *Mahārāja* Mahēndrapāla, this era commenced in A.D. 606, with the epoch of A.D. 605-606, . . . 178 n.; — an instance of the use of this era in India, 210; — another possible instance, 287; — it was adopted in Nēpāl, by the Thākurf rulers of that country, 96, 184, 289; — instances of the use of it by them, 178 to 184; — the fact of its introduction there is mentioned, in a mistaken manner, in the Nēpāl *Vamśavali* 185
- Harshadēva, a variant of the name of Harshavardhana of Kanauj, or more properly of Thāṇṣar . . . 207 and n.
- Harshagupta (Gupta of Magadha), 205; — Harshaguptā, wife of Adityavarman, was probably his sister . . . 24
- Harshaguptā, wife of Adityavarman, 221; — she was probably a sister of Harshagupta of Magadha . . . 24
- Harshavardhana (see also Harsha or Harshavardhana) of Kanauj, or more properly of Thāṇṣar . . . 15, 232
- Hastin, *Mahārāja* (Parivrājaka), 97, 104, 109, 111, 115; — he had the hereditary kingdom of Dabhāla, and the eighteen forest kingdoms, 13 n., 116; — his Khōh grant of the Gupta year 156, . . . 93; — his Khōh grant of the year 163, . . . 100; — there is no necessity to alter the date of this record from 163 to 173; and, in fact, the alteration is not justifiable, 110 to 114, 102 n.; — his Majh-gawāh grant of the year 191, . . . 106; — his Bhumarā pillar inscription, 110; — examination of the dates of these records . . . 104, 110, 114, 119
- Hastivarman of Veṅgt, a king in Southern India, conquered by Samudragupta 13
- Hembaṭa, a proper name . . . 190
- Hijra era, a Musalmān era, commencing in A.D. 622, and dating from the flight of the prophet Muhammad; an instance of this era being quoted in a Hindu epigraphical record . . . 85
- Himālaya (see also Himavat), the mountain; mentioned as the father of the goddess Pārvaī, 147; — as the mountain of snow, 148, 205, 230; — as the king of mountains . . . 169, 181
- Himavat, a name of Himālaya . . . 156
- Hissār or Hissār District, an inscription from the . . . 269
- Hoernle, Dr. A. F. R.; view expressed by him on the Gupta era . . . 65
- Hōpa, a tribe; a mention of them in Yādū-dharman's pillar inscription, 146, 148; — mentioned as defeated by Skandagupta, 56; — and by the Maukharis 206
- Ijjādēvi, wife of Vishvuguptadēva . . . 217
- Ilichpur District, an inscription from the images, inscriptions on the pedestals of 45, 208, 262, 266, 271, 272, 273, 278, 280, 281
- Indiana, a proper name . . . 118
- India, Northern; mentioned under the name of Aryāvarta, 13 and n.; — Southern India mentioned under the name of *dakṣiṇāpatha* . . . 13 and n.
- Indōr, a deserted village or mound in the Bulandshahar District, mentioned under the ancient name of Indrapura or Indrāpura, 71, — the grant of Skandagupta, of the (Gupta) year 146 . . . 68
- Indra, the god of the sky (see also Maghavan, Purāmdara, and Śakra; and, for his wife, see Sachi), 14, 28, 44, 50, 51, 54, 93, 195, 199, 257, 278; — mentioned as 'the lord of the gods,' 10, 62, 76, 77, 195; — as the elder brother of Vishnu, 50, 182 n.; — as 'the thousand-eyed,' 225; — mention of the mountain Sumēru as his abode, 278; — mention of the *kalpa*-tree in his paradise, 168, 228; — a reference to his elephant, Airāvata, 76; — deceased kings are described as going to the abode of Indra, conquering the realms of Indra, or obtaining a seat on the lap of Indra, 10 and n.; — and grants were made to secure this result . . . 195, 199
- Indrabala, of the Pāṇḍuvainās, 298; — his father was Udayana, of the Śavara lineage or tribe . . . 293
- Indrapura, Indrāpura, the ancient name of Indōr in the Bulandshahar District . . . 68, 71
- Indravishṇu, a proper name . . . 90, 160
- inscriptions on copper are usually denoted by the terms *śāsana*, 99 n., 194, 199, 218, 240, 242, 247, 249, 296; — and *śāstra-śāsana*, 99 n., 109, 116, 128, 132, 138, 195, 199; — and those on stone, by the term *prāsasti*, 87 n.; — an exceptional instance in which the term *prāsasti* is used to denote a copper-plate charter . . . 87 n
- intercalary months; the present arrangement of the intercalated fortnights in Northern and in Southern India, 88; — a verse attributed to the *Brahma-Siddhānta* indicates a more ancient arrangement of a different kind, 88 n.; — intercalated months are inauspicious, and the performance of ceremonies in them is prohibited, 88 n.; — but the Kaira grant of Dharasēna IV., of the (Gupta-Vaiṣṇv) year 330, shows an exception to this rule, 94; — note on a mistake which runs all through Cowasjee Patell's

<i>Chronology</i> , Table I., in respect of the intercalations for the southern Vikrama years, 87 n.;—instances of intercalation of the month Mārgaśīraha, which is usually held to be not liable to tercalation, 93;—and of the month Paśya, though the same rule is held to apply	179	Jayabhaṭṭa, a proper name	274
Īśa, the god Śiva as 'the lord, the powerful one'	87	Jayadēva I., the first historical person in the family of the Licchavis of Nēpāl, 125, 126, 129, 191;—calculating back from the recorded date for Mānadēva, his initial date is about A.D. 330, . . . 191;—and this needs but little adjustment to place him in A.D. 320, and to make the so-called Gupta era run from the commencement of his reign	135
Īśgaḥ District, inscriptions from the 21, 34, 258	258	Jayadēva II., <i>Rājya</i> (Thākurl of Nēpāl), 123, 124, 127 to 191;—he had the <i>biruda</i> or second name of Parachakra-kāma, 124, 127;—his wife was Rājya-matī, 127;—notice of an inscription of the (Harsha) year 145, which is probably one of his records, 123;—and of his inscription of the year 153 . . . 123, 125 to 128	128
Īśānavarman (Maukhāri), 24, 206, 220, 221;—his wife was Lakshmiṃvatī, 221;—he was conquered by Kumāragupta of Magadha	206	Jayadēva, <i>Rājaputra</i> , the <i>Dātaka</i> of the inscription of Śivadēva II. of the (Harsha) year 119	122
Īśvara, the god Śiva, as 'the lord, the powerful one'	120	Jayanātha, <i>Mahārāja</i> (of Uchchakalpa), 119, 123, 128, 131, 138;—his wife was Murugadēvi or Murugdasvāminī, 128, 132, 138;—his <i>Kīrtitāl</i> grant of the (Gupta or Kalachuri) year 174, . 117;—his Khōh grant of the year 177	121
Īśvarādāsa, the writer of the grant of Saṅkshobha of the (Gupta) year 209	116	Jayarāja, or Mahā-Jayarāja, <i>Rājya</i> (of Sarabhapura), 194;—his Arang grant <i>jaya-shandhadra</i> , 'a victorious camp'	191
Īśvarasārman, a grantee	243	Jayasvāmin, <i>Mahārāja</i> (of Uchchakalpa), 119, 123, 128, 131, 138;—his wife was Rāmadēvi	119, 123, 128, 131, 138
Īśvarasarmāya, a grantee	243	Jayasvāminī, wife of Harivarman (Maukhari)	221
Īśvaravarman, <i>Mahārāja</i> (Maukhari), 221, 229, 230;—his wife was Upaguptā, 221;—his Jaunpur inscription	228	Jayasvāminī, wife of Kumāradēva of Uchchakalpa	119, 123, 128, 131, 138
Īśvaravāsaka, an ancient village or allotment granted to the great Śīśpa at Sāñchi	33	Jayavarman, a proper name	122
Jabalpur District, an inscription from the	117	Jayésvara, a <i>linga</i> form of the god Śiva	122
Jāhnavī, the river Gaṅgā, as 'the daughter of Jahnu'	159, 181	Jhālāwād State, an inscription from the	72
Jāikadēva, a king of Saurāshtra, not to be identified, if his Dhiniki grant is genuine, with the Jāitka of the Mōrbi grant, 61, 62;—examination of the date in his grant, purporting to be in the Vikrama year 794, with the result that this grant must be held to be spurious	62 n.	Jina, a class of deified Jain saints	239
Jain inscriptions	65, 258	Jishnugupta (Thākurl of Nēpāl), 120, 121, 129, 190, 191;—notice of his inscription of the (Harsha) year 48, . . . 120;—and of two others, the dates of which are lost	121
Jain sect or religion; proof of its existence in the fourth century A.D. is furnished by the Kāhāuh pillar inscription of Skandagupta	16, 66	<i>jitam bhagavatā</i> , 'victory has been achieved by the Divine One;—an invocation used at the commencement of inscriptions, 25 n., 40, 41;— <i>jitam Vishvund</i>	270
Jāitka, a chieftain in Kāthiāwad; remarks on the reading and interpretation of the date of his Mōrbi grant of the (Gupta) year 585 expired, 21, 98, 58 n.;—examination of the details of the date, 97;—he is not to be identified with the Jāikadēva of the Dhiniki grant, if the latter is a genuine record	62	Jivanta, a proper name	71
Jāmbavati, wife of the god Vishṇu in his incarnation as Kṛishṇa	270	Jivita, a proper name	116
Janārdana, the god Vishṇu, as 'exciting or agitating men'	90, 129	Jvitagupta I. (Gupta of Magadha)	405
janēndra, 'a lord of a people or tribe, contrasted with <i>narddhīpati</i> , 'a chief ruler of men'	151 n.	Jvitagupta II., Jvitaguptadēva (Gupta of Magadha), 217;—his Dāśa-Baranārk inscription	213
Jaś State, an inscription from the	233	Julien, M. Stanislas; certain points, in his translation of the <i>Life and Travels of Hiuen Tsiang</i> , which may be made more clear through the Early Gupta chronology	39
Jaunpur, the chief town of the Jaunpur District; the inscription of Īśvaravarman	228		

- Junāgadh rock inscription of Skandagupta, of the Gupta years 136, 137, 138, 56
- Junāgadh State, inscriptions from the . 56, 164
- Jupiter, the planet; its regent mentioned under the names of Āngiras, 170;—the son of Āngiras, 170;—Bṛihaspati, 'the lord of prayer,' 170, 76, 86, 157;—Guru, 'the preceptor,' 169, 170, 171 and n., — Ijya, 'the teacher,' 170;—Ijva, 'the living being,' 170;—Suraguru, 'the preceptor of the gods,' 81, 90, 157;—Surjya, 'the teacher of the gods,' 173;—the counsellor of (Indra) the lord of the gods (*dhvapatimantrin*), 161;—the counsellor of the gods (*sura-mantrin*), 161 n.;—and the preceptor of the gods (*sura-guru* and *tridāsa-guru*) 157, 169 181
- Jupiter, the planet; exposition of the Twelve-Year Cycle based on his heliacal risings, with reference to his apparent longitude, in particular *nakshatras*, Appendix III., 161 to 176;—the authorities for this system of the cycle, with the rule for naming the years of it, according to the order of the lunar months, commencing with Kārttika, 161 and n., 170, 171;—the length of each year of the cycle, by this system, is roughly 400 days, 162;—a practical illustration of two cycles of this system, 167;—the years of this cycle that are liable to be omitted, and to be repeated, 168;—this is evidently the original system of the Twelve-Year Cycle, 172;—instances of the later and modern use of it, 173 and n., 175;—the heliacal risings of Jupiter are still noted in *Pañchāṅgs*, for religious purposes, 173 n.;—there are indications that the Sixty-Year Cycle also was originally regulated by the same system, 170 and n., 173, 174;—the years of the Twelve-Year Cycle, by this system, mentioned in records of the Early Gupta period, are, Mahā-Āśvayuja, 110, 117, 104, 115;—Mahā-Chaitra, 114, 108;—Mahā-Māgha, 119, 112;—and Mahā-Vaiśākha, 104, 96;—examination of the dates of these records, 101, 104, 110, 114, 117, 119;—the Pausa and Vaiśākha years of a Twelve-Year Cycle are mentioned in early Kadamba records (the absence of the prefix *māhā* possibly indicates that they are of the mean-sign system), 106 n.;—the proof that the epoch of the Gupta era was not determined by the Twelve-Year Cycle according to the heliacal-rising system 34, 35
- Jupiter, the planet; incidental remarks on the Twelve-Year Cycle based on his passage, with reference to his mean longitude, among the signs of the zodiac, 162, 169, 170;—the rule, as given by the first Aryabhata and by Brahmagupta, for determining the years of this cycle by this system, 169;—the years commence with the years of the Sixty-Year Cycle by the same system; and the length of each year, according to the *Sārya-Siddhānta*, is 361 days, 1 *ghaṭī*, 36 *palas*, 170;—(instances of the use of the cycle, by this system, indicated by the absence of the prefix *māhā*, are possibly to be found in early Kadamba records, 106 n.);—the proof that this is not the system of the cycle used in records of the Early Gupta period, 103, 108, 111, 115, 118, 121;—and that the epoch of the Gupta era was not determined by it 34, 35
- Jupiter, the planet; incidental remarks on the Sixty-Year Cycle based on his passage, with reference to his mean longitude, among the signs of the zodiac, 102, 169, 170;—the rule of the *Sārya-Siddhānta* for determining the years of this cycle by this system, 170;—the length of each year of this cycle, by this system, according to the same authority, is 361 days, 1 *ghaṭī*, 36 *palas*, 170;—a verse by Kaśyapa seems to indicate that the years of this cycle also were originally determined by the heliacal-rising system, 170 and n.;—Varāhamihira gives the rule that Prabhava, the first year of this cycle, commences when Jupiter comes to Dhanishṭhā and rises in Māgha, 173, 174;—comments on this rule, which is not correct for the mean-sign system, but is nearly so for the heliacal-rising system, 173 n., 174;—the Sixty-Year Cycle by the mean-sign system, was current in Southern, as well as in Northern, India, at least up to A.D. 804. 80 n.;—the proof that the epoch of the Gupta era was not determined by this cycle 34
- Jupiter, the planet; the use of the Sixty-Year Cycle, according to the southern luni-solar system, seems to have been introduced between A.D. 804 and 866. 80 n.;—and the epoch of the Gupta era cannot have been determined by this cycle 33, 34
- Jyēshthāśarmārya, a grantee 243
- Jyēshthādarpana*, an astrological work; its date is A.D. 1557-58. 175;—a quotation from it in support of the heliacal-rising system of the Twelve-Year Cycle of Jupiter 170
- ka*, an affix from which certain modern declensional suffixes are derived 69, 113, 117, 121, 125, 126, 130, 135, 197, 261
- Kābul, the Hindu kings of, remarks on some of their coins, which have been supposed to bear dates in the Gupta era 57 to 60

- Kācha, the name of two chieftains mentioned in an inscription in the Ajayā caves, 27 n.;—the name also occurs on certain gold coins which have always been attributed to Ghatōt-kacha, but, if they are Early Gupta coins, as seems probable, they must be attributed to Samudragupta. 4
Kācha must be his *birada* or second name 18, 27 n.
- Kācharapallika, an ancient village in the Mañināga *pēṭha* 138
- Kahāum, a village in the Gōrākhpur District; mentioned under the ancient name of Kakubha or Kakubhagrāma, 66, 67;—the pillar inscription of Skandagupta 65
- Kailāsa, a mountain in the Himālaya range, 78, 85, 86;—mentioned as one of the breasts of the earth 86 and n.
- Kailāsakōtābhavana, the palace of the Thākuri rulers of Nēpāl . 178 to 182, 189, 190
- Kaira (Khēdā), the chief town of the Kaira District; mentioned under the ancient name of Khētaka, 95 n., 173, 189;—examination of the date in the grant of Dharaśēna IV. of the (Gupta-Valabhī) year 330 93
- Kaira District, an inscription from the 171
- Kāka, a tribe, conquered by Samudragupta 14
- Kākanāda, the ancient name of Sāñchi in the Aśoka period 31
- Kākanādbōta, the name of the great *Śrēṣṭha* at Sāñchi in the Gupta period 31, 32, 262
- Kakka, a proper name 148, 150
- Kakubha, Kakubhagrāma, the ancient Sanskrit name of Kahāum 66, 67
- Kāla*, 'time, a space of time,' may be used in the sense of 'an era,' and is so used in respect of the Vikrama and Śāka eras, but there is no ancient authority for the early existence of the term *Gupta-Kāla* for the Gupta era 19, 22
- Kalachuri, a dynasty of kings in Central India; their dynastic name occurs under the Sanskritised form of Kalatāsuri, in a record of the sixth century A.D., and they are perhaps mentioned, under the name of the Aṅjunāyanas, in the Allahābād pillar inscription 10
- Kalachuri or Chēdi era, an era used by the Kalachuri kings of Central India; early instances of the use of it are perhaps to be found in the records of the *Mahārājās* of Uchchākalpa, which, however, would seem to require for the era an epoch about twenty-five years later than the epoch of A.D. 249-50 proposed by Gen. Sir A. Cunningham, 8, 9, 10;—also in the grants of the Traikūtaka *Mahārājās*, 9 n.;—(and possibly in the Bōdh-Gayā inscription of Mahānāman, the date of which has been referred in this volume to the Gupta era, 16, 275);—Prof. Kielhorn quoted as having fixed the commencement of the era in A.D. 249, with the epoch of A.D. 248-49 10
- Kali age (see also Kaliyuga era), the last and worst of the four Yugas or ages of the world; the one in which we now are 156, 168, 182
- Kālindī, the river Yamuna (Jamnā) 90
- Kaliyuga era, an era commencing, with the beginning of the Kali age, in B.C. 3102, though usually represented as commencing in B.C. 3101; it is of but rare use in epigraphical records, 69 n.;—quotations of the reckoning of this era, both by current and by expired years, from Hindu almanacs, 138 to 141;—its duration is 432,000 years of men; and we are still only in the *samāhāra* of it, 138 to 141, 139 n.;—it was the original astronomical era of the Hindus, and the substitution of the Śāka era for it, for astronomical purposes, seems to have taken place between A.D. 476 and 587 143
- Kalpa*-tree, a fabulous tree in Indra's paradise, granting all desires 168, 228
- Kāmadēva, the god of love (see also Smara); a mention of his two wives, Priti and Rati, 85;—a reference to his bow of flowers, 86;—a reference to his destruction by Śiva, 87;—an enumeration of the five flowers that form his arrows, 87;—mentioned as having a banner of flowers 58
- Kamaladēvi, wife of Dēvaguptadēva of Magadha 317
- Kāmarūpa, a country, the modern Assam, or its western portion, Samudragupta either included it in his empire, or else extended his conquests up to the confines of it 9 n., 14 and n.
- Kanauj, a town in the Farrukhābād District; perhaps mentioned, in connection with Samudragupta, under the ancient name of Pushpapura 5, 12
- Kanauj, Harshavardhana of, or more properly of Thānēsar, his genealogy 232
- Kāñchi, a town in Southern India, the modern 'Conjeeveram,' in the time of Samudragupta, its king was Vishṅugōpa 13
- Kāñḍārya, a grantee 243
- Kāngra District, an inscription from the Kanva or Kanvāyana, a tribe, family, or dynasty; there is no foundation for the supposition that the Kanva prince Nārāyana, mentioned in the *Vishṅu-Purāna*, is mentioned as the Tushāra king Vishnu, in the Tushāra rock inscription 270
- Kapālēsvara, the god Śiva, as 'the lord who is decorated with a garland of skulls' 290
- Kapila, an ancient sage 113

- harāṇa*, 'a document' 242 and n.
- Karañjavaraka, or perhaps Karañjachiraka, an ancient river in the Beppākārpara *śāḍga* 248
- Kārttalā, a village in the Jabalpur District; the grant of Jayanātha of the (Gupta or Kalachuri) year 174 117
- kartri*, 'a maker,' a technical term for the composer of a record, as opposed to the person who reduces it to writing 88, 99 n.
- Kartripura, a town, in the east or north-east; Samudragupta either included it in his empire, or else extended his conquests up to the confines of it 9 n., 14 and n.
- Kārttikēya, the god of war (see also Brahmanya, Skanda, and Svāmi-Mahāśana), 286;—mentioned as the son of Hara and riding on a peacock, 206;—and as having the banner of a peacock, 185;—an ancient temple of this god at Bilsāḍ 43
- Kāśī, one of the ancient names of the modern Benares; apparently mentioned as the capital of Prakaśāditya 285, 286
- Kasiā or Kasyā, a village in the Gōrakhpur District; the inscription on the *nirvāna*-statue of Buddha 272
- Kāsmīr: the early history of this country, as deduced from the *Rājatarāṅginī*, is to be adjusted by the now settled date of Mihirakula 56
- Kāśyapa, the preceptor of the god Indra Kāśyapa, an ancient astronomer, quoted by Utpala for the heliacal-rising system of the Twelve Year Cycle of Jupiter, 170;—his rule indicates that originally the years of the Sixty-Year Cycle also were determined by the heliacal risings of the planet 170 n.
- Kāthiāwāḍ, inscriptions from 56, 164
- Kāthiāwāḍ province, mentioned under the name of Surāshirāḥ, 62, 63;—a tradition of the bards of Kāthiāwāḍ, supposed to have an important bearing on the question of the Gupta era, 49;—but it is of quite recent origin, and of no value whatever, 50;—in the western part of this province, there is used a year, called the Hālarī year, of which the initial day is Aśāḍha sukla 7 n.
- Kātyāyanī, a name of the goddess Pārvatī 228
- kaubhārachchanda*, a particular kind of pearl-necklace 45
- Kaudravādya, a grantee 105
- kaustubha*, a jewel worn on the breast by Viṣṇu 87
- Kay, Mr. H. C.; his proposal for amending the translation of Alberdun's words regarding the origin of the Gupta era 28
- kāndra* (see also *utkōchcha-māna*, *tīthi-kāndra*, *tīthi-mādhyama-kāndra*, and *tīthi-spāṣṭa-kāndra*), or 'anomaly,' of the moon, is taken to be her distance from apogee, from which point it is always reckoned by Hindu astronomers, 149 and n.;—the annual variation in the moon's *kāndra* is 3 signs, 2 degrees, 6 2 minutes, or 7 *tīthi*s, 9 *ghaṭi*s, 42 *palas* 149
- Kēraja, a country in Southern India; in the time of Samudragupta, its king was Mañṭarāja 7 n., 13
- Kēśava, one of the composers of the Gwālīor inscription of Mihirakula 163
- 'Khadavayaka,' a Hindu king of Kābul; remarks on some of his coins, which have been supposed to bear dates in the Gupta era 57 to 60
- Khādyatāpākika, a tribal or family name, or an official title, applied to the *Mahādāyandāyaka* Harishēya 16
- Kharagraha I. (of Valabhi) 41, 181, 182 n., 183
- Kharagraha II. (of Valabhi) 41, 184;—he had the *biruda* or second name of Dharmāditya 184
- Kharaparika, a tribe, 'conquered by Samudragupta 14
- Khātmandu, the capital of Nēpāl; notices of inscriptions from its vicinity . 177 to 188
- Khētaka, an ancient form of the name of Kaira (Khēḍā); mentioned as the chief town of an *āndra* 173, 189
- Khōh, a village in the Nāgaudh State; the grant of Hastin, of the (Gupta) year 156, . . 93;—of Hastin, of the (Gupta) year 163, . . 100; there is no necessity to alter the date of this record from 163 to 173; and, in fact, the alteration is not justifiable, 110 to 114, 102 n.;—of Samkshōbha, of the (Gupta) year 209, . . 112, —an alteration in the reading of the date of this record, 76 n., 274 n.;—its importance in proving the *Pārnimānta* arrangement of the fortnights in the Gupta year, 76;—examination of the dates of these records, 104, 110, 117;—the grant of Jayanātha, of the (Gupta or Kalachuri) year 177, . . 121;—of Śarvanātha, of the (Gupta or Kalachuri) year 193, . . 125;—of Śarvanātha, without date, 129;—of Śarvanātha, of the (Gupta or Kalachuri) year 197, . . 132;—and of Śarvanātha, of the (Gupta or Kalachuri) year 214 135
- Kielhorn, Prof. F.; quoted as having fixed the commencement of the Kalachuri or Chēdi era in A. D. 249, with the epoch of A. D. 248-249 10
- Kipihikhētaka, an ancient village in the Beppākārpara *śāḍga* 248
- Kinnara, a class of supernatural beings 84
- kīrti*, used, like *kīrtana*, in the special meaning of 'any work which renders the constructor of it famous' 212 and n., 213 n.
- Kisōbrāvātaka, an ancient village in Bihār, near Dēō-Barapārk 218

Kṛpita, a fiscal term, requiring explanation 242, 249

Kollapūraka, an ancient village in the Benṣākārapara *bhūga* 248

Kōṣadēvi, wife of Adityasēna of Magadha, 208, 212, 217, — mentioned with the paramount titles, 212; — called Kōshadēvi in a late inscription 213 n.

Koṣṭarāja, a proper name 241

torata, a fiscal term, requiring explanation 248 and n.

Kōparagartā, an ancient village, or a boundary-trench, in Baghēlkhāṇḍ 105

Kōparika, an ancient *agrāhāra*, in Baghēlkhāṇḍ 104

Kōsala, a country in Southern India; in the time of Samudragupta, its king was Mahēndra, 13, — Tivaradēva had the title of 'supreme lord of Kōsala,' with reference to the more northern country of the same name 296

Kōsam, a village in the Allahābād District, the modern representative of the ancient Kauśāmbī: the Allahābād column, containing the Aśoka inscriptions and the posthumous pillar inscription of Samudragupta, may possibly have stood originally at this place, 2; — the image inscription of Bhlmarman of the (Gupta) year 139 266

Kōsavardhana, a mountain from which the monkey-king Hanumat took a leap through the air 205 and n.

Kōshadēvi, used by mistake, in a late inscription, for Kōṣadēvi 213 n., 214 n.

Kōta, a family, tribe, or dynasty, conquered by Samudragupta, and perhaps holding the city of Pushpapura at that time 6, 12

Kottūra on the hill, a town in Southern India; in the time of Samudragupta, its king was Svāmīdatta 7 n., 13

Kramāditya, a *biruda* or second name of Skandagupta 18

Kṛishṇa, the god Viṣṇu incarnate as the son of Vasudēva and Dēvaki, 55, 223, — mentioned under the name of Vāsudēva, 286; — mention of his wife Jāmbavatī, 270; — an image of Kṛishṇa was set up in the Barābar Hill cave by Anantavarman 223

Kṛishṇagupta (Gupta of Magadha), 205; — he came very shortly after Skandagupta 14

kṛita, 'accomplished,' i. e. 'completed,' (years) 73 n., 254

Kṛita age, the first of the four Yugas or ages of the world, characterised by truth and virtue; 'the golden age' 45, 181, 240, 248

Kṛitānta, the god Yama, as 'the one by whom death is accomplished' 28, 44, 51, 54, 157, 257

Kṛitānta-parasū, an epithet of Samudragupta, 28, 44, 51, 54, 257; — it occurs also on his coins 28 n.

Kshatrapas or Mahākshatrapas of Saurāshtra; the family or dynastic name of 'Sah' or 'Sāh' which has been allotted to them, is only based on the custom of omitting superscript vowels in the legends on their coins 36 n.

Kubēra, the god of wealth, mentioned under the names of Dhanada, 14, 21, 28, 44, 51, 54, 257, — and Dhanēsa 169, 181

Kubēra of Dēvarāshtra, a king in Southern India, conquered by Samudragupta 13

kul-ākhyā, 'a family appellation' 36

kulaputra, 'high-born' 190, 241, 248

Kumārādēva, a grantee 105

Kumārādēva, *Mahārāja* (of Uchchakalpa), 119, 123, 128, 131, 138; — his wife was Jayasvāmī 119, 123, 128, 131, 138

Kumārādēvi, daughter of Luchchhavi or of a Luchchhavi prince, and wife of Chandragupta I. 16, 44, 51, 54 257

Kumārādēvi, wife of Ōghadēva of Uchchakalpa 119, 123, 128, 131, 138

Kumārāgupta (Early Gupta), 7, 17, 40, 41, 44, 47, 50, 51, 55, 80, 86, — he had the *biruda* or second name of Mahēndra or Mahēndraditya, 18; — in the Mankuwār inscription he has only the feudatory title of *Mahārāja*, 46, 47; — a half illegible reference to his wife, 50; — his Gadhwā inscription, date lost, 39; — his Gadhwā inscription of the (Gupta) year 98, . . . 40; — his Bilād pillar inscriptions of the year 96, . . . 42; — his Mankuwār image inscription of the year 129, . . . 45; — the Mandasor inscription, which gives the date of Mālava-Samvat 493 for his feudatory Bandhuvvarman, 79; — the value of this record, in proving that the Gupta era runs from an epoch in or very close to A.D. 319-20, . . . 65; — the Sāñchi inscription of the (Gupta) year 131, which may belong to his time, 260; — a fragmentary inscription at Gadhwā, which may belong to his time 264

Kumārāgupta (Gupta of Magadha), 206; — he conquered Isānavarman 206

Kumārāmāya, an official title, 16 and n., 52, 170, 218; — used in connection with *Mahādāṇḍandiyaka* and *Sāndhivigraha* 16

Kumārānāga, a grantee 128

Kumārāśarmāya, a grantee, 242; — another of the same name, 243; — and a third of the same name 243

Kumārāsēna, a grantee 105

Kumārāsvāmīn, a grantee 138

Kurus, the land of the North 260 and n.

Kuśalaprakṣā, *Nikhilapattī*, the *Dātaka* of the Nirmāṇḍ grant of Samudrasēna 291

- Aulāin*, being in good health, used in the preamble of grants . 119 and n., 123, 128, 132, 138, 169, 217, 298
- Kusthalapura, a town in Southern India; in the time of Samudragupta, its king was Dhanabhjaya 13
- Kuṭiḷa, a conventional name for a particular variety of the northern alphabet 201
- ḷ*, a southern letter; instances of its use in northern inscriptions 4, 269
- Laghu-Ārya-Siddhānta*, the customary name of the Siddhānta by the second Āryabhata; the date of it is between A.D. 628-29 and 1150-51 156 n.
- Lāhōr, the chief town of the Lāhōr District; the seal of the *Mahārāja Mahā-varanāga* 282
- Lāhōr Provincial Museum, an inscription from the 25
- Lakshma, a proper name 40
- Lakshmi, wife of the god Vishnu, and goddess of wealth and fortune (see also Śrī), 61, 286;—mention of a form of this goddess, at Mānapura, under the name of Pishṭapurī or Pishṭapurikādēvi, 113 and n., 116, 132, 138;—Lakshmi and elephants, on seals of grants . 191, 196
- Lakshmiṅvatī, wife of Śānavarman . 220 n., 221
- Lambōshtha, a grantee 105
- lāṅghana*, 'a crest,' as distinguished from *dhvaja*, 'a banner' 151 n.
- Lankā, one of the names of Ceylon . 275, 277, 278
- Lāta *vishaya*, an ancient name of Central and Southern Gujārāt 80, 84
- Lauhitya, the river Brahmaputra (see also Lōhitya) 145, 148
- lōkhaka*, a 'writer' (see also *likhita*), a technical term for the actual drafter or writer of a record, as opposed to the composer of it 88, 291
- Lichchhavi, the traditional name of a very early member of the family of the Lichchhavis of Nēpāl 185
- Lichchhavi (see also Lichchhivi) the personal or tribal name of the father-in-law of Chandragupta I., 16, 28, 44, 51;—whence the name of 'the Lichchhavis' appears on some of his coins, 135;—and the epithet 'daughter's son of Lichchhavi or of a Lichchhavi' was always applied to his son Samudragupta . 135, 16, 28, 44, 51, 54, 257
- Lichchhavi era; this would probably be the more correct name of the so-called Gupta era 136
- Lichchhavi-kula-kṣṭa*, 'the banner or glory of the Lichchhavi family'; an epithet of Śivadēva I. of Nēpāl, 177, 178;—and of Dhruvadēva of Nēpāl 281
- Lichchhavi rulers of Nēpāl; their early traditional genealogy, which is traced back to the god Brahma through Śōrya or the Sun, 185;—in accordance with which, their family is mentioned in the Nēpāl *Varāṅgali* as a Śōrya-vamāi family, i.e. as belonging to the Śōryavamāśa or Solar Lineage, 188;—but, in the code of Manu, a Lichchhavi or Lichchhivi is defined as the offspring of a degraded Kshatriya, 16 n.;—mention of their family under the names of Lichchhavikula and Lichchhavivamāśa, 177, 178, 181, 185;—and with the indication that it had originally another name, not now known, 185;—the first historical person in the family is Jayadēva I., 185, 186;—the palace of the Lichchhavi rulers of Nēpāl was Mānagriha, 177, 178, 180, 181, 189, 190;—they used the so-called Gupta era, 96, 184, 188;—instances of this, 178, 182, 183, 184;—the dates of the known members of this family, 189;—they seem to have had the government of the eastern portion of Nēpāl, 190;—the great antiquity of the Lichchhavi clan or tribe, 135;—the connection by marriage between the Lichchhavis of Nēpāl and the Early Guptas, 135;—so-called Gupta era is probably a Lichchhavi era, dating from the monarchical constitution of the Lichchhavis, or from the accession of Jayadēva I. in Nēpāl 136
- Lichchhivi, a variant for Lichchhavi; as the personal or tribal name of the father-in-law of Chandragupta I., 54, 257;—and in the code of Manu 16 n.
- likhita*, 'written' (see also *lōkhaka*), a technical term in connection with the manual drafting or writing of a record, as opposed to the composition and engraving of it 99 and n., 105, 109, 116, 120, 124, 129, 134, 139, 171, 190
- linga*, the phallic emblem, connected with the worship of Śiva . 180 and n., 182, 241, 248
- Lōhitya, the river Brahmaputra (see also Lauhitya) 206
- Lōkakāla, a method of reckoning by cycles of a hundred years; Alberdun's illustration of the conversion of Lōkakāla dates into Śaka dates through the Gupta reckoning, 26 n.;—it entails the use of the first current year of the Gupta era, not of its epoch, 27 n.;—according to Kalhana's statement in the *Rājataranginī*, the first year of each Lōkakāla cycle coincided with the forty-eighth current year of each century of the Śaka era, 26 n.;—according to Alberdun's statements, the first year of each Lōkakāla cycle in Multān and those parts, commenced from one to three years later, 27 n.;—

the method of Durlabha of Multán, as quoted by Albérúni, indicates plainly that the use of the *Lôkakála* in that part of the country only dates from A.D. 926, and that it was not introduced by, or in the time of, the Early Guptas 27 n.

Lôkápála, a regent of one of the quarters of the world 90 and n., 251 and n.

m; the forms of this letter are a useful criterion in classifying alphabets 3

mâdâsyâta, a word requiring explanation 71 and n.

Mâdhava, the god Vishnu, as 'the descendant of Madhu' 206

Mâdhava, *Râja*, father of Gôparâja; he married the daughter of a *Śarabha* king 93

Mâdhavagupta (Gupta of Magadha), 206, 217; — mentioned in connection with Harshavardhana of Kanauj, 207; — his wife was *Śrîmatî* or *Śrîmatîdêvî* 208, 217

Madhunadi, a river in the *Bhôjâkṣa* kingdom 241

Madhusûdana, the god Vishnu, as 'the destroyer of the demon Madhu' 77

Madhyadêśa, 'the middle country,' an apparent reference to it 286

Madra, the person who caused the *Kabhûm* pillar to be set up 67

Mâdraka, a tribe; conquered by *Samudragupta* 14

Maghârya, a grantee 243

Maghasarman, a grantee 243

Maghavan, the god Indra, as 'the distributor of gifts' 156

Mahâ-Âsvayuja *samvatsara*; one of the years of the Twelve-Year Cycle of Jupiter 110, 117, 104, 115

Mahâbaldhîrîta, a military title 109 and n., 129, 134

Mahâbaldhyakṣa, a military title, of the officer who was the superior of the *Baldhyakṣas* 179

Mahâbhairava (see *Svâmi-Mahâbhairava*) 241, 248

Mahâbhârata, the epic poem, mentioned under this name, the verses quoted from it being attributed to *Vyâsa*, 120, 124, 129, 134, 139; — a reference to a section of it, or to the whole poem, under the name of *Satasâhâri-Samhitâ* 139

Mahâ-Chaitra *samvatsara*; one of the years of the Twelve-Year Cycle of Jupiter 114, 108

Mahâdaitya, the imaginary name of the father of *Dêvî*, the imaginary wife of *Samudragupta* 18, 19

Mahâdandânyaka, a military title (for a feminine form of the subordinate title *Dandânyaka*, see 263 n.), 16 and n.,

17, 218; — used in connection with *Mahâkîrtîkîrîta*, *Mahâprathîhâra*, *Mahârâja*, and *Mahâsâmanta*, 41, 15 n., 296 n.; — and in connection with *Kumârdmîtya* and *Sândhivîgrahika* 16

Mahâdêva, a grantee 105

Mahâdêva, the god *Śiva*, as 'the great god' 96, 104, 108, 111

Mahâdêvî, a title of the wives of paramount sovereigns, 16 and n., 27, 28, 44, 51, 54, 55, 208, 212, 217, 221, 232, 257; — applied also to the wives of feudatory *Mahârâjas* 16 n., 119, 123, 128, 131, 132, 138, 208

Mahâdêvî, the name of the wife of *Râjyavardhana* I, as read from the half-illegible *Sônat* seal (but Dr. Bühler's reading of the grant discovered since then, shews that her name was *Apsarôdêvî*) 232

Mahâdêvidêva, a proper name 109

Mahâdhirâja, a feudatory title 41

Mahâ-Jayarâja, see *Jayarâja* 192, 194

Mahâkântara, a country in Southern India; in the time of *Samudragupta*, its king was *Vyâghrarâja* 13

Mahâkîrtîkîrîta, an official title; used in connection with *Mahâdandânyaka*, *Mahâprathîhâra*, *Mahârâja*, and *Mahâsâmanta* 41, 15 n., 296 n.

Mahâ-Kâsyapa, an ancient Buddhist saint 277 and n.

Mahâkṣhapâṭalika, an official title . 190 and n.

Mahâkshatrapas; see *Kshatrapas* or *Mahâkshatrapas* of *Saurâshtra* 36 n.

Mahâkumârdmîtya, an official title 190 and n.

Mahâ-Mâgha *samvatsara*; one of the years of the Twelve-Year Cycle of Jupiter 119, 112

Mahânadi, a river 228 n.

Mahânâman I, a Buddhist teacher 277

Mahânâman II, a Buddhist teacher, 275, 278, 279; — his *Bôdh-Gayâ* inscription of the (Gupta or perhaps *Kalachuri*) year 269, . . 274; — his *Bôdh-Gayâ* image inscription 278

Mahâprathîhâra, an official title, 183, 190 and n., 218; — used in connection with *Mahâdandânyaka*, *Mahâkîrtîkîrîta*, *Mahârâja*, and *Mahâsâmanta*, 41, 15 n., 296 n.; — and in connection with *Sarvadandânyaka* 183

Mahârâja, a feudatory title, 17, 41, 177, 178, 180, 181, 183, 189, 190, 15 and n., 16, 25, 28, 36 n., 47, 51, 54, 90, 97, 104, 109, 111, 112, 115, 119, 123, 128, 131, 132, 138, 160, 168, 169, 171, 221, 230, 235, 240, 241, 247, 248, 257, 267, 283, 290; — it denotes equal rank with *Mahâsâmanta*, and *Mahâsîndhupati*, 15 n.; — used in connection with *Mahâsâmanta*, 289, 290; — in connection with *Mahâsîndhupati*, 15 n., 252; — and, with *Mahâsâmanta*, in connection with *Mahâdandânyaka*, *Mahâkîrtîkîrîta*, and *Mahâprathîhâra*, 41, 15 n., 296 n.; —

- Mahārajas* of Brāhmaṇ descent, and of the Maitrāyalya *śākhā*, 90, 160; — *Mahārāja*s allotted to the Bhadravāja *śākhā*, 115; — and to the Viṣṇuvridhna *śākhā* 241, 242
- Mahārājādāhi*, possibly a conventional abbreviation of *Mahārājādhirāja* . . . 25 and n.
- Mahārājādhirāja*, one of the technical titles of paramount sovereignty, 17, 41, 180, 182, 189, 10 and n., 16, 25, 27, 28, 32, 33, 36 n., 38, 40, 41, 44, 51, 52, 54, 55, 71, 160, 183, 185, 186, 187, 189, 212, 217, 218, 221, 232, 240, 247, 257; — its close connection with *Paramabhadrāra* and *Paramītoara* 10 n.
- Mahāsāmānta*, a feudatory title, 41, 177, 178, 179, 181, 189, 190, 148 n., 284, 289, 290; — it denotes equal rank with *Mahārāja* and *Mahāsēnāpati*, 45 n.; — used in connection with *Mahārāja*, 289, 290; — and, with *Mahārāja*, in connection with *Mahādāndānyaka*, *Mahāśaktikṛitika*, and *Mahāpratihāra* 41, 15 n., 296 n.
- Mahāsīmāhivigraha*, an official or military title . . . 16 n., 103 and n., 109, 129, 134
- Mahāsarvādāndānyaka*, a military title, of the officer next in rank above the *Sarvādāndānyakas* 178
- Mahāśiva*-*Tiṅgarāja*, a fuller name of *Tiṅgarāja* or *Tiṅgarāja* 293, 298
- Mahāsēna*, or *Svāmi*-*Mahāsēna*, a name of the god *Kārttikēya*, as 'the commander of a large army' 43, 44
- Mahāsēnagupta* (Gupta of Magadha), 206; — he conquered *Susthitarman*, 15, 206; — *Mahāsēnaguptā*, wife of *Adityavardhana*, was probably his sister 15
- Mahāsēnaguptā*, wife of *Adityavardhana*, 232 and n.; — she was probably the sister of *Mahāsēnagupta* of Magadha 15
- Mahāsēnāpati*, a military title, 252; — it denotes equal rank with *Mahārāja* and *Mahāsāmānta*, 15 n.; — used in connection with *Mahārāja* 252
- Mahā*-*Sudēvarāja*, see *Sudēvarāja* 197, 199
- Mahā*-*Itara*, an official title 169 and n., 170, 218
- Maha*-*Vaśākha* *śmśvatsara*; one of the years of the Twelve-Year Cycle of Jupiter 104, 96, 97
- Mahāvihārasvāmin*, a title of religious office 272 and n.
- Mahāvamsa*, the Pāli history of Ceylon; the dates derived from its details require to be rectified in accordance with the *Bōdh*-*Gayā* inscription of *Mahānāman* (or may be adjusted by means of that record, if the date of it should be in the *Kalachuri* era) 16, 275
- Mahēndra*, or *Mahēndragiri*, a mountain in the Eastern Ghāts, 7 n., 13 n.; — mention of a mountain *Mahēndra* in *Yaśōdharman*'s pillar inscription at *Mandaśor*; it may be the mountain in the Eastern Ghāts, or another of the same name in the Western Ghāts 146 and n., 148
- Mahēndra* of *Kōsala*, a king in Southern India, conquered by *Samudragupta* . . . 12
- Mahēndra* of *Pishtapura*, a king in Southern India, conquered by *Samudragupta* 7 n., 13
- Mahēndra*, or *Mahēndraditya*, a *śrūda* or second name of *Kumāragupta* 18
- Mahēndragupta*, the imaginary name of a supposed son of *Skandagupta* . . . 18, 19, 56 n.
- Mahēndrapāla*, *Mahārāja*; the value of his *Dighvā*-*Dubaul* grant of the (*Harsha*) year 155, towards proving the epoch of the *Harsha* era 178 n.
- Mahēśvara*, the god *Śiva*, as 'the great lord' 167, 168, 160, 180, 181, 182, 183, 184, 185, 186, 188, 189, 217, 221, 240, 248, 290
- Mahēśvaranāga*, *Mahārāja*, 283; — his *Lāhōr* copper seal 282
- Mahēśvarārāja*, a grantee 243
- Mahādēva* (Lichchhavi of *Nēpāl*) 186, 189
- Mahilabāl*, or *Mahilābāl*, an ancient village in the *Khētaka dhāra* 189
- mahimat*, *mahimat*, 'a king' 99 and n., 105, 109, 116, 120, 124, 129, 134, 139
- Mahishāsura*, a demon, defeated by the goddess *Pārvatī* in her form of *Dēvī* 227 and u.
- Mahiya*, a town and State in *Bagbhākhap*; it is not to be identified with *Mahēndra* or *Mahēndragiri* 13 n.
- Maitraka*, a tribe, conquered by *Bhāṭarka* of *Valabhī* 13, 167, 180
- Maitrēya*, an ancient Buddhist saint 277 and n.
- Maja*, a proper name 33
- Majhgawām*, a village in the *Nāgaudh* State; the grant of *Hastin* of the (*Gupta*) year 191, . . . 106; — its importance in helping to prove the *Pūrnimānta* arrangement of the fortnights in the *Gupta* year, 77, 107 n.; — examination of its date 114
- Mālava*, a country, the modern *Mālwa*; the *Rulers* of *Mālwa* 7, 76, 77, 86
- Mālava*, a tribe, conquered by *Samudragupta*, 14; — references to an era dating from the tribal constitution of the *Mālavas*, 66, 87, 158; — notice of certain ancient coins of the *Mālavas* 67
- Mālava* era, a convenient name for an era which sometimes is mentioned as dating from the tribal constitution of the *Mālavas*, 66, 87, 158; — sometimes is spoken of as the era of the *Mālava* lords, 66 n.; — and sometimes is called the *Mālava-kāli* or *Mālava* era, 66 n.; — other dates which are to be referred to it, 73, 74, 253; — it is in reality the *Vikrama* era, under its original name 68
- Māliya*, a village in the *Junāgaḍh* State; the grant of *Dharasēna* II. of the (*Gupta*-*Valabhī*) year 252 164

- Māliwa, inscriptions from 72, 79, 142, 149, 150
 Mānadēva (Lichchhavi of Nēpāl), 182, 186, 188, 189, 191; — notice of his inscription of the (Gupta) year 386, 182; — examination of the date, 95; — notice of another inscription of his time 182
- Mānagrīha, the palace of the Thākuri rulers of Nēpāl 177, 178, 180, 181, 189, 190
- Mānapura, an ancient town; perhaps the modern Mānpur near the Sōp 136, 138
- Mandākini, the river Ganges 184
- Mandār, a hill in the Bhāgalpur District; the rock inscriptions of Adityasēna 211
- Mandara, a mountain, used as the churning-stick when the ocean was churned by the gods and demous 206
- Mandasōr, a town in Scindia's Dominions; it is locally known as Dasōr, 79 n.; — mentioned under the ancient Sanskrit name of Dasapura, 79 n., 54, 86; — the inscription of the Mālava year 529, which gives the date of the Mālava year 493 for Kumāragupta and Bandhuvarman, 79; — the value of this record in proving that the Gupta era runs from an epoch in or very close to A.D. 319-20. 65; — the pillar inscriptions of Yasōdharman, 142, 149; — the inscription of Yasōdharman and Vishṇuvardhana, of the (Mālava) year 589 150
- Mandhāttri, an epic king 147, 149
- Maṅgalāsa (Early Chalukya), the value of his Bādāmi cave inscription, of Saka-Samvat 500 expiring, in proving that the historical starting-point of the Saka era is the commencement of the reign of some particular king or kings of the Saka tribe 142, 143
- Manināga pātha, an ancient division, partly in the territory of the Parivrājaka Mahārājās, 116, — and partly in that of the Mahārājās of Uchchakaṅpa 138
- Mankuār, a village in the Allahābād District; the image inscription of Kumāragupta, of the (Gupta) year 129 45
- Manōratha, Mahāsēmdhivijrahika, the writer of the grants of Sarvanātha of the (Gupta or Kalachuri) years 193 and 197 129, 134, 139
- Manṭarāja of Kēraja, a king in Southern India, conquered by Samudragupta 13
- Manu, the traditional author or compiler of a code of law, 147, 168, 182; — instance of a certain verse being allotted to him, which is usually quoted as being written by Vyāsa in the Mahābhārata 99 n.
- Mārgaśrīsha, one of the Hindu lunar months, a rare instance of its being intercalary 93
- mātaraḥ, the divine Mothers 48 and n., 51, 78,
- maṭha, a religious college 208
- Mathurā, the chief town of the District of the same name; the inscription of Chandragupta II., 25, — the image inscription of the (Gupta) year 135, 262; — the image inscription of the (Gupta) year 230 273
- Matila, a king in Northern India, conquered by Samudragupta 13
- Mātrārya, a grantee 243
- mātrās, the horizontal top strokes of letters; early instances of their development 43, 140
- Mātrichēta, the builder of an ancient temple of the Sun at Gwālior 163
- Mātridāsa, a proper name, 38, — another person of the same name 163
- Mātrisarman, a grantee, 105; — another of the same name 243
- Mātrīarmārya, a grantee, 243, — another of the same name 243
- Mātrīvaiva, *Uparika*, the additional *Dūtaka* of the grant of Sarvanātha of the (Gupta or Kalachuri) year 197 134
- Mātritrūta, a proper name 163
- Mātrīviṣṇu, *Mahārāja*, 90, 160; — in conjunction with his younger brother, Dhanyaviṣṇu, he caused the Eraṅga pillar, with the inscription of Budhagupta of the (Gupta) year 165, to be set up, 90, — the temple of Viṣṇu, in front of which is the boar with the inscription of Ībramāna, was finished by Dhanyaviṣṇu, for him, after his death 161
- Maukhari, a tribe, clan, or dynasty (see also Mukhara), 14, 15, 206, 221, 223, — the Maukharis were defeated by Damodaragupta, 206; — they had previously defeated the Hōṅas, 206, — an instance of the great antiquity of this tribe, 14; — intermarriage of the Maukharis with the Guptas of Magadha, 14, 187; — and with the Thākuri rulers of Nēpāl 187
- Mayūrākshaka, a minister of Viśiṅvarman 78
- Mēharauli, or Mēmharauli, a village in the Delhi District, its name is a corruption of Mihirapurī, 12, 139 and n.; — the posthumous pillar inscription of Chandia 139
- Mēru (see also Sumēru), a mountain which is supposed to form the central point of the Hindu world 77, 163
- Mēsha-Samkrānti* (see also *abdāpa*), 'the entrance of the Sun into the sign Aries,' this is the starting-point of the year adopted by Prof. K. L. Chhatre for his processes, 145 n.; — and it is the commencement of the Saka year, taken as a solar year for astronomical calculation, 101 n.; — the figures for the *abdāpa*, obtained by Prof. K. L. Chhatre's Tables, are for the apparent, not mean, *Mēsha-Samkrānti*, 145, 147; — so also those for

Nachné-ki-talât, a village in the Jasô State; the inscriptions of Prithivishêpa 211

Nâga race or tribe; a possible allusion to a defeat of the Nâgas by Skandagupta 62 and n.;— and by Tivaradêva, 298 and n.;— the *Mahârâja* Mahêsvara-nâga must have been of this race, 283;— other chiefs of this race are probably to be found in Gaṇapatiṅga, Nâgadatta, and Nâgasêna, who were conquered by Samudragupta . . . 12, 13

Nâgabhatta, a proper name . . . 283

Nâgadatta, a king in Northern India, conquered by Samudragupta . . . 13

Nâgadêya *santaka*, an ancient division in the territories of the *Mahârâja* of Uchchakalpa, 120;— it is not to be identified with the modern Nâgaudh . . . 94 n.

Nagara *bhukti*, an ancient territorial division in Bihâr . . . 218

Nâgarjuni Hill, in the Gayâ District; mentioned as a part of the Vindhya range, 227, 228;— the cave inscriptions of Anantavarman . . . 223, 226

Nâgasari, an ancient village or tank in Baghêlkhând . . . 105

Nâgasarman, a grantee, 105, — another of the same name, 243;— and a third of the same name . . . 243

Nâgasêna, a king in Northern India, conquered by Samudragupta . . . 12, 13

Nâgasinha, *Mahâbalâdhikrîta*, the *Dâtaka* of the grant of Hastin of the (Gupta) year 191 . . . 109

Nâgaudh or Nâgaundh, the name of a State in Baghêlkhând, it is possibly derived from *nâgavadha* or *nâgabandha*, but is certainly not to be identified with Nâgadêya, 94 n., — inscriptions from this State . . . 93, 100, 106, 110, 112, 121, 125, 129, 132, 135

Nâgavatsavâmin, a grantee . . . 199

Nâg;ur Provincial Museum, inscriptions from the . . . 191, 196

Nâgama, 'an interpreter of Vêdic quotations and words' . . . 156

'nail-headed' characters . . . 19 and n., 106

nakshatra, 'a lunar mansion,' 163;— the grouping of the *nakshatras* for naming the years of the Twelve-Year Cycle of Jupiter, according to the heliacal-rising system, 162, 163;— a variation by Garga and Parâsara, as quoted by Utpala, from the usually accepted grouping, 163 n.;— the longitudes of the ending-points of the *nakshatras*, according to the equal-space system, by which each *nakshatra* represents the exact twenty-seventh part of the ecliptic circle; according to the Garga system of unequal spaces, governed by

the same primary division; and according to the Brahma-Siddhânta system of unequal spaces, governed by the moon's daily mean motion, and introducing the additional *nakshatra* Abhijit, 165;— the proof that we must apply one or other of the unequal-space systems in dealing with the records of the Early Gupta period, 166;— and that one or other of them was in use, or both of them were, up to A.D. 862. . . 107 n.;— Dhanishthâ was the first *nakshatra* for the Five-Year Cycle of the Vêdânga-Jyautisha, and it seems to have been taken by Varâhamihira as the first *nakshatra* for the Sixty-Year Cycle of Jupiter according to the mean-sign system, 173 n.;— the only *nakshatra* mentioned by name in dates in the Gupta era, is Rôhinî, in one of the Nêpâl inscriptions 95, 182

Nâlânda, or Nâlândâ, an ancient Buddhist site in Bihâr, an apparent mention of it 210

namas, 'reverence,' an invocation connected with the names of gods, &c. at the commencement of inscriptions; it usually governs a dative case, 96, 104, 108, 115, 259. — but there are instances in which it is used with the genitive 46 n., 47

names, proper, the abbreviation of, 8 n.;— the only available instance of variation in the first and distinctive part of a king's name, 183;— special terminations of proper names in this series of records; and in the Nêpâl inscriptions, as far as the contents of them are quoted —

aditya, with Bâla, Dharma, Krama, Mahêndra, Prakaṣa, Śîla, Vikramâ

ddhya; with Dêva.

anka, with Vikrama.

arka, with Bhaṭa, Udyôta

ârya, with Bappa, Bhôjakadêva, Dêva, Dêvasarman, Dharma, Gana, Harîsarman, Isvarasarman, Jyêsthasarman, Kânda, Kumârasarman, Magha, Mahêsvara Mâtri, Mâtrisarman, Nandana, Rêvatisarman, Rôha, Rudra, Rudrasarman, Sarman, Skanda, Sôma, Sômasarman, Svâmîdêva, Svâtîsarman, Varsasarman.

ârya; with Bhadra.

bala, with Gôârasintha, Hari, Indra, Vishnu.

bhata; with Dêra, Dhro, Dhruva, Hari, Pulinda, Śkanda, Vishnu.

bhatta; with Nâga.

bhattâ; with Jaya.

bhattaka; with Tîla.

bhatti; with Vatsa.

bhâti; with Dhruva, Rudra.

bha (see 31 n.); with Raṅka.

chandra; with Râma, Surâsîmi

- chēta*; with Mātri.
ādśa (see 11 n.); with Ajagara, Bhujanga, Dharma, Śvara, Mātri, Śiva, Varāha, Viṣṇu.
datta; with Abhaya, Bhaga, Bhāskara, Bhava, Dhruva, Divākara, Gauri, Hara, Nāga, Nara, Parṣa, Phalgu, Ravi, Śarva, Shashṭhi, Śūrya, Svāmin, Vasu, Vibhu.
dēva; with Ādityasēna, Bālāditya, Bāopa, Bhōjaka, Dēvagupta, Dharma, Dhruva, Harsha, Jaya, Jitvagupta, Kaudrava, Kumāra, Mahādēvi, Mahī, Māna, Nanna, Narēndra, Ōgha, Rudra, Rukhara, Śamkara, Saśānka, Ślāditya, Śiva, Skanda, Svāmin, Tivara, Udaya, Vasanta, Vijaya, Viṣṇu, Vrisha, Vyāghra.
dēva; with Ajhita, Bhāgya, Bhōga, Datta, Dhruva, Ijjā, Kamala, Kōpa, Kumāra, Murunda, Rāma, Śrīmatī, Vatsa.
dharman (see 145 n.); with Yaśas.
dinna (see 124 n.); with Varāha, Vtki.
dōcha; with Bhagavat, Dharma.
gōmika; with Chhōḍu.
gōmin; with Chhōḍu.
gōpa; with Viṣṇu.
graha; with Bha or Bhā, Khara.
gupta (see 8 n., 11 n.); with Ananta, Bhānu, Budha, Chandra, Dāmōdara, Dēva, Dharna, Hari, Harsha, Jishṇu, Jivita, Kṛishna, Kumāra, Mādhyava, Mahāsēna, Ravi, Samudra, Śiva, Skanda, Viṣṇu.
guptā; with Ananta, Bhānu, Harsha, Mahāsēna, Prabhāvati, Upa.
ila; in Matila, Rājyila, Saṅghila, Sōmila.
jaya; with Dhanam.
kāma; with Parachaktra.
kardava; with Amra or Āmra.
kīrtti; with Guṇja, Ravi.
kula; with Mihira.
kumbha; with Dōha.
lakshmi; with Mihira.
mitra; with Ākhaṇḍala, Buddha, Dēva, Durdhara, Hamsa, Pushya, Rishi, Śūrya.
nda; with Bhava, Dēva, Gaṅgapatī, Kumāra, Mahāvāra, Śakti, Sarva, Skanda, Svāmin.
nōman; with Mahā (Mahat).
nandin; with Viṣṇu.
ndha; with Jaya, Śarva.
paksha; with Śāla.
pāla; with Śiṅu.
pāliṭa; with Chakra.
pati; with Paśu.
paṭṭa; with Dhara.
prakhā; with Kuśala.
putra; with Daiva, Gautami or Gautamī, Sandhyā.
rāja; with Dēva, Gōpa, Jaya, Konḍa, Manṭa, Nīla, Śatrughna, Sudēva, Tivara, Vyāghra.
rāta; with Amra or Āmra, Vyāghra, Yaśas.
īarman (see 11 n.); with Bhartri, Dēva, Dhruva, Gō, Gōṇḍa, Guha, Hari, Śvara, Jyēshtha, Kumāra, Magha, Mātri, Mōksha, Mūla, Nāga, Rēvati, Rudra, Śānti, Sōma, Su, Svāti, Vara, Varuṇa.
sēna; with Āditya, Ananta, Dazshitra, Dhara, Dhruva, Guha, Hari, Kumāra, Nāga, Pravara, Prithivi, Ravi, Rudra, Samjaya, Samudra, Siddha, Skambha, Śūra or Śūra, Ugra, Upa, Varuṇa, Vasanta, Vikrama, Vīra.
siddha; with Sana.
simha; with Drōḍa.
siṅha; with Achala, Drōṇa.
sinha; with Bhrukuṇṭha, Nāga.
śiva; with Bhāra, Mātri, Sōkshma.
sōma; with Bhāṭṭi, Rudra.
svāmika; with Dhriti.
svāmin; with Agni, Ananta, Bappa, Bhava, Brahmādēva, Dēva, Divākara, Gōmika, Gōpa, Gōri, Gōvinda, Guhila, Jaya, Kumāra, Mitra, Nāgavatsa, Śarva, Savitri, Svāti, Vindu.
svāmīnī; with Hari, Jaya, Murunda, Śikhara.
trita; with Hari, Sōma, Viṣṇu, Yaśas.
tula; with Mātri.
vādha; with Sarva.
vardhana; with Āditya, Harsha, Prabhākara, Rājya, Viṣṇu, Yaśas.
varman (see 11 n.); with Achala, Āditya, Amśu, Ananta, Avanti, Bala, Bandhu, Bhīma, Bhōga, Bōdhi, Chandra, Chitra, Hari, Hastin, Isāna, Śvara, Jaya, Nara, Sārdūla, Sarva, Susthita, Vibhu, Viśva, Yajña.
vatsa; with Bandhu, Nāga.
vishṇu; with Dēva, Dhanya, Hari, Indra, Mātri, Varuṇa.
vriddha; with Viṣṇu.
Nandanārya, a grantee 243
Nandi, or Nandin, the bull, the vehicle of the god Śiva; a reference to him as an emblem on Śiva's banner 147
Nandin, a king in Northern India, conquered by Samudragupta 13
Nannadēva, of the Pāṇḍuvarṃśa, 293, 298; — his adopted son was Tivara-dēva, 293 and n., 298 and n., — his son by birth was Chandragupta 293 n.
napti, and *pranapti*, as contrasted with *pantra* and *prapantra*, may fairly be rendered by 'grandson' and 'great-grandson' 97 n.
Nara, a class of mythical beings, allied to the Gandharvas and Kinnaras 84
Nārada, an ancient sage, the inventor of the lute 14

Nārada-Samhitā, an ancient astrological work, quoted in support of the heliacal-rising system of the Twelve-Year Cycle of Jupiter 170

Naradatta, *Bhōgika* and *Amātya* . 100, 105, 109

narādhipati, 'a chief ruler of men,' contrasted with *janādndra*, 'a lord of a people or tribe' 151 and n.

Naravarman, a Mālava feudatory of Chandragupta II. or of Kumāragupta 76

Nārāyana, a Kanva or K nvāyana prince, mentioned in the *Viṣṇu-Purāna*; there is no foundation for the supposition that he is mentioned, as the Tushāra king Vishṇu, in the Tuśām rock inscription 270

Nārāyana, the god Viṣṇu, as 'he whose path or station is the waters' 161

Narēन्द्रadēva (Thākurl of Nēpāl) 186, 187, 189, 191

Narmadā, a river, the modern 'Nerbudda' (see also *Rēvā*) 90

Nashli an ancient town or village in the *Sukuli dēśa* 32

Nātha, *Sāmdhivigrahika*, writer of the grant of Sarvanātha, of the (Gupta or Kalachuri) year 214 139

Nēpāla, a country, the modern Nēpāl; Samudragupta either included it in his empire, or else extended his conquests up to the confines of it, 14 and n.; — the chronology of the early rulers of the country, Appendix IV., 177 to 191; — their dates, 189; — the double government of the country, during this period, by the Lichchhavis of Mānagriha and the Thākuris of Kailāsakūtabhavana, 188, 189; — later instances of the same system of double government, 188 n.; — the earliest eras in this country were the Gupta era, used by the Lichchhavi rulers, 95, 96, 184, 188; — and the Harsha era, used by the Thākurl rulers, 95, 96, 184, 189; — the tradition of the *Vamśāvali*, that Vikramāditya came to Nēpāl and established his era there, refers really to the introduction of the Harsha era, 184, 185; — but, under the name of the Nēwār era, an offshoot of the Vikrama era, according to its southern reckoning, was introduced in A.D. 880, . . . 74, 184; — and, in more modern times, the Vikrama era itself, from Northern India 76

Nēwār era; an era used during a certain period in Nēpāl; its years being taken as current years, it commenced in A.D. 880, with the epoch of A.D. 879-80, . . . 74, 75; — the peculiarity of it, is, that it is an offshoot of the southern Vikrama era, with Kārttika śukla 1 as the initial day of each year, and with the *Amānta* arrangement of the lunar fortnights, 74, 75, 76; — the epigraphical names for the era, 74 n.; — examination of certain dates recorded in it 75

Newton, Mr.; views expressed by him on the Gupta era and connected matters 43

nīchōchcha-māsa (see also *kēndra*), 'the anomalistic month,' the period in which the moon comes from perigee or apogee to the same point again; its duration is 27 days, 33 *ghaṭṭis*, 16 3/6 *palas*, or 27 *tithis*, 59 *ghaṭṭis*, 33 3/6 *palas*, which figures, and not the practical equivalent of 28 *tithis*, are taken as the governing quantities for Prof. K. L. Chhatre's Table for the *tithi-kēndra* 149 and n.

nickname (*paribhūta-nāman*), an instance of a 290

Nihlapati, an official title, requiring explanation 291

Nīlarāja of Avamukta, a king in Southern India, conquered by Samudragupta 13

Nimād District, an inscription from the 219

nirayana, 'destitute of precession of the equinoxes' 146

Nīrmand a village in the Kāngra District, mentioned as the ancient Nīrmaṇḍa *agrāhāra*, 290; — the grant of the *Mahāśmanta* and *Mahārāja* Samudrasēna 286

nīrvāna, 'annihilation of human passion,' a stage in the Buddhist practices, anterior to *parinīrvāna* or complete annihilation of personal existence by absorption into the all-pervading spirit 264, 277

North-West Provinces, inscriptions from the 1, 25, 36, 39, 40, 42, 45, 52, 65, 68, 228, 249, 262, 264, 266, 267, 271, 272, 273, 281, 284

numerical symbols (see also dates); the dates up to which they continued to be used, 209 n.; — instances of the use of them in combination with decimal figures, 292 n.; — a possible instance of the vocalisation of numerical symbols, 73 n.; — forms of numerical symbols illustrated in this series of Plates,—

one	34, 91, 107, 261, 264, 287
two	19, 22, 34, 165, 264, 266
three	4, 19, 30, 34, 48, 107
four	4, 19, 30, 34, 117
five	19, 34, 48, 89, 165, 172, 192, 261, 263
six	19, 209, 287
seven	19, 91,
112 (see 274 n.),	172, 209, 266, 274, 292
eight	4, 37, 41, 46, 236, 253
nine	46, 110, 197, 255, 266, 274
ten 37, 46, 110, 117,	165, 197, 236, 255, 287
twenty	46, 112, 192, 233, 263
thirty	48, 261, 263, 266, 274
forty	172
fifty	165
sixty	89, 209, 274
seventy	117
eighty	22, 37

- ninety 30, 41, 91, 107
 one hundred 46, 89,
 91, 107, 117, 261, 263, 266
 two hundred 165, 273, 274
 four hundred 172, 253
 eight thousand 236
- numerical words; the earliest epigraphical and other instances of the use of them, 73 n.;—an instance of the use of them in a date in the Nēwār era . . . 75 n.
- ocean; an invocation of the ocean, with a reference to the legend of the sons of Sagara, 155;—the western ocean, 148, 157;—the southern ocean, 141;—the oceans enumerated as four in number, 27, 44, 51, 54, 86, 90, 160, 221, 257, 290;—the verge of the four oceans is the marriage-string of the earth, 86;—their waters are the couch of the god Viṣṇu, 90;—rivers spoken of as the wives of the ocean, 64;—reference to the submarine fire 297, 298
- Ōghadēva, *Mahārāja* (of Uchchakalpa), 119, 123, 128, 131, 138;—his wife was Kumārādēvi 119, 123, 128, 131, 138
- Oldenberg, Dr. H.; views expressed by him on the Gupta era and connected matters 56
- Om, an invocation used at the commencement of inscriptions, books, &c., and represented throughout this series of records by a symbol, not by actual letters, 46 n., 47 and n., 93, 115, 119, 128, 131, 138, 160, 163, 167, 180, 199, 205, 212, 223, 225, 227, 257, 277, 279, 282, 296;—it is not of very frequent use in Buddhist inscriptions; but there are instances 46 n., 47, 277, 279, 282
- Ōpāni, an ancient village in the Maṇi-nāga pāṭha 116
- pādachārin*, 'moving on feet; personified' 169 and n., 181
- pādānuḥyāta*, 'meditating on the feet;' a technical expression for the relations of a feudatory to his paramount sovereign, 17 and n., 25;—of a subordinate to a feudatory *Mahārāja*, 235;—of a son to his father, 17 n., 51, 119, 123, 128, 131, 132, 138, 181, 182, 186, 188, 189, 217, 221, 239, 290;—of a son to both his parents, 17 n., 195, 199, 298;—of a nephew to his 'uncle,' 185;—of a grandson to his grandfather, 187 n.,—and of a younger to his elder brother, 17 n., 181, 182, 232;—it is used also in respect of the worship of gods, 17 n., 111;—an instance in which *pāda* is omitted 17 n.
- pādapadmōpajivin*, 'subsisting (like a bee) on the water-lilies that are the feet;' a technical expression, of very common occurrence in southern inscriptions, but of rather rare use in northern records, for the relations of a feudatory to his paramount sovereign 98 n.
- pādapindōpajivin*, 'subsisting on the cakes that are the feet,' a technical expression to denote the relation of officials to a feudatory *Mahārāja*; rendered by 'feudatory' 98 and n., 195, 109, 116
- pādāvarta*, a particular land-measure 170 and n.
- Padmā, the name of a community of *Chaturvēdins* 71
- Padmāvati, a proper name 260
- padraka*, 'common-land,' in Bhumbhusa-padraka and Śivakapadraka, 170 and n.;—used as the termination of the name of a village, in Pimpripadraka 298
- Pahlādpur, a village in the Ghāṭpur District; the pillar inscription of Śiśu-pāla (?) 249
- pala*, a particular weight 71 and n.
- pala*, 'the sixtieth division of a *ghaṭī*,' equal to twenty-four English seconds 147
- Palakka, or Pālakka, a town or country in Southern India; in the time of Samudragupta, its king was Ugrasēna 13
- Pālāśini, a river flowing from the mountains Ūrjayat 64
- pālī*, 'a bridge' 124 and n., 125
- palimpsest grant, an instance of a 126
- Pallava, a tribe; a possible early record of them in Northern India 250
- Pamvā, an ancient village in the Pārvarāshṭra or Eastern Country 195
- pañcha ānantaryāni*, 'the five sins that entail immediate retribution' 34 and n.
- pañcha meghāpatākāni*, 'the five great sins' 38 and n., 39, 40, 72, 120, 124, 129, 134, 138, 171, 265, 269, 291
- pañcha-mahāśabda*, the sounds of five musical instruments, the use of which was allowed to persons of high rank and authority (see also *samadhigata-pañchamahāśabda*) 296 and n.
- pañcha-mahāyājñika*, the rites of the *pañcha-mahāyājña* or five great sacrifices; enumerated as *bali*, *charu*, *vaiśvadeva*, *agnihōtra*, and *atithi*, 170, 190;—mention of the *bali*, *charu*, and *sattra*, i.e. *atithi*, without the others 116 and n., 124, 129, 132, 290
- pañcha-maṇḍalī*, 'an assembly of five persons;' equivalent to the modern *Pañchālī*, *Pañchayat*, or *Pañch*, 'a village-jury' 32 and n.

- Pāchaka*, 'a committee' (see also *pañcha-mandalī*) 183
- Pañchāṅg*, 'a Hindu almanac'; in the Dekkan, and in some other parts, all *Pañchāṅgs* are now prepared from the *Graha-Lāghava* and the *Tithi-Chintāmaṇi* of Gaṇeśa Daiyajña 146 n.
- Pāṇḍuvāṃśa*, 'the lineage of Pāṇḍu'; Indrabala, Nannadēva and Tivaradēva, belonged to this lineage 298
- Pāṇini*, the grammarian; mentioned under the name of Śālāturiya 183
- Pañjāb*, inscriptions from the 139, 269, 282, 286
- Parachakrakāma*, a *biruda* or second name of Jayadēva II. of Nēpāl 184, 187
- parāhīya*, a correction in time, to be applied to the mean *tithi* 149
- paramabhāgavata*, a Vaiṣṇava sectarian title 28 and n., 38, 40, 41, 44, 51, 52, 54, 55, 116, 168, 195, 199, 217, 257
- Paramabhaṭṭāraka*; one of the technical titles of paramount sovereignty, 17, 41, 182, 10 n., 17 and n., 25, 71, 183, 185, 186, 187, 188, 189, 212, 217, 232;—its close connection with *Mahārājādhirāja* and *Paramēvara*, 10 n.,—an instance in which it is applied to a priest 17 n.
- Paramabhaṭṭārīkā*; a title of the wives of paramount sovereigns 17 n., 212, 217
- Paramadēvī*, a title of the wives of *Mahāśānta* and *Mahārājās* 290
- paramādityabhakta*, a sectarian title of solar worship 28 n., 168, 232
- paramamāhēvara*, a Śaiva sectarian title, 28 n., 167, 168, 169, 180, 181, 182, 183, 184, 185, 186, 188, 189, 217, 221, 240, 248, 290
- paramasaṅgata*, a Buddhist sectarian title 28 n., 232
- paramavaishṇava*, a Vaiṣṇava sectarian title 28 n., 298
- Paramēvara*, one of the technical titles of paramount sovereignty, 41, 10 n., 151, 156 n., 183, 185, 186, 187, 188, 189, 217, 218;—its close connection with *Mahārājādhirāja* and *Paramabhaṭṭāraka* 10 n.
- Paramēvara*, the god Śiva, as 'the supreme lord' 185 n.
- paramount sovereigns, titles of; *i.e.* of sovereigns supreme in their own dominions, but not necessarily reigning over the whole of India 10 n.
- Parāśara*, the father of *Vyāsa* 139
- Parāśara*, an ancient astronomer, quoted by *Kishiputra*, and through him, as well as directly, by *Utpala*, for the heliacal-rising system of the Twelve-Year Cycle of Jupiter, 170;—and for a variation from the usually accepted grouping of the *nakṣatras* 163 n.
- paribhāta-nāman*, 'a nickname'; an instance 290
- parichchēda*, a territorial term 105 and n.
- Paivrājaka Mahārājās*, 8, 95 n., 97, 104, 109, 111, 115;—they belonged to the *Bharadvāja gōtra*, 115;—they were feudatories of later members of the Early Gupta dynasty; and the extreme importance of their records lies in their proving that the Gupta dominion continued to A.D. 528 8
- Pāriyātra*, a mountain 157
- Parṇadatta*, Skandagupta's governor for *Saurāshṭra* 62, 63, 65
- Pārśva*, a Jain *Tirthamkara*; mention of an image of him, with a hooded snake and an attendant female 259 and n.
- Pārtha*, a metronymic of *Yudhisṭhira*, *Bhīmasēna*, and, in particular, *Arjuna* 86, 93
- Pārthiva*, a tribal name, perhaps denoting the *Pallavas* 250, 251
- Pārvatī* (see also *Bhavanī*, *Dēvī*, *Gaurī*, and *Kātyāyanī*), wife of the god Śiva; mentioned as the daughter of *Himālaya* 147
- Paśupati*, the god Śiva, as 'the lord of animals' 184, 16
- Paśupati*, a king, overthrown by *Mihirakula* 163
- Pāṭaliputra*, an ancient name of the modern *Paṭna* in *Bihār*, 36, 37, 39;—it is perhaps referred to, under the name of *Pushpapura*, in connection with *Samudragupta* and the *Kōtas* 5
- Pa-t'cha*, see *Tu-lu-po-pat'cha* 40
- pathaka*, a territorial term 173 and n., 189
- Paṭna*, the chief town of the *Paṭna District* in *Bihār*; mentioned under the ancient names of *Pāṭaliputra*, 36, 39;—and of *Pushpapura* 185, and perhaps, 5, 12
- Paṭna District*, an inscription from the 47
- patla*, apparently a territorial term 104 and n.
- Paulōmī*, the goddess *Śachi*, the wife of *Indra*, as the daughter of *Pulōman* 225
- Pausa*, one of the Hindu lunar months; a rare instance of its being intercalary 179
- pautra* and *prapautra*, especially as contrasted with *naptri* and *pranaptri*, are properly to be rendered by 'son's son' and 'son of a son's son', instead of vaguely by 'grandson' and 'great-grandson'. 15 n., 97 n.
- Pavara* *Javanāṭaka*, an ancient village in the *Bennākārapara bhāga* 234 n., 248
- Penthāma bhukti*, an ancient division in the territory of *Tivaradēva* 298
- pltha*, a territorial term 116 and n., 138
- Phakka*, a nickname 290
- phala-samskāra*, 'the equation of the centre' 149
- Phalgudatta*, *Amātya* and *Bhōgika* 124 and n., 129, 134, 139
- phuffa*, a *Prākṛit* word 121, 125, 130
- pillars*, inscribed 1, 42, 47, 52, 65, 88, 91, 110, 139, 142, 149, 249, 252, 279
- Pimpripadraka*, an ancient village in the *Peṭhāma bhukti* 29

- Pinâkin, the god Śiva, as 'having the bow called Pinâka' 154
- Piṣṭapura, a town in Southern India, the modern Piṭṭapuram, 7 n., 13, 113 n.; — in the time of Samudragupta, its king was Mahendra 13
- Piṣṭapurī, or Piṣṭapurikāḍḍvī, a form, at Mānapura, of the goddess Lakṣmī 113 and n., 116, 132, 138
- Piṭṭapuram, a town in the Gōḍavari District, mentioned under the ancient Sanskrit name of Piṣṭapura 7 n., 13, 113 n. posthumous inscriptions 1, 91, 139
- Prabhāḷā, wife of Varuṇasēna 290
- Prabhākaravardhana, a king of Kanau, or more properly of Thānēsar, 232. — his wife was Yaśōmatī, 232. — his father was the *Mahārāja* Adityavardhana, 232; — and not Pushyabhūti or Pushyabhūti, or Śilāditya of Mālava 15
- Prabhāṅjana, *Mahārāja* (Parivrājaka) 97, 104, 109, 115
- Prabhāvatiguptā, daughter of Dēvagupta, and wife of Rudrasēna II. 15, 240, 247
- Prakāṭḍitya, a king of Kāśī, 286; — his Sārānāth inscription 284
- Prākṛit language, an epigraphical mention of the 157
- Prākṛit names and words:—
- ajjaka* 187 n.
- Ajjhita* 119 and n., 123, 128, 131, 138
- bappa* 186 n.
- bāva* 186 n.
- boppa* 188 n.
- ljijā* 217 and n.
- phulṭa* 121, 125, 130
- santaka* 118 n., 241 and n., 248
- uchchhanna* 255
- prandīl*, 'a conduit' 180
- Frārijuna, a tribe, conquered by Samudragupta 14
- prastī*, 'an eulogy,' a technical term for an inscription on stone, 87 n., 201, 208, 286; — an exceptional instance in which this term is used to denote a copper-plate charter 87 n.
- Pratinartaka*, an official or family title, perhaps meaning 'a herald' 190 and n.
- praidīh*, 'a gateway with a flight of steps' 43 and n., 45
- pratyaya*, *pratyāya*, 'a holding' 170 and n.
- Pravaragiri, the ancient Sanskrit name of the Barābar Hill 22-, 223
- Pravarapura, the city from which Pravara-sēna II. issued his Chammak grant 240
- Pravarasēna I., *Mahārāja* (Vākātaka) 241, 248
- Pravarasēna II., *Mahārāja* (Vākātaka), 240, 247; — his Chammak grant, 235; — his Siwanī grant 243
- Prayāga, an ancient name of Allahābād 206
- Prinsep, Mr. James; his rendering of the date in the Kāhānū pillar inscription of Skandagupta, from which originated the idea of an era dating from the extinction of the Gupta sovereignty 35
- Prithivishēna, *Mahārāja* (Vākātaka), 235, 240, 248; — his Nachnē-ki-tālāi inscriptions 233
- prithivyūdm-a-pratiratha* (compare *svayam-a-pratiratha*, applied to Chandragupta II.), an epithet of Samudragupta, 14, 27, 44, 51, 54, 257; — used partially on his coins, 14 n.; — applied also to Vijayarāja (Chalukya of Gujarāt) 14 n.
- Prithu, an epic king 20
- Prīti, 'affection,' one of the wives of the god Kāmādēva 85
- prose, inscriptions which are entirely in 21, 25, 29, 36, 39, 40, 45, 110, 208, 211, 213, 219, 231, 251, 252, 254, 260, 264, 266, 267, 269, 271, 272, 273, 278, 279, 280, 281, 282
- Pulikēsin II. (Western Chalukya); examination of the date of his Haidarābād grant of the Śaka year 534 expired, which proves that, up to A.D. 612, the *Pārnimānta* arrangement of the lunar fortnights was used with the Śaka years, even in Southern India 79 n.
- Pulindabhaṭa, a grantee 138
- pundarika*, a particular sacrifice 254
- puraka*, 'a city'; this word is not justified by the only instance that is quoted for it 69 n.
- pūraka*, as a termination of names of villages, in Brahmāpūraka, Kollāpūraka, and Vaṭapūraka 248
- Purāmdara, the god Indra, as 'the destroyer of cities' 286
- Pārnimānta*, the technical name for the scheme of the lunar months in Northern India, according to which arrangement the months end with the full-moon day, and the dark fortnights precede the bright, 70; — in astronomical works, however, it is always the *Amānta* arrangement that is actually taken for calculations, 148 n.; — even in Southern India, the *Pārnimānta* arrangement was used with the Śaka years, for the civil reckoning, up to between A. D. 804 and 866, 79 n.; — on the other hand, even in Northern India, it was not used with the Nēwār era in Nēpāl, 75; — but it was adopted there, when the Nēwār era was followed by the Vikrama era in its northern variety 76
- Pūrvarāshtra, the Eastern Country, subject to Jayarāja and Sudēvarāja 192 and n., 195, 199
- Pushyabhūti, or Pushyabhūti, a king mentioned by Bāna in the *Harshacharita*, in connection with the family of Harshavardhana of Kanau; he has been wrongly assumed to be the father of Prabhākaravardhana 15

- Pushpapura, an ancient name of the modern Patna in Bihār, 185; — a town of this name is referred to in connection with Samudragupta and the Kōtas; but it may be Kanauj that is intended . . . 5, 12
- Pushyabhūti; see Pushpabhūti . . . 15
- Pushyamitra, a tribe, conquered by Skandagupta, 55; — the correct form of the name seems to be Pushyamitra, not Pushpamitra . . . 55 n.
- queen, widowed, selection of a successor to her husband by . . . 12 n.
- rachita*, 'composed'; a technical term in connection with the composition of a record, as opposed to the writing and engraving of it . . . 87, 99 n.
- Rāghava, 'a descendant of Raghu'; a name in particular of Rāmachandra, but also applied to Aja, Daśaratha, and Lakshmaṇa . . . 20
- Rāhula, a Buddhist teacher . . . 277
- Rajvataka, a hill near the mountain Ūrjayat . . . 64, 229, 230
- Rājādhirāja, a title of paramount sovereignty, properly obsolete in the Gupta period, but used in some metrical passages, both alone and in *Rājārjādhirāja* . . . 33 and n., 62, 151, 156 and n.
- rājakula*, 'of the royal household; a member of the king's household' 33 and n., 190
- Rājāmātya*, an official title . . . 218
- Rāja*, or more properly *Rājan*, a feudatory title . . . 189, 192, 197, 293
- Rājaputra*, an official title . 180, 182, 184, 218 and n.
- Rājasthāntya*, an official title . . . 157 and n., 170, 218
- Rājatarānginī*, a historical poem, of which the principal part was written by Kalhana; Kalhana's statement regarding the equation between the Lōkakāla and the Śaka era, 26 n.; — the early history of Kaśmīr, as deduced from this book, is to be adjusted by the now settled date of Mihirakula . . . 56
- Rajendrālala Mitra, Dr.; views expressed by him on the Gupta era and connected matters . . . 50
- Rājim, a town in the Rāypur District; the grant of Tivradēva . . . 291
- Rājīśī*, 'queen,' a title of the wives of paramount sovereigns . . . 212 and n., 217
- Rājputānā, inscriptions from . . . 251, 252
- Rājyamati, daughter of Harsha of Gauda, and wife of Jayadēva II. of Nēpāl . . . 187
- Rājyavardhana I., *Mahārāja*, an ancestor of Harshavardhana of Kanauj, 232; — the name of his wife, as read from the half-illegible Sōnpat seal, is given as Mahādēvī (but Dr. Bühler's reading of the grant discovered since then, shews that her name was Apsarōdēvī) . . . 232
- Rājyavardhana II., king of Kanauj, or more properly of Thānēsār . . . 232
- Rājyavati, wife of Dharmadēva of Nēpāl . 182
- Rājyīla, *Amātya* and *Bhōgika* . . . 120
- Rāma, an epic hero, one of the incarnations of Viṣṇu . . . 77
- Rāmachandra, a proper name . . . 286
- Rāmadēvī, wife of Jayasvāmin of Uchchakalpa . . . 119, 123, 128, 131, 139
- rana-stambha*, 'a column of victory in war,' the Mandasār pillars, with the inscriptions of Yasōdharman, are actual instances . . . 145
- Ranganātha, a commentator on the *Sūrya-Siddhānta*, the date of his commentary is A.D. 1603-1604. . . 175; — his remarks on a verse in the *Sūrya-Siddhānta* in connection with the heliacal-rising system of the Twelve-Year Cycle of Jupiter . . . 171 n.
- Rankabōta, a grantee . . . 123
- Rati, 'the pleasure of love,' one of the wives of the god Kāmādēva . . . 85
- ratna-grīha*, 'a jewel-house,' a term which apparently denotes the great *Śrēṇā* at Sāñchi . . . 33 and n., 34, 262
- Rāvāñ, wife of Vasudatta . . . 271
- Ravidatta, *Bhōgika* . . . 100, 105, 109
- Ravigupta, *Sarvadandanyaka* and *Mahāprathāra*, the *Dūtaka* of the inscription of Vasantasēna of the (Gupta) year 435 . . . 183
- Ravikīrti, a proper name . . . 156
- Ravishēṇa, *Mahāśamānta* and *Mahārāja*, 290; — his wife was Mihiralakshmi . . . 290
- Rāypur, a town in the Central Provinces; the grant of Mahā-Sudēvarāja . . . 196
- Rāypur District, inscriptions from the . 191, 196
- regnal or dynastic years, which have furnished the origin of most of the Hindu eras, can come to be ordinarily quoted as expired years, only when the era has been adopted by astronomers for astronomical processes, 143; — instances of dates recorded in regnal years, 159, 161, 192, 197, 236, 244, 287, 293; — instances of dates recorded apparently in regnal years, but really in years of an era . . . 38 and n., 40, 41, 44, 71, 268
- Rehatsck, Mr. E.; his proposal for amending the translation of Alberūnī's words regarding the origin of the Gupta era . . . 28
- Reinaud, M.; his rendering of Alberūnī's statements regarding the Gupta and other eras . . . 23, 36
- Rēvā, a name of the river Narmadā . . . 156, 157

Révatikā, an ancient village in the Gaya <i>vishaya</i>	257
Révatiśarman, a grantee	243
Révatiśarmārya, a grantee	243
Ripughna, apparently a proper name, used to denote Śatrughna or another Purāṅic king or hero	260 and n.
Rishimitra, a grantee	218
Rishiputra, an ancient Hindu astronomer, quoted by Utpala for the heliacal-rising system of the Twelve-Year Cycle of Jupiter, 161 n., 170; — he himself quotes Atri, Parāśara, and Vasishṭha, in support of the same	170
rock inscriptions	56, 269, 283
Rōhārya, a grantee	243
Rōhiṇī, a wife of the Moon, 286; — the name of a <i>nakṣatra</i>	95, 182
Rōhitaḡadh, or Rōhiṭāḡadh, a hill-fort in the Shāhābād District; the seal-matrix of Saśānkadēva	283
Royal Asiatic Society's Library, an inscription from the	171
Rudra, a proper name	280
Rudrabhūti, a grantee	170
Rudradēva, a king in Northern India, conquered by Samudragupta	13
Rudrārya, a grantee	243
Rudrasārman, a grantee, 105; — another of the same name	243
Rudrasārmarya, a grantee	243
Rudrasēna I., <i>Mahārāja</i> (Vākātaka)	241, 248
Rudrasēna II., <i>Mahārāja</i> (Vākātaka)	240, 248
Rudrasōma, also called Vyāghra	67
Rukharadēva, a grantee	105
Sāha, another name of Vīrasēna	27 n., 36
<i>sa-brahmachārin</i> , 'a religious student with (others who follow the same <i>śikṣā</i>)'	103, 108, 179, 256
Sachau, Prof. E.; his rendering of Albernūn's statements regarding the Gupta and other eras	24
Śachi, wife of the god Indra, mentioned under the name of Paulōmi	225
<i>śādyashra</i> , a particular sacrifice	241 and n., 248
Śāgar District, inscriptions from the	18, 88, 91, 158
Sagara, an epic king, 21, 99, 105, 109, 116, 120, 124, 129, 134, 139, 155, 171, 190, 195, 200, 291, 299; — mentioned with reference to the legend of the excavation of the bed of the ocean by his sixty thousand sons	155
<i>sa-gōtra</i> , 'belonging to the same <i>gōtra</i> with (the person from whom the <i>gōtra</i> -name is derived)'	70, 96, 103, 108, 114, 118, 166, 179, 193, 198, 236, 239, 240, 243, 246, 256, 270, 295

'Sah,' or 'Sāh,' the imaginary family or dynastic name of the Mahāksatrapas of Saurāshtra, based on the custom of omitting superscript vowels in the legends on their coins	36 n.
Sahya mountains, a range in Western India; mentioned as one of the breasts of the earth	86 n., 184 and n.
Śaiva inscriptions (for other instances of Śaiva worship, see <i>atyantamāhāśvara</i> , <i>atyantavāmimāhābhairavabhakta</i> , and <i>paramamāhāśvara</i>)	180, 182, 184, 35, 43, 48, 146, 149, 266
Śaka, a tribe, conquered by Samudragupta	14
Śaka era; an era of northern origin, commencing in A.D. 78, though usually represented as commencing in A.D. 79; according to the chief Hindu tradition, its starting-point was the defeat of a Śaka king by king Vikramāditya of Ujjain, 142; — according to a later tradition, it dates from the birth of king Śālivāhana of Pratiśṭhāna; but there is no proof of his name being connected with it before the thirteenth century A.D., 142 n.; — its real historical starting-point was the commencement of the reign of some particular king or kings of the Śaka tribe, 142; — a curious instance of confusion, by the Jain writer Śilāchārya, between the Śaka and the Gupta eras, 32 n.; — the difference in the scheme of the Northern and Southern Śaka years, both commencing with Chaitra śukla 1, . . . 70, 71; — even in Southern India, the <i>Amānta</i> arrangement of the lunar fortnights was not used with the Śaka era, for the civil reckoning, till between A.D. 804 and 866, . . . 79 n.; — for the civil reckoning, the Śaka year is luni-solar, commencing with Chaitra śukla 1, and it is sometimes used thus by astronomers; but also, for astronomical calculations, it is sometimes taken as a solar year, commencing with the <i>Mēsha-Samkrānti</i> , 101 n., 137 n.; — a note on the epoch and reckoning of the era, Appendix I, 137 to 144; — instances of the use of apparently current years of this era, which have to be applied as expired years, 80 n., 107 n.; — quotations of the reckoning of this era, both by current and by expired years, from Hindu almanacs, which give its total duration as 18,000 years, 137 to 141, 138 n.; — the present reckoning in Southern India is by current years; while the reckoning in Northern, Western, and Central India, is by expired years, 140, 141; — the habitual quotation of the latter reckoning has led to the mistaken idea that the era commenced in A.D. 79, . . . 141 and n.; — but it really commenced in A.D. 78, . . . 142; — the years of the era were originally	

- regnal or dynastic years, and must have been used as current years, 142, 143;—the substitution of the Śaka era for the Kaliyuga era, for astronomical purposes, which would introduce the ordinary use of its years as expired years, seems to have taken place between A.D. 476 and 587 143, 144
- śākhā*, lit. a 'branch,' a Vēdic school, following any particular recension of one of the Vēdas; names of *śākhās* mentioned in this series of records:—
- Aupamanyava 199
- Bahvr̥cha 190, 257
- Chhandōga-Kaūthama 109
- Kātha 105
- Maitrayaṇīya 90, 160
- Rāṇyanīya 71
- Taittirīya 248
- Vājasaneyā 105, 195, 199
- Vājasaneyā-Mādhyaṃdina 97, 120, 293
- Vājasaneyī-Kaṇva 170
- Śakra, the god Indra, as 'the powerful one' 67
- Śakta or Tāntrika worship; apparent early instances of it (see also Vajrēvara) 48 and n., 74, 226
- Śaktiṅga, a grantee 128
- Śākya, the name of the tribe or family of Buddha, 277;—mention of Śākya *Bhikṣhus*, 272, 279, 280, 282;—and of a Śākya *Bhikṣhant* 274
- Sālapakṣa, a *Baldhikrita* of Ādityasēna of Magadha 210
- Śālatūrya, a name of the grammarian Paṇini 183 and n.
- Śālivāhana-Śaka, an expression that is frequently used to denote the Śaka era; but it is an anachronism for any period earlier than the thirteenth century A.D. 142 n.
- sam*, an abbreviation of the word *samvatsara*, 'a year,' or of any of its declensional cases that can be used in expressing a date . 82, 84, 93, 22 n., 30 n., 32, 89, 167
- samaḥgata-paṅchamahāsabda*, a customary epithet of feudatory nobles, indicating that they are entitled to the privilege of the *paṅcha-mahāsabda*, 296 and n.;—three instances in which the epithet is applied to paramount sovereigns, 297 n.;—an instance of the privilege being conferred on a feudatory by his paramount sovereign . 297 n., 298 n.
- Sāmanta*, an official title, 42, 180, 182, 148 n., 223 and n.;—used in a non-technical sense 148 and n.
- Sāmantaḍvā, a Hindu king of Kābul; remarks on some of his coins, which have been supposed to bear dates in the Gupta era 57 to 60
- Samāsa-Samhitā*, an astrological work by Varāhamihira, quoted by Utpala in support of the heliacal-rising system of the Twelve-Year Cycle of Jupiter . . . 170
- samassa-rājakhyāndm-a-hasta-prasāhapanīya* (see also *sarna*), a fiscal term 171 and n.
- Samatata, a country, Lower Bengal; Samudragupta either included it in his empire, or else extended his conquests up to the confines of it . . . 9 n., 14 and n.
- Śaṭbbhu, the god Śiva, as 'he who exists for happiness or welfare' . . 36, 155, 240, 248
- Sāmdhvisvīrahika*, an official or military title, 16 and n., 120, 139, 171;—used in connection with *Kumdrāmātya* and *Mahādandanāyaka* 16
- samīdhyā*, a period at the commencement of each of the four Hindu ages; the *samīdhyā* of the Kaliyuga lasts for 36,000 years of men, and is still running 139 n.
- samīdhyāmsī*, a period at the end of each of the four Hindu ages; the *samīdhyāmsī* of the Kaliyuga is to last for 36,000 years of men 139 n.
- Saṃjayasēna, *Mahāśmanta* & *Mahārāja*, 290;—his wife was Śikharasvāminī . . 290
- Saṃkara, also called Sanghila, *Aśvapati* . 260
- Saṃkaradēva (Lichchhavi of Nēpāl) 182, 186, 189
- samkrānti*, or *samkrāmana*, 'the entrance of the sun into a sign of the zodiac,' the limits of the *paṇyakhā* or meritorious time for performing religious duties on these occasions, 178 n.;—the only *samkrānti* mentioned in this series of records is the *uttarāyana* (the winter solstice) 199
- Saṅkabhōḥa, *Mahārāja* (Parivrājaka), 115;—his Khōh grant of the Gupta year 209 . . 112;—an alteration in the reading of the date of this record, 76 n., 274 n.;—its importance in proving the *Pārumānta* arrangement of the fortnights in the Gupta year, 76;—examination of the date 117
- samrāj*, a paramount sovereign' . 147 and n.
- Samudragupta (Early Gupta), 17, 18, 11, 17 n., 21, 27, 44, 51, 54, 257;—his wife was Dattadēvī, 21 n., 27, 44, 51, 54;—description of his musical and poetical accomplishments, 11, 12, 14, 15;—the kings, tribes, and countries, conquered by him, 12, 13, 14;—Garuḍa-tokens, *i.e.* coins or banners bearing representations of Garuḍa, were given to him by feudatories, 14 and n.;—reference to a city named Pushpapura, apparently as his capital, 5, 12;—Aryōdhya represented, in a spurious grant, as a camp of his, 256;—he was specially selected by his father to succeed him, 12 n.;—he specially selected Chandragupta II. to succeed himself, 12 n., 27 n.;—he may have had the *biruda* or second name of Kācha, 18, 27 n.;—he revived the *asvamedha-sacrifice*, after it had been long in abeyance, 28 and n., 44, 51, 54, 257;—remarks on some of his coins, 12 n., 14 n., 15 n., 27 n., 28 n.;—three of his customary

- epithets are applied to Vijayarāja (Chalukya of Gujārāt), 14 n.;—his Allahābād (or Kauśāmbī) posthumous pillar inscription, 1;—his Ērap inscription, 18;—his spurious Gayā grant of the year 9 254
- Samudrasēna, *Mahādāmanā* and *Mahārāja*, 290;—his Nirmāṇḍ grant 286
- samvat*, an abbreviation of the word *samvatṣara*, 'a year,' or of any of its declensional cases that can be used in expressing a date, 84, 92, 95, 97, 178 to 184, 22 n., 30 n., 47, 92, 108, 119, 180, 210, 257, 261, 267, 277, 289;—the use of this word is not really confined to the Vikrama era; and, joined with the name of the era, it gives a convenient method of quoting the years of any of the different eras 22 n.
- samvatṣara*, 'a year' (see also *sam. samvat*, and year) 95 n.;—the reason why the earlier years of Hindu eras are quoted by this term, or by the abbreviations *sam* and *samvat*, without any dynastic appellation 143
- samvatṣaras* or years of the Twelve-year Cycle of Jupiter, by the heliacal-rising system, mentioned in records of the Early Gupta period:—
- Mahā-Āsvayuja 110, 117, 104, 115
- Mahā-Chaitra 114, 108
- Mahā-Māgha 119, 112
- Mahā-Vaiśākha 104, 95, 96
- Sanakānika or Sanakānika, a tribe, conquered by Samudragupta, 8 n., 14, 25;—certain *Mahārājas* of this tribe mentioned by name 25
- Sanasiddha, a proper name 262
- Sāñchi, or Sāchi, a village in the Bhōpāl State; its name is not derived from the Sanskrit word *sānti*, but is probably an alliterative vernacular word, 29 n., 260 n.;—in the Aśoka period, its name was Kākanāda, 31;—in the Gupta period, the name of the great *Stūpa* here was Kākanādabōtamahāvihāra, 31, 261;—in the inscriptions it seems to be denoted by the term *rātna-griha*, 33 and n., 34, 262;—the modern popular name of the great *Stūpa* is *Sās bahū hā bifā*, 30 n.;—the inscription of Chandragupta II. of the (Gupta) year 93, .29;—the inscription of the (Gupta) year 131, .260;—a pillar inscription 279
- Sandhyāputra, a grantee 97
- Saṅghila, another name of Śaṅkara, *Aśvapati* 260
- Saṅhārikā or Saṅhārikā, the imaginary name of a wife of Samudragupta 18, 19, 1
- śankha* 'a conch-shell,' as an emblem on seals 191, 196, 292
- Sanskrit language, an epigraphical mention of the 157
- santata*, a Prākṛit word meaning 'belonging to,' in *asmat santata* 118 n., 241, and n., 248
- santaka*, *santika*, a territorial term 118 and n., 120, 132
- 'Santāl' Parganās, a late inscription from the, mentioning Adityasēna of Magadhā 212 n.
- Śāntiārman, a grantee 243
- saptāṅga*, 'the seven constituent elements of a kingdom' 242 and n.
- Śarabha king, mention of a, as the maternal grandfather of Gōparāja (see also Śarabhapura) 14, 93
- Śarabhanga, a proper name 33
- Śarabhapura, the town from which Jayarāja and Sudevarāja issued their charters, 192, 194, 199;—it is not to be identified with Arvi, nor with 'Sambalpur' or 'Sambhalpur,' 192;—the *Rājyas* of Śarabhapura (see also Śarabha king) 14, 194, 199
- sarad*, 'the autumn,' the importance of the use of this word in connection with the Mālava or Vikrama era 66 n.
- saradhī*, 'a bow-string' 223 and n.
- Sarasvatī, wife of the god Brahman, and goddess of learning 208
- Śārdūla, Śārdūlavarman, a Maukhari chief 223, 225, 228
- Śarman, an abbreviation of the name of Dhruvasarman 9 n., 45 and n.
- Śarmārya, a grantee 243
- Śārngapāni the god Vishnu, as 'bearing in his hand the bow of horn named Śārngā' 147, 183
- Śārngin, the god Vishnu, as 'possessing the bow of horn named Śārngā' 56, 87
- Śārnāth, a village in the Benares District; an image inscription, 281;—the inscription of Prakāśāditya 284
- Śarva, the god Śiva 163
- Sarvadandanyaka*, a military title, of an officer next in rank below the *Mahāsarvadandanyaku*; used in connection with *Mahāpratihāra* 183
- Śarvadatta, the *Dātaka* of the grants of Jayanātha of the (Gupta or Kalachuri) years 174 and 177 120, 124
- Sarvādhyakṣha*, 'general superintendent,' an official title 241 and n., 248
- Śarvanāga, *Viśhayaapati*, a governor of Skandagupta for the Antavēdī country 71
- Śarvanātha, *Mahārāja* (of Uchchakalpa), 112, 128, 132, 133, 138;—his Bhumarā pillar inscription, 110;—examination of its date, 119;—his Khōh grant of the (Gupta or Kalachuri) year 197, .125;—his imperfect Khōh grant, without date, 129;—his Khōh grant, imperfect, of the year 197, .132;—his Khōh grant of the year 214 135

sarva-rājāṅgādām = a *hasta-prashāpantiya*, (see also *samasta*), a fiscal term . . . 190

sarva-rāj-ōchkhētrī, an epithet of Samudragupta, 27, 44, 51, 54, 257; — it occurs also on the coins that bear the name of Kācha . . . 27 n.

Śarvasvāmin, a grantee . . . 105

Sarvata, a proper name . . . 190

Śarvavāḥa, *Divira*, a grantee . . . 123

Śarvavarman (Maukhari), 215, 218, 220, 221; — his *Asrīgadh* seal . . . 219

Śarvavarman, *Mahārāja*, mentioned in the *Nirmaṇḍ* grant of Samudrasēna . . . 290

śāsana, 'a charter' (see also *tāmra-śāsana*), a technical term for a deed of conveyance on copper-plates, 99 n., 194, 199, 218, 240, 242, 247, 249, 296; — an illustration of functions connected with such a charter . . . 99 n.

Śāśānakadēva, *Mahāśamanta*, 284; — his *Rōhitasgadh* seal-matrix . . . 283

Śāśātaneya, apparently the name of a *gōtra* . . . 123

Śās-bahū kā bīḍā, the modern popular name of the great *Śāḥpa* at Śāñchi: with which we have to compare *Śās-bahū kā dāhrā*, which is the modern popular name of the temple at Gwālior in which there is the inscription of Mahāpāla of the Vikrama year 1150 . . . 30 n.

Śatasāhasrī-Samhitā, the name of a section of the Mahābhārata, or of the whole poem . . . 139

Sattī, popularly *Suttī*, see cremation of widows . . . 92 and n., 93

Śatrughnarāja, a proper name . . . 241

sattrā, 'an almshouse', 37, 38, 39, 40, 41, 45, 116 n., 265; — one of the five great sacrifices, usually called *atithi* 116 n., 124, 129, 132, 290

Śātva, a Vaiṣṇava sect . . . 271 and n.

Saulīka, an official title . . . 52 and n.

Saurāshtra, the modern Kāthiāwāḍ country; mentioned under the name of Surāshtrāh, and as subject to Skandagupta, 62, 63; — remarks on the coins of the Kshatrapas or Mahākshatrapas of Saurāshtra . . . 36 n.

Savitrisvāmin, a proper name . . . 199

śāyana, 'inclusive of precession of the equinoxes' . . . 146

Scindia's Dominions, inscriptions from 21, 34, 79, 142, 149, 150, 161, 258

sculptures accompanying inscriptions on stone . . . 72, 269, 274

seals of charters; emblems on them, 125, 164, 191, 196, 219, 231, 255, 292; — legends on them, 94, 101, 106, 112, 125, 164, 191, 196, 219, 231, 235, 244, 255, 292; — instances in which they are attached to the plates by rings, 94, 101, 106, 112, 117, 121, 125, 130, 132, 135, 164, 172, 191, 196, 235, 244, 267, 292; — instances in which they are

attached to the sides of the plates by soldering, 69, 219, 231, 255; — an instance of a stone matrix for casting seals . . . 283

seasons, references and allusions to the various:—

Grīshma, the hot season . . . 63, 64

Hēmanta, the cold season . . . 86, 87

Śarad, the autumn . . . 77, 158

Śīṭira, the dewy season . . . 77, 87

Varshāh, the rainy season . . . 63

Vasanta, the spring . . . 158

selection by kings of their successors, and by a widow of her husband's successor . . . 12 n.

Śēnāpati, a military title 41, 167 and n. 168, 243 249

serpent-emblem on seals . . . 283

Śēsha, the king of serpents, mentioned as supporting the earth on one of his hoods . . . 208

Shāhābād (Ārā) District, inscriptions from the . . . 213, 283

Shāhānushāhi, a dynasty or tribe, conquered by Samudragupta . . . 14

Shāhi, a dynasty or tribe, conquered by Samudragupta . . . 14

Shāhpur, a village in the Paṭna District; the image inscription of Adityasēna of the (Harsha) year 66 . . . 208

Shashthidatta, a proper name . . . 156

śiddhāsin, a particular sacrifice. 241 and n., 248

śiddha, 'a perfect one,' the epithet of a certain class of Jain saints; they are always invoked in the plural . . . 259 and n.

Siddha, a class of supernatural beings 84, 206

śiddham, 'perfection has been attained,' an invocation used at the commencement of inscriptions, 25 and n., 32, 35, 54, 61, 67, 71, 84, 154, 247, 252, 254, 262; — it is the remnant of some such expression as *śiddham bhagavatā* . . . 25 n.

Siddhānta-Sivōmani, an astronomical work by Bhāskarāchārya; it was written A. D. 1150–51, . . . 156 n.; — its author's explanation of the rule for the Brahma-Siddhānta unequal-space system of the *nakshatras* . . . 166

Siddhasēna, *Mahāprasthāna* and *Mahākshapatālika*, the *Dūtaka* of the grant of Śīlāditya VII. of the (Gupta-Valabhi) year 447 . . . 190

sign-manual at the end of a charter, indicated by the word *sva-hasta*, 171, 191; — actual representations of a sign-manual . . . 171 n., 191

Śikharasvāmin, wife of Samjayasēna . . . 290

Śīlāchārya, a Jain writer, author of the *Āchārasthā*, in which, in giving the date, he makes a curious confusion between the Gupta and the Śaka eras . . . 32 n.

Śīlāditya, a *biruda* or second name, given by Hiuen Tsiang, of Harshavardhana of Kanauj . . . 39, 40

- Śilāditya of Mālava, a king mentioned by Hiuen Tsiang, 39, 40; — he has been wrongly assumed to be the father of Prabhākara-vardhana 15
- Śilāditya I. (of Valabhi), 41, 181, 183; — he had the *biruda* or second name of Dharmāditya 181
- Śilāditya II. (of Valabhi) 41, 185
- Śilāditya III., Śilādityadēva (of Valabhi) 41, 185
- Śilāditya IV., Śilādityadēva (of Valabhi) 41, 185
- Śilāditya V., Śilādityadēva (of Valabhi) 41, 187
- Śilāditya VI., Śilādityadēva (of Valabhi) 41, 188
- Śilāditya VII., Śilādityadēva (of Valabhi), 41, 189; — he had the *biruda* of Dhruvabhata, i.e. Dhruvabhata, 172 and n., 189; — his Alṅka grant of the (Gupta-Valabhi) year 447 171
- Sinhā era, an era commencing in A.D. 1114, or perhaps in A.D. 1113; quoted in the Verāval inscription of the Valabhi year 945 85
- Sinhāla, one of the names of Ceylon: mentioned as conquered by Samudragupta 14
- Sindhu, the river Indus; mentioned as having seven mouths 141
- Sirpur, a town in the Rāypur District; mentioned under the ancient Sanskrit name of Śrīpura 293, 296
- Sirūr, a village in the Dhārwāḍ District; examination of the date of the inscription of Amoghavarsha I., of the Śaka year 788, which proves that the *Amānta* arrangement of the lunar fortnights was applied to the Śaka years, in Southern India, between A.D. 804 and 866 79 n.
- Śiśupāla, an epic king, 250; — probably the name of the king whose inscription is on the Pahlāḍpur pillar 250, 251
- Śiva, the god, 'the destroyer' of the Hindu triad (see also Bhūtapati, Hara, Iśa, Īvara, Jayēvara, Kapālēvara, Mahādēva, Mahēśvara, Mihirēvara, Paramēśvara, Paśupati, Pinākin, Śambhu, Śarva, Śhānu, Śōlapāṇi, Śārabhōgēvara, Svāmi-Mahābhairava, and Tripurāntaka; and, for his wife, see Pārvatī), 241, 248; — mentioned in connection with the *liṅga*, 180 and n., 182, 241, 248; — mention of the river Gaṅgā flowing through his matted hair, 16; — other references to his matted or braided hair, 87, 163; — mention of him as the father of Kārttikēya, 206; — a reference to his bull Nandi or Nandin, as an emblem on his banner, 147; — a reference to his destruction of Kāmadēva, 87; — spoken of as employing Brahma for creation, preservation, and destruction; and also as being himself the creator, with a necklace of skulls, a serpent round his neck, and the crescent moon on his forehead, 153 and n.; — other references to him as 'the creator,' 185 and n., 186, 290; — other references to the moon on his forehead, 87, 163, 206; — a probable early instance of his form, in combination with Pārvatī, as Ardhānārēvara, 224; — a form of Śiva in combination with the Sun 268
- Śivadāsa, a proper name 112
- Śivadēva, *Bhaṭṭārāha*, the *Dātaka* of the inscription of Śivadēva II. of the (Harsha) year 143 (?) 182
- Śivadēva I., *Mahārāja* (Lichchhavi of Nēpāl), 177, 178, 189, 191; — he had the epithet of 'the banner or glory of the Lichchhavikula,' 177, 178; — notice of his Gōlmāḍhiḍḍ inscription of the (Gupta) year 316, . 177; — the value of this record in proving the use of the Gupta era in Nēpāl, and in fixing the chronology of the early rulers of that country, 96, 177, 184; — notice of another of his inscriptions, the date of which is lost 178
- Śivadēva II. (Thākurt of Nēpāl), 182, 187, 189, 190, 191; — his wife was Vatsadēvi, 184, 187; — notice of his inscription of the (Harsha) year 119, . 182; — and of an inscription of the year 143 (?), which is probably one of his records 182
- Śivagupta *Mahābaladhikṛita*, the *Dātaka* of the grants of Sarvanātha of the (Gupta or Kalachuri) years 193 and 197 129, 134
- Śivakapadraka, the name of some land in the village of Antaratrā 170
- Siwanī, the chief town of the Siwanī-Chhapārā District; the grant of Pravarasēna II 243
- Skambhasēna, a proper name 170
- Skanda, a name of the god Kārttikēya 51
- Skandabhaṭṭa, *Sāmadāyagrāhika*, writer of the grant of Dharasēna II. of the (Gupta-Valabhi) year 252 171
- Skandadēva, *Yuvārāja*, the *Dātaka* of a Nēpāl inscription of the (Harsha) year 82 181
- Skāndagupta (Early Gupta), 27, 51, 52, 55, 62, 64, 67, 71; — he had the *biruda* or second name of Kramāditya, 18; — mentioned as restoring the fallen fortunes of his family by conquering the Puṣyamitras, 55; — as defeating the Hūnas, 56; — apparently as overcoming the Nāgas, 62 and n.; — and as establishing his fame in the countries of the Mlechchhas, 62; — remarks on two of his coins, 23 n., 46 n.; — his Bihār pillar inscription, 47; — his Bhitār pillar inscription, 52; — his Junāgaḍh rock inscription of the (Gupta) years 136, 137, and 138, . 56; — his Kaḥāum pillar inscription of the year 141, . 65; — his Indōr grant of the year, 146, . 68; — a Sāśchi inscription of the year

131, perhaps of his time, 260; — a Mathurā image inscription of the year 135, of his time, 262; — a Kōsam image inscription of the year 139, of his time, 266; — a Gadhwā inscription of the year 148, perhaps of his time . . . 267

Skandaguptabaṭa, apparently the name of an ancient village in Bihār . . . 51

Skandanāga, a grantee . . . 128

Skandārya, a grantee, 243; — another of the same name . . . 243

skandhāvura, 'a camp,' in *jaya-skandhāvura* . . . 217, 257

Smara, the god Kāmadēva, as 'he who excites memory' . . . 85, 158, 169, 181, 223, 225, 278

snake emblem on seals . . . 283

Sōmanāthadēvapattana, or the city of the god Sōmanātha (Śiva), an ancient name of the modern Verāwal . . . 85

Sōmārya, a grantee . . . 243

Sōmasarmārya, a grantee . . . 243

Sōmatrāta, a proper name . . . 270

Sōmila, a proper name . . . 67

Sōmpat, a town in the Delhi District; the seal of Harshavardhana of Kanauj, or more properly of Thānēsar . . . 231

sovereigns, paramount, titles of; i.e. of sovereigns supreme in their own dominions, but not necessarily reigning over the whole of India . . . 10 n.

spashja, an astronomical term, to be translated by 'apparent' . . . 145 n.

spashja-tithi, 'an apparent *tithi*,' the method of determining it from the mean *tithi* . . . 154

spurious inscription, an instance of a . . . 255

Sramana, 'a Buddhist (and Jain) ascetic' . . . 32, 277

śrēṅś, 'a corporation or guild' . . . 71, 85, 86, 87

śrī, an honorific prefix to names, rendered in the case of paramount sovereigns and their wives by 'glorious,' of feudatories and other ordinary persons by 'illustrious,' of priests, teachers, &c., by 'saintly,' of gods by 'holy,' and of towns, &c., by 'famous'; generally *śrī* is used before consonants and *śrīmat* before vowels, but there are exceptions to this . . . 10 n.

Śrī, the goddess Lakshmi . . . 164, 206, 208

Śrīgupta, an early *Mahārāja* mentioned by I-tsing, he is not to be identified with the *Mahārāja* Gupta (Early Gupta) . . . 8 n.

śrīmat, an honorific prefix to names, rendered in the same way as *śrī*; the use of it is not confined to feudatories, but it is applied in the case of paramount sovereigns also . . . 10 n.

Śrīmatī, or Śrīmatīdēvī, wife of Mādhava-gupta . . . 208, 217

Śrīpura, the ancient name of Śirpur . . . 293, 296

Śrīśāhikā, an ancient village in the Pūr-varāshtra or Eastern Country . . . 199

Śrīvāpikā, a well at Śrīśāhikā . . . 200

Śtāṅu, the god Śiva, as 'the immovable one' . . . 148

sthapatisamrāj, apparently meaning 'chief of architects' . . . 120 and n., 124

Stāvira, a Buddhist priestly title . . . 279

stone, inscriptions on, are usually denoted by the term *prasasti* . . . 87 n.

Stūpa, the technical name of a certain kind of Buddhist monument, 30 and n.; — in two records the term *rainagriha* seems to be used to denote a *Stūpa*, 33 and n., 34, 262, — in the neighbourhood of Śāśchi, the popular term for a *Stūpa* is *bifā* . . . 30 n.

śū, an abbreviation of *śukla* or *śuddha*, 'the bright fortnight'; used in connection with *di* (see also under *ba di*), 91, 97, 210, 277, 291; — used by itself 93, 191

Sudarāna, a lake at Girinagara . . . 63, 64

Sudēvarāja, or Mahā-Sudēvarāja, *Rāja* (of Śarabhapura), 199; — his Rāypur grant, 196; — reference to another grant by him, which requires to be re-edited . . . 14

Sugata, a name of Buddha, as 'the one who has attained a good state' . . . 232 n.

Śukra, the regent of the planet Venus, and the preceptor of the demons . . . 86

Sūkshmaśiva, the engraver of the Apsad inscription of Adityasēna . . . 208

Sukuli *dśā*, an ancient territorial division in the neighbourhood of Śāśchi . . . 32

Sulabhaka, a proper name . . . 290

Śūlapāni, the god Śiva, as 'holding the trident in his hand' . . . 147, 149, 286

Sūlisagrāma, an ancient village in the neighbourhood of Nirmaṇḍ . . . 290

Sumēru, another name of the mountain Mēru, 86, 147; — mentioned as the abode of Indra, 278; — and as one of the breasts of the earth . . . 86 and n.

sun, inscriptions of sun-worship, 68, 79, 126, 161, 208, 214, 288, — sun worship indicated elsewhere by the title *paramādityabhakta*, 168, 232; — invocations of the Sun as a god, 71, 84, 163; — worship of the Sun combined with that of Vishnu, 126; — and with that of Śiva, 288, — ancient temples of the Sun, at Indōr in the Bulandshahar District, 70; — at Mandasōr, 80; — at Āramaka, 126; — at Gwālior, 162; — and at Dēb-Baranār, 218; — an image of the Sun at Shāhpur, 210; — the Sun connected with Varuṇa in the name of Varuṇārka, 215; — the Sun mentioned under the name of Varuṇāśin, 218, — mention of the chariot and horses of the Sun, 78, 163; — cows spoken of as 'daughters of the Sun,' 195 and n., 200, 299; — a symbol of sun-worship, or perhaps the wheel-emblem . . . 219, 269

- Supushpa, a traditional and very early member, at Pushpapura, of the family of the Lichchhavis of Nēpāl 185
- Sūrabhḡśvara, a *linga* form of the god Siva 180 n.
- Suraguru, the regent of the planet Jupiter, as 'the preceptor of the gods,' 90 n., 157; — the day of Suraguru, *i.e.* Thursday 81, 90
- Sūrasēna, or Śūrasēna, *Rājaputra*; his wife was Bhḡgadēvi, sister of Amśuvarman 180
- Surāshtrāb (or more usually Saurashtṛa) country, the modern Kāthiāwād; it was subject to Skandagupta 62, 63
- Suraśmichandra, *Mahārāja*, a governor of Budhagupta for the country between the rivers Jamnā and Narmadā 89, 90
- Sūryadatta, *Mahāsādhivigrahika*, the writer of the grants of Hastin of the (Gupta) years 156 and 163 99, 105, 109
- Sūryadatta, a grantee 97
- Sūryamitra, a grantee 218
- Sūrya-Siddhānta*, an ancient astronomical work, it is — text-book of the Saurapaksha school of astronomers, 145 n.; — according to it, the length of the solar year is 365 *days*, 15 *ghatis*, 31'523 *palas*, 146; — and the length of the year of Jupiter, by the mean-sign system, is 361 *days*, 1 *ghati*, 36 *palas*, 170; — its rule for determining the years of the Sixty-Year Cycle of Jupiter by the mean-sign system, 170; — its rule for determining the years of the Twelve-Year Cycle of Jupiter by his heliacal rising in connection with the occurrence of *nakṣatras* on new-moon days, 171; — comments on this rule by Ranganātha and Dādābhāi 171 n.
- Sūryavānśa, the Solar Lineage; there are no grounds for allotting the Early Guptas to this lineage, 19, 1; — but, according to tradition, the family of the Lichchhavis of Nēpāl did belong to it 185, 188
- Sūsarma, the founder of the family of the Parivrājaka *Mahārājas* 115
- Susthitavarman, probably a Maukharī king, conquered by Mahāsānugupta 15, 206
- Suttee* (*Saīl*), see cremation of widows 92 and n., 93
- svarna*, a particular gold coin or weight of gold 265
- Suvarāpakshaka, apparently an ancient village in Baghēlkhāḡ 125
- sva-hasta*, 'a sign-manual,' 171, 191; — actual representations of a *sva-hasta* 171 n., 191 and n.
- Svāmīdatta of Koṭṭāra on the hill, a king in Southern India, conquered by Samudragupta 7 n., 13
- Svāmīdēvārya a grantee 243
- Svāmī-Mahābhairava, one of the terrific forms of the god Siva 241, 248
- Svāmī-Mahāsēna, the god Kārttikēya, as 'the commander of a large army' 43, 44
- Svāmin*, a title of office or rank 177
- Svāmīnāga, a proper name 128
- svāmīnī*, 'a noble lady,' or perhaps an abbreviation of *Vihārasvāmīnī* 262 and n.
- sva-mukh-dīkṣā*, 'the order or command of one's own mouth;' an expression, connected with charters, used when a *Dātaka* is not employed 100 n., 116 and n., 195, 200
- Svarbhānu, a name of Rāhu, the personified ascending node, as the causer of an eclipse of the sun 97
- svasti*, 'hail,' an exclamation used at the commencement of inscriptions, 96 and n., 104, 108, 111, 119, 123, 128, 131, 138, 167, 180, 194, 199, 217, 240, 257; — used with a dative case at the end of an inscription, 88; — used as a neuter noun, meaning 'prosperity,' with *astu*, and governing the dative 90, 161
- Svātīśarmārya, a grantee 243
- Svātīśvāmīn, a grantee 105
- svayam-a-pratiratha* (compare *prithivya-m-a-pratiratha*, applied to Samudragupta), an epithet of Chandragupta II. 44, 51, 54
- Svayambhū, the god Brahman, as 'the self-existent one' 155 and n.
- 'Syalapati,' a Hindu king of Kābul; remarks on some of his coins, which have been supposed to bear dates in the Gupta era 57 to 60
- Talāpura, or Tālāpura, an ancient town in the vicinity of Nirmaḡḡ 290 and n.
- Talādvāḡaka*, an official title 217 and n.
- Tamaśā, a river, the modern Tamas or 'Tons' 126, 128
- tāmra-śāsana*, 'a copper-charter' (see also *śāsana*), a technical term for a deed of conveyance written on copper-plates, 99 n., 109, 116, 128, 132, 138, 195, 199; — an illustration of functions connected with such a charter 99 n.
- tanaya-prāpta*, 'an adopted son' 293 n., 298
- Tāntrika, or Śākta worship, apparent early instances of (see also *Vajrēśvara*) 48 and n., 74, 226
- Thākūrī rulers of Nēpāl; Thākūrī is the name given in the Nēpāl *Vamśāvalī* to the family to which Amśuvarman and his successors belonged, 189; — their palace was Kailāśakūṭabhavana, 178, 179, 180, 181, 182, 189; — they used the Harsha era, 96, 184, 189; — instances of this, 178 to 184; — they seem to have had the government of

- the western portion of Népál, 190;— the dates of the known members of this family, 189;— their intermarriage with the Maukharis, and with the Bhagadatta family 187
- Thomas, Mr. E.; the views expressed by him on the Gupta era and connected matters, with the result that he held it to be identical with the Śaka era, 32, 36, 38, 51, 57
- Tilabhattaka, *Mahādandāyaka*, the superintendent of the work connected with the Allahābād posthumous pillar inscription of Samudragupta 17
- tilamaka*, 'a water-course' 180, 181
- Tīrthamkaras*, early Jain saints, mentioned under the epithet of *dāikartri* 68 and n.
- Tishyāmratīrtha, an ancient place 28
- tīthi*, 'a lunar day,' 32 n., 163;— an epigraphical quotation of the new-moon *tīthi* or fifteenth *tīthi* of the dark fortnight, as the thirtieth *tīthi* of the month, 110 n.,— the astronomical meanings of the term *tīthi*, 147;— one mean *tīthi*, of time, is equal to 0.9843529572 of a mean solar day and night, 149 n.;— the mean *tīthi* in a solar year are 371, and 3 *ghaṭis*, 534 *palas*, 148;— in general, the term *tīthi* means the end of a *tīthi*, not its beginning or duration; and the *tīthi*s are thus shewn in *Pañchāṅgas*, 148;— and so, for all ordinary purposes, the week-day of a *tīthi* is the week-day on which that *tīthi* ends; and consequently there may, in certain instances, or a nominal discrepancy between the resulting English and Hindu week-days, 156 n.,—the *tīthi*s given in *Pañchāṅgas* are apparent, not mean, 148;—and they are intended to be given from apparent sunrise, 155;— the method of determining the apparent *tīthi* from the mean *tīthi*, 154;— a method of calculating the week-days, ending-times, and English dates, of *tīthi*s, with Prof. K. L. Chhatre's Tables, Appendix II., 145 to 159;— the ending-time of a *tīthi*, thus obtained, may sometimes differ from the results obtained from the *Sūrya-Siddhānta* and other Hindu works, but the difference will not amount to more than 5 or 6 *ghaṭis* 155
- tīthi-bhōga*, 'the enjoyment or duration of a *tīthi*' 153
- tīthi-dhruva*, 'the constant of a *tīthi*,' a term denoting the number of complete *tīthi*s that elapse from the commencement of Chaitra up to the *tīthi* during which the *Mésha-Samkrānti* occurs 152
- tīthi-kēndra* (see also *kēndra*), 'the anomaly of a *tīthi*, expressed in *tīthi*s,' 140;— the annual variation in the *tīthi-kēndra* is 7 *tīthi*s, 9 *ghaṭis*, 43 *palas* 149
- tīthi-madhya-kēndra* (see also *kēndra*), 'the mean anomaly of a *tīthi* expressed in *tīthi*s,' a term denoting the number of *tīthi*s that elapse, up to the *Mésha-Samkrānti*, from the moon's preceding arrival at her apogee 149, 150
- tīthi-suddhi*, 'the subtraction of *tīthi*s,' a term denoting the number of *tīthi*s that elapse from the commencement of Chaitra up to the time of the *Mésha-Samkrānti*, 148, 150;—when the *tīthi-suddhi*, obtained from Prof. K. L. Chhatre's Tables, is less than 19, there cannot be an intercalary month in the year 153
- Tivaradēva, or Tivararāja, also called Mahāsiva-Tivararāja, of the Pāṇḍu-vamśa, 296, 298;— he had the title of 'supreme lord of Kōśala,' 296;— he was the adopted son of Nannadēva, 293, 298;— his Rājim grant 291
- 'Tons,' properly Tamas, a river in Būndēlkhāṇḍ and the North-West Provinces; mentioned under the ancient name of Tamasā 126, 128
- Tōramāna, a king of the Mihira tribe or clan among the Hōnas, and the father of Mihirakula, 10, 11, 12, 160, 163;— he came, in Eastern Mālwa, very shortly after Budhagupta, 10, 11;— remarks on the reading and interpretation of the date on his coins, 11, 12;— his Eraṇ boar inscription 158
- Traikūtaka, a tribe (see also *Triakūta*); the grant of the Traikūtaka *Mahārāja* Dharasēna, and another Traikūtaka grant, perhaps furnish early instances of the use of the Kalachuri or Chēdi era; but they may be dated in the Gupta era 92
- tree-sculpture, with cow-and-calf, on an inscription stone 274
- Triakūta, the origin of the name Traikūtaka, 234;— it has been identified with Tripura or Tripurī, the capital of the Kalachuris, but this point remains to be proved 92
- Tripurātaka, the god Śiva, as 'the destroyer of the demon Tripura, or of his three cities' 290
- Tu-lu-h'o-po-lu*, the Chinese transliteration of the Sanskrit name of the reigning king of Valabhi in the time of Hiuen Tsiang; it has been restored as Dhruvapāṇu, 39, 40;— and as Dhruvabhāṭa, 51;— the king in question has been identified with one of the Dhruvasēnas of Valabhi, 39, 47;— with Dharapāṇu, 41;— with Śīlāditya VII., 51;— with Dērabhāṭa, or one of the Dharasēnas, or one of the earlier Śīlādityas, 57;— and with Dhruvasēna II., 64;— there are difficulties in the way of finally determining his iden-

- tity; but the dates render it impossible that he should be Śīlāditya VII. of Valabhi 40
- Tu-lu-pa-pa-l'cha*, and simply *Pa-l'cha*, the Chinese form of the name of a king of Southern India, mentioned by Hiuea Tsiang, which has been restored as Dhruvapaṇa; there are difficulties in the way of establishing the identity of this king; but he cannot be Śīlāditya VII., or apparently any king of Valabhi 40
- Tumburu, one of the Gandharvas 14
- Tuśm, or Tusām, a village in the Hīśār or Hīśār District; the rock inscription Tushāra king, a, of the name of Vishnu, is not mentioned in the Tuśm rock inscription 269
- Uchaharā, the capital of the Nāgaudh State; it is not to be identified with a supposed 'Udyāra' 93 n
- Uchchakalpa, an ancient city or hill, from which Jayanātha and Sarvanātha issued their grants, 117 n., 119, 123, 128, 131, 138; — the *Mahārājyas* of Uchchakalpa, 8, 9, 10, 112, 119, 123, 128, 131, 132, 133, 138; — the dates of their records have been interpreted as being in the Gupta era, 8, 118, 121, 126, 133, 135; — but it is possible that they really are the earliest instances of the use of the Kalachuri era, and that these *Mahārājyas* were feudatories of early Kalachuri kings 8, 9, 10
- uchchhanna*, a Prakṛit corruption of *utsanna* 250
- Udayadēva, *Yuvardja*, the *Dātaka* of the inscription of Amśvarman of the (Harsha) year 39 180 and n.
- Udayadēva (Thākurl of Nēpāl) 186, 188, 189, 191
- Udayagiri, a village and hill in the Isāgaḍh District; the cave inscription of Chandragupta II. of the (Gupta) year 82, . . . 21; the cave inscription of Chandragupta II., not dated, 34; — the cave inscription of the time of Kumāragupta, of the year 106 258
- Udhava, an epic hero 156
- udraṅga*, a fiscal term, 97 and n., 104, 109, 120, 128, 132, 138, 170, 185, 189, 218, 290
- Udyōtarka, the writer of the Nirmanḍ grant of Samudrasēna 291
- Ugrasēna of Palakka or Pālakka, a king in Southern India, conquered by Samudragupta 13
- ukthya*, a particular sacrifice . . . 241 and n., 248
- Undāna, a proper name 32
- Unnata, an ancient town or village . . . 170
- Upādhyāya*, 'a sub-teacher,' the instructor in only a part of the Vēda, or in grammar and the other Vēdāṅgas . . . 271, 282
- Upaguptā, wife of Iśvaravarman . . . 220 n 221
- upakṛipta*, a fiscal term, requiring explanation 242, 249
- upapātaka*, a metrical form for *upapātika* 72 and n.
- upapātaka*, 'sins of the second degree' 72 n., 120, 124, 129, 134, 138, 171, 291
- Uparika*, an official title, requiring explanation 52, 120, 124, 174, 218
- uparikara*, a fiscal term (add a reference to *Ind. Ant.* VII. 66, note), 97, 98 and n., 105, 109, 120, 128, 132, 138, 170, 189, 218, 257
- Upāsaka*, a worshipper of Buddha who is not a member of the priesthood, i.e. 'a lay-worshipper' 262
- Upāsikā*, the feminine of *Upāsaka* . . . 202
- Upasēna I. and II., Buddhist teachers . . 277
- Upēndra, the god Vishnu, as the younger brother of Indra 180 and n.
- Uplēt, or Uplētā, a village in the Kaira District; mentioned under the ancient name of Uppalabhēta 173, 189
- Uppalabhēta, the ancient name of the modern Uplēt or Uplētā; mentioned as the chief town of a *pathaka* in the *Khētaka dhāra* 173, 189
- Ūrjayat, a mountain near Girinagara, now known by the name of Girnār 57, 64, 65
- utkrna*, 'engraved,' a technical expression for the actual engraving of an inscription on copper or on stone 99 n., 148, 150, 158, 195, 200
- Utpala, a commentator on the *Brihat-Samhitā*; his quotations of early astronomers for the heliacal-rising system of the Twelve-Year Cycle of Jupiter, 161 n., 170; — his quotation of Garga and Parāśara, as giving a variation from the usually accepted grouping of the *nakshatras*, 163 n.; — his quotation of the *Garga-Samhitā* for one of the unequal-space systems of the *nakshatras*, 164; — and of a verse by Garga, which seems to refer to the mean-sign system of the Twelve-Year Cycle 172
- Uttarakuru, the land of the Northern Kurus 260 and n.
- va*, an abbreviation of *vadya*, 'the dark fortnight,' or else a substitute for *ba*; used in connection with *di* (see also under *ba di*) 85
- Vāhlika, a tribe, conquered by Chandradra 141 and n.
- vaidila*, a word requiring explanation . . 290
- Vaiṣya, an epic king 77
- Vaishyava inscriptions (for other instances of Vaishyava worship, see *ajyanta-bhagavad-bhakti*, *bhagavad-bhakti*, *bhāgavata*, *paramabhagavata*, and

- paramavaishnava*) . . . 23, 53, 58,
74, 89, 113, 121, 126, 268
- Vaishnavi, perhaps a name of the earth
as the personification of the *śakti* or
female energy of Vishṇu . . . 195 n.
- vaivādēva*, one of the five great sacrifi-
cial rites . . . 170, 190
- vastastika*, a particular weapon; an ex-
act explanation of the term is re-
quired . . . 12
- vajrapēya*, a particular sacrifice . 241 and n., 248
- Vajragrāma, an ancient village in
Kāthiāwād . . . 170
- Vajrēsvara, a god; Mr. Bendall (*Journey
in Nēpāl*, p. 78, note) takes the name as
of the "early traces of the curious
position of Hindu and Buddhist
has the Tantric system brought
into Nēpāl" . . . 181
- Vākātaka, a tribe or dynasty, 15, 16, 235,
240, 241, 247, 248; — it may be the
name of a country also, but not in cer-
tain supposed cases, 234 n.; — it is de-
rived from an original form *vakāta*,
and is not to be identified with the
modern Bhāndak, 234; — the Vākātaka
Mahārājās, 15, 235, 240, 241, 247, 248,
— they belonged to the Vishnuvridhā
gāt, 241, 248; — they intermarried
with the Bhārasīvas, 241, 248; — their
date is determined by the marriage of
Rudrasēna II. with Prabhāvatiguptā,
daughter of Dēvagupta of Magadha . . . 15
- Vakkhalika, a proper name . . . 290
- Vakra, *Amātya* . . . 100, 105, 109
- Vakravaṇa, an ancient forest, or perhaps
town or village, in Baghēlkhand . . . 125
- Valabhī, the ancient name of the modern
Walā in Kāthiāwād, the chief city of
the Kings of Valabhī and their ances-
tors, 167; — the meaning of the name,
23 n.; — there is no authority for the
use by Reinaud and Sachau of the
forms Balabha, Ballaba, and Ballabha,
23 n.; — the Kings of Valabhī, and
their ancestors, 13, 167, 168, 169, 180
to 189; — their genealogy, 41; — it
was through their preservation of the
Gupta era that it came to acquire the
name of the Valabhī era, 23, 126; —
but they did not establish the era, 130;
— nor can they have introduced it into
Nēpāl, 134 n.; — list of the charters
issued by them from Valabhī itself,
126 n.; — Hiuen Tsang's remarks about
the reigning King of Valabhī in his
time . . . 40
- Valabhī era; the later name of the Gupta
era, due to its preservation by the Kings
of Valabhī, and used by Albérūnī in the
eleventh century A.D., and in epigra-
phical records of the thirteenth century,
22, 23; — Albérūnī distinctly states the
absolute identity of the Valabhī era
with the Gupta era . . . 31
- Valabhī-sam* and *Valabhī-samvat*, techni-
cal expressions, in the thirteenth century
A.D., for the Gupta era under its later
name of the Valabhī era . . . 22, 84, 91
- Valaka, apparently an ancient village in
Baghēlkhand . . . 105
- Valakaushan*, an official title, requiring
explanation . . . 257
- Vālavi *vishaya*, an ancient territorial
division in Bihār . . . 218
- valaya-yashkti*, 'a boundary-pillar' . . . 112
- Vālugarta, an ancient village in Baghēl-
khand . . . 109
- Vanga, a country, the modern Bengal or
the eastern parts of it, invaded by
Chandra . . . 141
- Vangara, an ancient village in Baghēl-
khand . . . 105
- vāpti*, *vāptkā*, 'an irrigation-well' . . . 170, 200
- vāra*, a 'week-day' (see also week-days),
which is reckoned by the Hindus from
sunrise to sunrise . . . 146, 147
- Varāhadāsa, a proper name . . . 156
- Varāhadinna, *Bhōgika* . . . 124, 129, 134, 139
- Varāhamihira, an astronomer, he died A.D.
587. . . 143 and n.; — his rules, in the
Bṛihat-Samhitā and the *Samāsa-Sam-
hitā*, for the naming of the years of the
Twelve-Year Cycle of Jupiter according
to the heliacal-rising system, 161, 170;
— his rule, in the *Bṛihat Samhitā*, for
the grouping of the *nakshatras* for that
purpose . . . 162
- Varāśarma, a grantee, 243, — another
of the same name . . . 243
- Varāśarmāya, a grantee . . . 243
- Vardhaki, a proper name . . . 170
- Varika, a tribe; mention of certain
chiefs of this tribe . . . 253, 254
- varsha*, 'a year', the reason why the ear-
lier years of Hindu eras are quoted by
this term, without any dynastic appella-
tion . . . 143
- Vārta*, an official title . . . 180 and n.
- Varuna, the god of the ocean, 14, 28, 44,
51, 54, 63, 257. — mentioned as the
regent of the west, 63, — connected
with the Sun in the name of Varuṇārka . . . 215
- Varuṇārman a grantee . . . 105
- Varuṇasēna, *Maṇḍāsanta* and *Mahā-
rāja*, 289; — his wife was Prabhālikā . . . 290
- Varuṇavāsini, a name of the Sun . . . 218
- Varuṇavishṇu, a proper name . . . 90, 160
- Vārūnikā, the ancient name of the modern
Dēō-Bārānark . . . 214, 215, 218
- Vasantadēva, a variant of the name of
Vasantasēna . . . 183 and n., 186, 189
- Vasantasēna (Lichchhavi of Nēpāl), 183,
188, 189, 191; — mentioned under the
name of Vasantadēva, 186; — notice of
his inscription of the (Gupta) year 435 . . . 183
- Vasishṭha, an ancient astronomer, quoted
by Rishipatra, and through him by Ut.

- pala, for the heliacal-rising system of the Twelve-Year Cycle of Jupiter . . . 170
- Vāsu, *Grāmika* 113
- Vasudatta, a proper name 271
- Vasudēva, the father of Vishṇu in his incarnation as Kṛishṇa 206
- Vāsudēva, the god Vishṇu, as Kṛishṇa, 'the son of Vasudēva' 115, 286
- Vāśula, the composer of the Mandaśr pillar inscriptions of Yaśōdharman 148
- Vasantarashāḍika, an ancient village in Baghōlkhand 97
- vidā*, a fiscal term, requiring explanation 170 and n., 189
- Vatāpūraka, an ancient village in the Beṣpākārpara *bhūga* 248
- Vatsabhajji, composer of the Mandaśr inscription of the Mālava year 529 88
- Vatsadēvi, daughter of the Maukhari Bhūgavarman, daughter's daughter of Adityasēna of Magadha, and wife of Sivādēva II. of Nēpāl 284, 287
- Vēdas (see also *śākhā*), the earliest sacred books of the Hindus; mentioned as arranged by Vyāsa, 98 and n., 103, 109, 116, 124, 129, 134, 139, 171, 190;—mentioned as three in number, under the term *trayī*, 189;—indicated as four in number by the word *Chaturvēda*, 71, 190., 242;—the only Vēda mentioned by name in this series of records, is the *Atharva-Vēda* 290
- Vēdhas, the god Brahman, as 'the creator' 156
- Vengl, a town or country in Southern India; in the time of Samudragupta, its king was Hastivarman 13
- Verāwal, a town in Kāthiāwād, the modern representative of the ancient Sōmanāthpāṭan; mentioned under the ancient names of Dēvapattana, 91;—and of Sōmanāthadēvapattana, or the city of the god Sōmanātha, 85;—examination of the date of the inscription of the Valabhī year 927 90;—and of the inscription of Arjunādēva of the Valabhī year 945 84
- vernacular terminations, in *ashtama*, *divasa*, and *samvatsara* 292, 296
- Vibhudatta, *Mahādēvādhipivrahika*, writer of the grant of Hastin of the (Gupta) year 191 109
- Vibhūvarman, *Vārtta* 180
- Vidhātṛi, the god Brahman, as 'the arranger or creator' 90, 160, 251
- Vidura, an epic hero 156 and n.
- Vidyādharma, a class of supernatural beings 77, 78, 86, 205
- vihāra*, 'a Buddhist (and Jain) temple or convent' 31, 32, 262, 274
- Vihāra, the ancient name of the modern Bihār in the Patna District; mentioned as 'the city of the glorious Yaśōvarman' 47 n.
- Vihārasvāmin*, a religious title 272 n., 279 n., 280
- Vihārasvāmini*, the feminine form of *Vihārasvāmin* 263 and n.
- Vijayadēva, *Yuvardja*, the *Dātaka* of a Nēpāl inscription of the (Harsha) year 145 283
- Vijayarāja (Chalukya of Gujarāt); three of the customary epithets of Samudragupta are applied to him in his Kaira grant of the year 394 14 n.
- vijhāpi*, derivatives from, used in connection with the making of a grant by one person at the request, or on the advice, of another 177 and n., 178 and n., 190, 109, 116
- Vikidinna, a proper name 170
- Vikrama, a *biruda*, or second name of Chandragupta II.; and perhaps also of Chandragupta I. 18
- Vikrama era; an era of western origin, commencing in B.C. 58, though usually represented as commencing in B.C. 57, and supposed to date from the beginning of the reign of king Vikrama or Vikramāditya of Ujjain; Mr. Ferguson's theory was that it was invented in the sixth century A.D., that its historical starting-point was in A.D. 544, and that it was referred to the earlier starting-point by ante-dating, 47, 55;—but the Mandaśr inscription of the year 529 proves that it existed before that time, under the name of the Mālava era, 68;—and, in Central India, it was known by this name at least up to the ninth century A.D., 66 n.;—an instance of the use of this era, with the name of Vikrama, in Central India, in the eleventh century A.D., 22 n.;—the name of Vikrama may have come to be connected with it through Chandragupta I. or II., 37 n.;—the difference in the scheme of the southern and northern Vikrama years, 70 and n., 71;—use of the word *śarad*, 'the autumn,' in the reckoning of this era, 66 n., 158;—this word may be used in the sense of 'a year' generally; but its original meaning is that of 'the autumn'; and the use of it with the Vikrama era is significant, in helping to show that the original scheme of its years is that still used in Gujarāt and Southern India, with Kārttika śukla 1 as the initial day of each year, and with the *Amānta* arrangement of the lunar fortnights; and this reckoning of the era was followed, in Central India, at least up to the ninth century A. D., 66 n.;—the statement of the Nēpāl *Vāśīśvati*, that Vikramāditya introduced his era into Nēpāl, refers really to the introduction of the Harsha era, 284;—but, under the name of the Nēwār era, an offshoot of the Vikrama

- era, with its original characteristics, was introduced there in A.D. 880, . . . 74, 124;—and, in more modern times, the Vikrama era itself was introduced there, from Northern India, with Chaitra śukla 1 as the initial day of each year, and with the *Paryśimānta* arrangement of the fortnights, 76;—instances of the use of expired years of this era, distinctly specified as such, 129;—of the use of both an expired and a current year, 22 n.;—and of the use apparently of a current year, which has to be applied as an expired year, 85;—quotations of the reckoning of this era, both by current and by expired years, from Hindu almanacs 137 to 141, 138 n.
- Vikramāditya, a *viruda* or second name of Chandragupta II., and perhaps also of Chandragupta I. 18
- Vikramāditya, also called Harsha, a king of Mālwa or of Ujjain, mentioned in the *Rājatarāngīnī*, allotted by Mr. Fergusson to the sixth century A.D., and held by him to be a real person in commemoration of whom the Vikrama era was invented and named 47, 55, 56
- Vikramānka, a *viruda* or second name of Chandragupta II. 18
- Vikramasēna, *Mahāsarvadāndyaśaka*, the *Dātaka* of one of the inscriptions of Aśśuvārman of the (Harsha) year 34 178 and n
- Vikramasēna, *Rājaputra*, the *Dātaka* of a Nēpāl inscription of the (Gupta) year 535 178 n., 184
- vimśatīma*, 'twentieth'; two instances of the use of this form, not in composition 134 and n
- Vindhya, a mountain range in Central India, 156, 157, 190, 230,—mentioned as one of the breasts of the earth, 86 n., 184;—and as constituting both the breasts, 185;—mentioned as extending up to, and including, the Nāgārjūnī Hill 227, 228
- Vindusvāmin *Mahābalādhyakṣa*, the *Dātaka* of one of the inscriptions of Aśśuvārman of the (Harsha) year 34 179
- Vinnyuktaka*, an official title 169 and n.
- Vīrasēna, also called Śāba, a minister of Chandragupta II 36
- Vīrasēnadantika, a proper name 170
- viśaya*, a territorial term . . 32 n., 52, 80, 84, 161, 173 n., 218, 257
- Vishayapati*, an official title 33, 69 n., 71
- Vishṇu, a proper name 190
- Vishṇu, the god, 'the preserver' of the Hindu triad (see also Anantasvāmin, Atmabhū, Chakrabhrī, Chakradhara, Chakrapāni, Chitrakūṭasvāmin, Dāmōdara, Gadādhara, Gōvinda, Hari, Janādana, Kṛishna, Mādhava, Madhusōdana, Murādāśa, Nārāyaṇa, Śārngapāni, Śārngin, Upēśadī, and Vāsudeva; and, for his wife, see Lakshmi), 61, 65, 76, 77, 78, 142, 164, 195, 200, 208, 270, 298, 299;—mentioned by the epithet *bhāgavatī*, without the use of his name, 40, 41, 123, 124, 129, 269, 270;—mentioned as the creator, preserver, and destroyer of the universe, 90;—as the younger brother of Indra, 50, 182;—as the four-armed god, 90;—as having the form of a boar, 160, 161;—as the man-lion, 188;—as the supporting pillar of the three worlds, 160;—and as the troubler of the demons, 90;—reference to his overthrowing the power of the demon Bali, 62;—mention of him as carrying the discus, 65, 78, 207,—and the club, 78;—mention of his bow of horn, Śārngā, and his sword, Nandaka, 207 and n.;—mention of his jewel, *kaustubha*, and his garland of water-lilies, 87,—references to his vehicle and ensign, the bird Garuḍa or Garuṭmat, 14, 62, 90, 298;—mention of the waters of the four oceans as his couch, 90;—an allusion to his slumber during the four months of the rainy season, 77,—the earth spoken of as 'belonging to Vishṇu, or as being Vaishṇavi, the female energy of Vishṇu,' 195 and n., 200, 299;—an instance of the worship of Vishṇu connected with that of the Sun 126
- Vishṇubhata, a proper name 78
- Vishṇudāsa, *Mahādrāja* (Sanaikānīka) 25
- Vishṇudēva, a grantee 105
- Vishṇugōpa of Kāñchi, a king in Southern India, conquered by Samudragupta 13
- Vishṇugupta, Vishṇuguptadēva (Gupta of Magadha), 217;—his wife was Ijjādēvi 217
- Vishṇugupta, *Yuvārāja*, the *Dātaka* of the inscription of Vishṇugupta of the (Harsha) year 48 180
- Vishṇunandin, a grantee 128
- Vishṇupada, the ancient name of the hill on which the Mēharaulī inscribed pillar stands, or stood 140, 142
- Vishṇutrāta, a proper name 271
- Vishṇuvardhana, a king of the Mālava country, 155;—he had the paramount titles, but seems to have been to a certain extent subordinate to Yaśōdharman, 151;—his *Mandasōrī* inscription of the Mālava year 589 150
- Vishṇuvardhana, *Rāja*, of the Varika tribe, 253, 254;—his Bijayagadhī inscription of the (Mālava) year 428 252
- Vishṇuvijuddha *gōtra* included the Vākātaka *Mahādrājas* 241, 246
- Viśvānātha, the god Śiva, as 'the lord of the universe' 85
- Viśvavārman, a Mālavi feudatory of Kumārāgupta, 7, 74, 77, 86;—his Gaṅgdhār inscription of the (Mālava) year 480 77

Vôta sanika, an ancient division in the territory of the *Mahârâjas* of Uchchakalpa 132

Vrîshadêva (Lichchhavi of Nêpâl) 182, 186; 189, 191

Vyâghra, *Mahârâja* (of Uchchakalpa), 119, 123, 128, 131, 138; his wife was Ajjhitadêvi 119, 123, 128, 131, 138

Vyâghra, another name of Rudrasôma 27 n., 67

Vyâghradêva, a feudatory of Prithivishêpa 235

Vyâghrapâlika, an ancient village in the *Maçinâga pârva* 138

yâghrarâja, of *Mahâkântara*, a king in Southern India, conquered by Samudragupta 13

Vyâghrarâta, a Varika chief 254

Vyâsa, an ancient sage, 195, 200, 242, 249, 299; — mentioned as the son of Parâsara, 139; — as the arranger of the *Vêdas*, 98 and n., 99, 105, 109, 116, 124, 129, 134, 139, 171, 190; — and as the author of certain verses allotted to the *Mahâbhârata* 120, 124, 129, 134, 139

Walâ, a village in *Kâthiâwâd*, mentioned under the ancient name of Valabhi . 165, 167

waterily-embell on the seals of grants 191, 196

Watson, Colonel J. W.; a tradition of the bards of *Kâthiâwâd*, supposed to have an important bearing on the question of the Gupta era, brought to notice by him, 49; — but it is of quite recent origin, and of no value whatever 50

week-days (see also days of the week); the Hindu term for a week-day is *vâra*, 146; — it is reckoned by the Hindus from sunrise to sunrise, 146, 147; — consequently, the English and Hindu week-days are not identical for a period of 57 minutes, 8 seconds, at the end of the Hindu week-day, when, by the English reckoning, the following week-day has already commenced; and thus, as for all ordinary purposes the week-day of a *tithi* is the week-day on which that *tithi* ends, there may, in certain instances, be a nominal discrepancy between the resulting English and Hindu week-days, 136 n.; — a method of calculating the week-days of *tithis*, with Prof. K. L. Chhatrets Tables 145 to 158

wheel-embell 219, 263, 260

Wright, Prof. W.: his rendering of Alberûnî's statements regarding the Gupta and other eras 27

yad atra panyam &c., a formula in certain donative inscriptions 263, 272, 274, 279, 0, 282

Yajñavarman, a Maukhari chief 225, 227

Yama, the god of the dead, and the dealer of death, mentioned under the names of Antaka, 14, 21, 28, 44, 51, 54, 257; — *Kritânta*, 28, 44, 51, 54, 157, 257; — and *Kâla* or *Death* 223

Yamunâ, the river, the modern *Jamnâ*; mentioned under the name of *Kâlindî* 89, 90

Yâsastrâta, a proper name, 270; — another person of the same name 271

Yasôdharman, a king of Northern India, 13, 145, 148, 150, 151, 155; — the extent of his kingdom, 148; — mentioned as conquering lands which not even the Guptas and the Hûpas could subdue, 148; — he had worship done to him by *Mihirakula*, 148, 150; — his duplicate pillar inscriptions at *Mandasôr*, 142, 149; — his *Mandasôr* inscription of the *Mâlava* year 589 150

Yasômati, wife of *Prabhâkaravardhana* 232

Yasôrâta, a Varika chief 254

Yasôvardhana, a Varika chief 254

Yasôvîhâra, an ancient monastery at *Mathurâ* 274

Yaudhêya, a tribe, conquered by *Samudragupta*, 14; — the fragmentary inscription of a leader of this tribe at *Bijayagadh* 251

Yazdajird, a Sasanian king of Persia; there is an era, dating from his accession in A.D. 632, of which the four-hundredth year is used by *Alberûnî* as a gauge-year for the comparison of dates 24 and n., 30

year (see also *samvatsara* and *varsha*); years of *Jupiter's Twelve-Year Cycle* denoted by the word *samvatsara*, 104, 120, 124, 127, 129, 95, 102, 107, 111, 114; — years of eras denoted by the words *abda*, 104, 120, 124, 127, 83, 95, 102, 107, 114; — *samâ*, 97; — *samvatsara*, 25, 37, 38, 40, 41, 43, 60, 70, 92, 119, 123, 128, 134, 137, 180, 210, 263, 298, 273; — *varsha*, 81, 61, 67, 89, 259; — and *vatsara*, 75, 83; — regnal years denoted by the words *abda*, 162; — *samvatsara*, 194, 199, 240, 246, 296; — and *varsha*, 159; — the length of the tropical year is 365 days, 14 *ghatis*, 31' 972 *palas*, 146; — of the same, according to the *Sârva-Siddhânta*, is 365 days, 15 *ghatis*, 31' 523 *palas*, 146; — of the Twelve-Year Cycle of *Jupiter* by the heliacal-rising system, is roughly 400 days, 162; — and of the Twelve-Year and the Sixty-Year Cycles by the mean-sign system, is 361 days, 1 *ghati*, 36 *palas* 170

<i>yōga</i> , 'the addition of the longitudes of the sun and the moon,' an astrological element	146	of the <i>Mahābhārata</i> , 99, 105, 109, 116, 120, 124, 129, 134, 139, 171, 195, 200, 241, 248, 299; — referred to as 'the king of justice'	108
Yōga, one of the systems of philosophy	27		
Yudhishtira, an ancient hero, of the time		<i>Yusvardja</i> , an official title	126, 121, 123

ERRATA.

INTRODUCTION.

- Page 36, line 15, for Mr. Blochmann's, read Mr. Kay's.
106, note 1, line 3, for Kādamba, read Kadamba.
117, line 3, for navōttarē, read nav-ōttarē.

TEXTS AND TRANSLATIONS.

- 6, Text line 5, for ōchchhri, read ōchchhri (chchhi).
" " " 9, for sadrisāny, read sadriśāny.
" " " 17, for parākkram-ānkasya, read parākkram-ānkasya.
7, " " 20, for mähābhagyasya, read mähābhāgyasya.
20, " " 20, for kula-vadhuh, read kula-vadhu(dhū)h.
" " " 21, for ḍrijitam, read ḍrijitam.
" " " 26, for paribrinhan(n), read paribrinhan(n).
26, " " 1, for ōchhētuh, read ōchchētuh
27, note 4, in lines 1 and 13, for ōchchētttri, read ōchchētttri; and in line 1, for ōchchēttā, read ōchchēttā.
28, note 6, line 4 from the bottom, for Purana, read Purāna.
31, Text line 3, for jlvita-sādhanah, read jlvita-sādhanah.
35, " " 3, for rmanah, read rmapah.
43, " " 6, for shan-navatē, read shan-navatē.
48, note 1, line 2, for Visvavarman, read Viśvavarman.
59, Text line 4, for Āpi, read Api.
" " " 11, for an-upaskritair, read an-upaskritair.
60, " " 15, for Athā, read Atha.
61, " " 27, the word Guptānām should be in the thick type.
73, line 4 for appratimēna, read appratimēna.
74, Text line 8, for a-sahyatamāñ, read a-sahyatamañ.
75, " " 19, for (? shthā), read (? shthā).
" " " 23, for trityam, read tri(tri)tyam.
76, " " 39, for śrīmān, read śrīmān.
83, " " 17, for ābhirāmān, read ābhirāmān.
96, " " 12, for pramukhānām, read pramukhānām.
115, " " 14, for khanda, read khaṇḍa.
118, " " 6, for ādin, read ādin.
" " " 7, for Kāṇva, read Kāṇva.
146, " " 4, for drishta, read dṛishta.
153, " " 4, for ḍdapan, read ḍdapān.
" " " 7, for udūḍham, read udūḍham.
" " " 10-11, for garimnas, read garimnas.
" " " 12-13, for visambvā(va)ditā, read visambvā(va)ditā.
154, " " 17, for dēsām, read dēśām; and for ḍimbām, read ḍimbām.
" " " 18, for Dharmmadō, read Dharmmadō.

- Page 154, Text line 19, for *khátayām*, read *khānayām*.
 156, line 27, for *mightly*, read *mighty*.
 162, Text line 4, for *vṛishashya*, read *vṛishasya*.
 165, " " 3, for *dīdhitir*, read *dīdhitir*.
 166, " " 14, for *vad-apāst*, read *d-apāst*.
 173, " " 5, for *trīṇa*, read *trīṇa*.
 193, line 6, to the word **TEXT** attach the note-reference 3.
 194, Text line 11, for *ātisra(sṛi)shtaḥ*, read *ātisra(sṛi)shtaḥ*.
 " " " 19, for *Shashthir*, read *Shashṭim*.
 203, " " 10, for *pariṇāyitavan*, read *pariṇāyitavān*.
 204, " " 23, for *lakshmlvan*, read *lakshmlvān*.
 " " " 24, for *āhō*, read *ahō*.
 237, " " 13, for *Chakra*, read *Chakra-*.
 238, " " 25, for *atisrishtaḥ*, read *atisrishtaḥ*.
 245, " " 1, for *Dṛishtam*, read *Dṛishṭam*.
 250, line 35, for *Oldhausen*, read *Olshausen*.
 254, Translation, line 2, twice, for *ana*, read *and*.
 280, No. 74, Text lines 2 and 3, the note-references should be 3 and 4.
 290, line 12, the word *Mihiralakshmi* should be in the thick type.
 294, Text line 1, as pointed out to me by Prof. Kielhorn, for *sūtra[h^o]*, read *stambha[h^o]*; and cancel the latter part of note 4.
 296, Translation, line 9, for *thread*, read *pillar*, in accordance with the correction in the Text.

I have not had the opportunity of examining the final printed sheets as thoroughly as I could have wished; and doubtless some other instances of oversight on my part will be discovered, in addition to the present corrections, most of which I owe to the kindness of Prof. F. Kielhorn. Some suggestions by him for altering my readings and translations, will be considered in the *Indian Antiquary*; since, to include them here, would further delay the issue of the book.

ABBREVIATIONS AND BIBLIOGRAPHY OF JOURNALS

A

- ABI : Annals of Bhandarkar Institute, Poona.
ABNUHS : Annual Bulletin of Nagpur University Historical Society.
ABORI : Annals of Bhandarkar Oriental Research Institute, Poona.
AI : Ancient India
An : Annual.
APRAS (NC) : Annual Progress Report of Archaeological Survey (Northern Circle).
AR : Asiatic Researches.
Annual Reports of Archaeology Department, Gwalior State
ASI Ar. : Archaeological Survey of India, Annual Report.
ASI : (N.I.S.) Archaeological Survey of India (New Imperial Series).
ASIR : Archaeological Survey of India Reports, Cunninghamham.

B

- BDCRI : Bulletin of Deccan College Research Institute, Poona.
BRVRI : Bulletin of Rama Varma Research Institute (Cochin)
BSS : Bangiya Sihatya Parishat Patrika (Bengali).
BV : Bharatiya Vidya.
BH : List.

E

- EI . Epigraphia Indica.

F

- FN : Footnote.

G

- G : Gupta Era.
G. Val. : Gupta-Valabhi era.

H

- HJMU : Half Yearly Journal of Mysore University.

I

- IA : Indian Antiquary (Bombay).
I. Arch. : Indian Archaeology.
IC : Indian Culture (Calcutta).
IEAR : Indian Epigraphy, Annual Reports on (Archaeological Survey of India)
IHQ : Indian Historical Quarterly (Calcutta)

Both the journals are same but named in different ways.

- INSCRS : Inscriptions in Central Provinces and Berar (Second Edition) R. B. Hirralal.
IMPORTANT Inscriptions from Baroda State. A. S. Gadre.

J

- JAHC : Journal of Andhra History & Culture.
JAHRS : Journal of Andhra Historical Research Society.
JARS : Journal of Assam Research Society.
JAS (Lt.) : Journal of Asiatic Society (Letters) Calcutta.
JASB : Journal of the Asiatic Society, Bengal.

JAU : Journal of the Annamalai University.
 JBBRAS : Journal of Bombay Branch of Royal Asiatic Society.
 JABORS : Journal of Bihar Orissa Research Society.
 JBRS : Journal of Bihar Research Society.
 JDL (Cal.) : Journal of the Department of Letters (Calcutta) University.
 JGRI : Journal of Ganganatha Jha Research Institute (Allahabad).
 JIH : Journal of Indian History.
 JMU : Journal of the Madras University.
 JOHRS : Journal of the Orissa Historical Research Society.
 JOI : Journal of Oriental Institute, Baroda.
 JOU : Journal of the Osmania University.
 JPASB (NS) : Journal & Proceedings of the Asiatic Society Bengal (New Series).
 JRAS : Journal of the Royal Asiatic Society of Great Britain & Ireland
 JRASB (Lt.) : Journal of the Royal Asiatic Society Bengal (Letters).
 JUB : Journal of the United Provinces Historical Society.

H

HA₁ : Hyderabad Archaeological Series.
 HIL : Historical & Literary Inscrs., R. B. Pandey, Chaukhambha, Sanskrit Series, Vol. XXIII, Varanasi, 1962.

M

MA SI : Memoirs of the Archaeological Survey of India.
 The same Journal differently named

N

NIA . New Indian Antiquary

P

PASB : Proceedings of the Asiatic Society of Bengal
 PDHC : Proceedings of the Deccan History Congress.
 PIHC : Proceedings of the Indian History Congress.
 PRAS WC (or EC or NC) : Progress Reports of Archaeological Survey, Western Circle (Eastern Circle or Northern Circle).

R

Res-Soc : Research Society.

S

SAII : Studies of Ancient Indian Inscriptions, B. Upadhyaya (1961), Pub. Motilal Banarasi Das, Varanasi.
 SI : Select Inscriptions, D. C. Sircar.
 SIEAR : South Indian Epigraphy, Annual Report.
 S Ind : Studies in Indology, 1960, V. V. Mirashi (Vol. I. Pub. by Vidarbha Samsodhana Mandala Nagpur, Vol. II. by Mirashi himself).

V

VOJ : Vienna Oriental Journal.

*The name differs for various sessions as Indian Oriental Conference (IOC) or Proceedings of Indian (Sometime all India) Oriental Conference (PIOC or PAIOC)

1. INSCRIPTIONS OF THE IMPERIAL GUPTAS & THE LATER GUPTAS OF MAGADHA

Sl. No.	Inscriptions	Date	References	Remarks
1A. THE IMPERIAL GUPTAS SAMUDRAGUPTA				
1.	NALANDA COPPER PLATE OF SAMUDRAGUPTA (<i>Bh. No. 2075</i>)	(G?) 5 Māgha di. 2.	Hiranand Sastri, <i>ASI AR.</i> 1927-28, p. 138; A Ghosh, <i>EI</i> Vol XX (1939-40), pp 50-53 & Pl., D. C. Sircar, <i>EI</i> . Vol. XXVI (1941-42), p. 135-36; & <i>SI</i> . Bk. III no. 4 pp. 262-64, R. C. Majumdar, <i>IC</i> . Vol XI (1944-45) pp 225-30, Hiranand Sastri, <i>MASI</i> No 66 pp. 77-78; P. L. Gupta, <i>PIHC</i> XVI (1953) pp. 94-95; B. Upadhyaya, <i>SAII</i> . pt. II, p. 50.	So-called spurious plate characters seem to belong to Samudragupta's time, see <i>Bh. List</i> b. 290 fn. 1.
2.	GAYA COPPER PLATE OF SAMUDRAGUPTA (<i>Fl. No. 60, BH. No. 1540</i>)	(G?) : Vaiśākha di. 10	D. C. Sircar, <i>SI</i> . Bk. III no 5, pp 264-66, R. C. Majumdar, <i>IC</i> . Vol XI (1944-45) pp 225-30; P. L. Gupta, <i>PIHC</i> . XVI (1953) pp. 95-5	So-called spurious Plate. (characters of about the beginning of the 8th cent. A.D.).
3.	THE ERANA INSCRIPTION (NOW IN INDIAN MUSEUM, CALCUTTA) OF SAMUDRAGUPTA (<i>Fl. No. 2, Bh. No. 1539</i>)	—	Hirala, <i>Inscr. in C.P. & Berar</i> p. 47 no. 79, Dasarath Sharma, <i>JIH</i> . Vol. XIV (1935) pp. 27-29; D. C. Sircar, <i>SI</i> Bk. III. no. 3, pp. 260-62; Jagan Nath, <i>JIH</i> . Vol. XIX (1940) pp 27-29; D. C. Sircar, <i>PIHC</i> XVII (1954) pp. 72-77; B. Upadhyaya, <i>SAII</i> . pt. II, pp. 49-50, R. B. Pandey, HLI. (1962) pp 77-78.	
4.	ALLAHABAD STONE PILLAR INSCR. OF SAMUDRAGUPTA (<i>Fl. No. 1, Bh. No. 1538</i>)	—	Bijhler, <i>Die indischen Inschriften und das Alter der indischen Kunstpoesie</i> , pp. 39 ff & 88 ff., K. P. Jaiswal, <i>JBORS</i> . Vol. XVIII (1932) pp. 207-11; V. Lakshminarayan, <i>JAHRS</i> . Vol. XIII (1941-42) pp. 141-44; D. C. Sircar, <i>SI</i> . Bk. III no. 2 pp. 254-60 & Pls.; S. V. Sohni, <i>ABORI</i> . Vol. XXXIX (1958) pp. 34-46; B. Upadhyaya, <i>SAII</i> . pt. II, pp. 47-49 & Pl,	Regarded as posthumous by Fleet.

Sl. No.	Inscriptions	Date	References	Remarks
			<i>IE. AR.</i> 1952-53 p. 71 no. 437 App. B; R. B. Pandey; <i>HLLI</i> (1962) pp. 72-76. For other references see <i>Select Bibliography of Articles S.V. I. A. Samudragaputa</i> (given at the end of this supplement.)	
CHANDRAGUPTA II				
5.	MATHURA PILLAR INSCR. OF THE TIME OF CHANDRAGUPTA II. (<i>Bh. Nj.</i> 2034)	G. 61 Prathama-Ashādha Su. 5.	D. R. Bhandarkar, <i>EI.</i> Vol. XXI (1931-32) pp. 8-9 & Pl; N.R. Ray, <i>IA.</i> Vol. LXI (1932) pp. 117-18; D. B. Diskalkar, <i>ABO-RJ.</i> Vol. XVIII (1936-37) pp. 166-170; D. C. Sircar, <i>IHQ.</i> Vol. XVIII (1942) pp. 271-75; & <i>SI</i> Bk. III no. 9, pp. 269-71; V. S. Agrawala, <i>JUPHS.</i> Vol. XXIV-V (1951-52) pp. 143-5; B. Upadhyaya, <i>SAIL.</i> pt. II. p. 51; R. B. Pandey, <i>HLLI.</i> (1962) pp. 78-79.	
6.	UDAYAGIRI CAVE (NO. 6, ON THE FACADE) INSCR. OF THE TIME OF CHANDRAGUPTA II. (<i>Fl. No.</i> 3, <i>Bh. No.</i> 1260)	G. 82 Ashadha Su. 11	D. C. Sircar, <i>SI.</i> Bk. III no. 10 p. 271; B. Upadhyaya, <i>SAIL.</i> pt. II pp. 51-52; <i>AR of Arch. Deptt Gwalior State</i> , Samvat 1974 no. 78; <i>Gwalior Rajya Abhilekha</i> , no. 551, <i>IE AR.</i> 1961-62 no. 1718 App C; R. B. Pandey, <i>HLLI</i> (1962) p. 79.	See also Cunningham than Bhilsu Topes p. 150; & ASIR Vol. X p 50
7.	GADHWA (ALLAHABAD DIST. U.P. NOW IN INDIAN MUSEUM CALCUTTA) INSCR. OF THE TIME OF CHANDRAGUPTA II. (<i>Fl. No.</i> 7, <i>Bh. No.</i> 1261)	G. 28 —		
8.	SANCHI STONE INSCR. OF CHANDRAGUPTA II. (<i>Fl. No.</i> 5, <i>Bh. No.</i> 1262).	G. 93 Bhadrapada di. 4	D. C. Sircar, <i>SI.</i> Bk. III. no. 12, pp. 273-74; B. Upadhyaya, <i>SAIL.</i> pt. II p. 52; <i>IE. AR.</i> 1961-62 no. 146 App. B.	
9.	MATHURA INSCR. OF CHANDRAGUPTA II. (NOW LAHORE MUSEUM) (<i>Fl. No.</i> 4, <i>Bh. No.</i> 1542)	--	V. S. Agrawala, <i>JUPHS.</i> Vol. XXIV-V (1951-52) pp. 141 43.	
10.	UDAYAGIRI CAVE (NO. 7, ON THE BACK WALL) INSCR. OF THE TIME OF CHANDRAGUPTA II (<i>Fl. No.</i> 6, <i>Bh. No.</i> 1541)	—	Buhler, <i>VOJ.</i> Vo. V. pp. 226 ff.; D. C. Sircar, <i>SI.</i> Bk. III. no. 11, p. 272; <i>AR of Arch. Dept., Gwalior State</i> , Samvat 1974 no. 79; <i>Gwalior Rajya Abhilekha</i> no. 645; <i>IE. AR.</i> 1961-62 no. 1719 App. C; Jagan Natha, <i>JIH.</i> Vol. XXI (1942) pp. 156-57; R. B. Pandey, <i>HLLI.</i> (1962) p. 80.	

Sl. No.	Inscriptions	Date	References	Remarks
11.	MEHARAULI IRON PILLAR INSCR. OF CHANDRA (<i>Fl. No.</i> 32, <i>Bh. No.</i> 1543)	---	C. H. Cakravarty, <i>ABI</i> . Vol. VIII (1927) pp. 172-76; D. R. Bhandarkar, <i>JAHR</i> . Vol. X (1936-7) pp. 86-88; D. C. Sircar, <i>SI</i> . Bk. III. no. 14 pp. 275-77; & <i>JRASB. (Lt.)</i> Vol. V (1939) p. 407 f.; Jagan Nath, <i>JIH</i> . Vol. XXI (1942) pp. 161-62; B. Upadhyaya, <i>SAII</i> . pt. II. p. 53 & Pt.; R. B. Pandey, <i>HLI</i> . (1962) pp. 80-81. For other references see <i>Select Bibliography of Articles S. V. 'I.A. Chandragupta II'</i> (given at the end of this supplement).	The identification of this Chandra is controversial but scholars mostly identify him with Chandragupta II of Imperial Gupta dynasty.
12.	BASADH (MUZAFFARPUR DIST., BIHAR) CLAY SEAL OF MAHADEVI DHRUVASAMINI, WIFE OF CHANDRAGUPTA II AND MOTHER OF MAHARAJA GOVINDAGUPTA (<i>Bh. No.</i> 1544)	---	Bloch, <i>ASI. A.R.</i> 1903-4 p. 107 & pl.	
<i>KUMARAGUPTA I</i>				
13.	BILASADA (ETAH DIST., U.P.) INSCR. OF THE TIME OF KUMARAGUPTA I (<i>Fl. No.</i> 10, <i>Bh. No.</i> 1263)	G. 96	--- Jagan Nath, <i>JUPHS</i> . Vol. XIII (1940) pt. II, p. 98; & <i>PIHC</i> . IV (1940) pp. 59; D. C. Sircar, <i>SI</i> . Bk. III. no. 15 pp. 278-9; B. Upadhyaya, <i>SAII</i> . pt. II. pp. 53-54.	
14.	GADHWA (ALLAHABAD DIST. U.P. NOW IN INDIAN MUSEUM, CALCUTTA) FRAGMENTARY INSCR. OF THE TIME OF KUMARAGUPTA I (<i>Fl. No.</i> 9, <i>Bh. No.</i> 1264)	G. 98	---	
15.	UDAYAGIRI (GWALIOR, M.P.) CAVE JAIN INSCR. OF THE REIGN OF KUMARAGUPTA I (<i>Fl. No.</i> 61, <i>Bh. No.</i> 1265)	G. 106 Kartti ka bahu (badi) 5.	--- <i>IE. AR.</i> 1952-53 p. 39 no. 132 App. B; <i>AR. Arch. Dept.</i> , <i>Gwalior State</i> , Samvat 1974 no. 80; <i>Gwalior Rājya Abhilekha</i> no. 552.	See if these ref. are correct.
16.	DHANAI DAH (RAJSHAHI DIST., BENGAL, NOW WITH VARENDRA RES. SOC., CALCUTTA) PLATE OF KUMARAGUPTA I (<i>Bh. No.</i> 1267)	G. 113	Banerji, <i>BSS</i> . Vol. XVI pp. 112 ff.; & <i>JPASB (NS.)</i> Vol. V (1909) p. 459 f. & Pl. XX; Basak, <i>Sir Asutosh Mookerji Silver Jubilee Volumes</i> , <i>Orientalia</i> pt. 2, p. 480; & <i>Sahitya (Bengali)</i> , Paush 1323 B.S. pp. 827 f.; & <i>EI</i> . Vol.	

Sl. No.	Inscriptions	Date	References	Remarks
			XVII (1923-24) pp. 345-48 & Pl.; D. C. Sircar, <i>SI</i> . Bk. III. no. 16 pp. 280-82; B. Upadhyaya, <i>SAII</i> . pt. II p. 54-55.	
17.	MATHURA JAIN IMAGE INSCR. (NOW LUCKNOW MUSEUM) OF THE TIME OF KUMARAGUPTA I. (<i>Bh. No.</i> 1268)	G. 113 (?) di. 20	Bühler, <i>EI</i> . Vol. II (1894) p. 210 & Pl.	
18.	TUMAIN (GWALIOR DIST. M.P., (NOW IN GUJARI MAHALA MUS., GWALIOR) FRAGMENTARY INSCR. OF GHATOTKACHAGUPTA (SON OF KUMARAGUPTA I ?) (<i>Bh. No.</i> 1269)	G. 116	M.B. Garde, <i>An. Administration Rep.</i> for Vikrama Samvat 1975 (A D. 1918-19), & <i>IA</i> . Vol. XLIX (1920) pp. 114 f.; & <i>EI</i> . Vol. XXVI (1941-42) pp. 115 ff & Pl.; D C. Sircar, <i>SI</i> Bk III. no 24 pp. 298-99; <i>AR. Arch Dept., Gwalior State, Samvat</i> 1975 no. 65; <i>Gwalior Rājya Abhilekha</i> No. 553.	In this inscr Ghatotkachagupta is mentioned as son of Kumāragupta who is most probably Kumāragupta I of Imperial Gupta dynasty
19.	KARMADAMDA (FAIZABAD DIST., U P, NOW LUCKNOW MUSEUM) INSCR OF THE REIGN OF DUMARAGUPTA I (<i>Bh No</i> 1270)	G. 117 Kārttika māsa divasa 10	Vogel, <i>PRAS. NC.</i> (1907-8) p. 39, Banerji, <i>JASB (NS., Vol V</i> (1909) p 458 & Pl. XIX, S Konow <i>EI</i> Vol X (1909-10) pp 70 ff & Pl . D C. Sircar, <i>SI</i> Bk III no 17 pp 282-3; B Upadhyaya, <i>SAII</i> . pt. II. p 55 & Pl ; <i>IE AR.</i> 1956-57 p. 109 no. 217 App. C; R. B. Pandey, <i>HJI</i> (1962) p. 82.	
20	KULAIKURI COPPER PLATE OF KUMARAGUPTA I (NOW IN VARENDRA RES. SOC., FINE-SPOT/SULTANPUR, RAJSHAHI DIST)	G. 120 Vai-sakha di 1	D.C. Sircar, <i>Vangasri</i> , Vaisakha, 1350 B. S.; <i>IHQ</i> . Vol. XIX (1943) p. 12-26 & Pls., B C. Sen, <i>Some Historical aspects of the Inscriptions in Bengal</i> (Calcutta 1942) p. Xii ff; Niradabandhu Sanjal, <i>EI</i> . Vol. XXXI (1955-56) pp 57-66 & Pl., <i>IE. AR.</i> 1955-56 p. 23 no. 110 App. A.	Mr. Niradabandhu Sanjal reads the date 121 see <i>EI</i> . XXXI p. 58).
21.	DAMODARPURA (DINAJPUR DIST., BENGAL, NOW VARENDRA RES SOC., CALCUTTA) PLATE NO. 1 OF KUMARAGUPTA I (<i>Bh. No.</i> 1271)	G. 124 Phal-guna di.7	R. G. Basak, <i>EI</i> . Vol. XV (1919-20) pp. 130 ff & Pl , D. C. Sircar, <i>SI</i> . Bk. III. no. 18 pp. 283-85; B. Upadhyaya, <i>SAII</i> . pt. II pp. 55-56; R. B. Pandey, <i>HJI</i> . (1962) pp. 82-84.	

Sl. No.	Inscriptions	Date	References	Remarks
22.	DAMODARPUR PLATE NO. 2 OF KUMARGUPTA I (NOW VARENDRA RES SOC., CALCUTTA) (<i>Bh. No.</i> 1272)	G. 128 Vaisakha di.13	R. G. Basak, <i>EI.</i> Vol. XV (1919-20) pp. 133 ff. & Pl.; Dikshit, <i>EI.</i> Vol. XVII (1923-24) p. 193; D. C. Sircar, <i>SI. Bk.</i> III. no. 19 pp. 285 f.; B. Upadhyaya, <i>SAII.</i> pt. II pp. 56-7.	Basak read the date 129. See <i>EI.</i> Vol. XV. pp. 133 ff.
23.	BAIGRAMA (BOGRA DIST., E. PAKISTAN) PLATE ISSUED FROM PANCHANAGARI BY THE KUMARAMATYA KULVRIDDHI AND THE GOVT. OF THE DIST. (VISHAYA - ADHIKARANA) (NOW GAUDA RES. SOC. HOWRAH) (<i>Bh. No.</i> 2114)	G. 128 Magha di.19	Basak, <i>EI.</i> Vol. XXI (1931-32) pp. 78-83; D. C. Sircar, <i>SI. Bk.</i> III. no. 41, pp. 342-45 & Pl.; B. Upadhyaya, <i>SAII.</i> pt. II. pp. 87-88; <i>IE. AR.</i> 1956-57 p. 27 no. 15 App. A; <i>IE. AR.</i> 1961-62 no. 22 App. A.	'Kulv ^g iddhi' is represented here meditating on the feet of the 'Bhattarakas' who can be no other than Kumaragupta I of Imperial Gupta dynasty.
24.	MANKUWAR (ALLAHABAD DIST., U.P.) BUDDHIST IMAGE INSCR. OF MAHARAJA KUMARAGUPTA I (<i>Fl. No.</i> 11, <i>Bh. No.</i> 1273)	G. 129 Jyeshtha Masa di. 18	Pathak, <i>IA.</i> Vol. XLI (1912) p. 244; D.C. Sircar, <i>SI. Bk.</i> III no. 20 pp. 287-88; B. Upadhyaya, <i>SAII.</i> pt. II. p. 57; <i>IE. AR.</i> 1957-58 p. 81 no. 320 App. C.	
25.	GADHIWA (ALLAHABAD DIST., U.P.) INSCR. (NOW INDIAN MUSEUM, CALCUTTA) OF THE TIME OF KUMARAGUPTA I (<i>Fl. No.</i> 8, <i>Bh. No.</i> 1545)	divas 10	---	Date given G. 129. See Classical Age p. 673 Sl. No. 24)
26.	GADHWA (ALLAHABAD DIST., U.P. NOW INDIAN MUSEUM CALCUTTA (INSCR. OF THE TIME OF KUMARAGUPTA I ?) (<i>Fl. No.</i> 64, <i>Bh. No.</i> 1546)	---	---	
27.	BASADHA (MUZAFFARPUR DIST. BIHAR) CLAY SEAL OF GHATOTKACHGUPTA (<i>Bh. No.</i> 1547).	---	Bloch, <i>ASI. AR.</i> 1903-4 pt. II p. 107 & Pl.	Perhaps the Same Ghatotkacha mentioned in Tumain Inscr. See no. 18.

SKANDAGUPTA

28.	JUNAGADHA (GUJARATA) ROCK INSCR. OF THE TIME OF SKANDAGUPTA. (<i>Fl. No.</i> 14, <i>Bh. No.</i> 1276)	G. 136, 137 & 138	— Buhler, <i>VOJ.</i> Vol. V. pp. 220 ff.; Jagan Nath, <i>JUPHS.</i> Vol. XIII Pt. II (1940) p. 98 & <i>PIHC.</i> IV (1940) p. 59; D.C. SIRCAR, <i>SI. Bk.</i> III. no. 25 p. 299; Dasarath Sharma,	
-----	--	-------------------	---	--

Sl. No.	Inscriptions	Date	References	Remarks
			<i>JGRI</i> . Vol. VI (1948-49) pp. 303-5; B. Upadhyaya, <i>SAII</i> . pt. II pp. 63-68; R. B. Pandey, <i>HLI</i> . (1962) pp. 92-99.	
29.	KAHAUM (DEORIA DIST., U.P.) JAIN INSCR. OF THE TIME OF SAKANDAGUPTA (<i>Fl. No.</i> 15, <i>Bh. No.</i> 1278)	G. 141 Jyeshtha māsa.	— D. C. Sircar, <i>SI</i> . Bk. III. no. 26 pp. 308-9; R. B. Pandey, <i>IHQ</i> . Vol. XXVIII (1952) pp. 298-300; B. Upadhyaya, <i>SAII</i> . pt. II pp. 68-69, R. B. Pandey, <i>HLI</i> . (1962) p. 92.	
30.	REWA (SUPIA. M. P.) PILLAR INSCR. OF SKANDAGUPTA.	G. 141 Jyeshtha Śukla 2	D. C. Sircar, <i>EI</i> . Vol. XXXIII (1959-60) pp. 306-8 & Pl., <i>I.E. AR.</i> 1959-60 p. 71 no. 249 App B.	
31.	INDORE (BULANDASAHAR, U.P.) COPPER PLATE INSCR. OF THE TIME OF SAKANDAGUPTA (<i>Fl. No.</i> 16, <i>Bh. No.</i> 1279)	G. 146 Phālguna māsa	— Kielhorn, <i>IA</i> . Vol XVIII (1889) p. 219, Jagan Nath, <i>JUPHS</i> . Vol. XIII (1940) pt II p. 99, & <i>PIHC</i> . IV (1940) p. 59, D. C. Sircar, <i>SI</i> Bk. III. no. 27 p. 309-12, B. Upadhyaya, <i>SAII</i> . pt. II. pp. 69-70.	
32.	BIHAR (PATANA DIST.) PILLAR INSCR. OF THE TIME OF SKANDRAGUPTA (<i>Fl. No.</i> 12, <i>Bh. No.</i> 1548)	---	— R. C. Majumdar, <i>JC</i> Vol X (1943-44) p. 170, H Hanid, <i>Monuments. of Bihar and Orissa</i> pp. 56-57; D. C. Sircar, <i>SI</i> Bk. III. no. 29 pp. 316-19, B. Upadhyaya, <i>SAII</i> pt. II, pp. 72-74; <i>I.E. AR.</i> 1960-61 no. 195, App. B.	Majumdar & Altaker ascribe this inscr. to a certain successor of Purugupta (See. <i>Vakataka</i> & <i>Gupta Age</i> p. 481 Inscr. no. 42)
33.	BHITARI (GHAZIPUR DIST., U.P.) PILLAR INSCR. OF SKANDAGUPTA (<i>Fl. No.</i> 13, <i>Bh. No.</i> 1549)	---	— Jagan Nath, <i>JUPHS</i> . Vol. XIII (1940) pt. II. p. 99; & <i>PIHC</i> . IV (1940) p. 60; D. C. Sircar, <i>SI</i> . Bk. III. no. 28 pp. 312-15; B. Upadhyaya, <i>SAII</i> pt. II. pp. 70-72; R. B. Pandey, <i>HLI</i> . (1962) pp. 99-102; Dasarath Sharma, <i>PIHC. XIX</i> (1956) pp. 148-50.	
KUMARAGUPTA II				
34.	SARANATHA (BANARAS DIST., U.P.) BUDDHA STONE IMAGE INSCR. OF THE TIME OF KUMARAGUPTA (II). (<i>Bh. No.</i> 1281)	G. 154 Jyeshtha dvitiyā	<i>APRAS (NC.)</i> 1914-15 no. 1; Gupte, <i>ASI. AR.</i> 1914-15. p. 124 no. XV & Pl. LXIX, n.; D. C. Sircar, <i>SI</i> . Bk. III. no. 31 pp. 320-21;	

Sl. No.	Inscriptions	Date	References	Remarks
			B. Upadhyaya, <i>SAII</i> . pt. II. p. 74; <i>IE. AR.</i> 1959-60 p. 135 no. 593 App C; Jagan Nath, <i>IH.</i> Vol. XXI (1942) pp. 169-171; R. B. Pandey, <i>HLI</i> (1962) p. 102.	
<i>BUDHAGUPTA</i>				
35.	SARNATHA BUDDHA STONE IMAGE INSCR. OF THE TIME OF BUDHAGUPTA (<i>Bh No</i> 1283)	G. 157 Vaiśakha 7, ba. Mūla.	<i>APRAS. (NC.)</i> 1914-15 no 5, Gupte, <i>ASI. AR</i> 1914-15, p. 125 no. XVII & Pl. LXIX. O. Jagan Nath, <i>JUPHIS</i> Vol. XIII (1940) pt II p. 100 & <i>PIHC</i> IV (1940) p. 60; D. C. Sircar, <i>SI Bk.</i> III. no. 33 p 323, B. Upadhyaya, <i>SAII</i> . pt. II p. 75; <i>IE. AR.</i> 1959-60 p. 185 no. 595 App. C; R. B. Pandey, <i>HLI.</i> (1962) pp. 103-4.	
36.	DUPLICATE SARANATHA BUDDHA IMAGE INSCR. OF THE TIME OF BUDHAGUPTA	G. 157	<i>APRAS. (NC.)</i> 1914-15 no. 4; Gupte, <i>ASI. AR.</i> 1914-15 pp. 124-25 no. XVI & Pl. LXIX 'p', <i>IE. AR.</i> 1959-60 p. 135 no. 594 App. C.	
37.	BHARAJA KALA BHAVANA (BHU, VARANASI, U.P.) PEDESTAL INSCR OF BUDHAGUPTA ON A BROKEN IMAGE.	G.157 Marg- srsh di. 20	<i>IE. AR</i> 1952-53 p. 73 no. 469 App. B.	
38.	PAHADAPURA COPPER PLATE OF THE TIME OF BUDHAGUPTA (<i>Bh. No</i> 2037)	G 159 Ma- gha di. 7	K N. Dikshit, <i>EI</i> Vol XX (1929-30) pp. 59-64 & Pl., R.G Basak, <i>BSS (Bengali)</i> Vol XXXIX pp 143 ff. Pl., D C. Sircar, <i>SI</i> Bk III no 42 p. 346; B. Upadhyaya, <i>SAII</i> . pt. II pp 89-90; <i>IE. AR.</i> 1956-57 p. 27 no. 14 App. A.	
39.	BANARAS (RAJGHAT) STONE PILLAR INSCR. OF THE TIME OF BUDHAGUPTA (NOW IN BHARATA KALA BHAVANA MUSEUM)	G. 159 or 157 Marg- srsha 28	S. C. Sircar, <i>JRASB (Lt)</i> Vol XV (1949) pp 5-7 & Pl., <i>IE. AR</i> 1952-53 p 73 no. 456 App. B, <i>IE AR.</i> 1955-66 p. 53 no 363 App B. (year given 157).	
40.	DAMODARPURA (DIST. DINAJPUR, BENGAL) PLATE OF BUDHAGUPTA (<i>Bh. No.</i> 1286)	G. 163 As- hādhā di.13	R. G. Basak, <i>EI</i> Vol. XV (1919-20) pp. 135 ff & Pl., D. C. Sircar, <i>SI.</i> Bk. III. no. 34 pp. 324-26; B. Upadhyaya. <i>SAII.</i> pt. II. pp. 75-76; R. B. Pandey, <i>HLI.</i> (1962) pp. 104-5.	

Sl No.	Inscriptions	Date	References	Remarks
41.	IRANA (SAUGOR DIST., M.P.) STONE PILLAR INSCR. OF THE TIME OF BUDHAGUPTA (<i>Fl No.</i> 19, <i>Bh. No.</i> 1287)	G. 165 Ās- hadha Su- kla dvagāṣā	Fleet, <i>J.A.</i> Vol. XX (1891) p. 377; Hiralal, <i>Inscr.</i> in <i>C.P.</i> & <i>Berar</i> p. 47 no. 80; D.C. Sircar, <i>SI. Bk.</i> III, no. 35 pp. 326-27; B. Upadhyaya, <i>SAIL</i> pt. II p. 76, R. B. Pandey, <i>HLI</i> (1962) p. 106.	
42.	DAMODARPURA (DINAJPUR DIST., BENGAL) COPPER PLATE INSCR. OF THE TIME OF BUDHAGUPTA (<i>Bh. No.</i> 1550)	Phalguna di. 15	R. G. Basak <i>EI.</i> Vol. XV (1919-20) p. 138 f. & Pl.; D. C. Sircar, <i>IC.</i> Vol. V (1938- 39) pp. 432-33; & <i>SI. Bk.</i> III. no. 36 pp. 328-30, B Upa- dhyaya, <i>SAIL</i> pt II pp 77- 78; R. B. Pandey, <i>HLI.</i> (1962) pp. 107-8.	
43	NALANDA SEAL OF TUDHA- GUPTA (NALANDA MUSEUM, REG. NO. 660)	---	Hiranand Sastri, <i>MASI</i> no. 66, p. 64 & Pl. VIII-a, A. Ghosh, <i>IHQ.</i> Vol. XIX (1943) pp 119-25, D C. Sircar, <i>IHQ.</i> Vol. XIX (1943) pp. 272-75.	
44	BELWA (VARANASI TAHASIL, U P) PILLAR INSCR. OF BUDHAGUPTA (?) OF IM- PERIAL GUPTA (?) DYNASTY.	---	<i>IE. AR.</i> 1959-60 p. 120 no 742 App B	In late Brāhm characters of 5th cent A.D

NARASIMHAGUPTA

45	NALANDA CLAY SEAL OF NARASIMHAGUPTA (NALAN- DA MUSEUM)	---	Hiranand Sastri, <i>MASI</i> no. 66 p. 65 & Pl. VIII b.c.	
46	SARANATHA (BANARAS, U P. NOW INDIAN MUSFUM, CAL- CUTIA) VAISHNAVA INSCR. OF A KING PRAKATADITYA OR PRAKASADITYA, SON OF BALADITYA AND DHAVALA OF KASI (?) (<i>Fl. No.</i> 79, <i>Bh. No.</i> 1789)	---	---	Inscr. is of about 6th century AD. Balāditya is identified with Narasimha- gupta Bālā- ditya of Gupta Dyna- sty (See <i>Bh.</i> <i>List.</i> p. 252 fn. 4 & 5)

VAINYAGUPTA

47.	GUNAIGHARA (TIPERA DIST., BENGAL) COPPER PLATE INSCR. OF VAINYAGUPTA (<i>Bh. No.</i> 2038)	G. 188 Pa- usha Māsa 24th day.	D. C. Bhattacharya, <i>IHQ.</i> Vol. VI (1930) pp. 45-60 & Pl., M. Ghosh, <i>IHQ.</i> Vol. VI (1930) p. 561; D C. Sircar, <i>SI. Bk.</i> III. no. 37 pp.	NOTE: See clas- sical age.
-----	--	--------------------------------------	--	-------------------------------

Sl. No.	Inscriptions	Date	References	Remarks
			331-35, B. Upadhyaya, <i>SAII</i> pt. II pp. 78-80, <i>IE AR</i> . 1952-53 p. 26 no. 36 App A.	
48.	NALANDA SEAL OF VAINYAGUPTA.	---	Hiranand Sastri, <i>MASI</i> . no. 66 p 67 & Pl. VIII f.; A. Ghosh, <i>IHQ</i> Vol. XIX (1943) p. 275-77; R C Majumdar, <i>IHQ</i> Vol. XXIV (1948) pp. 67-68.	
<i>BHANUGUPTA</i>				
49.	ERANA (SAUGOR DIST., M.P.) PILLAR INSCR. OF THE TIME OF BHANUGUPTA (<i>Fl. No. 20, Bh. No 1290</i>)	G. 191 Māgha di. 3	—Hiralal, <i>Inscr. in C P. and Berar</i> , p. 49 no. 83, D. C. Sircar, <i>SI</i> Bk. III. no. 38, pp 335-36; B Upadhyaya, <i>SAII</i> pt. II. p. 80, <i>IE AR</i> . 1951-52 p. 21 no 127, R. B. Pandey, <i>HLI</i> (1862) pp. 108-9.	
<i>KUMARAGUPTA III</i>				
50.	DAMODARPURA (DINAJPUR DIST., BENGAL) COPPER PLATE INSCR OF GUPTA (<i>Bh. No 1307</i>)	G. 224 Bhādra di. 6	R. G Basak, <i>EI</i> Vol XV (1919-20) pp. 142 ff. & Pl., K. N. Dikshit, <i>EI</i> Vol. XVII (1923-24) p. 193, D C. Sircar, <i>SI</i> . Bk. III no 39 pp. 337-40; B Upadhyaya, <i>SAII</i> pt. II pp. 80-82, Jagan Nath, <i>JIH</i> Vol XXI (1942) pp 167-68.	The name of the issuer of the inscr. is variantly restored as Kumāragupta, Budhagupta, Upagupta etc by various scholars. (See D C Sircar's <i>SI</i> . Bk III p. 337 fn 4)
51.	BHITARI, (GHAZIPUR DIST., U.P. NOW LUCKNOW MUSEUM) SEAL OF KUMARAGUPTA (III?) (<i>Bh. No. 1551</i>)	—	V.A. Smith, <i>JASB</i> . Vol LVIII pt. I (1889) pp. 84-88, Hoernle, <i>JASE</i> Vol LVIII pt I (1889) pp. 88-105 & Pl., Fleet, <i>IA</i> . Vol. XIX (1890) p. 225, Jagan Nath, <i>JUPHS</i> . Vol XIII pt. II (1940) pp. 100-101 <i>PI HC</i> IV (1940) pp. 60-61; Hiranand Sastri, <i>MASI</i> . no. 66 p. 66-67 (only text), D.C. Sircar, <i>SI</i> Bk III. no. 32 pp. 321-22, B Upadhyaya, <i>SAII</i> pt. II p 74, <i>IE AR</i> . 1957-58 p. 14 no. 15 App. A; <i>IE AR</i> 1960-61 no. 55 App. A. (Ascribed to Kumāragupta II); R. B. Pandey, <i>HLI</i> . (1962) pp. 102-3.	Dr. B. Upadhyaya (<i>SAII</i> pt II p. 74) ascribes this inscr. to Kumāragupta II.

Sl. No.	Inscriptions	Date	References	Remarks
52.	NALANDA SEAL OF KUMARAGUPTA (III)	—	Hiranand Sastri, <i>MASI</i> . no. 66 pp. 65-66 pl. VIII-d, e; J. F. Fleet, <i>I.A.</i> Vol. XIX (1890) p. 225; Jagan Nath, <i>JUPHS.</i> Vol. XIII (1940) pt. II, pp. 100-101; & <i>PIHC.</i> IV (1940) pp. 60-61.	
<i>VISHNUGUPTA</i>				
53.	NALANDA SEAL OF VISHNUGUPTA.	—	H. N. Sastri, <i>MASI.</i> no. 66 p. 64; Krishna Deb, <i>EI.</i> Vol. XXVI (1941-42) p. 235 & Pl., A. Ghosh, <i>IHQ.</i> Vol. XIX (1943) pp. 119 ff; <i>IE AR.</i> 1959-60 p. 124 no. 425 App C	
1B. THE LATER GUPTAS				
<i>HARSHAGUPTA</i>				
54.	LUCKNOW MUSEUM FRAGMENTARY SLAB INSCR. MENTIONING HARSHAGUPTA (OF LATER GUPTAS?)	—	<i>IE. AR.</i> 1957-58 p. 70 no. 577 App. B	In character of 7th century A.D.
<i>ADITYASENA</i>				
55.	SHAHPUR (PATANA DIST., BIHAR) STONE IMAGL. INSCR. OF THE TIME OF ADITYASENADEVA (<i>Fl. No.</i> 43, <i>Bh. No.</i> 1393).	H 66 Margga. Sudi 7	—H. N. Śastri, <i>MASI</i> no. 66 pp. 82-83.	
56.	APHASADA (GAYA DIST., BIHAR) INSCR. OF ADITYASENADEVA (<i>Fl. No.</i> 42, <i>Bh. No.</i> 1552).	—	—B. Upadhyaya, <i>SAII</i> pt. II pp. 82-85; R. B. Pandey, <i>HLI.</i> (1962) pp. 149-53.	
57.	MANDARA (BHAGALPUR DIST., BIHAR) HILL ROCK INSCR. OF ADITYASENADEVA (<i>Fl. No.</i> 44-45, <i>Bh. No.</i> 1553).	—	—	
<i>VISHNUGUPTA</i>				
58.	MANGRAON, PATANA MUSEUM INSCR. OF THE TIME OF VISHNUGUPTA	R. Y. 17 Śrāvana Su. 2 (C.700A.D.)	A. S. Altaker, <i>EI.</i> Vol. XXVI (1941-42) pp. 241 ff. & Pl., Priyatosh Banerji, <i>JBR.S.</i> Vol. XXX (1944) pp. 199-202 & Pl.; B. Upadhyaya, <i>SAII.</i> pt. II. p. 85 & Pl.	

Sl. No.	Inscriptions	Date	References	Remarks
59.	KAULESVARI HILL INSCR. OF VISHNUGUPTA	—	D. C. Sircar, <i>EI.</i> Vol. XXX (1953-54) pp. 84-85.	
<i>JIVITAGUPTA II</i>				
60.	DEO-BARNARAKA (ARRAH DIST., BIHAR) INSCR. OF JIVITAGUPTA (II) (<i>Fl. No.</i> 46, <i>Bh. No.</i> 1554)	—	—R. C. Majumdar, <i>IC.</i> Vol. XI (1944-45) pp. 124-25; B Upadhyaya, <i>SAII.</i> pt. II pp. 85-86; <i>IE. AR.</i> 1960-61 no. 208 App. B; R. B. Pandey, <i>HLL.</i> (1962) pp. 153-55.	
<i>JIVAGUPTA</i>				
61.	DARABHANGA (BIHAR) CHARACTER OF JIVAGUPTA	R. Y. 2 Chaitra [su] di. [14?]	<i>I. Arch.</i> 1958-59 no. 14; <i>IE. AR.</i> 1959-60 p. 34 no. 4 App. A; D. C. Sircar; <i>EI.</i> Vol. XXXV (1963-64) pp. 125-30 & Pl.	King Jivagupta & his father Rāmagupta are known for the first time from this record written in early mediaeval characters (8th cent. A.D.). We are not in a position to trace any relation of this king with later Guptas. He may be a local ruler like Samgrāmagupta (See <i>Bh. No.</i> 1555).

2. INSCRIPTIONS OF THE CONTEMPORARY FEUDATORY DYNASTIES

Sl. No.	Inscriptions	Date	References	Remarks
2A. VARMANS OF DASAPURA (MALAVA)				
NARAVARMAN				
62.	MANDASOR (GWALIOR, M.I. NOW IN GUJARI MAHALA MUSEUM, GWALIOR) FRAGMENTARY INSCR. OF THE TIME OF NARAVARMAN (<i>Bh. No. 3</i>)	V 461 Aśvoja Śukla 5	D R Bhandarkar, <i>PRAS WC</i> , (1912-13) p 58, & <i>IA</i> Vol XLII (1913) pp. 161-63, R. G Bhandarkar, <i>IA</i> Vol. XLII (1913) pp. 199 ff; H. P Sastri, <i>IA</i> , Vol. XLII (1913) pp 217 ff.; & <i>EI</i> Vol XII (1913-14) pp. 320 ff & Pl; R D Banerji, <i>EI</i> , Vol XIV (1917-18) p 367-371, <i>AR of Arch. Dept., Gwalior State</i> , Samvat 1970 no 13, <i>Gwalior Rājya Abhilekha</i> , no 1, Gorde, <i>ASI AR</i> 1922-23 p 187, D C Sircar, <i>SI Bk III</i> no 51 pp 377-379, B Upadhyaya, <i>SAI</i> pt. II, pp 95-96	Naravarma is probably a feudatory of Chandragupta II of Imperial Gupta Dynasty (See <i>Bh List</i> p 2, fn. 2)
63.	BIHAR KOTRA STONE INSCR. OF NARAVARMAN	V 474 Śrāvana Śu 2	S N Chakravarty, <i>II</i> Vol XXVI (1941-42) pp. 130-32 & Pl.	
VISVAVARMAN				
64	GANGDIHARA (JHALAWAR, RAJASIHAN) INSCR. OF THE TIME OF VISVAVARMAN SON (?) OF NARAVARMAN (<i>Fl. No. 17, Bh. No. 4</i>)	V. 480(?) Kārttika Sukla, 13	—B. R. Bhandarkar, <i>R G Bhandarkar Comm Vol.</i> , pp 187 ff. B H. Bhidc, <i>JBORS</i> Vol. VII (1921) pp. 33-35; D. C. Sircar, <i>SI Bk III</i> no. 52 p 379-86, B. Upadhyaya, <i>SAI</i> pt II pp. 96-100, <i>IE. AR.</i> 1952-53 p. 70 no. 422 App. B, R. .C. Agrawala, <i>JBRS.</i> Vol. XLI (1955) pp. 309-10.	

Sl. No.	Inscriptions	Date	References	Remarks
<i>BANDHUVARMAN</i>				
65.	MANDASOR (GWALIOR, M.P. NOW IN GUJARI MAHALA MUSEUM, GWALIOR) INSCR. OF THE TIME OF KUMARAGUPTA I AND HIS GOVERNOR (AT DASAPURA) BANDHUVARMAN, SON OF VISVAVARMAN (<i>Fl. No. 18, Bh. No. 6</i>)	V. 493 & 529 sahasya Sukla. 13	—R. G. Bhandarkar <i>JBBRAS.</i> Vol. XVII pt. II pp. 94 ff.; Buhler, <i>Die Indischen und das Alter der Indischen-Kunspoesie</i> , pp. 91 ff.; R.V. Shastri, <i>IC.</i> Vol. IV (1937-38) pp. 361-63; D.B. Diskalker, <i>JBBRAS. (NS.)</i> Vol. II (1926) pp. 176-78; D. N. Mookerji, <i>IC.</i> Vol. V (1938-39) pp. 331-32; Jagan Nath, <i>JIH</i> Vol. XVIII (1939) pp. 118-19; K R Pishorti, <i>IC</i> Vol VI (1939-40) pp. 339-41; Daṣaratha Sharma, <i>IC</i> , Vol VI (1939-40) p 110; <i>Gwalior Rājya Abhilekha</i> no. 2; Jagan Nath, <i>JUPHS.</i> Vol XIII, pt II (1940) pp. 99-100. & <i>PIHC.</i> IV (1940) p 60. D. C. Sircar, <i>SI</i> Bk. III. no. 21 pp 288 ff. B. Upadhyaya, <i>SAII.</i> pt. II pp. 57-62, R B. Pandey, <i>HLI</i> (1962) pp 84-90.	Bandhuvarman was perhaps the feudatory ruler under Kumāragupta I of Imperial Gupt a dynasty
2 B <i>PARIVRAJAKA MAHARAJAS</i>				
<i>HASTIN</i>				
66.	KHOHA (NAGAUDH, M. P., NOW LOST) PLATE OF MAHARAJA HASTIN (<i>Fl. No. 21, Bh. No. 1282</i>)	G 156	—————	
		kārttika Su. 3 (Mahāvaiśākha samvatsara)		
67.	KHOHA (NAGAUDH, M.P. NOW LUCKNOW MUSEUM) PLATE OF MAHARAJA HASTIN (<i>Fl. No. 22, Bh. No. 1285</i>)	G 163 Chaitra Sukla 2 (Mahāvaiśākha Samvatsara).	—Fleet, <i>IA.</i> Vol. XX (1891) pp. 377-78, <i>IE. AR.</i> 1957-58 p. 19 no 58 App A; <i>IE. AR.</i> 1960-61 no. 46 App A.	
68.	JABALPUR PLATES OF MAHARAJA HASTIN	G 170 Mahāyeshtha Samvata Phālguna Su .5	Rajabali Pandey, <i>EI.</i> Vol. XXVIII (1949-50) pp. 264-67 & Pl.; <i>HLI.</i> (1962) pp. 90-91.	
69.	MAJHAGAWAN (NAGAUDH, M.P.) PLATES OF MAHARAJA HASTIN (<i>Fl. No. 23, Bh. No. 1291</i>)	G. 191 Māgha babula 3 (Mahā-Chaitra Samvat)	—Fleet, <i>IA.</i> Vol. XX (1891) pp. 378-79; Diskhnt, <i>ASI. AR.</i> 1922-23 p. 171.	

Sl. No.	Inscriptions	Date	References	Remarks
70.	NAVAGRAMA GRANT OF MAHARAJA HASTIN	G. (1) 98 Mahasvayuja Samvat.	K. N. Dikshit, <i>El.</i> Vol. XXI (1931-32) pp. 124-26 & Pl; <i>IE. AR.</i> 1956-57 p. 36 no. 83 App A.	
71.	BHUMARA (NAGAUDH, M.P.) PILLAR INSCR. OF THE PARIVRAJAKA MAHARAJA HASTIN AND THE UCHCHHAKALPA MAHARAJA SARVANATHA. (<i>Fl. No.</i> 24, <i>Bh. No.</i> 1661)	G. 189 201 or 165(?) Karttika di 19 (Mahamagha Samvat)	—D. C. Ganguly, <i>IHQ.</i> Vol XXI (1945) pp 137-38, D.C. Sircar, <i>L.I.</i> Vol XXXIII (1959-60) pp. 167-172, <i>IE AR</i> 1957-58 p. 68, no 558 App B	For dates, See Fleet, <i>CII.</i> Vol III Intro. pp 105 ff., & <i>IA.</i> Vol XIX (1890) pp 228 f

SAMKSHOBHA

72	BETULA (M.P.) PLATES OF THE MAHARAJA SAMKSHOBHA (<i>Bh. No.</i> 1292)	G 199 Ka-rttika di 10 (Mahamarggastirsha Samvata).	Hiralal, <i>Inscrs in C.P and Berar</i> , p. 87 no 160; & <i>El</i> Vol VIII (1905-6) pp. 284 ff. & Pl.	
73.	KHOHA (NAGAUDH, M.P) PLATES OF MAHARAJA SAMKSHOBHA. (<i>Fl. No.</i> 25, <i>Bh No</i> 1298)	G 209 Chaitra Su 13 (Mahasvayuja Samvat)	—D. C Sircar, <i>SI.</i> Bk III no. 50 pp 374-77, B. Upadhyaya, <i>SAII</i> pt. II p 93-94. R. B Pandey, <i>H.I.I.</i> (1962) pp 109-111.	

2C MAHARAJAS OF UCHCHHAKALPA

JAYANATHA

74	KARITALAI (JABALAPUR, M.P) PLATES OF MAHARAJA JAYANATHA ISSUED FROM UCHCHHAKALPA. (<i>Fl. No.</i> 26, <i>Bh No.</i> 1194)	K (?) 174 Ashadha di 14	—Hiralal, <i>Inscrs in C.P and Berar</i> , p. 22-23 no 32.	The date is taken to be the Kalachuri era by Kiel horn & Fleet, See <i>IA</i> Vol XVIII (1888) pp. 215 ff. & <i>IA</i> Vol. XIX (1890) pp 227 f While G H. Ojha (<i>An Rep. Rajaputana Museum, Ajmer</i> 1923-24, p. 2) & Dubreuil [<i>IA</i> Vol. LV. (1926) p 103] take it as Gupta era.
----	--	-------------------------------	--	--

Sl. No.	Inscriptions	Date	References	Remarks
				To Bhandarkar it seems Kalachuri era (See <i>Bh. List</i> p. 159 fn. 5) D.C. Sircar intends to take it as Gupta era (See <i>Sl.</i> p. 370 fn. 1)
75.	KHOHA (NAGAUDH, M.P.) PLATES OF MAHARAJA JAYANATHA (<i>Fl. No</i> 27, <i>Bh No</i> 1195)	K (?) 177 Chaitra di 22	—	Do
<i>SARVANATHA</i>				
76.	SOHAVALA (BAGHILLKHANDA, M.P. NOW AJMER MUSEUM) PLATES OF MAHARAJA SARVANATHA (<i>Bh No</i> 1196)	K 191 As- ha dha di. 10	G H Ojha, <i>An Rep. Rajputana Museum, Ajmer</i> , 1923-24, p. 2, Haldar, <i>LI Vol XIX</i> (1927-28) pp. 127 ff & Pl., <i>IE. AR</i> 1955-56 p 21 no. 76 App A.	Do
77.	KHOHA PLATE OF MAHARAJA SARVANATHA (<i>Fl No</i> 28, <i>Bh No</i> 1197)	K (?) 193 Chaitra di. 10	— D C Sircar, <i>SI Bk III</i> no 49 pp 370-73 (date is referred to in Gupta era)	Do (First plate on outside contains a cancelled inscr. of the same prince)
78.	KHOHA (M.P.) SECOND PLATE OF MAHARAJA SARVANATHA (<i>Fl No</i> 30, <i>Bh No.</i> 1198)	K (?) 197 Asvayuja Māsa di. 20	—	As in case of no 74
79.	KHOHA PLATES OF MAHARAJA SARVANATHA (<i>Fl No.</i> 31, <i>Bh. No</i> 1201)	K (?) 214 Pasha Māsa divase (shthe)	—	Do.
80.	KHOHA (NAGAUDH, M.P.) PLATE OF MAHARAJA SARVANATHA (<i>Fl. No.</i> 29, <i>Bh. No.</i> 1702)	—	—	Do.

2 D. RAJAS OF SARABHAPURA

NARENDRA

81.	PIPARDULA COPPER-PLATE OF NARENDRA	R. Y. 3 Mārgga- śrīsha di. 10	D.C. Sircar, <i>IHQ.</i> Vol XIX (1943) pp. 139-46 & pl.; S.D. Chaturvedi, <i>IHQ.</i> Vol XIX (1943) pp. 358-59.	
-----	------------------------------------	-------------------------------------	---	--

Sl. No.	Inscriptions	Date	References	Remarks
82.	KURUD COPPER-PLATE INSCRO. OF NARENDRA	R. Y. 24 Vaisākha di. 4	S L. Katarc & B. C. Jain, <i>JBRIS</i> Vol. XLII (1956) pp. 330-32 & Pl.; M. G. Dikshit, <i>El.</i> Vol. XXXI (1955-56) pp. 263-66 & Pl; D. C Sircar, <i>El.</i> Vol XXXI (1955-56) pp. 267-8, <i>I. Arch.</i> 1957-58 p. 57 No 22.	
JAYARAJA				
83.	ARANGA (RAIPUR, M.P. NOW NAGPUR MUSEUM) PLATES OF MAHAJAYARAJA (<i>Fl. No. 40, Bh. No. 1878</i>)	R. Y. 5 Mārggasira 25	—Hiralal, <i>Inscrs. in C. P. and Berar</i> , p. 105 no. 175, <i>I. Arch.</i> 1957-58 p. 57 no. 20; <i>IE. AR</i> 1955-56 p. 18 No. 49 App A.	
84.	MALLAR PLATES OF JAYARASA	R. Y. 5 Kārttika di. 5	<i>IE. AR.</i> 1958-59 p 26 no 5 App. A; D C. Sircar, <i>El.</i> Vol. XXXIII (1959-60) pp. 155-58 & Pls.	
85.	SIRPUR PLATES OF JAYARAJA	R.Y.5 Dvī- Bhādra di.	L.P. Pandey, <i>IHQ.</i> Vol X (1934) pp. 100-103 & Pls	The inscr. has the name Sudevarāja while the seal of the inscr. bears the name of Jayarāja.
86.	MALLAR (BILASPUR, M.P.) PLATES OF JAYARAJA	R.Y. 9 Jyeshtha di.5	<i>I Arch.</i> 1958-59 p. 60 no. 24 first set; <i>IE. AR</i> 1958-59 p. 27 no. 8 App. A; G. Bhattacharya & M. Sivayya, <i>El.</i> Vol. XXXIV (1961-62) pp 28-31 & Pls.	
PRAVARARAJA I				
87.	MALLAR (BILASPUR, M.P.) PLATES OF VYAGHRARAJA OF THE REIGN OF PRAVARARAJA I	R. Y. 41 (?) Jyeshthaḥ [m*] ṅghe (he) na	<i>I. Arch.</i> 1958-59 p. 60, no. 24 & Pl. LXIX-LXX (3rd set); <i>IE. AR.</i> 1958-59 p 26 no. 6 App. A; D. C. Sircar & G. Bhattacharya, <i>El.</i> Vol. XXXIV (1961-62) pp. 45-50 & pls.	The inscr. was issued by the younger brother of Pravararāja I and is engraved in nail headed variety of South Indian characters. The Inscr. is unique and gives a new genealogy of Sarabhapuriyas.

Sl. No.	Inscriptions	Date	References	Remarks
SUDEVARAJA				
88.	KHARIAR (RAIPUR DIST. M.P.) NOW NAGPUR MUSEUM PLATES OF MAHA-SUDEVARAJA	R. Y. 2 Sravana di. 29	Sten Konow, <i>EI</i> Vol. IX (1907-8) pp. 170-73 & Pls.; Hiralal, <i>Inscrs in C.P. and Berar</i> , p. 106 no. 177; <i>IE. AR.</i> 1955-56 p. 18 no. 50. App. A.	
89.	SIRPUR PLATES OF MAHA-SUDEVARAJA	R. Y. 7 Dvi-Bhādra 10	Hiralal, <i>Inscrs. in the C.P. and Berar</i> , p. 106-A No. 177 (b); <i>IE. AR.</i> 1945-46 p 12 no. 52 App. A; & L. P. Pandey, <i>Mahakosala Historical Society Papers</i> , Vol. II, 1937, pp 42-43; S. L. Katarc, <i>EI.</i> Vol. XXXI (1955-56) pp. 103-108 & Pl.	
90.	KAUVATALA PLATES OF SUDEVA	R. Y. 7 Mārgga- rsha di. 10	L. P. Pandey, <i>IHQ.</i> Vol. XXI (1945) 294-95 & Pl.; D. C. Sircar, <i>IHQ</i> Vol. XXII (1946) pp. 62-63; <i>AI.</i> no. 5 p. 49, <i>IE. AR.</i> 1945-46 p 12 No. 53 App. A. & Pl.; A. N. Lahiri, <i>EI.</i> Vol. XXXI (1955-56) pp 314-16	
91.	ARANGA PLATES OF MAHA-SUDEVARAJA	R. Y. 8 Vaiśākha di. 29	Hiralal, <i>Inscrs. in C. P. & Berar</i> (2nd Edn) p. 106-A no. 177a; L. P. Pandey <i>EI</i> Vol. XXIII (1935-36) pp. 18-22 & Pl.	Sircar reads the date 7.
92.	RAIPUR (M.P. NOW NAGPUR MUSEUM) PLATES OF MAHA-SUDEVARAJA (<i>Fl.</i> No. 41, <i>Bh.</i> No 1880)	R. Y. 10 Magha 9	—Hiralal, <i>Inscr in. C. P. and Berar</i> , p. 106 No. 176; <i>IE. AR.</i> 1955-56 p. 19 no. 51 App. A.	
93.	SARANAGADHA (M.P.) PLATE OF SUDEVARAJA (<i>Bh.</i> No. 1881)	—	R. L. Mitra, <i>JASB</i> Vol. XXXV (1866) pp. 195 ff.; Hiralal, <i>EI.</i> Vol IX (1907-8) pp 281-85 & Pl., & <i>Inscrs in C.P. and Berar</i> p. 181 no. 310; L. P. Pandeya Sharma, <i>POC.</i> V. (1928) Vol. I, pp. 456-464 & Pl (of only inner side of the first plate).	
94.	POKHARA (CHATTISGARH, M.P.) INCOMPLETE GRANT of (SUDEVARAJA ?)	—	M. G. Dikshit, <i>IHQ.</i> Vol. XXXIII (1957) pp. 84-85 & Pl., <i>IE. AR.</i> , 1957-58 p. 15 no. 25 App. A.	The name of the issuer is not present in this plate.

Sl. No.	Inscriptions	Date	References	Remarks
<i>PRAVARARAJA II</i>				
95.	GHAKURDIYA COPPER PLATES OF MAHA-PRAVARARAJA.	R. Y. 3 Mārgga-sirsha di. 2.	V. V. Mirashi, <i>EI</i> . Vol. XXII (1933-34) pp. 15-23 & Pl.; L. P. Pandey Sharma, <i>JAHRS</i> . Vol. IX (1934) pt. II pp. 29-32.	
96.	MALLAR (BILASPUR DIST. M P) PLATES OF PRAVARARAJA.	R. Y. 3 Pausha di. 2.	B. C. Jain, <i>JIH</i> . Vol. XXXVII (1959) pp. 261-66 & Pls.; <i>I. Arch</i> 1958-59 p. 60 no. 24. <i>Second set, IE AR</i> , 1958-59 p. 26 no 7 App. A , G. Bhattacharya, <i>EI</i> Vol XXXIV (1961-62) pp 51-52 & Pls	

**3. INSCRIPTIONS OF THE HUNAS AND OTHER CONTEMPORARY POWERFUL
DYNASTIES RELEVANT TO GUPTA HISTORY**

Sl. No.	Inscriptions	Date	References	Remarks
3A. TORAMANA AND MIHIRAKULA				
<i>TORAMANA</i>				
97.	KUR (SALT RANGR, PANJAB NOW LAHORE MUSEUM) INSCR OF THE REIGN OF TORAMANA SHAH (<i>Bh</i> No. 1809)	Mārgasira Sukla 2.	Buhler, <i>Et.</i> Vol. I (1892) pp 239 ff. & Pl.; D. C. Sircar, <i>SI. Bk.</i> III. no 56 pp. 398-99, B Upadhyaya, <i>SAII.</i> pt II, pp 107-8.	
98	ERANA (SAUGOR DIST. M.P.) STONE BOAR INSCR OF TORAMANA (<i>Fl</i> No. 36, <i>Bh.</i> No 1877)	R. Y. 1. Phalgana di. 10.	—Himalal, <i>Inscrs. in C P. and Berar</i> , p. 48 no. 81, D. C. Sircar, <i>SI Bk</i> III. No 55 pp. 396-7; B. Upadhyaya, <i>SAII</i> pt. II p. 107; D. B. Diskalkar, <i>JBBRAS. (NS.)</i> Vol II (1926) pp. 180-82: R.B. Pandey, <i>H.I.</i> (1962) pp. 138-39.	
<i>MIHIRAKULA</i>				
99	GWALIOR FORT (M.P. NOW INDIAN MUSEUM CALCUTTA) INSCR OF MIHIRAKULA (<i>Fl.</i> No 37, <i>Bh.</i> No. 1869 & 2109)	R. Y 15 Kārttika Māsa	—D.C. Sircar, <i>SI. Bk.</i> III. no. 57 pp. 400-402, <i>AR. Arch. Dept. Gwalior State</i> , Samvat 1986 no. 43; <i>Gwalior Rājyo Adhulekha</i> no. 616; B. Upadhyaya, <i>SAII.</i> pt. II. pp. 108-9, R. B. Pandey, <i>H.I.</i> (1962) pp. 139-41.	
3B INSCRIPTIONS OF THE VAKATAKA FAMILY				
<i>MAIN BRANCH (3 B.)</i>				
<i>RUDRASENAI</i>				
100	DEOTEK STONE SLAB INSCR. OF RUDRASENA I (NOW NAGPUR MUSEUM)	—	V. V. Mirashi, <i>POC</i> , VIII (1935) pp. 613-22 & Pl.; <i>IE. AR.</i> 1946-47 p. 31 no. 165 App. B.; <i>IE. AR.</i> 1958-59 p. 45 no. 172 App. B.; V. V. Mirashi, <i>S. Ind.</i> Vol. I (1960) pp 109-117 & Pl.	

Sl. No.	Inscriptions	Date	References	Remarks
PRITHVISHENA I				
101.	NACHANE KI TALAI (BUN- DHLAKHANDA DIVISION M.P.) INSCR. OF PRITHVISHENA I AND HIS FEUDATORY VYA- GHRADEVA. (<i>Fl. No. 53 & 54, Bh. No. 1709</i>)	—	—	
102.	GANJA (AJAYAGADHA M.P.) INSCR. OF THE TIME OF PRITHVISHENA I (<i>Bh. No 1710</i>)	—	R. D. Banerji, <i>PRAS. Wc.</i> 1918-19 p. 45., Sukthankar, <i>EI. Vol. XVII</i> (1923-24) pp 12-14 & Pl.; K. N. Dikshit, <i>EI. Vol. XVII</i> (1923-24) p. 362; G. Ramdas, <i>JAHRS.</i> Vol. I (1926-27) pt. IV pp. 228-31.; Prof. G. J. Dub- reuil, <i>JAHRS. Vol II</i> (1927- 28) pt. III-IV p. 259.	
103.	A NEW INCOMPLETE COPPER PLATE INSCR. OF VAKATAKA (RUDRASENA II) ?	—	J. M. Nanavati, <i>JOI. Vol. X</i> (1960-61) p. 208 & Pl.	
PRABHAVATIGUPTA				
104.	POONA COPPER PLATE INSCR. OF PRABHAVATIGUPTA (<i>Bh. No 1703</i>)	R. Y. 13 Kārttika Su 12	Pathak, <i>JA. Vol XLI</i> (1912) pp. 214 f., Smith, <i>JRAS</i> 1914 pp. 317 ff; Pathak & Dikshit, <i>FII. Vol. XV</i> (1919- 20) pp. 41 f. & Pl.; D. C. Sir- car, <i>SI Bk. III. No. 60</i> pp. 411-15.; B. Upadhyaya, <i>SAII. pt. II. pp. 120-21.</i> ; Hiralal, <i>Inscr. in C. P. & Berar</i> , p. 3 No. 4; R B Pan- dey, <i>HLL. (1962) pp. 113-14</i>	
PRAVARASENA				
105.	KOTHURAK GRANT OF PRA- VARASENA II.	R. Y. 2 Āśvayuja Māsa Su. 12	V. V. Mirashi, <i>EI Vol. XXVI</i> (1941-42) pp. 155-61 & Pl.	
106.	BFLORA (DIST. WARDHA) INCOMPLETE GRANT OF PRA- VARASENA II	R. Y. 11 Kārttika Sukla 13	V. V. Mirashi, <i>EI. Vol. XXIV</i> (1937-38) pp. 265-67 & Pl.	
107.	CHAMMAKA (DIST. ILICHA- PUR, M. P.) INSCR. OF PRA- VARASENA II (<i>Fl. No. 55, Bh No. 1704</i>)	R. Y. 18 Jyeshṭha Su. 13	—Hiralal, <i>Inscr. in C. P. & Berar</i> , p. 139 No. 242.; D. C. Sircar, <i>SI. Bk. III. No. 62</i> , pp. 418-25; B. Upa- dhyaya, <i>SAII. pt. II pp. 122-25.</i>	

Sl. No.	Inscriptions	Date	References	Remarks
108.	SIWANI (M. P.) PLATE INSCR. OF PRAVARASENA II (<i>Fl. No. 56, Bh. No. 1705</i>)	R. Y. 18 Phālguna Su. 12	—Hiralal, <i>Inscrs. in C. P. & Berar</i> , p. 69 no. 126; V. V. Mirashi, <i>NUJ</i> . Dec. 1935 no. I pp. 1-3.	
109.	RITHAPURA (AMARAUTI, VIDARBHA) PLATE INSCR. OF PRABHAVATI GUPTA OF THE TIME OF PRAVARASENA II (<i>Bh. No. 1706</i>)	R. Y. 19 Kārttika Sukla 12	Hiralal, <i>Inscrs. in C. P. & Berar</i> , p. 139 no. 241; Gupte <i>IA</i> Vol. LIII (1924) p. 48; & <i>JPASB</i> . (NS). Vol. XX (1924) pp. 53-62 & Pls. ; & <i>JRAS</i> . 1924 pp. 94-96.; Jagan Nath, <i>JUPHS</i> . Vol. XIII (1940) pt. II pp. 97-98 & PIHC. IV (1940) pp. 58-59; D. C. Sircar, <i>SI Bk. III</i> , no. 61 pp. 415-18; B. Upadhyaya, <i>SAII</i> . pt. II. pp 121-22.	
110.	PANDHURNA (NAGPUR DIST) GRANT OF PRAVARASENA II.	R. Y. 20	<i>I. Arch.</i> 1957-58 p. 56 no. 17	Only reference to its discovery.
111.	INDORF (M. P.) INCOMPLETE PLATE OF PRAVARASENA II	R. Y. 23 Vaiśākha ba. 5	Sushil K. Bose, <i>EI</i> . Vol. XXIV (1937-38) pp. 52-56 & Pls.; <i>IE. AR.</i> 1957-58 p. 16 no. 29 App. A, R. B. Pandey, <i>HJI</i> (1962) pp. 118-20.	
112.	DUDJA (CHHINDAWADA DIST. M. P.) INSCR. OF PRAVARASENA II (<i>Bh. No. 1707</i>)	R. Y. 23	Kielhonn, <i>EI</i> . Vol. III (1894-95) pp. 260 ff. & Pl.; Hiralal, <i>Inscrs. in C. P. & Berar</i> , p. 93 no. 168.	
113.	TIRODI PLATES OF PRAVARASENA II	R. Y. 23 Māgha ba. 12	V. V. Mirashi, <i>EI</i> . Vol. XXII (1933-34) pp. 167-76.	
114.	CHICHOLI OR WADGAON PLATES OF PRAVARASENA II (NOW IN PRINCE OF WALES MUSEUM BOMBAY)	R. Y. 25 Jyeshtha Sukla 10	S. N. Chakravarty, <i>JBBRAS</i> . (NS.) Vol. XXII (1946) pp. 49-54 & Pls. ; V. V. Mirashi, <i>EI</i> . XXVII (1947-48) pp. 74-79 & Pl.	
115.	PATTANA PLATES OF PRAVARASENA II	R. Y. 27 Kārttika ba. 7	V. V. Mirashi, <i>EI</i> . Vol. XXIII (1935-36) pp. 81-88 & Pls. ; & <i>NUJ</i> . no. 2, Dec. 1936, pp. 54-6.	
116.	COPPER PLATE OF VAKATAKA PRAVARASENA II (FROM SUPERINTENDENT, TEMPLE SURVEY PROJECT, NORTHERN REGION, BHOPAL, THROUGH B. CH. CHHABRA)	R. Y. 29 Vaiśākha ba. 10	<i>IE AR.</i> 1957-58 p. 15 no. 24 App. A.	

Sl. No.	Inscriptions	Date	References	Remarks
117.	BELORA (WARDHA DIST.) INCOMPLETE GRANT INSCR. OF PRAVARASENA II	—	V. V. Mirashi, <i>EI</i> . Vol. XXIV (1937-38) pp. 260-65 & Pl.	
118.	PATANA (BIHAR) MUSEUM SINGLE PLATE (ORIGINALLY FROM M. P.) OF PRAVARASENA II (<i>Bh. No.</i> 2095)	—	A. S. Altakar, <i>JBORS</i> Vol. XIV (1928) pp. 465-75.; R. B. Hiralal, <i>Inscr. in C P. & Berar</i> , p. 5., V.V. Mirashi, <i>NUJ.</i> no 2 Dec. 1936 pp 48-50	
119.	MANSAR (NEAR RAMTEKA) COPPER PLATE INSCR. OF PRAVARASENA II	—	V. V. Mirashi, <i>NUJ.</i> no 3 Dec. 1937 pp 20-28 & Pl	R. B. Hiralal intends to associate this plate to the set of Patana Museum plates of the same king. (See <i>Inscr. in C P & Berar</i> , pp. 4-5).

PRITHVISHENA II

120.	BALAGHAT (NAGAPUR) NOW BENGAL ASIATIC SOCIETY'S INCOMPLETE PLATE OF PRITHVISHENA II (<i>Bh. No.</i> 1708)	—	Kailashin, <i>EI</i> Vol IX (1907-8) pp 270 ff & Pl., Hiralal, <i>Inscr. in C P & Berar</i> p 18 no. 26.	
121.	AN UNFINISHED DRUG (M. P.) PLATE (OF VAKATAKA PRITHVISHENA II)?	—	V. V. Mirashi, <i>EI</i> Vol. XXII (1933-34) pp. 207-12	The name of the king is lost but Altakar and Majumdar ascribe this inscr. to be of the Vāk aka Prithvishena II. See list of Inscr. <i>Vākāṭaka-Gupta Age</i> p 477 no. 18

MISCELLANEOUS INSCRIPTIONS

122.	PRIVATE FRAGMENTARY VAKATAKA RECORD FROM AMARAUTI	—	R. P. Chanda, <i>EI</i> . Vol. XV (1919-20) p. 267 no. 27 & Pl. 68.	Altakar and Majumdar assign this inscr. to be of the reign of Vakatakas of main branch See <i>Vākāṭaka-Gupta Age</i> p. 477, no. 19
------	---	---	---	---

Sl. No.	Inscriptions	Date	References	Remarks
123.	AJANTA BUDDHA IMAGE INSCR. OF THE TIME OF VAKATAKAS	—	<i>I. Arch.</i> 1957-58 p. 56 no. 14.	The inscr. was found in cave no. 4 and can be ascribed to Vākāṭaka period.

VAKATAKAS OF BASIM BRANCH (3. B₁)

VINDHYAŚAKTI II

124.	BASIM (VATSAGULMA) COPPER PLATE INSCR. OF VINDHYASAKTI II	R. Y. 37 Hemanta (nta) Paksha, di. 4.	D. C. Sircar, <i>IHQ</i> . Vol. XVI (1940) pp. 182-86; & <i>IHQ</i> Vol. XVII (1941) pp. 110-16; Y. K. Deshpandey and D. B. Mahajane, <i>PIHC</i> (1939) pp. 449-60; & <i>BRVRI</i> . no. 1972 pp. 449-60 & Pl.; V. V. Mirashi, <i>EI</i> . Vol. XXVI (1941-42) pp. 151-55 & pls.; D. C. Sircar, <i>IC</i> Vol. VIII (1941-42) pp. 394-96; & <i>SI</i> . Bk. III no. 59 pp. 406-11 & Pl.; B. Upadhyaya, <i>SAIL</i> , pt. 11, pp. 139-40; R. B. Pandey, <i>HLI</i> (1962) pp. 111-13.	
------	---	---------------------------------------	---	--

DEVASENA

125.	INDIA OFFICE INCOMPLETE PLATE OF VAKATAKA MAHARAJA DEVASENA	—	Randle, <i>NIA</i> . Vol. II (1939-40) pp. 177-180 & Pl.; V. V. Mirashi, <i>NIA</i> . Vol. II (1939-40) pp. 721-23.	
126.	GHATOTKACHA (NIZAM'S DOMINION) CAVE FRAGMENTARY INSCR. OF THE MINISTER OF VAKATAKA KING DEVASENA (<i>Bh. No.</i> 1711)	—	Burgess, <i>ASWI</i> . Vol. IV. pp. 138-40 & Pl. LX; V. V. Mirashi, <i>HAS</i> . no. XVI (1952).	Altaker and Majumdar assign this inscr. to Harishena, son of Devasena. See, <i>Vakataka Gupta Age, List of Vakāṭaka inscrls.</i> p. 477 no. 4.

HARISHENA

127.	AJANTA CAVE (NO. XVI) FRAGMENTARY STONE INSCR. OF HARISHENA (<i>Bh. No.</i> 1712).	—	Burgess, <i>ASWI</i> . Vol. IV. pp. 124-28 & Pl.; A. B. Biswas, <i>IC</i> . Vol. VII (1940-41) pp. 372-76; V. V. Mirashi, <i>HAS</i> .	
------	---	---	--	--

Sl. No.	Inscriptions	Date	References	Remarks
			no. XIV (1941); & PIHC. IV. (1940) pl. facing p. 88 ; V. V. Mirashi, <i>EI</i> . Vol XXVI (1941-42) pp. 142 ff., B. Upadhyaya, <i>SAII</i> pt II pp. 125-29; B. L. Indraji, <i>Inscrs. from the cave temples of Western India</i> pp. 69 ff.: <i>IE. AR</i> 1958-59 p 106 no. 331 App. C, V. V. Mirashi, <i>NUJ.</i> no. 6 (December) 1940 pp. 41 ff.: Sircar, <i>SI. Bk. III</i> No. 63 p. 425 ; R. B. Pandey <i>HLI.</i> (1962) pp. 114-18.	
128.	AJANTA CAVE FRAGMENTARY INSCR. OF A FAMILY OF KINGS SUBORDINATE TO THE VAKATAKAS (?) (<i>Bh. No.</i> 1713)	—	Burgess, <i>ASWI</i> . Vol. IV. pp. 128-32 & pl.; B. L. Indraji, <i>Inscrs. from the cave temples of Western India</i> p. 73 ff	The inscr mentions certain Harishena, perhaps the Vṛkātaka Harishena of Basim Branch.

3 C. MAITRAKAS OF VALABHI

DHARASENA I

129.	BOMBAY ASIATIC SOCIETY'S PLATES OF DHARASENA I (<i>Bh. No.</i> 1078)	S 400 Vaiśākha Pūrṇima	Buhler, <i>IA</i> . Vol. X (1881) pp. 283 ff. & Pl.; J.F. Fleet, <i>IA</i> . Vol. XXXII (1903) pp. 49-52.	Regarded as a spurious plate belonging actually to Dharasena II, the son of Guhasena.
------	---	------------------------------	---	---

DRONASIMHA

130.	BHAMODRA MOHOTA (BHAVANAGAR, KATHIAWAR, NOW PRINCE OF WALES MUSEUM, BOMBAY) PLATE OF DRONASIMHA (<i>Bh. No.</i> 1289)	G. 183 Sṛāvana Suddha 15.	Jackson, <i>JBBRAS.</i> Vol. XX (1897-98) pp. 1-6 & Pl.; Barneit, <i>EI</i> . Vol. XVI (1921-22) p. 17 f. & Pl.; Jagannath Agrawala, <i>PIHC.</i> XVII (1954) pp. 87-88; D. C. Sircar, <i>SI. Bk. III.</i> no. 58 pp. 403-5 ; B. Upadhyaya, <i>SAII.</i> pt. II. pp. 136-37 ; <i>IE. AR.</i> 1956-5/ p. 30 no. 32 App. A.	
------	--	---------------------------------	---	--

DHRUVASENA I

131.	PALITANA (KATHIAWAR) PLATES OF MAHARAJA DHRUVASENA I (<i>Bh. No.</i> 1293)	G. 206 Bhādra- pada śu. 5	Jackson, <i>IA</i> . Vol. XXXIX (1910) p. 129 no. II; Sten Konow, <i>EI</i> . Vol. XI (1911-12) pp. 105-9 Pl.; <i>IE. AR.</i> 1955-56 p. 21 no. 82 App. A.	
------	---	---------------------------------	--	--

Sl. No.	Inscriptions	Date	References	Remarks
132.	CAMBAY (NOW PRINCE OF WALES MUSEUM, BOMBAY), PLATE OF DHRUVASENA I (Bh. No. 1294)	G. 206 Aśvayuja Su. 3	Banerji, <i>PRAS. Wc.</i> 1917-18, p. 36; & <i>PRAS Wc.</i> 1919-20, p. 56, Sukthankar, <i>EI.</i> Vol. XVII (1923-24) pp. 109-10 & Pl.; <i>IE. AR.</i> 1955-56, p. 17 no. 36 App. A.	
133.	MOTA MACHIALA (AMRELI DIST. GUJARAT) COPPER PLATE OF DHRUVASENA I	[G] 206 Aśvayuja Suddha 5	A. S. Gadre, <i>EI.</i> Vol. XXXI (1955-56) pp. 299-301 & Pl.	
134.	PALITANA (NOW PRINCE OF WALES MUSEUM BOMBAY) PLATE OF DHRUVASENA I (Bh. No. 1295)	G. 207 Vaiśākha ba. 5	Banerji, <i>PRAS. Wc.</i> 1918-19 p. 45; Sukthankar, <i>EI.</i> Vol. XVII (1923-24) pp. 105-8 & Pl.; <i>IE. AR.</i> 1955-56 p. 17 no. 33. App. A.	
135.	GANLSGADHA (AMRELI, MAHARASHTRA, NOW BARODA MUSEUM) PLATES OF DHRUVASENA I (Bh. No. 1296)	G. 207 Vaiśākha ba. 15	Hultsch, <i>EI.</i> Vol. III (1894-95) p. 320 & Pl.; <i>IE. AR.</i> 1959-60 p. 37 no. 21 App. A.	
136.	PALITANA PL. OF DHRUVASENA I	G. 207 Kārttika Su. 3	H. G. Shastri, <i>BV.</i> Vol. VI. p. 248; & <i>JOI.</i> Vol. XII (1962-63) pp. 51-54 & Pls.	
137.	BHAVANAGAR (KATHIAWAR) PLATES OF DHRUVASENA I (Bh. No. 1297)	G. 207 Kārttika Su. 7	Buhler, <i>IA.</i> Vol. V. (1876) pp. 204-6 & Pls.	
138.	BHAVANAGAR (NOW PRINCE OF WALES MUSEUM BOMBAY) PLATES OF DHRUVASENA I (Bh. No. 1299)	G. 210 Sravana bahula 13	Banerji, <i>PRAS. Wc.</i> 1917-18 p. 36; Sukthankar, <i>EI.</i> Vol. XV (1919-20) pp. 255 ff. & Pl.; <i>IE. AR.</i> 1955-56 p. 17 no. 32 App. A (Findspot, given here is Kalvan, Nasik dist.).	
139.	PALITANA PLATES OF DHRUVASENA I (Bh. No. 1300)	G. 210 Sravana Su. 15	Jackson, <i>IA.</i> Vol. XXXIX (1910) p. 130, No. III.; Sten Konow, <i>EI.</i> Vol. XI (1911-12) pp. 109-112 & Pl.; <i>IE. AR.</i> 1955-56 p. 21 no. 83 App. A.	
140.	IYAVEJA (KATHIAWAR) PLATES OF DHRUVASENA I (Bh. No. 1301 & 2039)	G. 210 Bhādrapada ba 9	D. B. Diskalkar, <i>Purātattva</i> (Gujarat) Vol. I. pp. 403 ff.; & <i>EI.</i> Vol. XIX (1927-28) pp. 125-27 & Pl.; <i>IE. AR.</i> 1955-56 p. 21 no. 87 App. A.	
141.	PALITANA (NOW PRINCE OF WALES MUSEUM, BOMBAY) PLATES OF DHRUVASENA I (Bh. No. 1591)	—	Banerji, <i>PRAS. Wc.</i> 1918-19 p. 45; Sukthankar, <i>EI.</i> Vol. XVII (1923-24) pp. 108-9 & Pl.; <i>IE. AR.</i> 1955-56 p. 17 no. 34 App. A.	This is the first half of the plates of Dhruvasena I noticed in

Sl. No.	Inscriptions	Date	References	Remarks
				No. 1301 and 2039 of Bhandarkar's List.
142.	PRINCE OF WALES MUSEUM (BOMBAY) PLATES OF DHRUVASENSA I (<i>Bh. No.</i> 1302)	G. 210 Bhadrapada ba. 13	G. V. Acharya, <i>JBBRAS.</i> (NS) Vol. I (1925) pp. 65-66.	
143.	PALITANA PLATES OF DHRUVASENSA I (<i>Bh. No.</i> 1303)	G. 210 Asvayuja ba. 5.	Jackson, <i>IA</i> Vol. XXXIX (1910) p. 130 no. IV ; Sten Konow, <i>EI.</i> Vol. XI (1911-12) pp. 112-14 & <i>Pl.</i> ; <i>IE. AR.</i> 1955-56 p. 21 no. 84 App. A.	
144.	WALA (KATHIAWAR) PLATES OF DHRUVASENSA I (<i>Bh. No.</i> 1304)	G. 216 Magha badi 3(?)	Buhler, <i>IA.</i> Vol. IV (1875) p. 105.	
145.	BRITISH MUSEUM PLATES OF DHRUVASENSA I (<i>Bh. No.</i> 1305)	G. 217 Asvayuja ba. 13	Bloch, <i>JRAS.</i> 1895. pp. 379-84.	The name of the place from where this grant was issued is illegible
146.	VAVADIYA—JOGIA (JUNAGADH) PLATES OF DHRUVASENSA I (<i>Bh. No.</i> 1306)	G. 221 Asvayuja ba. 1	Vallabhji Haridatta, <i>VOJ.</i> Vol. VII. p. 297.	
147.	WALA MUSEUM PLATES OF DHRUVASENSA I (<i>Bh. No.</i> 1308)	G. 226 (228?) Karttika Su. 15	Diskalkar, <i>AR. of Watson Museum, Rajkot</i> (1922-23) p. 9 (dated read as 228); & <i>JBBRAS.</i> (NS.) Vol. I (1925) pp. 16-18.	
148.	PALITANA PLATE OF DHRUVASENSA I (<i>Bh. No.</i> 1592)	—	Jackson, <i>IA.</i> Vol. XXXIX (1910) p. 130, no. VI; Sten Konow, <i>EI.</i> Vol. XI (1911-12) p. 114-15; D. B. Diskalkar, <i>JBBRAS.</i> (NS.) Vol. I (1925) p. 18-19; <i>IE. AR.</i> 1955-56 p. 21 no. 85 App. A.	The second plate giving the date and details of the grant is missing.
149.	PLATES OF MAITRAKA MAHARAJA DHRUVASENSA I (<i>Bh. No.</i> 2078)	—	Vats, <i>EI.</i> Vol. XIX (1927-28) pp. 302 ff.; <i>IE. AR.</i> 1955-56 p. 17 no. 35 App. A.	
150.	FIRST PLATE OF A GRANT OF DHRUVASENSA I <i>GUHASENA</i>	—	D. B. Diskalkar, <i>JBBRAS.</i> (NS.) Vol. I (1925) p. 20-21.	
151.	PLATES OF MAHARAJA GUHASENA (<i>Bh. No.</i> 1311)	G. 240 (? 237) Sravana su.	Buhler, <i>IA.</i> Vol. VII (1878) pp. 66-68 & Pl.	The place name from which it was issued is illegible.

Sl. No.	Inscriptions	Date	References	Remarks
152.	WALA (KATHIAWAR, NOW BRITISH MUSEUM) PLATE OF GUHASENA (<i>Bh. No.</i> 1312)	G. 246 Magha (badi)	Buhler, <i>IA</i> . Vol. IV (1875) pp 174 ff.; Barnett, <i>EI</i> . Vol. XIII (1915-16) pp. 338-40 & Pl.	
153.	WALA SECOND PLATE ONLY OF GUHASENA (<i>Bh.No.</i> 1313)	G. 246 Magha (badi?)	Buhler, <i>IA</i> . Vol. IV (1875) pp. 174 ff.	Seems to be identical with above plate. See <i>Bh. List</i> p. 179 fn. 4.
154.	WALA FRAGMENTARY INSCR. CONTAINING THE NAME OF GUHASENA (OF VALABHI) (<i>Bh No.</i> 1314)	G (2) 47	Buhler, <i>IA</i> . Vol. XIV (1885) p.75 & Pl.	
155.	BHAVANAGAR SECOND PLATE OF GUHASENA (<i>Bh. No.</i> 1315)	G. 248 Asvayuja bahale 10 (?)	Buhler, <i>IA</i> . Vol. V (1876) pp. 206-7 & Pl.	On the first plate only a few words are legible. Buhler read the date 14th day of the dark demilunation of Asvayuja of Samvat 268
156	BANKODI (JAMANAGAR, KATHIAWAR, NOW BHAVANAGAR MUSEUM) FRAGMENTARY INSCR. CONTAINING THE NAME GUHASENA (OF VALABHI) (<i>Bh. No.</i> 1593)	—	— <i>Bhavanagar inscra.</i> p. 30 & Pl.	

DHARASEN II

157.	JHAR (AMRELI. DIST. BARODA) PLATES OF DHARASENA II (<i>Bh. No.</i> 1316)	G. 252 Chaitra ba. 5	<i>Bhavanagar Inscra.</i> pp. 31 ff & Pls.; Fleet, <i>IA</i> . Vol. XV (1886) p. 187.	
158.	BHADAVA (KATHIAWAR) PLATES OF DHARASENA II (<i>Bh. No.</i> 1317)	G. Val. 252 Vaisakha ba. 15	Discalkar, <i>ABI</i> . Vol. IV (1923) pp. 34-41 & Pl.: <i>IE. AR.</i> 1959-60 p. 41 no. 45 App A.	
159.	PALITANA (KATHIAWAR) PLATES OF DHARASENA II (<i>Bh. No.</i> 1318)	(G.) 252 Vaisakha ba. 15	Jackson, <i>IA</i> . Vol. XXXIX (1910) p. 130, no. V; Hultzsch, <i>EI</i> . Vol. XI (1911-12) pp. 80 ff.; <i>IE. AR.</i> 1955-56 p. 21 no. 81 App. A.	
160.	MALIYA (JUNAGADH) PLATES OF DHARASENA II (<i>Fl. No.</i> 38, <i>Bh. No.</i> 1319)	G. 252 Vaisakha ba. 16.	—V. Lakshminarayan, <i>PIHC.</i> VIII (1945) pp. 25-26,	

Sl. No.	Inscriptions	Date	References	Remarks
161.	SORATHA (JUNAGADH) PLATES OF DHARASENA II (Bh. No. 1320)	G. 252 Vaisakha ba. 15	Buhler, <i>IA</i> . Vol. VII (1878) pp. 68-70 & Pl.	
162.	BOMBAY ASIATIC SOCIETY'S PLATE OF DHARASENA II ISSUED FROM VALABHI (Bh. No. 1321)	G. 252 Vaisakha ba. 15	Fleet, <i>IA</i> . Vol. VIII (1879) pp. 301-5 & Pl.	
163.	KATAPUR (NOW BHAVANAGAR MUSEUM) PLATES OF DHARASENA II (Bh. No. 1322)	G. 252 Vaisakha badi 15	<i>Bhavanagar Inscrs.</i> pp. 35 ff. & Pl.; <i>IE. AR.</i> 1959-60 p. 38 no. 32 App. A.	
164.	MOTA MACHIALA (AMARELI DIST. GUJARATA) COPPER PLATE OF DHARASENA II	G. 252 Vaisakha ba. 15	A. S. Gadre ; <i>EI.</i> Vol. XXXI (1955-56) pp. 301-304 & Pl	
165.	INDIA OFFICE (LONDON) PLATES OF DHARASENA II	G. 252 Chaitra	<i>Prakrita & Sanskrit Inscrs. of Kathiawada</i> pp. 30 ff. & Pl.; <i>IE. AR.</i> 1952-53 p. 81 no. 569 App. B.	
166.	BANIYA (?) (KATHIAWAR) PLATES OF (THE MAITRAKA) DHARASENA II (Bh. No. 1324)	G. 257 or 254	Diskalkar, <i>AR Watson Museum, Rajkot</i> , 1925-26 pp. 13 ff.; & A.R. of Watson Museum, Rajkot, 1926-7) pp. 13 f.; & <i>JBBRAS. (NS.)</i> Vol. III (1927) pp. 184-85; & <i>EI</i> Vol. XXI (1931-32) pp. 179 ff.; D N. Mookerji, <i>JIH.</i> Vol. XXV (1947) pp. 33-38; <i>IE AR.</i> 1956-57 p. 30 no. 36 App. A (date transcribed 254).	NOTE :— The date refers to a solar eclipse [the 15th day of the dark half of Vaisakha of Gupta-Valabhi) Samvat 257, when there was Suryaoparage]. It is doubtful if the date has been correctly read, because in the month of Vaisakha there was no solar eclipse from 574 to 591 A. D. See <i>Bh. List</i> p. 189 fn. 2.
167.	WALA (KATHIAWAR) PLATES OF DHARASENA II (Bh. No. 1326)	G. 269 Chaitra ba. 2	Buhler, <i>IA</i> . Vol. VI (1877) pp. 9-12; B. Upadhyaya, <i>SAII.</i> pt. II. pp. 137-39.	
168.	PRINCE OF WALES MUSEUM (BOMBAY) PLATES OF DHARASENA II (Bh. No. 1327)	G. 270 Magha Su. 10	G. V. Acharya, <i>JBBRAS. (NS.)</i> Vol. I (1925) pp. 66-69.	

Sl. No.	Inscriptions	Date	References	Remarks
169.	ALINA PLATES OF DHARASENA II (<i>Bh. No.</i> 1328)	G. 270 Phalguna ba. 10	Buhler, <i>IA.</i> , Vol. VII (1878) pp. 70-73 & Pl.	
170.	THE WATSON MUSEUM PLATES OF DHARASENA II.	G. 270 (?) Bhadra, Badi. 2	A. S. Gadre, <i>AR. of Watson Museum, Rajkot</i> , 1934-35 p. 19; & <i>IHQ</i> Vol. XV (1939) pp. 281-87 & Pl. ; & <i>PIHC</i> II (1938) pp. 137-40.	M1 Gadre read the date firstly 250 or 260 and now 270.
171.	WALA PLATES OF DHARASENA II (<i>Bh. No.</i> 1594)	--	Diskalkar, <i>JBBRAS.</i> (NS.) Vol I (1925) pp. 21-24.	
172.	PITHADIA GRANT (NOW WATSON MUSEUM RAJKOT) OF DHARASENA II	--	A. S. Gadre, <i>JUB.</i> Vol. IV (1935-36) pt. I pp. 1-5.	
173.	WATSON MUSEUM (RAJKOT) PLATES OF DHARASENA II	--	<i>IE. AR</i> 1959-60 p 41 no. 47 App. A.	Only First Plate.
174.	WALA FIRST PLATE OF DHARASENA II (?) (<i>Bh. No.</i> 1595)	--	Diskalkar, <i>JBBRAS.</i> (NS.) Vol. I (1925) pp 24-26	

SILADITYA I

175.	WALA (KATHIAWAR) PLATE OF SILADITYA (I) DHARMADITYA (<i>Bh. No.</i> 1330)	G. 286 Vaisakha Va (?) 6	R G. Bhandarkar, <i>IA.</i> Vol. I (1872) p. 46	
176.	WALA (NOW BOMBAY ASIATIC SOCIETY) PLATES OF SILADITYA (I) DHARMADITYA (<i>Bh. No.</i> 1331)	G. 286 Jyeshtha ba 6	Mandalika, <i>JBBRAS.</i> Vol. XI (1975) pp. 359 ff., Kailhorn, <i>IA.</i> Vol XIV (1885) pp. 329 f. & Pls	So far as we know this the ear. List Valubhi inscr. which, in introductory, passage has the reading <i>sampanna</i> , instead of <i>Sampatha</i> of the earlier inscs. (<i>Bh. List.</i> p. 181. fn. 4).
177.	NAVALAKHI (JUNAGADH NOW BAHA MUSEUM JUNAGADH) PLATES OF SILADITYA (I) DHARMADITYA (<i>Bh. No.</i> 1332)	G. 286 Ashadha ba. 8	Bhandarkar, <i>EI.</i> Vol XI (1911-12) pp. 174 ff & Pl; <i>IE. AR.</i> 1955-56 p. 21 no. 80 App. A.	
178.	WALA SECOND PLATE OF SILADITYA (I) DHARMADITYA (?) (<i>Bh. No.</i> 1933)	G. 286 Sravana ba. 7	Diskalkar, <i>AR. Watson Museum, Rajkot</i> 1922-23 pp 9 ff. & <i>JBBRAS.</i> (NS.) Vol. I (1925) pp. 26-28.	

Sl. No.	Inscriptions	Date	References	Remarks
179.	PALITANA PLATE OF SILADITYA (I) DHARMADITYA (<i>Bh. No. 1334</i>)	G. 286	Jackson, <i>IA</i> . Vol. XXXIX (1910) p. 130 no. VII; Sten Konow, <i>EL</i> . Vol XI (1911-12) pp. 115-18; <i>IE. AR.</i> 1955-56 p. 21 no. 86 App.	This is the first plate of a grant issued by Siladitya I, of which, according to Sten know, the second plate is that transcribed in <i>IA</i> . Vol. I (1872) p. 46. (See <i>Bh. No.</i> 1330).
180.	WALA MUSEUM PLATES OF SILADITYA (I) DHARMADITYA (<i>Bh. No. 1335</i>)	G. 287 Marg Sirsha vadi 7	Diskalkar, <i>AR.</i> <i>Watson Museum, Rajkot</i> , 1922-23 p. 10; & <i>JBBRAS (NS)</i> Vol. I (1925) pp. 28-31.	
181.	WALA GRANT OF SILADITYA (I) DHARMADITYA	G. 287 Karttika vadi 7	A. S. Gadre, <i>JUB</i> . Vol. III (1934-35) pt. I. pp. 80-82 & Pls.; D. C. Sircar & A. S. Gadre (Notes & Answer), <i>JUB</i> . Vol. IV. (1935-36) pt. I pp. 175-77; <i>IE. AR.</i> 1959-60 p. 39 No. 37 App A	
182.	DHANKA (NOW WATSON MUSEUM RAJKOT) PLATES OF SILADITYA (I) DHARMADITYA (<i>Bh. No. 1338</i>)	G. 290 Bhadrapada ba. 8	Buhler, <i>IA</i> . Vol. IX (1880) pp. 238 f. & Pl.	
183.	WALA COPPER PLATE GRANT OF SILADITYA (I) DHARMADITYA	G. Val 290 Bhadrapada badi 7	A. S. Gadre, <i>JUB</i> . Vol. III (1934-35) pt. I. pp. 82-85 & Pls., D. C. Sircar & A. S. Gadre (Notes & Answer), <i>JUB</i> Vol IV (1935-36) pt. I. pp. 175-77, <i>IE. AR.</i> 1959-60 p. 40 no. 39 App A.	
184.	WALA COPPER PLATE OF SILADITYA (I) DHARMADITYA	G. Val. 290 Bhadrapada Sukla 10	A. S. Gadre, <i>JUB</i> . Vol III, (1934-35) pt. I. pp. 85-87 & Pls., D. C. Sircar & A. S. Gadre (Notes & Answer), <i>JUB</i> . Vol IV (1935-36) pt. I pp. 175-77; <i>IE. AR.</i> 1959-60 p. 39 no. 38 App. A.	
185.	BHADRENIYAKA (NOW PRINCE OF WALES MUSEUM, BOMBAY) PLATES OF SILADITYA (I) DHARMADITYA (<i>Bh. No. 1337</i>)	G. 290 or 292 (?) Chaitra Su. 14	Banerji, <i>PRAS. Wc.</i> 1919-20. p.54; & <i>EL</i> . Vol. XXI (1931-32) pp 116-19; <i>IE. AR.</i> 1956-57. p. 29 no. 30 App. A.	Mr. Hira Nanda Sastri and others read the date 292 [See <i>EL</i> Vol. XXI (1931-32 p. 116 fn. 3)].

Sl. No.	Inscriptions	Date	References	Remarks
186.	WALA PLATE OF SILADITYA (1) DHARMADITYA (<i>Bh. No.</i> 1596)	— ba. 7	Diskalkar, <i>AR. of Watson Museum, Rajkot</i> , 1922-23 p. 10; & <i>JBBRAS. (NS.)</i> Vol. I (1925) pp. 31-35.	
187.	FIRST PLATE OF VALABHI GRANT OF (SILADITYA 1?)	—	D. B. Diskalkar, <i>JBBRAS. (NS.)</i> Vol. I (1925) p. 43-44.	

KHARAGRAH I

188.	AMRELI (NOW AMRELI MUS.) PLATE INSCR. OF KHARAGRAH	G. Val. 279 Sravana Sudi 10	<i>IE. AR.</i> 1959-60 p. 34 no. 6 App. A.; A. S. Gadre, <i>Important Inscr. from the Baroda State</i> Vol. I pp. 7 ff.	Kharagraha I is the brother of Siladitya I who is so far supposed to be the son and successor of Dharasena II. Dates known from the grants of Siladitya I range between 286 and 292 while only one grant of Kharagraha was known of the year 297. If the present grant is issued by Kharagraha I it is very interesting because being dated in the year 279 it proves his accession on throne before and also after Siladitya I which may be taken as the sign of some war for succession or political disturbance. Mention of Kharagraha I as <i>dataka</i>
------	--	-----------------------------------	---	--

Sl. No.	Inscriptions	Date	References	Remarks
				in the later grants out of Siladitya I corroborates the conjecture.
189.	THE VIRDI COPPER PLATE OF KHARAGRAHA I	G. 297 Vaisakha Su. 12	A. S. Gadri., <i>PTIOC.</i> VII. (1933) pp. 659-676 & Pls.	The first Grant of Khara-graha I.
DHARASENA III				
190.	BHAVANAGAR (KATHIAWAR) PLATE OF DHARASENA III (<i>Bh. No.</i> 1340)	G. 304 Magha Su. 7	Diskalkar, <i>AR. Watson Museum, Rajkot</i> , 1925-26 p. 14 & <i>A.R. Watson Museum, Rajkot</i> , 1926-27 pp. 14 f.; <i>JBBRAS. (NS.)</i> Vol. III (1927) pp. 185-6; & <i>EI.</i> Vol XXI (1931-32) pp. 179 ff.; <i>IE. AR.</i> 1956-57 p. 30 no. 35 App. A.	
191.	KASANDRA (DASKROI MAHAL OF AHMEDABAD DIST.) PLATES OF DHARASENA III	G. 305 Sravana (Sukla 15)	H. G. Shastri, <i>JUB (NS)</i> Vol. XIX (1950-51) pt. IV. pp. 1-8 & Pls	
192.	GOPANATH (KATHIAWAR) FIRST PLATE ONLY OF VALABHI GRANT, WHICH BREAKS OFF IN THE DESCRIPTION OF DHARASENA II (<i>Bh. No.</i> 1957)	—	Hultsch. <i>I. A.</i> Vol. XII (1883) pp. 148 f.; <i>Bhavanagar Inscrs.</i> p. 64 & Pl.	
DHRUVASENA (II) BALADITYA				
193.	BOTADA (KATHIAWAR, NOW BHAVANAGAR MUSEUM) PLATES OF DHRUVASENA (II) BALADITYA (<i>Bh. No.</i> 1341)	G. 310 Asvyauja ba. 15	Buhler, <i>JA.</i> Vol. VI. (1877) pp. 13-16 & Pl.; <i>Bhavanagar Inscrs.</i> pp. 40 ff. & Pls.; <i>IE. AR.</i> 1959-60 p. 39. no. 33. App. A.	
194.	PRINCE OF WALES MUSEUM PLATES DHRUVASENA II (<i>Bh. No.</i> 1342)	G. 312 Jyeshtha	G. V. Acharya, <i>JBBRAS. (NS)</i> Vol. I (1925) pp. 69-70.	
195.	GORAS (BHAVANAGAR, KATHIAWAR) PLATES OF DHRUVASENA (II) BALADITYA (<i>Bh. No.</i>)	G. Val 313 Sravana Sudi 14	Diskalkar, <i>AR. Watson Museum, Rajkot</i> , 1922-23 p. 12; & <i>JBBRAS. (NS.)</i> Vol. I (1925) pp. 50-57; <i>IE. AR.</i> 1959-60 p. 39. no. 34 App. A.	

Sl. No.	Inscriptions	Date	References	Remarks
196.	WALA PLATES OF DHIRUVA- SENA II	G. Val 319 Jyestha Sudi 7	A. S. Gadre, <i>JUB</i> . Vol. III (1934-35) pt I pp. 88-91 & Pls.; D. C. Sircar & A. S. Gadre (Notes & Answer), b 8 d Vol. pt. I, pp. 175-77; <i>IE. AR.</i> 1959-60 p. 40 no. App. A.	
197.	BHAMODRA MOHOTA (BHAVA- NAGAR, KATHIAWAR) PLATE OF DHIRUVASENA (II) BALA- DITYA. (<i>Bh. No.</i> 1345)	G. 320 Ashadha Su. 1	Jackson, <i>JBBRAS</i> . Vol. XX (1897-98) pp. 6-10.	
198.	NOGWA (RATALAM, M.P.) PLATES OF DHIRUVASENA (II) BALADITYA (<i>Bh. No.</i> 1346)	G. 320 Bhadrapada ba. 5	Hultzsck, <i>EI</i> . Vol. VIII. (1905-6) pp. 188 ff. & Pls.	
199.	NOGWA (RATLAM, M.P.) PLATES OF DHIRUVASENA (II) BALADITYA (<i>Bh. No.</i> 1347)	G. 321 Chaitra ba 3	Hultzsck, <i>ASI. A. R.</i> 1902-3 pt. II. pp. 325 ff.; & <i>EI</i> Vol. VIII (1905-6) pp. 196 ff. & Pls.	
200.	MALILA (AMRELI DIST. GUJRAT) PLATES OF DHIRUVA- SENA (II) BALADITYA	G. 323 Ashadha Su. 5	<i>IE. AR.</i> 1959-60 p. 34 no. 7 & App. A; H. G. Shastri, <i>JOI</i> Vol. X, no. 2, pp. 123-128 & Pls., D. C. Sircar & J. Sundram, <i>EI</i> . Vol. XXXV (1963-64) pp. 281-286.	
201.	FIRST PLATE OF A VALABHI GRANT OF DHIRUVASENA II	—	D. B. Diskalkar, <i>JBBRAS</i> (NS.) Vol. I (1925) pp. 44-46.	
<i>DHARASENA IV</i>				
202.	BHAVANAGAR PLATES OF DHARASENA IV (<i>Bh. No.</i> 1348).	G. 326 5th day of the dark half of Magha	R. G. Bhandarkar, <i>IA</i> . Vol. I (1872) p. 45.	
203.	PLATES OF DHARASENA IV ISSUED FROM VALABHI (<i>Bh.</i> <i>No.</i> 1949)	G. 326 Ashadha Su. 10	R. G. Bhandarkar, <i>IA</i> . Vol. I (1872) p. 45.	
204.	ALINA PLATES OF DHARASENA IV (<i>Bh. No.</i> 1350)	G. 330 Marga Sira. Su. 3	Buhler, <i>IA</i> . Vol. VII (1878) pp. 73-75 & Pl.	
205.	KARRA PLATES OF DHARA- SENA IV (<i>Bh. No.</i> 1351)	G. 330 Margarasira Su. 2	Buhler, <i>IA</i> . Vol. XV (1886) pp. 339 ff.; Fleet, <i>IA</i> . Vol. XX (1891) pp. 380-81.	
206.	COPPER PLATE GRANT OF DHIRUVASENA III.	G. 332	B. L. Indraj, <i>Bombay Gazt.</i> Vol. I. pt. 1. p. 92 (only notice) <i>Bh. List.</i> p. 394 fn. 5 only refers to above refe- rence.	Records the grant of the village of Pedhapadra in Vanthali,

Sl. No.	Inscriptions	Date	References	Remarks
				the modern Vanthali in Navanagar state of North Kathiawada.
207.	KAPADAVANJA (KAIRA DIST. MAHARASHTRA) PLATES OF DHRUVASENA III (<i>Bh. No.</i> 1352)	G. 334 Magha Su 9	Hultzsch, <i>EI</i> . Vol. I (1892) pp. 86 ff.	
208.	WALA MUSEUM SECOND PLATE OF DHRUVASENA III (<i>Bh. No.</i> 1598)	—	Diskalkar, <i>AR. Watson Museum, Rajkot</i> , 1922-23 p. 10, & <i>JBBRAS (NS.)</i> Vol. I (1925) pp. 35-37.	
209	WALA MUSEUM FIRST PLATE OF MAHARAJA DHRUVASENA (II) (<i>Bh. No.</i> 1599)	—	Diskalkar, <i>JBBRAS. (NS.)</i> Vol. I (1925) pp. 18-19.	Diskalkar thinks that this plate belongs to Dhruvasena I & Bhandarkar thinks to Dhruvasena III (see <i>Bh. List</i>) p. 394 (The Matrikas of Valabhi no. 13)
KHARAGRAHA II				
210.	ALINA PLATES OF KHARAGRAHA II (<i>Bh. No.</i> 1353)	G. 337 Ashadha ba. 5	Buhler, <i>IA</i> . Vol. VII (1878) pp. 76-79 & Pls	
SILADITYA III				
211.	WALA MUSEUM SECOND PLATE OF SILADITYA III (<i>Bh. No.</i> 1354)	G 343 dvī Asha- dha va	Diskalkar, <i>AR. Watson Museum, Rajkot</i> , 1922-23 p. 11; & <i>JBBRAS (NS.)</i> Vol. I (1925) pp. 37.	
212.	PRINCE OF WALES MUSEUM (BOMBAY) PLATES OF SILADITYA III (<i>Bh. No.</i> 1335)	G 346 Marga Sira Ba. 3	G V. Acharya, <i>JBBRAS. (NS.)</i> Vol. I (1925) pp. 71-72.	
213.	PRINCE OF WALES MUSEUM (BOMBAY) PLATES OF SILADITYA III (<i>Bh. No.</i> 1356)	G. 346 Pausha Su. 7	G. V. Acharya, <i>JBBRAS (NS.)</i> Vol. I (1925) pp. 73-75.	
214.	KAKKAPADRA (NOW BARTON MUSEUM, BHAVANAGAR) PLATES OF SILADITYA III (<i>Bh. No.</i> 1957)	G. 347 Vaisakha Su. 15	D. R. Bhandarkar, <i>PRAS. Wc.</i> 1915-16, p. 55; R. D. Banerje, <i>EJ</i> Vol. XXI (1931-32) pp. 208-11, <i>IE. AR.</i> 1956-57 p. 30 no. 33 App. A.	

Sl. No.	Inscriptions	Date	References	Remarks
215.	LUNSADI (KATHIAWAR) PLATES OF SILADITYA III (<i>Bh. No.</i> 1358)	G. 350 Phalgun ba. 3	V. S. Ojha & Schtcherbatskoi, <i>EI.</i> Vol. IV. (1896-97) pp. 76 ff.; <i>IE. AR.</i> 1959-60 p. 39 no. 35 App. A.	
216.	LUNSADI (NOW BHAVANAGAR MUSEUM) PLATES OF SILADITYA III (<i>Bh. No.</i> 1959)	G. 352 Bhadra- pada Su. I	Buhler, <i>IA.</i> Vol. XI (1882) pp. 306 ff.; <i>Bhavanagar Inscrs.</i> pp. 45. ff. & Pls.	
217.	BHAVANAGAR RAJKOT (KATHIAWAR) MUSEUM PLATES OF SILADITYA III (<i>Bh. No.</i> 1360)	G. 356 Jyeshtha ba. (4)	Diskalkar, <i>AR. Watson Museum, Rajkot</i> , 1922-23 p. 12; & <i>JBBRAS. (NS)</i> Vol. I (1925) pp. 57-63. <i>IE. AR.</i> 1959-60 p. 39 no. 36 App. A (only second plate).	The first plate is in Barton Museum Bhavanagar and the second one in the Watson Museum, Rajkot. In <i>Bh. List</i> date is given Jyeshtha (7?)
218.	THE JEASAR (BHAVANAGAR, KATHIAWAR) PLATES OF SILADITYA III	G. (Val.) 357 or 354 Dvi-pausha badi 4	R. D. Banerji, <i>EI.</i> Vol. XXII (1933-34) pp 114-120 & Pl.; <i>IE. AR.</i> 1956-57 p. 30 no. 34 App. A <i>IE. AR.</i> 1959-60 p. 41 no. 42 App. A.	In <i>IE. AR.</i> date is given as 354.
219.	ANASTU (KARJAN TALUK, BARODA DIST.) PLATE OF SILADITYA III	G Val 357 Magha Su. 7	<i>IE AR.</i> 1959-60 p. 37 no. 28 App. A; A. S. Gadre, <i>Important Inscrs. from the Baroda State</i> Vol. I pp. 16 ff	
220.	KAIRA PLATES OF SILADITYA III (<i>Bh. No.</i> 1361)	G. 365(?) Vaisakha Su. 11 (?)	Prinsep. <i>JASB.</i> Vol VIII. (1838) p. 968	
221.	AMARELI PLATE INSCR. OF SILADITYA III ?	G. Val. 368 Paush Su. 1	<i>IE. AR.</i> 1959-60. p. 34 no. 8 App. A.	
222.	WALA MUSEUM SECOND PLATE OF SILADITYA III (<i>Bh. No.</i> 1600)	—	Diskalkar, <i>A. R. Watson Museum, Rajkot</i> , 1922-23 p. 11; & <i>JBBRAS (NS)</i> Vol. I (1925) pp. 40-42.	
223.	THE FIRST PLATE OF A VALABHI GRANT (NOW PRINCE OF WALES MUSEUM) OF SILADITYA III ?	—	G. V. Acharya, <i>JBBRAS (NS)</i> Vol. I (1925) pp. 70-71.	
<i>SILADITYA IV</i>				
224.	BHAVANAGAR PLATES OF SILADITYA IV (<i>Bh. No.</i> 1362)	G. 372 Sravana ba. 9	Buhler, <i>IA.</i> Vol. V (1876) pp. 207-12 & Pl.	Buhler regarded this grant to belong to Siladitya III and date 342.

Sl. No.	Inscriptions	Date	References	Remarks
225.	DEVALI (NOW BHAVANAGAR MUSEUM) PLATES OF SILADITYA IV (<i>Bh. No. 1363</i>)	G. 375 Jyeshtha ba. 5	V. S. Ojha, <i>VOJ.</i> Vol. I. pp. 253 ff. & Pls.; <i>Bhavanagar Inscr.</i> pp. 55. ff. & Pls.	
226.	PLATES OF SILADITYA IV OF VALABHI (<i>Bh. No. 1364</i>)	G. 376 Marga- Sirsha Su. 15	Keilhorn, <i>El.</i> Vol. V (1898-99) Appendix p. 69 no. 492.	The place name from which it was issued is illegible.
227.	PRINCE OF WALES MUSEUM (BOMBAY) PLATES OF SILADITYA IV (<i>Bh. No. 1365</i>)	G. 381 Marga- sira Su. 6	G. V. Acharya. <i>JBBRAS (NS.)</i> Vol I (1925) p. 75.	
228.	PLATES OF SILADITYA IV ISSUED FROM VALABHI (<i>Bh. No. 1366</i>)	G. 382 Marga- sira su. 6	Keilhorn, <i>El.</i> Vol. V (1898-99) Appendix p. 69 no. 493.	
229.	MADRASARA (NOW BARTON MUSEUM, BHAVANAGAR) PLATES OF SILADITYA (IV) (<i>Bh. No. 1368</i>)	G. 387 dvi-Pausa ba. 4	D. R. Bhandarkar, <i>PRAS. Wc.</i> 1915-16 p 55	
230.	DHASHA (GOHILAWAD DIST. SAURASHTRA) PLATES OF SILADITYA IV	G. 387 Marggasira Su. 6	<i>IE. AR.</i> 1955-56 p. 21 no. 79 App. A.	
231.	UNDAVI PLATES (NOW VALA STATE MUSEUM) OF SILADITYA IV (OR V)	—	A S. Gadre, <i>JUB.</i> Vol. IV (1935-36) pt. I pp. 5-6	Previously described as a grant of Dharsena IV. See <i>AR. Watson Mus.</i> for 1931-32 p. 6.
<i>SILADITYA V</i>				
232.	GONDALA (KATHIAWAR) PLATES OF SILADITYA V (<i>Bh. No. 1369</i>)	G. 403 Vaisakh Su (Doha 13)	Mandlik, <i>JBBRAS.</i> Vol. XI (1875) pp. 335. ff. & Pl.	
233.	GONDALA PLATES OF SILADITYA (<i>Bh. No. 1370</i>)	G. 403 Maga ba. 12	Mandlis, <i>JBBRAS.</i> Vol. XI (1875) pp. 335 ff. & Pls.	
<i>SILADITYA VI</i>				
234.	LUNAVADA (REWA, BOMBAY PRESIDENCY) PLATES OF SILADITYA VI (<i>Bh. No. 1374</i>)	G. 441 Karttika Su 5(?)	Buhler, <i>JA.</i> Vol. VI (1875) pp. 16-21 & Pl.	
<i>SILADITYA VII</i>				
235.	ALINA (KAIRA DIST. NOW ROYAL ASIATIC SOCIETY'S) PLATES OF SILADITYA VII (<i>Fl. No. 39, Bh. No. 1375</i>)	G. 447 Jyeshtha Su. 5	—	

Sl. No.	Inscriptions	Date	References	Remarks
<i>INCOMPLETE FIRST PLATES OF SOME LATER VALABHI RULERS</i>				
236.	FIRST PLATE OF A VALABHI GRANT	—	D. B. Diskalkar, <i>JBBRAS.</i> (NS.) Vol. I (1925) pp. 46-48.	Ends with description of Dharasena IV.
237.	FIRST PLATE OF A VALABHI GRANT	—	D. B. Diskalkar, <i>JBBRAS.</i> (NS.) Vol. I (1925) pp. 49-50.	Ends with the
238.	FIRST PLATE OF A VALABHI GRANT	—	D. B. Diskalkar, <i>JBBRAS.</i> (NS.) Vol. I (1925) pp. 49-50.	
239.	WATSON MUSEUM (RAJKOT) STRAY SEAL OF SOME MAITRAKA RULER.	—	<i>IE. AR.</i> 1959-60 p. 41 no. 48 App. A.	Reads Sri Bhatakka.

**4. INSCRIPTIONS OF THE DYNASTIES SUCCEEDING THE GUPTAS AND OF OTHER
LATER DYNASTIES RELEVANT TO GUPTA HISTORY OR TRACING
THEIR ORIGIN FROM THE GUPTAS**

Sl. No.	Inscriptions	Date	References	Remarks
4A1. MAUKHARIS OF KANNAUJ				
<i>HARIVARMAN</i>				
240.	NALANDA (BIHAR) FRAGMENTARY TERRACOTIA PLAQUE INSCR. OF KING HARIVARMANA (<i>Bh. No. 2080</i>) (MAUKHARI ?)	—	M. Hamid, <i>Anc. Monuments in Bihar and Orissa</i> [<i>ASI. (NIS.) Vol. LI.</i>] p. 88 no. 17.	
<i>ISVARAVARMAN</i>				
241.	JAUNAPUR (U.P.) INSCR. OF ISVARAVARMAN (<i>Fl. No. 51, Bh. No. 1601</i>)	—		
<i>ISANAVARMAN</i>				
242.	HARAHA (BARABANKI DIST. U.P.) INSCR. OF THE TIME OF ISANAVARMAN (<i>Bh. No. 10</i>)	V. 611	<i>AR. Lucknow Provincial Museum</i> 1915 p. 3; Hirananda Sastri, <i>AR. Lucknow Provincial Museum</i> , 1916 p. 3 & Appendix D. 8; H. R. Diwekar, <i>Sarasvati (Hindi)</i> 1322 B S., pp. 80 ff. & Pl.; N. G. Majumdar, <i>BSS.</i> 1323 B.S. pp. 2 ff. & Pl., & <i>IA.</i> Vol. XLVI (1917) pp. 126 ff.; Hiranada Sastri, <i>EI</i> Vol. XIV (1917-18) pp. 110-20, L. P. Pandey Sharma, <i>JAHRS.</i> Vol. VIII (1933) pp. 147-50, D. N. Mookerji, <i>Jc.</i> Vol. V (1938-39) pp. 104-5; R. C. Majumdar, <i>Jc.</i> Vol. XI (1944-45) pp. 123-24; B. Upadhyaya, <i>SAII.</i> pt. II pp. 110-112; <i>IE.</i> <i>A.R.</i> 1953-53 p. 75 no. 490 App. B.; R. B. Pandey, <i>HLI.</i> (1962) pp. 141-44.	
243.	NALANDA FRAGMENTARY TERRACOTTA SEAL INSCR. OF ISANAVARMAN (<i>Bh. No. 2079</i>)	—	M. Hamid, <i>Anc. Monuments in Bihar and Orissa</i> [<i>ASI. (NIS.) Vol. LI</i>] pp. 88-9, 18.	

Sl. No.	Inscriptions	Date	References	Remarks
SARVAVARAMAN				
244.	ASIRGADHA (NIMAR DIST. M.P.) COPPER SEAL INSCR. OF SARVAVARMAN (<i>Fl. No. 47, Bh. No. 1602</i>)	—	Hiralal, <i>Inscr. in C.P. and Berar</i> , p. 77-78 no. 141.	
245.	NALANDA TERRACOTTA SEAL OF SARVAVARMAN (<i>Bh. No. 2081</i>)	—	Hiranand Sastri, <i>ASI, AR. 1927-28 p. 139; & EI. Vol. XXI (1931-32) no. 12 pp. 73-74; & MASJ no. 66 p. 67-68 (Only text); IE. AR. 1956-57 p. 96 no. 80 App. C.</i>	
AVANTIVARMAN				
246.	SOHANAG (SALEMPUR DEORA DIST. U.P.) TERRACOTTA SEAL OF AVANTIVARMAN	—	M S. Vats, <i>EI. Vol. XXVII (1947-48) pp. 62-65 & Pl.</i>	
247.	NALANDA SEAL OF AVANTIVARMAN	—	A. Ghosh, <i>EI. Vol. XXIV (1937-38) p. 283-85 & Pl.; B. Upadhyaya, SAH. Pt. II pp. 225-26, no. (३) 2; IE. AR. 1957-58 p. 73 no. 227 App. C.</i>	
248.	NALANDA SEAL OF A SON OF AVANTIVARMAN (NALANDA ARCHAEOLOGICAL MUSEUM CLAY SEAL NO. 2)	—	A Ghosh, <i>EI. Vol. XXIV (1937-38) pp 283-85 & Pl.; IE. AR. 1957-58 p. 73 no. 228, App. C. (Name restored as Suchandravarman).</i>	The name of the issuer is broken Only Suva. . . . is restored.
4-A 2. MAUHARIS OF BIHAR				
ANANTAVARMAN				
249.	BARABAR (GAYA DIST. BIHAR) HILL CAVE INSCR. OF ANANTAVARMAN (<i>Fl. No. 48, Bh. No. 1603</i>)	—	M. Hamid, <i>Anc. Monuments in Bihar and Orissa [ASI. (NIS.) Vol. LI] pp. 37-38 (G.)</i> .	
250.	NAGARJUNI HILL CAVE INSCR. (GAYA, BIHAR) OF ANANTAVARMAN (<i>Fl. No. 49, Bh. No. 1604</i>)	—	Keilhorn, <i>JA. Vol. XX (1891) pp. 189 ff.</i>	
251.	NAGARJUNI (GAYA DIST. BIHAR) HILL CAVE INSCR. OF ANANTAVARMAN (<i>Fl. No. 50, Bh. No. 1741</i>)	—	M. Hamid, <i>Anc. Monuments in Bihar and Orissa [ASI. (NIS.) Vol. LI] pp. 40-42.</i>	

Sl. No.	Inscriptions	Date	References	Remarks
4-B. SASANKA				
252.	GANJAM PLATES OF THE REIGN OF SASANKA	G. 300	Hultzsch, <i>El.</i> Vol. VI pp. 143 ff.; B. Upadhyaya, <i>SAILI</i> . pt. II. pp. 114-15 & Pl., R. B. Pandey, <i>HLL</i> . (1962) pp 147-48.	
253.	MIDNAPUR (BENGAL) COPPER PLATES OF SASANKA	Samvata 19 Bhadra di. 19	M. N. Basu, Madhavi, Ashadha, 1345 B. S. pp. 3 ff.; D. C. Sircar, Prabasi (Bengali) Sravana, 1350 pp. 291 ff., R. C. Majumdar, <i>JRASB. (Lt.)</i> Vol. XI (1945) pp. 1-9 & Pl.	
254.	ROHATASAGADHA (ARRAH DIST. BIHAR) STONE SEAL-MATRIX OF THE MAHASAMAUTA SASANKADEVYA (<i>Fl. No. 78, Bh. No. 1741</i>)	—	B. Upadhyaya, <i>SAILI</i> . Pt. II p. 226 (₹)	
4-C. PUSHPABHUTIS HARSHA				
255.	BANSKHERA (SHAHAJAHANPUR DIST. U.P.) PLATE OF HARSHA (<i>Bh. No. 1385</i>)	H. 22 Kartika ba. 1	Buhler, <i>El.</i> Vol IV (1896-97) pp. 208 ff. & Pl.; B. Upadhyaya, <i>SAILI</i> . pt. II. pp. 112-13, <i>IE. AR.</i> 1960-61 no. 61 App. A; R. B. Pandey, <i>HLL</i> . (1952) pp. 145-47.	
256.	MADHUBANA (AZAMAGADH DIST. U.P.) PLATE OF HARSHA (<i>Bh. No. 1386</i>)	H. 25 Margasirsha ba. 6	Buhler, <i>El.</i> Vol. I (1892) pp. 67. ff.; Keilhorn, <i>El.</i> Vol. VII (1902-3) pp. 157 ff. & Pl., <i>IE. AR.</i> 1960-61 no. 49 App. A	
257.	NALANDA TERRACOTTA SEALS OF HARSHA OF THANESAR	—	Hirananda Sastri, <i>ASI AR.</i> 1927-28 pp. 139, & <i>El.</i> Vol. XXI (1931-32) pp. 73-77 & Pl. & <i>MASI</i> . no. 66 pp. 68-69 (Only text)	
258.	SONAPATI SEAL OF HARSHA (<i>Fl. No. 52, Bh. No. 1665</i>)			
4-D. PANDUVAMSIS OF SOUTH KOSALA UDAYANA				
259.	KALANJAR (BANDA DIST. U.P.) ROCK INSCR. (<i>Bh. No. 1649</i>).		Cunningham. <i>ASIR.</i> Vol. XXI Pl. IX. L.	

Sl. No.	Inscriptions	Date	References	Remarks
<i>NANNADEVA</i>				
260.	BHABDAK (CHANDA DIST. M.P. NOW NAGPUR MUSEUM) BUDDHIST INSCR. OF THE TIME OF NANNARAJADHIRAJA (<i>Bh. No. 1650</i>).		Stevenson, <i>JBRAS.</i> Vol. I pp. 148 ff.; Cunningham, <i>ASIR</i> , Vol. IX p. 127 : & <i>JRAS.</i> 1905 pp. 624 ff. Hiralal, <i>Inscrs. in C.P. and Berar</i> , pp. 13-14 No.	Of about 8th Century (See <i>Bh. List</i> p. 229. fn. 1).
261.	ADHABHARA PLATES OF MAHANANNARAJA (BILASPUR DIST. M.P.).	Bhadrapada ba. 12, Sam-Kranti	<i>IE. AR.</i> 1955-56, p. 19 No. 52 App. A; B. C. Jain, <i>EI.</i> Vol. XXXI (1955-56) pp. 219-222 & Pls.; end <i>PIHC.</i> XIX. (1956) pp. 133-39.	
<i>ISANADEVA</i>				
262.	KHAROD (BILASPUR, M.P.) INSCR. (<i>Bh. No. 1651</i>).		D. R. Bhandarkar, <i>PRAS. Wc.</i> 1903-5, p. 54 No. 2038; Cousen's Progress Report, 1904, p. 54; Hiralal, <i>Inscrs. in C. P. & Berar</i> pp. 125. ff. No. 208; <i>IEAR</i> 1960-61 No. 261 A. App. B.	The inscr. belongs to 8th Century A.D. (See <i>Bh. List</i> p. 229 fn. 3). Isandeve of this inscr. seems to be a brother of Nannadeva (See <i>Classical Age.</i> p. 221.)
<i>MAHASIVA-TIVARADEVA</i>				
263.	BONDA PLATE OF MAHASIVA TIVARA.	R. y.5 Marga sirsha di. 1 (i. e. badi I)	<i>IE. AR.</i> 1959-60 p. 43 No. 56 App. A.; D. C. Sircar, <i>EI.</i> Vol. XXXIV (1961-62) pp. 111-16 & Pls.	
264.	RAJIM (RAIPUR DIST. M.P) PLATES OF RAJA TIVARADEVA (<i>Fl. No. 81, Bh. No 1652</i>).	R. Y. 7 Karttika di. 8	Keilhorn, <i>IA.</i> Vol. XVIII (1889) pp. 220 f., Hiralal, <i>Inscrs. in C. P. & Berar</i> , p. 97 No. 172., V. V. Mirashi, <i>NUJ.</i> Dec. 1936. No. 2 pp. 50-51.	Of about the middle of 8th century A. D. (<i>Bh. List</i> p. 229 fn. 4.)
265.	BALODA (SAMBALAPUR, ORISSA NOW NAGPUR MUSEUM) PLATES OF TIVARADEVA (<i>Bh. No. 1653</i>).	R. Y. 9 Jyeshtha di. 27	Hultzsch, <i>EI.</i> Vol. VII (1902-3) pp. 102-107 & Pls.; Hiralal, <i>Inscrs. in C. P. & Berar</i> , p. 96 No. 171.	

Sl. No.	Inscriptions	Date	References	Remarks
MAHASIVAGUPTA-BALARJUNA				
266.	BARDULA (SARANAGARH, STATE M. P.) PLATES OF MAHASIVAGUPTA.	R. Y. 9 Karttika Su. 12	<i>IE. AR.</i> 1945-46 p. 12 No. 51 App. A.; P. B. B. Desai, <i>EI.</i> Vol. XXXVII (1963-64) pp. 287-291 & Pls.	
267.	BONDA PLATES OF MAHASIVAGUPTA.	R. Y. 22 Paushsudi 4	<i>IE. AR.</i> 1959-60 p. 43 No. 57 App. A; V. V. Mirashi, <i>EI.</i> Vol. XXXV (1963-64) pp. 60-65 & Pls.	
268.	LODHIA (RAIGADH DISTT. M.P.) PLATES OF MAHASIVAGUPTA.	R. Y. 57 Karttika (Purnima) 30	L. P. Pandey Sharma, <i>EI.</i> Vol. XXVII (1947-48) pp. 319 ff., V. V. Mirashi, <i>JOHRS.</i> Vol. I (1952) No. 1 pp. 63-65; <i>IE. AR.</i> 1952-53 p. 22 No. 4 App. A.	
269.	SENAKAPATA (RAIPUR DISTT. M.P.) STONE INSCR. (NOW IN SAUGOR UNIVERSITY MUSEUM) OF THE TIME OF SIVAGUPTA BALARJUNA.	—	M. G. Dikshut & D. C. Sircar, <i>EI.</i> Vol. XXXI (1955-56) pp. 31-36 & Pl.	
270.	SIRPUR (RAIPUR DISTT. M.P.) INSCR. OF THE TIME OF MAHASIVA GUPTA (<i>Bh. No.</i> 1654).	—	Hiralal, <i>EI.</i> Vol. XI (1911-12) pp. 190 ff. & Pl.; & <i>Inscr. in C.P. & Berar</i> pp. 99-105 no. 174.	Of about 8th or 9th century A.D. (See <i>Bh. List</i> p. 230 fn. 1).
271.	SIRPUR GANDHESVARA TEMPLE PILLAR INSCR. OF THE TIME OF SAIVAGUPTA BALARJUNA (<i>Bh. No.</i> 1655).	—	Cunningham, <i>ASIR.</i> Vol. XVIII pl. XVIII. A.; Keilhorn, <i>IA.</i> Vol. XVIII (1889) pp. 179 f.; Hiralal, <i>Inscr. in C.P. & Berar</i> , p. 97-99 no. 173; Cousen's Progress Report, 1904 pp. 49 ff.; <i>IE. AR.</i> 1954-55 p. 51 Nos. 281-283, 286, 287 App. B; <i>IE. AR.</i> 1956-57 p. 52 Nos. 113-116 App. B.	Of about the beginning of the 9th century A. D. (See <i>Bh. List</i> p. 230 fn. 3).
272.	MALLAR PLATES MAHASIVAGUPTA BALARJUNA.	Ashadha Amavasya Suryagraho parage	V. V. Mirashi & L. P. Pandya, <i>EI.</i> Vol. XXIII (1935-36) pp. 113-22 & Pl.; & <i>NUJ</i> Dec. 1936-No. 2 pp. 56-57.	
273.	SIRPUR (RAIPUR DIST. M.P.) RIVER GATEWAY INSCR. (<i>Bh. No.</i> 1882)	—	D. R. Bhandarkar, <i>PRAS.</i> <i>Wc.</i> 1903-4 p. 50 No. 2018; Hiralal, <i>Inscr. in C. P. and Berar</i> p. 111 f. No. 187.; <i>IE.</i>	The engraver of this inscr. is apparently the same

Sl. No.	Inscriptions	Date	References	Remarks
			<i>AR.</i> 1954-55 p. 51 No. 285 App. B.	(named Gonsiva) as on. no. 270 <i>Bh. No</i> 1964.
274.	SIRPUR INSCR. OF THE TIME OF BALARJUNA	—	<i>IE. AR.</i> 1954-55 p. 51 No. 290 App. B. ; M.G. Dikshit, <i>EI.</i> Vol. XXXI (1955-56) pp. 197-98 & Pl.; <i>IE. AR.</i> 1954-55 p. 51 No. 288 App. B.	
275.	SIRPUR (RAIPUR, M.P.) GANDHESVAR TEMPLE PLATE FORM INSCR. OF SIVAGUPTA BALARUTUNA	—	<i>IE. AR.</i> 1954-55 p. 51 No. 288 App. B.	
276.	RAIPRU M.G.M. MUSEUM STONE INSCR. (NO. 5) OF SIVAGUPTA FROM SIRPUR SURANG MOUND	—	Hiralal, <i>Inscrs. in C. P. & Berar</i> , p. 111 No. 185., <i>IE. AR.</i> 1954-55 p. 51 No. 279 App. B; <i>IE. AR.</i> (1956-57) p. 53 No. 119 App. B.	
4-D. PANDUVAMSIS OF MEKALA				
<i>BHARATABALA OR INDRABALA</i>				
277.	BAMHANI PLATES OF PANDAVA KING BHARAT-BALA	R. Y. 2 Bhadrapada Krishna 13, Pushya Nakshatra	B. Ch. Chhabra, <i>EI.</i> Vol. XXVII (1947-48) pp. 132 ff. & Pls.	

5. MISCELLANEOUS INSCRIPTIONS ARRANGED RELIGION-WISE ON THE FOLLOWING GROUNDS

I. INSCR. MENTIONED IN MISCELLANEOUS GROUP OF CORPUS INSCRIPTIONUM INDICARUM Vol. III —Fleet

II DATED IN GUPTA ERA

III DIRECTLY OR INDIRECTLY RELATED TO OR LYING IN THE REGIONS OF DYNASTIES MENTIONED ABOVE AND/OR SIMULTANEOUSLY BEING RELEVANT TO *THE GUPTA HISTORY*

Sl. No.	Inscriptions	Date	References	Remarks
5-A. PANJAB AND WEST PAKISTAN				
278.	TUSAM (HISSAR, PANJAB) ROCK INSCR. (<i>Fl. No. 67, Bh. No. 1808</i>)	—	—	Of about the end of 4th or the beginning of the 5th century A. D.
279.	LAHORE COPPER SEAL INSCR. OF THE MAHARAJA MAHESVARANAGA, SON OF NAGABHATA (<i>Fl. No. 77, Bh. No. 1807</i>)	—	—	The original place from where it was found is not known. Period is approximately the end of the 4th century A.D.
280.	NIRAMANDA (KANGRA DIST. PANJAB) PLATE OF MAHARAMANGA MAHARAJA SAMUDRASENA (<i>Fl. No. 80, Bh. No. 1810</i>).	Samvata 6, Kh:vat) Su. II.	J. N. Banerji, <i>PTIOC</i> . XV (1949) pp. 298-300.	Of about 7th. century A.D.
281.	SHORKOT (JHANG DIST. PANJAB NOW W. PAKISTAN) COPPER CAULDRON INSCR. (<i>Bh. No. 2035</i>)	G (?) 83 Magha Su di 5	Noticed in, <i>JPHS</i> . Vol. I p. 74; Vogel, <i>El. Vol XVI</i> (1921-22) p 15, <i>IE AR</i> . 1956-57 p. 37 No. 88 App. A.	
5-B. UTTAR PRADESH				
282.	KOSAMBI STONE SLAB INSCR. (NOW ALLAHABAD MUNICIPAL MUSEUM) OF BHADRAMAGHA OF MAGHA DYNASTY	G (?) 81 gri, pa 2, di. 5	Krishna Deva, XI. Vol. XXIV (1937-38) pp. 253 ff. & Pl.; <i>IE. AR</i> . 1957-58 p. 75 No. 248 App. C.	

S No.	Inscriptions	Date	References	Remarks
283.	ALLAHABAD MUSEUM INSCR. OF BHADRAMAGHA.	G (?) 87 Paksha 3 di 5.	Sten Ko now, <i>EI.</i> Vol. XXIII (1935-36) pp. 245-48 & Pls ; <i>IE. AR.</i> 1957-58 p. 66 No. 523 App. B.	
284.	KOSAM (ALLAHABAD MUSEUM) STONE SLAB INSCR. OF BHADRAMAGHA	G (?) 88 Paksha 3 diva sa 5	D. R. Sahani, <i>EI.</i> Vol. XVIII (1925-26) p. 160 & Pl.	Sir John Marshall thinks the date to be in Kanishaka era.
285.	ALLAHABAD MUNICIPAL MUSEUM BROKEN PILLAR INSCR. (MUSEUM NO. 3023) FROM KOSAMBI	G. 125 (?) Vaisakha di II	<i>IE. AR.</i> 1957-58 p. 66 No. 520 App. B.	
286.	MATHURA (NOW LUCKNOW MUSEUM U.P.) BUDDHA IMAGE INSCR. (<i>Fl. No.</i> 63, <i>Bh. No.</i> 1275)	G. 135 Pushya masa di 20	<i>IE. AR.</i> 1959-60 p. 131 No. 537 App. C.	
287.	KATRA KESAVADEVA (NOW MATHURA ARCHAEOLOGICAL MUSEUM) STONE INSCR	G. 145 Kartika di. 3	<i>IE. AR.</i> 1960-61 No. 620 App. B.	Records the date only.
288.	GADHWA (ALLAHABAD DIST. U.P.I. NOW I.M. CALCUTTA) VAISHNAVA INSCR. (<i>Fl. No.</i> 66, <i>Bh. No.</i> 1280)	G. 148 Magha di. 21		
289.	PALI (ALLAHABAD DIST. U.P. NOW LUCKNOW MUSEUM) PLATE OF THE MAHARAJA LAKSHMANADEVA ISSUED FROM JAYAPURA (<i>Bh. No.</i> 1284)	G (?) 158 Jyeshtha Purnamasi	Fuhrer, <i>EI.</i> Vol. II (1894) pp 363-65 & Pl., <i>IE. AR.</i> 1960-61 No. 47 App. A.	
290.	MATHURA (NOW LUCKNOW MUSEUM U.P.) BUDDHIST IMAGE INSCR. (<i>Fl. No.</i> 70, <i>Bh. No.</i> 1309)	G. 230	<i>IE. AR.</i> 1959-60 p. 131 No. 533 App. C.	In late Brahmi characters.
291.	KOSAM (ALLAHABAD DIST. U.P.) IMAGE INSCRIPTION OF THE TIME OF MAHARAJA BHIMAVARMAN (<i>Fl. No.</i> 65, <i>Bh. No.</i> 1277)			From the forms of the letter it seems to belong to the second half of the Fourth Century A. D. In that case the date has to be referred to the Kalchuri era and king

Sl. No.	Inscriptions	Date	References	Remarks
				Bhīmavarmān may be identified with Bhimsena of Bhita seal (<i>Bh. No. 1774</i>). (See <i>Bh. List</i> p. 173 fn. 3).
292.	PRAHALADPUR (VARANASI DISTT. U.P.) NOW BANARAS COLLEGE PILLAR INSCR. WITH THE NAME OF SISUPALA A PARTHYA GENERAL (<i>Fl. No. 57, Bh. No. 1780</i>).	—	—	Of about the 4th century A. D.
293.	DEORIYA (ALLAHABAD, DISTT. U.P. NOW LUCKNOW MUSEUM) IMAGE INSCR. (<i>Fl. No. 68, Bh. No. 1781</i>).	—	—	Of about 5th century A.D.
294.	SARNATH (NOW INDIAN MUSEUM, CALCUTTA) INSCR. OF HARIGUPTA (<i>Fl. No. 75, Bh. No. 1782</i>).	—	—	Do.
295.	KASIA (DEORIYA DISTT. U.P.) BUDDHA IMAGE INSCR. RECORDING THE GIFT. BY THE MAHAVIHARASWĀMIN HARIBALA (<i>Fl. No. 69, Bh. No. 1783</i>).	—	<i>IE. AR.</i> 1959-60 p. 128 No. 495 App. C.	Of about the end of the 5th century A. D.
296	KASIA (DEORIYA DISTT U.P.) PLATE CONTAINING THE NIDANASUTRA IN SAMSKRIT AND DEPOSITED BY HARIBALA IN THE NIRVANA-CHAITYA (<i>Bh. No. 1784</i>)	—	Pargitar, <i>ASI Ar.</i> 1910-11 pp. 76 f. & Pl. XXXIX; Hirananda Sastri, <i>ibid.</i> p. 65.	Haribala of this inscr. seems the same as that of No. 295 above (<i>Bh. No. 1783</i>).

5-C. BIHAR

297.	MUNDESVARI (SHAHABAD DISTT. BIHAR) INSCR. OF THE TIME OF THE MAHASAMANTA MAHAPRATIHARA MAHARAJA UDAYASENA (<i>Bh. No. 1257</i>)	G. 30 Karttika di. 22	Banerji, <i>IE.</i> Vol. IX (1907-8) p. 289 & Pl.; N. G. Majumdar, <i>IA.</i> Vol. XLIX (1920) pp. 21-29; <i>IE. AR.</i> 1956-57 p. 96 No. 76 App. C.	The character seems to be of Gupta period but the dating and language are in the Kushāna style.
------	---	-----------------------------	---	---

Sl. No.	Inscriptions	Date	References	Remarks
298.	BODHAGAYA (NOW INDIAN MUSEUM, CALCUTTA) BUDDHIST INSCR. OF THE TIME OF THE MAHARAJA TRIKAMALA (<i>Bh. No. 1258</i>)	G(?) 64 gri 3, di.	Cunningham, <i>Mahabodhi</i> , pl. XXV, R. P. Chanda, <i>ASI. AR. 1922-23</i> , p. 169	
299.	NANDANAPUR MONGHYR DIST. (BIHAR) COPPER PLATE	G. 169 Vaisakha Su. 8	N. G. Majumdar, <i>EI. Vol. XXIII</i> (1935-36) pp. 52-56 & Pls.; J. C. Ghosh, <i>EI. Vol. XXIV</i> (1937-38) pp. 126-29.	
300.	NALANDA INSCRIBED BRICK	G(?) 197 Magha di 25	A. Ghosh, <i>EI. Vol. XXIV</i> (1937-38) pp. 20-22; <i>IE. AR. 1957-58</i> p. 73 No. 229 App. C.	
301.	AMAUNA (GAYA DIST. BIHAR) PLATES OF THE KUMARAMATYA MAHARAJA NANDANA, ISSUED FROM PUDGAL (<i>Bh. No. 1310</i>)	G. 232 Margga di-20	P. Dayal, <i>JPASB. Vol. V</i> (1909) pp. 163-65; Bloch <i>EI. Vol. X</i> (1909-10) pp. 49-51; <i>IE. AR. 1955-56</i> P. 16 No. 21 App. A.	
302.	BODHAGAYA (NOW INDIAN MUSEUM, CALCUTTA) INSCR. OF THE BUDDHIST TEACHER MAHANAMN (<i>Fl. No. 71, No. 1325</i>)	G(?) 269 Chaitra Su. 7	Kielhorn, <i>IA. Vol. XX</i> (1891) p. 190; Smith, <i>IA. Vol. XXXI</i> (1902) p. 192	
303.	BODHAGAYA BUDDHIST IMAGE INSCR. (<i>Fl. No. 72, Bh. No. 1739</i>)	—		
304.	BODHAGAYA (NOW INDIAN MUSEUM, CALCUTTA) IMAGE INSCR. RECORDING THE GIFT BY TWO SAKYA MENDICANTS DHARMAGUPTA & DAMSHT-RASENA (<i>Fl. No. 76, Bh. No. 1738</i>).	—		Of about the 6th century A.D.
5-D. BENGAL AND EAST PAKISTAN				
305.	TIPERA (EAST PAKISTAN) PLATES OF LOKANATHA (NOW ASIATIC SOCIETY'S PLATES CALCUTTA)	G(S) 44 Phalguna Masa	R. G. Basak, <i>EI. Vol. XV</i> (1919-20) pp. 301-15 & pl. & <i>IE. AR. 1955-56</i> p. 15 No. 13 App. A	
306.	INDIAN MUSEUM, CALCUTTA, FRAGMENTARY INSCR. RECORDING THE GIFT BY SAKYA MENDICANT DHARMADAS (<i>Fl. No. 74, Bh. No. 1721</i>)			Of about 5th century A.D. The original find spot of the inscr. is not known

*Bhandarkar doubts this to be referred to in Kanchuri era. See *Bh. List.* p. 170 fn. 4.

Sl. No.	Inscriptions	Date	References	Remarks
5-E. ASSAM				
307.	BADAGANGA (NOWGONG DIST. ASSAM) ROCK INSCRIPTION OF BHUTIVARMA OF BHAUMA NARAKA DYNASTY OF PRAGJYOTISH.	G. 234(?)	N. K. Bhattasali, <i>JARS</i> . Vol. VIII (1941) pp. 138-39; & <i>EI</i> . Vol. XXVII (1947-48) pp. 18-23 & Pl.; <i>IE. AR.</i> 1951-52 p. 11 No. 17 App. B, D. C. Sircar, <i>EI</i> . Vol. XXX pp. 62-67 & Pl.	Bhutivarman was the 5th predecessor of Bhashkarvarman of Assam.
308.	TEJPUR (ASSAM) ROCK INSCR. OF HARAJJARAVARMADEVA (REIGNING AT HARUPESVERA) AND OF HIS GENERAL (SANADHYASKHA) MAHASAMANTA SUCHITTA. (<i>Bh.</i> No. 1376)	G. 510	Gaut, <i>Rep. Prog. Hist. Res. Assam</i> , Para 8. Bloch. <i>PRAS. EC.</i> 1902-3 p. 2; Kielhorn <i>Nachrichten d. k. Ges. d. Wissenschaften zu Gottingen</i> 1905; H. P. Sastri, <i>JBORS</i> . Vol. III (1917) pp. 508-14; Kamarupasasanavali p. 185.	
5-F. GUJARATA & MAHARASHTRA				
309.	WALA COPPER PLATE OF GARULAKA MAHARAJA VA-RAHADASA	G. Val 230 Magha Su. I	A. S. Gadre, <i>JUB</i> . Vol. III pt. 1 (1934-35) pp. 77-80 & Pls.; D. C. Sircar & A. S. Gadre (Notes & Answers) <i>JUB</i> . Vol. IV. pt. I. pp. 175-77; <i>IE. AR.</i> 1959-60 p. 40 No. 41 App. A.	
310.	PALITANA (KATHIAWAR) PLATES OF THE SAMANTA MAHARAJA SIMHADITYA (<i>Bh.</i> No. 1323)	(G) Asvayuja Su.	Hultzsch, <i>IA</i> . Vol. XXXIX (1910) p. 129 No. 1; & <i>EI</i> . Vol. XI (1911-12) pp. 16 ff. & Pl.; <i>IE. AR.</i> 1955-56. p. 21. No. 88, App. A.	
311.	HILOL (DEHGAM TAHASIL) PLATE OF RASTRAKUTA KING (OF GUJARATA) KARKKA II	(G. Vala- bhi) 470 Mārgga- Sirsha Suddha 7 Bhauma	<i>IE.</i> 1959-60 p. 34 No. 5 App. A. H. D. Sankalia, <i>EI</i> . Vol. XXXIV (1961-62) pp. 213 ff. & Pls.	
312.	DEVALI COPPER PLATE OF GOVINDARAJA (A RASTRAKUTA KING)	Val. 500	S. C. Upadhyaya, <i>JUPHS</i> . Vol. XXIV-V (1951-52) pp. 196-202 & Pl.; <i>IE. AR.</i> 1959-60 p. 38 No. 31 App. A; D. C. Sircar, <i>EI</i> . Vol. XIV (1963-64) pp. 269-280.	
313.	GHUMALI (NAVANAGAR) COPPER PLATE GRANT OF THE TIME OF AGGUKA II	G. 53	A. S. Altakar, <i>EI</i> . Vol. XXVI (1941-42) pp. 197-203 & Pls.; B. Ch. Chhabra, <i>EI</i> . Vol. XXVIII (1949-50) pp. 77-79.	

Sl. No.	Inscriptions	Date	References	Remarks
314.	GHUMALI (KATHIAWAR) GRANT OF RANAKA	G. 567	A. S. Altaker, <i>EI</i> . Vol. XXVI (1941-42) pp. 212-17 & Pls.	
315.	GHUMALI GRANT OF KING AGGUKA III	G. 567	A. S. Altaker, <i>EI</i> . Vol. XXVI (1941-42) pp. 217-22 & Pl.	
316.	UNA (KATHIAWAR) PLATE OF THE TIME OF THE (THE PRATHARA) MAHENDRA-YUDHADEVA SUCCESSOR OF BHOJADEVA OF KANNAUJA (<i>Bh. No.</i> 1379)	Val. 574 Magha Suddha 6	Kielhorn, <i>Nacrichtan</i> D. K. Ges. D. Wissan schaftan zu Gottingen, 1904 pp. 204 ff.; & <i>EI</i> . Vol. IX (1907-8) pp. 4 f.	
317.	MORBI (KATHIAWAR) PLATES OF JAINKA (<i>Bh. No.</i> 1378)	G. 585 Phālguna Su. 5	R. G. Bhandarkar, <i>J.A.</i> Vol II (1873) pp. 257 & Pl.; Fleet, <i>CII</i> . Vol. III (1888) Introduction p. 21 & 97 ff.; R. G. Bhandarkar, <i>JBBRAS</i> Vol. XVII (1887) pp. 86 & pp. 97 ff.; Fleet, <i>JA</i> . Vol. XX (1891) pp. 380-81.	Regarded as spurious one.
318.	GHUMALI GRANT OF KING JAIKA III	G. 596 Ashadha Su. 15	A. S. Altaker, <i>EI</i> . Vol. XXVI (1941-42) pp. 222-26 & Pl.	
319.	VERAVALA (JUNAGADH) INSCR. OF THE TEMPLE-PRIEST BHAVA-BRIHASPATI (<i>Bh. No.</i> 1380)	Val. 850 Ashadha	V. S. Ojha, <i>Voj.</i> Vol. II pp. 7 ff.; <i>Bhavanagara Inscrs.</i> pp. 186 ff.	
320.	JUNAGADH INSCR. OF THE TIME OF (?) THE CHAULUKYA KUMARAPALLA (<i>Bh. No.</i> 1381)	Val. 850 (?) Sri Simha- Samvata 60	<i>Bhavanagara Inscrs.</i> pp. 184 f.	
321.	GHELANA (MANGROB) INSCR. (<i>Bh. No.</i> 1382)	Val. 911 Sudi 5 Sukra di	<i>Bhavanagara Inscrs</i> p. 161 & Pl.; D. B. Diskalkar, <i>NIA</i> . Vol. I. (1938-39) p. 688 no. 5.	
322.	VERAVALA (JUNAGADH) IMAGE INSCR. (<i>Bh. No.</i> 1383)	Val. 927 Phālguna Su. 2 di. Soma	Fleet, <i>JA</i> . Vol. XV (1891) pp. 380-81; Kielhorn; <i>EI</i> . Vol. III (1894-95) pp. 303 f & P.; D. B. Diskalkar, <i>NIA</i> . Vol. I (1938-39) p. 690 No. 9	
323.	VERAVALA (JUNAGADH) INSCR. OF THE TIME OF THE CHALUKYA (VAGHELA) ARJUNADEVA (<i>Bh. No.</i> 1384)	Val. 945 V. 1320 Rasula Mahasamvat 622 & Sri Simha Samvat 151 Ashadha ba. 13	E. Hultzsch, <i>JA</i> . Vol. XI (1882) pp. 241 f.; <i>Bhavanagara inscriptions</i> pp. 224 f.; Fleet, <i>JA</i> . Vol. XX (1891) pp. 381-82.	

Sl. No.	Inscriptions	Date	References	Remarks
5-G RAJASTHANA				
324.	DADHIMATI MATA TEMPLE (JODHAPUR) INSCR. OF THE TIME OF DRUHLANA (<i>Bh. No.</i> 1336)	(G) 289 Sravana ba. 13	D. R. Bhandarkar, <i>PRAS. Wc.</i> 1906-7. p. 31; Ramakarna, <i>ET. Vol XI</i> (1911-12) pp. 299 f. Pl.; <i>IE. AR.</i> 1955-56 p. 58 No. 26 App. C.	
325.	DHODA (UDAIPUR) INSCR. OF THE TIME OF DHAVALAPPADDEV AND HIS FEUDATORY GHULAPUTRA DHANIKA OF BHAVAGARTA (<i>Bh. No.</i> 1371)	G. 407(?) Bhadrapada Su. 8	D. R. Bhandarkar, <i>PRAS. Wc.</i> 1905-6 p. 61 No. 2212; & <i>ET. Vol. XII</i> (1913-14) pp. 12 no. 1.	
326.	BIJAYAGADHA (BHARATPUR) PILLAR INSCR. OF VISHNUVARDHANA OF THE VARIKA TRIBE (<i>Fl. No.</i> 59, <i>Bh. No.</i> 2)	V 428 Phalgunab. ba. 15	Bhandarkar, <i>IA. Vol XLII</i> (1913) pp. 161 ff., <i>R. G. Bhandarkar Common Vol</i> pp. 187 ff	
327.	BIJAYAGADHA (BHARATPUR) INSCR. OF A MAHARAJA MAHASENAPATI WHOSE NAME IS LOST, OF THE GANA OF THE YAUDHEYAS (<i>Fl. No.</i> 58, <i>Bh. No.</i> 1847)			
5-H MADHYA PRADESH				
328.	INDORE GRANT MAHARAJA SVAMIDAS (<i>Bh. No.</i> 1259)	G. 67 Jyeshtha Su. 5	R. C. Majumdar, <i>EI. Vol XV</i> (1919-20) pp. 286-290 & Pl.; V. V. Mirashi, <i>CII. Vol. IV</i> No. 2 pp. 5-8 & Pl. II A.	Prof. Mirashi asserts the date to be in Kalachuri era. See <i>CII. Vol. IV</i> pp 5 ff.
329.	INDORE GRANT OF MAHARAJA BHULANDA ISSUED FROM VALKHA (<i>Bh. No.</i> 1266)	G. 107 Phalgunab. ba. 12	R. C. Majumdar, <i>EI. Vol. XV</i> (1919-20) pp. 290-91 & Pl. V.; V. Mirashi, <i>CII. Vol. IV</i> No. 3 pp. 8-10 & Pl. II B.	Prof. Mirashi asserts the date to be in Kalachuri era. See <i>CII. Vol. IV</i> pp 8 ff
330.	SANCHI INSCR. (<i>Fl. No.</i> 62, <i>Bh. No.</i> 1274)	G 131 Asvayuja di. 5		
331.	MANDASOR INSCR. (NOW IN GUJARI MAHAL MUSEUM, GWALIOR) OF DATTABHATA OF THE TIME OF PRABHAKRA (<i>Bh. No.</i> 7)	V. 524	M. B. Garde, <i>ASI. AR.</i> 1922-23 p. 187; & <i>EI. Vol. XXVII</i> (1947-48) pp. 12-18 & Pl.; <i>AR of Arch. dept., Gwalior State Samvat</i> 1979 No. 27; <i>Gwalior Rājya Abhilekha</i> No. 3.	Dattabhata is described as the Son of Vayurakhshita who was the general of the armies of Govindagupta, a son of the Gupta Emperor Chandragupta II.

Sl. No.	Inscriptions	Date	References
332.	BARAWANI PLATE INSCR. OF MAHARAJA SUBANDU (Bh. No. 1288)	G. 167 Bhadrapada Su. Sa (pta)	G. H. Ojha, <i>AR. Rajputana Museum</i> 1924-25 p. 2; R. R. Halldar, <i>El. Vol. XIX</i> (1927-28) pp. 261 f.; V. V. Mirashi, <i>CH. Vol. IV No. 6</i> pp. 17-19 & Pl. III B.

Prof. Mirash suggests the date to be in K. era. See *CH. Vol. IV No. 6*, p. 17-19.

VISHNUVARDHAN

333.	MANDASOR INSCR. OF YASODHARMAN-VISHNUVARDHAN (Fl. No. 35, Bh. No. 9)	V. 589	—Kielhorn, <i>IA. Vol. XVIII</i> (1889) p. 220; & <i>IA. Vol. XX</i> (1891) pp. 188 ff.; D. C. Surcar, <i>SI. BK. III No. 53</i> , pp. 388-92; B. Upadhyaya, <i>SAII. pt. II</i> pp. 100-4 & Pl.; <i>AR. Arch. Dept. Gwalior State</i> , Samvat 1984 No. 21; <i>Gwalior Rajya Abhilekha No. 4</i> ; <i>IE. AR. 1961-62 No. 1480 App. C</i> ; R. B. Pandey, <i>HJI</i> (1962) pp. 131-36.
334.	MANDASOR STONE PILLAR INSCR. OF KING YASODHARMAN (Fl. No. 33, Bh. No. 1870)	—	—R. G. Bhandarkar, <i>JBBRAS. Vol. XXII</i> (1905-8) pp. 96 f., Kielhorn, <i>IA. Vol. XVIII</i> (1889) p. 219; & <i>IA. Vol. XX</i> (1891) p. 188; M. B. Garde, <i>ASI AR. 1922-23</i> pp. 185 & 187, <i>AR. Arch. Dept. Gwalior State</i> , Samvat 1979 No. 28, <i>Gwalior Rajya Abhilekha No. 678</i> ; B. Upadhyaya, <i>SAII. pt. II</i> pp. 106-7; <i>IE. AR. 1954-55</i> p. 45 No. 197 App. B; R. B. Pandey, <i>HJI</i> (1962) pp. 136-38.
335.	MANDASOR DUPLICATE PILLAR INSCR. OF YASODHARMAN (Fl. No. 34)	—	— <i>IE. AR. 1954-55</i> p. 45 No. 198 App. B; <i>AR. Arch. Dept. Gwalior State</i> , Samvata 1979 No. 29; <i>Gwalior Rajya Abhilekha No. 679</i> .
336.	NALANDA STONE INSCR. OF THE REIGN OF YASOVARMADEVA (Bh. No. 1742 & 2105 revised)	—	H. N. Sastri, <i>ASI. AR. 1925-26</i> p. 131; & <i>El. Vol. XX</i> (1929-30) pp. 37-46 & Pl.; R. C. Majumdar, <i>IHQ. Vol. VII</i> (1931) p. 664; & <i>IHQ. Vol. VIII</i> (1932) pp. 371-73; Mri- thyunjayan <i>Ibid. Vol. VIII</i> (1932) pp. 228-30 & 615-17; Bhattasali, <i>Modern Review</i> , Sep. No. (1931); Gautama, <i>Ja-HRS. Vol. VI</i> (1931-32), pp. 145-46; H. N. Sastri,

H. N. Sastri intends to identify Yasovar-madeva with Yasodhar Mana of Mandasor Inscr. & Baladitya the subduer of Mihir Akula.

Sl. No.	Inscriptions	Date	References	Remarks
			<i>MA SI.</i> No. 66 pp. 78-82; B. Upadhyaya, <i>SA II.</i> pt. II. pp....; R. B. Pandey, <i>H LI.</i> (1962) pp. 155-58.	
337.	ARANG (RAIPUR DIST. M.P.) PLATE OF BHIMASENA (ii) (<i>Bh. No.</i> 1329)	G. 282 Bhadra di. 18	Hiralal, <i>Inscrs. in C.P. & Berar</i> , p. 94 No. 170; & <i>EI.</i> Vol. IX (1907-8) pp. 344 ff. & Pl., L.P. Pandey Sharma, <i>JAHRS.</i> Vol. IV (1929-30) pp. 446-48.	
338.	SANCHI PILLAR INSCR. (<i>Fl.</i> <i>No. 75, Bh. No.</i> 1868)			Of about 5th century A.D.
5-I. ORISSA				
339.	KORASHANDA (GANJAM DIST.) PLATE OF MAHARAJA VISAKHAVARMAN (<i>Bh....</i>)	G(?) 38 ma 7, divasa 20	S. N. Rajaguru, <i>JBORS.</i> Vol. XIV (1928) pp. 28 f.; G. Ranade, <i>EI.</i> Vol. XXI (1931-32) pp. 24 f.	
340.	SUMANDALA PLATES OF THE TIME OF PRITHVIVIGRAHA BHATTATAKA (OR OF DHARMA RAJA-AYASOBHITA II OF SAILODBHAVA DYNASTY)	G. 250 Magha ba. 11 Uttara- yana (589 A.D. Dec. 20)	S. No. Rajaguru, <i>JAHRS.</i> Vol. XIX (1948-49) pp. 117-18; & Manorama (Sanskrit) Vol I. pt. I (Saka 1871) pp. 17-24; & <i>EI.</i> Vol. XXVIII (1949-50) pp. 79 ff. & Pls.; & <i>JOHRS.</i> Vol. I (1958) pp. 66-69 & Pls.; <i>IE. AR.</i> 1949-50 p. 17 No. 60. App. A.	
341.	SORO (PURI DIST. ORISSA) PLATE OF SAMBHUYASAS	G. 260 Karttika di. 30	N. G. Majumdar, <i>EI.</i> Vol. XXIII (1935-36) pp. 197-202 & pls.	
342.	KANAS (PURI DIST.) PLATE OF LOKAVIGRAHA BHATTARA KA	G. 280 Phalguna 5	D.C. Sircar, <i>EI.</i> Vol. XXVII (1947-48) pp. 328 ff & Pl.; <i>IE. AR.</i> 1950-51 p. 7 No. 14 App. A.	
343.	PATIAKELA (CUTTOCK DIST. ORISSA) PL. OF MAHARAJA SIVARJA (<i>Bh. No.</i> 1203)	(G) (283)	R. D. Banerji, <i>EI.</i> Vol. IX (1907-8) pp. 283-85 & Pl.	Bhandarkar doubts the date to be referred to in Kalachuri era (<i>Bh. No.</i> 1203).
344.	PRUI. UTTARA-AR SVA TEMPLE PLATES OF SAILODBHAVA DHARMA RAJA (<i>Bh. No.</i> 2041)	G. 312 Vaisakha Su. 8	S. N. Rajguru. <i>JBORS.</i> Vol. XVI (1930) pp. 178 ff. & Pl.	

Sl. No.	Inscriptions	Date	References	Remarks
5-J, MADRAS				
345.	KONDEDDA PLATES OF SAIL- LODBHAVA DHARMA RAJA (<i>Bh. No.</i> 2040)	G. 312 Vaisakha Su. 8.	G. Venkoba Rao, <i>SIE. AR.</i> (1920-21) p. 93; Y. R. Gupte, <i>EI.</i> Vol. XIX (1927-28) pp. 267 ff. & Pls.	
6. NEPAL				
346.	GOLAMADHITOL (BHATA- GAON) INSCR. OF SIVADEVA (i) OF LICHCHHAVI FAMILY (<i>Bh. No.</i> 1344)	G. 316 (or 318 ?) Jyestha Su. diva dasa myam	Bendall, <i>IA.</i> Vol. XIV (1885) pp. 97 f., & <i>Journey of Nepal.</i> p. 72 & Pl.	
347.	KHOPASI (TO THE EAST OF BHATAGAON) INSCR. OF SIVADEVA I	G. 320(?) Chaitra ba. 5	Levi, <i>Le Nepal</i> , III p. 70-81 & Pl. XIII (date given Samvat 520)	
348.	CHANGU-NARAYANA (KATHA- MANDU) INSCR. OF MA- NADEVA (<i>Bh. No.</i> 1367)	G. 386 Jyestha Su. I. Rohini Nakshatra	B. L. Indrajī & Buhler, <i>IA.</i> Vol. IX (1880) pp. 163 ff. & Pl.; <i>Fleet, IA.</i> Vol. XX (1891) p. 379-80; Levi, <i>Lee Nepal</i> p. 126.; D. C. Sircar, 81, BK. III No. 48 pp. 366 ff.	
349.	DEVAPATANA (KATHAMAN- DU) INSCR. OF THE TIME OF MANADEVA (<i>Bh. No.</i> 1372)	G. 413	Buhler & B. L. Indrajī, <i>IA.</i> Vol. IX (1880) p. 166 f. & Pl.	
350.	LAGANTOL (KATHAMANDU) INSCR. OF MAHARAJA VASA- NTASENA (<i>Bh. No.</i> 1373)	G. 433 Asvayujī Sukla diva 1.	B. L. Indrajī & Buhler, <i>IA.</i> Vol. IX (1880) p. 167 & Pl.	
351.	LAGANTOL (KATHAMANDU) FRAGMENTARY INSR. (<i>Bh.</i> <i>No.</i> 1377)	G. 535 Sravana Su. 7	B. L. Indrajī & Buhler, <i>IA.</i> Vol. IX (1880) pp. 168 & Pl.	

वीर सेवा मन्दिर

पुस्तकालय

काष्ठ नं० 203.7 FLE
Fleet William F. H. P. 88